

May 3, 2010

OWEB Project # 206-363 Final Report

Project Description: Hudson Bay Aquifer-Spring Restoration Phase II and III

Dear Oregon Watershed Enhancement Board and Staff,

The Walla Walla Basin Watershed Council appreciates the support of the Oregon watershed enhancement Board through the years in helping the WWBWC and our local irrigators implement irrigation efficiency, fish passage projects, fish habitat projects, and shallow aquifer recharge to recover depleted groundwater.

The Walla Walla River no longer goes dry every summer. Aggressive irrigation efficiency has rewatered the river in the summer and farms remain viable. Our ESA listed Bull Trout and Steelhead population numbers continue to rise, and our partners, the Confederated Tribes of the Umatilla Indian Reservation have successfully reintroduced Chinook salmon back into the river. Increased river flow has improved fish passage and has increased the number of miles of available fish habitat.

Our improvements to flow have come at the expense of our aquifer. Groundwater levels have been in decline similar to our neighbors to the south, the Umatilla Watershed. Piping irrigation water delivery ditches has allowed the "saved" water to remain in river for fish, but has also resulted in an increasing decline of our groundwater. The second most commonly used tool for farms to leave part of their water rights instream for fish has been using existing wells for longer periods each year and drilling additional wells, also leading to dropping groundwater levels. Many spring fed creeks and shallow wells have dried up, demonstrating the decline of groundwater.

More flow is still needed for our fish in the summer. We need to replicate floodplain function and extend the time water resides in the basin. Putting more of our winter and spring runoff into the ground mimics this function and supplements groundwater base flows to the river during the drier months of the year.

The attached report covers the justification, initial operation, and hydrologic benefits observed from the Hudson Bay District Improvement Company Shallow Aquifer Recharge project. This truly innovative project has been essential in demonstrating that shallow aquifer recharge can show measurable improvements to groundwater tables as evidenced by improvements to the flow of spring creeks and water levels in monitoring wells located near and down-gradient from the project site. Not only have the flows in the Walla Walla River improved to enable passage and expanded habitat for Federally protected

Steelhead and Bull trout, and reintroduced Chinook Salmon, but the spring creeks across the valley floor that historically hosted steelhead and contain lingering populations of red band trout now have a proven mechanism, shallow aquifer recharge, that can utilize the availability of high winter and spring river flows to saturate the floodplain and hold that water longer for the benefit of multiple uses.

The WWBWC aquifer recharge program in the Walla Walla has put as much as 5772 acre feet into the ground each winter the last 5 years. We have been working with Hudson Bay District Improvement Company to bring a portion of the high winter and spring river flow to a series of basins and infiltration galleries located in floodplain gravels. We have recovered two spring creeks that are tributaries of a Steelhead stream. The state of Washington has seen our accomplishments and has funded the WWBWC to set up multiple aquifer recharge sites in the Washington portion of the watershed. OWEB has helped us implement aquifer recharge and document the results on the Oregon portion and we will continue to do so with our new OWEB grant # 210-6043.

There were very few changes from the original OWEB proposal. The WWBWC was able to secure much of the necessary match funding from BPA. The existing aquifer recharge site was expanded with the four types of infiltration galleries and their associated monitoring equipment installed, the spreading basins were expanded, monitoring of surface flow improvements and groundwater level improvements were documented as part of the monitoring component, the limited license for water use was renewed, and multiple education and outreach events have occurred.

WWBWC staff have promoted this project with presentations at WWBWC meetings, and Walla Walla County Watershed Planning meetings, irrigation district board meetings, Umatilla County Groundwater Taskforce meetings, site tours for our Umatilla County commissioners, the Washington Governor's office staff and husband, Water Management Conference and local conference attendees, state agency staff, and members of the local community. This project has also been highlighted in presentations at the Network of Oregon Watershed Council Conference 2009, and the Oregon Association of Conservation Districts Conference of 2009. The project has also been described in articles in the Walla Walla Union Bulletin, the East Oregonian, Southwest Hydrology Journal, and the Capital Press.

This project type is not described in the Oregon Aquatic Habitat Restoration and Enhancement Guide. However, this project's proven ability to improve stream flows demonstrates an innovative technique to restore aquatic habitat by restoring groundwater levels that maintain base flows of spring creeks and rivers.

A Financial Report is attached. The following is a list of the report's appendices:

- I) Water Quality lab reports on samples of water used for recharge
- II) Limited licenses and applications
- III) Engineered Designs of infiltration basins, Infiltration galleries, and turnout structures at the site including additional explanation of the construction and operations
- IV) Recommendations and next steps

This project would not have been possible without the contributions from Hudson Bay District Improvement Company, OWEB, BPA, NRCS, OWRD, ODEQ, the Walla Walla Watershed Alliance, Bernie Hewes Engineering, Groundwater Solutions, Inc., OSU extension, and the dedication of WWBWC staff.

For further questions contact myself, Brian Wolcott, WWBWC Executive Director, or Rick Henry, Staff Hydrologist, at 541-938-2170.

Sincerely,

Brian Wolcott

RWallto



Aquifer Recharge as a Water Management Tool: Hudson Bay Recharge Testing Site Report (2004-9)



HBDIC Recharge Project Expansion with Basin #1 (foreground), spring 2008

April 18th, 2010

Prepared by

Bob Bower, Hydrologist, WWBWC Kevin Lindsey, LHG (WA), GSI

For

Hudson Bay District Improvement Company (HBDIC)

In Support of

OWRD Limited Testing License (Final Order #1059)
ODEQ Water Quality Reporting (Final Order #1059)
OWEB Grant Funding (#206-363)
BPA Grant Funding (#35684)

45 Years Ago...

"Some initial tests at artificially recharging the gravel aquifers by placing excess surface water into gravel pits and onto unused gravelly fields have reportedly helped raise temporarily the water level in wells of their vicinities. A comprehensive plan for the systematic management of the old gravel as a water reservoir is an obvious need that will surely come about ultimately. Such a comprehensive plan and systematic management will need to include all phases of natural and artificial recharge in order to obtain maximum benefits from this important natural water-storage facility."

Geology and Groundwater Resources of the Walla Walla River Basin, Washington-Oregon.

Robert Newcomb, USGS - 1965

"What you have to do and the way you have to do it is incredibly simple. Whether you are willing to do it is another matter." (Peter F. Drucker)

Table of Contents

45 Years Ago	2
Equations	<i>6</i>
Acknowledgements	<i>6</i>
Executive Summary	δ
PART I. BACKGROUND	11
Forward	11
Basin Overview and Development of Managed Aquifer Recharge	14
Historical Trends in Walla Walla Basin Aquifer Hydrology and Hydrogeology Leading to Managed Aquifer Recharge	18
What is Managed Aquifer Recharge?	28
Managed Aquifer Recharge – Not a New Idea	32
PART II. THE HBDIC ALLUVIAL AQUIFER RECHARGE PROJECT	<i>3</i> 3
Testing Managed Aquifer Recharge: HBDIC Site Operations and Monitoring (2004-9)	<i>3</i> 3
Site Specific Hydrogeology and Geology	37
The HBDIC Alluvial Aquifer Recharge Site	39
Overview	39
Spreading Basins Operations	
Deciphering the Variations in Recharge Volumes and Rates	48
Seasonal Temperature Fluctuations	
Water Table Mounding and/or Basin Clogging	
HBDIC Water Quality Monitoring Program and Procedures (2004-2009)	5 3
2004-2009 HBDIC Recharge Water Quality Results	
Aquifer Response to Recharge	
Site-Specific Groundwater Response	
System Wide Groundwater Response to Spreading Basin Operations	65
Spring-Creek Responses	72
Linking Spring Responses to Declines in Groundwater Storage	80
Other Recharge Results: Johnson Creek Recovery	81
Summary of Spreading Basins Testing and Recommendations	
PART III. INFILTRATION GALLERIES	
Infiltration Gallery Testing	83
Overview Infiltration Gallery Designs, Permitting and Testing	
Infiltration Gallery Designs, Fermitting and Testing	
Infiltration Gallery Testing Results – Preliminary	90
Cost-Effectiveness Summary	
Summary of Infiltration Gallery Testing and Recommendations	93

PART IV. SUMMARY, CONCLUSIONS, AND RECOMMENDATIONS	94
Summary of Results	94
Managed Aquifer Recharge – Balancing Storage	95
Moving Forward: From Testing to Programmatic Response	96
Bibliography	00

Appendices

Appendix I Laboratory Results

Appendix II Limited Licenses

Appendix III Infiltration Basin and Gallery Design Plans

Appendix IV Photographs

Table of Figures

Figure 1. State of Oregon Beneficial Waters Uses for the Walla Walla Basin	.11
Figure 2. Mechanisms that influence balance of shallow aquifer storage (WWBWC, 2007)	
Figure 3. Historical changes propagating the status of shallow aquifer storage balance (ΔS_G)	
Figure 4 Map of the Walla Walla Basin Watershed (Baker T., 2010)	
Figure 5. 1858 Mullen Map of Distributary Walla Walla and Little Walla Walla River System (Mullan, 1863)	
Figure 6. Bi-state Walla Walla and Little Walla Walla River System Area including Aquifer Recharge Testing (WWBWC)	.17
Figure 7. Site Map for Oregon Water Resources' State Observation Wells (1933 to present)	.19
Figure 8. Depicting drop in aquifer at observation well next to Walla Walla River	.20
Figure 9. Oregon State Observation Well (SOW 853 – WWBWC #GW-17) showing historic declines of shallow aquifer water table	.21
Figure 10. Map of Walla Walla River system spring-creeks (Oregon only), showing the basic distribution of the inner zone.	.22
Figure 11. Historic versus Current Flow monitoring on McEvoy Spring Branch, tributary to the Walla Walla Rive	er .23
Figure 12. Comparison of the Walla Walla River meanders from 1939 to 2006 (ODEQ, 2006)	.25
Figure 13. (A, B, C, and D) Historical Progression of Groundwater Development - Oregon: 1903-2005 (WRIS Do	ata,
Figure 14. Anaheim Lake, one of OCWD's recharge basins (Courtesy of OCWD website)	
Figure 15. Map of OCWD's "Groundwater Replenishment System" (Courtesy OWCD website)	
Figure 16. August, 2006, WWBWC staff toured the Aqua Fria Recharge Project outside Phoenix Arizona (Courte:	sy
C.A.P. website)	.31
Figure 17. Walla Walla River valley shallow aquifer system	.35
Figure 18 Sediment Stratigraphic Chart of the Walla Walla shallow aquifer units (GSI INC et. al., 2007)	
Figure 19. Major sedimentary layer of the Walla Walla River Valley Shallow Aquifer. (GSI, 2007)	
Figure 20. Top of Columbia River basalt, or bedrock boundary for shallow aquifer (GSI, 2007)	
Figure 21. Geologic Transect of White Ditch at HBDIC Recharge Site (Baker T., 2010)	.39

Figure 22. Original HBDIC Site Designs 2003 – Engineering by Bernie Hewes, PE Oregon	40
Figure 23. Map of HBDIC Recharge site and Source Water Delivery System	42
Figure 24. Comparison Walla River source water to Diversions and Use (WY 2009)	43
Figure 25. Aerial Map of HBDIC Recharge Site with Monitoring	44
Figure 26. 2004-9 HBDIC Recharge Flows (daily average – cfs)	
Figure 27. Comparison of fall vs. Winter Effective Recharge Rates for Temperature	49
Figure 28. HBDIC Effective Recharge rates (cfs) – 2004-9	50
Figure 29. HBDIC Recharge Rates in Acre-feet/day	51
Figure 30. Conceptual Diagram of Aquifer Recharge Mounding and Saturated Groundwater Movement	52
Figure 31. HBDIC On-site Observation Well Water Level Data (2004-9)	
Figure 32. Surface versus Groundwater Fecal Coliform Results (2004-9)	
Figure 33. Comparison of Source vs. Groundwater fecal coliform statistics (2004-9)	59
Figure 34. On-site Surface to Groundwater Response to Recharge Operations (2009)	
Figure 35. HBDIC Site Monitoring Wells and Various Sources of Recharge	
Figure 36. Comparison of White ditch and HBDIC recharge site operations to Groundwater Response	
Figure 37. HBDIC Site Observation wells Irrigation Season water levels (2004-9)	
Figure 38. Water Table Response to HBDIC Recharge Operations: May 1st - May 31st	
Figure 39. WDOE Funded Dedicated Observation Well at Pepper Bridge Vineyards Road Grange Hall	
(Washington)	66
Figure 40. Map depicting WWBWC's Bi-state Well Monitoring System of the Walla Walla River valley Shallow	
Aquifer System	66
Figure 41. WWBWC Monitoring Wells and Transects Relative Recharge System Response	
Figure 42. WWBWC Dedicated Monitoring Well used as up gradient Control for HBDIC Recharge Groundwater	
Response (2001-9)	
Figure 43. Water Levels at WWBWC Monitoring Well GW-31 (2002-9)	
Figure 44. Water Levels at WWBWC Monitoring Well GW-34	
Figure 45. Groundwater Response to recharge in Johnson and Dugger Spring-Creeks Subbasins (2009)	
Figure 46. HBDIC Recharge Site Flow Direction(September 2009)	
Figure 47. Groundwater Specific Conductance Map (Baker T., 2010)	
Figure 48. 2008 OSU IWFM Modeling Scenario for Johnson Creek (Petrides, 2008)	
Figure 49. Transect from HBDIC project site headwaters of Johnson and Dugger Creek Springs	
Figure 50. WWBWC Monitoring Wells (Transect B2) from HBDIC Site to near Headwaters of Johnson Creek	
Springs	75
Figure 51. Aerial Map of GW-65 and Gauges-Springs on Johnson and Dugger Creeks	
Figure 52. South Fork Johnson Springs (Pond) – Before and After HBDIC Operations (Bower)	
Figure 53. GW-65 vs LWJS Comparison of Groundwater to Spring Response to HBDIC Recharge Project	
Operations	78
Figure 54. Comparison of Historic versus Current Johnson Spring-Creek flows (OWRD/USGS and WWBWC)	
Figure 55. Comparison of Recharge Groundwater Response to Dugger creek Flow (WY 2008)	
Figure 56. Walla Walla Basin Aquifer Water Table Fluctuations and Historical Trends	
Figure 57. Johnson Creek flowing again after 25 years (Umapine, Oregon – Bower)	
Figure 58 Infiltration Gallery Testing Area (HBDIC Site)	
Figure 59. Infiltration Gallery #3 - Stormtech Chamber Installation (2008)	
Figure 60. Infiltration Gallery #4 - Atlantis Raintanks Installation (2008)	
Figure 61. Infiltration Gallery monitoring equipment (2009)	
Figure 62. Preliminary Results of TSS and Conveyance Attenuation from Source to HBDIC Recharge Site	
Figure 63. Piezometer water level results from initial operations of IG-1 gallery (2009)	
Figure 64. Walla Walla River Basin springs and groundwater returns to the Walla Walla River	
Figure 65. Balancing Storage with Managed Aquifer Recharge and other methods.	
Figure 66. Conceptual Graph depicting goals of ARSR program	

Table of Tables

42
46
47
5 <i>6</i>
57
91
93
12

Acknowledgements

Primary Contributors:

Principal Author: Bob Bower, MS-Eng., Hydrologist, WWBWC

Co-author: Dr. Kevin Lindsey, Ph.D., GSI

Technical Editor: Rick Henry, Hydrologist, WWBWC

Project Director: Jon Brough, Manager HBDIC

Project Manager (HBDIC), John Zerba, CPA, HBDIC-WWBWC

Brian Wolcott, Executive Director, WWBWC Bernie Hewes, PE, Engineering and Designs

Other contributors:

Will Lewis, Hydrologic Technician, WWBWC

Steven Patten, Hydrologist Technician, WWBWC

Troy Baker, GIS Analyst, WWBWC

Wendy Harris, Project Manager, WWBWC

Tony Justus, Water Master, OWRD

Jim Chambers, Assistant Water Master, OWRD

Donn Miller, Groundwater Division, OWRD

Phil Richerson, Hydrogeologist, ODEQ

Mike Ladd, Regional Manager, OWRD

Bill Neve, Water Rights Specialist, Water Rights Solutions

Bill Duke, Fisheries Biologist, ODFW Cindy O'Toole, Chemist, Edge Analytical Inc. Ari Petrides, Ph.D-Candidate, OSU John Selker, Professor, OSU

Funding Provided by:

Oregon Watershed Enhancement Board
Natural Resource and Conservation Service
Hudson Bay District Improvement Company
Walla Walla Watershed Alliance
Bonneville Power Administration
Environmental Protection Agency (319 Program)

Special Thanks:

The HBDIC Board of Directors
The WWBWC Board of Council Members
OWEB Board of Directors

Dedicated to the citizens, water users and salmon recovery advocates of the Walla Walla Basin. Without the "can-do" spirit of the people of the Walla Walla River valley, none of this would have been possible.

Executive Summary

The Walla Walla Basin is a bi-state basin in northeastern Oregon and southeastern Washington, through which flows the Walla Walla River. The Walla Walla River, and its tributaries, originate in the Blue Mountains, and generally flow westward to a confluence with the Columbia River near Wallula Gap. The river system itself is a primary passage and rearing habitat for ESA-listed steelhead and bull trout, and a focus of tribal efforts at Chinook salmon and lamprey restoration. In addition, the portion of the Walla Walla River system which lies within the Walla Walla Basin and is the focus of this report overlies an alluvial aquifer system that displays a high degree of hydraulic continuity with the River. In the past 50 to 60 years a large number of wells (large and small) have been drilled into, and extract water from, this alluvial aquifer system.

This report:

- 1. Describes the basic hydrologic conditions that have developed in the Walla Walla Basin in response to development of basin water resources.
- Looks more closely at alluvial aquifer system conditions that have developed including a
 history of water level decline and the possible impacts these declines have had on streams and
 springs
- 3. Describes the results of six seasons of shallow aquifer recharge (SAR) activity at the Hudson Bay site.

The Setting: Alluvial sediments (clay, silt, sand, and gravel) largely derived from the adjacent Blue Mountains fills the Walla Walla Basin to a depth of 800 feet in some places. These strata filled a basin that formed as the basalt bedrock that underlies the region was down-dropped by a series of folds and faults that formed in response to regional tectonic stresses. As this bedrock dropped, sediments washed off the Blue Mountains by the ancestral Walla Walla River and other streams collected in the subsiding basin.

Prior to the advent of widespread diversion of surface water and groundwater for agricultural irrigation, industrial uses (primarily food processing), stock watering, and domestic and municipal water supply the Walla Walla Basin was crossed by a series of streams that drained off the Blue Mountains. Most of these streams flowed year round. In addition, as a result of seasonal snow melt and flooding these streams recharged an aquifer system hosted by the alluvial sediments filling the Basin. One of the manifestations of that recharge was the presence of numerous springs on the valley floor. These springs showed the locations where the aquifer system, once fed by seasonally flooding and recharge, discharged to surface waters providing base-flow for streams. In another sense, the abundant springs and streams demonstrated that the alluvial aquifer system was full, and had achieved an equilibrium that balanced recharge with discharge. With the advent of permanent settlement, irrigated farming, and the development of supporting industry, the hydrology of the basin was changed.

Changing Hydrologic Conditions: In the years following the establishment of the Whitman Mission, Fort Walla Walla, and the towns that now dot the Walla Walla Basin landscape, natural streams tributary to the Walla River, and the Walla Walla River itself, have been straightened and channelized to

facilitate the delivery of irrigation water and reduce the extent of seasonal flooding. Stream channel straightening, coupled with the draining of wetlands and boggy areas has increased cropped acreage, pasture availability, and rural residential home building sites. In recent years, un-lined ditches have been replaced by lined ditches and pipes to reduce water conveyance losses and withdrawals from the Wall Walla River. In addition, the primary irrigation districts active in the Basin have reduced the period of time during which they divert water from the Walla Walla River.

All of these actions resulted in the loss of alluvial aquifer recharge; as the residence time and spreading of surface water in the basin was reduced. These actions also likely facilitated a decline in alluvial aquifer water level as channel straightening led to channel deepening; this in turn led to declines in aquifer base level. With alluvial aquifer water level declines, stream flows were further impacted as base-flow and spring-flow was lost. Coupled with these changes to the surface hydrology has been a parallel increase in the number of wells extracting water from the alluvial aquifer system. The impact of these factors on Walla Walla Basin hydrology includes reduced river flow, a flashy river system, and declines in aquifer levels and corresponding base-flows, coupled with diminished aquifer storage.

Recognizing these trends, the Walla Walla Basin Watershed Council (WWBWC) in partnership with the Hudson Bay District Improvement Company (HBDIC) decided in 2003 and 2004 to build a pilot alluvial aquifer recharge project. The goals of this project are to test the feasibility of SAR, develop operational and monitoring plans that can be used to facilitate future SAR projects. Most importantly, the project aims to recharge the alluvial aquifer to the extent possible given the physical constraints of the recharge site and the surrounding aquifer system. Recharge operations have been conducted at the HBDIC SAR site in the winter and spring of each of the past 6 years, or seasons.

The HBDIC SAR Project: Construction and recharge operations at the Site began in the late winter and spring of 2004. At that time 3 infiltration basins, totaling 0.34 acres in size, were constructed adjacent to the HBDIC's White Ditch. The White Ditch delivers Walla Walla River water to the Site. Site recharge operations began in March 2004 after receiving Oregon Water Resources Department Limited License LL-758. This license permitted SAR at the site under OWRD's aquifer recharge rules, and includes:

- 1. Groundwater and source water monitoring requirements.
- 2. Stipulations on Site operation related to flows that can be delivered to the Site and minimum flows required in the Walla Walla River (the source of water for the project) to allow the project to operate.
- 3. The length of each recharge season, November 1st through the following May 15th.
- 4. Reporting criteria and requirements.

The license was granted following review and comment by other affected entities, including the Confederated Tribes of the Umatilla Indian Reservation and Oregon Department of Environmental Quality.

During the second season of operation, the 2004-2005 recharge season, the infiltration basins were increased in size, to a total area of 1.1 acres. A fourth basin was added during the 2007-2008 recharge season, increasing the total size of the infiltration basins to 1.4 acres. The original limited license

expired in February 2009. In lieu of an application for a permanent water right to operate the HBDIC SAR project, a second limited license (LL#1059) was granted to the project that extended the operational schedule to the summer of 2013. During the 2008-2009 recharge season, all four infiltration basins plus a series of four infiltration galleries were operated.

Through the course of the six recharge seasons completed to-date, the site was operated for a total of 602 days. During this time, approximately 13,100 acre-feet of water was discharged to the underlying alluvial aquifer system. Recharge volumes ranged from a low of approximately 400 acre-feet during the first recharge season, 36 days in the spring of 2004, to a high of 3200 acre-feet in the 128 day long 2006-2007 recharge season. The HBDIC SAR project is interpreted to have had a beneficial impact on the surrounding area, including restoration of flow from the springs that feed Johnson Creek and increased water levels seen in wells in the vicinity of the Site. The fact that long-term water level declines appear to have been slowed, or even reversed in wells in the area of the project suggest that SAR has the potential to both increase water levels in the alluvial aquifer and replace water lost to pumping (increase storage). Groundwater quality also has been shown to have not been degraded as a result of the project.

Conclusions: Our basic conclusion is that the HBDIC SAR project shows that this type of activity is a viable option for water resource managers in the Walla Walla Basin. SAR recharges the aquifer in areas where natural recharge mechanisms have been lost. As long as good quality water is used, such as is naturally flowing into the Basin via the Walla Walla River, alluvial aquifer degradation is not expected to occur. Selectively locating SAR sites across the Basin has the potential to help water managers replenish depleted groundwater supplies and provide clean, cold base-flow to streams and springs at critical times. Some challenges for future SAR projects will be finding locations that allow water managers to meet such goals and acquiring a source of water to use for SAR.

PART I. BACKGROUND

Forward

Water remains at the center of nearly all the current natural resource restoration efforts in the bi-state Walla Walla Basin. The State of Oregon has designated beneficial uses¹ for water in the Walla Walla Basin's to include fish and aquatic life, wildlife, domestic supply, irrigation, livestock, industrial, boating, recreation and for its aesthetic qualities (**Figure 1**). The water needs have changed over the years and now the pressure has increased to find water to ensure all beneficial uses are supplied and maintained. Like many watersheds across the arid western United States, water managers and watershed planning groups struggle to find solutions to the water supply – demand balance. In the Walla Walla Basin, there has been increasing interest in the capture and storage of surplus wet season (winter/spring) water for use during the times when supply is at a deficit. Currently there are a number of groups working to design tools for aquifer management, including: building small and large scale surface-storage reservoirs, a Columbia River pumping exchange projects, a water banking system for surface and groundwater rights, and as this document details the use of managed aquifer recharge for subsurface-storage.



Figure 1. State of Oregon Beneficial Waters Uses for the Walla Walla Basin.

The main purposes of this report are to provide an introduction to managed aquifer recharge (MAR) as a water management tool, the water management needs it targets and provide a report on the design, operation, monitoring and analysis conducted at the basin's largest recharge site, the HBDIC Recharge Site from 2004-9.

¹ OAR 340-04-0330 Table 330A. Online at: http://www.deq.state.or.us/standards/WQstdsFinalGenBenUseTables.htm

Managed aquifer recharge and the use of natural landforms or features to store water are in concert with the WWBWC' community-based mission:

"Protect the resources of the Walla Walla Watershed, deal with issues in advance of resource degradation, and enhance the overall health of the watershed, while also protecting, as far as possible, the welfare, customs, and cultures of all citizens residing in the basin." (WWBWC, 2003)

The community's exploration of MAR demonstrates the emerging appreciation that real solutions to water resource challenges of the future are non-simplistic (e.g. pipe water here, save it there) and cannot be solved by trying to isolate interconnected parts into unilateral solutions. As water continues to be an issue of varying political views it is important to clearly state the perspective from which this report is written with assumptions being:

- 1. The Little Walla Walla River system was historically and is currently an important part of the management of the basin's surface and subsurface water resources; particularly as they relate to flow in the Walla Walla River mainstem.
- 2. The historic springs that rely on the shallow aquifer are worthy of protection and restoration, and they serve critical physical and biological roles in the health of the watershed system.
- 3. Solutions to our water management issues will only be achievable if surface and groundwater is managed conjunctively into the future.

To define the occurrence of water in the shallow aquifer, it is easiest first to discuss the aquifer as it relates to the watersheds overall water balance. For all practical purposes we can treat the water balance of the Walla Walla watershed as a closed system, meaning there are no significant external inflows or outflows of groundwater. However it should be clarified for the purposes of this discussion that an aquifer's storage is always changing due to time related events ranging in minutes to years. Storage can change due to rainfall, spring river freshets, irrigation season well pumping and a long list of other hydrologic events. But when you view this system on a longer timeline for the purpose of managing the resource for future use, this is when trends in storage can be effectively assessed. The general water balance is:

$$P = Q + E + \Delta S_S + \Delta S_G$$

Equation 1 Watershed Water Balance (budget) Equation (Freeze, 1979)

Where **P** represents all the precipitation that falls on the watershed, **Q** (discharge) represents all the flow that leaves the watershed via the surface, **E** as the total evapotranspiration, or the sum of all evaporation and plant transpiration, ΔS_S as the change in storage of the surface-water reservoir and ΔS_G representing the change in storage of the groundwater reservoir. The value for ΔS_G or change in groundwater storage is dictated by the balance between what is recharged to how much is discharged from the confined and unconfined aquifers of the basin. For the purposes of this discussion, we focus on only the changes that influence the balance of groundwater storage in the shallow aquifer system.

Conceptually the shallow aquifer ΔS_G can be seen as dependent on the net balance between inputs (recharge) and outputs (discharge). The physical mechanisms that induce infiltration or recharge to groundwater storage (S_G) come in a variety of forms including precipitation, channel bed losses from streams, rivers and ditches, and the application of irrigation water such as flood, rill or sprinklers. Mechanisms by which groundwater storage (S_G) is lost or discharged include well pumping, groundwater seepage directly to channel beds and springs and seeps, and the evapotranspiration of water though agricultural vegetation with roots that extract water directly from the aquifer's water table (**Figure 2**).




Figure 2. Mechanisms that influence balance of shallow aquifer storage (WWBWC, 2007)

We define an aquifer' storage as balanced or *sustainable* when the net quantity and timing² of recharged water is equal relative to net quantity and timing of discharge water (**Figure 3**). A system is out of balance when storage is either increasing or decreasing.

² For the purposes of this introductory to recharge, a steady-state water balance was assumed.




Figure 3. Historical changes propagating the status of shallow aquifer storage balance (ΔS_G)

Basin Overview and Development of Managed Aquifer Recharge

The Walla Walla basin is located in Northeastern Oregon and Southeastern Washington (Figure 4). This bi-state system's primary water supply comes from the Walla Walla River which originates in the Blue Mountains of Oregon and flows down through Washington to the Columbia River near Wallula Gap. This river system is the Walla Walla watershed's primary passage and rearing corridor for ESA-listed steelhead and bull trout, and species of tribal cultural significance including chinook salmon and lamprey. In addition, it also serves as the main recharge source for the underlying shallow aquifer system. The Walla Walla River also has had two EPA required Total Maximum Daily Load (TMDL) assessments for nonpoint source pollution which were completed in Oregon (ODEQ-WWBWC) for temperature and in Washington (WDOE) for soluble organic compounds, temperature and sediment.




Figure 4 Map of the Walla Walla Basin Watershed (Baker T., 2010)

The area this report focuses on is the Walla Walla River Valley subbasin.³ In this subbasin the Walla Walla River historically exited the highlands bordering the basin, at which point it branched into a system of distributary channels that flowed out across the valley floor. These channels then recombined into a single main channel in the central portion of the valley (**Figure** 5). Within this branched distributary stream system groundwater fed spring-creeks were common. With agricultural development, many of these distributary branches were converted to and connected by, irrigation water delivery ditches and connecting lateral ditches.

Newcomb (1965), and even before him Piper (1933) provided a very compelling argument that showed the distributary and spring system was created and maintained over the top of an unconfined alluvial aquifer system. This aquifer supplies the baseflow for more than 50 valley spring-creeks in Oregon and Washington that historically provided year-round baseflow in the form of cool groundwater and off-channel habitat to the mainstem (**Figure** 6). The 240 square-mile

³ 2006-2010 Development of a Surface-groundwater model to use as a flow restoration and aquifer replenishment planning and management tool.

aquifer also provides direct groundwater contributions in channel to the mainstem Walla Walla River which is particularly important during the summer irrigation and fisheries rearing and passage season. With historically braided and meandering channels and native beaver populations helping to pond and slow water down, the Walla Walla or as the Cayuse Tribe named this subbasin the "land of many small waters" historically supported a thriving salmon fisheries and miles of distributary habitat.




Figure 5. 1858 Mullen Map of Distributary Walla Walla and Little Walla Walla River System (Mullan, 1863)

With the onset of irrigated agriculture, the way in which water was redistributed and used began to change the hydrologic balance of this system. Naturally meandering rivers and creeks were straightened for flood control and irrigation water delivery, acting indirectly to speed up the flow of water through the system. This was offset to a degree by the valley's early flood and rill irrigation practices and the development of the lateral ditch system that acted to effectively 'slow' surface

run-off. By redirecting surface waters away from the primary natural flow corridors, such activities were acting to unintentionally help recharge the underlying shallow aquifer system.

Coupled with these changes to the aquifer's ability to be replenished (recharged) there were subsequent dramatic increases in groundwater use. The dramatic increase in the number of wells for primary and supplemental irrigation rights acted to increase the amount of water coming out of groundwater storage. The net hydrologic impact of these changes was an aquifer-spring system that experienced reduced storage, as recharge was decreased and discharge was increased; creating an overall decline in storage that has manifested itself in a declining water table and the drying up of natural spring flows.




Figure 6. Bi-state Walla Walla and Little Walla Walla River System Area including Aquifer Recharge Testing (WWBWC)

While this surface to groundwater connection was first outlined by the USGS in 1933 (Piper, 1933) and again in 1965 (Newcomb, 1965) it was not revisited until the summer of 2000 that the community was forced to reexamine the situation. Starting with the ESA listing in 1998 and the *American Rivers* listing of the Walla Walla River on the top-10 most endangered rivers list in 2000, federal fish agencies worked out an agreement with the three larger irrigation districts to divert less water to these distributary branches and ditches and leave more in the 'mainstem' Walla Walla

River. This agreement re-watered an Oregon section of the river with 1/3 of the volume that had previously been diverted to irrigation during critically low summer-time base flows and was heralded nationally as a model of cooperation. However these dramatic changes in water management in the Little Walla Walla river system along with the piping of leaky ditches to stretch less water further had both immediate and longer term consequences. The springs that had been providing some baseflow (although not at historical potential) back to the Walla Walla River dramatically declined to the point that by 2009 many are nearly dry year round.

Through a series of public and WWBWC meetings, the WWBWC and its partners began to examine the historic conditions of these streams and their connection to the underlying alluvial aquifer; which they depend on for baseflow. Starting in 2001, the WWBWC and partners started developing a monitoring network and series of on-the-ground aquifer recharge projects designed to address these water management challenges. With the development of the Bi-state Watershed Management Initiative (WMI) Monitoring Program (2005 – present) a monitoring network currently comprising of over 110 wells and 50 stream flow gauges has been developed to monitor 'pre' and 'post' flow restoration conditions and provides the basis on which to build a programmatic solution. This program also funded a number of other technical activities from which to base the development of this program including: stratigraphy maps of the alluvial aquifer, a finite-element surface-groundwater numerical model (OSU) and various other field projects that help characterize the extent and properties of the shallow aquifer system.

Three main recharge projects have provided the basis upon which the WWBWC and its partners are now developing the Aquifer Replenishment and Spring Restoration (ARSR) Program (See Moving Forward Section). The Hudson Bay District Improvement Company's (HBDIC) aquifer recharge project was the first of its kind in Oregon and Washington in both its physical design and its water quality monitoring plan (co-developed with ODEQ and OWRD staff). The HBDIC recharge project site, a 7-acre area Northwest of Milton-Freewater, is entering the final phase of its three part expansion under this program. The two other recharge testing projects funded by Washington's Department of Ecology include one testing field flooding⁴ as a mechanism for aquifer recharge with the other using a historic gravel pit to recharge winter-spring water into groundwater storage. All of the sites have been providing detailed information on the designs, operations, monitoring and permitting-planning needs to implement aquifer recharge in the Walla Walla Basin.

Historical Trends in Walla Walla Basin Aquifer Hydrology and Hydrogeology Leading to Managed Aquifer Recharge

Generally the Walla River, its tributaries, its distributaries and the shallow gravel aquifer they pass over are interpreted to be highly interconnected. Water moves relatively easily between ditches, streams, rivers and the shallow alluvial aquifer because of the highly permeable nature of gravel streambed channels so common across the Basin, and the gravelly character of the underlying alluvial aquifer system. Depending on the spatial variation in these streambed and aquifer conditions, the

⁴ Hall-Wentland farm fields and the Locher Road historic gravel pit

degree of hydraulic connection between surface water and groundwater and the location of gaining and losing stream reaches generally can be defined by the depth to groundwater.

A survey of historical data shows changes in alluvial aquifer groundwater levels over time. WWBWC staff reviewed the existing data collected by Oregon Water Resources Department (OWRD) staff at historic observation wells originally set up by the United States Geological Survey (USGS). A total of 11 state observation wells (SOWs) that monitor the shallow, unconfined alluvial aquifer system were reviewed for trend information (**Figure** 7. Reviewing the data from the SOWs showed that all eleven wells display a downward trending water table with three (SOW # 844, 845, 857⁵) now having gone completely dry.

Taking a closer look at data from the OWRD SOW wells, SOW #850 shows approximately a 5 feet decline between 1940 and 2005 (**Figure** 8). The aquifer decline at this location is particularly




Figure 7. Site Map for Oregon Water Resources' State Observation Wells (1933 to present)

⁵ SOWs 844 and 845 have since been abandoned and backfilled due to lack of water to measure and posed a safe hazard.

Historical Static Level GW-20 G Ransom (OWRD SOW well: 1949 to 2005)




Figure 8. Depicting drop in aquifer at observation well next to Walla Walla River.

alarming because it is in an area near the Walla Walla River channel where considerable flow losses to the aquifer through the porous channel bottom is known to occur. Therefore, even with a steady source of recharge water available, aquifer level appears to be declining. This well location also sits on the geologic arc or contour of the 'inner zone springs'. Consequently, water level changes seen in it may provide insights into conditions expected within this zone of springs.

The well with one of the longer periods of record is SOW #853 (McKnight Well). It is located approximately 3 miles west, and down gradient from the Walla Walla River and Little Walla Walla River distributary system (**Figures** 7 and 9). The primary sources of recharge for this well generally are thought to include seepage from the Walla Walla River, the Little Walla Walla River, irrigation ditches and flood irrigation. This well demonstrates a characteristic found in nearly all of the historically hand-dug wells⁶ in the Walla Walla River valley; alluvial aquifer water levels have dropped below the base of the well which was once productively producing water from the upper few feet of that aquifer. By 2001, this well was dry nearly year round with very little recovery during the winter-spring freshet period.

⁶ Hand dug wells originally dug and utilized starting in the late 1800s. A typical design was a 6' x 6' hole, hand dug down to approximately 25-60 feet below ground surface. Water was originally extracted using a rope, pulley and bucket but later as combustion and electric water pumps became available, they were used to provide water for irrigation and domestic purposes. The WWBWC field staff, through working with numerous well owners around the valley, that a majority of these wells have been either outright abandoned, re-drilled deeper using casing and/or back filled all due to them having gone partially or completely dry.




Figure 9. Oregon State Observation Well (SOW 853 – WWBWC #GW-17) showing historic declines of shallow aquifer water table.

Complementing the observation well data is the information provided by surface flow data collected at numerous springs across the Walla Walla River valley. Originally surveyed and measured by the USGS (Piper, 1933; Newcomb, 1965) these springs provide an excellent surficial indication of status of subsurface water supplies. In the early 1930s, Piper described these springs as a "…integral part of the natural drainage system of the alluvial fan" and likened them to "the spillway of a reservoir, for they are supplied by overflow from the ground-water reservoir in the permeable alluvium… Consequently, the yield of the springs measures the decreased transmission capacity of the young alluvium." (Piper, 1933)

He went on to note that well before his work in the 1930s, there were problem areas being identified with "springs at the east end of the inner zone (Big Spring area) has decreased in the last 10-25 years.", putting the start of the decline of the system somewhere around 1900. He also confronted the continuing debate that the springs were simply a product of up gradient water management practices such as flood irrigation by carefully noting: "The regimen of the springs may well have been influenced in historic time by irrigation on the alluvial fans and flood plains but the springs were not created by that irrigation." (Piper, 1933)

⁷ The Big springs may have gone done due to more water being diverted to the East and West Prongs of the Little Walla Walla River, since the mainstem or Tum-a-lum Branch was used mainly in the winter for a flood control channel.

Walla Walla valley spring systems generally occur in two areas, the Little Walla Walla River and the Mill Creek—Yellowhawk Creek systems. The focus of this report is on the area Piper termed the "inner zone" where more than 30 springs occur on a contour-arc across the Walla Walla River alluvial fan near Milton-Freewater, Oregon (**Figure 10**). The hydrogeology created by a combination of geologic events, alluvial sedimentology and variation in hydraulic conductivity play significant roles in determining where and why these springs emerge.

Many of these *inner zone* springs are still flowing today, although their output has decreased significantly over the years. Piper measured these springs during his work in 1932-1934 which was continued until the early 1950s by the state of Oregon. Newcomb (USGS, 1965) contrasted Piper's measurements to that of his own and concluded:

"Under the natural and irrigation recharging of the 1930's and 1940s about 50,000 acre-feet of water passed through the gravel unit and flowed from the outlets during the average water year. Water diverted by pumping from wells has modified this formerly normal discharge as have changes in the recharge resulting from irrigation and other water regulation practices." (Newcomb, 1965)




Figure 10. Map of Walla Walla River system spring-creeks (Oregon only), showing the basic distribution of the inner zone.

Starting in 2001, the WWBWC-Oregon State University Research team field surveyed these springs and set up flow monitoring stations at or as close as was feasible to where Piper had originally measured them. While the story tends to be the same across the inner zone spring system, the McEvoy Spring (just north of Washington/Oregon Stateline) is representative of their general degraded conditions. Measuring near the exact location measured in the 1930s, flows now represent a fraction of their historic averages (**Figure 11**). Also note the seasonal pattern of historical flows in McEvoy creek which are related to upgradient changes in irrigation water management and Little Walla Walla River flows.




Figure 11. Historic versus Current Flow monitoring on McEvoy Spring Branch, tributary to the Walla River

As of 2009, McEvoy Creek is often dry for a significant portion of the year. A local farmer and member of the Native Creek Society, Tom Page⁸ was born, raised and still farms next to McEvoy Creek, and has publicly spoken many times about as his youth and being able to swim, fish for trout and irrigate out of the stream. Tom Page has worked to document the history of McEvoy Creek and many of the other valley spring-creeks providing some historical context to the loss of these natural resources.

"The namesake of McEvoy Spring Branch was John McEvoy. John McEvoy was married to Flora McBean, the daughter of William McBean. William McBean settled in the Walla Walla Valley in the 1840's when he worked for the Hudson's Bay Company. He was the Clerk in Charge at Fort Walla Walla at the time of

⁸ Tom Page is the co-founder of the Native Creek Society, has led a riparian and stream morphology restoration project and is operations lead for the McEvoy Spring Creek Aquifer Recharge Testing project.

the Whitman Massacre in 1847. When he retired from Company service in 1851 he filed for a Donation Land Claim (#39), one of a handful in the Walla Walla Valley. It is interesting to note where he staked the boundaries of his claim, a mile square and 640 acres. His reasoning must have been to encompass the most possible water resources within its boundary." (Page, 2007)

Moving west on the contour-arc of the Walla Walla River springs and further from the major sources of recharged water; the flow volume situation gets significantly bleaker. Dugger Creek which is fed by springs that are the furthest west on the inner zone was measured in the early 1930s to be between 8-10 cfs through the summer season (USGS/OWRD data). The Dugger Creek drainage is now an area of high tension among water right holders due to what little irrigation season flows remain. Recently the WWBWC set up a gauge station directly at the site that Piper measured the 8-10 cfs, and in early July 2007 measured 2.1 cfs but by month's end the creek was completely dry.

Through the history of the Walla Walla basin there have been significant changes to the mechanisms that control both sides of this storage balance. Natural recharge has been altered in a number of ways, one of which is the historical manipulation of the streams and river's channel shapes and structures (**Figure 12**). Historically rivers were channelized for flood control structures, to increase agriculturally productive areas, and to allow for structures such as bridges and roads to be built. These actions while providing community benefits also resulted in rivers and streams that were shorter in length which in turn decreased the amount of resident-time that water was in the basin and available for recharge via channel bed infiltration. Additionally for decades the federal and states governments actively promoted the draining of wetland areas to increase agricultural production which also acted to reduce the recharge potential by decreasing the residence time water had in the basin.





Figure 12. Comparison of the Walla Walla River meanders from 1939 to 2006 (ODEQ, 2006)

As irrigated agriculture became more prominent in the valley, the addition of lateral ditch systems and irrigation practices such as flood or rill irrigation acted to increase the recharge side of the balance. The USGS recently published a regionally relative report titled; *Estimates of ground-water recharge to the Yakima River Basin Aquifer System, Washington, for predevelopment and current landuse and land-cover conditions*.(USGS, 2006) In this report they quantified through modeling, the additional water contributed historically by irrigated agriculture to the groundwater storage balance. They estimated approximately a 38% (from 3.9 to 5.1 Million acre-feet) increase in recharged water entering the Yakima River aquifer from irrigation to that of pre-irrigation conditions. Therefore in the Walla Walla basin the expansion of irrigated agriculture has most likely added to the 'recharge' portion of the equation which has helped in part mediate for the dramatic increase in discharge or water use from the aquifer.

During the same period that irrigated agriculture was increasing the quantity of water being applied, the development of the aquifer's groundwater was taking place thus, increasing the discharge side of the storage balance (ΔS_G). Starting in the early 1900s, water wells were dug throughout the Walla Walla River valley for domestic, agricultural, municipal and industrial uses. Oregon Water Resource's Water Rights Information System (WRIS) database and Geological Information System (GIS) shows the numerous points of diversion (surface or groundwater) throughout the Oregon portion of the Walla Walla Basin, a significant majority of which are located in the Walla Walla River Valley.

Focusing specifically on Oregon's portion of the shallow aquifer, a WWBWC analysis of OWRD's WRIS GIS⁹ database indicates that there are more than 650 permits¹⁰ for irrigation wells with water rights totaling approximately 360 cfs, in the study area._Mapping this GIS information¹¹, **Figure** 13 (A, B, C, D) shows the historical progression of groundwater development in the Oregon portion of the shallow aquifer from 1908 to present. By 1908 primary irrigation wells were being permitted in the Walla Walla valley (**Figure** 13 A). About the time of the first hydrogeologic study of the basin (Piper, 1933), there was already a significant number of wells in the orchard area around Milton-Freewater (**Figure** 13B). When Newcomb was finishing his assessment, and Barker-McNish were starting their modeling project (USGS, 1976) permits for supplemental water rights, those used when the primary source (surface or groundwater) is no longer available due to lack of water, were becoming more prevalent for groundwater (**Figure** 13 C). And by December 31st, 2005, the permits for groundwater use had moved to all areas of the shallow aquifer system (**Figure** 13D).




A. 1908


⁹ http://www.wrd.state.or.us/OWRD/WR/wris.shtml

 $^{^{10}}$ Included in this data were wells cased into the confined, basalt aquifer system.


¹¹ Utilizing the GIS defined points of diversions and sorting them by priority date, a historical sequence of irrigation wells (water use codes IC, IS) was done by the WWBWC. Permits shown include those for wells drilled into the basalt, and do not include the exempt wells discussed by Wozniak.



B. 1930



C. 1970



D. 2005

Figure 13. (A, B, C, and D) Historical Progression of Groundwater Development - Oregon: 1903-2005 (WRIS Data, 2006)

Therefore the history of shallow aquifer development along with the surficial changes in water management has lead to dramatic changes to the shallow aquifer's water balance. The summation of these changes reflected in the historical groundwater levels and spring flows show a surface-groundwater system in decline.

What is Managed Aquifer Recharge?

In the western United States, managed aquifer recharge or MAR has been used for decades as a tool to help resolve water management issues. Three of the most common applications of recharge are for subsurface water storage and retrieval, offsetting salt water intrusion issues in impaired coastal aquifers, and mitigating for groundwater pollution issues. The objective of MAR is to capture and store available water into underlying aquifers and in the case of aquifer storage and recovery (ASR) retrieve that water for use when surface water is scarce. Some of the most common methods used to 'artificially' recharge groundwater are things such as engineered spreading basins, direct well injection and the use of streams and irrigation ditches as surficial water infiltration systems.

Water managers in many parts of the world have proven it to be cost effective way to capture and store water for these and many other water management needs. Significantly lower costs, land

availability, and surface associated environmental concerns have made it an attractive alternative to more conventional water management tools such as dammed surface reservoirs and desalination plants. In response to this growing demand the American Society of Civil Engineers has established a standardized set of guidelines for aquifer recharge for use as a water management tool in its publication titled *Standard Guidelines for Artificial Recharge of Groundwater* (ASCE, 2001). This publication gives a good general overview of the specific engineering, societal, and watershed planning issues associated with aquifer recharge and is an excellent place to start for those new to the field.

In the western United States two of the most prominent recharge projects occur in Orange County, California and in the Phoenix, Arizona metropolitan area. In southern California, Orange County Water District (OCWD) supplies water to millions of patrons via aquifer recharge and their renowned 'Groundwater Replenishment System¹² (**Figure** 14 and 15). In the technical circles of aquifer recharge, OWCD is often referred to as leaders in the application of aquifer recharge in the US, and many municipalities and other interested parties have toured and even trained with the OCWD staff to learn how they apply and maintain this tool for water management applications.

Their recharge program plays a large and critical role in supplying water on a year-to-year basis for their ever growing population:

"Groundwater reserves are maintained by a recharge system, which replaces water that is pumped from wells. OCWD's facilities have a recharge capacity of approximately 300,000 acre-feet per year. About two million people depend on this source for more than three-quarters of their water. Groundwater producers (city water departments and other local agencies) pump water from the groundwater basin and deliver it by pipeline to consumers. 13 (OWCD)

While they have more than 9 separate recharge facilities, one of the largest are some former gravel pits that were converted into an aquifer recharge facility and "currently recharge up to approximately 120 to 140 cubic feet per second (cfs) when full."¹⁴

¹² http://www.gwrsystem.com/about/background.html

¹³ http://www.ocwd.com/ html/recharge.htm

¹⁴ http://www.ocwd.com/_assets/_pdfs/_rfp/SantiagoCreekInitialStudy.pdf



Figure 14. Anaheim Lake, one of OCWD's recharge basins (Courtesy of OCWD website)




Figure 15. Map of OCWD's "Groundwater Replenishment System" (Courtesy OWCD website)

In the Phoenix Arizona metropolitan area aquifer recharge is also considered a critical component to its current and future water management planning needs. The Central Arizona Project or C.A.P.¹⁵ project utilizes Arizona's allocation of Colorado River water (according to the multi-state, Colorado River Compact) to supply more than 1.5 million acre-feet annually to this region. Currently Arizona is not exercising its full allocation of Colorado River water rights. The unused portion which is in excess of 460,000 acre-feet annually is going to a multiple spreading basin aquifer recharge program, storing it for future use. The CAP program refers to aquifer recharge as playing:

¹⁵ http://www.cap-az.com/index.cfm

"Recharge is a long-established and effective water management tool that allows renewable surface water supplies, such as Colorado River water, to be stored underground now for recovery later during periods of reduced water supply." 16

During August 2006, the WWBWC staff hydrologist participated in a tour of two CAP recharge projects just outside of Phoenix (**Figure** 16). A CAP hydrogeologist and project manager provided informative demonstration of projects whose geologic and hydrologic settings were similar to those experienced in the Walla Walla basin. This information has proven useful in the continued refinement of our local design efforts of this tool and application for our current water management issues.



Figure 16. August, 2006, WWBWC staff toured the Aqua Fria Recharge Project outside Phoenix Arizona (Courtesy C.A.P. website)

Locally MAR was first explored in the 1970s by the City of Walla Walla who began testing and implementing a direct injection Aquifer Storage and Recovery (ASR) program. This program stores water in the basalt aquifer during the high flow portions of the water year and then reclaims the water during the high demand summer season.

The list of national and international water programs that feature aquifer recharge as one of their management tools is extensive and too numerous to cover in this report. Setting up a system that complements and enhances the other water management strategies for the Walla Walla basin is merely a matter of designing and collaborating to find better ways to store water. With a better understanding of MAR application elsewhere, we can begin to discuss the water issues facing the basin and its intended application in solving those problems.

http://www.cap-az.com/static/index.cfm?contentID=81

Managed Aquifer Recharge - Not a New Idea

From these early assessments documenting the decline of the aquifer and associated springs artificial aquifer recharge was considered early in the assessment process as it was recommended by the USGS in 1965. R.C. Newcomb's' report titled *Geology and Ground-Water Resources of the Walla Walla River Basin Washington-Oregon* (USGS, 1965) is considered to be one of the most comprehensive assessment of the Walla Walla basin's water resources. R.C. Newcomb, who was highly respected in his time, had worked extensively in the arid American west assessing the geology and hydrology of many hydrologic systems. He was an early proponent for using our understandings of subsurface geologic features to store and manage water resources. Before coming to the Walla Walla basin, he had worked elsewhere in the Columbia basin and published a series of studies, one of which was titled: *Storage of ground water behind subsurface dams in the Columbia River basalt, Washington, Oregon, and Idaho, by R.C. Newcomb* (USGS, 1961), demonstrating his innovative approach to finding cost effective ways of better managing water. For the Walla Walla basin he observed:

"Some initial tests at artificially recharging the gravel aquifers by placing excess surface water into gravel pits and onto unused gravelly fields have reportedly helped raise temporarily the water level in wells of their vicinities. A comprehensive plan for the systematic management of the old gravel as a water reservoir is an obvious need that will surely come about ultimately. Such a comprehensive plan and systematic management will need to include all phases of natural and artificial recharge in order to obtain maximum benefits from this important natural water-storage facility." (USGS, 1965)

It was from Newcomb's early discussion of the potential of aquifer recharge that led the WWBWC and HBDIC to begin testing this tool. Additional interest was generated when further investigation revealed that there were other projects in the western United States (as discussed earlier) that had proven track records in recharge. Starting in 2003, a series of grants from the Oregon Watershed Enhancement Board (OWEB), the Walla Walla Watershed Alliance (WWWA) and in-kind contributions from the Hudson Bay District Improvement Company (HBDIC) allowed for the first successful limited testing license application, and subsequent installation and operation of the Hudson Bay Aquifer Recharge Project. The following sections will discuss the issues associated with aquifer recharge, the HBDIC project results to date, and aquifer recharge potential as a water management tool.

PART II. THE HBDIC ALLUVIAL AQUIFER RECHARGE PROJECT

Testing Managed Aquifer Recharge: HBDIC Site Operations and Monitoring (2004-9)

The Hudson Bay District Improvement Company (HBDIC) partnering with the Walla Walla Basin Watershed Council (WWBWC) sought and secured grant funding to test aquifer recharge starting in 2003. This project has been successfully operated for 6 recharge seasons and has been the main focus of the testing of MAR in the Walla Walla basin. This section reviews the results collected from the 2004-9 testing and helps provide the reader with a sense of how and what is monitored when testing MAR. There are two primary testing areas at the HBDIC Recharge Site; the spreading basins and the infiltration gallery testing areas. While the spreading basins have been operating since 2004, the infiltration galleries are relatively new being built during the 2008-9 recharge season.

To understand the application of aquifer recharge, hydrogeologic information about the aquifer-river system in the Walla Walla basin must be reviewed. For the purposes of simplification, this discussion focuses on the upper portion of the alluvial aquifer system, which is that portion of the alluvial system where groundwater is generally unconfined and hosted by gravelly strata. The basalt aquifer system will not be included in this discussion as its connection to surface water likely is minimal within the Walla Walla Basin (GSI, 2007). The deeper alluvial system also will not be discussed as it is at least semi-confined, hosted in and below extensive clayed strata, and probably has limited continuity to surface waters.

One of the first orders of business in defining the hydrogeology is to map the subsurface geologic features that influence the aquifer of interest. This subsurface mapping, sometimes referred to as hydrostratigraphic mapping, provides a three-dimensional, spatially-relevant description of the various layers (lenses, beds, formations) that comprise, or host, the aquifer system. Originally mapped by Newcomb in 1965, the alluvial aquifer system in the Walla Walla Basin generally is found within a mix of older river deposited (alluvial) clay, silt, sand, and gravel from the Blue Mountains, Missoula cataclysmic flood deposited silt and sand, and wind-blown loess.

The shallow or alluvial-aquifer system for our study area is present within a topographical depression, roughly triangular in shape bounded on the east by the Blue Mountains, the south and southwest by the Horse Heavens Hills, and the north and northwest by the Palouse slope. This alluvial aquifer system generally slopes from east to west, down the length of the Basin. The sloping aquifer receives most of its recharge from the Walla Walla River and Mill Creek drainages, although additional flow enters via the other smaller tributary drainages and through the subsurface. The water table gradient is generally east to west and its general movement is depicted in **Figure 17**. The basin has what we refer to as down gradient 'pinch point' through which surface water and groundwater eventually moves through. This point lies where the Walla Walla River crosses basalt outcrops at the base of Nine Mile Hill. The alluvial aquifer generally is considered to be *unconfined*, which means that it is open to

receive water from the surface; and whose water table surface is free to fluctuate up and down, depending on the recharge/discharge rate. This condition is more prevalent in the upper portions of the valley and grows less so the further down gradient and west you move through the system due to increasing proportion of finer grained alluvium.

In 2007, utilizing funding from the Washington Department of Ecology and Oregon Watershed Enhancement Board, GSI Water Solutions Inc. completed a hydrostratigraphic mapping project of the Walla Walla River valley alluvial aquifer system (GSI, 2007). Five basic hydrostratigraphic units were defined and mapped in the alluvial aquifer system. All of these are sedimentary strata (e.g., clay, silt, sand, and gravel lithologies) overlying basalt bedrock, and sometimes referred to as the suprabasalt sediments. The five suprabasalt sediment units mapped for this project are the: (1) Quaternary fine unit, (2) Quaternary coarse unit, (3) Mio-Pliocene upper coarse unit, (4) Mio-Pliocene fine unit, and (5) Mio-Pliocene lower coarse unit. The terms Quaternary and Mio-Pliocene refer to geological time periods, Quaternary representing from 2 Million years ago till present, and the Mio-Pliocene referring to the late Pliocene through the Miocene periods (10.5 to 3.5 Million years ago). The younger Quaternary sedimentary units are on top of the older, Mio-Pliocene units (**Figure** 18 and 19).

An often used analogy for this alluvial aquifer system is to picture a large, multi-layered, silty, sandy, and gravel-to-cobble filled bath tub, with basalt bedrock acting as the walls and bottom of the tub. The structure contour map of the top of basalt clearly shows the shape of this basalt bath tub (**Figure 20**). This map also depicts the major folds and faults that influence the lateral continuity of the basalt bedrock and the overlying suprabasalt sediments. The degree of hydraulic continuity between the basalt (which hosts a variety of confined aquifers) and the suprabasalt (or alluvial) aquifer system is not well understood.




Figure 17. Walla Walla River valley shallow aquifer system.

Water is found in all of the sediment layers comprising the alluvial aquifer system, but it moves easiest through gravelly portions, which are most abundant near the surface. In addition to water moving through the gravel, water is also flowing in and out of it, moving between the gravel alluvial aquifer and water flowing over the surface in the form of rivers, streams and ditches. Because the system is pitched slightly toward the Columbia River, both the surface water and groundwater drain toward it. The thickest of the coarse alluvial hydrostratigraphic units is the Mio-Pliocene Upper Coarse Unit (Figure 19). These coarse strata form the primary unit in which alluvial groundwater is found in the Basin. For more information about the specific geologic information on the shallow aquifer please refer to Groundwater Solutions' report: Geologic setting of the Miocene (?) to Recent Suprabasalt Sediments of the Walla Walla Basin, Southeastern Washington and Northeastern Oregon. (GSI, 2007).




Figure 18 Sediment Stratigraphic Chart of the Walla Walla shallow aquifer units (GSI INC et. al., 2007)




Figure 19. Major sedimentary layer of the Walla Walla River Valley Shallow Aquifer. (GSI, 2007)




Figure 20. Top of Columbia River basalt, or bedrock boundary for shallow aquifer (GSI, 2007)

Site Specific Hydrogeology and Geology

This section summarizes site specific geologic and hydrogeologic conditions, and is based on fieldwork at the Site and the basin wide hydrostratigraphic mapping presented in GSI (2007). The geologic cross-section in **Figure 21** was derived from this hydrostratigraphic mapping effort.

The uppermost geologic unit in the Test Site area is a sequence of interstratified silt and sand (Touchet Beds) comprising the Quaternary fine unit. However, at the site itself, these strata are absent and the uppermost unit is the coarse Quaternary unit. The coarse Quaternary unit at the Site consists of basaltic, sandy to clayey, uncemented gravel. Beneath the Test Site, geologic logging during site specific monitoring well drilling showed that these uncemented strata are approximately 20 feet-thick. The basin-wide mapping effort suggests these strata thicken to the west of the site.

Uncemented strata of the coarse Quaternary unit are underlain by the variably indurated (uncemented to cemented) Mio-Pliocene upper coarse unit. Site specific monitoring wells drilled for the project do not fully penetrate this unit. However, basin-wide hydrostratigraphic mapping (GSI, 2007) suggests this unit is approximately 150 to 160 feet thick in the immediate vicinity of the Site. Based on regional trends, interpretations of driller's logs, and our geologic logging of drill cuttings samples collected from recently drilled wells in the general area, the Mio-Pliocene upper coarse unit consists of variably indurated, weakly to moderately cemented, silty to sandy, indurated gravel (conglomerate). This unit is the primary host unit for the alluvial aquifer system in the general vicinity of the Site. The

coarse Quaternary unit – Mio-Pliocene upper coarse unit contact was identified using the following combination of criteria:

- A notable change in cuttings color from gray dominated hues to brown and yellow-brown hues
- Presence of cemented sand clasts and sand cemented to pebble and cobble clasts in the cuttings samples
- Increased mud content in the fine fraction of the cuttings
- Generally better air circulation reported by the driller

The functional base of the upper portion of the alluvial aquifer system in the area of the Site is essentially the top of the Mio-Pliocene fine unit. The contact between this unit and the overlying Mio-Pliocene upper coarse unit is predicted to lie approximately 200 feet below ground surface at the Site. Although there will be a degree of hydraulic continuity between these two units, the prevalence of laterally extensive clay and silt lithologies in the fine unit limits this.

The deepest part of the alluvial aquifer system in the Site area is hosted within a locally occurring coarse interval referred to as the Mio-Pliocene basalt coarse unit. This unit differs from the upper coarse unit. It is generally felsic, displaying thin (<10 feet thick) quartz sand layers. It also is saturated and may indeed make a locally productive water-bearing interval. However, the thickness and wide lateral extent of the overlying fine unit is inferred to greatly limit the hydraulic connection of this unit to the upper coarse unit and surface waters.




Figure 21. Geologic Transect of White Ditch at HBDIC Recharge Site (Baker T., 2010)

A number of studies and reports have looked at the hydrologic conditions of the various geologic stratigraphy mentioned above. The most recent work was done by the WWBWC-OSU team as portion of the Integrated Surface Water-Groundwater Flow Model (IWFM) project in 2006-8 (Petrides, 2008). A series of aquifer tests were performed at various times of the year including a 72-hour constant-rate pumping test and a step-drawdown pumping test at observation well #1 (GW-46) on the HBDIC Recharge site. The hydraulic conductivity value from that testing of the upper two layers of the aquifer ranged from 22 - 34 meters/day with a groundwater velocity at approximately 1 meter day. Other estimates of hydraulic conductivity are based on modeling and literature reviews. The USGS estimated values from their modeling exercise (MacNish, 1976) gave ranges (depending on geologic unit) from 4 - 65.84 meters/day. The literature (Bear, 1972) provides values for unconsolidated sand and gravel in 10^1 meters/day with the EPA (EPA, 1986) estimating 27 - 30 meters/day (Petrides, 2008).

The HBDIC Alluvial Aquifer Recharge Site

Overview

Starting in 2004, the HBDIC Recharge site was operated over 6 consecutive seasons. The site began operations in March of 2004 after receiving the OWRD limited testing license (OWRD #LL-758) in

February 2004 and construction being completed as the project was first turned on in March 2004. This first season was unlike the subsequent seasons because the site was being operated even before it was completed. This was mainly due to the HBDIC-WWBWC team wanting to get some aquifer recharge testing completed before the shut off date of May 15th, 2004. From 2005-2009 site construction was done during the winter shutdown period (February 1st onward) or done parallel to the site being operated. The site was expanded twice during this period. The first (2004-5 season) from 0.34 acres to 1.1 acres when the three original 50' x 100' spreading basins (**Figure** 22) were expanded, with spreading basin #1 being more than tripled in size. During the 2005-6 seasons, a fourth basin was added bringing the total basin area to 1.4 acres with an average depth between 5'-7'.




Figure 22. Original HBDIC Site Designs 2003 - Engineering by Bernie Hewes, PE Oregon

The spreading basins were operated successfully for 5 recharge seasons until the summer of 2008 just before the original OWRD limited testing license expired (February 2009). The HBDIC-WWBWC team informed OWRD resources that it intended to submit for a water right for the site through their department, the logical progression after successful limited license testing. Due to limitations in the OWRD Umatilla Basin Rules for the Walla Walla basin restricting aquifer recharge in this portion of the watershed, OWRD put together a Rules Advisory Committee (RAC) during the summer 2008. The Confederated Tribes of the Umatilla Indian reservation voiced concerns over aquifer recharge competing for non-irrigation season flows with a reservoir feasibility study they have been working on with the United States Army Corps of Engineers-Walla Walla (USACE). After several RAC meetings, it was decided that the HBDIC-WWBWC team would request another OWRD Limited testing License whilst awaiting the

CTUIR-USACE team to further work out their feasibility study details. This was applied for during the winter 2009 and received in time to operate the remaining of the 2008-9 recharge season. Since that decision, the CTUIR-USACE are advocating the Columbia River Pumping exchange project instead of the Pine Creek Reservoir, thus removing the potential for a water availability conflict between the two programs. Negotiations between the OWRD, HBDIC-WWBWC and CTUIR-USACE teams will now need to commence during this current limited license in order to allow the HBDIC project to apply for and receive a successful water right. Additionally through the collaboration of the groups mentioned above, aquifer recharge is now included in the CTUIR-USACE feasibility study to help protect and enhance Walla Walla River flows for salmon recovery. Currently no RAC meetings are scheduled but will need to be conducted before summer 2013 in order for the HBDIC site to receive a water right.

Starting in the fall of 2008, a portion of the HBDIC recharge site has been used as a test location for examining and comparing the performance of four different types of shallow aquifer recharge infiltration galleries. This test area is shown in **Figure** 23 below. Many of the local irrigators would like to implement shallow aquifer recharge on their farms, but do not have the space for spreading basins. Subsurface Infiltration galleries are being tested on the HBDIC site as a potential solution. A diagram in Appendix III shows the layout of the four galleries, water turnout, the location of meters, and piezometers to track groundwater responses.

Spreading Basins Operations

The HBDIC site consists of two operating areas, the first being the spreading basins the main focus of this document, with the second area designated for infiltration gallery testing, which will be covered in more detail in a later section. To conduct the recharge testing, the HBDIC project can divert a total of up to 50 cfs (OWRD LL#1059) from the Walla Walla River at the Little Walla Walla Diversion (OWRD # 14012100) during the November 1st through May 15th recharge period. OWRD, in the limited license, established minimum instream flows for the Walla Walla River that must be met at the Nursery Bridge (M-4) gauge (Figure 23) downstream of the HBDIC diversion. These minimum instream flows were determined through the OWRD limited testing license process in 2004 in consultation with Oregon Water Resources Department (OWRD), Oregon Department of Fish and Wildlife (ODFW), Oregon Department of Environmental Protection (ODEQ) and the Confederated Tribes of the Umatilla Indian Reservation (CTUIR). Minimum instream flows are only applicable to this project and any other OWRD water right currently diverting water from the Walla Walla River.

Other instream flow agreements such as the one completed under Civil Penalty agreement between the US Fish and Wildlife Service (USFWS) and the three main irrigation districts on the river do not apply to the HBDIC Recharge site Limited License requirements. The minimum instream flows and their applicable diversion periods for the HBDIC recharge site are listed in Table 1.

HBDIC Recharge Site Legal Diversion Periods	Minimum Walla Walla River Flow (cfs)		
November 1 st through November 30th	65 cfs		
December 1 st through January 31 st	95 cfs		
February 1 st through May 15th	150 cfs		

Table 1. HBDIC Minimum Instream Flow Requirements




Figure 23. Map of HBDIC Recharge site and Source Water Delivery System

Figure 24 shows the average daily flow volumes for the Walla Walla River compared to those of the Little Walla Diversion and the HBDIC recharge site flows for 2009 water year. Walla Walla

River Irrigation District and Hudson Bay District Improvement Company both divert a majority of their water rights at the Little Walla Walla River site at Cemetery Bridge (OWRD Gauge # 14012100). HBDIC White Ditch diverts water from the Little Walla Walla system at the OWRD HBDIC Gauge (OWRD Gauge # 14012300). The HBDIC recharge project diverts water from the White Ditch based on the instream flow values and other water user's priority as described earlier. HBDIC recharge flows represent only a small fraction of the total flow in the Walla Walla River during the November through May 15th operating period (**Figure 24**).

From the Little Walla Walla diversion, HBDIC recharge water flows to a split in the Little Walla Walla River system called the frog. At the frog HBDIC has an OWRD operated gauge station (OWRD # 14012300) to help monitor and manage their water use off the Little Walla Walla River system. The recharge water then flows into the White Ditch, HBDIC's main canal which flows for about 2.5 miles to the site's intake (Figure 25). The water then flows through the project filling the basins SP-1, SP-1B SP-2, SP-3, SP-4 with excessive water tailing back into the White Ditch. The intake and flow between each of the basins is maintained by HBDIC field staff and is controlled using a series of weir boards to control rates of flow in and through the project.




Figure 24. Comparison Walla Walla River source water to Diversions and Use (WY 2009).




Figure 25. Aerial Map of HBDIC Recharge Site with Monitoring

Flow is measured into the project in the intake weir structure where an unvented *In-situ LT-100* level logger records water level in PSI. Atmospheric PSI data is also collected on site and at the WWBWC office to help correct for water levels in the weir. Using the engineered weir rating table, water level data is converted into 15-minute flow data and is compiled annually... Tail water leaving the site is measured in a portable ramp flume using the same equipment described above. Both the intake and overflow sites have physical staff gauges with which to check the electronic logger measurements against actual physical water levels. This provides calibration information for the logger data and ensures correction against drift and other recorder abnormalities. Data is plotted for a visual check by WWBWC hydrology staff and then used to calculate recharge rates and water usage at the site for testing and reporting purposes.

Spreading Basins Recharge Results

To calculate the total recharge volume and average recharge rate at the HBDIC site, instantaneous overflow data (cfs) is subtracted from the instantaneous intake data (cfs). The amount of water delivered to the Site in each season of operations has varied from a low of 409 acre-feet in 2004 to a high of 3234 acre-feet in 2006-2007 (Table 2). These amounts were calculated using stage data measured in the flume that delivers water into the Site. The stage data was measured using a digital data logger and pressure transducer programmed to measure depth of water through the flume hourly. Table 2 presents our calculated daily average recharge rate (in cfs) and total volume delivered (in acrefeet) for the site each recharge season, or portion of a recharge season. Table 2 also lists total

infiltration basin area which has changed over time as the site has been periodically expanded. Comparing the area of the basins to the volume delivered shows us that recharge efficiency at the Site has varied over time.

The delivery of water to the site is influenced by a number of factors that are independent of site operation. Inflow to the site is susceptible to water elevation conditions in the White Ditch where upstream users can turn off, suddenly increasing the amount of water entering the project, making the overflow channel a necessity and the inflow data vary greatly. Alternatively, up gradient water users diverting water can cause the project to run below it optimal recharge potential. During the winter operational months, periods of low water temperatures can influence the rate at which water can infiltrate; decreasing water temperature equates to increasing water viscosity. All of these physical issues influence effective recharge rates, which are manifest in the variability in average daily Q seen in Figure 26.




Figure 26. 2004-9 HBDIC Recharge Flows (daily average - cfs)

Reviewing the average daily flows, it generally appears that the period between November 1st through February 1st has a decreased recharge rate overall but is also less sporadic in the flow peaks than the February 21st through May 15th period. As shown above, the period starting on February 1st is the period for HBDIC and Little Walla Walla River system shutdown. This shutdown is due to two factors: 1) The fish screen structure located at the Little Walla Walla diversion needs to be cleaned every year in order to be effective and 2) the instream flow requirement for the HBDIC project goes from 95 cfs to 150 cfs on February 1st. This, coupled with the generally low flow seen in the river at this time due to cold temperature and headwaters snow packs, makes it a good time to service the fish ladders and turn off the system. Consequently both the WWRID and HBDIC irrigation districts now perform some of their ditch maintenance to correspond to this off period.

					Infiltratio	n Area				
Rednarge Seasons	Period of Operation	Days of Operation (actual)	Average Recharge Rate (cfs)	Site Expansion Phase	(feet ²)	(acres)	Basin Recharge Volume (acre-feet)	Basin Recharge Volume (Gallons x 1,000)	Total Basin Recharge (acre-feet)	
Spring 2004	4/8/4 to 5/14/4	36.0	5.7	I	15,000	0.3	409	133,273	409 (2004)	
2004-2005	12/1/4to 2/3/5	28.7	13,2	I	15,000	0.3	388	126,398	4074 (2004 7	
2004-2005	3/27/5 to 4/30/5	35.7	15.8	II	47,420	1.1	650	211,803	1871 (2004-5)	
2005-2006	11/1/5 to 5/15/6	118.1	11.9	II	47,420	1.1	2,813	916,619	2813 (2005-6)	
2006-2007	11/1/6 to 5/15/7	128.0	11.3	II	47,420	1.1	3,278	1,068,140	3234 (2006-7)	
2007-2008	11/14/7 to 3/25/7	86.8	11.1	II	61,987	1.4	1,939	631,962		
2007-2008	4/10/8 to 5/15/8	34.5	12.0	III	61,987	1.4	820	267,125	2739 (2007-8)	
2008-2009	11/1/8 to 5/15/9	134.5	10.7	III	61,987	1.4	2,840	925,417	2840 (2008-9)	
	Total	602.3					13,137	4,280,736		

Table 2. 2004-9 HBDIC Spreading Basins Operations for Surface Flows

Clearly, actual water usage for the HBDIC site has been influenced by changes in foot-print and size. These included the "construct-as-you-run operations "of the spring 2004 season, to the HBDIC site upgrades during mid-recharge season (2004-5 and 2007-8). The periods and days of operations also varied depending on Walla Walla River flow conditions, water temperatures, and at times due to water users needs in the system. The site expansions were numbered I, II and III with the infiltration areas increasing from 0.3 acres (15,000 ft²) to 1.4 acres (61,987 feet²). The season for the highest total recharge rate was the second half of the 2004-5 season (15.8) cfs while the most effective year for total volume recharged was the 2006-7 season (3234 acre-feet). Over the six year period the site was operated for a total of 602 days for a total of 13,137 acre feet or over 4 billion gallons of water.

To better understand variations in recharge rates, volumes relative to changes in operation days and infiltration area were further calculated from the HBDIC site operations statistics (Table 3). With 194 potential operational days in a recharge season (as defined by the limited license) the 2006-7 year showed the highest number of operating days (144.1) and hours (3459). This was also the year having the highest *seasonal* average recharge rate (8.3 cfs) where average recharge is divided by the total number of potential recharge days. The 2004-5 recharge season showed the highest *operating* recharge rate (15 cfs) as well as the highest average deviation. The high average deviation suggests a higher

variability in the recharge rate. For the purposes of clarity, the term *effective average recharge rate* used throughout the rest of this document refers to the highest *operating recharge rate*.

	HBDIC Recharge Results by Season							
Aquifer Recharge Operations Statistics	2004	2004-5*	2005-6	2006-7	2007-8	2008-9		
Recharge Season Potential (Days)	194	194	194	194	195	194		
Recharge Operation (Days)	36.0	64.4	118.1	144.1	121.3	132.6		
Recharge Operation (Hours)	867	1546	2835	3459	2910	3183		
Seasonal Average Recharge Flow (cfs)	1.1	4.8	7.2	8.3	7.0	7.3		
Operating Average Recharge Flow (cfs)	5.7	15.0	11.9	11.3	11.4	10.7		
Operating Average Recharge Flow - Average Deviation (cfs)	2.3	4.1	2.5	1.4	3.5	2.3		
Peak Recharge Flow Rate (cfs)	14.1	35.2	27.3	30.6	20.2	37.6		
	* Some Synthetic data HBDIC Recharge Seasons							
	2004	2004-5	2005-6	2006-7	2007-8	2008-9		
Average Flow Rate - Nov 1st through Jan 31st (Winter)	N/A	13.4	13.6	11.8	9.7	10.3		
Average Deviation - Winter	N/A	1.5	0.8	1.3	3.9	2.0		
Average Recharge Rate - Mar 1st through May 15th (Spring)	5.7	15.6	11.0	10.9	13.2	11.2		
Average Deviation - Spring	2.3	5.1	3.1	1.5	2.6	2.8		

Table 3. HBDIC Recharge Site Operational Statistics

Calculating the total *effective* recharge rate as well as the total recharge volumes for the HBDIC project also requires estimating the amount of water lost in conveyance in the White Ditch from Little Walla Walla Diversion to the site. This is required by the limited license. Various ditch loss studies have been conducted by the WWBWC, OSU and others with varied results and confidence levels. For the purposes of this report an estimated conveyance loss of 10 cfs was used to calculate the total values for the project. This value is based on the HBDIC manager's operational knowledge of this system (e.g. constantly supplying known volumes of water to his patrons) and is supported by reviewing the OWRD Gauge and HBDIC intake data during periods when only the HBDIC site is in operations. Like the spreading basins on site, this 10 cfs value likely varies with temperature, flow volumes and other factors.

To conclude, Table 4 shows that the total *effective* recharge rate for the site and ditch appears to average around 22 cfs with an average total volume of around 5,000 acre-feet (excluding the spring 2004 season). To provide perspective, 5,000 acre-feet is the equivalent of 7.8 miles² a foot-deep in water. The $^{\sim}$ 22 cfs *effective* recharge rate means that the spreading basins portion of the HBDIC site and the ditch supplying water to the site is currently utilizing 44% of its total allowed recharge rate from the Walla River.

	Days of Operation	Tot	al Recharge Rate	s	Total Volumes			
Recharge Seasons		Operating Average Recharge Rate (cfs)	Estimated Conveyance Recharge Rate (cfs)	Total Recharge Rate (cfs)	Total Basin Recharge (acre-feet)	Total Conveyance Recharge (acre-feet)	Total HBDIC Project (acre-feet)	
Spring 2004	36	5.7	10.0	15.7	409.0	713.9	1,122.9	
2004-2005	64.4	15.0	10.0	25.0	1,871.0	1,277.1	3,148.1	
2005-2006	118.1	11.9	10.0	21.9	2,813.0	2,341.9	5,154.9	
2006-2007	128.0	11.3	10.0	21.3	3,234.0	2,538.2	5,772.2	
2007-2008	121.3	11.4	10.0	21.4	2,739.0	2,406.0	5,145.0	
2008-2009	134.5	10.7	10.0	20.7	2,840.0	2,667.1	5,507.1	
		A0				Total Recharge	25,850.2	

Table 4. Total Water Usage Values for the HBDIC Recharge Site (2004-9)

Deciphering the Variations in Recharge Volumes and Rates

As we review the water usage data provided in Tables 2 through 4 it becomes apparent that rates and volumes of recharge for the HBDIC site do not seem dependent solely on infiltration area or intake management. As discussed earlier there are many operational and physical factors that likely influence the effectiveness of the project to help replenish the shallow aquifer system. However there are other factors not mentioned in the previous section that also can influence the effectiveness of the spreading basins to replenish the shallow aquifer. For the purpose of this report we will review data relative to the following potential influences:

- 1. Seasonal Temperature Fluctuations
- 2. Seasonal and Long-term Infiltration Basin Clogging
- 3. Water Table Mounding

Seasonal Temperature Fluctuations

While the HBDIC-WWBWC team did not conduct an in-depth research project coupling the *effective* rates of recharge with the water and air temperatures at the site, it is a well established fact that water becomes more viscous with decreasing temperatures. This physical factor would have the effect of making it more difficult to recharge at maximum *effective* rates during the cooler portions of the recharge season typically from November 1st through February 28th. **Figure** 27 shows a basic comparison of average recharge rates for the first and second halves of each recharge season. While there does appear to be some variability in rates, it is not clear that temperature (e.g. first half (blue) dramatically influences the *overall effective* rate of recharge. A more in-depth site study where continuous water temperatures are measured against recharge rates would help to better define this potential operational consideration for the HBDIC site.




Figure 27. Comparison of fall vs. Winter Effective Recharge Rates for Temperature

Water Table Mounding and/or Basin Clogging

When we reviewed the overall rate information provided in Table 4 it became necessary to further partition the recharge rates and volumes based on infiltration areas. Therefore recharge rates were first grouped and graphed by infiltration areas (**Figure 28**). By doing this we could clearly see trends in the data. For the spring 2004 season and the first half of the 2004-5 seasons, rates varied a great deal. Some of this could likely be explained by the site construction operation limitations during the spring, but considering that the 13.4 cfs value in a 0.34 acre surface area is very high relative to the other seasons there may be other factors at work. Because this was the first portion of a season where all three original basins were operated it could be tied to the site being unclogged and ready for maximum infiltration. It should be noted that when engineering the design for the first 3' x 50' x 100' foot ponds, a small-pit slug test was performed. That test showed an infiltration rate in this much smaller area to be high enough that the 3 original basins should have taken 50 cfs. This indicates the size of the pond footprint and its interactions with the underlying water table (mounding) likely has an influence on recharge rates.

The three recharge ponds (2004-5 through 2007-8) have a combined infiltration area of 1.1 acres. It does appear that during this period that the recharge rate is declining particularly from the first data point to the second. This may also be due to the accumulation of sediment through the operation at the site. A similar decreasing recharge rate trend also appears to be seen after the Phase III expansion, where recharge rate dropped from 12.0 cfs to 10.7 cfs. This is a lower average recharge than when the site was 1.1 acres in total size. However, as mentioned earlier in this section the staff

operations of the intake relative to the white ditch, also may be playing a role influencing these values. Following this analysis, we weighted each of the recharge rates by total infiltration area (average recharge rate/infiltration area) and plotted the results in **Figure** 29. This helps to highlight that if surface area were the only thing to consider. It would appear that the benefits of increasing size to increase recharge rates likely plateaus somewhere between 0.34 acres and 1.1 acres, 38.3 cfs and 14.5 cfs respectfully. However the fact that infiltration rates do appear to drop when infiltration area is held constant indicates that surface area does not dictate infiltration rates alone.




Figure 28. HBDIC Effective Recharge rates (cfs) - 2004-9




Figure 29. HBDIC Recharge Rates in Acre-feet/day

Mounding of the water table below the site could also be influencing these rates over time. The mounding below the recharge project happens due to the manner which water leaves the site and moves through the unsaturated (vadose zone) to the saturated (water table) subsurface zones. Water moving directly out of the bottom of the basin toward the water table moves quicker due to gravity and unsaturated conditions (**Figure 30**). Once that water mingles with the water table it slows down because then its only direction of movement is down gradient which is expressed by Darcy's law¹⁷; including permeability and pressure gradient (P) or more simply, slope of the unconfined water table. Because this rate of movement is slower than the vertical movement through the unsaturated zone, water tends to back up and "mound" upward toward the spreading basins. This water then begins to influence the rate at which water can infiltrate from the site. Relative to the data being presented here, this would likely manifest itself in reduced infiltration rates even with increased infiltration areas.

¹⁷ In fluid dynamics and hydrology, Darcy's law is a phenomenologically derived constitutive equation that describes the flow of a fluid through a porous medium. Henry Darcy, Les Fontaines Publiques de la Ville de Dijon ("The Public Fountains of the Town of Dijon"), Dalmont, Paris (1856)




Figure 30. Conceptual Diagram of Aquifer Recharge Mounding and Saturated Groundwater Movement

Mounding could affect recharge rates over time if the HBDIC site was having the net effect of decreasing the distance between surface infiltration basins and the water table. In other words, if the HBDIC project through its six seasons of operations was having the net effect of localized aquifer recovery this could be expressed on the surface as decreasing *effective* recharge rates. **Figure** 31 shows one of the 4 on-site HBDIC monitoring wells (GW-45) and a seemingly increasing peak and trough recovery since recharge operations began. Due to localized aquifer pumping, the operations of the White Ditch and other potential up gradient influences on the water table, it is difficult to clearly use this graph to conclude a recovery. However, it does provide some insight into the possible reduction in overall average *effective* recharge rates at the site and as more years of operations occur, the trend may become even more conclusive.




Figure 31. HBDIC On-site Observation Well Water Level Data (2004-9)

HBDIC Water Quality Monitoring Program and Procedures (2004-2009)

The HBDIC Recharge Project represented the first project to apply for a limited testing license for aquifer recharge in the State of Oregon. With this, a concise water-quality sampling plan was developed during the project. Monitoring and ensuring that water quality is adequate to operate an aquifer recharge project was and continues to be a top priority for the HBDIC-WWBWC project team. Starting in 2003 Phil Richardson at Oregon Department of Environmental Quality (Pendleton, Oregon) along with Thomas Darnell at Oregon State University Extension (Milton-Freewater, Oregon) worked with WWBWC staff to develop the water quality parameters and testing protocols for the HBDIC project. This was completed during the original Limited Testing License application process in 2003-4. For more information on how this site-specific water quality monitoring plan for aquifer recharge was compiled, details can be found in *Hudson Bay Aquifer Recharge Project: An application for ASR Testing Limited License to Oregon Water Resources Department (OWRD) (OAR 690-350-0020), and attachments* (Bower R. J., 2003).

Since the original conception of the water quality plan, there have been a variety of progressive changes to the original plan. Working with ODEQ, the HBDIC-WWBWC team has adaptively modified the water quality monitoring to prioritize the analytes based upon collected samples and subsequent results. This has allowed the project to move from a fairly high-intensity sampling plan to a reduced, but focused list of key parameters. In some cases the analytes that were of most interest (mainly due to historic or current basin use) were not available from the HBDIC site laboratory contractor. Cindy O'toole at Edge Analytical worked with the HBDIC-WWBWC team to create laboratory standards for those analytes. In 2006 the original EPA SOC list was downsized to focus on priority analytes. Some of

the new standards that ODEQ was most interested in were added. As of the 2009-10 seasons, the list discussed below is the current water-quality parameter list. To summarize the program and the results from the past water quality monitoring, it is best to separate sampling into two categories of constituents.

Baseline Chemistry:

- o nitrate
- o total kjeldahl nitrogen (TKN)
- total dissolved solids (TDS)
- o chemical oxygen demand (COD)
- o chloride
- o orthophosphate
- o fecal coliform bacteria

Soluble Organic Compounds – Pesticides

(Common/Trade names, EPA Drinking Water Method)

- o 2,4 D acid, Dacamine, 515.1
- o Dimethoate, Cygon, 525.2
- o Metalaxyl, Ridomil, 525.2
- o Napropamide, Devrinol, 525.2
- Simazine, Princep, Aquazine, 525.2
- o 1-Naphthaleneacetamide, Amid-thin 525.2
- o Diazinon, Diazinon, 525.2
- o Fenarimol, Rubigan, 525.2
- o Lindane, Lindane, 525.2
- o Methidathinon, Supracide, 525.2
- Mevinphos, Phosdrin, 525.2
- Myclobutanil, Systhane, Rally 525.2
- o Triflumizole, Procure, 525.2
- o Azinphos-methyl, Guthion, 525.2
- o Carbaryl, Sevin, 531.1
- o Chlorpyrifos, Dursban, Lorsban, 525.2
- o DDD (TDE) Rhotane, DDD, 525.2
- DDE degradation product,
 525.2
- o DDT Anofex, Gesarol, 525.2
- o Dicofol, Kelthane, 525.2
- o Malathion, Cythion, 525.2
- o Methyl Parathion, Penncap, 525.2
- o Phosmet, Imidan, 525.2
- o Propargite, Omite, Comit, 525.2
- o Triadimefon Dimethoate, Bayleton, 525.2

- o Oxamyl, Vydate, 531.1
- Hexazinone DPX 3674, Pronone, and Velpar, 525.2
- o Parathion-Ethyl, Niran, Phoskil (56), 525.2

The WWBWC has a ODEQ approved Quality Assurance and Quality Control plan that requires at least 10% repeatability on all water quality and temperature sampling. Therefore, for all of the sampling completed at the HBDIC site, additional samples are collected for QA/QC. Edge Analytical Laboratory Inc. a certified laboratory in Burlingame, Washington, performed the basic chemistry and soluble organic compound analysis under their laboratory QA/QC plan. Their results are shared along with 2004-9 sampling results in Appendix I. Fecal coliform and total coliform testing is done by the City of Walla Walla's Water and Waste Water Treatment facility in Walla Walla, Washington. They also have an internal QA/QC plan that controls the quality and repeatability of their procedures.

In the first several years of site operations Kuo Testing Laboratories staff collected water quality samples. WWBWC staff took over the field sampling effort in 2008. Source water samples are collected from the weir-channel on the intake structure, typically in the weir's small backwater eddy. Groundwater samples were originally collected using sterile eco-bailers from Observation Well #1 (GW-46). In 2006 the HBDIC-WWBWC team purchased a submersible pump specifically designed for evacuating several total volumes of the observation well before collecting the water quality sample. This was to ensure that samples represented ambient groundwater conditions and not those inside the well casing.

Upon collection, samples are immediately placed in ice filled coolers that are transported to either the City of Walla Walla's laboratory (fecal coliform samples) or a local over-night shipping company to be sent to Edge Analytical. Typically, the samples arrived at Edge Analytical in adequate time for them to be processed in the required holding time. Turnaround time for the results from either lab is dependent upon the parameter being analyzed. Fecal coliform and general chemistry are often fairly quickly completed, while SOC analyses typically takes the longest to process. All results are sent as paper and electronic copies to the HBDIC-WWBWC and the information is kept in our project database. In the event there is any detection that appears to be of concern, ODEQ staff in Pendleton is immediately notified via email and/or phone. Instructions on how to proceed are acted upon by HBDIC-WWBWC staff in a timely manner. More information on the annual sampling can be requested from the WWBWC staff through the website or by phone.

WWBWC staff also conducted additional water quality sampling for the infiltration gallery testing portion of the site. Samples are collected and analyzed for Total Suspended Solids (TSS) and Total Organic Carbon (TOC). These samples were collected to evaluate the rates of clogging that can influence the design and operations of these infiltration galleries.

2004-2009 HBDIC Recharge Water Quality Results

All of the original laboratory reports for HBDIC water quality sampling from 2004 through 2009 recharge seasons can be found in Appendix I of this document. Results include laboratory QA/QC, field

notes and other pertinent information on the collection of this information over the six recharge seasons. For the 2004-9 recharge seasons the baseline chemistry for both the source and groundwater sites is summarized in Table 4. All values appear to be well within the maximum contaminant levels (MCL) for the state of Oregon. Surface water samples typically have slightly higher Chloride, Phosphate (ortho), Total Dissolved Solids (TDS), Total Suspended Solids (TSS) and Total Organic Carbon (TOC). The recharged groundwater samples tend to have slightly higher Chemical Oxygen Demand (COD) and TKN as Nitrogen; with Nitrates being about the same for both surface and groundwater samples.

Water Sample Sites: Ground/Surface	Analyte	Samples (n)	Minimum	Maximum	Average	Units
Groundwater	Chloride	16	ND	0.8	0.3	mg/L
Groundwater	Chemical Oxygen Demand	18	ND	55	12.9	mg/L
Groundwater	Nitrate as Nitrogen	13	0.1	0.6	0.2	mg/L
Groundwater	Orthophosphate as P	14	ND	0.5	0.2	mg/L
Groundwater	TKN as Nitrogen	15	ND	1.6	0.2	mg/L
Groundwater	Total Dissolved Solids	15	ND	84	48.7	mg/L
Groundwater	Total Suspended Solids	3	ND	ND	ND	mg/L
Groundwater	Total Organic Carbon	3	0.9	1.2	1.1	mg/L
Surface	Chloride	8	ND	1	0.8	mg/L
Surface	Chemical Oxygen Demand	7	ND	21	ND	mg/L
Surface	Nitrate as Nitrogen	5	ND	0.5	0.2	mg/L
Surface	Orthophosphate as P	4	0.1	0.6	0.3	mg/L
Surface	TKN as Nitrogen	7	ND	ND	ND	mg/L
Surface	Total Dissolved Solids	7	ND	76	57.4	mg/L
Surface	Total Suspended Solids	1	N/A	8	N/A	mg/L
Surface	Total Organic Carbon	1	N/A	8	N/A	mg/L

Table 4. Summary of Baseline Chemistry Sampling Results (2004-9)

During the 2004-9 sampling period there were only two Soluble Organic Compounds (SOC) detections at the HBDIC recharge site... Di (ethylhexyl)-phthalate was detected in observation well #1 at 2.2 ug/L on April 13, 2004. The 2004 EPA Maximum Contaminant Level (MCL) value for this compound is 6.0 ug/L. HBDIC-WWBWC monitoring staff working with ODEQ concluded that this was possibly a low-level detection arising from the newly installed PVC observation-well casing or possibly the well

sampling equipment. The substance was never detected again at the site; however the HBDIC WQ monitoring strategy continues to include this analyte in the sampling routine. The only other detection was 3.2 ug/L of Bisphenol-A at HBDIC Observation well #1 on May 27, 2009. Bisphenol-A is not listed by EPA as having a MCL value but has recently been in the national media associated with concerns over the chemicals widespread use in water bottles and other plastic containers. The HBDIC-WWBWC team continues to monitor for this analyte but are unclear as to its source, whether from the site or in the laboratory equipment.

Table 5 provides a statistical summary of the results of the fecal coliform analyses taken at both the surface and groundwater sites from 2004-9. Surface water samples averaged between 0 to 39 MPN/100 ml from 2004-9 while groundwater showed much lower averages of 0.8 to 3.8 MPN/100 ml. During the first two recharge seasons additional fecal coliform and total coliform samples were collected in order to clarify the extent to which the HBDIC sample results were controlled by ambient conditions. Those results and discussion were shared in the 2004 (Bower R. , 2004) and 2004-5 (Bower R. , 2005) reports which can be found by contacting the WWBWC. In summary, due to the widely distributed extent of low level fecal contamination, it was determined that the detected fecal coliform was considered an ambient background condition; and was not a result of HBDIC recharge site operations.

		Surface					
Sampling Year	Minimum	Maximum	Average	Minimum	Maximum	Average	Units
2004	1	130	39.8	0	14.8	3.8	MPN/100 ML
2004-5	0	62	9.4	0	12	2	MPN/100 ML
2005-6	14	20	17	0	3	1	MPN/100 ML
2006-7	7	23	15.3	0	3	1	MPN/100 ML
2007-8	11	14	12.5	0	1	0.5	MPN/100 ML
2008-9	N/A	19	N/A	0	2	0.8	MPN/100 ML

Table 5. 2004-9 Fecal Coliform Bacteria Sampling Statistical Summary of Results

Indicators of Soil-aquifer Treatment (SAT) at the HBDIC Recharge Site

Through the work of Dr. Herman Bouwer and others in the field of infiltration-basin aquifer recharge, the concept of natural attenuation of source water entering the groundwater through unsaturated soil has been formulated. Bouwer summarized the surface to subsurface process as:

"Where soil and groundwater conditions are favorable for artificial recharge of groundwater through infiltration basins, a high degree of upgrading can be achieved by allowing partially-treated sewage effluent to infiltrate into the soil and move down to the groundwater. The unsaturated or "vadose" zone then acts as a natural filter and can remove essentially all suspended solids, biodegradable materials, bacteria, viruses, and other microorganisms. Significant reductions in nitrogen, phosphorus, and heavy metals concentrations can also be achieved." (Bouwer, 1987)

While the source water entering the HBDIC site is not "sewage effluent" the process of bacteria and other pollutants being stripped from the water as it moves through the unsaturated zone is worthy of further review. When reviewing the data collected at the HBDIC recharge site, the parameter that is most likely to benefit from this process is ambient (but prevalent) fecal coliform contamination. During the initial start-up sampling of each recharge season, source and recharged water samples were collected. The results, when compared statistically, seem to indicate that natural attenuation is occurring at the site. **Figures** 32 and 33 show an order of magnitude lower fecal coliform concentration (average 2.7 MPN/100 ml) in the recharged groundwater than in the recharge source water (28.3 MPN/100 ml).




Figure 32. Surface versus Groundwater Fecal Coliform Results (2004-9)




Figure 33. Comparison of Source vs. Groundwater fecal coliform statistics (2004-9)

Enteric bacteria like fecal coliform arise from the intestines of animals and are an indicator of more harmful pathogens in our water supplies. They have a limited range of temperature at which they can survive, usually corresponding to their host organism's body temperature (e.g. humans 37°C). While more sampling would be required to determine a more statistically robust conclusion, this does seem to correspond to literature supporting the process of source water quality improving through natural attenuation during aquifer recharge. This may help water quality regulators in the permitting future aquifer recharge projects.

Aquifer Response to Recharge

The purpose of aquifer recharge for the Walla Walla basin is to help stabilize and recover the shallow aquifer's groundwater storage supplies. Increased groundwater storage means historic springs that have experienced diminished flow could recover and flow again to the Walla Walla River- providing enhanced flow and off-channel habitat for recovering salmonids. In addition, increased groundwater storage would result in increased potential returns from the shallow aquifer to the Walla Walla River, helping to support and protect base flow - particularly during the low-flow months. Monitoring an

aquifer recharge project, in order to document its contributions toward this overall aquifer recovery purpose, can be broken down into two main scientific questions:

- 1. Did the aquifer respond to aquifer recharge operations?
- 2. Did the springs respond to changes in aquifer conditions from recharge operations?

This section focuses on tracking the process of aquifer recharge from the site out through the groundwater system; then intends to document the connection between those responses seen in the groundwater to those expressed in the springs. As the shallow aquifer system is large and complex, the focus of this section is limited to an area where recharge response is visually and graphically apparent. To demonstrate the overall benefits to aquifer storage, system wide recovery of springs and contributions to the Walla Walla River, the HBDIC-WWBWC team is relying on the IWFM modeling work¹⁸ that Oregon State University will complete in mid-2010. Since the HBDIC likely represents only a small portion of the recharge 'need' in the alluvial aquifer system, it is not intended to show complete recovery of the aquifer. Understanding how much recharge and where to place it for maximum benefit, will be based on the scenarios generated by the IWFM model as well through the WWBWC's Bi-state Aquifer Storage and Spring Restoration program (ARSRP)¹⁹.

Site-Specific Groundwater Response

In order to track the aquifer response to HBDIC recharge operations, responses in on-site monitoring wells were reviewed. **Figure**s 34 and 35 illustrate the response of the four on-site monitoring wells (GW-45, GW-46, GW-47, and GW-48) to recharge operations during the 2008-2009 recharge seasons. These hydrographs are very typical of what was observed in previous recharge seasons.

¹⁸ IWFM modeling project funded by WDOE and OWEB in collaboration with the WMI Monitoring Program. Contact the WWBWC for more information.

¹⁹ ARSRP is a bi-state recovery strategy that was the logical outcome from the aquifer recharge and WMI monitoring program lead by the WWBWC. For more information contact the WWBWC.




Figure 34. On-site Surface to Groundwater Response to Recharge Operations (2009)

Figure 34 shows the recharge flow rate (cfs) into the basins and the groundwater response to the recharge at the four on-site monitoring wells. It is clear that operations of the HBDIC recharge site have a direct mounding effect on the local water table. The staggered nature of the water levels in each of the wells is due to both their proximity to the mounding and their placement relative to the direction of groundwater flow. GW-45 now resides between the infiltration gallery and the down gradient spreading basins, which explain its higher overall water level. Also GW-45 shows the groundwater response (A.) to the 2008-9 infiltration galleries testing, which was done in 1-2 week blocks of operations.

Figure 35 shows GW-45 has the greatest response to operations. The up gradient well GW-40, which is ~10-15 feet from the White Ditch, also shows the influences of canal infiltration on the water table.




Figure 35. HBDIC Site Monitoring Wells and Various Sources of Recharge




Figure 36. Comparison of White ditch and HBDIC recharge site operations to Groundwater Response

After the HBDIC recharge operations are turned off (May 15th), the HBDIC White Ditch continues operating into the late spring and early summer. In 2009 the system ran for the entire irrigation season due to an exceptional snow pack; however this is not typical of most years. **Figure** 36 illustrates the groundwater response to operation of the White Ditch (OWRD Gauge #) and HBDIC recharge site. When the White Ditch operation ceases the aquifer responds with declines in water level. Subsequently when the ditch is operating and HBDIC recharge is not occurring, the aquifer rises, to a higher level, which does appear to stabilize; suggesting an equilibrium between seepage and water level is reached. The data indicates that canals and ditch systems provide recharge water that if piped, will need to be replaced in order to achieve the purpose of aquifer stabilization and recovery.

Next, we shift our analysis to determine if there are any visible signs of water table recovery over the first 6 seasons of operations. **Figures** 37 and 38, respectively, show groundwater levels (2004-9) during low flow periods and peak recharge periods. During the low-flow period (June 1st through September 30th) the recharge site is not operating but the White Ditch and surrounding groundwater pumping are underway. WY 2005 was a drought year during which surface water irrigation was drastically reduced due to lower than average Walla Walla River flows and additional groundwater pumping was done by many water users. Contrasting WY2005 to WY2009 (when strong Walla Walla River flow allowed HBDIC to operate the White Ditch for the entire summer) groundwater levels remained high. Conclusively determining groundwater recovery is difficult in this highly interconnected and volatile aquifer system, due to season by season changes in surface and groundwater conditions.




Figure 37. HBDIC Site Observation wells Irrigation Season water levels (2004-9)

Shifting the focus to the water table peak elevations when the HBDIC Recharge site is operating may indicate a general trend toward higher water table elevations at the site. While this could be tied to recovery of the localized water table it is also likely linked to the expanding infiltration area getting closer to the GW-45 well head. It appears there may be some correlation between rates of *effective* recharge and the height of the mounding at the site. Also it appears that the closer the infiltration area gets to this well higher water levels are observed. Further, investigations using this well and the horizontal distance to infiltration water may provide insights into actual depth to water mounding at the HBDIC site.




Figure 38. Water Table Response to HBDIC Recharge Operations: May 1st- May 31st

System Wide Groundwater Response to Spreading Basin Operations

Starting in 2001 the WWBWC working with its partners at OWRD, WDOE and OWEB began to put together a bi-state well monitoring system through state and federal grant funding. The purpose of this system is to better document overall shallow alluvial groundwater conditions as well as monitor subsurface responses to water management activities such as aquifer recharge and ditch piping. When the program started there were approximately 11 OWRD observation wells in Oregon and 1 WDOE well in the Washington portion of the Walla Walla River Valley. As of 2010, there are over 110 wells in the WWBWC's Bi-state well monitoring system that include dedicated (**Figure** 39) and existing wells that are either instrumented for continuous data or measured quarterly for static water levels (Bower R. , 2009; Patten S. , 2009). **Figure** 40 shows the extent of the monitoring system and their placement relative to the alluvial aquifer system in the Walla Walla River Valley.



Figure 39. WDOE Funded Dedicated Observation Well at Pepper Bridge Vineyards Road Grange Hall (Washington)




Figure 40. Map depicting WWBWC's Bi-state Well Monitoring System of the Walla Walla River valley Shallow Aquifer System

In the area interpreted to be down gradient of the Site water level data was examined to evaluate aquifer response, if any, to site recharge operations. By looking in the Johnson Creek area, we can focus on an area where recharge mounding more distally from the site should be seen in the water table response. To do this, several transects were selected. Moving up gradient from the HBDIC site, transect A on **Figure** 41 starts at the HBDIC up gradient control well GW-14 which shows no visible signs of HBDIC recharge activities. This well is directly underneath irrigated orchards near the Walla Walla River. Influences from irrigation are suggested by water level recovery during spring and summer irrigation activities. Additionally, GW-14 may show signs of decreasing groundwater levels in the Little Walla Walla River area (**Figure** 42). Transect A parallels the White Ditch that delivers the source water from the Walla Walla River to the HBDIC Recharge Site. The elevation difference along Transect A is from 910 (GW-14) to 817 feet (GW-40).




Figure 41. WWBWC Monitoring Wells and Transects Relative Recharge System Response

Moving down gradient from the HBDIC recharge project and GW-45 (**Figure** 41) two transects were selected in which to track groundwater response. An earlier 2005 HBDIC Recharge Site Monitoring

report (Bower R. , 2005) documented the pressure wave from HBDIC recharge activities in wells in the Johnson and Dugger Spring-Creeks areas. Transect B1 generally follows the monitoring wells paralleling the Johnson Spring-Creek with transect B2 paralleling the Dugger Spring-Creek system. Monitoring wells GW-31 (Figure 43) and GW-34 (Figure 44) in the Johnson Creek sub-basin show indications of possible groundwater recovery albeit with the incomplete continuous dataset sets, it makes it more difficult to be conclusive. Note the arrow lines provided on each graph are for trend-visualization only and are not linear regressions of the data. This is an area where extensive piping has occurred in recent years (e.g. HBDIC's Richartz Ditch-to-Pipeline conversion) which would seem counter intuitive to what appears to be gradual groundwater recovery. Coupling these results with those of increasing water table levels at the HBDIC recharge site will be something to continue to monitor as the project progresses.




Figure 42. WWBWC Dedicated Monitoring Well used as up gradient Control for HBDIC Recharge Groundwater Response (2001-9)




Figure 43. Water Levels at WWBWC Monitoring Well GW-31 (2002-9)




Figure 44. Water Levels at WWBWC Monitoring Well GW-34

Plotting all the groundwater elevation data for transects A to B1-B2 for water year 2009 (November 1st 2008 through September 30th 2009) helps show the spatial response of this area to HBDIC operations. **Figure** 45 clearly shows that GW-14 provides a representative up gradient control well for the purposes of documenting HBDIC operations. Wells GW-40, GW-45, GW-46 GW-48 representing the on-site HBDIC operations monitoring wells document the near-basin mounding effects of aquifer recharge. Down gradient and away from the site, wells GW-35, GW-118, GW-60, GW-61 and GW-65

show the height of the mounding decreases with horizontal distance. GW-65 clearly shows that by approximately one mile down gradient (GW-45 to GW-65), the mounding is still visually apparent.

Moving toward the outer boundary of the each of the transects B1 and B2, wells GW-110, GW-63, GW-31 all show an increase in head during the upgradient recharge operations (**Figure** 45). However, with numerous users of the HBDIC ditch also operating during this period of active infiltration from the project, recharge from up gradient water users and the Little Walla Walla River system likely plays a role in a portion of this recovery. From the extensive aquifer testing done at the project site OSU-WWBWC estimated groundwater velocity to be approximately 1 meter/day. This is significantly less than the measured response seen in the water table around the project as the project has turned on and off. The water table response to recharge changes propagates through the aquifer many times faster than the water actually moves. The next step in the process of linking recharge operations to directly helping to restore spring-creeks in the basin is to link these change in water table head to the changes in flow that occur at the down gradient springs.




Figure 45. Groundwater Response to recharge in Johnson and Dugger Spring-Creeks Subbasins (2009)

A groundwater flow model is being constructed to assess groundwater responses to the HBDIC Recharge project, particularly overall groundwater storage and spring flow restoration. Utilizing finite-element IWFM modeling work by OSU (Petrides, 2008), WWBWC GIS water table mapping using data from the well network (Baker T., 2010) and other USGS hydrologic studies and models, **Figure** 46 was

created to show the water table contours and general flow direction relative to the HBDIC recharge site during September 2009. Generally groundwater flows in a west to northwest direction. Additionally, specific conductance (uS) collected from groundwater monitoring sites was assessed using Arch GIS Spatial Analyst to help depict groundwater movement (**Figure 47**). HBDIC recharge site shows lower values indicating the recharge of surface water at site and down gradient movement.




Figure 46. HBDIC Recharge Site Flow Direction(September 2009)




Figure 47. Groundwater Specific Conductance Map (Baker T., 2010)

Spring-Creek Responses

Since one of the stated purposes of the aquifer recharge is to stabilize and restore historic spring flows, an important part of documenting the system wide responses is to link groundwater changes interpreted to be caused by recharge operations, to the springs that flow from this aquifer system. OSU's IWFM modeling work in 2008 provided us some the first supporting evidence linking both HBDIC operations and the operation of unlined canals to the recharge of the shallow aquifer system. Figure 48 depicts the three scenarios run by the 2008 model for the flow in the Johnson Spring-Creek system which included; 1) Johnson Creek flow without HBDIC recharge site operations, 2) Johnson Creek flow with HBDIC recharge site operations and 3) Johnson Creek flow with the lining of the canals and without HBDIC recharge site operations (Petrides, 2008). The HBDIC recharge site clearly played a role in why Johnson Creek was running again after 25 years of being dry (Figure 48). However other factors helping to restore a partial amount of flow from Johnson Springs were at work preceding the 2004 HBDIC recharge operations. Possibly, with the emerging awareness of the irrigation community that ditches played a positive role in groundwater supply encouraged them to increase the amount and duration of

seasonal canal usage. Also this IWFM scenario underlines the importance the man-made canals play in recharging the groundwater system-from which the historic springs are dependent on for their flow.




Figure 48. 2008 OSU IWFM Modeling Scenario for Johnson Creek (Petrides, 2008)

Utilizing the transect B2 from the prior groundwater response section, **Figure** 49 illustrates the groundwater and springs monitoring sites from the HBDIC Recharge site to the spring heads of Johnson and Dugger Springs. Plotted next to each of the well sites is the elevation of the ground surface (top of grade) that was surveyed by WWBWC staff during summer 2009 (Patten S. , 2010). Moving down gradient, Transect B2 covers a total distance of about 0.9 miles with a total change in topographic surface of about 70 feet from the HBDIC recharge site (~793 feet) to both flow gauges on Johnson Creek (~723 feet) and Dugger Creek Springs (724 feet). This translates into about a 1.3 % grade of topographic slope.




Figure 49. Transect from HBDIC project site headwaters of Johnson and Dugger Creek Springs

Figure 50 shows hydrographs for WWBWC monitoring wells from GW-40 to GW-65 along this transect with GW-65 being the closest to the headwaters of both springs. The groundwater infiltration pressure perturbations (denoted here at R-1, R-2, and R-3) can be tracked down gradient through the water table toward the near-spring well site, GW-65. It should be noted that GW-35 is a shallow well that has some use associated with it, which explains the periodic drawdown in it.




Figure 50. WWBWC Monitoring Wells (Transect B2) from HBDIC Site to near Headwaters of Johnson Creek Springs

Utilizing the changes in water level from recharge operations at GW-65 we now can look to the WWBWC spring gauges for signs of groundwater-to-spring-discharge similarities. **Figure** 51 shows this well site relative to the headwaters of both Johnson and Dugger creek springs. The horizontal distances between this well site and the actual spring heads were not surveyed as a part of this project, but were measured using the Arc-GIS distance tool. Johnson Creek's South Fork springs are approximately 1059 feet from GW-65 with a slope of 2.4% (25 feet vertical in 1059 feet horizontal). Dugger Creek spring is approximately 929 feet from GW-65 with a slope of 2.6%. These marked increases in topographic slopes relative to the estimated 1.43% slope from GW-45 to GW-65 (4780 feet) may help explain why these springs emerge at this point in the aquifer system. Other factors likely playing a role in where springs emerge are changes in stratigraphy that may decrease the permeability of the saturated and unsaturated zones. With an increase in groundwater slope and a decrease in permeability (e.g. likely due to cataclysmic Missoula flood deposition of clays and Touchet bed materials) faster moving groundwater would be forced upward (mounding) toward the topographic surface producing the historic springs that the USGS (Piper, 1933) likened to 'spillways on a reservoir'.

The WWBWC surface-groundwater monitoring network also includes more than 50 small-order springs, creeks and ditch sites throughout the Walla Walla River Valley (Lewis, 2009). The WWBWC has

three relevant gauge sites to monitor spring and creek flow in these two subbasins. WWBWC gauge # LWSJ (South Fork Johnson Creek spring) measures the elevation of a pond fed exclusively by South Fork Johnson Springs (Figure 52). This site along with the other gauge sites were surveyed (Patten S. , 2010) with the purpose of tracking these recharge-to-spring physical connections. WWBWC gauge #LWDC1 measures flow (cfs) out of a series of springs at the headwaters of Dugger creek. The WWBWC installed a weir structure at the site and placed a water level logger and staff gauge at the site. Periodic in-stream stage measurements are recorded and used to calculate flow data. While the site does not capture all of the numerous springs along the headwaters of Dugger Creek, it does provide an understanding of the timing and volumes of flow arising from groundwater changes. WWBWC site #LWJG is a continuous level logger placed in the engineered intake weir for the Johnson Creek reconnection pipeline (Bower R. , 2008). It was installed in 2007 with the first two full years of data being 2008 and 2009. It should be noted however that this site is downstream from the springs and there are a number of active surface water rights that may influence the data recorded at this site. The map also shows other unmapped spring-seeps that likely provide some flow to Johnson and Dugger creeks. These features can be seen as wetland type swales in the fields near GW-65.




Figure 51. Aerial Map of GW-65 and Gauges-Springs on Johnson and Dugger Creeks




Figure 52. South Fork Johnson Springs (Pond) – Before and After HBDIC Operations (Bower)

Utilizing the water level elevation data from WY 2009 (October 1st 2008 through September 30th 2009) for both GW-65 and the spring-pond level data from LWSJ a graphical comparison was done (**Figure** 53). Groundwater level peaks G-1, G-2 and G-3 appear to correspond directly to pond water levels peaks Sp-1, Sp-2 and Sp-3 in the spring-fed pond. Therefore with this data set we can demonstrate the following logic:

Recharge Action = Groundwater Response = Spring Response

R-1 = G-1 = SP-1

R-2 = G-2 = SP-2

R-3 = G-2 = SP-3

Therefore:

Recharge Action = Spring Response




Figure 53. GW-65 vs LWJS Comparison of Groundwater to Spring Response to HBDIC Recharge Project Operations

Starting in the early 1930s some historic data was collected by the USGS (Piper, 1933) in support of the Supreme Court case Oregon v. Washington over management of the Bi-state Walla Walla and Little Walla Walla River system. The State of Oregon continued collecting both surface and groundwater data on many of the springs until the middle 1940s, and contined some of the well monitoring sites until present. Using historic data collected from 1932 through 1942 and WWBWC gauge data for Johnson Creek we made a comparision of historic versus current flow conditions. Historic grab sample data was compared against daily-average data that the WWBWC has collected. In order to graph them together, WWBWC data was averaged to monthly values that could be compared with the cooresponding values of the historic dataset. Figure 54 shows this comparison for historic water years 1932-34, 36-43 against current data from water years 2008 and 2009. For the water years 2008 and 2009 we utilized the WWBWC gauge data from LWJG as well as a gauge measuring the tail-water from the HBDIC Richartz Pipeline. The tail water was subtracted from the Johnson Creek flow as it is there artifically and would not represent a true comparison to historic conditions.

Historical data shows a relatively constant flow throughout the year which corresponds to more total groundwater storage available to provide this baseflow. The current data mimics the general pattern of the historic flows where a smaller peak flow value in the fall (November-December) and a large peak flow during the spring freshet (April-June). WY 2008 appears to be lower than the subsequent

WY 2009 flows for Johnson Creek. The early season WY 2009 data was not available due to a faulty logger. Clearly the groundwater to spring pattern for this location helped to better understand that groundwater recharge and discharge up gradient lead to flows in the down gradient Johnson Creek springs.




Figure 54. Comparison of Historic versus Current Johnson Spring-Creek flows (OWRD/USGS and WWBWC).

Turning to the other proximal springs relative to the GW-65, Dugger Creek Springs; **Figure** 55 shows the 2008 water year flow data for the spring gauge at Dugger Creek Springs relative to the groundwater pertubations from HBDIC recharge activities (GW-65). Similar to that shown in the Johnson Creek datasets, Dugger Creek surface flows also seem to correspond directly to HBDIC recharge site operations.




Figure 55. Comparison of Recharge Groundwater Response to Dugger creek Flow (WY 2008)

Linking Spring Responses to Declines in Groundwater Storage

The seasonal fluctuations of the water table in the sub-catchments discussed in the previous sections can be shown to link both the infiltration of water from recharge to the discharge of water through groundwater extraction. However with a system appearing this responsive to change, how is groundwater storage as described in the previous sections actually expressed?

In an early section, **Figures** 8 and 9 showed that the historic static water table readings showed high variably in levels for any given water year. This variability can be further defined by plotting the values by month to show seasonal change. **Figure 56** shows a summary of water table measurements taken at the OWRD State Observation Well #850 from the 1930's until present. Years with the most monthly static water measurements were selected and synthetic data was generated to map the seasonal trend apparent in the entire dataset. Starting in the 1930s through early 2000 the seasonal pattern of the water table are reasonably consistent across the period of record. However, while the pattern is similar the height of a given year (Y-axis) decreases through time toward the bottom of the well, which subsequently went dry. This overall drop in average readings represents the historical loss of storage in the aquifer system. As spring flow has been shown to be linked to elevation of the groundwater this explains why springs such as Dugger or Johnson Creeks flowed perennially in the past but now flow only when the elevation of the peaks (**Figure** 56) are above the required elevation at the

surface. This helps us better understand the role storage plays in the base flows of springs and likely the Walla River.




Figure 56. Walla Walla Basin Aquifer Water Table Fluctuations and Historical Trends

Other Recharge Results: Johnson Creek Recovery

In the early 1930s, just one of the three springs that feed Johnson Creek was measured to range between 2-4 cfs during the summer months. During that time, Johnson Creek served a series of water rights through and past the town of Umapine and most likely was the primary water supply during the establishment of the town in the mid-1800s. For decades what little water came out of the springs, didn't make it down to the lower end of the system.

Starting in 2003, the flows are returning to Johnson Creek after being dry for nearly three decades and appeared to incrementally increase from the subsequent year. The headwaters of Johnson Creek, like the observation well SOW #853 discussed earlier, are directly down gradient from both the Hudson Bay District Improvement Company Aquifer Recharge project and the other up gradient water management changes mentioned earlier. During the winter of 2007, the WWBWC, HBDIC and citizens from the town of Umapine, using OWEB funding, worked together to reconnect this disconnected

tributary to the Walla Walla River via the Dugger-Schwartz-Pine Creek tributary system. Today Johnson Creek flows for a portion of the water year directly to Dugger Creek (**Figure** 57). This is water that had not been historically available for down gradient flow restoration before the HBDIC testing site operations. These results emphasize both the ability of recharge to play a role in helping to restore flow to historic springs and serve as a cautionary note on recharge and down gradient springs that have been abandoned due to declining flows.




Figure 57. Johnson Creek flowing again after 25 years (Umapine, Oregon – Bower)

Summary of Spreading Basins Testing and Recommendations

Spreading basins are effective at HBDIC and have shown their ability to move large amounts of water into the groundwater system. Relative to the value of the water being stored, this tool can be considered the preferred method of water storage. Results from the 2004-9 testing indicate that clogging and/or subsurface mounding of groundwater are issues that will need to be addressed for the long term operations of this site. Off-season treatment and removal of the sediment layers that appear to be accumulating is recommended as first steps toward this goal. There are numerous techniques used by larger recharge programs that can help address these issues of long term operations. Water quality for the site, both source and recharged groundwater, has shown itself to be of good and consistent quality. On-site water table monitoring may indicate that localized groundwater storage is recovering from HBDIC recharge activities, although additional years of monitoring will help confirm this trend. Additional site upgrades should include a reexamination of the intake structure and its ability to measure flow more effectively with regards to White Ditch fluctuations as well as water backing up from the first spreading basin. The overflow flume site should also be upgraded from a portable weir to a concrete structure to ensure that excessive water leaving the site is measured.

PART III. INFILTRATION GALLERIES

Infiltration Gallery Testing

Overview

Making irrigation systems more efficient through the lining and piping of irrigation canals is another tool for water management. While you lose the aquifer recharge benefits you gain more surface water volume with which to irrigate. Irrigation efficiency in these terms does provide the Walla Walla basin with a method to better manage surface waters. However with the urgency of addressing the declining aquifer system and drying up of spring-creeks, developing methods of incorporating managed aquifer recharge into piped and lined canals systems is critical. The idea is to save water during times of scarcity without losing the ability to replenish the natural groundwater storage of the system. Furthermore the availability of acres of open ground, such as used for spreading basins is not always available or cost effective. Subsequently numerous smaller recharge areas spread spatially in watershed may be helpful to reduce the subsurface mounding created by larger projects and better disperse the storage of water.

The concept of recharging groundwater in subsurface galleries or chambers is not a new one. For years storm water managers in municipalities and along road systems have devised ways to collect run-off from impervious surfaces and infiltrate that water into the subsurface so as to avoid overland flow and flooding. In these situations the water can often contain pollutants and suspended solids that make their deposal difficult. The risk of toxic water quality issues along with the clogging of disposal area makes this a unique water management challenge. More recently many municipalities in water restricted areas of the world are developing these subsurface recharge galleries to be used in parks, golf courses, and in some cases for capturing run-off from roof tops for backyard recharge programs.

The methods and designs utilized in the infiltrating of storm water can be built upon in the case of recharging with clean winter source water such as the case at the HBDIC recharge site. The HBDIC team decided that there was a need to test the varying methods and materials for infiltrating recharge water into the subsurface. A number of designs and materials were reviewed to determine which infiltration galleries were tested including material costs versus their perceived effectiveness at recharging groundwater. From reviewing other recharge testing projects we knew that the most difficult challenge for these systems was clogging. The presence of suspended solids in the source water along with the possibility of biological clogging from algae growth in the galleries was an issue that has thwarted effectiveness of these projects in the past. In designing the testing galleries, collaboration was established with Adam Hutchinson who leads the Orange County Water District's managed aquifer recharge (MAR) program. The Orange County team has been testing infiltration galleries type MAR projects under golf courses, in city parks and in other locations where small, discreet subsurface recharge sites were needed to maximize the programs ability to recharge and store water. Information from their experiences was used extensively to design the galleries as well as develop the testing methodology for the project.

Infiltration Gallery Designs, Permitting and Testing

Four types of subsurface materials were used to design for infiltration galleries at the upper end of the HBDIC recharge site (See **Figure** 25). The materials were chosen primarily to compare the cost of materials relative to their anticipated effective recharge rates and how those rates may decrease through time due to clogging. Infiltration gallery # 1 (IG-1) was constructed using 4" perforated pipe (ADS) that can be purchased inexpensively from any home builder supply and its easy installation allowed for low labor costs. Infiltration Gallery #2 (IG-2) utilized 4 inch perforated PVC pipe typically used in domestic septic-tiling systems. This was also fairly easy to install; also keeping the overall constructions costs down. Galleries #3 and #4 both utilized materials developed by companies designing subsurface infiltration methods for the storm water industry. Infiltration Gallery #3 (IG-3) was built with *Stormtech Chambers* that are open bottomed allowing the water to infiltrate downward. Further, they can be designed to be periodically cleaned of sediment and debris. Infiltration gallery #4 (IG-4) utilized *Atlantis Raintanks* which resemble boxes that are open on all sides allowing for intra-chamber water exchange, but the 336 "tanks" each require assembly making their installation costs the highest of the four designs. Preliminary trials of these 'tank' style galleries were conducted successfully in the City of Adelaide Australia (Higginson, 2007).

Figure 58 shows the general schematic of the completed IG testing area while engineered designs for the galleries, turnout and other structures can be found at the WWBWC offices. Water is diverted from the White Ditch via a self-cleaning, screened weir (A) situated on the bottom of the canal. Water moves down gradient through the 21 inch main pipe to a stilling well which has the primary control valve (butterfly) to release water in to the testing galleries (B). An YSI Model # 6920 V2 turbiditytemperature-conductivity meter is at this location allowing continuous data recording during the operation of the galleries. IG-1, 2, 3, and 4 are supplied water from the main pipeline via 5" connector pipes (C) that have 5 inch butterfly control valves and McCrometer (Model #EO3000) propeller-style flow meters that measure both instantaneous flow rates (gallons per minute) as well as totalize the inflow (total gallons x 100). Each set of galleries were installed with air-release vents that also provide a method by which to visually inspect inside the gallery. These vents are located in different locations depending on the type of gallery. At the end of the main line is an overflow basin (D) that allows a location to drain any accumulated sediment from the intake and main pipeline structure prior to turning on the infiltration galleries. Adjacent to the gallery testing area HBDIC Observation Well #4 (GW-45) is located just downgradient (E). Figures 59 and 60 show the materials and installation of the IG-3 and IG-4 galleries.




Figure 58 Infiltration Gallery Testing Area (HBDIC Site)



Figure 59. Infiltration Gallery #3 - Stormtech Chamber Installation (2008)



Figure 60. Infiltration Gallery #4 - Atlantis Raintanks Installation (2008)

Next to each of the galleries piezometers were installed in perpendicular transects away from the galleries in order to measure both groundwater mounding as well as water quality (PZ-1 through PZ-15). The piezometers varied on depth from approximately 4 to 11 feet in length with a horizontal spacing of 2 to 5 feet between each gallery with the first piezometer located directly adjacent to the infiltration gallery. Water level recorders (*In-situ Inc. LT100, Unvented, pressured transducers*) were used to measure water levels and temperatures during each of the individualized gallery testing. Each piezometer was outfitted with pre-packed mesh screens so that samples could be extracted effectively from each measurement point. **Figure** 61 shows the various gallery-specific monitoring equipment installed at the site.

Water recharged below the ground surface is classified by the State of Oregon and the Federal Environmental Protection Agency as requiring special permitting and review under the Underground Injection Control (UIC) permitting program. The HBDIC team worked with the Department of Environmental Quality (ODEQ) to apply for and receive a UIC permit to test all four galleries (2009, ODEQ's UIC # 13233-1, 13233-2, 13233-3, 13233-4). Under this approved application (Bower R., WWBWC-HBDIC's Infiltration Gallery Testing Project: Application for UIC Permit (ODEQ), 2008) a summary of results for the HBDIC site water quality monitoring program and the results to-date were supplemented with detailed gallery designs and additional turbidity, total suspended solids (TSS) and total organic carbon (TOC) testing to track potential clogging of the galleries. As the HBDIC recharge site already has a permit from Oregon Water Resource Department (OWRD #LL1189) to divert water for testing, no further water use permits were required. The galleries were specifically designed to have a separate water intake from that of the site's spreading basins so they could be tested independently. While the water recharged would be important to helping the overall goal of recharging the aquifer, the main purpose of this installation was for testing purposes. After receiving the permit in December 2008, they were constructed over an 8 week period and were ready for testing starting in late January 2009.

Infiltration Gallery Testing Plan

The scheduled testing for the first recharge session aimed to accomplish two main goals. First, each gallery would be initially run independently of the others to measure the individual recharge rates and monitor any immediate changes relative to clogging during the first week of operations. Each gallery was to be run for a week and then turned off for 24 hours before the next down gradient gallery was turned on. Operating more than one gallery at once also created the potential problem of cross influencing each other through the mounding of subsurface water due the close proximity of the galleries therefore, individualized testing was preferred. The testing would take a total of 5 weeks to complete. After this initial individualized testing the galleries were to be all operated in tandem for the remaining portion of 2009 to track any long-term changes in recharge rates over a recharge season or from year to year.



Figure 61. Infiltration Gallery monitoring equipment (2009)

Turbidity, TSS and TOC measurements were to be taken during both the individualized and tandem testing at several pertinent locations and sent to *Edge Analytical Inc.* in Burlingame, Washington. Samples were collected in sterile, 250 ml bottles from the channels edge at the Little Walla Walla River diversion from the source waters of the Walla Walla River. Measurements were also taken at the intake structure of the galleries where the YSI continuous meter was recording turbidity and total dissolved solids in 15-minute intervals during operations. These samples could then be compared to build a regression relationship between TSS and turbidity. By characterizing this relationship the use of turbidity meter can help both with the testing of the galleries as well as establishing water quality guidelines by which to operate the HBDIC and other future MAR sites in the basin. When this information is further linked to mainstem flow, real-time monitoring could help to automate a basin wide recharge system. The purpose of measuring at both the Walla Walla River and at the HBDIC site was to further investigate and potential change in TSS and TOC values as the water moved through the conveyance system.

Infiltration Gallery Testing Results – Preliminary

Construction of the site lasted until late January 2009, just a few days before the Little Walla Walla diversion annual shut down. This allowed only a short test of IG-1 to start the season. Later in February all the galleries were operated for 5-7 days to test all of their individual recharge rates and map the mounding with the piezometers. It was found during the operations of IG-2, the meter's totalizer was not operating. This made the instantaneous portion of the meter the only way by which to monitoring operations. At IG-3 and IG-4 it was found that the 5" feeder pipe was sized too small for these two galleries as air vents at the far end of the galleries showed water was not making to the gallery ends. Therefore, the results for these two galleries under-estimate the true operation rates for *Stormtech* and *Atlantis* style designs. After the individual gallery testing was completed, galleries were operated as spaced pairs (IG-1 and IG-3, IG-2 and IG-4). Lastly, the YSI turbidity meter had power-source difficulties that limited the 2008-9 water quality monitoring to TSS lab sample source to intake comparisons.

At the time of this report the 2010 season has not been completed, so the 2008-9 results are shown along with preliminary information for 2009-10 season (**Table** 6). The galleries have different infiltration areas (due to the materials used and restriction on the site area) and once the rates were normalized by infiltration-area IG-2 seems to have the highest average infiltration rate (2008-9) of 1.67 cfs. Of course with IG-3 and IG-4 having a restricted inflow pipe, their values are likely to be significantly higher than shown here. The galleries combined to recharge approximately 180 acre-feet of additional recharge water (2008-9) during a very limited operation period. Preliminary 2009-10 results show some potential changes in flow rates with all galleries appearing to lose 10-20 gpm from the prior season. IG-1 appears to be operating at about 1/3 of the prior season but it is unclear if that is a factor of clogging or some influence of individual versus dual (IG-1 and IG-3) gallery operations. The galleries have contributed approximately 488 acre-feet of additional recharge at the HBDIC site to date.

Reviewing the preliminary TSS samples from the Little Walla Walla Diversion and the IG gallery intake, it appears there may be a weak correlation between sites suggesting some attenuation of

suspended solids between locations (Figure 62). Water level data at all 15 piezometers provided detailed water mounding profiles for each of the galleries during the 2008-9 seasons as shown for IG-1 in Figure 63.

Recharge Season	Infiltration Gallery#	Average Flow (gpm)		Infiltration Area (feet ²)	Average Flow (cfs) - Area adjusted (1086 feet)	Total Volume (2009) (gallons)	Total Volume (2009) (acre-feet)	Comments
2008-9	IG - 1	371.3	0.83	667	1.35	9,160,000	28.1	Piezometers with TSS sampling
2008-9	IG - 2	460.0	1.02	667	1.67	10,156,800	31.2	Estimated Volume (days x average rate)
2008-9	IG - 3	539.4	1.20	1,086	1.20	15,882,700	48.7	5" intake constricts total rate
2008-9	IG - 4	568.2	1.27	1,008	1.36	23,379,400	71.8	5" intake constricts total rate
Season Total Recharge Volume						58,578,900	179.8	IG-2 and Overflow pit not included
Recharge Season	Infiltration Gallery#	Flow (gpm)	HIOW	Infiltration Area (feet ²)	Average Flow (cfs) - Area adjusted	Total Volume (2009-10) (gallons)	Volume To Date (acre-feet)	Comments
0			Flow	mintration	-	(2009-10)	Date	Comments Reduced Rate - dogging or dual operations?
Season	Gallery#	(gpm)	Flow (cfs)	Area (feet ²)	Area adjusted	(2009-10) (gallons)	Date (acre-feet)	
Season 2009-10	Gallery # IG - 1	(gpm)	Flow (cfs) 0.26	Area (feet ²)	Area adjusted 0.4	(2009-10) (gallons) 22,425,200	Date (acre-feet)	Reduced Rate - dogging or dual operations?
Season 2009-10 2009-10	Gallery # IG - 1 IG - 2	(gpm) 115.0 452.0	Flow (cfs) 0.26 1.01	Area (feet ²) 667 667	Area adjusted 0.4 1.6	(2009-10) (gallons) 22,425,200 N/A	Date (acre-feet) 69 N/A	Reduced Rate - dogging or dual operations? Volume not estimated
Season 2009-10 2009-10 2009-10	Gallery # IG - 1 IG - 2 IG - 3	(gpm) 115.0 452.0 520.0	Flow (cfs) 0.26 1.01 1.16	Area (feet ²) 667 667 1,086	Area adjusted 0.4 1.6 1.2	(2009-10) (gallons) 22,425,200 N/A 22,428,500	Date (acre-feet) 69 N/A 68.8	Reduced Rate - dogging or dual operations? Volume not estimated 5" intake constricts total rate

Table 6 Infiltration Gallery Testing Preliminary Results




Figure 62. Preliminary Results of TSS and Conveyance Attenuation from Source to HBDIC Recharge Site




Figure 63. Piezometer water level results from initial operations of IG-1 gallery (2009)

Cost-Effectiveness Summary

The limitations poised by the small intake feeder pipes combined with the galleries being limited in mounding area make doing a straight forward cost-benefit (recharge rate vs. costs) analysis impractical. If the galleries are operated and tested individually in the future, and larger feed pipes are installed in IG-3 and 4, perhaps an estimate can be generated. The galleries as currently configured will serve to test the clogging issue, which is really the most pressing of the original research questions. Table 7 provides a basic break-down of the overall costs of materials for the IG testing as well as a \$/foot value for each gallery. Labor should be considered in the construction of these galleries, particularly if numerous galleries were installed around a watershed. It is estimated that labor costs were significantly higher for the IG-3 and IG-4 with the *Raintanks* taking approximately 60 man-hours. Exact labor and materials costs will differ by region and supplier; an extensive analysis was not undertaken for this report.

	Total Material Costs	Cost/infiltration
Infiltration Galleries Materials	(2008)	Area (\$/foot)
Inlet Structure	\$4,300	n/A
Mainline Pipe	\$14,200	n/A
Main Value Structure	\$3,330	n/A
IG #1 Perforated Pipe	\$2,211	\$3.32
IG #2 Drain Tile (septic)	\$2,274	\$3.41
IG #3 Stormtech Chambers	\$7,764	\$7.15
IG#4 Atlantis Rain Tanks	\$10,078	\$10.00
Total	\$44,157	_

Table 7 General costs breakdown for Infiltration Galleries (does not include gravel).

Summary of Infiltration Gallery Testing and Recommendations

Infiltration gallery testing includes not only the physical monitoring and water quality monitoring of various gallery designs but also the process by which they are permitted for operations. The HBDIC recharge team was successful in obtaining UIC permits for the testing site which coupled with the OWRD limited testing license allowed the system to be built for testing. Initial results on recharge rates show that these galleries have the potential to recharge considerable amounts of water if spaced sufficiently from other areas where surface water is infiltrating (e.g. ditches, ponds or natural water bodies). Issues with pipe sizing, meter failures and site placement limited the independent testing results of the galleries. However even with these issues all the galleries will provide long-term clogging information to the HBDIC team over the life of the testing project. Recharge notes do not appear to have varied greatly between the various materials; however the limitations mentioned previously make any firm predictions tenuous. When funding is secured, it is recommend that the faulty flow meter (IG-2) and the limiting 5" feeder pipes (IG-3 and 4) are replaced so that actual flow rates and volumes can be accurately recorded over the next 5 years of the limited testing license. Establishing the TSS to Turbidity Meter rating curve and keeping careful records of operation times, rates and volumes is critical to better assess the most critical issue, clogging.

PART IV. SUMMARY, CONCLUSIONS, AND RECOMMENDATIONS

Summary of Results

The HBDIC recharge site has been operated for six recharge seasons totaling 602 days of operations. On-site recharge spreading basins and infiltration galleries have recharged the aquifer with more than 13,500 acre-feet of water, which represents more than 21 square-miles a foot deep of water. The OWRD limited testing license that the HBDIC Site operates under (LL-1159) requires that ditch conveyance losses be included under the 50 cfs maximum use quantity, taking the projects total recharged volume to 25,000 acre-feet (40 square-miles a foot deep of water.) Onsite recharge rates have varied by year depending on the water year availability and the infiltration area with *effective average* values between 5.7 to 15 cfs. Basin clogging and water table recovery may also be acting to slightly reduce the surface infiltration rates on site.

Water quality monitoring performed at the site has shown an ambient low-level fecal coliform contamination in the surface water and surrounding shallow aquifer system. Surface water to groundwater treatment through recharge activities may indicate that natural attenuation processes are applicable for the HBDIC site operations. General chemistry results showed no significant findings while only two low-level detections were made of any Soluble Organic Compounds (e.g. pesticides, etc) during this testing period. Water quality of both the source water and groundwater appear to be stable and predictable during the recharge season. Recharge did not degrade groundwater quality.

WWBWC monitoring wells have helped track the recharged water as it moved into the groundwater system. Pressure perturbations directly linked to HBDIC recharge activities were used to track the recharge influence on groundwater response and to down-gradient springs. The springs were showing recovery when compared directly to historic flows recorded during the 1930s and 1940s. From these results the WWBWC-HBDIC team believes the HBDIC recharge site has been successfully testing aquifer recharge and is recharging a portion of the shallow aquifer system. The benefits of groundwater recovery while helping to restore historic spring flows also appear to be linked to HBDIC recharge site operations (Figure 64). We believe these results provide the basis by which to pursue the Bi-state ARSR program outlined in the following section of this document.




Figure 64. Walla Walla River Basin springs and groundwater returns to the Walla Walla River.

Managed Aquifer Recharge – Balancing Storage

The results of testing at the HBDIC site indicate that MAR can be a useful water management tool in the Walla Walla basin. When considering numerous historical as well as new stresses that face the storage of water in the shallow aquifer system, MAR should be considered (**Figure** 65). Other options currently being considered include surface water storage behind dams, large pumping exchanges with the Columbia River and/or curtailment of existing water rights, both irrigation and domestic. Some of these other options require hundreds of millions of dollars while others threaten political polarization of the community. None of the options in themselves can guarantee that the balance of water in this highly interconnected surface-groundwater system will be sustainable for fish and people into the future.




Figure 65. Balancing Storage with Managed Aquifer Recharge and other methods.

Managed Aquifer recharge has shown positive results toward being a water management tool for the Walla Walla Basin. As a tool it can be used as it is designed and for nothing more. Other water management strategies that could ensure better management includes restoring wetlands, river and creek flood plains through levee setback projects. Slowing water down after decades of making it move faster through the basin seems the best strategy as these activities also improve the habitat of wildlife and increase the quality of life of the residents of the basin. As supplies of water decrease the value of water will increase, making it more useful to buy and sell water (water banking) or utilizing it with crops of higher commercial value. Finally, using less water through conservation is always the least expensive alternative to all of the above mentioned and should be part of the overall Walla Walla basin strategy.

Moving Forward: From Testing to Programmatic Response

The operations, analysis, and modeling of the HBDIC Recharge testing site coupled with the information collected at the other 2 Walla Walla basin's recharge sites has provided critical answers to the most pressing questions about aquifer recharge for this basin, including;

- 1. Aquifer recharge has been shown to effectively transfer seasonally available surface water into the shallow aquifer for the purposes of storage
- 2. Aquifer recharge has been shown to help restore flows in historical springs that are tributaries to steelhead and redband trout creeks
- 3. Source water used for aquifer recharge should be shown to have good and consistent quality

- 4. Aquifer properties have been measured showing this system can provide a viable water storage
- 5. Continued piping coupled with over-allocated well pumping without mitigation will result in continued spring declines and threatens to jeopardize instream flows throughout the system.

The information generated by this monitoring along with applied research conducted by the WWBWC and its partners has led to vast improvements in our understanding of groundwater conditions and characteristics. Complementing our scientific understanding of the hydrology within the Walla Walla basin, the WWBWC and its partners have also been moving forward with policy development for the Aquifer Recharge and Spring Restoration (ARSR) program. Supporting this effort, in 2009 the State of Washington passed legislation creating the Walla Walla Watershed Management Partnership.²⁰ The Partnership is a public agency operating under RCW 90.92 (2SHB 1580, Chapter 183, Session Laws of 2009) and is charged with piloting local water management in the Walla Walla Basin. Efforts leading up to the formation of the Partnership were made up of community members including landowners, local governments, conservation groups, tribes, state and federal agencies, and many other entities working to develop local solutions to the unique water issues in the Walla Walla Basin. In Washington, the Partnership integrates local water and watershed management with state oversight, providing a primary governance structure for improved water management and ensuring that local and statewide interests are protected.

In spring 2009, the WWBWC hosted a Bi-state Groundwater Status meeting where hydrogeologists representing both states (OWRD/WDOE) met with WWBWC technical staff and discussed basin monitoring, aquifer trend analysis, and regulatory and enforcement tools by which the system can be better managed. In Washington the shallow aquifer is closed to further irrigation appropriations and has recently restricted the amount of water new exempt wells can utilize. In Oregon the shallow aguifer is still officially open to new well applications. However, new applications are being reviewed under a more detailed evaluation and additional scrutiny.

The WWBWC is also working with Oregon and Washington Water Trusts to create a bi-state water banking system in order to create 'cap-n-trade' mechanism. By creating a water banking system the intent is to create a system where new wells are required to mitigate for their use by purchasing mitigation credits through the Trusts. This system can help create revenue by which to help support the implementation of the ARSR program.

Progressive water management on the Oregon side of the basin is represented in the Umatilla Critical Groundwater Task Force²¹ recently completed 2050 Plan²² and its primary goal:

http://www.wallawallawatershed.org/http://umatillacounty.net/planning/Groundwater.htm

http://www.co.umatilla.or.us/planning/Groundwater.htm

"... ensure a coordinated, integrated response with maximum use of all water resources and to mitigate the effects of water declines impacting Umatilla County." (Umatilla County CGT, 2009)

This forward thinking plan proposes the creation of water management districts, encouraging the construction and operations of aquifer recharge projects and working to create revenue streams from which funding can be acquired to implement more management projects in Umatilla County. The ARSR goals for the Walla Walla Basin follow those of the Umatilla County plan and have support for further development at the county level.

Water management efforts in both states have been working together to come up with programmatic solutions to addressing this bi-state hydrologic, biologic and economic issue. The Walla Walla Basin Aquifer Replenishment and Spring Restoration Program intends to build on all of these efforts by creating a coordinated bi-state approach to address the legal, design, distribution, timing, habitat, water quality and quantity issues that are anticipated in creating an aquifer and river system that is managed in a sustainable fashion. The overall goal, as illustrated in Figure 66, is to first *stabilize* the declining aquifer and then move toward *recovery* of lost storage.




Figure 66. Conceptual Graph depicting goals of ARSR program

The goals of the ARSR program are to:

- 1. Build adequate recharge capacity to first stabilize and then recover shallow aquifer storage to historic levels.
- 2. Recovered groundwater storage will lead to the recovery of the natural springs which provide cool baseflow back to the Walla Walla River and its distributaries.
- 3. Whenever possible, refine and enhance current management of surface and groundwater capacities to support goal #1 (e.g. better management of Little Walla Walla River during non-irrigation season)
- 4. Work with water conservation efforts to design and build water systems that conserve water during times of scarcity and recharge water during times of abundance
- 5. Educate the general public on the complexity of surface water-groundwater management in the Walla Walla Valley

This ambitious program will not be done unless the WWBWC and its partners pursue its creation and application. There are no state or federal programs that are set up to address this critical issue and without action now, the aquifer and related springs will continue to decline along with the fish and farms that depend on them. This program represents a clear and present need in the Walla Walla basin.

Bibliography

ASCE. (2001). Standard Guidelines for Artificial Recharge of Groundwater. EWRU.ASCE 34-01. ASCE.

Baker, T. (2010). *Final Report Seasonal Seepage Assessments (WMI Task 4.2)*. Milton-Freewater, Oregon: WWBWC, For WMI Monitoring Program Phase II.

Baker, T. (2010). Walla Walla Basin GIS Data Model: For the Analysis of Hydrology and Fisheries Data (WMI Task 5.5). Milton-Freewater, Oregon: WWBWC, Report for: Watershed Management Initiative Monitoring Program Phase II.

Barke, R. (2007). State cancels water shut-off: Magic Valley farmers can keep irrigating this season while their dispute with fish producers is worked out in court. rldaho Statesmen Journal, http://www.idahostatesman.com/newsupdates/story/100152.

Bear, J. (1972). *Dynamics of Fluids in porous Media*. American Elsevier, (also Dover Publications, 1988; translated into Chinese).

Bouwer, H. (1987). *Soil-aquifer treatment of sewage.* . Rome : Paper prepared for the Land and Water Development Division, FAO. .

Bower, R. (2004). *Hudson Bay Aquifer Recharge Testing Project: 2004 Annual Report.* Milton-Freewater, Oregon: WWBWC.

Bower, R. (2005). *Hudson Bay Aquifer Recharge Testing Project: 2004-5 Annual Report.* Milton-Freewater, Oregon: WWBWC.

Bower, R. (2005). *Hudson Bay Aquifer Recharge Testing: 2005 Annual Report.* Milton-Freewater, Oregon: WWBWC.

Bower, R. J. (2003). *Hudson Bay Aquifer Recharge Project: An application for ASR Testing Limited License to Oregon Water Resources Department (OWRD) (OAR 690-350-0020), and attachments*. Milton-Freewater, Oregon: WWBWC.

Bower, R. (2005). Walla Walla River Surface Water Budget Assessment (2002-2004). . Milton-Freewater, Oregon: WWBWC

www.wwbwc.org/projects/monitoring_research/Seepage_2004/Walla%20Walla%20River%20Surface%2 0Water%20Budget%20Assessment.pdf.

Bower, R. (2009). *Watershed Management Iniative Monitoring Program Phase II: Drilling of Additional Observation/Monitoring Wells.* Milton-Freewater, Oregon: WWBWC.

Bower, R. (2008). WWBWC Final Report: Johnson Creek Reconnection Project. Milton-Freewater, Oregon: WWBWC, OWEB Grant # 207-116.

Bower, R. (2008). WWBWC-HBDIC's Infiltration Gallery Testing Project: Application for UIC Permit (ODEQ). Milton-Freewater, Oregon: Walla Walla Basin Watershed Council.

Butcher, D. (2006). *Walla Walla Subbasin: Stream Temperature Total Maximum Daily Load and Water Quality Management Plan. Oregon Department of Environmental Quality*. Pendleton, Oregon Department of Environmental Quality (ODEQ):

http://www.deq.state.or.us/wg/tmdls/docs/wallawallabas.

Butcher, D. B. (2006). *Appendix A: Walla Walla River Temperature Analysis. Vegetation, Hydrology and Morphology, Walla Walla River Subbasin.* Pendleton, Oregon: Oregon Department of Environmental Quality -State of Oregon. http://www.deq.state.or.us/wq/tm.

Douglas, T. (2006). *Review of Salmon-Salmon Interactions in British Columbia*. Vancouver, BC: Prepared for Watershed Watch Salmon Society and the Walter, Duncan and Gordon Foundation. http://www.watershed-watch.org/publications/files/Groundwater+Salmon++hi+res+print.pd.

Fleckenstein, J. A. (2004). *Managing Surface Water-Groundwater to Restore Fall Flows in the Cosumnes River*. Journal of Water Resource Planning and Management. Vol. 130. no. 4, pp. 310-310. July-August 2004. ISBN 0733-9496.

Freeze, R. A. (1979). Groundwater. Prentice-Hall Publishing. ISBN 0-13-365312-9.

Higginson, S. B. (2007). Managed aquifer recharge using infiltration galleries:comparative study of recharge operations at two field sites in Western Australia. Phoneix, Arizona: International Syposium of Managed Aquifer Recharge.

Kendy E., B. J. (2006). *Transient effects of groundwater pumping and surface-water irrigation returns on streamflow.* WATER RESOURCES RESEARCH, VOL. 42, W08415, doi:10.1029/2005WR004792, 2006.

Lewis, W. (2009). Watershed Management Iniative Phase II: Final Report Small-order Stream and Spring Monitoring Network 2009 Report. Milton-Freewater, Oregon: WWBWC.

Lindsey, K. (2007). *Geologic Setting of the Miocene (?) to Recent Suprabasalt Sediments of the Walla Walla Basin, Southeastern Washington and Northeastern Oregon*. Richland, Washington: Groundwater Solutions Inc.Prepared for the WWBWC and WDOE. .

MacNish, R. &. (1976). *Digital model of the gravel aquifer WW Basin*. Report - http://www.ecy.wa.gov/programs/eap/wsb/pdfs/WSB_45_Book.pdf Plates: http://www.ecy.wa.gov/programs/eap/wsb/pdfs/WSB_45_Plate_1.pdf: US Geological Survey. Report WSB 45.

Metcalf, S. (2003). Monitoring of Groundwater and Surface water Interactions on the Walla Walla River, Oregon for the Purpose of Restoring In-Stream Flows for ESA Listed Fish Habitat. Corvallis, Oregon: Thesis for MS Degree in Bioresource Engineering, Oregon State University.

Mullan, C. J. (1863). Report of the Construction of a Military Road from Fort Walla Walla to Fort Benton in 1863. Ye Galleon Press, Fairfield, WA.: United States Army.

Newcomb, R. (1965). *Geology and Groundwater Resources of the Walla Walla River Basin, Washington-Oregon.* USGS for the Washington State Division of Water Resources. Water Supply Bulletin No. 21. 151p.

Newcomb, R. (1961). Storage of ground water behind subsurface dams in the Columbia River basalt, Washington, Oregon, and Idaho. o: U.S. Geological Survey Professional Paper 238A, 15 p.

News, H. C. (2007). Of Politics and the river. HCN Vol. 39 No. 14. www.hcn.org.

Olsen, J. V. (2006). *Estimates of ground-water recharge to the Yakima River Basin Aquifer System, Washington, for predevelopment and current land-use and land-cover conditions.* U.S. GEOLOGICAL SURVEY Scientific Investigations Report 2007–500.

Page, T. (January 2007.). *Email from Tom Page on Replenishment of McEvoy Spring Creek*. Walla Walla, Washington.

Patten, S. (2010). Watershed Management Initiative - Phase II: Final Report GPS Survey. Miton-Freewater, Oregon: WWBWC. Report for the Watershed Management Initiative – Phase II.

Patten, S. (2009). Watershed Management Initiative – Phase II: Final Report Shallow Aquifer Monitoring in the Walla Walla Basin. Milton-Freewater: WWBWC.

Petrides, A. (2008). *Modeling Surface Water and Groundwater Interactions Near Milton-Freewater, Oregon.* Corvallis, Oregon: Thesis for MS Bioresource Engineering, Oregon State University.

Piper, A. R. (1933). *Groundwater in the Walla Walla Basin, Oregon-Washington-Part 2.* Department of the Interior, U.S. Geological Survey. 176p.

Piper, A. R. (1933). *Groundwater in the Walla Walla Basin, Oregon-Washington-Part I.* Department of the Interior, U.S. Geological Survey. 99p.

Reser, Y. (2007). Walla Walla River Basin (WRIA 32), Water Resources Program Rule, Chapter 173-532 WAC. Walla Walla, Washington: Report of Planning Unit Member Yancey Reser to Planning Unit and Director Manning. (Email).

Richardson, P. C. (2000). *April 1999 Milton-Freewater Groundwater Quality Study.* Pendleton, Oregon: . Department of Environmental Quality.

http://www.deq.state.or.us/wq/groundwater/docs/gwqrpts/miltonfreewater/study.pdf.

Unlimited, T. (2007). Gone to the Well Once Too Often: The Importance of Gorundwater to Rivers in The West. Trout Unlimited's Western Water Project. (Second Printing).

Warinner, J. (2006). Strategic Plan: Shallow Aquifer Recharge, Strategy for Restoring and Seasonally Recharging Shallow Gravel Aquifer(s) and Spring-fed Stream of the Walla Walla Watershed. Walla Walla Watershed Alliance and NRCS.

Wolcott, B. P. (2003). *Walla Walla Basin Watershed Council - Strategic Action Plan.* Milton-Freewater, Oreogn: WWBWC report to OWEB . www.wwbwc.org.

Wozniak, K. (2007). Water Use and Recharge Estimates in the Umatilla and Walla Walla Drainage Basins, Oregon. Salem, Oregon: Prepared by Oregon Water Resources Department Staff for the Umatilla County Critical Groundwater Taskforce. .

Yancey, R. (2005). *Email Documenting to WWBWC, USFWS, NOAA, OWRD, WWWA, ODFW, WDFW and CTUIR the loss of West Little Walla Walla Flows.* Valley Chapel Grange, Washington: Native Creek Society.

* Electronic aerial photos of basin provided by: Dr. William Bowen California Geographical Survey (http://geogdata.csun.edu) 10907 Rathburn Avenue Northridge, CA 91326 william.bowen@csun.edu

Appendices Available at:

www.wwbwc.org

541-938-2170

Appendices I-A

HBDIC Recharge Water Quality Testing:
Lab Results, Notes and Records

2004 Recharge Season

Main Identity (HYDRO)

From:

"RICHERSON Phil" < Richerson. Phil@deq.state.or.us>

To:

"Bob Bower" <bob.bower@wwbwc.org>; "Walla Walla River Irrigation District"

<wwrid@qwest.net>; "Tony Justus" <tony.g.justus@wrd.state.or.us>;

<Stephen.c.hall@usace.army.mil>; "Rick George" <rickgeorge@ctuir.com>; "Mike Ladd"
<michael.f.ladd@wrd.state.or.us>; "Kevin Scribner" <ktscribner@gohighspeed.com>; "Jon Brough" <jon@gohighspeed.com>; "John Zerba" <wahs@bmi.net>; "John Warinner"

<warinner@bmi.net>; "John Covert" <jcov461@ecy.wa.gov>; "Jim Chambers"

<Jim.R.CHAMBERS@WRD.State.or.us>; "Gary James" <garyjames@ctuir.com>; "Donn Miller" <Donn.W.MILLER@wrd.state.or.us>; "Chris J Hyland" <chris.j.hyland@nww01.usace.army.mil>;

"Brian Wolcott" <bri>brian.wolcott@wwbwc.org>; "Brian Mayer OWRD-Wells Inspector"

<bri>drian.m.mayer@wrd.state.or.us>; "Bill Neve" <wnev461@ecy.wa.gov>; "Dan Evans GTH-Law"

<devans@qth-law.com>

Cc:

"WOLGAMOTT Mitch" < WOLGAMOTT.Mitch@deq.state.or.us>

Sent:

Monday, April 19, 2004 8:32 AM

Subject:

RE: Update

After talking with my manager and several colleagues, we feel it would be OK to continue the recharge project for now, as long as fecal coliform is the only contaminant being detected in the source water and it is not being detected in the downgradient compliance wells. It would probably be a good idea to get the total count on the source water. The detection of pesticides in the source water would likely need to be handled differently. Please keep me up to date on your analytical (and hydrologic) results.

Thanks. Phil Richerson

Phil Richerson Nonpoint Source Hydrogeologist Oregon Department of Environmental Quality 700 SE Emigrant, #330 Pendleton, OR 97801 (541) 278-4604 (541) 278-0168 fax Richerson.Phil@deq.state.or.us

----Original Message----

From: Bob Bower [mailto:bob.bower@wwbwc.org]

Sent: Monday, April 19, 2004 9:15 AM

To: Walla Walla River Irrigation District; Tony Justus; Stephen.c.hall@usace.army.mil; Rick George; RICHERSON Phil; Mike Ladd; Kevin Scribner; Jon Brough; John Zerba; John Warinner; John Covert; Jim Chambers; Gary James; Donn Miller; Chris J Hyland; Brian Wolcott; Brian Mayer OWRD-Wells Inspector;

Bill Neve; Dan Evans GTH-Law

Subject: Update Importance: High

Greetings,

Well a mixed bag of information this morning. I will start with the down side:

Kuo testing sent us notice that the water quality samples we took last week produced a PRESENT hit for Fecal Coliforms. The observation well we were also measuring was negative for the same test, which is really good news. After talking with Phil Richardson (DEQ), the best course of action is to shut the project down and re-test the sample water and well water. I will drive this morning and get the bottles and sample the water this afternoon. We should have results by weeks end. I have shut down the project as of this am.

The good news is that all three ponds have been completed and the aquifer (downloaded monitoring wells

this am) were continuing to climb. I also drove down to the headwaters of Johnson Creek, which for as long as I can remember has been dry, there was water in the creek bottom this morning.

I have to say I am a bit disappointed in the positive hit for fecals. Things were moving along so well. We will resample and see where that takes us. All of the other tests we have done thus far have been "no detection" so this is the first major road block in the project. A total count will provide a lot more information. I have ordered several to make sure we have QA/QC.

I will of course keep you all posted.

Bob Bower

Bob Bower

From:

"Bob Bower" <bob.bower@wwbwc.org>

To:

"Walla Walla River Irrigation District" <wwrid@qwest.net>; "Tony Justus"

<tony.g.justus@wrd.state.or.us>; <Stephen.c.hall@usace.army.mil>; "Rick George"

<rickgeorge@ctuir.com>; "Phil Richerson" <RICHERSON.Phil@deq.state.or.us>; "Mike Ladd" <michael.f.ladd@wrd.state.or.us>; "Kevin Scribner" <ktscribner@gohighspeed.com>; "Jon Brough" <jon@gohighspeed.com>; "John Zerba" <wahs@bmi.net>; "John Warinner" <warinner@bmi.net>; "John Covert" <jcov461@ecy.wa.gov>; "Jim Chambers"

<Jim.R.CHAMBERS@WRD.State.or.us>; "Gary James" <garyjames@ctuir.com>; "Donn Miller" <Donn.W.MILLER@wrd.state.or.us>; "Dan Evans GTH-Law" <devans@gth-law.com>; "Chris J Hyland" <chris.j.hyland@nww01.usace.army.mil>; "Brian Wolcott" <bri>brian.wolcott@wwbwc.org>;

"Brian Mayer OWRD-Wells Inspector" <bri>hrian.m.mayer@wrd.state.or.us>; "Bill Neve"

<wnev461@ecy.wa.gov>; "Tom Darnell" <Thomas.Darnell@orst.edu>

Cc:

"WOLGAMOTT Mitch" < WOLGAMOTT.Mitch@deq.state.or.us>; "Stephanie Eaton"

<stephanie.eaton@wwbwc.org>; "Gina Massoni" <gina.massoni@wwbwc.org>; "Eric Pfeifer"

<pfeifdog@whitties.org>; "Rivera Chris" <chris.rivera@wwbwc.org>; "Brian Wolcott" <bri>sprian.wolcott@wwbwc.org>; "Bob Chicken" <bob.chicken@wwbwc.org>; "Bob Bower"

<Bob.bower@wwbwc.org>

Sent:

Thursday, April 22, 2004 11:34 AM

Subject:

WQ update

Good morning,

Some news on the recharge site (left voice mail with Phil).

After our fecal coliform hit at the intake site (ditch water) last week, I did a battery of fecal and E. coli (CFU counts) samples on:

(1) Intake (ditch water)

(2) Well 1 (downgradient obs well, influenced by project water)

(3) Well 3 (upgradient control well).

I just received the results this am (via phone and fax):

Recharge Intake was fecal 40 cfus, E. Coli 24.1 (cfus = colony forming units per 100 ml) Well #1 fecal 3.1 cfus, E. Coli 2.0 Upgradient control Well # 3 fecal 14.8, E. Coli 7.5

In my opinion this is what I believe is going on (knowing that this a very small sample size).

We know that the ditch by itself brought up the aquifer ~20 feet before we turned on the recharge project. I would guess that the ditch is the main vector for movement of the bacteria based on reported concentrations and the aquifer static being dramatically influenced by the ditch without the project being on. I would say that the problem may be background all along the ditch back to where ever the source is. I have 12 more fecal/e, coli concentration (cfus) tests ordered (here Monday) that I was going to use to move back up gradient of the site and test both ditch and wells along the way. I would also take three samples from Well #1 (recharge influenced) ~ throughout a 24 hour period, to see if this is an episodic plume type event. whereus soumple well 1, sample #3

As I told Phil on the phone, hind site is 20-20. We have WQ samples for the conditions before the ditch was on, and after the ditch AND the recharge project were running. What we missed was a WQ sample with JUST the ditch on, which would provide us with a better background condition for the recharge operation. We can capture that when we turned off the project and sample before the ditch goes off. One thing we can definitely refine for next year's recharge season.

In my thesis work in the Tillamook watershed, we saw that septic related feces in river/streams appeared to trend with time of day. Early morning and evenings when people are home, using their toilets, showers, etc. Certainly

with the nature of our substrate here and how quickly water moves, that would seem a logical guess for our valley as well. Fecal bacteria are enteric (intestinal tracks) and are not very fond of a climate outside of the 96 degrees F range. As all our samples are early morning, it makes sense we might be capturing a daily upgradient septic plume. Of course, I need a lot more information before I can start shoring up theories like these. Also one thing I learned from that work was how variable FC and E.Coli concentrations could be even between samples collected at the same time, so concentrations from just a few samples are always something to use carefully.

So to clarify what I would propose to move forward with as our sampling plan:

Set 1:

12 additional fecal/e.coli cfus tests (this next early Monday)

Questions: Is this fecal presence background conditions? Does it come from areas around ditch or WW River?

Period: early morning

2 samples in ditch moving back upgradient toward WW River

4 on site samples (intake, well 1 (x 2 for 10 % repeatability QA/QC) and control well 3)

3 samples in upgradient wells (we have several I could use staggered up along the ditch) (Hypothesis: fecals are back ground to this system).

Question: Chronic or episodic fecal events?

Period: 24 hour period (Wednesday next week)

4 samples at well #3 through out the rest of a 24 hour period (about 8 hours apart, 1 extra at Well 1 for 10% QA/QC repeatability). Give us more information on the idea of if this is a chronic condition or episodic events.

Set 2:

Question: Is this fecal presence persistent? Does it get worse/better?

Period: 2-3 days

CFU samples (fecal/e.coli) at OBS well 3 until end of project.

(*** and possibly more fecal depending on results from Set 1 sampling)

Final Set 3:

Question: Is this a background condition associate with common ditch operations?

Period: 2-3 days after project offlline, ditch still running full.

Full set of analytes and FC cfu testing at Intake and Well #1

JUST FC cfu at Well #3

Thoughts, concerns or questions?

We get our EPA analyte results late Friday, I will keep you all posted.

Cheers,

Bob Bower

Freul Coliforn testing Wells matrale Surface wells HAGE O. ful FC-7 Frog @ 7:50 am FC-3 5W40 Huelete Irigation FC-1 4/29/4 (Gravel - hum) day well 6w39 well C 4/29/4 temp = 6.3° c Eswards (Country Rs) 9:50 am NS = S2.7 + | 29 / 4 NS 3 128.7 8:20 am temp = 13.8 NS = 13.0 しんけ static=35 + 27 11 FC-2 @ Winesop temp = 10.6 C 9:06 wie skriba en baile fc-8 4/29/7 old John house Static 35/+9" (ovatypo). kmp = 6.5 for TOG Down scalest NS = 53.1 4/19/4 FC-4a GW 47 10:30 FC- & To take 4/29 + NS= 79.1 NS = 276.4 9:35 temp= 14.0 temp = 16.2 time 9:30 am Stat. = 25 Static = 35'-4" 4 22 4 Sterile en boiler NI = 52.9 Deplicate sample (94/90) temp = 7.4 FC-46 taken same time o FC-5 005 Well # 1 4/21 H GW-48 tini 9: 12 an Stati: 20' NS = 5 +8" MMp 13 6

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free http://www.kuotesting.com e-mail: kuotest@atnet.net Web Site:

DATE COLLECTED

DATE RECEIVED

DATE REPORTED

5/21/2004

SEND REPORT TO:

5/21/2004

6/2/2004

W.W.B.W.C.

SYSTEM / CUSTOMER

PO Box 68 Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

SAMPLE NO. CUSTOMER

	SAMPLE NO	ANALYSIS	RESULTS	MOL	UNITS	ANALYSTS
70881	OBS Well #1	COD	11	8	mg/L	Qian
70881	OBS Well #1	TKN as Nitrogen	< 0.72	0.72	mg/L	Qian
70881	OBS Well #1	Chloride	ND	0.03	mg/L	Qian
70881	OBS Well #1	Orthophosphate as P	0.20	0.037	mg/L	Qian
70881	OBS Well #1	Total Dissolved Solids	<20.3	20.3	mg/L	Qian
						1
	11-2-31-100011-3001					
_						
	5-15 m 2 m 2 m 2 m					arinto .

<(0.001): indicates the analyte was not detected at or above the concentration indicated.

None Detected

...Indicates milligrams per litre

rQL=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

MDL: Method Detection Limit

Please check out our new Web Site at http://www.kuotesting.com

06-09-04

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

> DATE COLLECTED 4/13/2004

DATE RELEVEN

OF FROM STAD

SEND REPORT TO 4/14/2004

4/23/2004

W.W.B.W.C. PO Box 68

5 - C - N. C - 2" GWTT

Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Aim:

SALPLE feb	Carlo delle le Englishet i Sat	ANALYET)	RESULT9	MEG.	UNITS	ANALYSTS
70295	Well #1	Chloride	N.D	0.297	mg/l_	Qian
70295	Well #1	TKN as Nitrogen	<0.72	0.72	mg/l.	Qian
70295	Well #1	Total Dissolved Solids	<20.3	20.3	mg/L	Qian
70295	Well #1	Orthophosphate as P	0.19	0.037	mg/l.	Qiari
70295	Well#1	COD	55	8	mg/L	Qian
		the state of the same of the s				
	in a special in production that agreement and the first three three special and the special special special and the special sp					AND THE PERSON OF THE PERSON O
p						A
	and the second of the second or the second of the second o					400000000000000000000000000000000000000
	A THE CONTRACT OF THE CONTRACT					
	and the second s	And the second s				
			,			
		A CONTRACTOR OF THE STREET				
-	The second secon		***		-	
-	California representativa de la companio del la companio de la companio del la companio de la co					The same of the sa
		The state of the s				
and the same of th			~1000 CHICAGO			
	The state of the s	CONCRETE SECURIOR SEC		************		
	A REAL PROPERTY AND ADDRESS OF THE PERSON ADDRESS OF THE PERSON AND ADDRESS OF THE PERSON AND ADDRESS OF THE PERSON ADDRESS	A) - Advisor Anna Caracter of the Anna Anna Anna Anna Anna Anna Anna Ann				
		A		a in anti-minute party.		Anna all the state of the state
		- Water 1920		Section of the sectio	ATTAIN THE PARTY OF P	- April 1990 - State Sta
-	APPA SEASTING TO SEAST AND THE TAXABLE PARTY.			- After two challenges at		***************************************

<(0.001) indicates the shalfse was not detected at or above the concentration indicated.</p>


NO. None Detected

mgl, indicates sulligrams per hire

PQ_PPractical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions
Mpl. Method Detection Limit

Please check out our new Web Site of http://www.kuotesting.com

Mollydin for Guyana



Agricultural - Industrial - Environmental

INVOICE DATE **INVOICE** # CLIENT #

WWB2170 04-04-348 04/23/04

PURCHASE ORDER#

Address: PO Box 68 Client: W.W.B.W.C.

MiltonFreewater, OR 97862

Grower:

PN ..

Project:

Sampler: Bob Bower

KptNo	RptNo RptDate	Field Identifier	Test	Description	Qty	Price	Extension
F70201	00/11/00	Tetele Will Hi	TANK STOREGIST				
T670/1	04/14/04	Intake,Well #1	A17-1	Ortho-P	3	35 00	
E70291	04/14/04	Thtake Well #1			1	20.00	50
10004	04/24/04	and description of the second	G-RTW	Dissolved Solids	0	25 00	50
T620/9	04/14/04	Intake, Well #1	D-C4	MONITOR IN COLUMN TO A COLUMN	1	10.00	200
E70291	04/14/04	Intako Woll #1		******	7	35.00	70.0
10001	04/14/04	THE THE THE	A8	COD	2	32.00	79
E / UZST	104/14/04	Intake.Well #1	200	Chi			04.0
		1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	N3-2	Culoride	N	18.00	36

Notes: 04-04-348

Invoice Total

270.00

0 %

Discount

FAX Charge

-0.00

Invoice Total Due

Terms: Net 30 days following date of invoice. Invoices not paid in 30 days will be subject to interest charged at 1.5% per month (18% per year) with a minimum charge of 50 cents.

\$270.00

0.00

Due Date

05/23/04

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

DATE COLLECTED 4/13/2004

DATE RECEIVED

DATE REPORTED

SEND REPORT TO:

4/14/2004

4/23/2004

W.W.B.W.C.

SYSTEM / CUSTOMER

PO Box 68

Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

SAMPLE NO. CUSTOMER

	CUSTOMER SAMPLE NO	ANALYSIS	RESULTS	MDL	UNITS	ANALYSTS
70295	Well #1	Chloride	N/D	0.297	mg/L	Qian
70295	Well #1	TKN as Nitrogen	< 0.72	0.72	mg/L	Qian
70295	Well #1	Total Dissolved Solids	<20.3	20.3	mg/L	Qian
70295	Well #1	Orthophosphate as P	0.19	0.037	mg/L	Qian
70295	Well #1	COD	55	8	mg/L	Qian
					*	
-						
-						
			*			

001): indicates the analyte was not detected at or above the concentration indicated.

None Detected

L:Indicates milligrams per litre

-QL=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

MDL: Method Detection Limit

Please check out our new Web Site at http://www.kuotesting.com

Dr. Eugene Kuo, Quality Assurance Coordinator

April 23, 2004

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free http://www.kuotesting.com e-mail: kuotest@atnet.net Web Site:

DATE COLLECTED

DATE RECEIVED

DATE REPORTED

4/13/2004

SEND REPORT TO

4/14/2004

4/23/2004

W.W.B.W.C.

SYSTEM / CUSTOMER

PO Box 68 Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

SAMPLE NO.

	CUSTOMER SAMPLE NO	ANALYSIS	RESULTS	MDL	UNITS	ANALYSTS
70291	Intake	COD	21	8	mg/L	Qian
70291	Intake	Total Dissolved Solids	<20.3	20.3	mg/L	Qian
70291	Intake	TKN as Nitrogen	< 0.72	0.72	mg/L	Qian
70291	Intake	Chloride	N/D	0.297	mg/L	Qian
70291	Intake	Orthophosphate as P	0.21	0.037	mg/L	Qian
•						
+					-	

9,001); indicates the analyte was not detected at or above the concentration indicated.

None Detected

L:Indicates milligrams per litre

PQL=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

MDL: Method Detection Limit

Please check out our new Web Site at http://www.kuotesting.com

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

> DATE COLLECTED 4/13/2004

DATE RECEIVED

DATE REPORTED

SYSTEM / CUSTOMER

SEND REPORT TO: 4/14/2004

4/23/2004

W.W.B.W.C.

PO Box 68

Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

ample no.	SAMPLE NO.	AMALYSIS	RESULTS	MOL	UNITS	AMALYSTS
70295	Well#1	Chloride	N/D	0.297	mg/L	Qian
7.0295	Weil #1	TKN as Nitrogen	< 0.72	0.72	mg/L	Qian
70295	Well #1	Total Dissolved Solids	<20.3	20.3	mg/L	Qian
70295	Well #1	Orthophosphate as P	0.19	0.037	mg/L	Qian
70295	Well#1	COD	55	8	mg/L	Qian
				THE RESERVE THE PROPERTY OF THE PERSON NAMED IN COLUMN TWO		
						THE PROPERTY OF THE PARTY OF TH
Table State Service		WALLEY BOOK OF THE PARTY OF THE				
		Tables - And the same of the s	THE PERSON NAMED IN COLUMN TWO IS NOT THE OWNER.			SANDERS NOT THE THE PERSON NAMED IN
WANTED STATE	The Control of the Co					Marketine and properties where the second
					TOTAL THE MAKE DISPLETED HAVE A	NATIONAL PROPERTY OF THE PROPE
		CONTRACTOR OF THE PROPERTY OF				
	THE RESERVE OF THE PERSON NAMED IN		THE RESERVE OF THE PERSON NAMED IN		THE PROPERTY OF THE PERSON NAMED IN	AND THE PERSON NAMED IN COLUMN TWO IS NOT THE PERSON NAMED IN COLUMN TWO IS NAMED I
			TO SERVE ASSESSMENT OF THE PARTY OF			
		Edwinor-mark with the post of the first of the country of the				Control of the second s
			THE STATE OF THE S			
		CONTRACTOR STATE STATE OF THE S				Charles of the second second
	120121-1201		Charles and the state of the st		THE PERSON NAMED IN COLUMN 2 IS NOT	THE PERSON NAMED OF THE PE

<(0.001): indicates the analyse was not detected at or above the concentration indicated ND: None Detected

mg/L:Indicates milligrams per hire

* PQL=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and securacy during routine laboratory operating conditions

MDL: Method Detection Limit

Picase thack out our new Web Site at http://www.kupuskug.com

Molledon for Guyana

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

> DATE CULLECTED 4/13/2004

DATE RECEIVED

DATE REPORTED

SEND REPORT TO

4/14/2004

4/23/2004

W.W.B.W.C. PO Box 68

SYSTEM / CUSTOMER

Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

70291 Intake 70291 Intake 70291 Intake 70291 Intake 70291 Intake 70291 Intake		COD Total Dissolved Solids TKN as Nitrogen Chloride Orthophosphate as P	RESUL 21 <20.7 <0.77 N/D 0.21	3	8 20.3 0.72 1.297	mg/L mg/L mg/L mg/L	ANALYSTS Qian Qian Qian Qian Qian
70291 Intake 70291 Intake		TKN as Nitrogen Chloride	<0.77 N/D	2.	0.72	mg/L mg/L mg/L	Qian Qian Qian
70291 Intake		Chloride	<0.72 N/D	2	.297	mg/L mg/L	Qian Qian
STATE AND RESIDENCE AND RESIDE			N/D	0		mg/L	Qian
70291 Intake		Orthophosphate as P	CANADA SERVICIO DE LA COMPANSION DE LA COMP	STATE OF THE REAL PROPERTY CONTRACTOR OF THE PROPERTY OF THE P	O 3 7	THE STATE OF THE S	
				COMPANIES NAMED AND DESCRIPTION OF THE PERSONS	ON THE REAL PROPERTY OF THE	NATO-Secretary	
	ADMINISTRATION OF THE VALUE OF	or and another state of the second se					
	i Minister (1900) i Statisti (1900) i Nederli (1900) i Statisti (1900) i Sta				OMETICANISTI SANTONIO	an parameter series.	
**************************************			OUTHER CONTROL OF THE				
	and a complete the common electric desirable at the Administration of the Administration	The state of the s					
						P CONTRACTOR OF THE PARTY OF TH	
TOWN IN THE PARTY OF THE PARTY							

<(0,001): indicates the analyse was not detected at or above the concentration indicated.

mg/Lindicates milligrams per litre

PQL=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions MDL: Method Dotection Limit

Please thack out our now Web Site at hen: / www.kuotestine.com

Dr. Eugene Kuo, Quality Assurance Coordinator

Apr. (23, 2004



Kuo Testing Labs, Inc. | Agricultural - Industrial - Environmental

Othello, Washington 99344 (509) 488-0112; Fax (509) 488-0118

ington 99344

INVOICE #

04-04-227

INVOICE DATE

CLIENT #

WWB2170

PURCHASE ORDER#

Client: W.W.B.W.C.

Address: PO Box 68
MiltonFreewater, OI

MiltonFreewater, OR 97862

PN .:

Project:

Grower:

Sampler: Bob Bower

18.00	18.00	1	Chloride	A9-2		METT #T	00/20/00	110000
32.00	32.00	1	COD	AO		E-17 #1	04/05/04	£70053
33.00	00.00	-		30		Well #1	04/02/04	E70053
35 00	35 00	1	TRO	A2-4		Well #1	04/02/04	E/0003
25.00	25.00	1	Dissolved Solids	A18-5		TH TTOM	04/00/00	110000
23.00	20.00	-	1			W-11 #1	04/03/04	E70053
200	25 00	•	Ortho-P	A17-1		Well #1	04/02/04	E70053
		7-3						
Extension	Price	Otv	Description	Test	Field Identifier		KptNo KptDate	KPTNO

Notes: 04-04-227

Terms: Net 30 days following date of invoice. Invoices not paid in 30 days will be subject to interest charged at 1.5% per month (18% per year) with a minimum charge of 50 cents.

Invoice Total

135.00

Discount 0

FAX Charge

% -0.00

0.00

Invoice Total Due \$135.00

Due Date

05/16/04

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

DATE COLLECTED

DATE RECEIVED

DATE REPORTED

4/2/2004

SEND REPORT TO

4/2/2004

4/14/2004

W.W.B.W.C. PO Box 68

SYSTEM / CUSTOMER

Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

SAMPLE NO

MPLE NO	SAMPLE NO.	ANALYSIS -	RESULTS	MDL	UNITS	ANALYSTS
70053	Well #1	COD	20	8	mg/L	Qian
70053	Well #1	TKN as Nitrogen	< 0.72	0.72	mg/L	Qian
70053	Well #1	Chloride	ND	0.72	mg/L	Qian
70053	Well #1	Orthophosphate as P	0.206	0.037	mg/L	Qian
70053	Well #1	Total Dissolved Solids	<20.3	20.3	mg/L	Qian
100	4					

<(0.001): indicates the analyte was not detected at or above the concentration indicated.

ND: None Detected

mg/L:Indicates milligrams per litre

* PQL=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

MDL: Method Detection Limit

Please check out our new Web Site at http://www.kuotesting.com

NOV-18-04 TUE 11:45 AM KUC TESTINGLABSING FAX NO. 5094886865 VALLEY Environmental Laboratory

Washington State Certified Lab #153 - DOE Accredited Lab C345

1.8	b/Sample No: I	Below	Date (Collected:	04/20/04			
A Charles State of Contract of	ate Received:	THE STREET STREET, SALES	Date l	Reported:	04/21/04	Supervisor:	DCR	
Sam	ple Location:					Invoice#:	2033 Water	
end Report To				Sample In	formation	Manta	· Traces	
(UO Testing I 37 South 1st Othello, WA 9				70359 - W 70360 - W	'ell #1		* * <u> </u>	
Fecal Coliform	/E. coli	Intak2	1/21/41	10011#3				
VEL Sa	imple Number: le ID/Location:	15342008 70358	15342009 70359	15342010 70360				
Analyte	Units	Results	Results	Results		Method	Date Analyzed	
Fecal Coliforni	CFU/100mL	40.0	3.1	14.8 7.5		SM 9222D SM 9223B	04/21/04	
Trigger; DOH Drin	orting Level): Indicar ting Water response les maminant level): Hig Indicates this compour	rel. hest lavel recon	unended by the	rederal governm	sent for public water	r systems.		

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free

Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

To Phil Richardia OPEP A COLLECTED 20/2004

DATE RECEMED

DATE REPURTED

SEND REPORT TO 4/20/2004

4/22/2004

Bob Bower PO Box 68

Milton Freewater OR

97862

	PTCIMER MINE NIA	ANALYSIS	RESULTS	MOL	UNITS	ANALYST
70358	ntake	Fecal Coliform	40.0	MOL 2	MPN/100ml	Valley Labs
	ntake	Fecal E-Coli	24.1	2	MPN/100ml	Valley Labs
			excessions and the second	and the second s	ovarrado artación e de construidado en mentralectropos d	
-			**************************************			
			TOWN TO THE CONTRACT OF THE PARTY OF THE PAR			
	-	nyenn yaketukka meurova militari sara terratika sara ka	CARREST (
				ATTENNESS CONTRACTOR OF	MANAGER SALTER STREET, PROPERTY AND ADDRESS.	MANAGEMENT TO THE PARTY.
******************************	**************************************	***************************************				Managar Angel Control Control Control
			to the second second second second			
			TO THE RESIDENCE OF THE PARTY O	******************	STATE OF THE PROPERTY OF THE P	TO STATE OF THE ST
-		v. du.				
		na arterior (m. 1821). Maj (Maj (Maj (Maj (Maj (Maj (Maj (Maj				
	-					
			TOTO CONTRACTOR OF THE PROPERTY OF			
	sensored or vistilenes/ks (Asia) milks		A CONTRACTOR OF THE CONTRACTOR			
THE PROPERTY OF THE PARTY OF TH	O SAN THE PROPERTY OF THE PROP	(PP) 3/2/Farror Principle Some Sense Sense Some area of the Sense				
		AND AND THE PROPERTY OF THE PR	AND AND ADDRESS OF THE PARTY OF		NAME OF THE OWNER OF THE OWNER, OF THE OWNER, OF THE OWNER, OWNER	A PRINT STANISHED BY PROPERTY OF
					***********	-
	was the country of the second of the second					
	de la Constitue de la constitu					
	And the second s					
						The state of the s

<(0.001). Indicates the analyte was not detected at or above the concentration indicated

ND. None Detected

mg/L:Indicates milhigrams per litte

* PQL-Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

MDL. Method Detection Limit

Please check out our new Web Sue at http://www.kuntesting.com

Mollylin for Eugano

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

> DATE COLLECTED 4/20/2004

DATE RECEIVED

DATE REPORTED

SEND PEPORT TO

4/20/2004

4/22/2004

W.W.B.W.C. PO Box 68

SYNTEM CONTONEY

Milton Freewater OR 97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

nette met	CONTOUR R	ANCLYDS	RESULTS	MOL	UNITS	AMALYSTS
70359	Well #1	Fecal Coliform	3.1	2	MPN/100ml	Valley Labs
70359	Well #1	Fecal E-Coli	2.0	2	MPN/100ml	Valley Labs

-						THE REAL PROPERTY AND ADDRESS.
	NATIONAL SECTION OF THE PROPERTY OF THE PROPER		S. A.			
					TOWN DUNCTORS AND STREET	

	Carlot and Carlottiness of the Section of the Secti		NAMES AND ADDRESS OF THE PARTY			
					UAL A CONTROL OF THE	

<(0.001) indicates the analyte was not detected at or above the concentration indicated.

ND: None Detected

mg/L:Indicates milligrams per litre

* PQL=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

MDL: Method Detection Limit

Please check out our new Web Site of http://www.kuotesting.com

Mollylin for Eugene Dr. Eugene Kuo, Quality Assurance Coordinator



Kuo Testing Labs, Inc. Agricultural - Industrial - Environmental

04-04-320

WWB2170

INVOICE DATE

CLIENT#

INVOICE #

PURCHASE ORDER#

Othello, Washington 99344

(509) 488-0112; Fax (509) 488-0118

Client: W.W.B.W.C.

Address: PO Box 68

MiltonFreewater, OR 97862

PN:

Project:

Sampler: Bob Bower

Grower

67.50 Price Qty Description Fecal Coliform Test FECAL Field Identifier Intake, Well #1, Well #3 RptDate 04/20/04 RptNo E70358

202.50

Extension

 Invoice Total
 202.50

 Discount
 0 %
 -0.00

 FAX Charge
 0.00

 Invoice Total Due
 \$202.50

05/23/04

Due Date

Terms: Net 30 days following date of invoice. Invoices not paid in 30 days will be subject to interest charged at 1.5% per month (18% per year) with a minimum charge of 50 cents.

Notes: 04-04-320

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free

http://www.kuotesting.com e-mail: kuotest@atnet.net Web Site:

DATE COLLECTED

4/20/2004

DATE RECEIVED

DATE REPORTED

SEND REPORT TO

4/20/2004

4/22/2004

SYSTEM / CUSTOMER

W.W.B.W.C. PO Box 68

Milton Freewater OR 97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

APLE NO	CUSTOMER SAMPLE NO	ANALYSIS	RESULTS	MDL	UNITS	ANALYSTS
70358	Intake	Fecal Coliform	40.0	2	MPN/100ml	Valley Labs
70358	Intake	Fecal E-Coli	24.1	2	MPN/100ml	Valley Labs
-						
-						

<(0.001): indicates the analyte was not detected at or above the concentration indicated.

No None Detected

.:InL:Indicates milligrams per litre

Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

MDL: Method Detection Limit

Please check out our new Web Site at http://www.kuotesting.com

Mollillin for Gugena Dr. Eugene Kuo, Quality Assurance Coordinator



Burlington WA | 1620 S Walnut St - 98233 | 800.755.9295 • 360.757,1

800.755.9295 • 360.757.1400 • 360.757.1402fax Bellingham WA 805 Orchard Dr Suite 4 - 98225

360.671.0688 • 360.671.1577fax

Page 1 of 1




QUALITY CONTROL REPORT **BLANK REPORT**

Reference Number: 06-06951

Report Date: 12/12/06

Batch	Analyte	Result	Units	Limit	QC Qualifier Method	Type*	Comments
COD_060609	CHEMICAL OXYGEN DEMAND	ND	mg/L	4.00	SM5220 D	LRB	
1060602A	CHLORIDE	ND	mg/L	0.10	300.0	LRB	
TDS_060607	TOTAL DISSOLVED SOLIDS	ND	mg/L	10.00	SM2540 C	LRB	
TKN-060621	TOTAL KJELDAHL NITROGEN	ND	mg/L	1.00	SM4500-Norg	(LRB	
TKN-060621	TOTAL KJELDAHL NITROGEN	ND	mg/L	0.12	SM4500-Norg	C MB	**







Corporate Office

Burlington WA | 1620 S Walnut St - 98233 B00.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225 360.671.0688 • 360.671.1577fax Page 1 of 1



QUALITY CONTROL REPORT QCS/LFB REPORT

Reference Number: 06-06951

Report Date: 12/12/06

			True			%		QC	
Batch	Analyte	Result	Value	Units	Method	Recovery	Limits	QualifierType*	Comment
COD_060609	CHEMICAL OXYGEN DEMAND	48	50	mg/L	SM5220 D	96	80-120	LFB	
TDS_060607	TOTAL DISSOLVED SOLIDS	474	500	mg/L	SM2540 C	95	80-120	LFB	
	TOTAL DISSOLVED SOLIDS	482	500	mg/L	SM2540 C	96	80-120	LFB	
TKN-060621	TOTAL KJELDAHL NITROGEN	4.06	4.00	mg/L	SM4500-Norg C	102	80-120	LFB	
TKN-060621	TOTAL KJELDAHL NITROGEN	4.00	4.00	mg/L	SM4500-Norg C	100	80-120	LFB	
COD_060609	CHEMICAL OXYGEN DEMAND	120	127	mg/L	SM5220 D	94	80-120	QCS	
060602A	CHLORIDE	29	30	mg/L	300,0	97	80-120	qcs	

^{*}Notation:

[%] Recovery = (Result of Analysis)/(True Value) * 100

NA = Indicates % Recovery could not be calculated.

QCS: Quality Control Sample, a solution containing known concentrations of method analytes which is used to fortify an alliquot of reagent matrix. The QCS is obtained from an external source and is used to check lab performance.

LFB: Laboratory Fortified Blank, an aliquot of reagent matrix to which known quantities of method analytes are added in the lab. The LFB is analyzed exactly like a sample, and its purpose is to determine whether method performance is within accepted control limits.



Burlington WA 1620 S Walnut St - 99233
Corporate office 8 800.755.24026x 360.757.1402(ax Bellingham WA 805 Orchard Dr Sulte 4 - 99225
Macrobiology 350.671,0688 • 360.671,1577(ax



Page 1 of 2

QUALITY CONTROL REPORT

Duplicate and Matrix Spike/Matrix Spike Duplicate Report

Reference Number: 06-06951

Report Date: 12/12/2006

Batch	Sample Analyte	Result	Duplicate Result	Units	20078	-4 U0076	000		
COD_060609								Comments	
TDS_060607	14252 CHLORIDE	5	13	тдл	0.0	0-45	and		
TKN-060624	14154 TOTAL DISSOLVED SOLIDS 14243 TOTAL DISSOLVED SOLIDS	278	286	mg/L mg/L	2.8	0.45	DUP DUP		
	14174 TOTAL KJELDAHL NITROGEN 14583 TOTAL KJELDAHL NITROGEN	146	150 1.28	mg/L mg/L	2.7	0-45	and and		

%RPD = Relative Percent Difference

NA = Indicates %RPD could not be calculated

Martix Spike (MS)/Matrix Spike Duplicate (MSD) analyses are used to determine the accuracy (MS) and precision (MSD) of a analytical method in a given sample matrix. Therefore, the usefulness of this report is limited to samples of similar matrices analyzed in the same analytical batch.

Only Duplicate sample with detections are listed in this report



Page 2 of 2

Report Date: 12/12/2006 Reference Number: 06-06951

Matrix Spike	pike			Duplicate	_									
Batch	Sample Analyte	E S	Spike	Spike	Spike		Percen	Percent Recovery				20 ,		
משטשט ערטט		Illinos.	lineav	Mesuli	Cons	nulls	MS	MSD	Limits	%RPD	%RPD Limits	Qualifier	Comments	
1060602A	14228 CHEMICAL OXYGEN DEMAND	Q.	22	84	20	mg/L	104	96	80-120	8.0	09-0	LFM		
TKN-060624	14146 CHLORIDE	N	2		1.00	mg/L	110	NA	80-120	Ä	0-80	LFM		
	14175 TOTAL KJELDAHL NITROGEN 14675 TOTAL KJELDAHL NITROGEN	7.74	11.5		4.00	mg/L.	94		80-120	A A	09-0	LFM		

%RPD = Relative Percent Difference

NA = Indicates %RPD could not be calculated

Matrix Spike (MS)/Matrix Spike Duplicate (MSD) analyses are used to determine the accuracy (MS) and precision (MSD) of a analytical method in a given sample matrix. Therefore, the usefulness of this report is limited to samples of similar matrices analyzed in the same analytical batch.

Only Duplicate sample with detections are listed in this report



Kuo Testing Labs, Inc. Agricultural - Industrial - Environmental

(509) 488-0112; Fax (509) 488-0118 Othello, Washington 99344

W.W.B.W.C. Client:

PO Box 68 Address:

MiltonFreewater, OR 97862

04-05-074 05/07/04 WWB2170 PURCHASE ORDER# INVOICE DATE INVOICE # CLIENT#

PN ..

Project:

Grower:

Sampler: Bob Bower

RotNo	RotNo RotDate	Field Identifier	Test	Description	Qty	Oty Price	Extension
E70498	E70498 04/30/04	FC-1, Frog,FC-2. Winesap Rd.,FC-3, Well GW-40,FC-4b OBS Well #3,FC-5 OBS Well #1,FC-7 GW-39,FC-8 GW-60 (John),GW-40,SW-801 #3,Intake,OBS Well #1 9:35P,OBS Well #1 6:40A,OBS Well #3 9:00P,OBS Well#3 6:30A	FECAL	FECAL Fecal Coliform	13	13 67.50	877.50

Notes: 04-05-074

Terms: Net 30 days following date of invoice. Invoices not paid in 30 days will be subject to interest charged at 1.5% per month (18% per year) with a minimum charge of 50 cents.

00.0 877.50 \$877.50 -0.00 % 0 Invoice Total Due Invoice Total FAX Charge Discount

06/06/04

Due Date

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

DATE COLLECTED 4/29/2004

DATE RECEIVED

DATE REPORTED

2004 SEND REPORT TO

4/30/2004

5/4/2004

SYSTEM / CUSTOMER

W.W.B.W.C. PO Box 68

Milton Freewater OR 97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

SAMPLE NO. CUSTOMER ANALYSIS ANALYSTS RESULTS SAMPLE NO CFU/100ml Valley Labs FC-1, Frog Fecal Coliform 12.2 70498

<(0.001): indicates the analyte was not detected at or above the concentration indicated.

None Detected

L:Indicates milligrams per litre

QL=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

MDL: Method Detection Limit

Please check out our new Web Site at http://www.kuotesting.com

05-04-04

Date

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

DATE COLLECTED 4/29/2004

DATE RECEIVED

DATE REPORTED

29/2004

SEND REPORT TO:

4/30/2004

UNITS

5/4/2004

ANALYSTS

SYSTEM / CUSTOMER

W.W.B.W.C. PO Box 68

Milton Freewater OR

CUSTOMER

SAMPLE NO

97862

ANALYSIS

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

RESULTS

SAMPLE NO.

70499 FC-2. Winesap Rd. Fecal E-Coli 4.1 2 CFU/100ml Valley Labs

<(0.001): indicates the analyte was not detected at or above the concentration indicated.

: None Detected

L:Indicates milligrams per litre

rQL=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

MDL: Method Detection Limit

Please check out our new Web Site at http://www.kuotesting.com

05 -09

Date

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free

Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

DATE COLLECTED

DATE REPORTED

4/29/2004

SEND REPORT TO

4/30/2004

DATE RECEIVED

5/4/2004

SYSTEM / CUSTOMER

W.W.B.W.C. PO Box 68

Milton Freewater OR 97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

SAMPLE NO.

CUSTOMER ANALYSIS UNITS ' ANALYSTS SAMPLE NO RESULTS MOL FC-3, Well GW-40 CFU/100ml Valley Labs 70500 Fecal E-Coli

<(0.001)	indicates the anal	te was not detec	ted at or	above the	concentration	indicated


None Detected

L:Indicates milligrams per litre

PQL=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions MDL: Method Detection Limit

Website at http://www.kuotesting.com

Date



337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free http://www.kuotesting.com e-mail: kuotest@atnet.net

DATE COLLECTED

DATE REPORTED

4/29/2004

SEND REPORT TO

5/4/2004

W.W.B.W.C.

SYSTEM / CUSTOMER

PO Box 68

Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

SAMPLE NO. CUSTOMER

ANALYSIS

LIMITS

DATE RECEIVED

4/30/2004

	SAMPLE NO	MINELOID	RESULTS	MDL	UNITS	ANALYSTS
70501	FC-4b, OBS Well #3	Fecal E-Coli	3.1	2	CFU/100ml	Valley Labs
- 14-11						
-						
_						
_						
-						
_						
_						
174	-					
-						

<(0.001): indicates the analyte was not detected at or above the concentration indicated.

None Detected

L:Indicates milligrams per litre

PQL=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

MDL: Method Detection Limit

Please check out our new Web Site at http://www.kuotesting.com

Eugene Kuo, Quality Assurance Coordinator

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free http://www.kuotesting.com e-mail: kuotest@atnet.net

DATE COLLECTED

DATE RECEIVED

4/30/2004

DATE REPORTED

4/29/2004

SEND REPORT TO:

5/4/2004

SYSTEM / CUSTOMER

W.W.B.W.C. PO Box 68

Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

SAMPLE NO. CUSTOMER

	SAMPLE NO.	ANALYSIS	RESULTS	MDL	UNITS	ANALYSTS
0502	FC-5, OBS Well #1	Fecal E-Coli	11.0	2	CFU/100ml	Valley Labs
-						
_						
-						
-						
-						
*0						
-						
				-		
T						

<(0.001): indicates the analyte was not detected at or above the concentration indicated.

L:Indicates milligrams per litre

"QL=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

MDL: Method Detection Limit.

Please check out fur new Web Site at http://www.kuotesting.com

Dr Eugene Kuo, Quality Assurance Coordinator

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

DATE COLLECTED 4/29/2004

DATE RECEIVED

DATE REPORTED

SEND REPORT TO

4/30/2004

5/4/2004

W.W.B.W.C. PO Box 68

SYSTEM / CUSTOMER

Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

SAMPLE NO. CUSTOMER **ANALYSIS** SAMPLE NO RESULTS UNITS ANALYSTS FC-7, GW-39 70503 Fecal E-Coli CFU/100ml Valley Labs <1

<(0.001):	indicates the	analyte was	s not detecte	d at or above	the concentration	indicated.
AUD. Man	Datasad					

None Detected

L:Indicates milligrams per litre

Please check out our www Web Site at http://www.kuotesting.com

r. Eugene Kuo, Quality Assurance Coordinator

05-04-04

[.] QL=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions MDL: Method Detection Limit

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free

http://www.kuotesting.com e-mail: kuotest@atnet.net

DATE COLLECTED 4/29/2004

DATE RECEIVED

DATE REPORTED

SYSTEM / CUSTOMER

SEND REPORT TO

4/30/2004

5/4/2004

W.W.B.W.C. PO Box 68

Milton Freewater OR 97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

SAMPLE NO.

CUSTOMER

ANALYSIS UNITS SAMPLE NO RESULTS ANALYSTS FC-8, GW-60 (John) 70504 Fecal E-Coli <1 CFU/100ml Valley Labs

<(0.001): indicates the analyte was not detected at or above the concentration indicated.

MD: None Detected

L:Indicates milligrams per litre


QL=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

MDL: Method Detection Limit

Please check out our new Work Site at http://www.kuotesting.com

Eugene Kuo, Quality Assurance Coordinator

05-04-04



337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free http://www.kuotesting.com e-mail: kuotest@atnet.net

> DATE COLLECTED 4/29/2004

DATE RECEIVED

DATE REPORTED

SEND REPORT TO:

4/30/2004

UNITS

5/4/2004

W.W.B.W.C. PO Box 68

SYSTEM / CUSTOMER

Milton Freewater OR

CUSTOMER

SAMPLE NO

97862

ANALYSIS

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

SAMPLE NO.

RESULTS ANALYSTS GW-47, OBS Well #3 70505 Fecal E-Coli CFU/100ml 2.0 Valley Labs

<(0.001): indicates the analyte was not detected at or above the concentration indicated.

None Detected

L:Indicates milligrams per litre

L=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions MDL: Method Detection Limit

Web Site at http://www.kuotesting.com

Edgene Kuo, Quality Assurance Coordinator

05-04-04

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

DATE COLLECTED

DATE RECEIVED

DATE REPORTED

4/29/2004

SEND REPORT TO

4/30/2004

5/4/2004

SYSTEM / CUSTOMER

W.W.B.W.C. PO Box 68

Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

SAMPLE NO

WII LE IVO	CUSTOMER SAMPLE NO	ANALYSIS	RESULTS	MDL	UNITS	ANALYSTS
70506	Intake	Fecal E-Coli	1.0	2	CFU/100ml	Valley Labs
*						

<(0.001): indicates the analyte was not detected at or above the concentration indicated.

None Detected

L:Indicates milligrams per litre

- PQL=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

MDL: Method Detection Limit

Please check out our new Web Site at http://www.kuotesting.com

05-04-04

Date

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free http://www.kuotesting.com e-mail: kuotest@atnet.net Web Site:

DATE COLLECTED

DATE RECEIVED

DATE REPORTED

4/29/2004

SEND REPORT TO

4/30/2004

5/4/2004

SYSTEM / CUSTOMER

W.W.B.W.C. PO Box 68

Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

SAMPLE NO. CUSTOMER

	OBS Well #1, 9:35p	ANALYSIS	RESULTS	MDL	UNITS	ANALYSTS
70507	OBS Well #1, 9:35p	Fecal E-Coli	5.2	2	CFU/100ml	Valley Labs
_						
-						
_						
	-					

<(0.001): indicates the analyte was not detected at or above the concentration indicated.

D: None Detected

/L:Indicates milligrams per litre

PQL=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

MDL: Method Detection Limit

Please check out our new Web Site at http://www.kuotesting.com

05-04-04

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free http://www.kuotesting.com e-mail: kuotest@atnet.net Web Site:

> DATE COLLECTED 4/30/2004

DATE RECEIVED

DATE REPORTED

SEND REPORT TO

4/30/2004

5/4/2004

SYSTEM / CUSTOMER W.W.B.W.C.

PO Box 68

Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

SAMPLE NO. CUSTOMER

SAMPLE NO	ANALYSIS	RESULTS	MDL	UNITS	ANALYSTS
OBS Well #1, 6:40a	Fecal E-Coli	9.7	2	CFU/100ml	Valley Labs
			N. C.		
					4
	OBS Well #1, 6:40a	OBS Well #1, 6:40a Fecal E-Coli	ODG W. II #1 4 40	ODG W 11 11 4 40	

<(0.001): indicates the analyte was not detected at or above the concentration indicated.

None Detected

.: Indicates milligrams per litre

QL=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions MDL: Method Detection Limit

Web Site at http://www.kuotesting.com Please check out our

Dr. Eugene Kuo, Quality Assurance Coordinator

05-04-04

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

DATE COLLECTED

DATE RECEIVED

DATE REPORTED

4/29/2004

SEND REPORT TO 4/30/2004

2004

5/4/2004

SYSTEM / CUSTOMER

W.W.B.W.C. PO Box 68

Milton Freewater OR 9

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

SAMPLE NO. CUSTOM

3111 22 110	SAMPLE NO.	ANALYSIS	RESULTS	MDL	UNITS	ANALYSTS
70509		Fecal E-Coli	3.0	2	CFU/100ml	Valley Labs
				-		
-					***	
_						

<(0.001): indicates the analyte was not detected at or above the concentration indicated.

None Detected

L:Indicates milligrams per litre


PQL=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

MDL: Method Detection Limit

Please check out our new Web Site at http://www.kuotesting.com

05-04-04

Date



337 South 1st Avenue, Othello, WA 99344 (509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free Web Site: http://www.kuotesting.com c-mail: kuotest@atnet.net

ASTEM (COC)ONER	0ATE 001LE0TED 4/29/2004	SEND RE		0/2004	5/4/2004
W.W.B.W.C. PO Box 68 Milton Freewater OR Project Name:	97862	PO E	Bower Box 68 on Freewater	OR 97	7862
AMPLE NO AUGIOMER SAMPLE NO	ANALYSIS Facel Put'nli	RESULTS	MOL	UNITS CFU/100ml	ANALYSTS Valley Labs
AMPLE NO AUGUSTOMER SAMPLE NO 70503 FC-7, GW-39	ANALYSIS Fecal E-Coti	RESULTS <1			The second section is a second section of the second section of the second section is a second section of the section of the second section of the section of the second section of the second section of the sect
					The state of the s
The state of the s	A STATE OF THE STA	ONLY OF THE OWNER O		Carlotter Management (see a 1 a september 1	

<(0.001): indicates the analyte was not detected at or above the concentration indicated.

ND: None Detected

mp/L indicates milligrams per litre

• PQL=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

MUL: Method Detection Limit

Please chuck you our you Web Site or http://www.kuptesting.com

Dr. Eugene Kuo, Quality Assurance Coordinator

05-04-04

Date

Dr. Eugene Kuo, Quality Assurance Coordinator

Date

Kuo Testing Labs, Inc.
337 South 1st Avenue, Othello, WA 99344

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free
Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

	4/29/2004	SEND REP	ORT TO 4/3	0/2004	5/4/2004
W.W.B.W.C. PO Box 68 Milton Freewater OR Project Name:	97862	Bob B PO Bo Milton Attn:		OR 9	7862
AMPLE NO LUSTOMER	ANALYSIS	RESURTS <1	<u>M:)E</u>	CFU/100ml	ANALYSTS Valley Labs
70504 FC-8, GW-60 (John)	Fecal E-Coli	<u> </u>		TAMES AND ADDRESS OF THE PARTY.	
			and the constant of the consta		
		A A COMMON DESCRIPTION OF THE PROPERTY OF THE			
		WAT 1000 THE REAL OF THE REAL			
					- APPROXIMATION
		Control of the Contro	CONTRACTOR OF STREET		
			AND THE BEST OF THE PARTY.	and the second s	
				DESCRIPTION OF THE PROPERTY OF	
	A FARRENCE OF THE PROPERTY OF			The state of the s	a designation of the second se
	and at an obasia the consensation indicate	od			
c(0,001); indicates the analyte was not dete ND: None Detected rag/L:Indicates intiligrams per litte POL=Practical Quantitation Lines is the lev			ov during mating	laboratory operating	enaditions
POL=Practical Quantitation Limit is the low		AND THE PERSON NAMED IN COLUMN TWO IS NOT THE OWNER.			

337 South 1st Avenue, Othello, WA 99344 (509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

DATE RECEIVED DATERCHORTED DATE COLLECTED 5/4/2004 4/29/2004 SEND REPORT FO: 4/30/2004 SYSTEM / CUE KINNEP Bob Bower W.W.B.W.C. PO Box 68 PO Box 68 97862 Milton Freewater OR Milton Freewater OR 97862 Atin: Project Name: SAMPLE NO UNITS ANALYSTS CONTOMER. ANALYSIS RESULTS GW-47, OBS Well #3 CFU/100ml Valley Labs 2.0 Fecal E-Coli 70505

•:(0.001): indicates the analyse was not delected at or above the concentration indicated.

ND: None Desceted

mg/Librdicates milligrams per like?

* PQL=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during founder laboratory operating conditions

MDL. Method Detection Limit

Please check out our new web Site at http://www.kuotestiag.com

Dr. Edgene Kuo, Quality Assurance Coordinator

05-04-04 Date

Kuo Testing Labs, Inc. 337 South 1st Avenue, Othello, WA 99344

337 South 1st Avenue, Othello, WA 99344
(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free
Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

STEM - CUSTOMUR	5ATE COLLECTED 4/29/2004	SEND ROP	ORT TO: 4/30/2004	5/4/2004
W.W.B.W.C. PO Box 68 Milton Freewater OR Project Name:	97862	Bob B PO Bo Miltor Attn:	ox 68 1 Froewater OR	97862
MPCENO COSTOMAR SAMPLE NO	e:2YJANA	RESULTS 1.0	Mil UN:7S 2 CFU/100m	ANALYSTS Nalley Labs
70506 Intake	Fecal ft-Coli			
	AND ADDRESS OF THE PROPERTY OF			
		100 00 00 00 00 00 00 00 00 00 00 00 00		
Appendix of the second of the				
and the same and t			A CONTRACTOR OF THE PROPERTY O	
				AND CONTRACTOR OF THE PARTY OF
D: None Detected	the detected at or above the concentration in the lowest level that can be achieved within it http://www.kuolestine.com			nting conditions 5 -04-04 ate

337 South 1st Avenue, Othello, WA 99344 (509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

> DATE COLLECTED 4/29/2004

DATE RECEIVED

DATE REPORTED

SEND REPORT TO 4/30/2004

5/4/2004

SYSTEM/CUSTOMICH

W.W.B.W.C. PO Box 68

Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

MPLE NO	OBS Well #1, 9:35p	ANALYSIS	RESULTS	M:3L 2	UNITS	ANALYSTS
70507	()BS Well #1, 9:35p	Fecal E-Coli	5.2	2	CFU/100ml	Valley Labs
10301		Approximately 1000		Taretta de la Proposition de la Prop		
-		The state of the s				
		TOTAL TOTAL PROPERTY AND DESCRIPTION OF THE PARTY.	The second secon			Market Anna Carlotte Control of the
and through the section	Na section of the sec		NAME OF THE OWNER OW			
			Columbia (Columbia)			A STATE OF THE PARTY OF THE PAR
***	A ACCRECATE OF THE PARTY OF THE	The second section of the sect	A STATE OF THE PARTY OF THE PAR		AND DESCRIPTION OF THE PARTY OF	
-		The state of the s				
-34/100000000000		A STATE OF THE STA	Married State of the State of t			AND DESCRIPTION OF THE PARTY OF
-	A. CONSTRUCTOR OF PROPERTY AND ADDRESS OF THE PROPERTY OF THE	The state of the s			NAME OF THE OWNER OWNER OF THE OWNER OWNE	
	the same of the sa	- And Annual Control of the Control			CANADA I CANADA	
-					termination and the same	······································
					A.P. Charles and Company of Confession	-
					A THE RESERVE THE PERSON NAMED IN COLUMN	-1-1-4-4-4-4-4-4-4-4-4-4-4-4-4-4-4-4-4-
		CONTRACTOR OF THE REAL PROPERTY OF THE PERSON OF THE PERSO	COLUMN TO THE REAL PROPERTY.			
			4-4-1-4-1-4-1-4-1-4-1-4-1-4-1-4-1-4-1-4	-		
-	Agranger,				_ and a second	
	-	NAME AND POST OFFICE ADDRESS OF THE PARTY OF	***************************************		A	
a manuscravite "			A STREET, STRE	Comments of the Comments of th	ENTERNANCE OF THE PARTY OF THE	
ner war da even		CALL CONTRACTOR OF STREET			CONTRACTOR OF THE PROPERTY OF	
- Patient community		·			AND STATE OF THE PERSON OF PERSON	
Marianos	······································		1000			
-	***************************************	**************************************	AND THE RESERVE OF THE PERSON			
	Control of the Contro		The same of the sa			
	Annual Company of the last of	THE PERSON NAMED IN COLUMN TWO IS NOT THE OWNER.	Manager of Property and the State of St	No.		

<(0.001); indicates the analyte was not detected at or above the concentration indicated.

ND: None Detected

* PQL «Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during fouring laboratory operating conditions MDL. Method Detection Limit

Please thack out our new Wah Site at http://www.huotesting.com

Dr. Hagene Kuo, Quality Assurance Coordinator

05-04-04

Date

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free http://www.kuotesting.com e-mail: kuotest@atnet.net

> DATE COLLECTED 4/30/2004

DATE RECEVED

DATE REPURTED

SEND REPORT TO 4/30/2004

5/4/2004

SYSTEM CONTROLER

W.W.B.W.C. PO Box 68

Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Aun:

CUSTOMER	ANALYSIS	RESULTS	M:31	UNITS	ANALYSTS
OBS Well #1, 6:40a	Fecal E-Coli	9.7	2	CFU/100ml	Valley Labs
		ALL ALL AND AL		DOG SAMESHOW TO SAME	
CONTRACTOR OF THE PERSONS ASSESSMENT		Aller Aller	CHANGE OF THE COURSE OF		
A CONTRACTOR OF STREET, STREET			eastern of the state of the sta		ALIMAN DAY
and decreased an inches of the second decreased and the second decrease			Manual and and a second		
The state of the s					
			-		
		TO STATE OF THE PARTY OF THE PA			
	100	THE STREET, WHICH STREET, STRE	-		
- Commission of Contract of Co					
ALLENSON I ALERTHANIA TO ALERTA OF THE STATE			- Mine for designation a service		
		The state of the s	mayor, largery when the server		
		and the second of the second of the second of			
			ALCO AND A STREET AND A STREET AND A STREET		Commence of the second second
		water or your and a second			
		Mary and the same of the same	-		A DESCRIPTION OF THE PERSONS
		r tamer some one of the same o	COLUMN TO THE RESERVE		
	AND DESCRIPTION OF THE PROPERTY OF THE PROPERT	Market and the second s	-		
		AND ACCOUNT OF THE PARTY OF THE			-
	Control of the Contro	A RESIDENCE OF THE PARTY OF THE			
		- A CONSTRUCTION AND A PARTY OF THE PARTY OF			
	ALCOHOL MANAGEMENT OF A CONTRACT OF A CONTRA	Charles and the Control of the Contr		M	NAME OF TAXABLE PARTY.
	and the second second				April 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
	The same way and the same way	· · · · · · · · · · · · · · · · · · ·		NAMES OF THE OWNER, WHEN PERSONS ASSESSED.	
	- Company - Architecture - Transport				
	THE PARTY OF THE P				V
				-	-
	OBS Well #1, 6:40a	OBS Well #1, 6:40a Fecal E-Coli	OBS Well #1, 6:40a Fecal E-Coli 9.7	OBS Well#1, 6:40a Fecal E-Coli 9.7 2	SAPPL 20 OBS Well #1, 6:40a Fecal E-Coli 9.7 2 CFU/100ml

4(0.001): indicates the analyte was not detected at or above the concentration indicated.

ND: None Desected

mg/L: indicates milligrams per litre

* PQL=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

MDL: Method Detection Limit

Please check out our new yet Site at http://www.kuotesting.com

Dr. Evgene Kuo, Quality Assurance Coordinator

05-04-04

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free Web Site: http://www.kuotesting.com c-mail: kuotest@atnet.net

> DATE COLLECTED 4/29/2004

DATE RECEIVED

DATE REPORTED

SEND REPORT TO 4/30/2004

Bob Bower

5/4/2004

SYSTEM CUSTOMER

W.W.B.W.C. PO Box 68

Project Name:

Milton Freewater OR 97862

PO Box 68 Milton Freewater OR

97862

Aiin:

SAMPLE NO. CUSTOMER UNITS ANALYSTS **克福森LY茅**部 Valley Labs CFU/100ml 3.0 OBS Well #3. 9:00p Fecal E-Coli 70509

<(0.001); indicates the analyte was not delected at or above the concentration indicated

Dr. Eugene Kuo, Quality Assurance Coordinator

ND. None Detected top/L. Indicates milligrams per large top/L. Indicates milligrams per large repair to the lowest level that can be achieved within specified firmts of precision and accuracy during routing taboratory operating conditions.

MDL: Mothod Detection Limit Please check true our new Not Site at http://www.knotesting.com

337 South 1st Avenue, Othello, WA 99344 (509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free

Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

STEM / CUETOMER	9ATE COLLECTED 4/30/2004	SENO REF		0/2004	5/4/2004
W.W.B.W.C. PO Box 68 Milton Freewater OR 97862 Project Name:		Bob Bower PO Box 68 Milton Freewater OR 97862 Attn:			
AMPLE NO CUSTOMFR SAMPLE NO	AM/L/YS/9	RESULTS	MDL	UNITS CHI/100ml	ANALYSTS Valley Labs
70510 OBS Well#3, 6:30a	Fecal H-Coli	5.2	Z	Cru/100m	Valley Edgs

5(0.001): indicates the analyte was not detected at or above the concentration indicated.

ND. None Detected the None Detection Limit to the lowest level that can be achieved within specified limits of precision and accuracy during countries aboratory operating conditions the None Detection Limit Please theek and our new Year Site at http://www.kuotesting.com

Dr. Eugene Kuo, Quality Assurance Coordinator

Kuo Testing Labs, Inc. 337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

		DATE RECEIVED	DATE REPORTED
DATE COLLECT 4/29/2004	÷ù	SEND REPORT TO 4/30/2004	5/4/2004
SYSTEM: CUSTOMER			
W.W.B.W.C. PO Box 68 Milton Freewater OR 97862		Bob Bower PO Box 68 Milton Freewater OR Attn:	97862

BAMPLL NO	CHISTORIES SEMPLE NO FC-1, Prog	ANAL 753	RESULT6	- Mil.	UNITS	ANALYST
	SAMPLE PRO	Fecal Coliform	12.2	2	CFU/100ml	Valley Labs
70498	FC-1, Prog	Pecal Comon				
	-	CONTRACTOR OF THE PROPERTY OF	-			
			and the state of t			Walter Walter
			NAME AND ADDRESS OF THE OWNER, TH			
	and the same of the same of		The state of the s			
			THE RESERVE THE PERSON NAMED IN COLUMN TWO IS NOT THE OWNER.			
		District of the Control of the Contr	THE RESERVE TO BE A STREET TO BE A	-	and a summer of the summer	
			-A		CANADA CA	
			The second secon		The Commence of the Commence o	
			and the second s			The second secon
			The formation of the second section is a second sec			,,
						The second secon
			CHARLES OF THE PERSON OF THE P			Commission of the Commission o
-	The state of the s					-
				-	and the second s	COLUMN TO SERVICE AND ADDRESS OF THE PERSON
amena cy trólymany				Constitution of the Assession	Address of the second	CONTRACTOR OF THE PERSON NAMED IN COLUMN
-	Section of the sectio					AND A PROPERTY OF THE PERSON NAMED AND ADDRESS OF THE PERSON N
-	Action and the State of th					CALL STREET, CALL
-	A CONTRACTOR OF THE PARTY OF TH	Mary 11				
-					THE RESERVE OF THE PERSON NAMED IN COLUMN TWO	
	The state of the s				A PROPERTY AND DESCRIPTION OF THE PERSON OF	Mary approximation of the Particular States of
	TO SHARE THE PERSON OF THE PER				Mark School of the Control of the Co	A STATE OF THE PERSON NAMED IN COLUMN 2 IS NOT THE PERSON NAMED IN
		and the second s	THE REAL PROPERTY AND PERSONS ASSESSMENT OF THE PERSONS ASSESSMENT OF			AND DESCRIPTION OF THE PERSON NAMED IN COLUMN TWO
		A CONTRACTOR OF THE PARTY OF TH				201-79-00-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1-1
		The state of the s	to the commence with the property of the second			
-	-	The second secon	AND THE RESERVE OF THE PARTY OF	ACTUAL VIOLENCE AND ADDRESS.		The same of the sa
-						
	and American Commission	A		Daniel Cryman passas - was feld		
CONTRACTOR OF THE PARTY OF THE		A STATE OF THE PARTY OF THE PAR			AND ASSESSMENT AND ASSESSMENT OF THE PARTY O	

<(0.001), indicates the analyte was not detected at or above the concentration indicated. ND: None Detected

mg/L Indicates milligrams per lare

* POL-Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

MOL Method Detection Limit

Plears check out our new W. Site at http://www.kuolesting.com

Dr. Fugene Kuo, Quality Assurance Coordinator

05-04-04

Kuo Testing Labs, Inc. 337 South 1st Avenuc, Othello, WA 99344

337 South 1st Avenuc, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free
Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

	DATE SPILLEDTED		received	DATE REPORTED 5/4/2004
STEM / CUSSOMER	4/29/2004	SEND REPORT TO 4/	30/2004	3/4/2001
W.W.B.W.C. PO Box 68 Milton Freewater OR Project Name:	97862	Bob Bower PO Box 68 Milton Freewate Attn:	r OR 9	7862
MANE NO CONTONALL	TOTALYSUS .	RESULTS MOL	CFU/100ml	Valley Labs
70499 FC-2. Winesap Rd.	Pecal E-Coli		CONTRACTOR OF THE PROPERTY OF	
	STORE		named to the supplementary of	
		A TOTAL MANAGEMENT OF THE PARTY		
			AND AND DESCRIPTION OF THE PERSON OF THE PER	
		And the second s	- Andrew Control of the Control of t	
	Annual An			
AND THE REAL PROPERTY AND THE PROPERTY A				
ND: Name Detected	tooled at or above the concentration indicate			. Links are
e t el		and timits of american and occurred during routing	e laboratory aperating	conditions
mgL:Indicates milligrams per litre POL-Practical Quantitation Limit is the l MDL: Method Detection Limit Please check out my the W. Site at hi		and many or precious as		-04-04

Dr. Eugene Kuo, Quality Assurance Coordinator

Kuo Testing Labs, Inc. 337 South 1st Avenue, Othello, WA 99344

337 South 1st Avenue, Othello, WA 99344
(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free
Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

		0ATE COLLECTED 4/29/2004		SEND REPO		RECEIVED 80/2004	DATE REPORTED 5/4/2004
W.W.B.W PO Box 68 Milton Fre Project Na	.C. cwater OR	97862		Bob B PO Bo Milton Attn:	x 68 Freewater	OR 97	7862
5.47	STOMER WPLE NO	ANALYSIS		RESULTS	MDI.	UNITS CFU/100ml	ANALYSTS Valley Labs
	-3, Well GW-40	Fecal E-Coli		<		CF1//100mi	Valley Caus
National Advantage of the Control of		un annual					
	A CONTRACTOR OF THE PROPERTY O	A STATE OF THE STA			PARTITION OF THE PARTIT		
	AND DESCRIPTION OF THE PROPERTY OF THE PROPERT			**************************************			
						THE PARTY OF THE P	AND DESCRIPTION OF THE OWNER, OR THE OWNER, OR THE OWNER, OR THE OWNER,
							,
							- The state of the
							AND THE PERSON NAMED IN COLUMN 1
	The second secon				decimal property of the Paris		
		And the second s		A STATE OF THE PARTY OF THE PAR	Approximation to the second		
ND: None Detect	lud	steered at or above the concentrat			1.1.	I be reton an agresing	on/hitians
POL=Practical C	Duantitician Limit is the l	owast level that can be achieved	willim specified I	mind of precision and accura	acting tourne	secondary operating	

Kuo Testing Labs, Inc.
337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

STEM FOUSTONIER	2/29/2004	SEND RF	PORT TO 4/3	0/2004	5/4/2004
W.W.B.W.C. PO Box 68 Milton Frecwater OR Project Name:	97862	POB	Bower ox 68 on Freewater	OR 9	7862
MPILNO CUSTOMER SAMPLE NO	ANALYSIS	RESULTO	MDL	UNITS	ANALYSTS
70502 FC-5, OBS Well #1	Fecal E-Coli	11.0	2	CFU/100ml	Valley Labs
		-		A CONTRACTOR OF THE CONTRACTOR	
			2		
	-	A Commission of the Commission			
					Particular and the second second
				A CONTRACTOR OF THE PARTY OF TH	
				- Agenmunaana	
	APPENDING THE PROPERTY OF THE			-	
D. None Detected	lected at or above the concentration indicat		uracy during routine l	laboratory operating	conditions
DL: Method Detection Limit Hease check out sur now Web Site at ht					-04-04
Dr. Willenc Kuo Quality	Assurance Coordinator			Date	Control of the Contro

Kuo Testing Labs, Inc.
337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

		The second second second second second		DATER	EGETVED	DATE REPORTED
		4/29/2004	SENITA RE	EPORT TO 4/3(0/2004	5/4/2004
W.W.B.W PO Box 6 Milton Fr	V.C.	97862	PO E Milto	Bower Box 68 on Freewater	OR S	07862
Project N	lame:		\ \frac{\Lambdattr}{\lambdattr}	1:		
	LSTOMER	ANALYSIS	BC SULTG	MCH	UNITS	ANALYSTS
70501	AMPLE NO FC-4b, OBS Well #3	Fecal E-Coli	3.1	2	CFU/100ml	Valley Labs

<0.001) indicates the analyte was not detected at or above the concentration indicated.

mg/Lindicates milligrams per litre

* PQL-Practical Quantitation Limit is the lowest level that can be achieved within specified limits of practices and accuracy during toutine laboratory operating conditions

* PQL-Practical Quantitation Limit

* Multiple Detection Limit

Please check out par negotieh Site at http://www.kuotesting.com

Dr. Higene Kuo, Quality Assurance Coordinator

337 South 1st Avenue Othello, WA 99344 509-488-0112

Fax: 509-488-0118 or 509-488-6865



Date: 5/4/04	Fax No:	
To: Bob Bower	Fax No:	
From: Mary		
Message:		
The state of the s		
And the second s		
to different constraints and applications are supplied in the constraints of the constrai	The second secon	
the second secon	The second secon	
personal and the second		
The second secon	Number of Pages to Follow:	Pages

Return Fax No: 509-488-0118 or 509-488-6865

If Problems with Transmission, Call 509-488-0112

337 South 1st Avenue Othello, WA 99344 (509)488-0112 (800)328-0112 Fax (509)488-0118 Web Site http://www.kuotesting.com

INORGANIC CHEMICALS (IOCS) REPORT FOR NITRATES

Type of System: Individual

Water System/Customer Name:

W.W.B.W.C.

System Address PO Box 68

CITY Milton Freewater

County Umatilla

ZIP 97362

Sample Location: Intake

Date Collected: 4/13/2004

Date Received: 4/14/2004

Date Analyzed: 4/15/2004

PWS ID No.:41

Laboratory No.:WA060-70290

Date Reported: 4/15/2004

ichomica eva compentica o niva e niva e nimenimente

PO Box 68

PO Box 68

Milton Freewater

OR 97862

Milton Freewater

OR 97862

Contaminant - Method	Code	MCL mg/L	Analyst	Analysis mg/L
Nitrate (NO3- N)SM4500-NO3-D Nitrite (NO2-N)SM4500-NO2-B Nitrite + Nitrate	1040 1041 10387	10. 1.0 10.	Qian	ND

NOTES:

MCL (Maximum Contaminant Level): if the contaminant amount exceeds the MCL, immediately contact your regional DOH office.

NA (Not Analyzed): in the results column indicates this compound was not included in the current analysis.

ND (Not Detected): in the results column indicates this compound was analyzed and not detected at a level greater than or equal to the value shown.

mg/L: indicates milligrams per liter or parts per million.

<0.100: indicates the compound was detected but at a value below the concentration indicated.


Comments: See our new Web Site at http://www.kuotesting.com

Dr. Eugene Buo, Quality/Assurance Coordinator

April 15, 2004 Date

337 South 1st Avenue Othello, WA 99344 509-488-0112

Fax: 509-488-0118 or 509-488-6865



Return Fax No: 509-488-0118 or 509-488-6865

If Problems with Transmission, Call 509-488-0112



Agricultural

Industrial

Environmental

KUO TESTING LABS, INC

337 South 1st, Othello, Washington 99344

Tel: (509) 488-0112

Fax: (509) 488-0118

Dear Bob,

Sorry it has taken so long to get you this list, but we were waiting for the other lab, and they just faxed it to me today. This is a list of what the lab can do, the method and the price. Pricing assumes standard ten to fourteen working day turnaround time.

Analysis	Method	Price
Trifloxystrobin, Water or Soil	Modified EPA 8081	\$164.70/Ea.
Triadimefon and Triflumazole, Water or Soil	Modified EPA 8270	\$191.70/Ea.
Imidicloprid, Water only	Modified EPA 632	\$182.25/Ea.
Spinosad, Water only	Manufacturer's Method	\$182.25/Ea.

If you have any questions regarding this price quote, please do not hesitate to call.

Sincerely,

Renay Jorgensen

oct 28 '03 10:40AM KUO TESTING LABSThis analysis is fore water birly.

The Price is \$815.40.



Page 1 of 1

HERBICIDES IN DRINKING WATER

Client Name: KUO Testing Labs Inc

337 S 1st

Othello, WA 99344

System Name:

System ID Number:

DOH Source Number:

Multiple Sources:

Sample Type: Sample Purpose:

Sample Location:

County:

Reference Number:

Project:

Field ID:

Lab Number: .

Date Collected:

Date Extracted:

Date Analyzed:

Report Date:

Analyst:

Supervisor

OH#	COMPOUNDS	RESULTS	Units	SRL	Trigger	MCL	COMMENT	
	EPA Regulated		AND SOME STREET, ST. T.			1		
37	2.4 - D	ND	ug/L	0.2	0.2	. 70		
38	2.4,5 - TP (SILVEX)	ND	ug/L	0,4	0.4	50		
134	PENTACHLOROPHENOL	ND	ug/L	0.08	0.08	. 1		
137	DALAPON	ND	ug/L	2	2	200		
139	DINOSEB	ND	, navr	0.4	0.4	7		
140	PICLORAM	ND	· ug/L	0.2	0.2	500		
	EPA Unregulated		3	1				
138	DICAMBA	ND	· ug/L	0.2	0.2	3		
	State Unregulated	1	1				E	
135	2,4 DB	ND	ug/L	1	1.0	1		
136	2,4,5 T	ND	· ug/L	0.4	0.4	3		
220	BENTAZON	ND	ug/L	0.5	0.5	3		
221	DICHLORPROP	ND	' ug/L	0.5	0.5			
223	ACTIFLORFIN	ND	: ug/L	2	2.0			
225	DACTHAL (DCPA)	ND	: ug/L	0.1	0.1	d a	-	
226	13.5 - DICHLOROBENZOIC ACID	ND	419/4	0.5	0.5		181	
			j				4	
							3	
	19		7.		1			
	*						1	
	*		1					
			1					
				1				
	* Part of the second			- 1				
	* 85-11	*	4		14			
			1		,			
						1	4	
			1	1	7:	M.	183	
			1		3		10	

^{*}An amount of NO* indicates hat the compound was not detected above the Leb's Method Disposition Limit - NiDL,

An amount of NO indicates hat the compound was not detected above the Leb's Method Disposition Limit - NiDL,

*A stark MCL or SAL value indicates a layor is not currently established.

*A stark MCL or SAL value indicates a layor is not currently established.

**If a compound is delected a or - to the State Reporting Level, SRL, specified increased monitoring frequencies may occur per DOH.

**If a compound is delected a or - to the State Reporting Level, SRL, specified increased monitoring frequencies may occur per DOH.

**If a compound is delected a or - to the State Reporting Level, SRL, specified increased monitoring frequencies may occur per DOH.

**If a compound consentration is greater than zero.

**If a compound consentration is greater than zero.

**If a compound consentration is greater than zero.



Page 1 of 1

CARBAMATES IN DRINKING WATER

Client Name: KUO Testing Labs Inc

337 S 1st

Othello, WA 99344

System Name:

System ID Number:

DOH Source Number:

Multiple Sources:

Sample Type: . Sample Purposa:

Sample Location:

County:

Reference Number: 1

Project:

Field ID:

Lab Number:

Date Collected:

Date Extracted:

Date Analyzed:

Report Date:

Analyst:

Supervisor:

EPA Method 531.1 For State Drinking Water Compliance

DOH#	COMPOUNDS	RESULTS	Units	SRL	Trigger	MCL	COMMENT	
	EPA Regulated	PORCHASTA (AND A PERFORMANCA PA	and the ball market and an array and a second	**************************************	(1421-144 1875-19-141-14-14-14-14-14-14-14-14-14-14-14-14			
146	CARBOFURAN	ND	ug/L	1.8	1.8	40		
148	OXYMAL.	ND	ugh	4	4.0	200		
	EPA Unregulated							
141		ND	ug/L	2	2.0			
142	ALDICARE	ND	ug/L	1	1.0			
143	ALDICARS SULFONE	ND	, µg/l.,	1.6	1.6			
144	ALDICARB SULFÓXIDE	ND	ug/L	1	1.0			
145	:CARBARYL	ND	ug/L	2	2.0			
147	METHOMYL	ND	ug/L	1	4.0			
	State Unregulated - Other							
326		ND	ug/L	1				
327	METHICCARB	ND	ug/L	4				

^{*}An amount of "ND" indicates that the compound was not delected above the Lab's Mehind Delection Cimi * MDL.

**Maximum Contembrant Level, maximum permissible level of a contembrant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unrequisted compounds.

A blank NCL or SAL value indicates a level is not currently established.

**If a compound is retacted a portion to the State Reporting Level, SRL, specified increased monitoring inequancies may occur per DOH.

***Mehind Delegidan Limit to line lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than sero.

J - Estimated value.

Total pool 815. 40





SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

Client Name: KUO Testing Labs Inc.

337 S 1st

Othelio, WA 99344

System Name: ---System ID Number:

DOH Source Number: 1

Multiple Sources:

Sample Type:

Sample Purpose:

Sample Location: County:

EPA Method 508.1 For State Drinking Water Compliance

Reference Number:

Project:

Field iD:

Lab Number:

Date Collected:

Date Extracted: . .

Date Analyzed:

Report Date:

Analyst:

Supervisor:

DOH# COMPOUNDS RESULTS Units Trigger MCL COMMENT PCBs/Toxaphene 2 3 36 TOXAPHENS ND 2 ug/L 173 AROCLOR 1221 ND ug/L 0.5 20 : ND 174 AROCLOR 1232 0.1 0.5 ug/L 175 AROCLOR 1242 ND 0.1 0.3 176 AROCLOR 1248 ND 0.1 0.1 Vg/L 177 AROCLOR 1254 ND 0.1 0.1 ug/L 178 AROGLOR 1260 ND 0.1 0.2 ug/L 180 AROGLOR 1016 ND 0.1 0.1 ug/L

*- An amount of "NO" indicates that the compound was not detected above the Lab's Method Detector Limit - MOL

FORM: SOC87

P.5



Reference Number: Lab Number: Report Date: Page 2 of 2

SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

DOH#	COMPOUNDS	RESULTS	Units	SRL	Trigger	MCL	COMMENT	
	CYANAZINE	NO	ug/L	0.2	1 0.2			
239	MALATHION	ND	ug/L	. 0.2	0.2		+	
240	PARATHION	ND	ug/L	0.2	0.2		**************************************	
243	TRIFLURALIN	· ND	ug/L	0.2	0.2			
	- PAHs				4	1		
96	NAFTHALENE	ND	ug/L	, 0.1	0.1	14		
154	FLUORENE	ND	ug/L	0.2	0.2			
244	ACENAPHTHYLENE	ND .	ug/L	0.2	0.2			
245	ACENAPHTHENE	ND	ug/L	0.2	0.2			
246	ANTHRACENE	ND	ug/L	0.2	0.2			
247	BENZ(A)ANTHRACENE	· ND	ug/L	0.1	0.1			
248	BENZO(S)FLUORANTHENS	ND	ug/L	0.2	0.2			
249	BENZO(G.H.I)PERYLENE	ND	ug/L	0.2	: 0.2			
250	BENZO(K)FLUORANTHENE	ND	ug/L	0.2	0.2	N		
251	CHRYSENE	ND .	ug/L	0.2	0.2			
252	DIBENZO(A.H)ANTHRACENE	ND	ug/L	0.2	0.2			
253	FLUORANTHENE	ND	ug/L	0.2	0.2			
255	INDENO(1,2,3-CD)PYRENE	, ND	ug/L	0.2	0.2			
256	PHENANTHRENE	ND	ug/L	0.2	0.2			
257	PYRENE	ND	ug/L	0.2	0.2			
	- Phthalates		157,000		No.			
258	BENZYL BUTYL PHTHALATE	ND	ug/L	0.6	0.6			
259	DI-N-BUTYL PHTHALATE	ND	ug/L	0.6	0.6			
260	DIETHYL PHTHALATE	ND	ug/L	0.6	0.6			
261	DIMETHYL PHTHALATE	. ND	ug/L	0.6	0.8			

^{**} An amount of TND* indicates that the compound was not detected above the Laby Method Detection Limit - MDL.

**- Maximum Constminant Lavel, maximum permissible level of a contaminant in water established by \$PA. NPOWR. State Asvisory Level (SAL) for Unregulated compounds.

A Mark MCL or SAL value indicated a level is not currently established.

**- If a compound is datasted by or a to the State Reporting Lavel, \$PAL, specified increased monitoring inducations may occur per DOH.

***- Natived Detection Limit is the leaf a minimum concentration is greater than zero.

J - Estimated value.



Page 1 of 2

SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

Client Name: KUO Testing Labs Inc

337 S 1st

Othello, WA 99344

System Name:

System ID Number:

DOH Source Number:

Multiple Sources:

Sample Type:

Sample Purpose:

Sample Location:

County:

Reference Number:

Project:

Field ID:

Lab Number

Date Collected:

Date Extracted:

Date Analyzed

Report Date:

Analyst:

Supervisor

対HC	COMPOUNDS	RESULTS	Units	SRL	Trigger	MCL	COMMENT	
	EPA Regulated		· · · · · · · · · · · · · · · · · · ·		COLUMN TO STATE OF THE STATE OF	-	, _ 4111112111	
33	ENDRIN	ND	ug/L	0.02	0.02	2		
34	LINDANE (BHC - GAMMA)	. ND	ug/L	0.04	0.04	0.2		
35	METHOXYOHLOR	ND	ug/L	0.2	0.2	40		
117	ALACHLOR	ND	ug/L	0.4	0.4	2		
119	ATRAZINE	ND	ug/L	0.2	0.2	3		
120	BENZO(A)PYRENE	ND	ug/L	0.04	0.04	0.2		
122	CHLORDANE, TECHNICAL	ND	ug/L	0.4	0.4	2		
124	DI(ETHYLHEXYL)-ADIPATE	ND	ug/L	1.3	1.3	400		
125	DICETHYLHEXYLLAPHTHALATE	ND	ug/L	1.3	1.3	6		
	HEPTACHLOR	ND	yg/L	0.08	0.08	0.4		
127	HEPTACHLOR EPOXIDE (A&B)	ND	ug/L	0.04	0.04	0.2		
128	HEXACHLOROBENZENE	ND	ug/L	0.2	0.2	1		
129	HEXACHLOROCYCLO-PENTADIENE	ND	ug/L	0.2	0.2	50		
133	BIMAZINE	ND	ug/L	0.15	0.15	4		
	EPA Unregulated		ř.					
118	ALDRIN	ND	: ug/L	0.2	0.2			
121	BUTACHLOR	ND	ug/L	0.4	0.4			
123	DELDRIN	ND	ug/L	0.2	0.2			
130	METOLACHLOR	ND	ug/L	1.0	1.0			
131	METRIBUZIN	: ND	ug/L	0.2	0.2			
132	PROPACHLOR	ND	ug/L	0.2	0.2			
	State Unregulated - Other		31					
	BROMACIL	ND	ug/L	0.2	0.2			
	PROMETON	ND	ug/L	0.2	0.2			
190	TERBAÇIL	ND	ug/L	0.2	0.2			
.202	DIAZINON	ND	ug/L	0.2	0.2	6		
208	EPTO	ND	ug/L	0.3	0.3		E E	
232	4,4-DDD	: ND	ug/L	0.2	0.2			
233	4,4-DDE	ND	ug/L	0.2	0.2			
234	4,4-DDT	ND	ug/L	0.2	0.2	1		



FORM: SOCOT

An Smount of ND Indicates that the compound was not detected above the Lab's Method Detection Limit - MpC.

**- Maximum Confernment Level, maximum permissible level of a contaminant in water established by S.P.A., NPDWR. State Advisory Level (SAL) for Unrequisted compounds.

A blank MCL or SAL value indicates a level is not currently established.

**- It is compound to detected a or a to the State Reporting Level, SRL, specified increased manifolding frequencies may occur per DOH.

***- Method Detection Limit is the lab's minimum concentration is compound can be measured and reported with SG% confidence that the compound concentration is grower than zero.

J. Sathrated value.

337 South 1st Avenue, Othello, WA 99344 (509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

YSTEM/CUSTOMER	3/10/2004	SEND	REFORT TO	3/11/2004	DATE REPORTED 4/9/2004
W.W.B.W.C. PO Box 68 Milton Freewater OR 9' Project Name:	7862	PO	b Bower Box 68 ton Freew tn:	ater OR	97862
ASSET NO SERVICE SAMPLE NO 69717 Well #2-Recharge Project	SOC/Synthetic Organic Co	RCSULTS	NOL	UNITS	ANALYSTS.
	Nell #12	Report	THE PERSON NAMED IN COLUMN	mg/L	Edge Analytical
			- Antonio		
1400					

lyte was not detected at or above the concentration indicated.

ND. None Detected mg/L Indicates milligrams per litro

right indicates managering for use
PQL=Fractices Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

April 9, 2004

APR-08-2004 15:46



11525 Knudson Rd. Burlington, WA 98233 (800) 755-3205 (360) 757-1400 - FAX (360) 767-1402

Page 1 of 1

SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

Client Name: KUO Testing Labs Inc.

337 \$ 1st

Othello, WA 99344

System Name: Bob Bower (WWBWC)

System ID Number: DOH Source Number:

> Multiple Sources: Sample Type: B

Sample Purpose: B Sample Location: well #2-recharge project (observation well)

County: Umatilla

Reference Number: 04-1650

Project 69717

Field ID: 69717

Lab Number: 04603328

Date Collected: 3/18/2004 Date Extracted: 508_040331

Date Analyzed: 4/2/2004 Report Date: 4/5/2004 Analysi: CMH

Supervisor

	Walter Waster	EPA Meth	od 508.1 F	Of State Di	Invited and	ter Complia		0010/51/7	
OH#	COMPOUNDS	R	ESULTS	Units	SRL	Trigger	MCL	COMMENT	- Committy Committee of States
	PCBs/Toxaphene		Married Co.			2	3	1	
36	TOXAPHENE		Ð	MB/E	20	20			
	AROCLOR 1221		D	ugiL		0.5		1.	
	AROCLOR 1232	0	Ď	ug/L	0.5	0.3	i		
	AROCLOR 1242	1	D	ugit	0.5	0.1			
	AROCLOR 1248	10	ID	ug/L	0.1	0.1	1		
	AROCLOR 1254	1 2	ID	ug/L	0.1	0.2	1		V-
	AROCLOR 1260	1.3	(D	ug/L	0.2				
	AROCLOR 1016	1 7	(D)	ug/L	0.1	0.1	1	i -	
100		1		1			1	1	
	Į.	1		i		1	· ·	1	
	Ĭ .	1				i			
35	1 -	-			i				
			=	1	1	1	*		
				1	1	į			i
	1				1	1			1
		ĺ			1		1	1.	1
	1	-1		1	- 1		1		
	1				. }				
	Î	1			1				
					1	19			1
	1			1	1				
				1			1		4
				1		i		j.	4
				1	ì	1	8		
					i		1.250		
	1	5	P.				1		
	·		1	1	1	i			1
			4						-
400	of THOY Indicates that the correction of Constrained Lovel, reserved before	into not descript him.	the Litt's Mest Co	Consession Limit -	ndl York sine asy	say Level (SAL) for	Urregulated com	portis	4 1
· ALL STEWNS · ·	Consentinent Level, Inspires a level to	while lawes of a common mor customing especially	ORY UNDER AN AMERICAN STORM	and the same of	ncies may count to	R DOH		must for five 2000.	
A DUNK	Consistent Level, masurum permas ACL of SAL value indicates a level to supple to dissessed > or > to the State R peticipien Links at the Sat's minister of	legating Lands, SPL. 1	pacified increases and each do member	and study and under an	en 96% comidano	that the compound	CONCREDENCE IS		
" Magrad	Distributed of travers of him own a	Charles As several a provider.	TOTAL TOTAL						1
- Esterousid									1

APR-08-2004 15:46



Reference Number: 04-1650

Page 2 of 2

Lab Number: 04603328 Report Date: 4/2/2004

SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

OH#	COMPOUNDS	RESULTS	Units	SRL	Trigger	MCL	COMMENT	
233	4,4-DOE	ND -	ug/L	0.2	0.2	Maria de la Companya		Description we have drawn
234	4,4-007	ND	ug/L	0.2	0.2		!	à
236	CYANAZINE	ND	ug/L	0.2	0.2			1
	MALATHION	ND	ug/L	0.2	0.2		1	- 1
240	PARATHION	ND	ug/L	0.2	0.2	1.76		. 1
	TRUFLURALIN	ND	ug/L	0.2	0.2			
	- PAHs	• 3177.5	1_					1
96	NAPTHALENE	ND	ug/L	0.1	0.1		1	
154	FLUORENE	ND	ug/L	0.2	0.2			1
244	IACENAPHTHYLENE	. ND	ugiL	0.2	0.2		i	J
245	ACENAPHTHENE	ND	ug/L	0.2	0.2			1
	ANTHRACENE	ND	ug/L	0.2	0.2			1
	BENZIA)ANTHPACENE	ND	ug/L	0.1	0.1			.*
	BENZO(5)FLUORANTHENE	ND	ug/L	0.2	0.2			
	BENZOIG.H.IPERYLENE	ND	ug/L	0.2	0.2			
	BENZOKYLUGRANTHENE	ND	ug/L	: 0.2	0.2		1	
	CHRYSENE	ND	ug/L	0.2	0.2			
(2) (1) (1) (1) (1) (1) (1) (1) (1) (1) (1	DISENZO(A.H)ANTHRACENE	ND	ug/L	0.2	0.2	*		1 .
	FLUORANTHENE	ND	ug/L	0.2	0.2			
	INDENO(1,2,3-CD)PYRENE	ND	ug/L	0.2	0.2	1	Š	
	PHENANTHRENE	מא	ug/L	0.2	0.2		7	
		ND	na/r	0.2	0.2			
	PYRENE - Phthalates	No	EQ.L	9.2	V.E		i	
ACCUPANCE OF	BENZYL BUTYL PHTHALATE	ND	ug/L	0.8	0.6	:		
	DHN-BUTYL PHTHALATE	פא	ug/L	0.6	0.6	6	f:	1
		ND	ug/L	0.6	0.6	E 6	*	-
The second second	DIETHYL PHTHALATE	ND	ug/L	0.5	0.6		,	
201	DMETHYL PHTHALATE	NU	Ug/L	0,0	0.5		1	
1					+			
				1				
				Í				
i						i.		
			İ					
			1					
							1	
1			3					
Ē					1			
			1	100	1	30		1
- 1						1	1	
11 8		1						
	* * *							
						:		

⁻ on amount of "NO" indicates that the companies were not educated above the Lars Newton Deserting Lynn - MDL.

"Liability of Crisminities Level, finishment primagates intel of a commitment in water establishes by EPA, NPCMR. State Advisory Level (Sal.) for Unregulated compositeds.

A blank NDL or Sal. value indicates a level is not currently established.

""It is confequent is deserted in at a tell the State Reporting Level, ERL, isosofied indresses represent representations may use of particular or at a tell the State Reporting Level, ERL, secrified indresses represent the State
APR-08-2004 15:45



11525 Knudeon Rd. Burlington, WA 98253 (800) 755-9295 (360) 757-1400 - FAX (360) 757-1402

HERBICIDES IN DRINKING WATER

Client Name: KUO Testing Labs Inc

337 S 1st

Othello, WA 99344

System Name: Bob Bower (WWBWC)

System ID Number: DOH Source Number: Multiple Sources:

> Sample Type: B Sample Purpose: B

Sample Location: well #2-recharge project (observation well)

County: Umatilla

Reference Number: Q4-1650

Project: 69717

Field ID: 69717

Lab Number: 04603328 Date Collected: 3/18/2004 Date Extracted: 515_040331

Date Analyzed: 4/7/2004 Report Date: 4/8/2004 Analyst CMH

Supervisor:

		Method 515.1 F			toge c		000000		1
DOH#	COMPOUNDS	RESULTS	Units	SRL	Trigger	MCL	COMMENT		-
Marie Walter Street	EPA Regulated				1	**		1	
37	2,4 - 0	ND	ug/L	0.2	0.2	70	1	+	
38	2,4,5 - TP (SILVEX)	ND CIM	ug/L	0.4	0.4	50			1 1
134	PENTACHLOROPHENOL	NO	ug/L	0.08	80.0	1			1
137	DALAPON	NED	ug/L	2	2	200		100	1
139	DINOSEB	ND	; ug/L	0.4	0.4	7		1	1
140	PICLORAM	ND	ug/L	0.2	0.2	500		d :	
	EPA Unregulated			1		1		1	
138	DICAMBA	ND	uga	0.2	0.2	1	1		1 1
	State Unregulated				1	1			1
135	2,4 06	ND	ug/L	1	1.0		:	1	
136	2,4,5 T	ND	ugit	0.4	0.4				
220	BENTAZON	P4D	1.age/L	0.5	0.5	*			
221	DICHLORPROP	ND	ug/L	0.5	0.5	ê.	1		1
223		ND	Ug/L	2	2.0		-3	1	,
225	DACTHAL (DCPA)	ND	ugile	0.1	0.1				
	3.5 - DICHLOROSENZOIC ACID	CM !	ug/L	0.5	0.5	*			
-		i i	1			1			
						;	î		
				1			14		
							i		1
		4.	1			i	1		
					1				1
				1			4		1
						1	Ī		1
							1		
			\$	1		1	1	1 .	
				7				1	9
						1			
	"ALD" local-stree that the control-state was not described			ORDERS IN T			.,	Late And	-7

An underst of "All' indicated that the time compound was not consistent who have been been under expensional been an applicable of \$PA, NPDWR. Since Applicacy Level (EAL) for Unrequisited compounds, "Association Conformation Level, mathemate particular of a contraction of wasternament of the conformation
Synthetic Organic Chemicals (SOC's)

(EPA Methods 515.2, 525.2, 531, 547, 549) Herbicides, Pesticides, Adipate, PAH's, Carbamates, Glyphosate, Paraquat & Diquat

Instructions for Sample Collection

Collection Point

Samples must be collected in the proper number, at the appropriate time and locations, and of the proper volume in order to satisfy the requirements of the Phase II and V Rules. Samples that fulfill these criteria are called compliance monitoring samples. Groundwater and surface water systems should be representative of the source water following treatment (see figure on back of this sheet). Systems that draw water from more than one source and that combine these sources prior to distribution must sample during periods of normal operating conditions. Samples must be collected at the same sampling point each cycle unless conditions make another sampling point more representative. Generally, samples should be taken at the tap on the pipeline before the treated water is sent to the distribution system. Sometimes sampling taps (faucets) are available in the plant laboratory for the water entering the distribution system. If the water system is treating for any organic compounds (i.e. packed tower aeration, granular activated carbon, oxidation, etc.) contact your regional Drinking Water Specialist to locate the proper collection point. You will find the name and telephone number on the back of this sheet.

Bottles must NOT be filled near gasoline cans, gasoline-powered motors, paint cans, lighter fluid, paint strippers, pesticide bottles or exhaust fumes from running engines. Fumes and vapors may contaminate the samples.

SAMPLE COLLECTION

 If water taps are to be used for sampling, all aerators, strainers, and hose attachments need to be removed. Open the tap and allow the system to flush for about ten minutes or until the water temperature has stabilized, Adjust the flow to about the thickness of a pencil. Position the container under the tap and collect the sample. Introduce the water very gently to reduce agitation and to avoid introducing air bubbles. Fill the bottle so that little or no air space will remain in the bottle after the cap is secured.

Collect	one-liter bottle(s) at each collection point for method 525.
Collect	500 ml bottle(s) at each collection point for method 515.2
Collect	100ml bottle(s) at each collection point for method 547
Collect	250ml plastic bottle(s) at each collection point for method 549
Collect	250ml bottle(s) at each collection point for method 531
	Collect Collect

IMPORTANT: Be careful not to touch or otherwise contaminate the inside of the lid or the lip of the bottle during sampling.

- 3. All samples need to be kept <u>cold.</u> If the samples are to be held for a day or longer prior to shipping, place the bottles in a refrigerator. Once samples are ready to be shipped, add a bag of ice to the cooler. Samples must be received at laboratory within four days of sampling.
- 4. Insert the completed sample information form (WSI) into a plastic bag and place in cooler.

If you have any questions, please call KUO Testing Labs, Inc. at 509-488-0112 or 541-922-6435

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free

Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

DATE COLLECTED

DATE RECEIVED

DATE REPORTED

4/13/2004

SEND REPORT TO:

4/14/2004

4/26/2004

SYSTEM / CUSTOMER

W.W.B.W.C. PO Box 68

Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

SAMPLE NO. CUSTOMER

ANALYSIS

RESULTS

ANALYSTS

	SAMPLE NO.		KE20F12	MUL	Grillia.	
0296	SAMPLE NO. Well #1	SOC/Synthetic Organic Co	Report		mg/L	Edge Analytical
_						
						2
_						
-						
			110			

<(0.001):	indicates the anal	vte was not detecte	d at or above	the concentration	indicated.
-----------	--------------------	---------------------	---------------	-------------------	------------

): None Detected

PQL=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

MDL: Method Detection Limit

Please check out our new Waste at http://www.kuotesting.com

04-28-04

Dr. Eugene Kuo, Quality Assurance Coordinator



11525 Knudson Rd.

Burlington, WA 98233

(800) 755-9295

(360) 757-1400 - FAX (360) 757-1402

Page 1 of 2

SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

Client Name: KUO Testing Labs Inc

337 S 1st

System ID Number:

Multiple Sources:

Sample Type: B

Sample Purpose: B

DOH Source Number:

Othello, WA 99344

Reference Number: 04-2367

Project: 70296

Field ID:

Lab Number: 04604660

Date Collected: 4/13/2004 Date Extracted: 525 040419

Date Analyzed: 4/19/2004 Report Date: 4/26/2004

Analyst: CMH

Supervisor:

System Name: WWBWC

Sample Location: Well#1 recharge project

County: Umatilla

#	COMPOUNDS	RESULTS	Units	SRL	Trigger	MCL	COMMENT
	EPA Regulated						
33	ENDRIN	ND	ug/L	0.02	0.02	2	
34	LINDANE (BHC - GAMMA)	ND	ug/L	0.04	0.04	0.2	
35	METHOXYCHLOR	ND	ug/L	0.2	0.2	40	
117	ALACHLOR	ND	ug/L	0.4	0.4	2	
119	ATRAZINE	ND	ug/L	0.2	0.2	3	
120	BENZO(A)PYRENE	ND	ug/L	0.04	0.04	0.2	
122	CHLORDANE, TECHNICAL	ND	ug/L	0.4	0.4	2	
124	DI(ETHYLHEXYL)-ADIPATE	ND	ug/L	1.3	1.3	400	
125	DI(ETHYLHEXYL)-PHTHALATE	2.2	ug/L	1.3	1.3	6	Field dup 1.7 ppb
126	HEPTACHLOR	ND	ug/L	0.08	0.08	0.4	
127	HEPTACHLOR EPOXIDE (A&B)	ND	ug/L	0.04	0.04	0.2	
128	HEXACHLOROBENZENE	ND	ug/L	0.2	0.2	1	1
129	HEXACHLOROCYCLO-PENTADIENE	ND	ug/L	0.2	0.2	50	1
133	SIMAZINE	ND	ug/L	0.15	0.15	4	
	EPA Unregulated		1			1	
118	ALDRIN	ND	ug/L	0.2	0.2	1	
121	BUTACHLOR	ND	ug/L	0.4	0.4		
123	DIELDRIN	ND	ug/L	0.2	0.2		
130	METOLACHLOR	ND	ug/L	1	1.0		
131	METRIBUZIN	ND	ug/L	0.2	0.2		
132	PROPACHLOR	ND	ug/L	0.2	0.2		
	State Unregulated - Other			1	1		
179	BROMACIL	ND	ug/L	0.2	0.2		
183	PROMETON	ND	ug/L	0.2	0.2	1	
190	TERBACIL	ND	ug/L	0.2	0.2		
202	DIAZINON	ND	ug/L	0.2	0.2		
208	EPTC	ND	lug/L	0.3	0.3		P.
232	4,4-DDD	ND	ug/L	0.2	0.2		

[&]quot;- An amount of "ND" indicates that the compound was not detected above the Lab's Method Detection Limit - MDL.

[&]quot;- Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPOWR. State Advisory Level (SAL) for Unregulated compaused.

A blank MCL or SAL value indicates a level is not currently established.

J - Estimated value.



Reference Number: 04-2367

Lab Number: 04604660 Report Date: 4/26/2004

SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

233 4 234 4 236 239 240 243 96 154 244 245 247 248 249	LA-DDT CYANAZINE MALATHION PARATHION TRIFLURAUN - PAHS NAPTHALENE FLUORENE ACENAPHTHYLENE ACENAPHTHENE ANTHRACENE BENZ(A)ANTHRACENE BENZO(B)FLUORANTHENE	RESULTS ND ND ND ND ND ND ND ND ND N	Units ug/L SRL 0.2 0.2 0.2 0.2 0.2 0.1 0.2 0.2	Trigger 0.2 0.2 0.2 0.2 0.2 0.2 0.2 0.2 0.1 0.2 0.2 0.2 0.2			÷		
233 4 234 2 236 239 240 243 96 154 244 245 246 247 248 249	LA-DDT CYANAZINE MALATHION PARATHION TRIFLURAUN - PAHS NAPTHALENE FLUORENE ACENAPHTHYLENE ACENAPHTHENE ANTHRACENE BENZ(A)ANTHRACENE BENZO(B)FLUORANTHENE	ND N	ug/L ug/L ug/L ug/L ug/L ug/L ug/L ug/L	0.2 0.2 0.2 0.2 0.2 0.2 0.1 0.2 0.2	0.2 0.2 0.2 0.2 0.2 0.2 0.1 0.2			÷ .	
236 239 240 243 96 154 244 245 246 247 248 249	CYANAZINE MALATHION PARATHION TRIFLURALIN - PAHS NAPTHALENE FLUORENE ACENAPHTHYLENE ACENAPHTHENE ANTHRACENE BENZ(A)ANTHRACENE BENZO(B)FLUORANTHENE	ND ND ND ND ND ND ND ND	ug/L ug/L ug/L ug/L ug/L ug/L ug/L ug/L	0.2 0.2 0.2 0.2 0.1 0.2 0.2	0.2 0.2 0.2 0.2 0.2				
239 240 243 96 154 244 245 246 247 248 249	MALATHION PARATHION TRIFLURALIN - PAHS NAPTHALENE FLUORENE ACENAPHTHYLENE ACENAPHTHENE ANTHRACENE BENZ(A)ANTHRACENE BENZO(B)FLUORANTHENE	ND ND ND ND ND ND	ug/L ug/L ug/L ug/L ug/L ug/L ug/L	0.2 0.2 0.2 0.1 0.2 0.2	0.2 0.2 0.2 0.1 0.2	! 			
239 240 243 96 154 244 245 246 247 248 249	MALATHION PARATHION TRIFLURALIN - PAHS NAPTHALENE FLUORENE ACENAPHTHYLENE ACENAPHTHENE ANTHRACENE BENZ(A)ANTHRACENE BENZO(B)FLUORANTHENE	ND ND ND ND ND ND	ug/L ug/L ug/L ug/L ug/L ug/L	0.2 0.2 0.1 0.2 0.2	0.2 0.2 0.1 0.2			*	
240 243 96 154 244 245 246 247 248 249	PARATHION TRIFLURALIN - PAHS NAPTHALENE FLUORENE ACENAPHTHYLENE ACENAPHTHENE ANTHRACENE BENZ(A)ANTHRACENE BENZO(B)FLUORANTHENE	ND ND ND ND ND	ug/L ug/L ug/L ug/L ug/L	0.2 0.1 0.2 0.2	0.2				
243 96 154 244 245 246 247 248 249	TRIFLURALIN - PAHS NAPTHALENE FLUORENE ACENAPHTHYLENE ACENAPHTHENE ANTHRACENE BENZ(A)ANTHRACENE BENZO(B)FLUORANTHENE	ND ND ND ND	ug/L ug/L ug/L ug/L	0.1 0.2 0.2	0.1				
96 154 244 245 246 247 248 248	- PAHS NAPTHALENE FLUORENE ACENAPHTHYLENE ACENAPHTHENE ANTHRACENE BENZ(A)ANTHRACENE BENZO(B)FLUORANTHENE	ND ND ND	ug/L ug/L ug/L	0.2	0.2	1			
96 154 244 245 246 247 248 248	NAPTHALENE FLUORENE ACENAPHTHYLENE ACENAPHTHENE ANTHRACENE BENZ(A)ANTHRACENE BENZO(B)FLUORANTHENE	ND ND ND	ug/L ug/L ug/L	0.2	0.2	i			
154 244 245 246 247 248 249	FLUORENE ACENAPHTHYLENE ACENAPHTHENE ANTHRACENE BENZ(A)ANTHRACENE BENZO(B)FLUORANTHENE	ND ND ND	ug/L ug/L	0.2	1	-	1		
244 245 246 247 248 249	ACENAPHTHYLENE ACENAPHTHENE ANTHRACENE BENZ(A)ANTHRACENE BENZO(B)FLUORANTHENE	ND	ug/L	The state of the s	0.2				
245 246 247 248 249	ACENAPHTHENE ANTHRACENE BENZ(A)ANTHRACENE BENZO(B)FLUORANTHENE	ND	4		1.5				
246 247 248 249	ANTHRACENE BENZ(A)ANTHRACENE BENZO(B)FLUORANTHENE	I have a second		0.2	0.2				
247 248 249	BENZ(A)ANTHRACENE BENZ(B)FLUORANTHENE	I have a second	ug/L	0.2	0.2				
248 249	BENZO(B)FLUORANTHENE		ug/L	0.1	0.1	1			
249	BENZO(B)FLUORANTHENE	ND	ug/L	0.2	0.2	1			
	THE PARTY OF THE P	ND	ug/L	0.2	0.2				
250	BENZO(G,H,I)PERYLENE	1	ug/L	0.2	0.2	1			
	BENZO(K)FLUORANTHENE	ND	ug/L	0.2	0.2				
251	CHRYSENE	ND		0.2	0.2	1 2			
252	DIBENZO(A.H)ANTHRACENE	ND	ug/L	0.2	0.2		1		
	FLUORANTHENE	ND	ug/L	0.2	0.2	1			
	INDENO(1,2.3-CD)PYRENE	ND	ug/L	1	0.2				
	PHENANTHRENE	ND	ug/L	0.2					
	PYRENE	ND	ug/L	0.2	0.2	4	1		
231	- Phthalates	1				1			
1 250	BENZYL BUTYL PHTHALATE	ND	ug/L	0.6	0.6	24.4			
258	DI-N-BUTYL PHTHALATE	ND	ug/L	0.6	0.6	- i			
		ND	ug/L	0.6	0.6			220	
260	DIETHYL PHTHALATE	ND	ug/L	0.6	0.6				
261	DIMETHYL PHTHALATE								
1						1			
1							ļ.		
i						1	-		
1 -									
1 -	10,400,400,400								
I.			i						
							1		
1					İ		1		
1			1	1			4		
1	}		1				1		
i			1				1		
				100					

^{**-} An emourn of "ND" indicates that the compound was not detected above the Lab's Method Detection Limit - MDL

**- Maximum Contaminant Level, insulmum permissible level of a configuration in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds.

**- Maximum Contaminant Level, insulmum permissible level of a configuration in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds.

**- A blank MCL or SAL value indicates a level in not currently established.

**- If a compound is detected > or = to the State Reporting Level, SRL, specified increased monitoring frequencies may occur per DOH.

**-- Memod Detection Limit is the Lab's minimum concentration is compound can be measured and reported with 99% confidence that the compound concentration is greater than 2 era.

**-- Memod Detection Limit is the Lab's minimum concentration is compound can be measured and reported with 99% confidence that the compound concentration is greater than 2 era.

**-- Lestimated value. J - Estimated value.



11525 Knudson Rd.

Burlington, WA 98233

(800) 755-9295

(360) 757-1400 - FAX (360) 757-1402

Page 1 of 1

CARBAMATES IN DRINKING WATER

Client Name: KUO Testing Labs Inc

337 S 1st

Othello, WA 99344

System Name: WWBWC

System ID Number: DOH Source Number:

Multiple Sources:

Sample Type: B Sample Purpose: B

Sample Location: Well#1 recharge project

County: Umatilla

Reference Number: 04-2367

Project: 70296

Field ID:

Lab Number: 04604660 Date Collected: 4/13/2004 Date Extracted: 531_040415 Date Analyzed: 4/15/2004

Report Date: 4/19/2004

Analyst TW

Supervisor

or State Drinking Water Compliance

		RESULTS	Units	SRL	Trigger	MCL	COMMENT
148 141 142 143 144 145 147	COMPOUNDS EPA Regulated CARBOFURAN OXYMAL EPA Unregulated 3-HYDROXYCARBOFURAN ALDICARB ALDICARB SULFONE ALDICARB SULFOXIDE CARBARYL METHOMYL State Unregulated - Other PROPOXUR (BAYGON)	RESULTS ND ND ND ND ND ND ND ND ND N	ug/L ug/L ug/L ug/L ug/L ug/L ug/L ug/L	1.8	1.8 4.0 2.0 1.0 1.6 1.0 2.0 4.0	40 200	

[&]quot;- An amount of "ND" indicates that the compound was not detected above the Lab's Method Desection Limit - MDL. **- Mobilimum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWRL State Advisory Level (SAL) for Unregulated compounds,

A blank MCL or SAL value indicates a level is not currently established.

^{*-} If a compound is detected > or > to the State Reporting Level, SRL, specified increased monitoring frequencies may occur per DOH.

J - Estimated value.



11525 Knudson Rd.

Burlington, WA 98233

(800) 755-9295

(360) 757-1400 - FAX (360) 757-1402

Page 1 of 1

HERBICIDES IN DRINKING WATER

Client Name: KUO Testing Labs Inc

337 S 1st

Othello, WA 99344

System Name: WWBWC

System ID Number.

DOH Source Number:

Multiple Sources:

Sample Type: B

Sample Purpose: B

Sample Location: Well#1 recharge project

County: Umatilla

Reference Number: 04-2367

Project: 70296

Field ID:

Lab Number: 04604660

Date Collected: 4/13/2004 Date Extracted: 515_040420

Date Analyzed: 4/21/2004

Report Date: 4/26/2004

Analyst: CMH

Supervisor

FPA Method 515.1 For State Drinking Water Compliance

H#	COMPOUNDS	RESULTS	Units	SRL	Trigger	MCL	COMMENT
01111	EPA Regulated					70	
37	2,4 - D	ND	ug/L	0.2	0.2	70	
	2.4.5 - TP (SILVEX)	ND	ug/L	0.4	0.4	50	
	PENTACHLOROPHENOL	ND	ug/L	80.0	80.0	1	
137	A CONTRACTOR OF THE CONTRACTOR	ND	ug/L	2	2	200	
	DINOSEB	ND	ug/L	0.4	0.4	7	
	PICLORAM	ND	ug/L	0.2	0.2	500	
140	EPA Unregulated						
138	DICAMBA	ND	ug/L	0.2	0.2	1	
100	State Unregulated	j					
135	2,4 DB	ND	ug/L	1	1.0		
	2,4,5 T	ND	ug/L	0.4	0.4		
220		ND	ug/L	0.5	0.5		
	DICHLORPROP	ND	ug/L	0.5	0.5	!	
223		ND	ug/L	2	2.0		
		ND	ug/L	0.1	0.1	1	
225		ND	ug/L	0.5	0.5	÷	
226	3,5 - DICHLOROBENZOIC ACID			1			
	1.			ļ.		!	
				1		i	
						á	+
				1		i	
			j				
				1		1	1
		1	i -			0 1	
	7			1			
		1	Ĭ				
a amount o	TND indicates that the compound was not detected on the contaminant Level, maximum permissible level of a contaminant Level, maximum permissible level of a contaminant Level.	above the Lab's Method C	Detection Limit - MC	X WR State Adviso	ry Level (SAL) for Ur	regulated comp	ounds.

A DIATIK MALL OF SALL VALUE INDICATES A LEVEL IS NOT CONTROLLY ESTABLISHED.

——If a compound is detected > or * to the State Reporting Level, SRL, specified increased monitoring frequencies may occur per DOH.

——Attanded Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.

J - Estimated value.

337 South 1st Avenue, Othello, WA 99344 (509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

> DATE COLLECTED 4/13/2004

DATE RECEIVED

DATE REPORTED

SEND REPORT TO 4/14/2004 4/26/2004

W.W.B.W.C. PO Box 68

SYSTEM / CUSTOMER

Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

USTOMER AMPLE NO	ANALYSIS	RESULTS	NiDL	UNITS	ANALYSTS
Well #1	SOC/Synthetic Organic Co	Report		mg/L	Edge Analytical

THE STATE ST			INTERNATION OF THE PERSON OF T	* a source service and	
	NATIONAL PROPERTY OF THE PARTY	O'UT NICEDE (UIT) BED on Armon Armon			
·					
	ACTION AND ADMINISTRATION OF THE PROPERTY OF THE PARTY OF	WHAT STATE OF THE			
	The state of the second	NAME OF TAXABLE PARTY.			
	ENDER CONTRACTOR OF THE PROPERTY OF THE SAME AND ADDRESS OF THE SAME AND ADDRE		100 p	**************	·
			danisan marka sa		Access of the second
			- CONTRACTOR	Maria Called S. H. Johnson	WE'V WE'RE HIS CONTROL OF
CONTRACTOR OF SA		STEEN STATE			
	-				CONTRACTOR OF STREET
			estiminate de la companya del companya del companya de la companya		WALKER THE WAY A STATE OF THE PARTY OF THE P
	USTOMER AMPLE NO Well #1	USTOMER AMPLE NO Well #1 SOC/Synthetic Organic Co	USTOMER ANALYSIS RESULTS Well #1 SOC/Synthetic Organic Co Report		

<(0.001); indicates the analyte was not detected at or above the concentration indicated.

ND: None Detected

mg/Litadiostes milligrams per litre

PQL=Practical Quantization Limit is the lowest level that can be ashieved within specified limits of precision and securacy during routine laboratory operating conditions

MDL: Method Detection Limit

Please theck out our new Word Sho at http://www.kusigsting.com

04-28-04

Dr. Ecgene Kuo, Quality Assurance Coordinator



11525 Knudson Rd. Budington, WA 98233 (800) 755-9295

(360) 757-1400 - FAX (360) 757-1402

Page 1 of 2

SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

Client Name: KUO Testing Labs Inc

337 S 1st

Othello, WA 99344

System Name: WWBWC

System ID Number: DOH Source Number: Multiple Sources: Sample Type: 8

Sample Purpose: 6
Sample Lecation: Well#1 recharge project

County: Umatilia

Reference Number: 04-2367

Project: 70296

Field ID:

Lab Number: 04604660 Date Collected: 4/13/2004 Date Extracted: 525_040419 Date Analyzed: 4/19/2004 Report Date: 4/28/2004 Analyst: CMH

Supervisor

EPA Method 525.2 For State Drinking Water Compliance

DOH#	COMPOUNDS	RESULTS	Units	SRL	Trigger	MCL	COMMENT	
	EPA Regulated	100 P. 10 P.	THE CONTRACTOR OF THE PERSON NAMED IN CO	THE PERSON NAMED IN COLUMN TWO IS NOT THE PERSON NAMED IN COLUMN TWO IS NAMED IN COLUMN TWO IS NAMED IN COLUMN TWO IS NAMED IN COLUMN TWO IS NAMED IN COLUMN TWO IS NAMED IN COLUMN TWO IS NAMED IN COLUMN TWO IS NAMED IN COLUMN TWO IS NAMED IN COLUMN TWO IS NAMED IN COLUMN TWO IS NAMED IN COLUMN TWO IS NAMED IN COLUMN TWO IS NAMED IN COLUMN TWO IS NAMED IN COLUMN TWO IS NAMED IN COLUMN TWO IS NAMED IN COLUMN TW	- CONTRACTOR OF THE PARTY OF TH	CONTRACTION OF THE PARTY OF THE	THE PERSON NAMED IN COLUMN	
33	ENDRIN	ND	ngit	0.02	0.02	2		
34	LINDANE (BHC - GAMMA)	ND	ाजिए"	0.04	0.08	, 0.2	1	*
35	METHOXYCHLOR	ND	LIGHL	0.2	0.2	40		
117	ALACHLOR	ND	nav-	0.4	0.4	2	-	
119	ATRAZINE	NO	ug/L	0.2	0.2	3	1	
120	BENZO(A)PYRENE	MD	ug/L	0.04	0.04	0.2	1	
122	CHLORDANE, TECHNICAL	NO	ug/L.	0.4	0.4	2		
124	DI(ÉTHYLHEXYL)ADIPATE	ND	ug/L	1.3	1.3	460		
125	DICETHYLHEXYL)-PHTHALATE	2.2	ug/L	1.3	1.3	0	Fleid dup 1.7 pp	sb da
126	HEPTACHLOR	ND	ug/L	0.08	0.08	0.4		
127	HEPTACHLOR SPOXIDE (ASS)	NO.	ug/L	0.04	0.04	0.2	1	
128	HEXACHLOROSENZENE	ND	ug/L	0.2	0.2	1	1	
129	HEXACHLOROCYCLO-PENTADIENE	ND	ug/L	0.2	0.2	50	4	
133	SMAZINE	NO "	ug/L	0.15	0.15	4		
	EPA Unnegulated			1 P				
118	ALDRIN	NO	ug/L	0.2	0.2	1		
121	BUTACHEOR	NO.	ug/L	. 0.4	0.4		, .	
123	DISLOPIN	ND	ug/L	0.2	0.2			
130	METOLACHLOR .	ND .	nav-	1.	1.0			
131	METABLEN	NO	ug/L	0.2	0.2			
132	PROPACHLOR	ND	ug/L	0.2	0.2			
	State Unregulated - Other				1			
179	BROMACIL	ND	ug/L	0.2	. 0.2	1		
183	PROMETON	ND	ug/L	0.2	0.2			
190	TERBACIL	ND	ug/t.	0.2	0.2			
202	DIAZINON	ND	ug/L	0.2	0.2			*
208	EFTC	ND	navr.	0.3	0.3		1	
282	4.4-000	ND	ug/L	0.3	.0.2			

PORAR BOCS7

Modernum Conteminant Level, meathern permissible level of a contem.

A blank MCL, or SAL value indicates a level is not comenty attable of a contectud a description of a contectud a or = to the district Reparting Level. SRL.

Page 2 of 2



P.4



Reference Number: 04-2387 Lab Number: 04804860 Report Date: 4/25/2004

SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

na i-M	COMPOUNDS	RESULTS	Units	SRL	Trigger	MCL	COMMENT	AND DESCRIPTION OF THE PROPERTY.
计学	The state of the s	ND	US/L	10.2	0.2	Marie Commencer		24
	4.4-DDE	ND	ug/L	0.2	0.2	1	1	
234	A,4-DD7	NO	ug/L	0.2	0.2	1		247
	CYANAZINE	NO	ug/L	0.2	0.2	1	ľ	mile .
	MALATHION	NED	UgA.	0.2	0.2			
240	PARATHON		ug/L	0.2	0.2	1	1	
243	TRIFLURALIN	ND	taggree			1	1.	N.
	- PAHs	ND	ug/L	0.1	Q.1	4		
	NAPTHALENE	ND	ug/L	0.2	0.2	1		
	PLUORENE	1.000	ug/L	0.2	0.2			
	ACENAPHTHYLENE	ND	Light	0.2	0.2			
	ACENAPHTHENE	ND		0.2	0.2	1	1.	
	ANTHRACENE	ND	ng/L	0.1	0.1		Is .	
		ND :	NAT.	0.2	0.2	4	I	2.5
248	BENZO(B)FLUGRANTHENE	ND	tag/L		0.2			
	BENZO(G,H,I)PERYLENE	ND	ug/L	9.2			1	
	BENZO(K)FLUORANTHENE	ND	ug/L	0.2	0.2			
	CHRYSENE	NO	ug/L	0.2	0.2	***	1	
252		ND	ug/L	0.2	0.2	1		
259		ND CH	ug/L	0.2	0.2	Ĭ.	1	
255	· ·	ND.	Jug/L.	0.2	0.2	1 "		
256		NO .	USAL	0.2	0.2			
	The state of the s	ND	ug/L	0.2	0.2	İ		
257	PYRENE	1		. 1		1	1	
	- Phihalates	NED	ug/L	0.6	0.6	1	1	
258		MD	US/L	0.6	0.6	1	1	**
259		ND	uell	0.8	0.6	. !		
	DISTHYL PHINALATE	ND	ve/la ·	0.6	0.6	1	i	
261	CHETHYL PHTHALATE	MB	23.0		-			
					i			
				i.	1			
				İ	1	1 -		
			1					
1.9	1			1		1.1		1.
			1			1		
				1	1	i		
+6)				. 1	.			
- 2				1				
		E*		1 .	1			
				1	- 10 m		1 2	
			1				4	
1 2		1	. [3	
	*		1 4 4 4 4 4		Î	1	- 1 - 1	- 1
)	(4):			. 1	1	T	-91
	4		1	i	1	4	. 1	

[&]quot; An executed of "NO" (Address that the configurate you not detected about the Land House destricted by CEA, In-CHARL Stone Advisory Loved (EAL) for Liverignment compounded in water executations by CEA, In-CHARL Stone Advisory Loved (EAL) for Liverignment compounded in water executations by CEA, In-CHARL Stone Advisory Loved (EAL) for Liverignment compounded in water executations by CEA, In-CHARL Stone Advisory Loved (EAL) for Liverignment compounded in water executations by CEA, In-CHARL Stone Advisory Loved (EAL) for Liverignment compounded in the CEA, In-CHARL STONE ADVISORY COMPOUNDED AND ADVISO

A HARTE AND OF EAL LIGHER PROFESSION & BOWL IN THE CHARTON SHEET, SANSTAND HUTCHARD HER HOLLD THEN THE THE PARTY THAT HE CANNOT THE PARTY THAT HE CANNOT THE PARTY THAT HE CANNOT THE PARTY THAT HE CANNOT THE PARTY THAT HE CANNOT THE PARTY THAT HE CANNOT THE PARTY THAT HE CANNOT THE PARTY THAT HE CANNOT THE PARTY THAT THE PARTY THE PARTY THE PARTY THE PARTY THE PARTY THE PARTY THE PARTY THE PART

with the description of the second process o

^{1 -} BORNOUS NO. NO.



11925 Knudson Rd. Burlington, WA 98233 (800) 755-9295

(380) 757-1400 - FAX (360) 757-1402

Page 1 of 1

CARBAMATES IN DRINKING WATER

Client Name: KUO Testing Labs Inc

337 S 1st

Othello, WA 99344

System Name: WWBWC

System ID Number: DOH Source Number.

Multiple Sources: Sample Type: B

Sample Purpose: B Sample Location: Well#1 recharge project

County: Umestilla

Reference Number: 04-2367

Project: 70296

Field ID:

Lab Number: 04604660 Date Collected: 4/13/2004 Date Extracted: 531_040415 Date Analyzed: 4/15/2004

Report Date: 4/19/2004 Analyst TW

Supervisory

)H神	COMPOUNDS	RESULTS.	Units	SRL	Trigger	MCL	COMMENT	
/1 19P	EPA Regulated		THE REAL PROPERTY AND ADDRESS OF THE PARTY AND		1.8	40		
148	CARBOFURAN .	ND	right.	1.8	1	200	1	
148	OXYMAL	פא	wit	4	4.0	1 800	i	
	EPA Unregulated	· [1	12.0			
141	3-HYDROXYGAROOFLERAN	ND	ug/L	2		1		*
142	ALDICARB	ND	ug/L	13	1.0	3		
	ALDICARD SULFONE	NO	ug/L	1.6	1.6			
144	ALDICARD SULFOXIDE	NO	HEAL	. 1	1.0	-		*
145	CARBARYL	ND	ug/L	2	717	1,	*	
	METHOMYL	ND	ug/L	1	4.0	1		
	State Unregulated - Other	=						
326	PROPORUR (RAYGON)	ND	ug/L	11				
	METHIOCARD	ND	ug/L					
*			1					
				1	1 .	15		-
	*			1	1			
			1	1.		F -		
		1	T.		1		1	
			1 -				1	
					1			
	i						1	
			*	i				
	*			1		1		2
				1 .		*		
		1	1			1		
					1			1 5= 0
	4		'	1			1	

colleges that the compared was not decreased above the Lac's Montal Dissection Lives - MCA.



11525 Knudson Rd. Burlington, WA 98238 (800) 755-9295 (350) 757-1400 - FAX (360) 757-1402

Page 1 of 1

SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

Glient Name: KUO Testing Labs Inc.

337 S 1st

Othello, WA 99344

System Name: VWBWC

System ID Number:

DOH Source Number:

Multiple Sources!

Sample Type: 13

Sample Purpose: B Sample Lecation: Wellis's recharge project

County: Umatilla

Reference Number: 04-2367

... Project 70296

Field ID:

Lab Number: 04604660

Date Collected: 4/13/2004 Date Extracted: 508_040419

Date Analyzed: 4/19/2004

Report Date: 4/22/2004

Analyst CMH

Supervisor.

Polis	COMPOUNDS	RESULTS	Units	SRL	Trigger	MCL	COMMENT	and the same of th
173 174 175 176	PCBs/Toxaphone TOXAPHD45 AROCLOR 1221 AROCLOR 1232 AROCLOR 1242 AROCLOR 1245 AROCLOR 1264 AROCLOR 1266	ND ND ND ND ND ND ND	ugh ugh ugh ugh ugh ugh	2 20 0.6 0.5 0.1 0.1 0.2	2 20 0.5 0.3 9.1 0.1 0.2	3		
at at								

^{*} An emphase of "NO" instinution that the companies were not decisioned service the Law's released Decisional Lipsis - Milk.

* An emphase of "NO" instinution that the companies were not decisioned services the discussion of the Companies of th

FORM: SCOOL

oproceed intensitating begalarschem may cassur par DOM. Unaccudest strat appartati atta 1979, somfalenzae shak ma compassed cancergruidom is greater shun soma. ASSISTMENT CONSENSES LA A MARIA WICL OF SAL VO



11525 Kayasan Rd. Burlington, WA 98233 (800) 755-8285

(360) 767-1400 - FAX (360) 757-1402

Page 1 of 1

HERBICIDES IN DRINKING WATER

Client Name: KUO Testing Labs Inc.

337 S 1st

. Othello, WA 99344 ..

System Name: WWSWC

System ID Number:

DOH Source Number:

Multiple Sources:

Sample Type: B

Sample Purpose: 8

Sample Location: Well#1 recharge project

County: Umatilla

Reference Number: 04-2367

Project: 70296

Field ID:

Lab Number: 04604660 Date Callected: 4/13/2004

Date Extracted: 515_040420 Date Analyzed: 4/21/2004

Report Date: 4/26/2004

Analyst: CMH

Supervisor

#HOC	COMPOUNDS	RESULTS	Units	SRL	Trigger	MCL	COMMENT	graph and the second se
	EPA Regulated							
37	24-0	ND	MAN.	0.2	0.2	70		
38	2,4,5 - TP (SILVEX)	NO	49/L	0.4	0.4	: 50	1	7
134	PENTACHLOROPHENOL	MD	ug/L	0,08	0.08	1		
137	DALAPON	NED	ug/L	3	2	500		
139	DINOSES .	NO	ug/L	9.4	0.4	7.		
140	PICLORAM	ND	WEAL.	0.2	0.2	500		
.,,_	EPA Unregulated						1.	V. V.
138	DICAMBA	NO	ug/L	0.2	0.2	1		72
	State Unregulated		15			i		
135	2,4 DB	ND	ug/L	1	1.0			
	2,6.5 T	NO	ug/L	0.4	0.4	1	1	
220	BENTAZON	CM	ug/L	0.5	0.5			
221	DICHLORPROP	ND .	ug/L	0.5	0.5	1	L .	
223	ACTIFLOREN	ND	ug/L .	2	2.0			
225	DACTHAL (DCPA)	ND	UBA.	0.1	0.1	P a	,	
	3.5 - DICHLOROSENZOIC ACID	ND	ug/L	0.5	0.5	1	+	
Barrier W				1		F	1 .	
			1			1		
	1			1 .	1 1			
		• 1		1				
		8					T	
						:		
						1 . *		+4
		1				1	1	
				1		1		
		1			i .	1,	1	V 7
					1 .	10	1	
		1 /	. 1		1	*		8
	NOT INCOME THE THE COMPOSITE WERE SEE ASSESSED IN		A STATE OF THE PARTY OF THE PAR		J	· morning	1 am membranes	

FORRE SDORT

Kuo Testing Labs, Inc. 337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free

Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

·STEM/CUV-CAMETP	4/13/2004	SENO RI		4/2004	DATE REPORTED 4/26/2004
W.W.B.W.C. PO Box 68 Milton Freewater O Project Name:	OR 97862	POI	Bower Box 68 on Freewater	OR	97862
AMI: END CUSTOMER FORTLE NO	ANNI YSIS	RESULTS	M3L	JMTS	ANALYSTS
70292 Intake	SOC/Synthetic Organic Co	Report		mg/L	Edge Analytica

 $<\!(0.001)_{\rm C}$ indicates the analyte was not detected at or above the concentration indicated. ND: None Detected

mg/L indicates milligrams per litre

* PQLs Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

MDL: Method Detection Limit,

Please check out our new yeh Site at http://www.kuotesting.com

Dr. Lagene Kuo, Quality Assurance Coordinator

04-26-04 Date



11525 Knudson Rd. Burlington, WA 98233 (800) 755-9295 (360) 757-1400 - FAX (360) 757-1402

Page 1 of 1

CARBAMATES IN DRINKING WATER

Client Name: KUO Testing Labs Inc.

337 S 1st

Othello, WA 99344

System Name: WWBWC

System ID Number:

DOH Source Number. Multiple Sources:

Sample Type: B

Sample Purpose: B Sample Location: intake

County: Umatilia

Reference Number: 04-2366

Project 70292

Field ID:

Lab Number: 04604659

Data Collected: 4/13/2004 Date Extracted: 531_040416

Date Analyzed: 4/15/2004 Report Date: 4/19/2004

Analyst TW

Supervisor.

DH#	COMPOUNDS	RESULT6	Units	SRL	Trigger	MCL	COMMENT	
J11#	EPA Regulated			1.8	1.8	40		
146	CARBOFURAN	ND	ugit	4	4.0	200		
148	OXYMAL	ND	ug/L			į		
	EPA Unregulated			12	2.0	1		
141	3-HYDROXYCARBOFURAN	ND	Jeg/L	9	1.0			
142	ALDICARS	ND	ug/L	1.6	1.5			
143	ALDICARS SULFONE	ND	ug/L	1	1.0	1		
144	ALDICARS BULFOXIDE	ND	ug/L	2	2.0	1		
	CARBARYL	ND	ug/L	11 .	4.0	1		
	METHONYI.	MD	ng/L		710	1		
7000	State Unregulated - Other			1		1		
328	PROPOXUR (BAYGON)	NO	rag/L	4				
	METHOCARS	NO	ug/L	46		1		
					1	1.0		
		1		1	1			
		1		- 1	1			
	1 ***				1			
	1							
	-		İ	i i	1			
	I - I							
10						1		
					1			
		- Y	1	1		Ÿ.		
				i	1			
	1	i		1				
	7			1				

^{**} An articular of "NCT indicates that the community was not detected showe the Lone Mathed Desirction Liver > NDL.

** An articular of "NCT indicates that the community was not detected showe the Lone Mathed Desirction Liver > NDL.

** A bank NCL of Situ Situal indicates a level is not currently established.

** A bank NCL of Situal Situal indicates a level is not currently established.

** I a community is essected > or a to the Sicas Popolary Lives Situal Indicates included increases into the proposed or reported with 19th considerate that the compound concentration is greater from Latt.

*** A bank NCL of Situal Situal Indicates a level is not currently established.

*** A bank NCL of Situal Situal Indicates a level is not currently established.

*** A bank NCL of Situal Situal Indicates a level is not currently established.

*** A bank NCL of Situal Situal Indicates a level is not currently established.

*** A bank NCL of Situal Situal Indicates a level is not currently established.

*** A bank NCL of Situal Indicates a level is not currently established.

*** A bank NCL of Situal Indicates a level is not currently established.

*** A bank NCL of Situal Indicates a level is not currently established.

*** A bank NCL of Situal Indicates a level is not currently established.

*** A bank NCL of Situal Indicates a level is not currently established.

*** A bank NCL of Situal Indicates a level is not currently established.

*** A bank NCL of Situal Indicates a level is not currently established.

*** A bank NCL of Situal Indicates a level is not currently established.

*** A bank NCL of Situal Indicates A bank NCL of Situal Indicates Indicates Indicates A bank NCL of Situal Indicates Ind

^{1 -} Emiracted value



11525 Knudsen Rd. Burlington, WA 98233 (800) 755-9296 (360) 757-1400 - FAX (360) 757-1402

Page 1 of 1

SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

Client Name: KUO Testing Labs Inc

337 S 1st

Othello, WA 99344

System Name: WWBWC

System ID Number:

DOH Source Number:

Multiple Sources:

Sample Type: B

Sample Purpose: B

Sample Location: intake

County: Umatilia

Reference Number: 04-2366

Project: 70292

Field ID:

Lab Number: 04604659

Date Collected: 4/13/2004

Date Extracted: 508_040419

Date Analyzed: 4/21/2004

Report Date: 4/22/2004

Analyst: CMH

Supervisor:

36 173 174 175	COMPOUNDS PCBs/Toxaphene TOXAPHENE ARCCLOR 1221	PA Method 508.1 F	Units	SRL	Trigger	MCL	COMMENT	AND DESCRIPTION OF THE PARTY OF
36 173 174 175	PCBs/Toxaphone TOXAPHENE	ND				The state of the s		
36 173 174 175	TOXAPHENE	ND		100	2	3		
173 174 175			ugit	12	20	1 0		
174 175	MARINE ALL INC.	ND	ugiL	0.5	0.5	1		
175	AROCLOR 1232	ND	UNL	0.5	0.3			
	AROCLOR 1242	ND	ug/L	0.1	0.1			
	AROCLOR 1248	ND	UNIL.	0.1	0.1	1		
177	AROCLOR 1254	NO	ug/L	0.2	0.2	1		
	AROCLOR 1290	ND	ug/L	0.1	0.1	i		
	AROCLOR 1016	ND	ug/L	J. 1			1	
				1		1		
						1		
1		. 2		1				
1						1		
1	1					120		

An ameura of PDP indicates their the compound and his desector above the Lair shall de Common Limit - MSL.

***Maximum Constrainer Level, magnitum serialisable limit of a contaminant in larger established by EPA, MROVR, State Accessory Level (SAL) for Unrequisted compounds.

**A plants MCL of Sout which indicates a level is not carefully accombined.

**A plants MCL of Sout which indicates a level is not carefully accombined increased sociating leagueness into occur for DOM.

**A plants MCL of Sout which indicates a level is not carefully accombined increased sociating leagueness into occur for DOM.

**A plants MCL of Sout which indicates a level is not carefully accombined and reposted with Birst confidence that the pumpound confidence is presser than zone.

**He segment Desection Limits to the leaf or minimum concentration is compound can reposted with Birst confidence that the pumpound confidence is presser than zone.

**J. Eathering within the level leaf or minimum concentration is compound can reposted usin Birst confidence that the pumpound confidence is presser than zone.

FORM; SOC97



11525 Knudson Rd. Burlington, WA 98233 (800) 755-9295 (360) 757-1400 - FAX (360) 757-1402

Page 1 of 2

SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

Client Name: KUO Testing Labs Inc.

337 8 1st

Othello, WA 99344

System Name: WWBWC

System ID Number: DOH Source Number:

Multiple Sources:

Sample Type: B Sample Purpose: B

Sample Location: Intake

County: Umatilla

Reference Number: 04-2366

Project: 70292

Field ID:

Lab Number: 04604659 Date Collected: 4/13/2004 Date Extracted: 525_040419

Date Analyzed: 4/21/2004 Report Date: 4/22/2004

Analyst CMH Supervisor.

....

WHO	COMPOUNDS	RESULTS	Units	SRL	Trigger	MCL	COMMENT
	EPA Regulated	T			0.02	2	
33	ENDRIN	ND	ug/L	0.02	1.170.00	0.2	
0.00	LINDANE (SHC - GAMMA)	ND	nayr_	0.04	0.04		
	METHOXYCHLOR	ND	ug/L	0.2	0.2	40	
	ALACHLOR	ND	ug/L	0.4	0.4	2	
	ATRAZINE	ND	ug/L	0.2	0.2	3	
	BENZOLA)PYRENE	ND	ug/L	0.04	0.04	0.2	
122	- Louis and a state of the stat	ND	ugit	0.4	0.4	2	
ACC COMM	DIETHYLHEXYL)-ADIPATE	ND	ug/L	1.3	1.3	1 400	
		ND	ug/L	1.3	1.3	6	
126		ND	ug/L	0.08	0.03	0.4	
	HEPTACHLOR	ND	ug/L	0.04	0.04	0.2	
	HEPTACHLOR EPOXIDE (ALE)	NO	ug/L	0.2	0.2	1	
	HEXACHLOROBENZENE	ND	ug/L	0.2	. 0.2	50	+
	HEXACHLOROCYCLO-PENTADIENE	ND	ug/L	0.15	0,15	4	
133	SIMAZINE				1		1
1970.9	EPA Unregulated	NO :	ug/L	0.2	0.2		
	ALDRIN	ND	ug/L	0,4	0.4		
3(5),375	BUTACHLOR	ND	ug/L	0.2	0.2	:	
	DIELDRIN	ND	un/L	1	1.0	1	
	METOLACHLOR	ND	DDVL.	0.2	0.2	1	
	METRIBUZIN	ND	ug/L	0.2	0.2		
133	2 PROPACHLOR	1957					
	State Unregulated - Other	ND	ugh	0.2	0.2		
31/4	9 BROMACIL	IND	ng/L	0.2	0.2		
18	3 PROMETON	1000	ug/L	0.2	0.2	t	
19	O TERBACIL	OM	ug/L	0.2	0.2	i	
20	2 DIAZINON	ND	nav-	0.3	0.3	1	
20	8 EPTC	ND	1000	0.2	0.2	d.	
23	2 4,6-000	NO	ng/L			1	_

.I - Expressed value.

FORM: SOC97

^{**} An arround of NOT indicates that the compound was not determine the call is identical Desertion Link - MOU.

** Magning Conformation Links. Recommend permanents based of a conformation in sense desembles by EPA, MRCHAR. State Advisory Links (SAL) for Unrequiented compounds.

**A blank MCC of SAL* volume indicates a level is not currently explaighed.

**A blank MCC of SAL* volume indicates a level is not currently explaighed.

**A blank MCC of SAL* volume indicates a level is not currently explaighed.

**A blank MCC of SAL* volume indicates a level is not currently explaighed.

**A blank MCC of SAL* volume indicates a level is not currently explaighed.

**A blank MCC of SAL* volume indicates a level is not currently explaighed indicates a level indicate.

**A blank MCC of SAL* volume indicates a level is not currently explaighed indicates a level indicates.

**A blank MCC of SAL* volume indicates a level is not currently explaighed indicates and reported with USAL confidence in the currently explained contained in the currently explained in the currently explained indicates a level indicates a level indicates a level indicates a level indicates a level indicates a level indicates.

**A blank MCC of SAL* volume indicates a level is not currently explaighed.

**A blank MCC of SAL* volume indicates a level is not currently explaighed.

**A blank MCC of SAL* volume indicates a level is not currently explaighed.

**A blank MCC of SAL* volume indicates a level is not currently explaighed.

**A blank MCC of SAL* volume indicates a level is not currently explained.

**A blank MCC of SAL* volume indicates a level is not currently explained.

**A blank MCC of SAL* volume indicates a level is not currently explained.

**A blank MCC of SAL* volume indicates a level is not currently explained.

**A blank MCC of SAL* volume indicates a level is not currently explained.

**A blank MCC of SAL* volume indicates a level indicates a level indicates a level indicates a level indicates a level indicates a level indicates a level

Page 2 of 2



Reference Number: 04-2366 Lab Number: 04604659

Report Date: 4/22/2004

SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

OH#	COMPOUNDS	RESULTS	Units	SRL		MCL	COMMENT
	6,4-DDE	ND	ug/L	: 0.2	0.2	1	
	4,4-DDT	: ND	ug/L	0.2	0.2		
	CYANAZINE	ND	vg/L	0.2	0.2		
	MALATHION	ND	ug/L	0.2	0.2	4	
	PARATHION	ND	ug/L	0.2	0.2	7.0	
	TRIFLURALIN	ND	ugit	0.2	0.2	1	
240	- PAHS	1			1		
O.S.	NAPTHALENE	ND	ug/L	0.1	0.1		-
	FLUORENE	ND	ug/L	0.2	0.2		*
	ACENAPHTHYLENE	ND	ug/L	0.2	0.2		
	ACENAPHTHENE	ND	ug/L	0.2	0.2		
	A CONTRACTOR OF THE PROPERTY O	ND	ug/L	0.2	0.2		
	ANTHRACENE	ND	ug/L	0.1	0.1		
	SENZ(A)ANTHRACENE	NO	ug/l	0.2	0.2		
	BENZO(B)ALUORANTHENE	ND	ug/L	0.2	0.2		0
	BONZO(G,H,I)PERYLENE	ND	ug/L	0.2	0.2		
	RENZO(X)FLLIORANTHENE		ug/L	0.2	0.2		
	CHRYSENE	ND		0.2	0.2		
252	DIBENZO(A,H)ANTHRACENE	ND	ug/L	0.2	0.2		
	FLUORANTHENE	NO	ug/L		A. Mariana	8	
255	INCENO(1,23-CD)FYRENE	ND	υgΛ	0.2	0.2		
256	PHENANTHRENE	ND	ug/L	0.2	0.2	1	
257	PYRENE	NO	nav_	0.2	0.2		
	- Phthalates						
258	BENZYL BUTYL PHTHALATE	ND	19/1	0.6	0.6		
259	DI-N-BUTYL PHTHALATE	ND	nay.	0.6	8.0		
260	DIETHYL PHTHALATE	ND	vg/L	0.6	0.8	100	
261	DIMETHYL PHTHALATE	ND	ugit	0.6	0.6		
					1		
						1	
	1						
		1					
		b/ =					
		65					
				1	1.		
					1	1	
						į	†
						į	
						1	
	4				I.		
				:			
				- E	10		4

^{*-} ALL EXPORTS OF MOT indicates that the companied was not described above the Lab's historic Disposion Limit - MOC.

*- House Continuous Purish antiques a level of a continuous provide expensional by EPA, NPDWAR. State Advisory Limit (SAL) for Unrepolated configuration.

A blank NCL or SAL value indicates a level of not summitly described as a level of the continuous and the configuration of the continuous and the configuration of the configurat



11525 Knudson Rd. Burlington, WA 98233 (800) 755-9295 (360) 757-1400 - FAX (360) 757-1402

Page 1 of 1

HERBICIDES IN DRINKING WATER

Client Name: KUO Testing Labs Inc

337 S 1st

Othello, WA 99344

System Name: WWBWC "

System ID Number: DOH Source Number:

Multiple Sources: Sample Type: B

Sample Purpose: B Sample Location: intake

County: Umatilla

Reference Number: 04-2365

Project: 70292

Field IO:

Lab Number: 04604659 Date Collected: 4/13/2004 Date Extracted: 515_040420 Date Analyzed: 4/21/2004 Report Date: 4/26/2004

Analyst CMH Supervisor:

HHC	COMPOUNDS	RESULTS	Units	SRL	Trigger	MCL	COMMENT
	EPA Regulated						
37	2,4 • 0	ND	ug/L	0.2	0.2	70	
38	2,4,5 - TP (SILVEX)	ND	ug/L	0.4	0.4	50	
134	PENTACHLOROPHENOL	ND	ugAL	0.08	0.08	1	
	DALAFON	ND	ugit.	2	2	200	
	DINOSES	ND	ug/L	0.4	0.4	7 .	
	PICLORAM	ND	Ug/L	0.2	0.2	500	
	EPA Unregulated			- +			•
138	DICANBA	ND	ug/L	0.2	0.2	-	
,	State Unregulated						
135	2,4 06	ND	U9/6	1	1.0		
	2,4,5 T	ND	ug/L	0.4	0.4		
	GENTAZON	ND	ug/L	0.5	0.5		
	DICHLORPROP	ND	ug/L	0.5	0.5	İ	
	ACTIFLORFIN	MID	ug/L	2	2.0		
	DACTHAL (DCPA)	NO	130/1_	0.1	0.1		
	3.5 - DICHLOROBENZOIC ACID	ND	VS/L	0.5	0,5		
220	3.5 Diguidadoria de la como de la						
			1				5
					-		
						3	
				i	a la		
				1			

^{**} An amount of ND* Indicated that the compound was not constant place on Link tended Constant Link; - MCL.

** An amount of ND* Indicated that the compound was not constant in water admissible by EPA, NPCVVR. State Advisory Lavet (SAL) for chrespitated compounds.

** Alank NCL or SAL, value indicates a level to an currently attributed.

** Alank NCL or SAL, value indicates a level to an extendibility.

** A compound is described > or an one State Regioning Lavet, SAL, specified increased marketing frequencies may social par COM.

*** If a compound is described > or an one State Regioning Lavet, SAL, specified increased marketing frequencies may social par COM.

*** If a compound is described Link! is the test minimum consequence is compound can be immeasured and reported with first, confidence that are compound concernation in orbital concernation.

*** I - Essential Consequence in the consequence of the content of the co

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free

Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

DATE COLLECTED

DATE RECEIVED

DATE REPORTED

SYSTEM / CUSTOMER

4/13/2004

SEND REPORT TO

4/14/2004

4/26/2004

W.W.B.W.C.

PO Box 68 Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

SAMPLE NO CUSTOMER UNITS Intake SOC/Synthetic Organic Co mg/L Edge Analytical 70292 Report

(0.001):	indicates the analyte was not	detected at o	or above the	concentration	indicated.

L'Indicates milligrams per litre

PQL=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

MDL: Method Detection Limit
Please check out our new Web Site at http://www.kuotesting.com // wo

04-26-04

Date

Dr. Eggene Kuo, Quality Assurance Coordinator

*- An amount of "ND" indicates that the compound was not detected shove the Leb's Method Detection Limit • MDL.

*-- Maximum Conterninant Level, maximum permissible level of a conterninant in water established by EPA, NPDWR, St.

A blank MCL or SAL value indicates a level is not currently established.

*-- If a compound is detected > or > to the State Reporting Level, SRL, specified increased monitoring frequencies may

--- Memod Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% co.

J - Estimated value.

y occur per DOH.



11525 Knudson Rd.

Burlington, WA 98233

(800) 755-9295

(360) 757-1400 - FAX (360) 757-1402

Page 1 of 1

SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

Client Name: KUO Testing Labs Inc

337 S 1st

Othello, WA 99344

System Name: WWBWC

System ID Number:

DOH Source Number:

Multiple Sources:

Sample Type: B

Sample Purpose: B

Sample Location: intake

County: Umatilla

Reference Number: 04-2366

Project: 70292

Field ID:

Lab Number: 04604659

Date Collected: 4/13/2004

Date Extracted: 508_040419

Date Analyzed: 4/21/2004

Report Date: 4/22/2004

Analyst: CMH

Supervisor: <1

DOH#	COMPOUNDS	RESULTS	Units	inking Wa	Trigger	MCL	COMMENT
DON	PCBs/Toxaphene			2	2	3_	
36	TOXAPHENE	ND	ug/L	2	20		
	AROCLOR 1221	ND	ug/L	20	0.5	÷	
174	AROCLOR 1232	ND	ug/L	0.5	0.3	*	_
	AROCLOR 1242	ND	ug/L	0.5	0.1		
	AROCLOR 1248	ND	ug/L	0.1	0.1	1	
	AROCLOR 1254	ND	ug/L	0.1	0.1	1	
	AROCLOR 1260	ND	ug/L	0.2	0.1	1	
	AROCLOR 1016	ND	ug/L	0.1	0.1		
						1	
1							
				i		1	
		_				I.	
1	1					i	

[&]quot;- An emount of "ND" Indicates that the compound was not detected above the Lab's Method Detection Limit - MDL.

^{*-} An amount of "ND" indicates that the compound was not detected above the Lab's Method Detection Limit - MDL.

*- Meximum Contaminent Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds.

A blank MCL or SAL value indicates a level is not currently established.

J - Estimeted value.



11525 Knudson Rd. Burlington, WA 98233

(800) 755-9295

(360) 757-1400 - FAX (380) 757-1402

Page 1 of 2

SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

Client Name: KUO Testing Labs Inc

337 S 1st

Othello, WA 99344

System Name: WWBWC

System ID Number: DOH Source Number: Multiple Sources:

Sample Type: B Sample Purpose: B Sample Location: Intake

County: Umatilla

Reference Number: 04-2366

Project: 70292

Field ID:

Lab Number: 04604659 Date Collected: 4/13/2004 Date Extracted: 525_040419 Date Analyzed: 4/21/2004 Report Date: 4/22/2004

Analyst: CMH

Supervisor.

EDA Method 525 2 For State Drinking Water Compliance

OH#	COMPOUNDS	RESULTS	Units	SRL	Trigger	MCL	COMMENT
	EPA Regulated			10.2			
33	ENDRIN	ND	ug/L	0.02	0.02	. 2	
34	LINDANE (BHC - GAMMA)	ND	ug/L	0.04	0.04	0.2	
35		ND	ug/L	0.2	0.2	40	
117	ALACHLOR	ND	ug/L	0.4	0.4	2	
	ATRAZINE	ND	ug/L	0.2	0.2	3	
	BENZO(A)PYRENE	ND	ug/L	0.04	0.04	0.2	
	CHLORDANE, TECHNICAL	ND	ug/L	0.4	0.4	2	
	DKETHYLHEXYL)-ADIPATE	ND	ug/L	1.3	1.3	: 400	
	DI(ETHYLHEXYL)-PHTHALATE	ND	ug/L	1.3	1.3	6	
	HEPTACHLOR	ND	ug/L	0.08	80.0	0.4	
	HEPTACHLOR EPOXIDE (A&B)	ND	ug/L	0.04	0.04	0.2	
	HEXACHLOROBENZENE	ND	ug/L	0.2	0.2	1	
	HEXACHLOROCYCLO-PENTADIENE	ND	ug/L	0.2	0.2	50	
133		ND	ug/L	0.15	0.15	4	
,,,,,	EPA Unregulated						
118	ALDRIN	ND =	ug/L	0.2	0.2		
121		ND	ug/L	0.4	0.4		
	DIELDRIN	ND	ug/L	0.2	0.2	:	
130	METOLACHLOR	ND	ug/L	1	1.0		
	METRIBUZIN	ND	ug/L	0.2	0.2	- P	
	PROPACHLOR	ND	ug/L	0.2	0.2		
, , ,	State Unregulated - Other	1					
179	BROMACIL	ND	ug/L	0.2	0.2		
	PROMETON	ND	ug/L	0.2	0.2		
11.57.555	TERBACIL	ND	ug/L	0.2	0.2		1
	2 DIAZINON	ND	ug/L	0.2	0.2	1	
	B EPTC	ND	ug/L	0.3	0.3	!	
6	2 4,4-DDD	ND	ug/L	0.2	0.2		

[&]quot;An amount of "ND" indicates that the compound was not detected above the Lab's Method Detection Limit - MDL. minant in water established by EPA, NPOWR. State Advisory Level (SAL) for Unregulated compounds. -- Maximum Contaminant Level, maximum permissible level of a conta

A blank MCL or SAL value indicates a level is not currently established.

⁻ If a compound is detected > or = to the State Reporting Level, SRL, specified increased monitoring frequencies may occur per DOH. -- Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 95% confidence that the compound concentration is greater than zero.

J - Estimated value.



Agricultural - Industrial - Environmental

INVOICE # INVOICE DATE

04-04-361 04/23/04

- Ama

CLIENT #

WWB2170

PURCHASE ORDER#

Client: W.W.B.W.C.

Address: PO Box 68

MiltonFreewater, OR 97862

PN :

Project:

Sampler: Bob Bower

Grower:

KPENO	крсмо крсласе	Fleid identifier	Test	Description	Qty	Price	Extension
E70292	04/14/04	Intake, Well #1	A26-1	SOC/Synthetic Organic Compounds	2	815.40	1,630.

Notes: 04-04-361

Invoice Total

1630.80

Discount

0 %

-0.00

FAX Charge

Invoice Total Due

\$1,630.80

0.00

Due Date

Terms: Net 30 days following date of invoice. Invoices not paid in 30 days will be subject to interest charged at 1.5% per month (18% per year) with a minimum charge of 50 cents.

05/23/04

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free

Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

DATE COLLECTED

DATE RECEIVED

DATE REPORTED

5/21/2004

SEND REPORT TO: 5/21/2004

6/17/2004

W.W.B.W.C. PO Box 68

SYSTEM / CUSTOMER

Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

SAMPLE NO

CUSTOMER

ge Analytical
-
+
1

(001): indicates the analyte was not detected at or above the concentration indicated.

None Detected

.Indicates milligrams per litre

* 2QL=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions MDL: Method Detection Limit

Please check out our new Web Site at http://www.kuotesting.com

Eugene Kuo, Quality Assurance Coordinator

06-18-04





11525 Knudson Rd.

Burlington, WA 98233

(800) 755-9295

(360) 757-1400 - FAX (360) 757-1402

Page 1 of 1

HERBICIDES IN DRINKING WATER

Client Name: KUO Testing Labs Inc

337 S 1st

Othello, WA 99344

System Name:

System ID Number:

Multiple Sources:

DOH Source Number:

Reference Number: 04-3844

Project: WWBWC/SOC

Field ID: 70882

Lab Number: 04607654

Date Collected: 5/21/2004 Date Extracted: 515 040602

Date Analyzed: 6/7/2004

Report Date: 6/9/2004

Analyst: CMH

Supervisor:

Sample Location: OBS Well #1 County: Umatilla

Sample Type: B - Before treatment Sample Purpose: Investigative or Other

OH#	COMPOUNDS	RESULTS	Units	SRL	Trigger	MCL	COMMENT
	EPA Regulated						
37	2,4 - D	ND	ug/L	0.2	0.2	70	
38	2,4,5 - TP (SILVEX)	ND	ug/L	0.4	0.4	50	
134	PENTACHLOROPHENOL	ND	ug/L	0.08	0.08	1	
137	DALAPON	ND	ug/L	2	2	200	
139	DINOSEB	ND	ug/L	0.4	0.4	7	
140	PICLORAM	ND	ug/L	0.2	0.2	500	
	EPA Unregulated						
138	DICAMBA	ND	ug/L	0.2	0.2		
	State Unregulated						
	2,4 DB	ND	ug/L	1	1.0		
136	2,4,5 T	ND	ug/L	0.4	0.4		
220	BENTAZON	ND	ug/L	0.5	0.5		
221	DICHLORPROP	ND	ug/L	0.5	0.5		
223	ACTIFLORFIN	ND	ug/L	2	2.0		
225	DACTHAL (DCPA)	ND	ug/L	0.1	0.1		
226	3,5 - DICHLOROBENZOIC ACID	ND	ug/L	0.5	0.5		
					111,4		

^{*-} An amount of "ND" indicates that the compound was not detected above the Lab's Method Detection Limit - MDL.

FORM: SOC97

^{**-} Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds.

A blank MCL or SAL value indicates a level is not currently established.

***- If a compound is detected > or = to the State Reporting Level, SRL, specified increased monitoring frequencies may occur per DOH.

^{****-} Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.

J - Estimated value.



11525 Knudson Rd.

Burlington, WA 98233

(800) 755-9295

(360) 757-1400 - FAX (360) 757-1402

Page 1 of 2

SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

Client Name: KUO Testing Labs Inc

337 S 1st

Othello, WA 99344

System Name:

System ID Number:

DOH Source Number:

Multiple Sources:

Sample Type: B - Before treatment

Sample Type: D - De

Sample Purpose: Investigative or Other

Sample Location: OBS Well #1

County: Umatilla

Reference Number: 04-3844

Project: WWBWC/SOC

Field ID: 70882

Lab Number: 04607654

Date Collected: 5/21/2004

Date Extracted: 5/21/2004

Date Extracted: 525 040601

Data Analysis 6

Date Analyzed: 6/2/2004

Report Date: 6/7/2004

Analyst: CMH

Supervisor:

EPA Method 525.2 For State Drinking Water Compliance

OOH#	COMPOUNDS	RESULTS	Units	SRL	Trigger	MCL	COMMENT
	EPA Regulated						
33	ENDRIN	ND	ug/L	0.02	0.02	2	
34	LINDANE (BHC - GAMMA)	ND	ug/L	0.04	0.04	0.2	
35	METHOXYCHLOR	ND	ug/L	0.2	0.2	40	
117	ALACHLOR	ND	ug/L	0.4	0.4	2	
119	ATRAZINE	ND	ug/L	0.2	0.2	3	
120	BENZO(A)PYRENE	ND	ug/L	0.04	0.04	0.2	
122	CHLORDANE, TECHNICAL	ND	ug/L	0.4	0.4	2	
124	DI(ETHYLHEXYL)-ADIPATE	ND	ug/L	1.3	1.3	400	
125	DI(ETHYLHEXYL)-PHTHALATE	ND	ug/L	1.3	1.3	6	
126	HEPTACHLOR	ND	ug/L	0.08	0.08	0.4	
127	HEPTACHLOR EPOXIDE (A&B)	ND	ug/L	0.04	0.04	0.2	
128	HEXACHLOROBENZENE	ND	ug/L	0.2	0.2	1	
129	HEXACHLOROCYCLO-PENTADIENE	ND	ug/L	0.2	0.2	50	
133	SIMAZINE	ND	ug/L	0.15	0.15	4	
	EPA Unregulated						
118	ALDRIN	ND	ug/L	0.2	0.2		
121	BUTACHLOR	ND	ug/L	0.4	0.4		
123	DIELDRIN	ND	ug/L	0.2	0.2		
130	METOLACHLOR	ND	ug/L	1	1.0		
131	METRIBUZIN	ND	ug/L	0.2	0.2		
132	PROPACHLOR	ND	ug/L	0.2	0.2		
	State Unregulated - Other						
179	BROMACIL	ND	ug/L	0.2	0.2		
183	PROMETON	ND	ug/L	0.2	0.2		
190	TERBACIL	ND	ug/L	0.2	0.2		
202	DIAZINON	ND	ug/L	0.2	0.2		
208	EPTC	ND	ug/L	0.3	0.3		
232	4,4-DDD	ND	ug/L	0.2	0.2		

^{*-} An amount of "ND" indicates that the compound was not detected above the Lab's Method Detection Limit - MDL.

FORM: SOC97

^{**-} Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds. A blank MCL or SAL value indicates a level is not currently established.

^{***-} If a compound is detected > or = to the State Reporting Level, SRL, specified increased monitoring frequencies may occur per DOH.

^{****-} Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.

J - Estimated value.





Reference Number: 04-3844

Lab Number: 04607654 Report Date: 6/7/2004

SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

H#	COMPOUNDS	RESULTS	Units	SRL	Trigger	MCL	COMMENT
233	4,4-DDE	ND	ug/L	0.2	0.2		
234	4,4-DDT	ND	ug/L	0.2	0.2		
236	CYANAZINE	ND	ug/L	0.2	0.2		
239	MALATHION	ND	ug/L	0.2	0.2		
240	PARATHION	ND	ug/L	0.2	0.2		
243	TRIFLURALIN	ND	ug/L	0.2	0.2		
	- PAHs						
96	NAPTHALENE	ND	ug/L	0.1	0.1		
154	FLUORENE	ND	ug/L	0.2	0.2		
244	ACENAPHTHYLENE	ND	ug/L	0.2	0.2		
245	ACENAPHTHENE	ND	ug/L	0.2	0.2		
246	ANTHRACENE	ND	ug/L	0.2	0.2		THE RESERVE
247	BENZ(A)ANTHRACENE	ND	ug/L	0.1	0.1		
248	BENZO(B)FLUORANTHENE	ND	ug/L	0.2	0.2		
249	BENZO(G,H,I)PERYLENE	ND	ug/L	0.2	0.2		
250	BENZO(K)FLUORANTHENE	ND	ug/L	0.2	0.2		
251	CHRYSENE	ND	ug/L	0.2	0.2		
252	DIBENZO(A,H)ANTHRACENE	ND	ug/L	0.2	0.2		
253	FLUORANTHENE	ND	ug/L	0.2	0.2		
255	INDENO(1,2,3-CD)PYRENE	ND	ug/L	0.2	0.2		
256	PHENANTHRENE	ND	ug/L	0.2	0.2		
257	PYRENE	ND	ug/L	0.2	0.2		
	- Phthalates						
258	BENZYL BUTYL PHTHALATE	ND	ug/L	0.6	0.6		
259	DI-N-BUTYL PHTHALATE	ND	ug/L	0.6	0.6		
	DIETHYL PHTHALATE	ND	ug/L	0.6	0.6		
261	DIMETHYL PHTHALATE	ND	ug/L	0.6	0.6		
				1			
		7					

^{*-} An amount of "ND" indicates that the compound was not detected above the Lab's Method Detection Limit - MDL.

*-- Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds. A blank MCL or SAL value indicates a level is not currently established.

***- If a compound is detected > or = to the State Reporting Level, SRL, specified increased monitoring frequencies may occur per DOH.

***- Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.

J - Estimated value.



11525 Knudson Rd.

Burlington, WA 98233

(800) 755-9295

(360) 757-1400 - FAX (360) 757-1402

Page 1 of 1

SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

Client Name: KUO Testing Labs Inc

337 S 1st

Othello, WA 99344

System Name:

System ID Number: DOH Source Number:

Multiple Sources:

Reference Number: 04-3844

Project: WWBWC/SOC

Field ID: 70882

Lab Number: 04607654 Date Collected: 5/21/2004

Date Extracted: 508_040601

Date Analyzed: 6/9/2004 Report Date: 6/11/2004

Analyst: CMH

Supervisor:

Sample Type: B - Before treatment Sample Purpose: Investigative or Other

Sample Location: OBS Well #1 County: Umatilla

EPA Method 508.1 For State Drinking Water Compliance

DOH#	COMPOUNDS	RESULTS	Units	SRL	Trigger	MCL	COMMENT
	PCBs/Toxaphene						
36	TOXAPHENE	ND	ug/L	2	2	3	
173	AROCLOR 1221	ND	ug/L	20	20		
174	AROCLOR 1232	ND	ug/L	0.5	0.5		
175	AROCLOR 1242	ND	ug/L	0.5	0.3		
176	AROCLOR 1248	ND	ug/L	0.1	0.1		
177	AROCLOR 1254	ND	ug/L	0.1	0.1		
	AROCLOR 1260	ND	ug/L	0.2	0.2		
180	AROCLOR 1016	ND	ug/L	0.1	0.1		
			-				
					4		

^{*-} An amount of "ND" indicates that the compound was not detected above the Lab's Method Detection Limit - MDL.

^{**-} Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds. A blank MCL or SAL value indicates a level is not currently established.

^{***-} If a compound is detected > or = to the State Reporting Level, SRL, specified increased monitoring frequencies may occur per DOH.

^{****-} Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.

J - Estimated value.



11525 Knudson Rd.

Burlington, WA 98233

(800) 755-9295

(360) 757-1400 - FAX (360) 757-1402

Page 1 of 1

CARBAMATES IN DRINKING WATER

Client Name: KUO Testing Labs Inc

337 S 1st

Othello, WA 99344

System Name:

System ID Number:

DOH Source Number:

Reference Number: 04-3844

Project: WWBWC/SOC

Field ID: 70882

Lab Number: 04607654 Date Collected: 5/21/2004 Date Extracted: 531 040603

Date Analyzed: 6/3/2004 Report Date: 6/8/2004

Analyst: TW


Supervisor:

Multiple Sources: Sample Type: B - Before treatment Sample Purpose: Investigative or Other

Sample Location: OBS Well #1

County: Umatilla

EPA Method 531.1 For State Drinking Water Compliance



^{*-} An amount of "ND" indicates that the compound was not detected above the Lab's Method Detection Limit - MDL

^{**-} Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds. A blank MCL or SAL value indicates a level is not currently established.

^{***-} If a compound is detected > or = to the State Reporting Level, SRL, specified increased monitoring frequencies may occur per DOH.

^{****} Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.

J - Estimated value.

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

a 114 ° Millioner	5/21/2004	ST-WO RET		21/2004	0A7E REFORTED 6/17/2004
W.W.B.W.C. PO Box 68 Milton Freewater OR Project Name:	97862	Bob F PO Bo Milton Attn:	ox 68 n Freewater	OR	97862
43 1 60	Awat Kajiri	PESULIS	. N.C.	, N. T.S.	ANALYSTS
70882 OBS Well #1	SOC/Synthetic Organic Co	Report		mg/L	Edge Analytical
	The state of the s				

(0.001)* unificates the analyte was not detected at or above the concentration indicated.
 ND. None Detected
mg/Lindicates milligrams per litre

 PQL-Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during (making laboratory operating conditions)

MDI Method Detection Limit

Dr. Eugene Kuo, Quality Assurance Coordinator

06-18-04 Date



11525 Knudson Rd. Burlington, WA 98233

(800) 755-9295

(380) 757-1400 - FAX (360) 757-1402

Page 1 of 1

HERBICIDES IN DRINKING WATER

Client Name. KUO Testing Labs Inc.

337 S 1st

Othello, WA 99344

System Name:

System ID Number:

DOH Source Number: Multiple Sources:

Sample Type: B - Before treatment

Sample Purpose: Investigative or Other

Sample Location: OBS Well #1

County: Umatilla

Reference Number: 04-3844

Project: WWBWC/SOC

Field ID: 70882

Lab Number: 04607654

Date Collected: 5/21/2004

Date Extracted: 515_040602

Date Analyzed: 6/7/2004

Report Date: 6/9/2004

Analyst: CMH

Supervisor:

OH#	COMPOUNDS	RESULTS	Units	SRL	Trigger	MCL.	COMMENT	
	EPA Regulated			*				
37	2,4 - D	ND	UQ/L	0.2	0.2	70		
38	2,4,5 - TP (SILVEX)	ND	ug/L	0.4	0.4	50		
134	PENTACHLOROPHENOL	ND	ug/L	80.0	0.08	1		
137	DALAPON	ND	ug/L	2	2	200		
139	DINOSER	ND	ug/L	0.4	0.4	7 -		
140	PIOLORAM	ND	ψg/L	0.2	0.2	500		
	EPA Unregulated							
138	DICAMBA	ND	ug/L	0.2	0.2			
	State Unregulated							
	2,4 DB	ND	ug/L	1	1.0			
136	2,4,5 T	ND	ug/L	0.4	0.4			
220	BENTAZON	ND	ug/L	0.5	0.5			
221	DICHLORPROP	ND	ug/L	0.5	0.5			
223	ACTIFLORFIN	ND	∪g/L	2	2.0	11		
225	DACTHAL (DCPA)	ND	ug/L	0.1	0.1			
226	3,5 - DICHLOROBENZOIC ACID	ND	ug/L	0.5	0.5			
			8	9				
				4				
			Ē				# ve	
				4				
			1				1	
				d .				

J - Estimated value.

FORM: SOCAT

^{*} An amount of "NO" indicates that the compound was not detected above the Lab's Mathod Detection Limit - MOL.
** Maximum Contaminant Level, maximum permisable level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds. A blank MCL or SAL value indicates a level is not currently established.



11525 Knudson Rd Burlington, WA 98233 (800) 755-9295 (360) 757-1400 - FAX (360) 757-1402

Page 1 of 2

SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

Client Name: KUO Testing Labs Inc.

337 S 1st

Othello, WA 99344

System Name:

System ID Number:

DOH Source Number:

Multiple Sources:

Sample Type: B - Before treatment

Sample Purpose: Investigative or Other

Sample Location: OBS Well #1

County: Umatilla

Reference Number: 04-3844

Project WWBWC/ \$OC

Field ID: 70882

Lab Number: 04607654

Date Collected: 5/21/2004

Date Extracted: 525_040601

Date Analyzed: 6/2/2004

Report Date: 6/7/2004

Analyst: CMH

Supervisor:

EDA Method 525 2 For State Drinking Water Compliance

DH#	COMPOUNDS	RESULTS	Units	SRL	Trigger	MCL	COMMENT	
	EPA Regulated	MAY MANAGED AS SHOWN						
33	ENDRIN	ND	ug/L	0.02	C.02	2		
34	LINDANE (BHC - GAMMA)	ND	ug/L	0.04	0.04	0.2		
35	METHOXYCHLÖR	ND	ug/L	0.2	0.2	40		
117	ALACHLOR	ND	ug/L	0.4	0.4	2		
110	AYRAZINE	ND	ug/L	0.2	0.2	3		
120	BENZO(A)PYRENE	ND	ug/L	0.04	0.04	0.2		
122	CHLORDANE, TECHNICAL	ND	ug/L	0.4	0.4	2		
124	DI(ETHYLHEXYL)-ADIPATE	ND	ug/L	1.3	1.3	400		
125	DI(ETHYLHEXYL)-PHTHALATE	ND	ug/L	1.3	1.3	6		
126	HEPTACHLOR	ND	ug/L	0.08	0.08	0.4		
127	HEPTACHLOR EPOXIDE (A&B)	ND	ug/L	0.04	0.04	C.2		
128	HEXACHLOROBENZENE	ND	υφΛ	0.2	0.2	1		
129	HEXACHLOROCYCLO-PENTADIENE	NO	ug/L	0.2	0.2	50		
133	SIMAZINE	ND	ug/L	0.15	0.15	4		
	EPA Unregulated	19						
118	ALDRIN	ND	ug/L	0.2	0.2			
121	BUTACHLOR	ND	ug/L	0.4	0.4			
123	DIELDRIN	ND	ug/L	0.2	0.2	11 04		
130	METOLACHLOR	ND	Lg/L	1	1.0			
131	METRIBUZIN	ND	ug/L	02	0.2			
132	PROPACHLOR	ND	ug/L	0.2	0.2			
	State Unregulated - Other							
179	BROMACIL	ND	. ug/L	0.2	0.2			
183	PROMETON	ND	ug/L	0.2	0.2			
190	TERBACIL	ND	Lg/L	0.2	0.2			
	DIAZINON	ND	ug/L	0.2	0.2			
208	EPTC	ND	ug/L	0.3	0.3	1		
232	4,4-DDD	ND	ug/L	0.2	0.2			

FORM: SOCH!

^{*}An amount of Tith' Exicates that the compound was not detected above the Lad's Method Detection Limit - ArCL,

**Maximum Contaminant Level, maximum permise bia level of a contaminant in water established by EPA, NPDWR—State Advisory Level (BAL) for Unregulated compounds.

A blank MCL or SAL value indicates a level is not currently established.

^{***} If a compound is defected a review on content of seasons read.

*** If a compound is defected a review of the State Reporting Level, SNL, specified increased inoritioning frequencies may occur per DOH.

**** If a compound is defected a review of the State Reporting Level, SNL, specified increased inoritioning frequencies may occur per DOH.

***** Method Detection Limit is the labble minimum concentration is greater than zero.

Page 2 of 2



Reference Number: 04-3844

Lab Number: 04607654 Report Date 6/7/2004

CVAITHETIC ODCANIC COMPOLINDS (SOC) PEPORT

H#	COMPOUNDS	RESULTS	Units	SRL	Trigger	MCL	COMMENT	
233	4.4-DDE	NO	ug/L	0.2	0.2			
234	4,4-DDT	ND	ug/L	0.2	0.2			
236	CYANAZINE	ND	ug/L	0.2	0.2			
239	MALATHION	ND	ug/L	0.2	0.2			
240	PARATHION	ND	ug/L	0.2	0.2			
243	TRIFLURALIN	NĎ	ug/L	0.2	0.2			
	- PAHs							
96	NAPTHALENE	ND	ug/L	0.1	0.1			
154	FLUORENE	ND	ug/L	0.2	0.2			
244	ACENAPHTHYLENE	ND	JQ/L	0.2	0.2	1		
245	ACENAPHTHENE	ND	ugA	0.2	0.2			
246	ANTHRACENE	ND	ug/L	0.2	0.2			
247	BENZ(A)ANTHRACENE	NO	ug/L	0.1	0.1			
248	BENZO(B)FLUORANTHENÉ	ND	ψg/L	0.2	0.2			
249	BENZO(G,H,I)PERYLENE	ND	ug/L	0.2	0.2			
250	BENZO(K)FLUORANTHENE	NO	Jg/L	0.2	0.2		ti .	
251	CHRYSENE	ND	ug/L	0.2	0.2			
252	DIBENZO(A,H)ANTHRACENE	MD	ug/L	0.2	0.2			
253	FLUORANTHENE	ND	· ug/L	0.2	0.2			
255	INDENO(1,2,3-CD)PYRENE	ND	ugh	0.2	0.2			
256	PHENANTHRENE	ND	ug/L	0.2	0.2		4	
257	PYRENE	ND	'ug/L	0.2	0.2			
	- Phthalates	i i				10	(1)	
258	BENZYL BUTYL PHTHALATE	מא	ug/L	0.6	0.8	4		
259	OI-N-BUTYL PHTHALATE	ND	ugAL	0.6	0.6	1	R	
260	DIETHYL PHTHALATE	ND	ug/L	0.6	0.6			
261	DIMETHYL PHTHALATE	ND	ug/L	0.6	0.6			
					*	海		
			G H		ì			

<sup>An amount of "NO" indicates that the compound was not delected above the Let's Method Defection Limit - MOL.

*** Maximum Contaminant Level, maximum parmissible lavel of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds.

A blank MCL or SAL value indicates a level is not currently established.

*** At a compound is detected > or a to the State Reporting Level, SRL, specified increased monitoring frequencies may occur per DOH.

****- Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 95% confidence that the compound concentration is greater than zero.

J - Estimated value.</sup>



11525 Knudson Rd. Burington, WA 98233 (800) 755-9295 (360) 757-1400 · FAX (360) 757-1402

Page 1 of 1

SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

Client Name: KUO Testing Labs Inc.

337 S 1st

Othello, WA 99344

System Name:

System ID Number:

DOH Source Number:

Multiple Sources:

Sample Type: B - Before treatment Sample Purpose: Investigative or Other

Sample Location: OBS Well #1

County: Umatilla

Reference Number: 04-3844

Project WWBWC/SOC

Field ID. 70882

Lab Number: 04607654

Date Collected: 5/21/2004

Date Extracted: 508_040601

Date Analyzed: 6/9/2004

Report Date: 6/11/2004

Analyst: CMH

Supervisor: -

#HOC	COMPOUNDS	RESULTS	Units	SRL	Trigger	MCL	COMMENT	
	PCBs/Toxaphene		a Selection of the Sele					VI-10
36	TOXAPHENE	ND	ug/L	2	2.	3		
173	AROCLOR 1221	ND	ug/L	20	20			
174	AROCLOR 1232	מא	ug/L	0.5	0.5	5		
175	AROCLOR 1242	ND	ug/L	0.5	0.3			
176	AROCLOR 1248	ND	Ug/L	0.1	0.1			
177	AROCLOR 1254	ND	ug/L	0.1	0.1			
178	AROCLOR 1260	ND	ug/L	0.2	0.2			
180	AROCLOR 1016	ND	ug/L	0.1	0.1			
						ti.		
				2				
							T.	
		4						
		1						
		:						
				- 1				
		1				0	2	
	<i>l</i>	1				Di Di		
		7						
4		1					¥ ×	
				1				
	Varing called that the compound was not deli-		OTHER STREET,					1 + 44



11525 Knudson Rd. Burlington, WA 98233 (800) 755-9295 (360) 757-1400 - FAX (360) 757-1402

Page 1 of 1

CARBAMATES IN DRINKING WATER

Client Name: KUO Testing Labs Inc.

337 S 1st

Othello, WA 99344

System Nama:

System ID Number: DOH Source Number:

Multiple Sources:

Sample Type: B - Before treatment Sample Purpose: Investigative or Other

Sample Location: OBS Well #1

County: Umatilla

Reference Number: 04-3844

Project: WWBWC/SOC

Field ID: 70882

Lab Number: 04607654 Date Collected: 5/21/2004

Date Extracted: 531_040603 Date Analyzed: 6/3/2004

Report Date: 6/8/2004 Analyst: TW

Supervisor:

EPA Method 531.1 For State Drinking Water Compliance

DOH#	COMPOUNDS	RESULTS	Units	SRL *	Trigger	MCL	COMMENT
	EPA Regulated					1.	
146	CARBOFURAN	ND	ug/L	1.8	1.8	40	
148	OXYMAL	ND	· ug/L	4	4.0	200	
	EPA Unregulated					10	
141	3-HYÖRÖXYCARBOFURAN	ND	· ug/L	2	2.0	1	T:
142	ALDICARB	ND	ug/L	1	1.0		1
143	ALDICARB SULFONE	ND	ug'L	1.6	1.6		
144	ALDICARB SULFÓXIDE	ND	uģ/L	1	1.0		
145	CARBARYL	ND	ug/L	2	2.0		20
147	METHOMYL	ND	ug/L	1	4.0	:H	
	State Unregulated - Other				,		
326	PROPOXUR (BAYGON)	ND	ug/L	1			
327	METHIOCARB	ND	ug/L	4			
							le z
	ŧ						

^{*} An amount of "NO" indicates that the compound was not detected above the Cat's Method Detection Limit - MDL.

^{***} Maximum Contaminant Lava: insuring permissible level of a contentiant in water established by EPA, NPDVR. State Advisory Level (SAL) for Unrequisited compounds. A brank MCL or SAL value indicates a level in nor currently established.
**** If a compound is detected > or ≥ to the State Reporting Level, SRL, specified increased monitoring frequencies may occur per DOH.
***** A tripled Detection Limit is the set's minimum concentration is greater than zero.
***** A tripled Detection Limit is the set's minimum concentration is greater than zero.

04-05-272 05/14/04

WWB2170

INVOICE DATE

CLIENT#

INVOICE #

PURCHASE ORDER#



Kuo Testing Labs, Inc. Agricultural - Industrial - Environmental

(509) 488-0112; Fax (509) 488-0118 Othello, Washington 99344

W.W.B.W.C. Client:

Address: PO Box 68

MiltonFreewater, OR 97862

PN:

Project:

Grower:

Sampler: Bob

RptNo RptDate	e Field Identifier	Test	Description	Qty	Price	Extension
70637 05/07/04	OBS Well #1,OBS Well #3	FECAL	Fecal Coliform	K	67.50	135.00

06/13/04	Due Date 06
\$135.00	Invoice Total Due
00.00	FAX Charge
-0.00	Discount 0 %
135.00	Invoice Total

Terms: Net 30 days following date of invoice. Invoices not paid in 30 days will be subject to interest charged at 1.5% per month (18% per year) with a minimum charge of 50 cents.

Notes: 04-05-272

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

DATE	COLLE	ECT	ED
5/7/2	2004		

DATE RECEIVED

5/7/2004

DATE REPORTED

SEND REPORT TO:

5/12/2004

SYSTEM / CUSTOMER W.W.B.W.C.

PO Box 68

SAMPLE NO.

Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

CUSTOMER ANALYSIS SAMPLE NO RESULTS UNITS ANALYSTS OBS Well #1 70637 Fecal E-Coli CFU/100ml Valley Labs

<(0.001):	indicates the analyte was not	detected at or above the concentration indicated.
-----------	-------------------------------	---

.: Indicates milligrams per litre

* PQL=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

MDL: Method Detection Limit

Please check out our new Web Site at http://www.kuotesting.com

05-12-04

Dr. Eugene Kuo, Quality Assurance Coordinator

Date

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free http://www.kuotesting.com e-mail: kuotest@atnet.net Web Site:

DATE COLLECTED

DATE RECEIVED

DATE REPORTED

5/7/2004

SEND REPORT TO

5/7/2004

5/11/2004

SYSTEM / CUSTOMER W.W.B.W.C.

PO Box 68

Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

SAMPLE NO. CUSTOMER SAMPLE NO	ANALYSIS	RESULTS	MDL.	UNITS	ANALYSTS
70638 OBS Well #3	Fecal E-Coli	2	2	CFU/100ml	Valley Labs
	the state of the s				
-					

<(0.001)·	indicates the applies up	s not detected at a	s about the consentration	ion indicated
<(0.001):	indicates the analyte wa	s not detected at of	r above the concentrat	ion indicated.

None Detected

:Indicates milligrams per litre

¿L=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

MDL: Method Detection Limit

Please check out our new Well Site at http://www.kuotesting.com

05-11-04

0		Washington NT of Healt		0	30 j
	BACTERIO	LOGICA	LANAL		
	non: read instru Filone are not folia				XXP

DATE COLLECTED THAT COLL	TANKS LOOKEN	A A A A A A A A A A A A A A A A A A A
MONTH DAY TEAR	ECTED COUNTY	Lesdaill
4/13/14 1911	TIPM //M/	afilla
TYPE OF SYSTEM OF PUBLIC SYSTEM.	land I was	wwa
TRUBLIC POST	and excellent property and a series of the	1 AUDO: T. ADDULT
INDIVIDUAL [I.D. No.]		CIRCLE GROUP
(serves only 1 residence)	OF SECURIOR SHARES (SAFE SOCIAL)	mend A D
NAME OF SYSTEM		
HOTA shows	no Raina	alan-
SPECIFIC LOCATION WHERE SAMPLE COLLECTE	OF LIGHTONE MO	L
to make an overlanding and the street, and debrach the	DAY FYS) E	12 25 26L
. 4.		and the same of th
(1001) =	EVENING 84	938-200
SAMPLE COLLECTED BY: (Name)	SYSTEM OWNER	MGR.: (Name)
: Bundy	HADIC IN	DOBLOC
SOURCE TYPE GROUND WATER UN		
SURFACE WELL OF SPRIN	G PURCHASE	D or COMBINATIO
SEND REPORT TO: (Print Full Name, Address	INTERTIE	or OTHER
POTENTIAL TO CHARLES PRIME, MOC1930	a marach (4556)	
CONTROL OF THE PARTY OF THE PAR		
	WASHER	ron
TYPE OF SAMPLE (check only one in this or	piumn)	
DRINKING WATER	Norinated (Residual:	Total Free)
check vesiment	kered	
900.00	mer and	
The state of the s	ntreated or Other	THE PARTIES OF THE PARTY OF THE PARTY.
REPEAT SAMPLE Previous coliform presence Lab #_		
REPEAT SAMPLE		
PREPEAT SAMPLE Previous colliform presences Lab #		
REPEAT SAMPLE Previous collions presence Lab #	ntreated or Other	Total Colliorm
Previous colliform presence Lab #	ntrealed or Other	Total Colform
Previous collectin presences Lab #	ntrealed or Other	
PREPERT SAMPLE Previous collidate presences Lab #	ntrealed or Other	
PREPERT SAMPLE Previous collidate presences Lab #	ntrealed or Other	
PREPERT SAMPLE Previous colliform presences Lab #	ntrealed or Other	Fecal Costoms
Previous coliform presence Lab #	ntrealed or Other	Feeal Costom
PREPEAT SAMPLE Previous collidate presence Lab # Date Date PAW-SOURCE WATER Source NEW CONSTRUCTION or REPAIRS OTHER (Specify) LAB USE ONLY) DRIN UNSATISFACTORY, Californe present	e # S S	Feeal Costom
PREPEAT SAMPLE Previous coliform presence Lab # Date Date PAW-SHIPPE WATER Source NEW CONSTRUCTION or REPAIRS OTHER (Specity) EMARKS: (LAS USE ONLY) DRIN LINSATISFACTORY, Cellorme present REPEAT SAMPLES	e # S S SKING WATER RES	Feeal Colform
REPEAT SAMPLE Previous colliform presence Lab # Date Date PAW-Selence WATER Source NEW CONSTRUCTION or REPAIRS OTHER (Specify) EMARKS: (LAS USE ONLY) DRIN UNSATISFACTORY, Celloring present REPEAT Cost present REPEAT SAMPLES REQUIRED Feesel present	e / S Coli absent	Feeal Colform
PREPEAT SAMPLE Previous coliform presence Lab # Date Date PAW-SHIPPE WATER Source NEW CONSTRUCTION or REPAIRS OTHER (Specity) EMARKS: (LAS USE ONLY) DRIN LINSATISFACTORY, Cellorme present REPEAT SAMPLES	e / S Coli absent	Feeal Costom
PREPEAT SAMPLE Previous collidate presence Lab # Deto PAWESHARE WATER Source NEW CONSTRUCTION of REPAIRS OTHER (Specify) (LAB USE ONLY) DRIN LINSATISFACTORY, Califorms present REPEAT SAMPLES REQUIRED OTHER LABORA TOTAL COUPORM	INTERIOR PRESULTS E. COLI	Feeal Costoms #LTS SATISFACTORY, Costoms absent
REPEAT SAMPLE Previous collidate presence Lab # Deto PAW-SOURCE WATER Source NEW CONSTRUCTION of REPAIRS OTHER (Specify) LINSATISFACTORY, Califorms present REPEAT SAMPLES REQUIRED Feet present OTHER LABORA TOTAL COUPORM //100 mi	e # S	Feeal Colform A.TS SATISFACTORY, Colforms absent
PREPEAT SAMPLE Previous collidate presence Lab # Deto PAWESHARE WATER Source NEW CONSTRUCTION of REPAIRS OTHER (Specify) (LAB USE ONLY) DRIN LINSATISFACTORY, Califorms present REPEAT SAMPLES REQUIRED OTHER LABORA TOTAL COUPORM	e # S	Feeal Colform A.TS SATISFACTORY, Colforms absent
REPEAT SAMPLE Previous colliform presence Lab # Deto PAW-SHARE WATER Source NEW CONSTRUCTION or REPAIRS CTHER (Spesity) EMARKS: (LAB USE ONLY) DRIN LINSATISFACTORY, Celforms present AEPEAT SAMPLES REQUIRED Fees present OTHER LABORA TOTAL COUPORM /100 mi FECAL COLIFORM /100 mi	E. Coli absent Poel seens E. Coli periori Plate Count Plate Count Plate Count Plate Count	Feeal Colform A.TS SATISFACTORY, Colforms absent
REPEAT SAMPLE Previous colliform presence Lab # Deto PAW-SHARE WATER Source NEW CONSTRUCTION or REPAIRS CTHER (Spesity) EMARKS: (LAB USE ONLY) DRIN LINSATISFACTORY, Celforms present AEPEAT SAMPLES REQUIRED Fees present OTHER LABORA TOTAL COUPORM /100 mi FECAL COLIFORM /100 mi	ECOLI PLATE COUNT TEST UNIS	Feeal Colform ILTS SATISFACTORY, Colforms absent
REPEAT SAMPLE Previous colliform presence Lab # Deto PAW-SHERCE WATER Source NEW CONSTRUCTION or REPAIRS CTHER (Spesity) EMARKS: (LAB USE ONLY) DRIN LINSATISFACTORY, Celforms present REPEAT SAMPLES REQUIRED Feed present OTHER LABORA TOTAL COUPORM /100 mi FECAL COLIFORM /100 mi ANOTHER SAM SAMPLE NOT TESTED SECAUSE:	ECOLI PLATE COUNT TEST UNIS	Feeal Colform ILTS SATISFACTORY, Colforms absent /100ml /mi
REPEAT SAMPLE Previous colliform presence Lab # Date Date PAW-Selence Water Source New Construction of Repairs CTHER (Specify) LINEATISFACTORY, Celloring present REPEAT SAMPLES REQUIRED Fees present OTHER LABORA TOTAL COUPORM /100 mi FECAL COUPORM /100 mi ANOTHER SAM SAMPLE NOT TESTED SECAUSE: Sample too old	E. Coli absent Fotel absent FOTEL FEGURED TEST UNIS TURN TURN TURN TURN TURN TURN TURN TUR	Feeal Costorm R.TS SATISFACTORY, Costorms absent /100mil /mil LITABLE BECAUSE: Ruent growth C id culture
REPEAT SAMPLE Previous colliform presence Lab # Date Date PAW-Selence WATER Source New Construction or REPAIRS OTHER (Spesily) EMARKS: (LAS USE ONLY) DRIN LINSATISFACTORY, Cellorms present REPEAT SAMPLES REQUIRED Fees present OTHER LABORA TOTAL COUPORM /100 mi FECAL COLIFORM /100 mi ANOTHER SAM SAMPLE NOT TESTED SECAUSE: Sample too old Wrong container	E. Coli absent Fotel absent FOTEL FEGURED TEST UNIS TURN TURN TURN TURN TURN TURN TURN TUR	Feeal Colform A.TS SATISFACTORY, Colforms absent /100ml /mi UITABLE BECAUSE: Ruent growth C
REPEAT SAMPLE Previous colliform presence Lab # Deto PAM-SHARES WATER Source NEW CONSTRUCTION or REPAIRS OTHER (Specify) EMARKS: (LAS USE ONLY) DRIN LINSATISFACTORY, Califorms present AMPLES REQUIRED Feest present OTHER LABORA TOTAL COUPORM /100 mi FECAL COLIFORM /100 mi ANOTHER SAM SAMPLE NOT TESTED SECAUSE: Sample too old Wrong container Incomplets form	E. COLI PLATE COUNT TEST UNS TOTAL TOTAL TOTAL TOTAL TOTAL TOTAL EXCEL EXCEL TEST UNS TOTAL TOTAL EXCEL EXCEL TOTAL TOTAL EXCEL EXCEL EXCEL TOTAL EXCEL EXC	Feeal Costom A.TS SATISFACTORY, Colliforms absent //icomi /mi /ini LittaBLE BECAUSE: Ruent growth C id culture loss debris
REPEAT SAMPLE Previous coliform presence Lab # Date Date PANI-SHIPEE WATER Source NEW CONSTRUCTION of REPAIRS CITHER (Specify) LINEATISFACTORY, Cellorme present REPEAT SAMPLES REQUIRED Feest present OTHER LABORA TOTAL COUPORM /100 mi FECAL COLIFORM /100 mi ANOTHER SAM SAMPLE NOT TESTED SECAUSE: Sample too old Wrong container Incomplete form SEE REVERSE SIDE OF GREEN CO	ECOLI PLATE COUNT TEST UNS TYPE FOR EXPLANATE FY FOR EXPLANATE CONT EXCE FY FOR EXPLANATE CONT EXCE FY FOR EXPLANATE CONT EXCE FY FOR EXPLANATE CONT EXCE FY FOR EXPLANATE CONT EXCE FY FOR EXPLANATE CONT EXCE FY FOR EXPLANATE FY FY FY FY FY FY FY FY FY FY FY FY FY F	Feeal Costom A.TS SATISFACTORY, Colliforms absent //icomi /mi /ini LittaBLE BECAUSE: Ruent growth C id culture loss debris
REPEAT SAMPLE Previous coliform presence Lab # Date Date PANI-SHERE WATER Source NEW CONSTRUCTION of REPAIRS CITHER (Specify) LINEATISFACTORY, Collorms present REPEAT SAMPLES REQUIRED Fees present OTHER LABORA TOTAL COUPORM /100 mi FECAL COLIFORM /100 mi ANOTHER SAM SAMPLE NOT TESTED SECAUSE: Sample too old Whose container Incomplete form SEE REVERSE SIDE OF GREEN CO	E. COLI PLATE COUNT TEST UNS TOTAL TOTAL TOTAL TOTAL TOTAL TOTAL EXCEL EXCEL TEST UNS TOTAL TOTAL EXCEL EXCEL TOTAL TOTAL EXCEL EXCEL EXCEL TOTAL EXCEL EXC	Feeal Costom A.TS SATISFACTORY, Costorms absent //Incent //Incent growth C id culture less debris On OF RESULTS
REPEAT SAMPLE Previous coliform presence Lab # Date Date PANI-SHIPEE WATER Source NEW CONSTRUCTION of REPAIRS CITHER (Specify) LINEATISFACTORY, Cellorme present REPEAT SAMPLES REQUIRED Feest present OTHER LABORA TOTAL COUPORM /100 mi FECAL COLIFORM /100 mi ANOTHER SAM SAMPLE NOT TESTED SECAUSE: Sample too old Wrong container Incomplete form SEE REVERSE SIDE OF GREEN CO	ECOLI PLATE COUNT TEST UNS TYPE FOR EXPLANATE FY FOR EXPLANATE CONT EXCE FY FOR EXPLANATE CONT EXCE FY FOR EXPLANATE CONT EXCE FY FOR EXPLANATE CONT EXCE FY FOR EXPLANATE CONT EXCE FY FOR EXPLANATE CONT EXCE FY FOR EXPLANATE FY FY FY FY FY FY FY FY FY FY FY FY FY F	Feeal Costom A.TS SATISFACTORY, Costorms absent //Incent //Incent growth C id culture less debris On OF RESULTS
REPEAT SAMPLE Previous coliform presence Lab # Date Date PANI-SHIPEE WATER Source NEW CONSTRUCTION of REPAIRS CITHER (Specify) LINEATISFACTORY, Cellorme present REPEAT SAMPLES REQUIRED Feest present OTHER LABORA TOTAL COUPORM /100 mi FECAL COLIFORM /100 mi ANOTHER SAM SAMPLE NOT TESTED SECAUSE: Sample too old Wrong container Incomplete form SEE REVERSE SIDE OF GREEN CO	ECOLI PLATE COUNT TEST UNS TYPE FOR EXPLANATE FY FOR EXPLANATE CONT EXCE FY FOR EXPLANATE CONT EXCE FY FOR EXPLANATE CONT EXCE FY FOR EXPLANATE CONT EXCE FY FOR EXPLANATE CONT EXCE FY FOR EXPLANATE CONT EXCE FY FOR EXPLANATE FY FY FY FY FY FY FY FY FY FY FY FY FY F	Feeal Costom A.TS SATISFACTORY, Costorms absent //Incent //Incent growth C id culture less debris On OF RESULTS
REPEAT SAMPLE Previous colliform presence Lab # Date Date PROVESSIBLE WATER Source NEW CONSTRUCTION or REPAIRS CITHER (Specify) LINEATISFACTORY, Celforms present REPEAT SAMPLES REQUIRED Fossi present OTHER LABORA TOTAL COUPORM /100 mi FECAL COUPORM /100 mi SAMPLE NOT TESTED SECAUSE: Sample too old Wrong container Incomplets form SEE REVERSE SIDE OF GREEN CO LAS NO. (7 DIGITS) DATE, T LOG - 7002-73 ALS	ECOLI PLATE COUNT TEST UNS TYPE FOR EXPLANATE FY FOR EXPLANATE CONT EXCE FY FOR EXPLANATE CONT EXCE FY FOR EXPLANATE CONT EXCE FY FOR EXPLANATE CONT EXCE FY FOR EXPLANATE CONT EXCE FY FOR EXPLANATE CONT EXCE FY FOR EXPLANATE FY FY FY FY FY FY FY FY FY FY FY FY FY F	Feeal Costom A.TS SATISFACTORY, Costorms absent //Incent //Incent growth C id culture less debris On OF RESULTS

opp.	10	101	DA + DODM	MUO TECT	TNIC	Lond
HLK	16	64	01:09PM	KUU IESI	TIAN	LHDD

Cartely 2: 20 pm April 116/04 And Sory

STATE OF WASHINGTON	17,	0	
		0	21
WATER BACTERIOLOGICAL	ANA	LYSIS	23
SAMPLE COLLECTION: READ INSTRUCTIONS ON BACK	OF GOL	DENROD	יקטב

If instructions are not followed, cample will be rejected. DATE COLLECTED TIME COLLECTED COUNTY NAME TYPE OF SYSTEM. IF PUBLIC SYSTEM, COMPLETE: PUBLIC CIRCLE GROUP " INDIVIDUAL. I.D. No. AB (serves only 1 residence) NAME OF SYSTEM HBOIE SPECIFIC LOCATION WHERE SAMPLE COLLECTED | TELEPHONE ND. EVENING > SAMPLE COLLECTED BY: (Name) SYSTEM OWNER/MOR! (Name) HEDIC GROUND WATER UNDER SURFACE INFLUENCE SURFACE WELL OF SPRING PURCHASED OF COMBINATION SEND REPORT TO: (Frint Full Name, Address and Zip Code). theres whence TYPE OF SAMPLE (check only one in this column) PRINTINE DRINKING WATER Check FRETRINK — Chlorinated (Plesidual: _ "Total Filtered Untreated or Other REPEAT SAMPLE
Previous collicin presence Daw _ Total Coliform
Fecal Coliform RAW SOURCE WATER Source
NEW CONSTRUCTION or REPAIRS Source # 8 Fecal Coliform OTHER (Specify) REMARKS: (LAB USE ONLY) DRINKING WATER RESULTS LINBATISFACTORY, COMOTHE PRESENT SATISFACTORY, Collionne ebsert E. Coll absent E. Coli present Fecal present Feosi absent REQUIRED OTHER LABORATORY RESULTS TOTAL COLIFORM . /100 ml E. COLI __ /100ml PLATE COUNT ___ __ /100 ml FECAL COLIFORM _ ANOTHER SAMPLE REQUIRED TEST UNSUITABLE BECAUSE: SAMPLE NOT TESTED BECAUSE: Sample too old
Wrong containe Continent grow
TNTC
Turbid culture Confluent growth Wrong container Incomplete form Excess debris SEE REVERSE SIDE OF GREEN COPY FOR EXPLANATION OF RESULTS RECEIVED B LAS NO. (7 DIGITS) LABORATORY:

4/16/04

DON SOS-003 (REV. 4/60)

-		44.4	pe . 1	100	100	100	*	-	13	9
- 4	H Y	NO.	51	100	134	×	n	52	18	à

STATE OF WASHINGTON
DEPARTMENT OF HEALTH
WATER BACTERIOLOGICAL ANALYSIS
SAMPLE COLLECTION: READ INSTRUCTIONS ON BACK OF GOLDENROD COPY
In instructions are not followed, sample will be rejected.

4/13/4 RAM	ILECTED COUNTY NAME
PUBLIC SYSTEM IF PUBLIC SYSTE PUBLIC INDIVIDUAL INDUSTRIAL INDUSTR	tool .
ME OF SYSTEM HBOLE ECIFIC LOCATION WHERE SAMPLE COLLECT THE COLLEGE SAMPLE COLLEGE THE COLLEGE SAMPLE COLLEGE THE COLLEGE SAMPLE COLLEGE THE COLLEGE SAMPLE COLLEGE THE COLLEGE SAMPLE COLLEGE THE COLLEGE SAMPLE COLLEGE THE COLLEGE SAMPLE COLLEGE THE COLLEGE SAMPLE COLLEGE THE COLLEGE SAMPLE COLLEGE THE COLLEGE SAMPLE COLLEGE THE COLLEGE SAMPLE COLLEGE THE COLLEGE SAMPLE COLLEGE THE COLLEGE SAMPLE COLLEGE THE COLLEGE SAMPLE COLLEGE THE COLLEGE SAMPLE COLLEGE THE COLLEGE SAMPLE COLLEGE SAMPLE COLLEGE THE COLLEGE SAMPLE SAMPLE SAMPLE COLLEGE SAMPLE SAM	Recharge & 17+
Intake	EVENING +
MPLE COLLECTED BY: (Name)	SYSTEM OWNER/MGR: (Name)
SURFACE WELL OF SF	RUNDER SURFACE INFLUENCE PRING PURCHASED OF COMBINATION OF OTHER
NO REPORT TO: (Print Full Name, Add	(INTERMIC
(2003)	57 68 M-F- UR 978
DRINKING WATER check treatment AEPEAT SAMPLE Provious coliform presence Lat Dai	te / /
RAW SOURCE WATER S NEW CONSTRUCTION of REPA	Source S Total Coliforn AIRS Fecal Coliforn
EMARKS:	
A-044	DRINKING WATER RESULTS
AUNSATISFACTORY, Coliforms pre REPEAT SAMPLES Fecal present REQUIRED Fecal present	A STATE OF THE STA
	A CONTRACT TO
OTHER LA	BORATORY RESULTS
TOTAL COLIFORM /100 ml	E. COU /100ml
TOTAL COLIFORM	E. COLI /100ml PLATE COUNT /ml R SAMPLE REQURED TEST UNSUITABLE 66CAUSE: Confluent growth TNTC Turbid culture Excess cabris
TOTAL COLIFORM	E. COLI /100ml PLATE COUNT /ml R SAMPLE REQURED TEST UNSUITABLE 66CAUSE Confluent growth TNTC Turbid quiture
TOTAL COLIFORM	E. COLI /100ml PLATE COUNT /ml R SAMPLE REQURED TEST UNSUITABLE 66CAUSE: Confluent growth TINTC TUTOR CUITURE EXCESS GEBTIS EN COPY FOR EXPLANATION OF RESULTS DATE, TIME RECEIVED HEGGIVED BEGGIVED

OF CENTER COPY

Bob Bower

From: "Bob Bower" <bob.bower@wwbwc.org>

"Walla Walla River Irrigation District" <wwrid@qwest.net>; "Tony Justus" To:

<tony.g.justus@wrd.state.or.us>; <Stephen.c.hall@usace.army.mil>; "Rick George"

<rickgeorge@ctuir.com>; "Phil Richerson" <RICHERSON.Phil@deq.state.or.us>; "Mike Ladd" <michael.f.ladd@wrd.state.or.us>; "Kevin Scribner" <ktscribner@gohighspeed.com>; "Jon Brough" <jon@gohighspeed.com>; "John Zerba" <wahs@bmi.net>; "John Warinner"

<warinner@bmi.net>; "John Covert" <jcov461@ecy.wa.gov>; "Jim Chambers"

<Jim.R.CHAMBERS@WRD.State.or.us>; "Gary James" <garyjames@ctuir.com>; "Donn Miller" <Donn.W.MILLER@wrd.state.or.us>; "Dan Evans GTH-Law" <devans@gth-law.com>; "Chris J Hyland" <chris.i.hyland@nww01.usace.army.mil>; "Brian Wolcott" <bri>brian.wolcott@wwbwc.org>;

"Brian Mayer OWRD-Wells Inspector" <bri>brian.m.mayer@wrd.state.or.us>; "Bill Neve"

<wnev461@ecy.wa.gov>; "Tom Darnell" <Thomas.Darnell@orst.edu>
"WOLGAMOTT Mitch" <WOLGAMOTT.Mitch@deq.state.or.us>; "Stephanie Eaton" Cc:

<stephanie.eaton@wwbwc.org>; "Gina Massoni" <gina.massoni@wwbwc.org>; "Eric Pfeifer"

<pfeifdog@whitties.org>; "Rivera Chris" <chris.rivera@wwbwc.org>; "Brian Wolcott"

<Bob.bower@wwbwc.org>

Sent: Thursday, April 22, 2004 11:34 AM

Subject: WQ update

Good morning,

Some news on the recharge site (left voice mail with Phil).

After our fecal coliform hit at the intake site (ditch water) last week, I did a battery of fecal and E. coli (CFU counts) samples on:

(1) Intake (ditch water)

(2) Well 1 (downgradient obs well, influenced by project water)

(3) Well 3 (upgradient control well).

I just received the results this am (via phone and fax)

Recharge Intake was fecal 40 cfus, E. Coli 24.1 (cfus = colony forming units per 100 ml) Well #1 fecal 3.1 cfus, E. Coli 2.0 Upgradient control Well # 3 fecal 14.8, E. Coli 7.5

In my opinion this is what I believe is going on (knowing that this a very small sample size).

We know that the ditch by itself brought up the aquifer ~20 feet before we turned on the recharge project. I would guess that the ditch is the main vector for movement of the bacteria based on reported concentrations and the aquifer static being dramatically influenced by the ditch without the project being on. I would say that the problem may be background all along the ditch back to where ever the source is. I have 12 more fecal/e. coli concentration (cfus) tests ordered (here Monday) that I was going to use to move back up gradient of the site and test both ditch and wells along the way. I would also take three samples from Well #1 (recharge influenced) throughout a 24 hour period, to see if this is an episodic plume type event.

As I told Phil on the phone, hind site is 20-20. We have WQ samples for the conditions before the ditch was on, and after the ditch AND the recharge project were running. What we missed was a WQ sample with JUST the ditch on, which would provide us with a better background condition for the recharge operation. We can capture that when we turned off the project and sample before the ditch goes off. One thing we can definitely refine for next year's recharge season.

In my thesis work in the Tillamook watershed, we saw that septic related feces in river/streams appeared to trend with time of day. Early morning and evenings when people are home, using their toilets, showers, etc. Certainly

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free http://www.kuotesting.com e-mail: kuotest@atnet.net

DATE RECEIVED.

DATE REPORTED

DATE COLLECTED 5/21/2004

SEND REPORT TO: 5/21/2004 6/7/2004

SYSTEM / CUSTOMER

W.W.B.W.C. PO Box 68

97862 Milton Freewater OR

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

ANALYSIS UNITS ANALYSTS RESULTS SAMPLE NO OBS Well #1 MPN/100mL Cascade Analytical 70878 Fecal Coliform <2

<(0.001): in	dicates the anal	vte was not	detected at o	r above th	ne concentration indicated.
--------------	------------------	-------------	---------------	------------	-----------------------------

ND: None Detected

Indicates milligrams per litre

=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions Method Detection Limit

se check out our new Web Site at http://www.kuotesting.com

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

DATE RECEIVED

DATE REPORTED

5/21/2004

SEND REPORT TO:

5/21/2004

6/7/2004

SYSTEM / CUSTOMER

W.W.B.W.C. PO Box 68

Milton Freewater OR

97862

DATE COLLECTED

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

SAMPLE NO. CUSTOMER ANALYSIS SAMPLE NO RESULTS OBS Well #3 MPN/100mL 70879 Fecal Coliform 2 Cascade Analytical <2

<(0.001):	indicates the analyte was not detected at or above the concentration indicated.

e check out our new Web Site at http://www.kuotesting.com

⁼Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions Method Detection Limit

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

DATE COLLECTED

DATE RECEIVED

DATE REPORTED

5/21/2004

SEND REPORT TO

5/21/2004

6/7/2004

SYSTEM/CUSTOMER

W.W.B.W.C. PO Box 68

Milton Freewater OR 97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

MPLE NO	SAMPLE NO	ANALYSIS	RESULTS	MDL	UNITS	ANALYSTS
70880	Intake	Fecal Coliform	130	2	MPN/100mL	Cascade Analytic
_						
Y						
_						

<(0.001): in	dicates the analyte	was not	detected at	or above th	e concentration in	ndicated.
--------------	---------------------	---------	-------------	-------------	--------------------	-----------

ND: None Detected

Indicates milligrams per litre

=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions Method Detection Limit

check out our new Web Sire at http://www.kuotesting.com

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

> DATE COLLECTED 5/7/2004

DATE RECEIVED

DATE REPORTED

SEND REPORT TO

5/7/2004

5/12/2004

SYSTEM / CUSTOMER

W.W.B.W.C. PO Box 68

Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

IPLE NO	CUSTOWER SAMPLE NO. OBS Well #1	ANALYSIS	RESULTS	MOL	UNITS	ANALYSTS
70637	OBS Well #1	Fecal E-Coli	<2	2	CFU/100ml	Valley Labs
					WAS IN THE RESIDENCE OF THE PARTY OF THE PAR	60 Feb 2000 (2015 COLUMN ASSETS ASSETTS ASSETT ASSETS ASSETT ASSE
						AND DESCRIPTION OF THE PROPERTY OF THE PROPERT
	-					
			Anna Anna Anna Anna Anna Anna Anna Anna	CANADA A		······································
			The state of the s			
-	***************************************					
			5000111 A	***************************************		
		arms after the second s				
			WE ENGINEERING THE THE THE THE THE THE THE THE THE THE	an management		

		CONTRACTOR OF THE STREET			***************************************	ACCOUNTS OF THE PERSON OF THE

<(0.001): indicates the analyte was not detected at or above the concontration indicated.

ND: None Detected

mg/L/Indicates milligrams per life.

* PQL=Practice! Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

MDL: Method Detserion Limit

Please check out our new 1986 Site of http://www.kuetesting.com

05-12-04

Dr. Eugene Kuo, Quality Assurance Coordinator

Date

337 South 1st Avenue, Othello, WA 99344 (509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

> DATE COLLECTED 5/7/2004

DATE RECEIVED

DATE REPORTED

SEND REPORT TO

5/7/2004

5/11/2004

W.W.B.W.C.

SYSTEM / CUSTOMER

PO Box 68

Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

BAMPLE NO	GUSTOMER SAMPLE NO. OBS Well #3	ANALYSIS	RESULTS	MOL	UNITS	ANALYSTS
70638	OBS Well #3	Pecal E-Coli	2	2	CFU/100ml	Valley Labs
	Strain and a supplement control control to be a supplement to the supplement of the			Discourance of the Contraction		
A STREET STREET, STREET,	Property and the Property of the Party of th	TO SERVICE OF THE PARTY OF THE				
					A THE RESIDENCE OF THE PARTY OF	POCAPO INC.
	THE OWNER AND ADDRESS OF THE OWNER AND ADDRESS					Marines were proportion and the
	The state of the s	- AND AND AND AND AND AND AND AND AND AND	**************************************		of the second second	
OR THE COMPANY CANADA			California de la compania del compania del compania de la compania del la compania dela compania del la compani	The same of the sa		
					NAME OF TAXABLE PARTY OF TAXABLE PARTY.	THE COLUMN TWO IS NOT THE OWNER, THE PARTY OF THE OWNER, THE PARTY OF THE OWNER, THE OWN
-				- William Control	THE STREET STREET, SALES	
	-			CALIFORNIA DE LA CALIFO	- Verilla Co	
NATIONAL PROPERTY.		NUMBER OF THE PROPERTY OF THE	NAME OF TAXABLE PARTY OF TAXABLE PARTY.			
Chance and the same of the sam		The same of the sa	Name and Publishers of the Owner, where the Publishers of the Publ	Chillian many pagests	WAREL CO.	
				WOODS PRODUCED IN		
		AND THE PARTY OF T		-	Contract the Contract of	
		THE RESERVE AND PERSONS ASSESSED FOR THE PERSON AND PARTY.		- CHESTAN WHOLE IS		
					CONTRACT OF THE PARTY OF THE PA	
				···· EDINUENSKA UP-		
	THE RESIDENCE OF THE PARTY OF T			A	TOTAL THE STREET, STRE	
-						The second secon
			THE REPORT OF THE PARTY OF THE	THE STATE ST		
-	************************		Minus in the control of the state of the sta	THE COLUMN TWO ASSESSMENT OF		
-versional			PORTON CONTRACTOR OF THE PROPERTY OF THE PROPE	PROCESSION AND ADDRESS		***************************************
andier de ar	THE SHALL SHE WAS AND ADDRESS OF THE SHALL SHE	NAME OF PERSONS ASSESSMENT OF THE PERSONS ASSESSMENT ASSESSMENT ASSESSMENT ASSESSMENT ASSESSMENT		District and Constitution of the	-	-
			W	NO-RESIDENCE AND ADDRESS OF	-	****
	Tributania and tribut			and the same of th		
	POLICE AND ADDRESS OF THE PARTY			MITTER STATE OF THE	CONTRACTOR OF THE PARTY OF THE	-
***				Phones and phones and	A THE OWNER WHEN PERSON NAMED IN	

<(0.001): Indicates the analyte was not descoted at or above the concentration indicated.

mg/L. Indicates milligrams per litre

PQL Practical Quantitation Limit is the lowest level that can be selieved within specified limits of precision and accuracy during rounne laboratory operating conditions

MDL: Method Detection Limit

Please check out our new Wolf Sile at http://www.kuntesting.com

Kuo Testing Labs, Inc.
337 South 1st Avenue Othello, WA 99344

(509)488-0112 (800)328-0112 Fax (509)488-0118 Web Site http://www.kuotesting.com

INORGANIC CHEMICALS (IOCS) REPORT FOR NITRATES

Water System/Customer Na W.W.B.W.C.	ame:			PWS ID No	o.:41
System Address PO Box 68					
CITY Milton Freewater	Cou	inty Umatil l	agnuld beZIP 97862		
Sample Location: Well					
Date Collected: 3/10/2004		te Received:	/	Date Analyzed	d: 3/15/2004
Laboratory No.:WA0	60-69716			Date Reported	d: 3/15/2004
Party To Pay for Testing W. PO Box 68	W.B.W.C		Send Results To: Bob PO Box 68	Bower	
	W.B.W.C OR 97862				R 97862
PO Box 68		MCL mg/L	PO Box 68		Analysis
PO Box 68 Milton Freewater	OR 97862		PO Box 68	0	

mg/L: indicates milligrams per liter or parts per million.

greater than or equal to the value shown.

<0.100: indicates the compound was detected but at a value below the concentration indicated.

Comments: See our new Web Site at http://www.kuotesting.com

ND (Not Detected): in the results column indicates this compound was analyzed and not detected at a level

Dr. Eugene Kuo, Quality Assurance Coordinator

03-15-04 Date

pd \$41,00-#1548 \$/1/04

# in boxes below: MICROBIOLOGICAL ANALYSIS PUBLIC WATER SUPPLIES	Analyst: Date: Date:	Send results to: DHS-Drinking Water Program: P.O. Box 14350, Portland OR 97293-0350 Phone (503) 731-4381	Send results to: DHS-Drinking
# in boxes below: MICROBIOLOGICAL ANALYSIS PUBLIC WATER SUPPLIES PUBLIC WATER SUPPLIES PUBLIC WATER SUPPLIES PUBLIC WATER SUPPLIES PUBLIC WATER SUPPLIES PUBLIC WATER PROGRAM	□ Leaked □ Over 30 hrs. old □ Heavy non-coliform growth (as defined by method) □ Other	M. Man-Free weeting CR 9762	Address City, state, zip
# in boxes below: County	Invalidation reason:		Return address to Name
# in boxes below: MICROBIOLOGICAL ANALYSIS PUBLIC WATER SUPPLIES PUBLIC WATER SUPPLIES DRINKING WATER PROGRAM	Date & time analysis begun:Comments:	*If repeat	Sample point: #
# in boxes below: MICROBIOLOGICAL ANALYSIS PUBLIC WATER SUPPLIES DRINKING WATER PROGRAM	Date & time received:	Fecal coliforms: E. coli: CF	If repeat, date of initial positive if repeat, location: Upstream (
Public Water System ID # in boxes below: 1	LabID#	Day Year Hour Min. Test Methods:	Collection date and time:
MICROBIOLOGICAL ANALYSIS PUBLIC WATER SUPPLIES DRINKING WATER PROGRAM	to recinition of the control of the	Total coliforms: Present* P	200
	Laboratory Name	YDHS Organ dearment of Himan services	Enter Public Water System ID

337 South 1st Avenue Othello, WA 99344

(509)488-0112 (800)328-0112 Fax (509)488-0118 Web Site http://www.kuotesting.com

INORGANIC CHEMICALS (IOCS) REPORT FOR NITRATES

Type of System: Individual

Water System/Customer Name:

PWS ID No.:41

W.W.B.W.C.

System Address PO Box 68

CITY Milton Freewater

County Umatilla

ZIP 97862

Send Resurs To Bab Bower

Sample Location: Well #1

Date Collected: 4/13/2004

Date Received: 4/14/2004

Date Analyzed: 4/15/2004

Laboratory No.:WA060-70294

Date Reported: 4/15/2004

Party To Pay for Testing W. W. B. W. C.

PO Box 68

PO Box 68

Milton Freewater

OR 97862

Milton Freewater

OR 97862

Contaminant - Method	Code	MCL mg/L	Analyst	Analysis mg/L
Nitrate (NO3- N)SM4500-NO3-D Nitrãe (NO2-N)SM4500-NO2-B Nitrãe + NItrate	1040 1041 1038	10. 1.0 10.	Qian ,	ND

NOTES:

MCL (Maximum Contaminant Level): if the contaminant amount exceeds the MCL, immediately contact your regional DOH office.

NA (Not Analyzed): in the results column indicates this compound was not included in the current analysis.

ND (Not Detected): In the results column indicates this compound was analyzed and not detected at a level greater than or equal to the value shown.

mg/L: indicates milligrams per liter or parts per million.


<0.100: indicates the compound was detected but at a value below the concentration indicated.

Comments: See our new Web Site at http://www.kuotesting.com

Dr. Eugene Kuc Quality Assyrance Coordinator

April 15 , work Date





Kuo Testing Labs, Inc. Agricultural - Industrial - Environmental

Othello, Washington 99344

W.W.B.W.C. Client:

Address: PO Box 68

MiltonFreewater, OR 97862

INVOICE DATE INVOICE # CLIENT#

04-04-258 04/16/04 WWB2170

PURCHASE ORDER#

Grower:

PN:

Project:

Sampler: Bob Bower

RptNo	RptNo RptDate	Field Identifier	Test	Description	Qty	Price	Extension
E70289	04/14/04	04/14/04 Intake,Well #1	A1-1	Total Coliform and E. Coli		17.00	34.00
70289	04/14/04	Intake, Well #1	A2-1	NO3-N		24.00	48.00

Notes: 04-04-258

00.0 82.00 \$82.00 -0.00 % 0 Invoice Total Due Invoice Total FAX Charge Discount

05/16/04

Due Date

Terms: Net 30 days following date of invoice. Invoices not paid in 30 days will be subject to interest charged at 1.5% per month (18% per year) with a minimum charge of 50 cents.

STATE OF WASHINGTON DEPARTMENT OF HEALTH

WATER BACTERIOLOGICAL ANALYSIS

SAMPLE COLLECTION: READ INSTRUCTIONS ON BACK OF GOLDENROD COPY If Instructions are not followed, sample will be rejected.

DATE COLLECTED TIME COLLECTED COUNTY NAM	/E
MONTH DAY YEAR 7:30	11
4/13/04 DAM DPM UMate	lla
TYPE OF SYSTEM IF PUBLIC SYSTEM, COMPLETE:	
PUBLIC	CIRCLE GROUP
INDIVIDUAL (serves only 1 residence)	A B
NAME OF SYSTEM	
ALSO OF OTHER DESIGNATION OF THE PROPERTY OF T	
_ HBDC Mechania Krongot	
SPECIFIC LOCATION WHERE SAMPLE COLLECTED TELEPHONE NO.	
DAY (6.91) 500	-3534
1001 =1	n n
	56-2170
SAMPLE COLLECTED BY: (Name) SYSTEM OWNER/MG	iH.: (Name)
Dower HEDIC 1000	BLOC
SOURCE TYPE GROUND WATER UNDER SURFACE INFLUE	NCE
SURFACE WELL or SPRING PURCHASED or	COMBINATION
SEND REPORT TO: (Print Full Name, Address and Zip Code)	O OTTIET
WASHINGTON	
TYPE OF SAMPLE (check only one in this column)	
ROUTINE Chlorinated (Residual:	_Total Free)
check treatment — Filtered	
Untreated or Other	
Previous coliform presence Lab #	A TOWN
Date/ / /	neut s
RAW SOURCE WATER Source # S	Total Coliform
NEW CONSTRUCTION or REPAIRS	Fecal Coliform
OTHER (Specify)	
REMARKS:	
The state of the s	
(LAB USE ONLY) DRINKING WATER RESULTS	
V .	
UNSATISFACTORY, Coliforms present	SATISFACTORY, Coliforms absent
REPEAT E. Coli present E. Coli absent	
REQUIRED Fecal present Fecal absent	
OTHER LABORATORY RESULTS	
FFOU COUPONI	A A A
ANOTHER SAMPLE REQURED	/ml
The state of the s	Total - Horno
SAMPLE NOT TESTED BECAUSE: TEST UNSUITAB	BLE BECAUSE:
Sample too old Confluent	growth
Wrong container TNTC	AUTHOUNCE OF
Incomplete form Turbid cul	ALDER OF THE PARTY
Excess de	bris
SEE REVERSE SIDE OF GREEN COPY FOR EXPLANATION O	F RESULTS
VO. (7 DIGITS) DATE, TIME RECEIVED	RECEIVED BY
200 7 000 of 1	00
109-10293 414104 500	alul
DATE REPORTED LABORATORY:	
4116/04	
REMARKS	
nemania	

WATER SUPPLIER COPY

STATE OF WASHINGTON DEPARTMENT OF HEALTH

WATER BACTERIOLOGICAL ANALYSIS

SAMPLE COLLECTION: READ INSTRUCTIONS ON BACK OF GOLDENROD COPY if instructions are not followed, sample will be rejected.

DATE COLLECTED TIME COLLE	CTED COUNTY NAME
A A A TAM T	PM
TYPE OF SYSTEM IF PUBLIC SYSTEM, C	
PUBLIC	CIRCLE GROUP
(serves only 1 residence) I.D. No.	A B
NAME OF SYSTEM	
SONE ST	I character
SPECIFIC LOCATION WHERE SAMPLE COLLECTED	TELEPHONE NO.
	DAY()
NICK	EVENING ()
SAMPLE COLLECTED BY: (Name)	SYSTEM OWNER/MGR.: (Name)
生 - 经基础支票	the state of the s
	ER SURFACE INFLUENCE
SURFACE WELL OF SPRING	PURCHASED or COMBINATION OF OTHER
SEND REPORT TO: (Print Full Name, Address	and Zip Code)
The Burger	WINDLEY C
The Desired	WASHINGTON
TYPE OF SAMPLE (check only one in this colu	
ROUTINE DRINKING WATER Chi	orinated (Residual:TotalFree)
check treatment → Filt	ered
REPEAT SAMPLE	reated or Other
Previous coliform presence Lab # Date	
RAW SOURCE WATER Source	# S Total Coliform
NEW CONSTRUCTION or REPAIRS	Fecal Coliform
OTHER (Specify)	
REMARKS:	Colors Handblad
(LAB USE ONLY) DRINI	KING WATER RESULTS
UNSATISFACTORY, Coliforms present	SATISFACTORY, Coliforms absent
REPEAT E. Coli present SAMPLES	E. Coli absent
REQUIRED Fecal present	Fecal absent
OTHER LABORAT	TORY RESULTS
TOTAL COLIFORM /100 ml	E. COLI /100ml PLATE COUNT /ml
ANOTHER SAME	THE PROPERTY OF THE PROPERTY O
SAMPLE NOT TESTED BECAUSE:	TEST UNSUITABLE BECAUSE:
Sample too old	Confluent growth
Wrong container	TNTC
Incomplete form	Turbid culture Excess debris
OFF DEVEDOS ONE OF ODERA COM	
NO. (7 DIGITS) SEE REVERSE SIDE OF GREEN COP' NO. (7 DIGITS) DATE, TH	WE RECEIVED RECEIVED BY
110 - 000	ATT 1 (()
101-10381 411	HICH TO - LAW
DATE REPORTED LABORATORY:	
1 77 1 = -	

DOH 305-002 (REV. 4/92)
WATER SUPPLIER COPY

Kuo Testing Labs, Inc.
337 South 1st Avenue Othello, WA 99344

(509)488-0112 (800)328-0112 Fax (509)488-0118 Web Site http://www.kuotesting.com

INORGANIC CHEMICALS (IOCS) REPORT FOR NITRATES

Type of System: Individual

Water System/Customer Name:

W.W.B.W.C.

System Address

PO Box 68

CITY Milton Freewater

County Umatilla

ZIP 97862

Sample Location: Intake

Date Collected: 4/13/2004

Date Received: 4/14/2004

Date Analyzed: 4/15/2004

PWS ID No.:41

Laboratory No.:WA060-70290

Date Reported: 4/15/2004

Party To Pay for Testing: W.W.B.W.C

Send Results To: Bob Bower

PO Box 68

PO Box 68

Milton Freewater

OR 97862

Milton Freewater

OR 97862

Contaminant - Method	Code	MCL mg/L	Analyst	Analysis mg/L
Nitrate (NO3- N)SM4500-NO3-D Nitrite (NO2-N)SM4500-NO2-B Nitrite + Nitrate	1040 1041 1038	10. 1.0 10.	Qian	ND

NOTES:

MCL (Maximum Contaminant Level): if the contaminant amount exceeds the MCL, immediately contact your regional DOH office.

NA (Not Analyzed): in the results column indicates this compound was not included in the current analysis.

ND (Not Detected): in the results column indicates this compound was analyzed and not detected at a level greater than or equal to the value shown.

mg/L: indicates milligrams per liter or parts per million.

<0.100: indicates the compound was detected but at a value below the concentration indicated.

Comments: See our new Web Site at http://www.kuotesting.com

Dr. Eugene Kuo, Quality/Assurance Coordinator

April 15, 2000 Date

Kuo Testing Labs, Inc.
337 South 1st Avenue Othello, WA 99344

(509)488-0112 (800)328-0112 Fax (509)488-0118 Web Site http://www.kuotesting.com

INORGANIC CHEMICALS (IOCS) REPORT FOR NITRATES

			<u> 1.5. 5778</u>	
9:			PWS ID No.	:41
Count	y Umatilla	ZIP 9786 2	2	
Date	Received: 4/	14/2004	Date Analyzed:	4/15/2004
70294			Date Reported:	4/15/2004
B.W.C		Send Results To: Bok	Bower	
		PO Box 68		
OR 97862		Milton Freewater	OF	R 97862
Code	MCL mg/L		Analyst	Analysis mg/L
1040 1041 1038	10. 1.0 10.		Qian	ND
ant Level): if th	ne contamir	nant amount exceed	Is the MCL, im	nediately conta
esults column i	ndicates th	is compound was n	ot included in the	ne current
esults column ir	ndicates this	s compound was ar	alvzed and not	detected at a
		o compound mac an	any zou and mo	actoriou at a
o the value show	wn.			
	Count Date 70294 B.W.C Code 1040 1041 1038 ant Level): if the results column in the sults column in	County Umatilla Date Received: 4/ 70294 B.W.C Code MCL mg/L 1040 10. 1041 1.0 1038 10. ant Level): if the contamir results column indicates the	County Umatilla Date Received: 4/14/2004 TO294 B.W.C Send Results To: Bob PO Box 68 PO Box 68 Milton Freewater Code MCL mg/L 1040 10. 1041 1.0 1038 10. ant Level): if the contaminant amount exceed results column indicates this compound was not esults column indicates this compound was an esults column indicates this column indicates this column indicates this column indicates this column indicates this column indic	County Umatilla ZIP 97862 Date Received: 4/14/2004 Date Reported: Date Reported: Date Reported: Date Reported: Date Reported: Date Reported: Date Reported: Date Reported: Date Reported: Date Reported: Date Reported: Analyst PO Box 68 Milton Freewater OF Code MCL mg/L 1040 10. 1041 1.0. 1038 10. Analyst Qian Date Analyzed: Date Analyzed: Date Analyzed: Date Reported: Date Reported: Date Reported: Date Reported: Date Reported: Date Reported: Date Reported: Date Analyzed: Date Analyzed: Date Analyzed: Date Analyzed: Date Analyzed: Date Reported: Date

Dr. Eugene Kuo Quality Assurance Coordinator

Comments: See our new Web Site at http://www.kuotesting.com

SATISFACTORY, Colifornis absent UNSATISFACTORY, Coliforms present
REPEAT
SAMPLES

Coli present E. Coli absent REPEAT Facal absent Fecal present REQUIRED OTHER LABORATORY RESULTS E. COLJ ____ TOTAL COLIFORM . , /100 m PLATE COUNT _/100 ml FECAL COLIFORM . ANOTHER SAMPLE REQUEED TEST UNSUITABLE BECAUSE: SAMPLE NOT TESTED BECAUSE: Confluent growth Sample too old TNTC Wrong container Turbid culture Incomplete form Excess dobris SEE REVERSE SIDE OF GREEN COPY FOR EXPLANATION OF RESULTS

DATE TIME RECEIVED

LABORATORY:

RECEIVED BY

ABAARKS DOH 306-002 (REV. 4/12)

LAB NO. (7 DIG TS)

Appendices I-B

HBDIC Recharge Water Quality Testing: Lab Results, Notes and Records

2004-2005 Recharge Season

337 South 1st Avenue, Othello, WA 99344 (509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

DATE COLLECTED

DATE RECEIVED

DATE REPORTED

5/19/2005

SEND REPORT TO:

6/24/2005 5/20/2005

SYSTEM / CUSTOMER

Project Name:

W.W.B.W.C. PO Box 68 Milton Freewater OR

97862

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

SAMPLE NO. CUSTOMER ANALYSIS UNITS ANALYSTS RESULTS MOL SAMPLE NO Edge Analytical mg/L OBS-#1 SOC/Synthetic Organic Co Report 76494

01): indicates the analyte was not detected at or above the concentration indicated. None Detected

VL:Indicates milligrams per litre

QL=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

MDL: Method Detection Limit

Web Site at http://www.kuotesting.com Please check out our new



11525 Knudson Rd.

Burlington, WA 98233

(800) 755-9295

(360) 757-1400 - FAX (360) 757-1402

Page 1 of 1

HERBICIDES IN DRINKING WATER

Client Name: KUO Testing Labs Inc

337 S 1st

Othello, WA 99344

System Name:

System ID Number:

DOH Source Number:

Multiple Sources:

Sample Type:

Sample Purpose: Investigative or Other

Sample Location: OBS #1

County:

Reference Number: 05-05830

Project: 76494

Field ID: WWBWC Lab Number: 04613162

Date Collected: 5/19/2005 Date Extracted: 515 050601

Date Analyzed: 6/3/2005

Report Date: 6/6/2005 Analyst: CMH

Supervisor:

OH#	COMPOUNDS	RESULTS	Units	SRL	Trigger	MCL	COMMENT
	EPA Regulated						
37	2,4 - D	ND	ug/L	0.2	0.2	70	
38	2,4,5 - TP (SILVEX)	ND	ug/L	0.4	0.4	50	
	PENTACHLOROPHENOL	ND	ug/L	0.08	0.08	1	
137	DALAPON	ND	ug/L	2	2	200	
	DINOSEB	ND	ug/L	0.4	0.4	7	
140	PICLORAM	ND	ug/L	0.2	0.2	500	
	EPA Unregulated						
138	DICAMBA	ND	ug/L	0.2	0.2		
	State Unregulated						
	2,4 DB	ND	ug/L	1.0	1.0		
	2,4,5 T	ND	ug/L	0.4	0.4		
	BENTAZON	ND	ug/L	0.5	0.5		
	DICHLORPROP	ND	ug/L	0.5	0.5		
	ACTIFLORFIN	ND	ug/L	2.0	2.0		
	DACTHAL (DCPA)	ND	ug/L	0.1	0.1		
226	3,5 - DICHLOROBENZOIC ACID	ND	ug/L	0.5	0.5		
-23				4			
125							

^{*-} An amount of "ND" indicates that the compound was not detected above the Lab's Method Detection Limit - MDL.

^{**-} Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds. A blank MCL or SAL value indicates a level is not currently established.

^{***-} If a compound is detected > or = to the State Reporting Level, SRL, specified increased monitoring frequencies may occur per DOH.

^{****-} Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.

J - Estimated value.



11525 Knudson Rd.

Burlington, WA 98233

(800) 755-9295

(360) 757-1400 - FAX (360) 757-1402

Page 1 of 2

SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

Client Name: KUO Testing Labs Inc

337 S 1st

Othello, WA 99344

System Name:

System ID Number:

DOH Source Number:

Multiple Sources:

Sample Type:

Sample Purpose: Investigative or Other

Sample Location: OBS #1

County:

Sampled By:

Sampler Phone:

Reference Number: 05-05830

Project: 76494

Field ID: WWBWC

Lab Number: 04613162

Date Collected: 5/19/2005 Date Extracted: 525 050601

Date Analyzed: 6/7/2005 Report Date: 6/17/2005

Analyst: MW

Supervisor:

FDA Mothod 525 2 For State Drinking Meter

OOH#	COMPOUNDS	RESULTS	Units	SRL	Trigger	MCL	COMMENT
	EPA Regulated				55-1		COMMENT
33	ENDRIN	ND	ug/L	0.02	0.02	2	
34	LINDANE (BHC - GAMMA)	ND	ug/L	0.04	0.04	0.2	
35	METHOXYCHLOR	ND	ug/L	0.2	0.2	40	
117	ALACHLOR	ND	ug/L	0.4	0.4	2	
119	ATRAZINE	ND	ug/L	0.2	0.2	3	
120	BENZO(A)PYRENE	ND	ug/L	0.04	0.04	0.2	
122	CHLORDANE, TECHNICAL	ND	ug/L	0.4	0.4	2	
124	DI(ETHYLHEXYL)-ADIPATE	ND	ug/L	1.3	1.3	400	
125	DI(ETHYLHEXYL)-PHTHALATE	ND	ug/L	1.3	1.3	6	
126	HEPTACHLOR	ND	ug/L	0.08	0.08	0.4	
127	HEPTACHLOR EPOXIDE (A&B)	ND	ug/L	0.04	0.04	0.2	
128	HEXACHLOROBENZENE	ND	ug/L	0.2	0.2	1	
129	HEXACHLOROCYCLO-PENTADIENE	ND	ug/L	0.2	0.2	50	
133	SIMAZINE	ND	ug/L	0.15	0.15	4	
	EPA Unregulated						
118	ALDRIN	ND	ug/L	0.2	0.2		
121	BUTACHLOR	ND	ug/L	0.4	0.4		
123	DIELDRIN	ND	ug/L	0.2	0.2		
130	METOLACHLOR	ND	ug/L	1.0	1.0		
131	METRIBUZIN	ND	ug/L	0.2	0.2		
132	PROPACHLOR	ND	ug/L	0.2	0.2		
	State Unregulated - Other					1 - 1	
179	BROMACIL	ND	ug/L	0.2	0.2		
183	PROMETON	ND	ug/L	0.2	0.2		Qualitative Analysis Only
190	TERBACIL	ND	ug/L	0.2	0.2		
	DIAZINON	ND	ug/L	0.2	0.2		Unstable in Acidified Sample Matrix
208	EPTC	ND	ug/L	0.3	0.3		- Totalio Sanipis Matrix

An amount of "ND" indicates that the compound was not detected above the Lab's Method Detection Limit - MDL.

J - Estimated value.

^{**-} Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds. A blank MCL or SAL value indicates a level is not currently established.

^{***-} If a compound is detected > or = to the State Reporting Level, SRL, specified increased monitoring frequencies may occur per DOH.

^{****-} Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.





Reference Number: 05-05830

Lab Number: 04613162 Report Date: 6/17/2005

SYNTHETIC ORGANIC COMPOLINDS (SOC) REPORT

H#	COMPOUNDS	RESULTS	Units	SRL	Trigger	MCL	COMMENT
	4,4-DDD	ND	ug/L	0.2	0.2		
233	4,4-DDE	ND	ug/L	0.2	0.2		
CONTRACTOR OF	4,4-DDT	ND	ug/L	0.2	0.2		
236	CYANAZINE	ND	ug/L	0.2	0.2		Qualitative Analysis Only
239	MALATHION	ND	ug/L	0.2	0.2		
240	PARATHION	ND	ug/L	0.2	0.2		
243	TRIFLURALIN	ND	ug/L	0.2	0.2		
	- PAHs						
LANCE DE LA CONTRACTOR	NAPTHALENE	ND	ug/L	0.1	0.1		
154	FLUORENE	ND	ug/L	0.2	0.2		
244	ACENAPHTHYLENE	ND	ug/L	0.2	0.2		
245	ACENAPHTHENE	ND	ug/L	0.2	0.2		
246	ANTHRACENE	ND	ug/L	0.2	0.2		
247	BENZ(A)ANTHRACENE	ND	ug/L	0.1	0.1		
248	BENZO(B)FLUORANTHENE	ND	ug/L	0.2	0.2		
	BENZO(G,H,I)PERYLENE	ND	ug/L	0.2	0.2		
	BENZO(K)FLUORANTHENE	ND	ug/L	0.2	0.2		
100000000	CHRYSENE	ND	ug/L	0.2	0.2		
	DIBENZO(A,H)ANTHRACENE	ND	ug/L	0.2	0.2		
	FLUORANTHENE	ND	ug/L	0.2	0.2		
A-11200541	INDENO(1,2,3-CD)PYRENE	ND	ug/L	0.2	0.2		
	PHENANTHRENE	ND	ug/L	0.2	0.2		
And the latest and the	PYRENE	ND	ug/L	0.2	0.2		
17072000	- Phthalates		39.2	0.2	0.2		
	BENZYL BUTYL PHTHALATE	ND	ug/L	0.6	0.6		
	DI-N-BUTYL PHTHALATE	ND	ug/L	0.6	0.6		
E Section 1	DIETHYL PHTHALATE	ND	ug/L	0.6	0.6		
	DIMETHYL PHTHALATE	ND	ug/L	0.6	0.6		
			ug/L	0.0	0.0		

^{*-} An amount of "ND" indicates that the compound was not detected above the Lab's Method Detection Limit - MDL.

^{*-} An amount of "ND" indicates that the compound was not detected above the Lab's Method Detection Limit - MDL.

**- Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds.

A blank MCL or SAL value indicates a level is not currently established.

***- If a compound is detected > or = to the State Reporting Level, SRL, specified increased monitoring frequencies may occur per DOH.

***-- Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.

J - Estimated value.



11525 Knudson Rd.

Burlington, WA 98233

(800) 755-9295

(360) 757-1400 - FAX (360) 757-1402

Page 1 of 1

SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

Client Name: KUO Testing Labs Inc

337 S 1st

Othello, WA 99344

System Name:

System ID Number:

DOH Source Number:

Multiple Sources:

Sample Type:

Sample Purpose: Investigative or Other

Sample Location: OBS #1

County:

Reference Number: 05-05830

Project: 76494

Field ID: WWBWC

Lab Number: 04613162

Date Collected: 5/19/2005 Date Extracted: 508_050601

Date Analyzed: 6/2/2005

Report Date: 6/3/2005

Analyst: MW

Supervisor: <

EPA Method 508.1 For State Drinking Water Complian

COMMENT
70111112111

^{*-} An amount of "ND" indicates that the compound was not detected above the Lab's Method Detection Limit - MDL

J - Estimated value.

^{**-} Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. Slate Advisory Level (SAL) for Unregulated compounds. A blank MCL or SAL value indicates a level is not currently established.

^{***-} If a compound is detected > or = to the State Reporting Level, SRL, specified increased monitoring frequencies may occur per DOH.

^{****-} Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.



11525 Knudson Rd.

Burlington, WA 98233

(800) 755-9295

(360) 757-1400 - FAX (360) 757-1402

Page 1 of 1

CARBAMATES IN DRINKING WATER

Client Name: KUO Testing Labs Inc

337 S 1st

Othello, WA 99344

Reference Number: 05-05830

Project: 76494

Field ID: WWBWC Lab Number: 04613162 Date Collected: 5/19/2005 Date Extracted: 531_050609 Date Analyzed: 6/9/2005

Report Date: 6/13/2005

Analyst: TW

Supervisor:

System Name:

System ID Number: DOH Source Number:

Multiple Sources:

Sample Type:

Sample Purpose: Investigative or Other

Sample Location: OBS #1

County: Sampled By:

Sampler Phone:

DOH#	COMPOUNDS	RESULTS	Units	SRL	Trigger	MCL	COMMENT
	EPA Regulated	A CONTRACTOR OF THE SECOND SEC			1119901	- INOL	COMMENT
146	CARBOFURAN	ND	ug/L	1.8	1.8	40	
148	OXYMAL	ND	ug/L	4.0	4.0	200	
	EPA Unregulated						
141	3-HYDROXYCARBOFURAN	ND	ug/L	2.0	2.0		
142	ALDICARB	ND	ug/L	1.0	1.0		
143	ALDICARB SULFONE	ND	ug/L	1.6	1.6		
144	ALDICARB SULFOXIDE	ND	ug/L	1.0	1.0		
145	CARBARYL	ND	ug/L	2.0	2.0		
147	METHOMYL	ND	ug/L	1.0	4.0		
	State Unregulated - Other				119 12 1		
326	PROPOXUR (BAYGON)	ND	ug/L	1.0			
327	METHIOCARB	ND	ug/L	4			

^{*-} An amount of "ND" indicates that the compound was not detected above the Lab's Method Detection Limit - MDL.

^{**-} Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds. A blank MCL or SAL value indicates a level is not currently established.

^{***-} If a compound is detected > or = to the State Reporting Level, SRL, specified increased monitoring frequencies may occur per DOH.

^{****-} Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.

J - Estimated value.

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

part on a girl

19441" RUCH -VUD

DATE WES CHIEF.

12/8/2004

ST NO REPORT TO

12/9/2004

1/24/2005

W.W.B.W.C.

Constitution Constitution

PO Box 68

Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

7 - 19 Ac. 19 14 - 1944 1 - 1951

AMALYS 8

.

RESULTS

UNITS.

ANALYSIS

74116 OBS Well #1

SOC/Synthetic Organic Co

Report

.....

mg/13

mg/L Edge Analytical

<(0.001); indicates the analyte was not detected at or above the concentration indicated.

ND: None Detected.

mg/L. Indicates milligrams per litre

* PQL=Practical Quartitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

MDL: Method Detection Limit

Please check our our new Web Sue at http://www.kuotesting.com

Dr. Eugene Kuo, Quality Assurance Coordinator

01-24-03

Date

C (C) 9 C 8 39 5 858



11525 Knudson Rd. Burlington, WA 98233 (800) 755-9295

(360) 757-1400 - FAX (360) 757-1402

Page 1 of 1

HERBICIDES IN DRINKING WATER

Client Name: KUO Testing Labs Inc.

337 S 1st

Othello, WA 99344

System Name: System ID Number: DOH Source Number:

> Multiple Sources: Sample Type:

Sample Purpose: Investigative or Other Sample Location: OBS Well #1

County:

Reference Number: 04-12075

Project 74115/74116

Field ID: 74116 Lab Number: 04624846 Date Collected: 12/8/2004 Date Extracted: 515_041217 Date Analyzed: 1/5/2005 Report Date: 1/7/2005 Analyst: CMH

Supervisor:

	COMPOUNDS	RESULTS	Units	SRL	Trigger	MCL	COMMENT
	ÉPA Regulated						
37	2,4 - D	ND	ug/L	0.2	0.2	70	
38	2,4,5 - TP (SILVEX)	ND	ug/L	0.4	0.4	50	
134	PENTACHLOROPHENOL	ND	ug/L	0.08	0.08	1	
137	DALAPON	ND	ug/L	2	2	200	
139	DINOSEB	ND	ug/L	0.4	0.4	7	
140	PICLORAM	ND	ug/L	0.2	0.2	500	
	EPA Unregulated						
138	DICAMBA	ND	ug/L	0.2	0.2		
	State Unregulated						
	2,4 DB	ND	ug/L	1	1.0		
136	2,4,5 T	ND	Ug/L	0.4	0.4		
220	BENTAZON	ND	ug/L	0.5	0.5		
221	DICHLORPROP	ND	ug/L	0.5	0.5		
223	ACTIFLORFIN	ND	ug/L	2	2.0		
225	DACTHAL (DCPA)	ND	ug/L	0.1	0.1		
226	3.5 - DICHLOROBENZOIC ACID	ND	ug/L	0.5	0.5		
						1	
						1	
		į.					

^{*.} An amount of "ND" indicates that the compound was not detected above the Cab's Method Detection Limit - MDL

^{**} Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds

A bitsh MCL or SAL value indicates a level is not currently established.

***- If excreption is delected or = to the Glafe Reporting Level, SRL, specified increased monitoring frequencies may occur per DOH.

***- If excreption is delected or = to the Glafe Reporting Level, SRL, specified increased monitoring frequencies may occur per DOH.

***- Method Detection Limit is the lab a minimum concentration is greater than zero.

J - Estimator value.



11525 Knudson Rd.

Burlington, WA 98233

(360) 757-1400 - FAX (380) 757-1402

Page 1 of 2

SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

Client Name: KUO Testing Labs Inc.

337 S 1st

System ID Number: DOH Source Number:

Othello, WA 99344 System Name:

Reference Number: 04-12075

Project: 74115/74116

Field ID: 74116

Lab Number: 04624846

Date Collected: 12/8/2004

Date Extracted: 525_041220

Date Analyzed: 12/22/2004

Report Date: 1/6/2005

Analyst CMH Supervisor.

Multiple Sources: Sample Type:

Sample Purpose: Investigative or Other


Sample Location: OBS Well #1

)上併	COMPOUNDS	RESULTS	Units	SRL	Trigger	MCL	COMMENT
***********	EPA Regulated		1				
33	ENDRIN	ND	ug/L	0.02	0.02	2	
34	LINDANE (BLIC - GAMMA)	ND	ug/L	0.04	0.04	0.2	
35	METHOXYCHLOR	ND	ug/L	0.2	0.2	40	
117	ALACHLOR	ND	ug/L	0.4	0.4	2	
119	ATRAZINE	ND	ugiL	0.2	0.2	3	
120	BENZO(A)PYRENE	ND	ug/L	0.04	0.04	0.2	
122	CHLORDANE, TECHNICAL	ND	ug/L	0.4	0.4	2	
124	DI(ETHYLHEXYL) ADIPATE	ND	ug/L	1.3	1.3	400	
125	DI(ETHYLHEXYL)-PHTHALATE	ND	ugiL	1.3	1.3	6	
126	HEPTACHLOR	ND	ug/L	80.0	0.08	0.4	
127	HEPTACHLOR EPOXIDE (A&B)	ND	ug/L	0.04	0.04	0.2	
128	HEXACHLOROBENZENE	ND	ug/L	0.2	0.2	1	
129	HEXACHLOROCYCLO-PENTADIENE	ND	ug/L	0.2	0.2	50	
133	SIMAZINE	ND	ug/L	0.15	0.15	4	
	EPA Unregulated					-	
118	ALDRIN	ND	ug/L	0.2	0.2		
121	BUTACHLOR	ND	ug/L	0.4	0.4		
123	DIELDRIN	ND	ug/L	0.2	0.2		
130	METOLACHLOR	ND	ug/L	1	1.0	ì	
131	METRIBUZIN	ND	Ug/L	0.2	0.2	1	
132	PROPACHLOR	ND	ug/L	0.2	0.2		
	State Unregulated - Other		1				
	SROMACIL	ND	L/g/L	0.2	0.2		
	PROMETON	ND	ug/L	0.2	0.2		
	TERBACIL	ND	ug/L	0.2	0.2		
	DIAZINON	ND	ug/L	0.2	0.2		
	EPTC	ND	ug/L	0.3	0.3		
	4,4-DDD	ND	ug/L	0.2	0.2		
233	4,4-DDE	ND	⊔g/L	0.2	0.2		

^{**} Missense Contaminant (and), maximum pomilispile level of a commentant in water established by EPA, NPDWR. Slate Advisory Level (EAL) for Unregulated compounds. A blank MCL or SAL value indicates a level is not currently established.

^{***-} If a compound is detected > or = to the State Reporting Level, SRIL, specified increased monitoring frequencies may objurner DOH
***** Method Defection Limit is the lebts minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero

J - Estimated value



Report Date: 1/5/2005

Lab Number 04624845

Page 2 of 2



SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

DOH#	COMPOUNDS	RESULTS	Units	SRL	Trigger	MCL	COMMENT	
	4,4-DDT	ND	ug/L	0.2	0.2			
	CYANAZINE	ND	uġ/L	0.2	0.2	A .		
	MALATHION	ND	ug/L	0.2	0.2			
	PARATHION	ND	ug/L	0.2	0.2			
	TRIFLURALIN	ND	ug/L	0.2	0.2	1		
	- PAHs							
96	NAPTHALENE	ND	ug/L	0.1	0.1			
	FLUORENE	ND	ug/L	0.2	0.2			
	ACENAPHTHYLENE	ND	ug/L	0.2	0.2			
	ACENAPHTHENE	ND	ug/L	0.2	0.2			
	ANTHRACENE	ND	ug/L	0.2	0.2			
	BENZ(A)ANTHRACENE	ND	ugiL	0.1	0.1			
	BENZO(B)FLUORANTHENE	ND	ug/L	0.2	0.2			
	BENZO(G,H,I)PERYLENE	ND	ug/L	0.2	0.2		No. of the second	
	A commence of the commence of	ND	ug/L	0.2	0.2	i		
	BENZO(K)FLUORANTHENE CHRYSENE	ND	ug/L	0.2	0.2			
		ND	ug/L	0.2	0.2			
	DIBENZO(A,H)ANTHRACENE	AND ADDRESS OF THE PARTY OF THE	ug/L	0.2	0.2	İ		
	FLUORANTHENE	ND		0.2	0.2			
	INDENO(1,2,3-CD)PYRENE	ND	ug/L	0.2	0.2	İ		
	PHENANTHRENE	ND	ug/L	0.2	0.2			
257	PYRENE	ND	ng/L	0.2	0.2			
	- Phthalates	1100	-	0.6	0.6			
	BENZYL BUTYL PHTHALATE	ND	ug/L	0.000		İ		
	DI-N BUTYL PHTHALATE	ND	ug/L	0.6	0.6			
	DIETHYL PHTHALATE	ND	ug/L	0.6	0.6			
261	DIMETHYL PHTHALATE	ND	ug/L	C.6	0.6			
				1	1			
						1		
			1					
							_ 1	

J - Esilmated value.

An amount of "NDI indicates that the compound was not detected above the Lab's Method Detection Limit - MDL

Maximum Contaminant Level, maximum pennissable level of a configurant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds.

A blank MCL or SAL value indicates a level is not currently established.

If a compound is detected > or = to the State Reporting Level. SPL, specified increased monitoring frequencies may occur per DOH.

If a compound is detected > or = to the State Reporting Level. SPL, specified increased monitoring frequencies may occur per DOH.

If a compound is detected > or = to the State Reporting Level. SPL, specified increased monitoring frequencies may occur per DOH.

If a compound is detected > or = to the State Reporting Level. SPL.

If a compound on the state is the lab's minimum concentration is compound can be measured and reported with 90% confidence that the compound concentration is greater than zero.



11525 Knudson Rd. Burlington, WA 98233

(800) 755-9295

(360) 757-1400 - FAX (360) 757-1402

Page 1 of 1

CARBAMATES IN DRINKING WATER

Client Name: KUO Testing Labs Inc.

337 S 1st

Othello, WA 99344

System Name:

System ID Number: DOH Source Number:

Multiple Sources:

Sample Type:

Sample Purpose: Investigative or Other

Sample Location: OBS Well #1

County:

Reference Number: 04-12075

Project: 74115/74116

Field ID: 74116

Lab Number: 04624846

Date Collected: 12/8/2004

Date Extracted: 531_041215

Date Analyzed: 12/15/2004

Report Date: 12/20/2004

Analyst: TW

Supervisor:

146 148 141 142 143	EPA Regulated CARBOFURAN OXYMAL EPA Unregulated	ND ND	ug/L		Trigger	-	
148 141 142 143	OXYMAL		wall				
141 142 143		MD	-Air	1.8	1.8	40	
141 142 143	EPA Unregulated	1487	ug/L	4	4.0	200	
142 143							
143	3-HYDROXYCARBOFURAN	ND	ug/L	2	2.0		
	ALDICARB	MD	ug/L	1	1.0		
144	ALDICARB SULFONE	ND	↓g/L	1.6	1.6	+	
1-1-4	ALDICARB SULFOXIDE	ND	ug/L	1	1.0		
	CARBARYL	ND	ug/L	2	2.0		
	METHOMYL	ND	ug/L	1	4.0		
	State Unregulated - Other						
1	PROPOXUR (BAYGON)	ND	ug/L	1			
327	METHIOCARB	ND	ug/L	4			
			1				
į							
1							
		1					

^{*} An amount of "ID" indicates that the compound was not detected above the Lab's Method Detection Limit - MDL

An amount of '10' indicates that the compound was not detected above the Latis Method Detection Limit. • MDL

"- Meaning Contament Level, maximum permissible located a continent in water established by EPA, NPDWR, State Advisory Level (SAL) for Unregulated compounds.

A brank MCL or SAL value indicates a level is not ownerify established.

"-- If a compound is detected > or = to the State Reporting Level, SPL, specified increased monitoring frequencies may occur per DOH.

"--- Method Detection Limit is the labit wherein the concentration is compound can be measured and reported with 99% confidence that the compound concentration is greater than zero J - Estimated value.



11525 Knudson Rd. Burlington, WA 93233 (800) 755-9295 (360) 757-1400 - FAX (360) 757-1402

Page 1 of 1

SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

Client Name: KUO Testing Labs Inc.

337 S 1st

Othello, WA 99344

System Name:

System ID Number: DOH Source Number: Multiple Sources:

Sample Type:

Sample Purpose: Investigative or Other Sample Location: OBS Weli #1

County:

Reference Number: 04-12075

Project 74115/74116

Field ID: 74116

Lab Number 04624846 Date Collected: 12/8/2004

Date Extracted: 508_041220 Date Analyzed: 1/17/2005

Report Date: 1/7/2005 Analyst CMH

Supervisor.

Bs/Toxaphene KAPHENE OCLOR 1221 OCLOR 1232 OCLOR 1242 OCLOR 1248 OCLOR 1254 OCLOR 1260 OCLOR 1016	ND ND ND ND ND ND	ug/L ug/L ug/L ug/L ug/L ug/L ug/L	2 20 0.5 0.5 0.1 0.1 0.2 0.1	2 20 0.5 0.3 0.1 0.1 0.2 0.1	3	
OCLOR 1221 OCLOR 1232 OCLOR 1242 OCLOR 1248 OCLOR 1254 OCLOR 1260	ND ND ND ND ND	ug/L ug/L ug/L ug/L ug/L ug/L	20 0.5 0.5 0.1 0.1 0.2	20 0.5 0.3 0.1 0.1	3	
OCLOR 1232 OCLOR 1242 OCLOR 1248 OCLOR 1254 OCLOR 1260	ND ND ND ND	ug/L ug/L ug/L ug/L ug/L	0.5 0.5 0.1 0.1 0.2	0.5 0.3 0.1 0.1 0.2		
OCLOR 1242 OCLOR 1248 OCLOR 1254 OCLOR 1260	ND ND ND	ug/L ug/L ug/L ug/L	0.5 0.1 0.1 0.2	0.3 0.1 0.1 0.2		
OCLOR 1248 OCLOR 1254 OCLOR 1260	ND ND ND	ug/L ug/L ug/L	0.1 0.1 0.2	0.1 0.1 0.2		
OCLOR 1254 OCLOR 1260	ND ND	ug/L ug/L	0.1	0.1		
OCLOR 1260	ND	ug/L	0.2	0.2		
OCLOR 1016	ND	ug/L	0.1	0.1		

An encount of "ND" indicates that the contigound was not detected above the Latin Method Detection Limit - MDL.
 Maximum Commission Level, maximum permissible level of a contaminant in water established by EPA, NPOWR. State Advisory Level (SAL) for Unregulated compounds.

A bignix MCL or SAL value indicates a level is not ourrently established.

**** If a compound is detected > or = to the State Reporting Level, SPL, specified increased monitoring frequencies may occur per DOH.

***** Melicol Detection Limit is the lab's minimum concentration a compound can be researched and reported with 99% confidence that the compound concentration is greater than zero J - Estimated value

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free http://www.kuotesting.com e-mail: kuotest@atnet.net

TALE COLLECTED

12/8/2004

DATE RECEIVED

tent offered als

SYSTEM ROUNDEDOME.

W.W.B.W.C. PO Box 68

Milton Freewater OR

97862

Project Name:

SHAD RESORT TO 12/9/2004

1/24/2005

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

SAMPLE NO GLIFT WAYS

ANHAGE

RESULTS

mg/L

Edge Analytical

THE MALE STOP 74115

SOC/Synthetic Organic Co

Report

<(0.001): indicates the analyte was not detected at or above the concentration indicated

mg/L indicates milligrams per litre

* PQL=Practical Quentifation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

MDL: Method Detection Limit

Please check out our new tyet Site at http://www.knotestiap.com

110 Dr. Fusene Kuo, Quality Assurance Coordinator

FAX NO.

MA 04:0 LEW 80-82-TOO KNO LESTINGLABSING



11525 Knudson Rd. Burlington, WA 98233

(800) 755-9295

(360) 757-1400 - FAX (360) 757-1402

Page 1 of 1

CARBAMATES IN DRINKING WATER

Client Name: KUO Testing Labs Inc.

337 S 1st

Othello, WA 99344

System Name:

System ID Number.

DOH Source Number.

Multiple Sources:

Sample Type:

Sample Purpose: Investigative or Other

Sample Location: Intake

County:

Reference Number: 04-12075

Project 74115/74116 .

Field ID: 74115

Lab Number: 04624845

Date Collected: 12/8/2004

Date Extracted: 531_041215

Date Analyzed: 12/15/2004

Report Date: 12/20/2004

Analyst: TW

Supervisor:

OH#	COMPOUNDS	RESULTS	Units	SRL	Trigger	MCL	COMMENT
	EPA Regulated				99-	11102	V V VIIVILIVI
	CARBOFURAN	ND	ug/L	1.8	1.8	40	
148	OXYMAL	ND	ug/L	4	4.0	200	
	EPA Unregulated						
	3-HYDROXYCARBOFURAN	ND	ug/L	2	2.0		
	ALDICARB	ND	ug/L	1	1.0	į i	
143	ALDICARB SULFONE	ND	ug/L	1.6	1.6		
144	ALDICARB SULFOXIDE	ND	ug/L	1	1.0		
	CARBARYL	ND	ug/L	2	2.0		
147	METHOMYL	ND	ug/L	1	4.0		
	State Unregulated - Other						
326	PROPOXUR (BAYGON)	ND	ug/L	1			
327	METHIOCARB	ND	ug/L	4			
							4.5.2.2.2.2.2.2.2.2.2.2.2.2.2.2.2.2.2.2.
1							
-							
1							
1			100				1

⁻ An amount of NIT indicates that the compound was not detected above the Leb's Method Detection Limit - MCL.

-- An amount of NIT indicates that the compound was not detected above the Leb's Method Detection Limit - MCL.

-- Mountain Contaminant Levol, inspiritum permissible level of a contaminant in water established by EFA, NPOWR. State Advisory Level (SAL) for Unregulated compounds.

-- A blank MCDL or SAL value indicates a level is not currently established.

-- If a compound is detected > or = to the State Reporting Level SRL, appected increased monoring frequencies may occur per DOH.

-- Moting Detected Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concertration is greater than zero



11525 Knudson Rd Burlington, WA 98233 (800) 755-9295 (360) 757-1400 - FAX (360) 757-1402

Page 1 of 2

SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

Client Name: KUO Testing Labs Inc

337 S 1st

Othello, WA 99344

System Name:

System ID Number:

DOH Source Number:

Multiple Sources:

Sample Type:

Sample Purpose: Investigative or Other

Sample Location: Intake

County:

Reference Number: 04-12075

Project: 74115/74116

Field ID: 74115

Lab Number: 04624845

Date Collected: 12/8/2004

Date Extracted: 525_041220 Date Analyzed: 12/21/2004

Report Date: 1/5/2005

Analyst: CMH

Supervisor:

d sas a See State Drinking Water Compliance

OOH#	COMPOUNDS	RESULTS	Units	SRL	Trigger	MCL	COMMENT	
	EPA Regulated	A COMPANY OF THE PARTY OF THE P	THE PERSON NAMED IN		1			
33	ENDRIN	ND	ug/L	0.02	0.02	2		
	LINDANE (BHC - GAMMA)	ND	ug/L	0.04	0.04	0.2		
35	METHOXYCHLOR	ND	ug/L	0.2	0.2	40		
117	ALACHLOR	ND	ug/L	0.4	0.4	2	į	
	ATRAZINE	ND	ug/L	0.2	0.2	3		
	BENZO(A)PYRENE	ND	ug/L	0.04	0.04	0.2		
	CHLORDANE, TECHNICAL	ND	ug/L	0.4	0.4	2		
	DI(ETHYLHEXYL)-ADIPATE	ND	ug/L	1.3	1.3	400		
	DI(ETHYLHEXYL)-PHTHALATE	ND	ug/L	1.3	1.3	6		
	HEPTACHLOR	ND	ug/L	0.08	0.08	0.4		
	HEPTACHLOR EPOXIDE (A&B)	NO	ug/L	0.04	0.04	0.2		
	HEXACHLOROBENZENE	ND	ug/L	0.2	0.2	1		
	HEXACHLOROCYCLO-PENTADIENE	ND	ug/L	0.2	0.2	50		
	SMAZINĒ	ND	ug/L	0.15	0.15	4		
	EPA Unregulated							
118	ALDRIN	ND	ug/L	0.2	0.2	1		
	BUTACHLOR	ND	ug/L	0.4	0.4			
	3 DIELDRIN	ND	ug/L	0.2	0.2			
	METOLACHLOR	ND	ug/L	1	1.0			
	1 METRIBUZIN	ND	ug/L	0.2	0.2			
	2 PROPACHLOR	ND	ug/L	0.2	0.2			
	State Unregulated - Other				1 22			
179	B BROMACIL	ND	ug/L	0.2	0.2	1		
18	3 FROMETON	ND	ug/L	0.2	0.2			
	0 TERBACIL	ND	ug/L	0.2	0.2			
35.00	2 DIAZINON	ND	ug/L	0.2	0.2		3	
	8 EPTC	ND	ug/L	0.3	0.3			
	2 4,4-000	ND	ug/L	0.2	C.2			
	3 4,4-DDE	ND	ug/L	0.2	0.2			

FORM, SOCHY

9989987609 ON XAT OCL-Se-02 MED 8:41 PW KNO LESTINGLABSING

^{*}An emount of 'ND' indicates that the compound was not detected above the Latis Method Detection Limit - MOL.

*An emount of 'ND' indicates that the compound was not detected above the Latis Method Detection Limit - MOL.

*A blank MC, or SAL value indicates a laye) is not outrinity established.

A blank MC, or SAL value indicates a laye) is not outrinity established.

**If a compound is detected > or = to the State Reporting Level, SPL, apesited independ more large frequencies may occur per DOH

***If a compound is detected > or = to the State Reporting Level, SPL, apesited independ and reported with 39% confidence that the compound concentration is greater than zero.

***Lighted Detection Limit is the light's minimum concentration a compound can be measured and reported with 39% confidence that the compound concentration is greater than zero.

***Lighted Detection Limit is the light's minimum concentration a compound can be measured and reported with 39% confidence that the compound concentration is greater than zero.



11525 Knudson Rd.

Burtington, WA 98233

(800) 755-9295

(360) 757-1400 - FAX (360) 757-1402

Page 1 of 1

HERBICIDES IN DRINKING WATER

Client Name: KUO Testing Labs Inc

337 S 1st

Othelio, WA 99344

System Name:

System ID Number:

DOH Source Number:

Multiple Sources:

Sample Type:

Sample Purpose: Investigative or Other

Sample Location: Intake

County:

Reference Number: 04-12075

Project: 74115/74116

Field ID: 74115

Lab Number: 04624845

Date Collected: 12/8/2004

Date Extracted: 515_041217

Date Analyzed: 1/5/2005

Report Date: 1/7/2005

Analyst: CMH


Supervisor.

DA Mathad 515 1 For State Drinking Water Compliance

PA Regulated	THE REAL PROPERTY AND ADDRESS OF THE PARTY AND					
.4 - D	ND	ug/L	0.2	0.2	70	
1,4,5 - TP (SILVEX)	ND	ug/L	0.4	0.4	50	
PENTACHLOROPHENOL	ND	ug/L	0.08	0.08	1	
DALAPON	ND	ug/L				
DINOSEB	ND	ug/L	0.4	550		105 05 FD 11075
PICLORAM	ND	ug/L	0.2	0.2	500	SEE COVER NOTE
EPA Unregulated						
DICAMBA	ND	ug/L	0.2	0.2		
State Unregulated		1				
2,4 DB	ND	ug/L				
2.4,5 T	ND	ug/L	10000			
BENTAZON	ND	ug/L		1000		i
DICHLORPROP	ND	ug/L				
ACTIFLORFIN	ND	ψg/L				
DACTHAL (DCPA)	ND	ug/L				
3,5 - DICHLOROBENZOIC ACID	ND	ug/L	0.5	0.5		
		·				
		24/0				
or Stall value indicates a tevel is not currently est	ablished.			NAME:		
O. O. O. O. O. O. O. O. O. O. O. O. O. O	ALAPON INOSEB ICLORAM EPA Unregulated ICAMBA State Unregulated 4 DB 4.5 T SENTAZON ICCHLORPROP ICTIFLORFIN DACTHAL (DCPA) 8.5 - DICHLOROBENZOIC ACID OF indicates that this compound was not detected minant (evol, maximum permissible level of a ci or SAL value midicates a tevel is not currently cist a detected > or = to the State Reporting Lavel is ion Livit is the tab's minimum concentration a ci	ALAPON INOSEB ICLORAM PA Unregulated ICAMBA IState Unregulated ICAMBA ISTATE Unregulated ICAMBA IND	ALAPON INOSEB ICLORAM	ALAPON ALAPON INOSEB ND Ug/L 0.4 ND Ug/L 0.2 ICLORAM ND Ug/L 0.2 ICLORAM ND Ug/L 0.2 ICLORAM ND Ug/L 0.2 ICLORAM ND Ug/L 0.2 ICLORAM ND Ug/L 0.2 ICLORAM ND Ug/L 0.2 ICLORAM ND Ug/L 0.2 ICLORAM ND Ug/L 0.4 ICLORAM ND Ug/L 0.5 ICLORAM ICLORAM ND Ug/L 0.5 ICLORAM	ALAPON ALAPON IND Ug/L 0.4 0.4 0.4 0.4 0.4 0.6 IND Ug/L 0.2 0.2 EPA Unregulated RGAMBA RD Ug/L 0.2 0.2 0.2 RGAMBA REAL Unregulated A DB A,5 T ND Ug/L 0.4 0.4 0.4 0.4 0.5 IND Ug/L 0.5 0.5 IND Ug/L 0.5 0.5 IND Ug/L 0.5 0.5 IND Ug/L 0.5 0.5 IND Ug/L 0.5 0.5 IND Ug/L 0.5 0.5 IND Ug/L 0.5 0.5 IND Ug/L 0.5 0.5 IND Ug/L 0.5 0.5 IND Ug/L 0.5 0.5 IND Ug/L 0.5 0.5 IND Ug/L 0.5 0.5 IND Ug/L 0.5 0.5 IND Ug/L 0.5 0.5 IND Ug/L 0.5 0.5 IND Ug/L 0.5 0.5 IND Ug/L 0.5 0.5 IND Ug/L 0.5 0.5 IND Ug/L 0.5 IND Ug/L 0.5 IND Ug/L 0.5 IND Ug/L 0.5 IND Ug/L 0.5 IND Ug/L 0.5 IND Ug/L 0.5 IND Ug/L 0.5 IND Ug/L 0.5 IND Ug/L 0.5 IND Ug/L 0.5 IND Ug/L 0.5 IND Ug/L 0.5 IND Ug/L 0.5 IND Ug/L 0.5 IND Ug/L 0.5 IND Ug/L	ENTACHLOROPHENOL ALAPON ND ug/L 0.4 0.4 0.4 7 INDSEB ND ug/L 0.2 0.2 500 EPA Unregulated ICAMBA ND ug/L 0.2 0.2 500 EPA Unregulated ICAMBA ND ug/L 0.2 0.2 500 EPA Unregulated IND ug/L 0.4 0.4 0.5 0.5 IND ug/L 0.5 0.5 IND ug/L 0.5 0.5 IND Ug/L 0.5 0.5 IND Ug/L 0.5 0.5 IND Ug/L 0.5 0.5 IND Ug/L 0.5 0.5 IND Ug/L 0.5 0.5 IND Ug/L 0.5 0.5 IND Ug/L 0.5 0.5 IND Ug/L 0.5 0.5 IND Ug/L 0.5 0.5 IND Ug/L IND Ug/L IND Ug

FORM: SOC97

9989887609 FAX NO. OCT-26-05 WED 9:41 AM KUO TESTINGLABSING





11525 Knudson Rd. Burlington, WA 98233

(800) 755-9295 (380) 757-1400 - FAX (360) 757-1402

Page 1 of 1

SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

Client Name: KUO Testing Labs Inc

337 S 1st

Othello, WA 99344

System Name:

System ID Number:

DOH Source Number:

Multiple Sources:

Sample Type:

Sample Purpose: Investigative or Other

Sample Location: Intake

County:

Reference Number: 04-12075

Project: 74115/74116

Field ID: 74115

Lab Number: 04624845

Date Collected 12/8/2004

Date Extracted: 508_041220

Date Analyzed: 12/22/2004

Report Date: 1/5/2005

Analyst: CMH

Supervisor

	1	EPA Method 508.1 F	or State D	rinking Wa	ter Complia	nce	. yan a ama a maa
DOH#	COMPOUNDS	RESULTS	Units	SRL	Trigger	MCL	COMMENT
	PCBs/Toxaphene						
36	TOXAPHENE	ND	ug/L	2	2	3	
	AROCLOR 1221	ND	ug/L	20	20		
	AROCLOR 1232	ND	vg/L	0.5	0.5		
	AROCLOR 1242	ND	ug/L	0.5	0.3		
	ARDCLOR 1248	ND	ug/L	0.1	0.1		
	AROCLOR 1254	ND	ug/L	0.1	0.1		
	AROCLOR 1260	ND	ug/L	0.2	0.2		
	AROCLOR 1016	ND	ug/L	0.1	0.1		
					1		
							1
			· ·	1			
				i			

An amount of "ND" indicates that the corripound was not celected above the Lab's Method Detection Limit - MDL

J - Estimated value

FORM: 80087

9989887609 ON XAT OCL-Se-OF MID 8:43 AM KUO TESTINGLABSING



Reference Number: 04-12075 Lab Number: 04624846

Report Date: 1/6/2005

Page 2 of 2

SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

1-1#	COMPOUNDS	RESULTS	Units	SRL	Trigger	MCL	COMMENT
	4,4-DDT	ND	ug/L	0.2	0.2		
	CYANAZINE	ND	ug/L	0.2	0.2		
239	MALATHION	ND	ug/L	0.2	0.2	1	
	PARATHION	ND	ug/L	0.2	0.2	i	
	TRIFLURALIN	ND	ug/L	0.2	0.2		
	- PAHs						
96	NAPTHALENE	ND	ug/L	0.1	0.1		
	FLUORENE	ND	ug/L	0.2	0.2		
	ACENAPHTHYLENE	ND	ug/L	0.2	0.2		
	ACENAPHTHENE	ND	ug/L	0.2	0.2		
	ANTHRACENE	ND	ug/L	0.2	0.2		
	BENZ(A)ANTHRACENE	ND	ug/L	0.1	0.1		
	BENZO(B)FLUORANTHENE	ND	ug/L	0.2	0.2		
	BENZO(G,H,I)PERYLENE	ND	ug/L	0.2	0.2		
	BENZO(K)FLUORANTHENE	ND	ug/L	0.2	0.2		
	CHRYSENE	ND	ug/L	0.2	0.2		
	DIBENZO(A,H)ANTHRACENE	ND	ug/L	0.2	0.2		
	FLUORANTHENE	ND	ug/L	0.2	0.2		
	INDENO(1,2,3-CD)PYRENE	ND	ug/L	0.2	0.2		
	PHENANTHRENE	ND	ug/L	0.2	0.2		
	PYRENE	ND	ug/L	0.2	0.2		
231		IAD	ug/L	0.2	U.Z		
259	- Phthalates BENZYL BUTYL PHTHALATE	ND	ug/L	0.6	0.6		
	DI-N BUTYL PHTHALATE	ND	ugit	0.6	0.6		
	DIETHYL PHTNALATE	ND	ug/L	0.6	0.6		
		ND		0.6	0.6	4	
201	DIMETIME PHTHALATE	ND	ug/L	0.0	0.0		
			1	1		1	
						1	
			1				
		1			1	1	
		1					
			1				
			1				
		į				1	
						1	
			1				
						1	
		1				1	
			1		1		

J. Estimated value

An amount of "ND" indicates that the compound was not detected above the LED's Method Detection Limit - MDL.

Makingun Contaminant Level, maximum permissable level of a configurant in water established by EPA. NPDWR - State Advisory Level (SAL) for Unregulated compounds. A blank MCL or SAL value indicates a level is not currently established.

If a compound is detected > or = to the Blank Reporting Level, SRIL, specified indicated in minimum permissable and reported with 93% confidence that the compound concentration is greated than zero.

337 South 1st Avenue, Othello, WA 99344 (509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free http://www.kuotesting.com e-mail: kuotest@atnet.net

DATE OCH BUTER

12/1/2004

DATERICANTO

DATE REPORTED

GEND REPORT TO

12/6/2004

12/6/2004

SYSTEM - CAPTER BY

W.W.B.W.C. PO Box 68 Milton Freewater OR Project Name:

97862

Bob Bower PO Box 68 Milton Freewater OR

97862

74008

SALAMIT 'SA

Reesa Well

68 AL 45 S

Feeal E-Coli

INTS

ANALVSTS.

MPN/100mL Valley Environment

<(0.001): indicates the analyte was not detected at or above the concentration indicated.

ND None Detocated

work. Indicates milligrams per litre

PQL=Practical Quantitation Limit is the lewest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

MDL: Method Detection Limit.
Please check out gur new Web Site at http://www.kuotesilag.com

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free

Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

DATE	COLLEC)TI	50
12/1	/2004		

DATE RECEIVED

DATE REPORTED

12/1/2004

SEND REPORT TO

12/6/2004

12/6/2004

SYSTEM / CUSTOMER

W.W.B.W.C. PO Box 68

Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

SAMPLE NO

ANALYSIS

MOL

UNITS

74008

Reesa Well

Fecal E-Coli

3

MPN/100mL

Valley Enviornment

<(0.001): indicates the analyte was not detected at or above the concentration indicated.

ND: None Detected

mg/L:Indicates milligrams per litre

)L=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

.: Method Detection Limit

Please check out our new Web Site at http://www.kuotesting.com

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

DATE COLLECTED 12/1/2004 SYSTEM/CUSTOMER		DATE RECEIVED DATE REPORTED SEND REPORT TO: 12/6/2004 12/6/2004						
W.W.B.W.C. PO Box 68 Milton Freewater OR 97862 Project Name:			Bob Bower PO Box 68 Milton Freewater OR 97862 Attn:					
74025	McKnight	Fecal E-Coli	<1	1	MPN/100mL	Valley Enviornment		

<(0.001): indicates the analyte was not detected at or above the concentration indicated.

ND: None Detected

mg/L:Indicates milligrams per litre

QL=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

L: Method Detection Limit

rlease check out our new Web Site at http://www.kuotesting.com

12-07-04

Date

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

SAMPLE NO. CUSTOMER SAMPLE NO. Fecal E-Coli TIMPN/100m	12/6/2004 97862
74009 Brown Fecal E-Coli <1 I MPN/100m	ANALYSTS
	L Valley Enviornment

<(0.001): indicates the analyte was not detected at or above the concentration indicated.

Dr. Eagene Kuo, Quality Assurance Coordinator

ND: None Detected

mg/L:Indicates milligrams per litre

L=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

L: Method Detection Limit

Please check out our new Web Site at http://www.kuotesting.com

12-07-04

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free

http://www.kuotesting.com e-mail: kuotest@atnet.net Web Site:

DATE COLLECTED

DATE RECEIVED

DATE REPORTED

12/1/2004

SEND REPORT TO:

12/6/2004

12/6/2004

SYSTEM / CUSTOMER

W.W.B.W.C. PO Box 68 Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

IPLE NO	CUSTOMER SAMPLE NO	ANALYSIS	RESULTS	MOL	UNITS	ANALYSTS
74010	Winesap	Fecal E-Coli	<1	1	MPN/100mL	Valley Enviornmer

-						

<(0.001).	indicates the analy	to was not	detected	at or	ahove	the	concentration	indicated	
<(0.001):	indicates the analy	he was not	detected	at Oi	above	HIL	Concentiation	marcuted	

ND: None Detected

mg/L:Indicates milligrams per litre

QL=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

L: Method Detection Limit

Please check out our new Web Site at http://www.kuotesting.com

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free

Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

DATE COLLECTED

DATE RECEIVED

DATE REPORTED

12/1/2004

SEND REPORT TO

12/6/2004

12/6/2004

SYSTEM / CUSTOMER

W.W.B.W.C. PO Box 68

Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

AMPLE NO	CUSTOMER SAMPLE NO	ANALYSIS	RESULTS	MDL	UNITS	ANALYSTS
74011	Frog	Fecal E-Coli	<1	1	MPN/100mL	Valley Enviornmer
74011						
-					-	
			And the second s			

<(0.001): indicates the analyte was not detected at or above the concentration indicated.

ND: None Detected

mg/L:Indicates milligrams per litre

L=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

L: Method Detection Limit

See at http://www.kuotesting.com Please check out our new Web

Kuo Testing Labs, Inc. 337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free

Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

W.W.B.W.C. PO Box 68 Milton Freewater OR 97862 Project Name:		Bob Bower PO Box 68 Milton Freewater OR 97862 Attn:				
AMPLE NO. CUSTOMER SAMPLE NO	ANALYSIS	RESULTS	MOL	UNITS	ANALYSTS	
74012 Vern's Well	Fecal E-Coli	<1	1	MPN/100mL	Valley Enviornment	

DL=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

12-07-04

ng/L:Indicates milligrams per litre

Please check out our new Web site at http://www.kuotesting.com

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free

(50) 100	0112 1 Home (50) 100 0110 1	WA (000)	DAO OTTA TOTTATO
Web Site:	http://www.kuotesting.com	e-mail:	kuotest@atnet.net

DATE COLLECTED

12/1/2004

DATE RECEIVED

DATE REPORTED

SEND REPORT TO

12/6/2004

12/6/2004

W.W.B.W.C.

SYSTEM / CUSTOMER

PO Box 68

Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

MPLE NO.	CUSTOMER SAMPLE NO	ANALYSIS	RESULTS	MOL	UNITS	ANALYSTS
74013	LeFore	Fecal E-Coli	<1	1	MPN/100mL	Valley Enviornment
			- And the second			
-						
a a management						
		· · · · · · · · · · · · · · · · · · ·				

<(0.001): indicates the analyte was not detected at or above the concentration indicated.

ND: None Detected

mg/L:Indicates milligrams per litre

)L=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

L: Method Detection Limit

Please check out our new Welf Site at http://www.kuotesting.com

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free

http://www.kuotesting.com e-mail: kuotest@atnet.net

DATE COLLECTED

DATE RECEIVED

DATE REPORTED

12/1/2004

SEND REPORT TO

12/6/2004

12/6/2004

SYSTEM / CUSTOMER

W.W.B.W.C. PO Box 68

Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

AMPLE NO.	CUSTOMER SAMPLE NO	ANALYSIS	RESULTS	MOL	UNITS	ANALYSTS
74014	John P.	Fecal E-Coli	<1	1	MPN/100mL	Valley Enviornmen
, , , , ,						
		and the second s				

<(0.001): indicates the analyte was not detected at or above the concentration indicated.

ND: None Detected

ng/L:Indicates milligrams per litre

QL=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

DL: Method Detection Limit

Please check out our pew Wood Site at http://www.kuotesting.com

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free

Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

DATE COLLECTED

12/1/2004

DATE RECEIVED

DATE REPORTED

SEND REPORT TO:

12/6/2004

12/6/2004

SYSTEM / CUSTOMER W.W.B.W.C.

PO Box 68

Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

AMPLE NO.	CUSTOMER SAMPLE NO	ANALYSIS	RESULTS	MOL	UNITS	ANALYSTS
74015	Wondra Well	Fecal E-Coli	<1	1.	MPN/100mL	Valley Enviornmen
					- Anna Anna Anna Anna Anna Anna Anna Ann	
-						
-						

<(0.001): indicates the analyte was not detected at or above the concentration indicated.

ND: None Detected

mg/L:Indicates milligrams per litre

QL=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

L: Method Detection Limit

Please check out our new Web/site at http://www.kuotesting.com

12-07-04

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free http://www.kuotesting.com e-mail: kuotest@atnet.net

DATE COLLECTED

DATE RECEIVED

DATE REPORTED

12/1/2004 SYSTEM / CUSTOMER

SEND REPORT TO

12/6/2004

12/6/2004

W.W.B.W.C. PO Box 68

Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

SAMPLE NO CUSTOMER

	SAMPLE NO	ANALYSIS	RESULTS	MOL	UNITS	ANALYSTS
74016	OBS Well 3B	Fecal E-Coli	<1	1	MPN/100mL	Valley Enviornment
-						
-						
-	**					

<(0.001): indicates the analyte was not detected at or above the concentration indicated.

ND: None Detected

mg/L:Indicates milligrams per litre

D=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions : Method Detection Limit

Please check out our new, Web Site at http://www.kuotesting.com

Kuo Testing Labs, Inc. 337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

W.W.B.W.C. PO Box 68 Milton Freewater OR 97862 Project Name:			SEND RE		2/6/2004	DATE REPORTED 12/6/2004	
		Bob Bower PO Box 68 Milton Freev Attn:		er OR 9	97862		
AMPLE NO.	SAMPLE NO	ANALYSIS	RESULTS	MDL	UNITS	ANALYSTS	
74017	OBS Well #2	Fecal E-Coli	<1	1	MPN/100mL	Valley Enviornment	
\							
			m 100				
(0.001): indi	cates the analyte was not de	etected at or above the concentration indicated.					

QL=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

mg/L:Indicates milligrams per litre

L: Method Detection Limit

Please check out our new Web Site at http://www.kuotesting.com

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

DATE	COLLEC	TED
12/1	/2004	

DATE RECEIVED

DATE REPORTED

12/1/2004 SYSTEM/CUSTOMER

SEND REPORT TO

12/6/2004

12/6/2004

W.W.B.W.C. PO Box 68

SAMPLE NO.

Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

ANALYSIS
RESULTS
MDL UNITS
ANALYSIS
74018
OBS Well IA
Fecal E-Coli
<| 1 | 1 | MPN/100mL | Valley Enviornment

| 1 | MPN/100mL | Valley Enviornment | MPN/100mL | Valley Enviornment | MPN/100mL | Valley Enviornment | MPN/100mL | Valley Enviornment | MPN/100mL | Valley Enviornment | MPN/100mL | Valley Enviornment | MPN/100mL | Valley Enviornment | MPN/100mL | Valley Enviornment | MPN/100mL | Valley Enviornment | MPN/100mL | Valley Enviornment | MPN/100mL | Valley Enviornment | MPN/100mL | Valley Enviornment | MPN/100mL | Valley Enviornment | MPN/100mL | Valley Enviornment | MPN/100mL | Valley Enviornment | MPN/100mL | Valley Enviornment | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL | MPN/100mL

<(0.001): indicates the analyte was not detected at or above the concentration indicated.

ND: None Detected

mg/L:Indicates milligrams per litre

QL=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

DL: Method Detection Limit

Please check out our new Welf Site at http://www.kuotesting.com

Dr. Eugene Kuo, Quality Assurance Coordinator

12-07-04

Date

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free http://www.kuotesting.com e-mail: kuotest@atnet.net Web Site:

DATE COLLECTED

DATE RECEIVED

DATE REPORTED

SYSTEM / CUSTOMER

12/1/2004

SEND REPORT TO

12/6/2004

12/6/2004

W.W.B.W.C. PO Box 68

Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

MPLE NO	CUSTOMER SAMPLE NO	ANALYSIS	RESULTS	MDL	UNITS	ANALYSTS
74019	OBS Well 1B	Fecal E-Coli	<1	I	MPN/100mL	Valley Enviornmen
-						
****	W					

<(0.001): indicates the analyte was not detected at or above the concentration indicated.

Dr. Eugene Kuo, Quality Assurance Coordinator

ND: None Detected mg/L:Indicates milligrams per litre

L=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

L: Method Detection Limit

Please check out ourney Web Site at http://www.kuotesting.com

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

DATE COLLECTED

DATE RECEIVED

DATE REPORTED

12/1/2004

SEND REPORT TO:

12/6/2004

12/6/2004

SYSTEM / CUSTOMER

W.W.B.W.C. PO Box 68

Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

CHMPLE INC.

CUSTOMER SAMPLE NO

ANALYSIS

ESULTS

MUL

UNITS

NALIYSTS

74020 Intake B Fecal E-Coli <1 1 MPN/100mL Valley Enviornment

<(0.001): indicates the analyte was not detected at or above the concentration indicated. ND: None Detected

mg/L:Indicates milligrams per litre

QL=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

L: Method Detection Limit

Please check out our new Web Site at http://www.kuotesting.com

Dr. Eugene Kuo, Quality Assurance Coordinator

12-07-04

Date

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free http://www.kuotesting.com e-mail: kuotest@atnet.net

DATE COLLECTED

DATE RECEIVED

DATE REPORTED

12/1/2004

SEND REPORT TO:

12/6/2004

12/6/2004

SYSTEM / CUSTOMER

W.W.B.W.C. PO Box 68

Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

SAMPLE NO

CUSTOMER UNITS SAMPLE NO 74021 Intake A Fecal E-Coli MPN/100mL Valley Enviornment <1

<(0.001): indicates the analyte was not detected at or above the concentration indicated.

ND: None Detected

mg/L:Indicates milligrams per litre

'QL=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

L: Method Detection Limit

Please check out our new Web Site at http://www.kuotesting.com

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free

http://www.kuotesting.com e-mail: kuotest@atnet.net Web Site:

DATE COLLECTED

12/1/2004

DATE RECEIVED

DATE REPORTED

Valley Enviornment

SEND REPORT TO:

12/6/2004

UNITS

MPN/100mL

12/6/2004

SYSTEM / CUSTOMER

W.W.B.W.C. PO Box 68

Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

SAMPLE NO.

CUSTOMER ANALYSIS SAMPLE NO OBS Well 4 Fecal E-Coli 74022 <1

<(0.001): indicates the analyte was not detected at or above the concentration indicated.

ND: None Detected

mg/L:Indicates milligrams per litre

QL=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

L: Method Detection Limit

Please check out our new Web Site at http://www.kuotesting.com

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

DATE RECEIVED DATE COLLECTED DATE REPORTED 12/1/2004 SEND REPORT TO: 12/6/2004 12/6/2004 SYSTEM / CUSTOMER W.W.B.W.C. Bob Bower PO Box 68 PO Box 68 Milton Freewater OR 97862 Milton Freewater OR 97862 Attn: Project Name: CUSTOMER ANALYSIS UNITS GW-39 74023 Fecal E-Coli MPN/100mL Valley Enviornment <1

QL=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

<(0.001): indicates the analyte was not detected at or above the concentration indicated.

ND: None Detected
mg/L:Indicates milligrams per litre

L: Method Detection Limit

rlease check out our new Web Site at http://www.kuatesting.com

Eugene Kuo, Quality Assurance Coordinator

12-07-04

Date

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free

http://www.kuotesting.com e-mail: kuotest@atnet.net

DATE	COLLECTED
1011	10004

DATE RECEIVED

DATE REPORTED

12/1/2004 SYSTEM / CUSTOMER

SEND REPORT TO:

12/6/2004

12/6/2004

W.W.B.W.C. PO Box 68

Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

SAMPLE NO.

SAMPLE NO

UNITS

MPN/100mL Prunedale Fecal E-Coli <1 Valley Enviornment 74024

<(0.001): indicates the analyte was not detected at or above the concentration indicated.

ND: None Detected

mg/L:Indicates milligrams per litre

QL=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

)L: Method Detection Limit

Please check out our new Web Site at http://www.kuotesting.com

337 South 1st Avenue, Othello, WA 99344 (509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

> DATE COLLECTED 12/1/2004

DATE RECEIVED

DATE REPORTED

SEND REPORT TO: 12/20/200

11/28/2005

W.W.B.W.C. PO Box 68

SYSTEM / CUSTOMER

Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

SAMPLE NO

CUSTOMER SAMPLE NO

ANALYSIS

RESULTS

UNITS MD

ANALYSTS

OBS Well 3A 74313

Fecal E-Coli

<1

MPN/100ml Cascade Analytical

(0.001): Indicates the analyte was not detected at or above the concentration indicated.

ND: None Detected

mg/L Indicates milligrams per litre

* PQL=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory uper sing conditions

MDL: Method Detection Limit

Please check out our new Web Site at http://www.kuotesting.com

337 South 1st Avenue, Othello, WA 99344 (509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

> DATE COLLECTED 1/5/2005

DATE RECEIVED

DATE REPORTED

SEND REPORT TO

1/6/2005

11/28/2005

W.W.B.W.C.

SYSTEM / CUSTOMER

PO Box 68

Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

SAMPLENO

CUSTOMER SAMPLE NO

ANALYSIS

RESULTS

UNITS MOL

ANALYSTS

GW 62 74644

Fecal E-Coli

11

MPN/100ml Cascade Analytical

QUIDOLE indicates the energie was not detected at or above the concentration indicated

** PQL**Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during rounne laboratory operating conditions

Please check out our new Web Site at http://www.kuolesting.com

337 South 1st Avenue, Othello, WA 99344 (509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

DATE COLLECTED

DATE RECEIVED

1/6/2005

DATE REPORTED

1/5/2005

SEND REPORT TO

11/28/2005

SYSTEM / CUSTOMER

W.W.B.W.C. PO Box 68

Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

SAMPLE NO

CUSTOMER SAMPLE NO

ANALYSIS

RESULTS

UNITS MOL

ANALYSTS.

OBS Well I Fccal E-Coli 74643

MPN/100ml Cascade Analytical

(U.UII), indicates the analyte was not detected at or above the concentration indicated. ND: None Detected

mg/L indicates milligrams per litre .

* PQL=Practical Questitation Limit is the lowest level that can be acquired within specified hearts of precision and accuracy during routine laboratory operating conditions. MDL Method Detection Little

Please check out our new Web She of https://www.kaatesting.com

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free http://www.kuotesting.com e-mail: kuotest@atnet.net

Web Site:

DATE COLLECTED 5/19/2005

DATE RECEIVED

DATE REPORTED

SEND REPORT TO: 5/25/2005

5/25/2005

SYSTEM / CUSTOMER

W.W.B.W.C. PO Box 68

Milton Freewater OR 97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

IPLE NO.	CUSTOMER SAMPLE NO	ANALYSIS	RESULTS	MDL	UNITS	ANALYSTS
76546	OBS #1	Fecal E-Coli	5	1	MPN/100 ml	Valley Enviornenta
-		1				
		•				
						

<(0.001): indicates the analyte was not detected at or above the concentration indicated.

ND: None Detected


* PQL=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

MDL: Method Detection Limit

Please check out our new Web Site at http://www.kuotesting.com

Dr. Eugene Kuo, Quality Assurance Coordinator

Date



Kuo Testing Labs, Inc. | Agricultural - Industrial - Environmental

Othello, Washington 99344

W.W.B.W.C. Client:

Address: PO Box 68

MiltonFreewater, OR 97862

Grower:

WWB2170 **PURCHASE ORDER#** INVOICE DATE INVOICE # CLIENT#

04-12-091 12/10/04

PN:

Project:

Sampler: Bob Bower

ifier Test Description Qty Price Extension	B.John P., LeFore, OBS Well 1B,OBS Well 3B, fecal Coliform OBS Well, Winesap,
Field Identifier Test	E74008 12/06/04 Brown.Frog.GW-39.Intake A.Intake B.John P., LeFore, McKnight, OBS Well #2, OBS Well 1A, OBS Well 4, Prunedale, Reesa Well, Vern's Well, Winesap,
RptNo RptDate	.2/06/04 Bro
RptNo	E74008 1

Notes: 04-12-091

Terms: Net 30 days following date of invoice. Invoices not paid in 30 days will be subject to interest charged at 1.5% per month (18% per year) with a minimum charge of 50 cents.

1215.00 Invoice Total

-0.00 % 0 FAX Charge Discount

00.0

\$1,215.00 **Invoice Total Due**

Due Date

01/09/05

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free

Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

DATE COLLECTED

12/1/04

DATE RECEIVED

DATE REPORTED

2/1/04

SEND REPORT TO:

12/20/04

12/20/04

W.W.B.W.C.

Project Name:

SYSTEM / CUSTOMER

PO Box 68

Milton Freewater OR

97862

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

SAMPLE NO.

OPLE NO. CUSTOMER SAMPLE NO

ANALYSIS

SIS

RESULTS

MDL

UNITS

ANALYSTS

74313

OBS Well 3A

Fecal E-Coli

<1

MPN/100mL

Valley Enviornment

<(0.001): indicates the analyte was not detected at or above the concentration indicated.

None Detected

L:Indicates milligrams per litre

QL=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

MDL: Method Detection Limit

Please check out our new Web Site at http://www.kuotesting.com

Dr. Eugene Kuo, Quality Assurance Coordinator

12-20-04

Date

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free http://www.kuotesting.com e-mail: kuotest@atnet.net

CAIX COLLEGIES

12/1/2004

DATE REGENTED

DATE REPORTED

SEND REPORT TO

12/6/2004

12/6/2004

为多年程(2017年)3年代

W.W.B.W.C. PO Box 68 Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

gald in feet plant troops

RESULTS

ANALYSTS

Vern's Well

MPN/100mL Valley Enviorement

74012

Feesl E-Coli

<0.001): indicates the analyte was not detected at or above the concentration indicated ND: None Dutected

* PQ1.-Practicel Quantitation 1 limit is the lowest level that can be achieved witten specified limits of precision and accuracy during routine laboratory operating conditions

MDL: Method Detection Limit

Please check out our new Weg Site at http://www.kuntesting.com

Dr. Eugene Kur, Quality Assurance Coordinator

12-07-04 Date

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free

Web Site:	http://www.kuotesting.com	n e-mail:	kuotest@	atnet.net
	BATH OUR SECTES		DATE RECEIVED	DATCREFORTLO
	10/1/0004	LATE DE DE DE TAI	10/6/0004	12/6/2004

W.W.B.W.C. PO Box 68 Milton Freewater OR

97862

Project Name:

SYSTEM CULTIFIER

Bob Bower PO Box 68 Milton Freewater OR

97862

 $\{ (N_{i,j}) \in \{0,0\} \}$ ANALYSIS Valley Enviorament Fecal E-Coli 74011

<0.001): indicates the analyte was not detected at or above the concentration indicated. ND: None Detected

mg/L:Indicates milligrams per litre

ring continuous uning our part is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions.

MDL: Method Detection Limit

Please wheck out our new the best of http://www.kuolesting.com

Quality Assurance Coordinator

337 South 1st Avenue, Othello, WA 99344 (509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free http://www.kuotesting.com c-mail: kuotest@atnet.net

DATE COLLECTED.

12/1/2004

DATE RUCL VID

DATE SEPONDER

SEND REPORT TO

12/6/2004

12/6/2004

SYSTEM CHEIT HAT P

W.W.B.W.C. PO Box 68 Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

BAMIL NO COLORS

(15 4 v NO)

MPN/100ml

74010

Winesap

Valley Enviorament

<(0.901): indicates the analyte was not detected at or above the concentration indicated.

mg/Lindicates milligrams per litre

• PQL-Practical Quantitation Limit is the lowest level that can be achieved within specified limits of practision and accuracy during routine laboratory operating conditions

MDL: Muthod Detection Limit

MDL: Method Detection Lunit
Please check out our new Wyo Site at http://www.kugtesting.com

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free http://www.kuotesting.com e-mail: kuotest@atnet.net Web Site:

DATE GUILFOTFO

DATE REPURE CO

12/1/2004

SEND REPORT TO

12/6/2004

DATE RECEIVED

12/6/2004

8 × 8 : 8 64 ((1 +) 135 5" (+

W.W.B.W.C. PO Box 68 Milton Freewater OR

97862

Bob Bower PO Box 68

Milton Freewater OR

97862

1 . 11 W. P

ANALYSIS

RESULTS

MOL

CHARTS

ANALYSTS.

MPN/100mL Valley Enviorement

Brown 74009

Project Name:

Fecal E-Coli

1

<(0.001); indicates the analyte was not detected at or above the concentration indicated. ND: None Detucted mg/L Indicates milliprams per inte

* PQL.-Practical Quantitation Limit is the lowest fevel that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

Plaase check out our flew 1966 Site at http://www.kwalesting.com

337 South 1st Avenue, Othello, WA 99344 (509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

> DATE STREETED 12/1/2004

DATERECENTED

DATE REPORTED

SEND REPORT TO

12/6/2004

12/6/2004

SESTEM CONTRACTOR

W.W.B.W.C. PO Box 68 Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

74025

Sandhart WO McKnight

AMALYS'S Fecal E-Coli

RESULTS

100773 MPN/100ml. ANALYSTS

Valley Enviorement

<(0.001); indicates the analyse was not detected at or above the concentration indicated

ND. None Descried

mg/L:indicates milligrams per litre

PQL-Practical Quantitation Limit is the lowest level that can be achieved within specified limits of practicion and accuracy during matine laboratory operating conditions

MDL: Method Detection Limit,
Please check out gar new Neb Site at http://www.kuotesting.com

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free http://www.kuotesting.com e-mail: kuotest@atnet.net

JAME COLLECTED

12/1/2004

DATE RECEIVED

DATE REPURTED

SEND REPORT TO

12/6/2004

12/6/2004

SYSTEM COUNTRIES OF

W.W.B.W.C. PO Box 68 Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

The second of th

WANTED HE CONTR

AMALVS/S

RESULTS

UNIS

ANALYST

MPN/100mL

Valley Enviornment

LeFore 74013

Fecal E-Coli

THE RESERVE OF THE PERSON OF T

No common to the second of the the second contract to the second contract to

the form of the contraction and the second of the contract of

to the many a country tracks it an appropriate account own 10000 - 1

The rate that were see to be seeing to strong and the control of the second sees of

The side of the state of the st

<(0.001): undicates the analyte was not detected at or above the concentration indicated ND: None Detected

ingressmancates tanggrouns per sure.

1 PQL—Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions.

MDL: Method Descetion Limit Please theck and our New Wey Sile on http://www.kuotesting.com

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free http://www.kuotesting.com e-mail: kuotest@atnet.net

DATE COLLECTED

12/1/2004

DATE RECEIVED

DATE REPORTED

SEND APPORT TO

12/6/2004

12/6/2004

SYSTEM COLLEGE IT

W.W.B.W.C. PO Box 68 Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

with the contract and the contract of the cont

A LIGHTE ALLEY THE

SWALTERS

RESC. 78

where the same of the state of the same of

ONTE MPN/100ml ANALYSTA

74014

Valley Enviornment

<0.001): indicates the analyte was not detected at or above the concentration indicated.

mp/L. Indicates milligrans per life

* PQL=Proptical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

MDL: Method Detection Limit Please check out our new Web Site at http://www.kuviesting.com

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free http://www.kuotesting.com e-mail: kuotest@atnet.net

DATE RECEIVED

DATE RUPORTED

DATE COLLECTED 12/1/2004

SEND REPORT TO

12/6/2004

12/6/2004

SVSTICE OF STAMES

W.W.B.W.C. PO Box 68

97862 Milton Freewater OR

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

state that the state

AMM YES

RESULTS

MPN/100mL

ANALYST'S

Valley Enviornment

Wondra Well 74015

the same of the same of the same

manufacture of the contract of

when the property of the second contract of t

<(0.001); indicates the analyte was not detected at or above the concentration indicated. ND: None Detected

NO: Poste Detection in the instruction is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions • PQL=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

MDL: Method Detection Limit Please check out our now Web file of http://www.kuotesting.com

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free http://www.kuotesting.com e-mail: kuotest@atnet.net

MATE COLLECTED.

DATE RECENTED

DATE REPORTED

12/1/2004

SOND REPORT TO: 12/6/2004

12/6/2004

SESTIMATE CLETONER

W.W.B.W.C. PO Box 68 Milton Freewater OR Project Name:

97862

Bob Bower PO Box 68 Milton Freewater OR

97862

Attn:

ANALYSTS UNITE 7 to 4,5141 m ANALYSIS A. 141 M. Valley Enviornment MPN/100mL Feeal H-Coli OBS Well 3B 74016

<(0.001) indicates the analyte was not detected at or above the concentration indicated.</p>

mgA. Indicates milligrams per litre

• PQL-Tractical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions ND: None Detected

MDL. Mahod Detection Limit Please check out our weng Web Site at http://www.kuotesting.com

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free http://www.kuotesting.com e-mail: kuotest@atnet.net

> DATE COLLECTED 12/1/2004

DATE RECEIVED

DATE REPORTED

SEND REPORT TO

12/6/2004

12/6/2004

pentity of the William

W.W.B.W.C. PO Box 68 Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

ANALYSIS Valley Enviorement MPN/100mL OBS Well #2 74017

<0.001); indicates the analyte was not detected at or above the concentration indicated.

ND: None Detected mg/L Indicates untiligrams per litre

ingo mancates many and part in the lowest level that can be achieved within specified limits of practical Quantitative during routine laboratory operating conditions.

Mill. Method Detection Limit

Please check out our new With Site at http://www.huotesting.com

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free http://www.kuotesting.com e-mail: kuotest@atnet.net

HATE COLLECTED

DATE RECEIVED

DATE RUPORTED

12/1/2004

SEND REPORT TO: 12/6/2004

12/6/2004

SECTION OF STORED

W.W.B.W.C. PO Box 68

Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

SAIS L. NO

FE KKI PHARLE NO ANTHYSIS

The second secon

UNITS

property of the party of the second section of the second section of the second section of the second section of the second section of the second section of the second section of the second section of the second section of the second section of the second section of the second section of the second section of the second section of the second section of the second section of the section of the second section of the second section of the second section of the section o

AMALYSIS

74018

OBS Well 1A

Fecal E-Coli

MPN/100ml. Valley Enviorament

<0.001); indicates the analyte was not detected at or above the concentration indicated.

ND: None Detected mg/L:ladicates milligrams per line PQL=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

Please check out our gen Wey Sue at http://www.kuntesting.com

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free http://www.kuotesting.com e-mail: kuotest@atnet.net

DATE RELEVED DAT COLLECTEL

DATE IC PORTED

12/1/2004

SENT/REPORT TO 12/6/2004

12/6/2004

Action to the second

Project Name:

W.W.B.W.C. PO Box 68 Milton Freewater OR

97862

Bob Bower PO Box 68

Milton Freewater OR

97862

THE STREET CONTROL OF THE STREET CONTROL OF

ANALYSIS UNITS ENGINEE N 12 198 1 W Valley Enviorament Feeal E-Coli OBS Well 1B 74019

<(0.001): indicator the analyse was not detected at or above the concentration indicated.

ND: None Detected

ring Entirences an imagencies per mine.

* PQL-Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions.

Please check out opening Web Site at http://www.kuntestinu.com

Kuo Testing Labs, Inc. 337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free http://www.kuotesting.com e-mail: kuotest@atnet.net

DATE COLLECTED

DATE REMARKS ED

SEND REPORT TO

12/6/2004

DATE RECEIVED

12/6/2004

54年117 M 2013 与标准处理

W.W.B.W.C. PO Box 68 Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68 Milton Freewater OR

97862

THE R. LEWISSELL. . HE WAS IN SCHOOL CO. COMMON SET THE PART OF THE LEWIS CO., LANSING, MICH.

11, the day in Small to Sile

ANALYSIS

12/1/2004

RESULTS

ANALYSIS

74020

intake B

Fecal E-Coli

<1

MPN/100ml. Valley Enviornment

<0.001): indicates the analyte was not detected at or above the concentration indicated ND None Detected

mgL. Indicates milligrams per litre

* PQL-Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

MDL: Method Detection Limit

Please check out our new Web Sue at http://www.kuotesting.com

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free http://www.kuotesting.com e-mail: kuotest@atnet.net

DATE RECEIPED

DATE REFORTED

PATE COLLECTED 12/1/2004

SEND OCPORT TO

12/6/2004

12/6/2004

SYSTEM, SICKLOSET

W.W.B.W.C. PO Box 68

Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68 Milton Freewater OR

97862

ANNEYET-Ph. WOMER STRANCE NO. MPN/100ml. Valley Enviorament Fecal E-Coli Intake A 74021

<(0.001): indicates the analyte was not detected at or above the concentration indicated.

ND None Detected

mg/Lindicates multigrams per litre

PQL-Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

PQL-Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

MDL: Method Detection Limit

Please check out our new Web Ble at http://www.kuotesting.com

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0.18 Fax (800) 328-0112 Toll Free http://www.kuotesting.com e-mail: kuotest@atnet.net

> CATE GOLLEGIED 12/1/2004

DATE RECEIVED

DATE FOR MARTED

SEND REPORT TO: 12/6/2004

12/6/2004

SECTION OF SHARP

W.W.B.W.C. PO Box 68 Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

The property of the second of

Milton Freewater OR

97862

Charles W.N.

ANALYSIS

ANALYSTS

The state of the s

MPN/100ml.

Valley Enviorement

OBS Well 4 74022

The second secon

AND THE PARTY AN

FOR A STATE OF THE PARTY OF THE

The same of the sa

<(0.001): indicates the analyte was not detected at or above the concentration indicated ND: None Derected

mg/L Indicates milligrams per litre * PQL-Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

MDL: Method Detection Limit Please check out our new Web Site of http://www.kuotesting.com

337 South 1st Avenue, Othello, WA 99344 (509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

PARE COLLECTED

DATE RECEIVED

DATE REPORTED

12/1/2004

SEND REPORT TO

12/6/2004

12/6/2004

BMB:5M 《工程扩张机构

W.W.B.W.C. PO Box 68 Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

ANKLYSIA

74023

GW-39

Feesl E-Coli

MI'N/100mL

Valley Enviorament

<(0.001): indicates the analyse was not detected at or above the concentration indicated.

ND: None Detected

* FQL-Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions MDL. Method Detection Limit

Please check out our new Web Silv of http://www.kuotesting.com

337 South 1st Avenue, Othello, WA 99344 (509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free

http://www.kuotesting.com e-mail: kuotest@atnet.net

DATE RECEVED DA & CONTECTED

BATCREFORTED

12/1/2004 SEND REPORT TO:

12/6/2004

12/6/2004

SVS TIGHTS STOMED

W.W.B.W.C. PO Box 68 Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

COLUMN CO

and the state of t

Berto treete comment of the same

97862

ANALYSIS ABALYSTS. MPN/100ml. Valley Enviorament Fecal E-Coli Prunedale 74024

s(0.001): indicates the analyte was not detected at or above the concentration indicated. ND: None Detected

* PQL: Practical Quantitation Limit is the lowest level that can be addicted within specified limits of precision and accuracy during routine laboratory operating conditions MDL: Method Detection Limit

Picase check out our new Well Site at http://www.kuvjerting.com

Dr. Eagene Kuo, Quality Assurance Coordinator

Date

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free http://www.kuotesting.com e-mail: kuotest@atnet.net

WIE COLLECTED

DATE REPORTED

4/6/2005

SEND REPORT TO

4/14/2005

DATE RECEIVED

4/14/2005

SHE THIS CONTOURE

Project Name:

W.W.B.W.C. PO Box 68 Milton Freewater OR

97862

Bob Bower PO Box 68 Milton Freewater OR

SEC 122 NO. COMMAN PROPERTY OF CONTRACTOR

97862

SAME (NO) YESTOWN P UNITS ANALYSTS ANALYSIS SECTION THE Fecal E-Coli 75928

-40.001): indicates the analyte was not detected at or above the concastration indicated.

ong L. Indicates milligrams per litre

• PQL -Praorical Quaptitution Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

MDL. Method Detection Limit

Please check out our new Web Site at http://www.kuotesting.com

Makylino for Gigan 8 Dr. Eugene Kug Quality Assurance Coordinator April 14 , 2005

337 South 1st Avenue, Othello, WA 99344 (509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free

http://www.kuotesting.com e-mail: kuotest@atnet.net

CARE COLLEGIED

4/6/2005

DATE RECLIVED

DATE REPORTED

SEND REPORT TO

4/14/2005

4/14/2005

STRIP OF THE PART

W.W.B.W.C. PO Box 68

Milton Freewater OR Project Name:

97862

Bob Bower PO Box 68

Milton Freewater OR

97862

COSTONIA R JUNE 25 MO ANGLYSIS.

75932

GW-62 9

Valley Labs

Fecal E-Coli

MPN/100 inl

<(0.001): indicates the analyte was not detected at or above the concentration indicated.

ND: None Detected mg/L motions management per nece and the lowest level that one be achieved within specified limits of precision and accuracy during routine laboratory operating conditions.

MDL Method Detection Limit

Please check aut our new Web Site in http://www.kuelesting.com

Mollogland Dr. Eugene Kuo, Quality Assurance Coordinator

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free http://www.kuotesting.com e-mail: kuotest@atnet.net

DATE REGENTED

DATE REFORELL

DATE COLLECTED 4/6/2005

SEND REPORT TO

4/14/2005

4/14/2005

SYSTEM CUTTOREF

W.W.B.W.C. PO Box 68 Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68 Milton Freewater OR

97862

SHARE CAR CARRIES UNITE ANALYSTE ANALYSIS SOMETH WE MPN/100 ml Fecal E-Coli OBS-1 75929

<(0.001): indicates the analyte was not detected at or above the concentration indicated.

ND. None Detected

ingle molecules managemes per une

PQL=Practical Quantitation Limis is the lowest level that can be achieved within specified limits of precision and accuracy during routing laboratory operating conditions

MDL. Method Detection Limit

Please check out our new Web Situ at http://www.kuolesting.com

Mollylin for for Dr. Eugene Ruo, Quality Assurance Coordinator

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free http://www.kuotesting.com c-mail: kuotest@atnet.net

DATE RECEIVED

DATE REPORTED

DATE COLLECTED 4/6/2005

SEND REPORT TO

4/14/2005

4/14/2005

searm obstitute

W.W.B.W.C. PO Box 68 Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68 Milton Freewater OR

97862

SAMOLENO CLETOMER UNITS RUSULTS SPOSHIE WO MPN/100 ml Valley Labs Pecal E-Coli 75930

<(0.001): indicates the analyte was not detected at or above the concentration indicated.

ND: None Detected

ingularing cares mangrains per nac.

* PQL=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions.

and the second care and is a second common to produce the common of the common contract that

MDL: Method Detection Limit

Piease check out our new Web Site of http://www.kuptesting.com

Mollylin for Gigane Dr. Eugene Ruo, Quality Assurance Coordinator Apr: 614, 2005

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free http://www.kuotesting.com e-mail: kuotest@atnet.net

DATE RUCENED

DATE REMOREED

DATE COLLECTED 4/6/2005

SCHUREPORT TO

4/14/2005

The second contract of the second

4/14/2005

SYST WITH HOME

Project Name:

W.W.B.W.C. PO Box 68

Milton Freewater OR

97862

Bob Bower PO Box 68

Milton Freewater OR

97862

and any other section of the section

SAMP, I BE. PARTINGS B CHARLE ANALYSTS ANALY 345 WASSELF WY 75931

-(0.001): indicates the analyse was not detected at or above the concentration indicated.

ND: None Detected

mg/Lindicates milligrams per live

Poli-Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

Poli-Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

MDL: Melliod Detection Limit

Please check out our new Web Site at http://www.kuotesting.com

Mollyline for Engane Dr. Eugen Kuo, Quality Assurance Coordinator

Di(2-ethylhexyl) Phthalate Chemical Backgrounder

ONLY Analyte 2354

Description:

Di(2-ethylhexyl) phthalate, (C.A.S. 117-81-7) also commonly called bis(2-ethylhexyl) phthalate, is a colorless, oily liquid with a slight odor. Patented in 1933, it is primarily used as one of several plasticizers in polyvinyl chloride (PVC) resins for fabricating flexible vinyl products. These PVC resins have been used to manufacture teething rings, pacifiers, soft squeeze toys, balls, shower curtains, raincoats, adhesives, polymeric coatings, components of paper and paperboard, defoaming agents, enclosures for food containers, animal glue, surface lubricants, flexible devices for administering parenteral solutions, and other products that must stay flexible and uninjurious for their lifetime. It is also used to manufacture vinyl gloves used for medical examinations and surgery.

As a non-plasticizer, di(2-ethylhexyl) phthalate is used as a replacement for polychlorinated biphenyls (PCBs) in dielectric fluids for electric capacitors. It is also used as a solvent in erasable ink, an acaricide for use in orchards, an inert ingredient in pesticides, a component of cosmetic products, and a vacuum pump oil; it is used to detect leaks in respirators and to test air filtration systems.

Chemical properties:

Di(2-ethylhexyl) phthalate is insoluble in water, miscible with mineral oil and hexane, and soluble in most organic solvents. It is easily dissolved in body fluids such as saliva and plasma. Di(2-ethylhexyl) phthalate is a combustible liquid; it may burn, but does not readily ignite. It produces poisonous gas in a fire. When heated to decomposition, it emits acrid smoke.

Synonyms for di(2-ethylhexyl) phthalate are bis(2-ethylhexyl) phthalate, bis(2-ethylhexyl)-1,2-benzenedicarboxylate, di(2-ethylhexyl)ortho-phthalate, di-sec-octyl phthalate, 2-ethylhexyl phthalate, NCI-c52733, disec-octyl phthalate, 1,2-benzenedicarboxylic acid, bis(2-ethylhexyl) ester, DOP, DEHP, and octoil.

Identification:

- Chemical Name: Di(2-ethylhexyl) Phthalate
- Regulatory Name: DEHP, BIS (2-ethylhexyl) Phthalate, Di(2-ethylhexyl) Phthalate
- Formula: C24H38O4
- CAS: 117-81-7
 CHRIS: EHE

Health effects:

Di(2-ethylhexyl) phthalate is a substance which may reasonably be anticipated to be a carcinogen, according to the National Toxicology Program of the U.S. Department of Health and Human Services. It is classified as a carcinogen in EPA's Toxic Release Inventory (TRI). It is also a teratogen and may damage the testes. Repeated exposure to di(2-ethylhexyl)

phthalate may affect the kidneys and liver, and may cause numbness and tingling in the arms and legs. Exposure can occur through inhalation, ingestion or dermal contact; it may cause irritation to the eyes, nose and throat.

Exposure Values:

IDLH: Ca [5000 mg/m3] (NIOSH, 1997)

NIOSH REL: Ca TWA 5 mg/m3 ST 10 mg/m3

OSHA PEL: TWA 5 mg/m³

Economics:

U.S. manufacturers of Di(2-ethylhexyl) phthalate are Aristech Chemical Corporation, Hq, Neville Island, PA; Eastman Chemical Company, Kingsport, TN; and Velsicol Chemical Corporation, Chestertown, MD.

Regulation:

EPA regulates di(2-ethylhexyl) phthalate under the Clean Water Act; Comprehensive Environmental Response, Compensation, and Liability Act; Resource Conservation and Recovery Act; Superfund Amendments and Reauthorization Act; and Toxic Substances Control Act. EPA classifies the chemical as an air toxic listed on the Hazardous Air Pollutant List, a volatile organic compound, and a water priority pollutant.

The Food and Drug Administration (FDA) regulates di(2-ethylhexyl) phthalate as an indirect food additive. The Occupational Safety and Health Administration (OSHA) established a permissible exposure limit for di(2-ethylhexyl) phthalate of 5 mg/m3 as an eight-hour time-weighted average, and has set a short-term exposure limit of 10 mg/m3 for the chemical. OSHA also regulates di(2-ethylhexyl) phthalate under the Hazard Communication Standard and as a chemical hazard in laboratories.

Under Section 313 of the Emergency Planning and Community Right to Know Act of 1986, releases of more than one pound of di(2-ethylhexyl) phthalate into the air, water, and land must be reported annually and entered into the Toxic Release Inventory (TRI).

National Overview of 1998 Toxics Release Inventory

In 1998, 355 facilities released 1,314,634 pounds of di(2-ethylhexyl) phthalate. Of those releases, 207,795 pounds were air emissions; 669 pounds were surface water discharges; 0 pounds were released by underground injection; 24,184 pounds were released to land; and, 1,081,986 pounds were transferred off-site for disposal. Total emissions for 1998 represented an increase from 1997 emissions, which totaled 1,302,131 pounds; a decrease from 1996 emissions, which totaled 2,270,653 pounds; from 1995 emissions, which totaled 3,537,174 pounds; and from 1988 (baseline) emissions, which totaled 4,873,091 pounds.

In 1998, 10,522,031 pounds of di(2-ethylhexyl) phthalate waste were managed; 4,985,166 pounds were recycled on-site; 1,804,174 pounds were recycled off-site; 335,646 pounds were used for energy recovery on-site; 1,674,585 pounds were used for energy recovery off-site; 403,536 pounds were treated on-site; 252,953 pounds were treated off-site; and 1,065,971

pounds were released on-and off-site.

The 10 states in which the largest amounts of di(2-ethylhexyl) phthalate were released in 1998 were: OK (45,931 pounds); CT (26,885 pounds); GA (24,650 pounds); NC (23,082 pounds); MO (16,161 pounds); AL (13,500 pounds); TX (10,485 pounds); OH (9,618 pounds); TN (8,867 pounds); and NJ (8,385 pounds).

The 10 facilities releasing the largest amounts of di(2-ethylhexyl) phthalate in 1998 were: Zapata Ind. Inc., Muskogee, OK (45,921 pounds); Spongex Intl. Lt, Shelton, CT (26,800 pounds); Rotation Dynamics Corp., Covington, GA (14,303 pounds); Sinclair & Rush, Saint Louis, MO (13,783 pounds); 3M, Guin, AL (13,500 pounds); Wix Corp. Allen Plant, Gastonia, NC (11,977 pounds); Georgia Duck & Cordage Mill, Scottdale, GA (10,347 pounds); Baxter Healthcare Corp., Mountain Home, AR (7,100 pounds); Johnsonite, Chagrin Falls, OH (5,552 pounds); and Bayshore Vinyl Compounds Inc., Tennent, NJ (5,000 pounds).

Notations:

The NIOSH recommended exposure limits (**REL**s) are time-weighted average (**TWA**) concentrations for up to a 10-hour workday during a 40-hour workweek. A short-term exposure limit (**STEL**) is designated by "**ST**" preceding the value; unless noted otherwise, the STEL is a 15-minute TWA exposure that should not be exceeded at any time during a workday. A ceiling REL is designated by "C" preceding the value. Any substance that NIOSH considers to be a potential occupational carcinogen is designated by the notation "**Ca**."

The OSHA permissible exposure limits (PEL) are found in Tables Z-1, Z-2, and Z-3 of the OSHA General Industry Air Contaminants Standard (29 CFR 1910.1000). Unless noted otherwise, PEL are TWA concentrations that must not be exceeded during any 8-hour workshift of a 40-hour workweek. A STEL is designated by "ST" preceding the value and is measured over a 15-minute period unless noted otherwise. OSHA ceiling concentrations (designated by "C" preceding the value) must not be exceeded during any part of the workday; if instantaneous monitoring is not feasible, the ceiling must be assessed as a 15-minute TVVA exposure. In addition, there are a number of substances from Table Z-2 (e.g., beryllium, ethylene dibromide, etc.) that have PEL ceiling values that must not be exceeded except for specified excursions. For example, a "5-minute maximum peak in any 2 hours" means that a 5-minute exposure above the ceiling value, but never above the maximum peak, is allowed in any 2 hours during an 8-hour workday.

Information Sources:

- CAMEO®, U.S. Environmental Protection Agency, National Oceanic and Atmospheric Administration, www.epa.gov/ceppo.
- Chemical Manufacturers Association, 1300 Wilson Blvd., Arlington, VA 22209: (703) 741-5000 or Chemical Referral Library, (800) 262-8200.
- National Institute of Environmental Health Sciences, Clearinghouse on Environmental Health Effects, 100 Capitola Drive, #108, Durham, NC 27713; (800) 643-4794; fax (919) 361-9408.
- TOXNET, National Library of Medicine, National Institutes of Health; www.toxnet.nlm.nih.gov
- U.S. Environmental Protection Agency, 401 M St., SW, Washington, DC 20460; Right to Know Hotline (800) 535-0202.
- U.S. Department of Labor, Occupational Health and Safety Administration, Washington, DC, www.osha.gov
- OSHA PEL: Z-1 Table: www.osha-slc.gov/OshStd_data/1910_1000_TABLE_Z-1.html
- OSHA PEL: Z-2 Table: www.osha-slc.gov/OshStd_data/1910_1000_TABLE_Z-2.html

337 South 1st Avenue, Othello, WA 99344 (509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

CAPELOGLICOTES

12/8/2004

DATE ROOF MED.

MAYOREHUN LO

SEND REPORT TO

12/9/2004

12/21/2004

W.W.B.W.C. PO Box 68

SHOUSE CHARGE

Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

NAM- : A	TATALAN YA	1.NAU YS/S	RESULTS	54:33	JNST/G	AKALYSTE
74118	OBS Well #1	COD	<8	8	mg/L	Wang
74118	OBS Well #I	TKN as Nitrogen	<0.72	0.72	mg/L	Wang
74118	OBS Well #1	Nitrate as Nitrogen	0.1	0.044	mg/L	Wang
74118	OBS Well #1	Chloride	ND	0.297	mg/L	Wang
74118	OBS Well #1	Soluble Reactive Phosphoru	0.06	Commence of the commence of th	mg/L	Wang
74118	OBS Well #1	Total Dissolved Solids	34	20.3	mg/L	Wang
74118	OBS Well #1	Fecal E-Coli	12	1	MPN/100mL	Valley Enviornment

<0.001): indicates the analyte was not detected at or above the concentration indicated.

ND: None Delected

mg/L.Indicates milligrams per litre

PQL=Practical Quantitation Lumn is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

MDI. Method Detection Limit

Please check out our new Web Site at http://www.kuotestine.com

Mollytin for auciona Dr. Eugene Kuo, Quality Assurance Coordinator

Nesults 2004-5

_
0
0
a
7
Ø
⋜
-

Ocation: OBS	OBS Well #1					
fion Date	Sample #	Analysis	Results	Duplicates	MDL	Units
12/8/2004	74118 COD		89	8	8.000	mg/L
12/8/2004	74118	74118 TKN as Nitrogen	<0.72	<0.72	0.720	mg/L
12/8/2004		74118 Nitrate as Nitrogen	0.1	0.1	0.044	mg/L
12/8/2004		74118 Chloride	QN	ND	0.297	mg/L
12/8/2004		74118 Soluble Reactive Phosphorus	90.0	90.0	0.037	mg/L
12/8/2004		74118 Total Dissolved Solids	34	34	20.300	mg/L
Location:	Intake					
Collection Date	Sample #	Analysis	Results	Duplicates	MDL	Units
12/8/2004	74117	COD	12		8.000	mg/L
12/8/2004	74117	74117 TKN as Nitrogen	<0.72		0.720	mg/L
12/8/2004		74117 Nitrate as Nitrogen	0.1		0.044	mg/L
12/8/2004		74117 Chloride	1		0.297	mg/L
12/8/2004		74117 Soluble Reactive Phosphorus	0.05		0.037	mg/L
12/8/2004	74117	Total Dissolved Solids	24		20.300	mg/L
_ocation	OBS Well #1					
Collection Date	Sample #	Analysis	Results	Duplicates	MDL	Onits
5/19/2005		COD	8 4		8.000	mg/L
5/19/2005		TKN as Nitrogen	<0.72		0.720	mg/L
5/19/2005		Nitrate as Nitrogen	0.11		0.044	mg/L
5/19/2005		Chloride	QN		0.297	mg/L
5/19/2005		Soluble Reactive Phosphorus	s 0.155		0.037	mg/L
5/19/2005		Total Dissolved Solids	48		20.300	mg/L

WQ-Table 2
Fecal E. Coli Sampling Results
Date Time

240	Time	Location	Kesuits	What	Collector
12/1/2004	11:05	GW-16	3	Fecal E-Coli (MPN/100 ML)	Z Gray
	12:25	HBDIC OBS#3 (A)	<1	Fecal E-Coli (MPN/100 ML)	Z Gray
	12:10	GW-61	<1	Fecal E-Coli (MPN/100 ML)	Z Gray
	11:25	GW-28	<1	Fecal E-Coli (MPN/100 ML)	Z Gray
	13:15	GW-17	<1	Fecal E-Coli (MPN/100 ML)	Z Gray
	12:25	HBDIC OBS #3(B)	<1	Fecal E-Coli (MPN/100 ML)	Z Gray
	11:45	GW-14	<1	Fecal E-Coli (MPN/100 ML)	Z Gray
	13:05	GW-39	<1	Fecal E-Coli (MPN/100 ML)	Z Gray
	11:40	White Ditch #1 (Frog)	<1	Fecal E-Coli (MPN/100 ML)	Z Gray
	13:05	White Ditch#3 (Prunesdale Road)	<1	Fecal E-Coli (MPN/100 ML)	Z Gray
	12:40	HBDIC OBS #1	<1	Fecal E-Coli (MPN/100 ML)	Z Gray
	12:50	HBDIC Intake (B)	<1	Fecal E-Coli (MPN/100 ML)	Z Gray
	12:50	HBDIC Intake (A)	<1	Fecal E-Coli (MPN/100 ML)	Z Gray
	12:55	HBDIC OBS #4	<1	Fecal E-Coli (MPN/100 ML)	Z Gray
	12:40	HBDIC OBS #1B	<1	Fecal E-Coli (MPN/100 ML)	Z Gray
	11:35	White Ditch #2 (Winesap Road)	<1	Fecal E-Coli (MPN/100 ML)	Z Gray
	12:35	HBDIC OBS #2	<1	Fecal E-Coli (MPN/100 ML)	Z Gray
	11:55	GW-9	<1	Fecal E-Coli (MPN/100 ML)	Z Gray
1	12:05	09-M5	7	Fecal E-Coli (MPN/100 ML)	Z Gray
12/8/2004	14:00	HBDIC OBS #1	12	Fecal E-Coli (MPN/100 ML)	Z Gray
12/8/2004	14:15	HBDIC Intake	62	Fecal E-Coli (MPN/100 ML)	Z Gray
1/5/2005	12:05	HBDIC OBS #1	2	Fecal E-Coli (MPN/100 ML)	Z Gray
	12:20	GW-62	11	Fecal E-Coli (MPN/100 ML)	Z Gray
1					
4/6/2005	11:25	HBDIC Intake	4	Fecal E-Coli (MPN/100 ML)	Z Gray
	11:40	HBDIC OBS #1	1	Fecal E-Coli (MPN/100 ML)	Z Gray
	12:00	GW-40	<1	Fecal E-Coli (MPN/100 ML)	Z Gray
	12:10	GW-62	<1	Fecal E-Coli (MPN/100 ML)	Z Gray
		GW-62	2	Fecal E-Coli (MPN/100 ML)	Z Gray
2005	NI/A	HRDIC OBS #1	u	Becal E Coli OriBNI /100 MT	7 0
2/13/2002	N/A	HBDIC OBS #1	C	recal E-Сон (MPN/100 ML)	Z Gray

Synthetic Organic Compound Analysis: 2004-5

ollection Date	Sample #	Reference #	Analysis	DOH#		Results	Units	SRL	Trigger	MCL	Comments
					Carbamates in Drinking water						
12/8/2004	74116	04-12075	SOC/Synthetic Organic Co	146	Carbofuran	ND	ug/L	1.800	1.800	40.0	EPA Regulate
	110			148	Oxymat	ND	ug/L	4.000	4.000	200.0	
				141	3-Hydroxycarbofuran	ND	ug/L	2.000	2.000	-	EPA Unregulat
				142	Aldicarb	ND	ug/L	1.000	1.000	_	EPA Unregulat
				143	Aldicarb Sulfone	ND	ug/L	1.600	1.600		EPA Unregulat
		-		144	Aldicarb Sulfoxide	ND	ug/L	1.000	1.000		EPA Unregulat
				145	Carbaryl	ND	ug/L	2.000	2.000	-	EPA Unregulat
				147	Methomyl	ND	ug/L	1.000	4.000	_	EPA Unregulat
				326	Propoxur(Baygon)	ND	ug/L	1.000			State Unregular
				327	Methiocarb	ND	ug/L	4.000			State Unregular
		-			Synthetic Organic Compounds	NIP		0.000	0.000	0.0	FOA Danislate
		-	Z	33	Endrin	ND	ug/L	0.020	0.020	2.0	EPA Regulate
				34	Lindane (BHC-Gamma)	ND	ug/L	0.040	0.040	40.0	EPA Regulate EPA Regulate
				35	Methoxychlor Alachlor	ND	ug/L		0.400	2.0	EPA Regulate
				117		ND	ug/L	0.400	0.400	3.0	EPA Regulate
		-	and the second second	119	Atrazine	ND ND	ug/L	0.200	0.040	0.2	EPA Regulate
				120	Benzo(a)pyrene	ND	ug/L ug/L	0.400	0.400	2.0	EPA Regulate
				124	Chlordane Technical	ND	ug/L	1.300	1.300	400.0	EPA Regulate
		-			Di(ethylhexyl)-Adipate	ND		1.300	1.300	6.0	EPA Regulate
		-		125	Di(ethylhexyl)-phthalate	ND	ug/L	0.080	0.080	0.4	EPA Regulate
		-		126 127	Heptachlor	ND	ug/L	0.040	0.040	0.4	EPA Regulate
		-		128	Heptachlor epoxide (A & B)	ND	ug/L	0.200	0.200	1.0	EPA Regulate
		-			Hexachlorobenzene		ug/L		0.200	50.0	EPA Regulate
				129	Hexachlorocyclo-Pentadiene	ND ND	ug/L	0.200	0.200	4.0	EPA Regulate
		-		133	Simazine	ND	ug/L	0.130	0.130	4.0	EPA Unregulat
				118	Aldrin	ND	ug/L ug/L	0.400	0.400		EPA Unregulat
				121	Butachlor Dieldrin	ND	ug/L	0.200	0.200	_	EPA Unregulat
				130	Metolachlor	ND	ug/L	1.000	1.000		EPA Unregulat
		-		131	Metribuzin	ND	ug/L	0.200	0.200		EPA Unregulat
				132	Propachlor	ND	ug/L	0.200	0.200	-	EPA Unregulat
		—		179	Bromacil	ND	ug/L	0.200	0.200		State Unregula
				183	Prometon	ND	ug/L	0.200	0.200		State Unregula
				190	Terbacil	ND	ug/L	0.200	0.200		State Unregula
				202	Diazinon	ND	ug/L	0.200	0.200		State Unregula
-				208	EPTC	ND	ug/L	0.300	0.300		State Unregular
		-		232	4,4-DDD	ND	ug/L	0.200	0.200		State Unregula
				233	4,4-DDE	ND	ug/L	0.200	0.200		State Unregula
		-		234	4,4 DDT	ND	ug/L	0.200	0.200		State Unregula
		-		236	Cyanazine	ND	ug/L	0.200	0.200		State Unregula
		_		239	Malathion	ND	ug/L	0.200	0.200		State Unregular
				240	Parathion	ND	ug/L	0.200	0.200		State Unregula
-				243	Trifluralin	ND	ug/L	0.200	0.200		State Unregular
-				96	Napthalene	ND	ug/L	0.100	0.100		PAHs
		-		154	Fluorene	ND	ug/L	0.200	0.200		PAHs
				244	Acenaphthylene	ND	ug/L	0.200	0.200	10108	PAHs
	1 1 3 1 1	-		245	Acenaphthene	ND	ug/L	0.200	0.200		PAHs
				246	Anthracene	ND	ug/L	0.200	0.200		PAHs
			11 - 12 - 12 - 12 - 12 - 12	247	Benz(a)anthracene	ND	ug/L	0.100	0.100	4	PAHs
				248	Benzo(b)fluoranthene	ND	ug/L	0.200	0.200		PAHs
				249	Benzo(g,h,i)perylene	ND	ug/L	0.200	0.200		PAHs
				250	Benzo(k)fluoranthene	ND	ug/L	0.200	0.200		PAHs
				251	Chrysene	ND	ug/L	0.200	0.200		PAHs
				252	Dibenzo(A,H)anthracene	ND	ug/L	0.200	0.200		PAHs
				253	Fluoranthene	ND	ug/L	0.200	0.200		PAHs
				255	Indeno(1,2,3-CD)Pyrene	ND	ug/L	0.200	0.200		PAHs
				256	Phenanthrene	ND	ug/L	0.200	0.200		PAHs
-				257	Pyrene	ND	ug/L	0.200			PAHs
		T		258	Benzyl Butyl Phthalate	ND	ug/L	0.600	0.600		Phthalates
				259	Di-N-Butyl Phthalate	ND	ug/L	0.600	0.600		Phthalates
				260	Diethyl Phthalate	ND	ug/L	0.600	0.600		Phthalates
				261	Dimethyl Phthalate	ND	ug/L	0.600	0.600		Phthalates
				36	Toxaphene	ND	ug/L	2.000	2.000	3.0	PCBs/Tocxaph
				173	Aroclor 1221	ND	ug/L	20.000	20.000		PCBs/Tocxaph
	I TO STATE OF THE			174	Aroclor 1232	ND	ug/L	0.500	0.500		PCBs/Tocxaph
				175	Aroclor 1242	ND	ug/L	0.500	0.300		PCBs/Tocxaph
				176	Aroclor 1248	ND	ug/L	0.100	0.100		PCBs/Tocxaph
				177	Aroclor 1254	ND	ug/L	0.100	0.100		PCBs/Tocxaph
				178	Aroclor 1260	ND	ug/L	0.200	0.200		PCBs/Tocxaph
				180	Aroclor 1016	ND	ug/L	0.100	0.100		PCBs/Tocxaph
					Herbicides in Drinking Water			3 - 1-			
				37	2,4-D	ND	ug/L	0.200	0.200	70.0	EPA Regulat
				38	2,4,5-TP (Silvex)	ND	ug/L	0.400	0.400	50.0	EPA Regulat
				134	Pentachlorophenol	ND	ug/L	0.080	0.080	1.0	EPA Regulat
				137	Dalapon	ND	ug/L	2.000	2.000	200.0	EPA Regulat
				139	Dinoseb	ND	ug/L	0.400	0.400	7.0	EPA Regulat
				140	Picloram	ND	ug/L	0.200	0.200	500.0	
		-		138	Dicamba	ND	ug/L	0.200	0.200		EPA Unregula
				135	2,4 DB	ND	ug/L	1.000	1.000		State Unregula
		-		136	2,4 DB 2,4,5 T	ND	ug/L	0.400	0.400		State Unregula
		-		220	Bentazon	ND	ug/L	0.500	0.500		State Unregula
					Dichloroprop	ND	ug/L	0.500	0.500	100	State Unregula
				221							
				000	Antiffering						
				223 225	Actiflorfin Dacthal (DCPA)	ND ND	ug/L ug/L	2,000 0.100	2.000 0.100		State Unregula

Synthetic Organic Compound Analysis: 2004-5

			The state of the s		ompound Analysis: 2004-5	Paculte	Unite	SRI	Trigger	MCL	Comments
ollection Date	Sample #	Reference #	Analysis	DOH#	Compounds Carbamates in Drinking water	Results	Units	JIL	ingger	MOL	-
101010001	74445	04 42076	SOC/Synthetic Organic Co	146	Carbofuran Carbofuran	ND	ug/L	1.800	1.800	40.0	EPA Regulated
12/8/2004	74115	04-12075	SOC/Synthetic Organic Co	148	Oxymal	ND	ug/L	4.000	4.000	200.0	EPA Regulated
						ND	ug/L	2.000	2.000		EPA Unregulate
				141	3-Hydroxycarbofuran Aldicarb	ND	ug/L	1.000	1.000		EPA Unregulate
				142	Aldicarb Sulfone	ND	ug/L	1.600	1.600		EPA Unregulate
				143		ND	ug/L	1.000	1.000		EPA Unregulate
				144	Aldicarb Sulfoxide	ND	ug/L	2.000	2.000		EPA Unregulate
				145	Carbaryl	ND		1.000	4.000		EPA Unregulate
				147	Methomyl		ug/L	1.000	4.000		State Unregulate
				326	Propoxur(Baygon)	ND	ug/L			-	State Unregulate
				327	Methiocarb	ND	ug/L	4.000			State Offiegulate
					Synthetic Organic Compounds			0.000	0.000	00	EPA Regulated
				33	. Endrin	ND	ug/L	0.020	0.020	2.0	EPA Regulated
				34	Lindane (BHC-Gamma)	ND	ug/L	0.040	0.040	0.2	
				35	Methoxychlor	ND	ug/L	0.200	0.200	40.0	EPA Regulated
- Miles III				117	Alachlor	ND	ug/L	0.400	0.400	2.0	EPA Regulated
				119	Atrazine	ND	ug/L	0.200	0.200	3.0	EPA Regulated
				120	Benzo(a)pyrene	ND	ug/L	0.040	0.040	0.2	EPA Regulated
				122	Chlordane Technical	ND	ug/L	0.400	0.400	2.0	EPA Regulated
				124	Di(ethylhexyl)-Adipate	ND	ug/L	1.300	1.300	400.0	EPA Regulated
				125	Di(ethylhexyl)-phthalate	ND	ug/L	1.300	1.300	6.0	EPA Regulated
				126	Heptachlor	ND	ug/L	0.080	0.080	0.4	EPA Regulated
		-		127	Heptachlor epoxide (A & B)	ND	ug/L	0.040	0.040	0.2	EPA Regulated
-		-		128	Hexachlorobenzene	ND	ug/L	0.200	0.200	1.0	EPA Regulated
				129	Hexachlorocyclo-Pentadiene	ND	ug/L	0.200	0.200	50.0	EPA Regulated
		-		133	Simazine	ND	ug/L	0.150	0.150	4.0	EPA Regulate
				118	Aldrin	ND	ug/L	0.200	0.200		EPA Unregulate
		-		121	Butachlor	ND	ug/L	0.400	0.400		EPA Unregulati
				123	Dieldrin	ND	ug/L	0.200	0.200		EPA Unregulati
			+		Metolachlor	ND	ug/L	1.000	1.000		EPA Unregulat
				130		ND	ug/L	0.200	0.200		EPA Unregulat
				131	Metribuzin	ND	ug/L	0.200	0.200		EPA Unregulate
The state of the s				132	Propachlor	ND	ug/L	0.200	0.200		State Unregulat
				179	Bromacil			0.200	0.200		State Unregulat
				183	Prometon	ND	ug/L		0.200	-	State Unregular
				190	Terbacil	ND	ug/L	0.200		-	State Unregulat
				202	Diazinon	ND	ug/L	0.200	0.200		State Unregulat
				208	EPTC	ND	ug/L	0.300	0.300		
				232	4,4-DDD	ND	ug/L	0.200	0.200		State Unregulat
				233	4,4-DDE	ND	ug/L	0.200	0.200		State Unregulat
				234	4,4_DDT	ND	ug/L	0.200	0.200		State Unregulat
				236	Cyanazine	ND	ug/L	0.200	0.200		State Unregulat
				239	Malathion	ND	ug/L	0.200	0.200		State Unregulat
				240	Parathion	ND	ug/L	0.200	0.200		State Unregular
				243	Trifluralin	ND	ug/L	0.200	0.200		State Unregulat
				96	Napthalene	ND	ug/L	0.100	0.100		PAHs
		_		154	Fluorene	ND	ug/L	0.200	0.200		PAHs
		-		244	Acenaphthylene	ND	ug/L	0.200	0.200		PAHs
COLUMN TO SERVICE		-	-	245	Acenaphthene	ND	ug/L	0.200	0.200		PAHs
		-		246	Anthracene	ND	ug/L	0.200	0.200		PAHs
		-		247	Benz(a)anthracene	ND	ug/L	0.100			PAHs
		-		248	Benzo(b)fluoranthene	ND	ug/L	0.200			PAHs
				249	Benzo(g,h,i)perylene	ND	ug/L	0.200			PAHs
					Benzo(k)fluoranthene	ND	ug/L	0.200			PAHs
				250	Chrysene	ND	ug/L				PAHs
				251		ND	ug/L				PAHs
			The second second	252	Dibenzo(A,H)anthracene	ND	ug/L	0.200			PAHs
"				253	Fluoranthene	ND	ug/L	0.200			PAHs
				255	Indeno(1,2,3-CD)Pyrene	ND		-			PAHs
	STATE OF THE STATE			256	Phenanthrene		ug/L ug/L			1	PAHS
				257	Pyrene	ND				1	Phthalates
				258	Benzyl Butyl Phthalate	ND	ug/L	0.600			Phthalates
				259	Di-N-Butyl Phthalate	ND	ug/L			-	Phthalates
				260	Diethyl Phthalate	ND	ug/L			0	Phthalates
				261	Dimethyl Phthalate	ND	ug/L			100	
				36	Toxaphene	ND	ug/L	2.000	2.000	3.0	PCBs/Tocxaph
	101500-			173	Aroclor 1221	ND	ug/L				PCBs/Tocxaph
		-		174	Aroclor 1232	ND	ug/L				PCBs/Tocxaph
				175	Aroclor 1242	ND	ug/L				PCBs/Tocxaph
											PCBs/Tocxaph
					Aroclor 1248	ND	ug/L				
				176	Aroclor 1248	ND ND	ug/L ug/L				PCBs/Tocxaph
				176 177	Aroclor 1248 Aroclor 1254			0.100	0.100	X	PCBs/Tocxaph PCBs/Tocxaph
				176 177 178	Aroclor 1248 Aroclor 1254 Aroclor 1260	ND ND	ug/L	0.100	0.100		PCBs/Tocxaph PCBs/Tocxaph
				176 177	Aroclor 1248 Aroclor 1254 Aroclor 1260 Aroclor 1016	ND	ug/L ug/L	0.100	0.100		PCBs/Tocxaph PCBs/Tocxaph
				176 177 178 180	Aroclor 1248 Aroclor 1254 Aroclor 1260 Aroclor 1016 Herbicides in Drinking Water	ND ND ND	ug/L ug/L ug/L	0.100 0.200 0.100	0.100 0.200 0.100		PCBs/Tocxaph PCBs/Tocxaph PCBs/Tocxaph
				176 177 178 180	Aroclor 1248 Aroclor 1254 Aroclor 1260 Aroclor 1016 Herbicides in Drinking Water 2,4-D	ND ND ND	ug/L ug/L ug/L	0.100 0.200 0.100	0.100 0.200 0.100 0.200	70.0	PCBs/Tocxaph PCBs/Tocxaph PCBs/Tocxaph EPA Regulat
				176 177 178 180 37 38	Aroclor 1248 Aroclor 1254 Aroclor 1260 Aroclor 1016 Herbicides in Drinking Water 2,4-D 2,4,5-TP (Silvex)	ND ND ND	ug/L ug/L ug/L ug/L	0.100 0.200 0.100 0.200 0.400	0.100 0.200 0.100 0.200 0.200 0.400	70.0	PCBs/Tocxaph PCBs/Tocxaph PCBs/Tocxaph EPA Regulat EPA Regulat
				176 177 178 180 37 38 134	Aroclor 1248 Aroclor 1254 Aroclor 1260 Aroclor 1016 Herbicides in Drinking Water 2,4-D 2,4,5-TP (Silvex) Pentachlorophenol	ND ND ND ND ND	ug/L ug/L ug/L ug/L ug/L	0.100 0.200 0.100 0.200 0.400 0.400	0 0.100 0 0.200 0 0.100 0 0.200 0 0.400 0 0.080	70.0 50.0 1.0	PCBs/Tocxaph PCBs/Tocxaph PCBs/Tocxaph EPA Regulat EPA Regulat EPA Regulat
				176 177 178 180 37 38 134 137	Aroclor 1248 Aroclor 1254 Aroclor 1260 Aroclor 1016 Herbicides in Drinking Water 2,4-D 2,4,5-TP (Silvex) Pentachlorophenol Dalapon	ND ND ND ND ND ND	ug/L ug/L ug/L ug/L ug/L ug/L	0.100 0.200 0.100 0.200 0.400 0.080 2.000	0 0.100 0 0.200 0 0.100 0 0.400 0 0.080 0 2.000	70.0 50.0 1.0 200.0	PCBs/Tocxaph PCBs/Tocxaph PCBs/Tocxaph PCBs/Tocxaph EPA Regulat EPA Regulat EPA Regulat EPA Regulat
				176 177 178 180 37 38 134 137 139	Aroclor 1248 Aroclor 1254 Aroclor 1260 Aroclor 1016 Herbicides in Drinking Water 2,4-D 2,4,5-TP (Silvex) Pentachlorophenol Dalapon Dinoseb	ND ND ND ND ND ND ND	ug/L ug/L ug/L ug/L ug/L ug/L ug/L	0.100 0.200 0.100 0.400 0.080 2.000	0 0.100 0 0.200 0 0.100 0 0.400 0 0.080 0 0.400 0 0.400	70.0 50.0 1.0 200.0 7.0	PCBs/Tocxaph PCBs/Tocxaph PCBs/Tocxaph PCBs/Tocxaph EPA Regulat EPA Regulat EPA Regulat EPA Regulat EPA Regulat
				176 177 178 180 37 38 134 137	Aroclor 1248 Aroclor 1254 Aroclor 1250 Aroclor 1260 Aroclor 1016 Herbicides in Drinking Water 2,4,5-TP (Silvex) Pentachlorophenol Dalapon Dinoseb Picloram	ND ND ND ND ND ND ND ND	ug/L ug/L ug/L ug/L ug/L ug/L ug/L ug/L	0.100 0.200 0.100 0.400 0.080 2.000 0.400 0.200	0 0.100 0 0.200 0 0.100 0 0.400 0 0.080 0 0.400 0 0.400 0 0.400 0 0.200	70.0 50.0 1.0 200.0 7.0	PCBs/Tocxaph PCBs/Tocxaph PCBs/Tocxaph PCBs/Tocxaph PCBs/Tocxaph EPA Regulat EPA Regulat EPA Regulat EPA Regulat EPA Regulat
				176 177 178 180 37 38 134 137 139	Aroclor 1248 Aroclor 1254 Aroclor 1260 Aroclor 1016 Herbicides in Drinking Water 2,4-D 2,4,5-TP (Silvex) Pentachlorophenol Dalapon Dinoseb	ND ND ND ND ND ND ND ND ND	ug/L ug/L ug/L ug/L ug/L ug/L ug/L ug/L	0.100 0.200 0.100 0.400 0.400 0.400 0.200 0.200	0 0.100 0 0.200 0 0.100 0 0.400 0 0.080 0 0.400 0 0.400 0 0.400 0 0.200 0 0.200 0 0.200	70.0 50.0 1.0 200.0 7.0 500.0	PCBs/Tocxaph PCBs/Tocxaph PCBs/Tocxaph PCBs/Tocxaph PCBs/Tocxaph EPA Regulat EPA Regulat EPA Regulat EPA Regulat EPA Regulat EPA Regulat EPA Regulat EPA Regulat
				176 177 178 180 37 38 134 137 139	Aroclor 1248 Aroclor 1254 Aroclor 1250 Aroclor 1260 Aroclor 1016 Herbicides in Drinking Water 2,4,5-TP (Silvex) Pentachlorophenol Dalapon Dinoseb Picloram	ND ND ND ND ND ND ND ND ND ND	ug/L ug/L ug/L ug/L ug/L ug/L ug/L ug/L	0.100 0.200 0.100 0.400 0.080 2.000 0.400 0.200 0.200 1.000	0 0.100 0 0.200 0 0.100 0 0.400 0 0.080 0 0.400 0 0.400 0 0.200 0 0.200 0 0.200 0 0.200 0 1.000	70.0 50.0 1.0 200.0 7.0	PCBs/Tocxaph PCBs/Tocxaph PCBs/Tocxaph PCBs/Tocxaph EPA Regulat EPA Regulat EPA Regulat EPA Regulat EPA Regulat EPA Regulat EPA Lpregulat EPA Unregula State Unregula
				176 177 178 180 37 38 134 137 139 140 138	Aroclor 1248 Aroclor 1254 Aroclor 1260 Aroclor 1016 Herbicides in Drinking Water 2,4-D 2,4,5-TP (Silvex) Pentachlorophenol Dalapon Dinoseb Picloram Dicamba	ND ND ND ND ND ND ND ND ND ND	ug/L ug/L ug/L ug/L ug/L ug/L ug/L ug/L	0.100 0.200 0.100 0.400 0.080 2.000 0.400 0.200 0.200 0.400 0.200 0.200 0.200	0 0.100 0 0.200 0 0.100 0 0.400 0 0.400 0 0.400 0 0.200 0 0.200 0 0.200 0 0.200 0 0.400	70.0 50.0 1.0 200.0 7.0	PCBs/Tocxaph PCBs/Tocxaph PCBs/Tocxaph PCBs/Tocxaph PCBs/Tocxaph EPA Regulat EPA Regulat EPA Regulat EPA Regulat EPA Regulat EPA Regulat EPA Unregula State Unregula State Unregula
				176 177 178 180 37 38 134 137 139 140 138 135 136	Aroclor 1248 Aroclor 1254 Aroclor 1250 Aroclor 1016 Herbicides in Drinking Water 2,4-D 2,4,5-TP (Silvex) Pentachlorophenol Dalapon Dinoseb Pictoram Dicamba 2,4 DB 2,4,5 T	ND ND ND ND ND ND ND ND ND ND	ug/L ug/L ug/L ug/L ug/L ug/L ug/L ug/L	0.100 0.200 0.100 0.400 0.080 2.000 0.400 0.200 0.200 0.400	0.100 0.200 0.100 0.200 0.400 0.400 0.080 0.080 0.200 0.000	70.0 50.0 1.0 200.0 500.0	PCBs/Tocxaph PCBs/
				176 177 178 180 37 38 134 137 139 140 138 135 136 220	Aroclor 1248 Aroclor 1254 Aroclor 1260 Aroclor 1016 Herbicides in Drinking Water 2,4,5—TP (Silvex) Pentachlorophenol Dalapon Dinoseb Pictoram Dicamba 2,4 DB 2,4,5 T Bentazon	ND ND ND ND ND ND ND ND ND ND ND ND ND N	ug/L ug/L ug/L ug/L ug/L ug/L ug/L ug/L	0.100 0.200 0.100 0.400 0.400 0.400 0.200 0.200 1.000 0.400 0.400 0.400 0.400	0.100 0.200 0.100 0.200 0.100 0.200 0.400 0.080 0.200 0.200 0.200 0.200 0.200 0.200 0.200 0.200 0.200 0.200 0.200 0.200 0.200	70.0 50.0 1.0 200.0 500.0	PCBs/Tocxaph PCBs/Tocxaph PCBs/Tocxaph PCBs/Tocxaph EPA Regulat EPA Regulat EPA Regulat EPA Regulat EPA Regulat EPA Regulat EPA Regulat EPA Unregulat EPA Unregulat State Unre
				176 177 178 180 37 38 134 137 139 140 138 135 136 220 221	Aroclor 1248 Aroclor 1254 Aroclor 1260 Aroclor 1016 Herbicides in Drinking Water 2,4-D 2,4,5-TP (Silvex) Pentachlorophenol Dalapon Dinoseb Picloram Dicamba 2,4 DB 2,4,5 T Bentazon Dichloroprop	ND ND ND ND ND ND ND ND ND ND ND ND ND N	ug/L ug/L ug/L ug/L ug/L ug/L ug/L ug/L	0.100 0.200 0.100 0.400 0.400 0.200 0.200 0.200 1.000 0.400 0.500	0.100 0.200 0.100 0.200 0.100 0.200 0.400 0.200 0.400 0.200 0.000	70.0 50.0 1.0 200.0 500.0	PCBs/Tocxaph PCBs/Tocxaph PCBs/Tocxaph PCBs/Tocxaph EPA Regulat EPA Regulat EPA Regulat EPA Regulat EPA Regulat EPA Regulat EPA Regulat EPA Unregulat EPA Unregulat State Unre
				176 177 178 180 37 38 134 137 139 140 138 135 136 220	Aroclor 1248 Aroclor 1254 Aroclor 1254 Aroclor 1260 Aroclor 1016 Herbicides in Drinking Water 2,4-D 2,4,5-TP (Silvex) Pentachlorophenol Dalapon Dinoseb Picloram Dicamba 2,4 DB 2,4,5 T Bentazon Dichloroprop Actiflorfin	ND ND ND ND ND ND ND ND ND ND ND ND ND N	ug/L ug/L ug/L ug/L ug/L ug/L ug/L ug/L	0.100 0.200 0.100 0.400 0.080 0.200 0.200 0.200 1.000 1.000 0.500 0.500 0.500	0.100 0.200 0.100 0.200 0.100 0.200 0.000	70.0 50.0 1.0 200.0 7.0 500.0	PCBs/Tocxaph PCBs/Tocxaph PCBs/Tocxaph PCBs/Tocxaph EPA Regulat EPA Regulat EPA Regulat EPA Regulat EPA Regulat

Synthetic Organic Compound Analysis: 2004-5

		T	THE RESERVE OF THE PERSON NAMED IN	CONTRACTOR OF THE PERSON NAMED IN	ompound Analysis: 2004-5	Results	Unito	CDI	Trigger	MCL	Comments
Collection Date	Sample #	Reference #	Analysis	DOH#	Compounds Carbamates in Drinking water	Results	Units	SKL	rrigger	MCL	Comments
5/19/2005	76494	05-05830	SOC/Synthetic Organic Co	146	Carbofuran Carbofuran	ND	ug/L	1.800	1.800	40.0	EPA Regulated
5/19/2005	70494	05-05050	Social interest of game of	148	Oxymal	ND	ug/L	4.000	4.000	200.0	
		-		141	3-Hydroxycarbofuran	ND	ug/L	2.000	2.000		EPA Unregulated
				142	Aldicarb	ND	ug/L	1.000	1.000		EPA Unregulated
	NI III			143	Aldicarb Sulfone	ND	ug/L	1.600	1.600		EPA Unregulated
				144	Aldicarb Sulfoxide	ND	ug/L	1.000	1.000		EPA Unregulated
			1000	145	Carbaryl	ND	ug/L	2.000	2.000	Lance &	EPA Unregulated
				147	Methomyl	ND	ug/L	1.000	4.000		EPA Unregulated
				326	Propoxur(Baygon)	ND	ug/L	1.000			State Unregulated
				327	Methiocarb	ND	ug/L	4.000			State Unregulated
					Synthetic Organic Compounds						
				33	Endrin	ND	ug/L	0.020	0.020	2.0	EPA Regulated
				34	Lindane (BHC-Gamma)	ND	ug/L	0.040	0.040	0.2	EPA Regulated
				35	Methoxychlor	ND	ug/L	0.200	0.200	40.0	EPA Regulated
				117	Alachlor	ND	ug/L	0.400	0.400	2.0	EPA Regulated
				119	Atrazine	ND	ug/L	0.200	0.200	3.0	EPA Regulated
				120	Benzo(a)pyrene	ND	ug/L	0.040	0.040	0.2	EPA Regulated
				122	Chlordane Technical	ND	ug/L	0.400	0.400	2.0 400.0	EPA Regulated
				124	Di(ethylhexyl)-Adipate	ND	ug/L	1.300	1.300	6.0	EPA Regulated EPA Regulated
				125	Di(ethylhexyl)-phthalate	ND	ug/L	1.300	1.300	0.4	EPA Regulated
			The second second	126	Heptachlor (A.S. D)	ND ND	ug/L	0.080	0.080	0.4	EPA Regulated
	ļ			127	Heptachlor epoxide (A & B)		ug/L	0.200	0.200	1.0	EPA Regulated
				128	Hexachlorobenzene	ND ND	ug/L ug/L	0.200	0.200	50.0	EPA Regulated
		-		129	Hexachlorocyclo-Pentadiene		ug/L	0.150	0.200	4.0	EPA Regulated
	-	-		133	Simazine Aldrin	ND ND	ug/L	0.130	0.130	4.0	EPA Unregulated
	-	-		118	Butachlor	ND	ug/L	0.400	0.400		EPA Unregulated
				123	Dieldrin	ND	ug/L	0.200	0.200		EPA Unregulated
		-		130	Metolachlor	ND	ug/L	1.000	1.000		EPA Unregulated
		-		131	Metribuzin	ND	ug/L	0.200	0.200		EPA Unregulated
	_	1		132	Propachlor	ND	ug/L	0.200	0.200		EPA Unregulated
		-	THE RESERVE OF THE PERSON OF T	179	Bromacil	ND	ug/L	0.200	0.200		State Unregulated
		1		183	Prometon	ND	ug/L	0.200	0.200		State Unregulated
	C	210		190	Terbacil	ND	ug/L	0.200	0.200		State Unregulated
				202	Diazinon	ND	ug/L	0.200	0.200		State Unregulated
				208	EPTC	ND	ug/L	0.300	0.300		State Unregulated
				232	4,4-DDD	ND	ug/L	0.200	0.200		State Unregulated
				233	4,4-DDE	ND	ug/L	0.200	0.200		State Unregulated
				234	4,4_DDT	ND	ug/L	0.200	0.200		State Unregulated
				236	Cyanazine	ND	ug/L	0.200	0.200		State Unregulated
				239	Malathion	ND	ug/L	0.200	0.200		State Unregulated
				240	Parathion	ND	ug/L	0.200	0.200	8 4	State Unregulated
				243	Trifluralin	ND	ug/L	0.200	0.200		State Unregulated
	55			96	Napthalene	ND	ug/L	0.100	0.100		PAHs
				154	Fluorene	ND	ug/L	0.200	0.200		PAHs
				244	Acenaphthylene	ND	ug/L	0.200	0.200	-	PAHs
				245	Acenaphthene	ND	ug/L	0.200	0.200		PAHs PAHs
				246	Anthracene	ND	ug/L	0.200	0.200		PAHS
				247	Benz(a)anthracene	ND ND	ug/L ug/L	0.200	0.100	-	PAHs
				248	Benzo(b)fluoranthene	ND	ug/L	0.200	0.200		PAHS
			Name and Address of the Owner, where the Owner, where the Owner, where the Owner, where the Owner, where the Owner, where the Owner, where the Owner, where the Owner, where the Owner, where the Owner, where the Owner, where the Owner, where the Owner, where the Owner, where the Owner, where the Owner, where the Owner, where the Owner, which is the Owner, where the Owner, which is the Owner, where the Owner, which is the Ow	249	Benzo(g,h,i)perylene Benzo(k)fluoranthene	ND	ug/L	0.200	0.200	-	PAHs
		-	Allico	250	Chrysene	ND	ug/L	0.200	0.200	100	PAHs
		_		251	Dibenzo(A,H)anthracene	ND	ug/L	0.200	0.200		PAHs
	-			253	Fluoranthene	ND	ug/L	0.200	0.200		PAHs
		-		255	Indeno(1,2,3-CD)Pyrene	ND	ug/L	0.200	0.200		PAHs
		1	S 10 10 10 10 10 10 10 10 10 10 10 10 10	256	Phenanthrene	ND	ug/L	0.200	0.200		PAHs
	-	1		257	Pyrene	ND	ug/L	0.200	0.200		PAHs
	R THE TO STATE	1 325		258	Benzyl Butyl Phthalate	ND	ug/L		0.600		Phthalates
	100 - 100			259	Di-N-Butyl Phthalate	ND	ug/L	0.600	0.600		Phthalates
11-11-11				260	Diethyl Phthalate	ND	ug/L	0.600	0.600		Phthalates
				261	Dimethyl Phthalate	ND	ug/L	0.600	0.600		Phthalates
				36	Toxaphene	ND	ug/L	2.000	2.000	3.0	PCBs/Tocxaphene
The second				173	Aroclor 1221	ND	ug/L	20.000			PCBs/Tocxaphene
				174	Aroclor 1232	ND	ug/L	0.500	0.500		PCBs/Tocxaphene
				175	Aroclor 1242	ND	ug/L	0.500	0.300		PCBs/Tocxaphene
				176	Aroclor 1248	ND	ug/L	0.100			PCBs/Tocxaphene
				177	Aroclor 1254	ND	ug/L	0.100	0.100		PCBs/Tocxaphene
				178	Aroclor 1260	ND	ug/L	0.200	0.200		PCBs/Tocxaphene
				180	Aroclor 1016	ND	ug/L	0.100	0.100		PCBs/Tocxaphene
		120			Herbicides in Drinking Water	15.00	_				
				37	2,4-D	ND	ug/L	0.200	0.200	70.0	EPA Regulated
				38	2,4,5-TP (Silvex)	ND	ug/L	0.400	0.400	50.0	EPA Regulated
				134	Pentachlorophenol	ND	ug/L	0.080	0.080	1.0	EPA Regulated
				137	Dalapon	ND	ug/L	2.000	2.000	200.0	
				139	Dinoseb	ND	ug/L	0.400	0.400	7.0	EPA Regulated EPA Regulated
	70.576						1 confl	1 0 200	0.200	500.0	
				140	Picloram	ND	ug/L	0.200		300.0	
				138	Dicamba	ND	ug/L	0.200	0.200	500.0	EPA Unregulated
				138 135	Dicamba 2,4 DB	ND ND	ug/L ug/L	0.200 1.000	0.200 1.000	300.0	EPA Unregulated State Unregulated
				138 135 136	Dicamba 2,4 DB 2,4,5 T	ND ND ND	ug/L ug/L ug/L	0.200 1.000 0.400	0.200 1.000 0.400	500.0	EPA Unregulated State Unregulated State Unregulated
				138 135 136 220	Dicamba 2,4 DB 2,4,5 T Bentazon	ND ND ND ND	ug/L ug/L ug/L ug/L	0.200 1.000 0.400 0.500	0.200 1.000 0.400 0.500	300.0	EPA Unregulated State Unregulated State Unregulated State Unregulated
				138 135 136 220 221	Dicamba 2,4 DB 2,4,5 T Bentazon Dichloroprop	ND ND ND ND	ug/L ug/L ug/L ug/L ug/L	0.200 1.000 0.400 0.500 0.500	0.200 1.000 0.400 0.500 0.500	300.0	EPA Unregulated State Unregulated State Unregulated State Unregulated State Unregulated
				138 135 136 220 221 223	Dicamba 2,4 DB 2,4,5 T Bentazon Dichloroprop Actiflorfin	ND ND ND ND ND	ug/L ug/L ug/L ug/L ug/L	0.200 1.000 0.400 0.500 0.500 2.000	0.200 1.000 0.400 0.500 0.500 2.000	500.0	EPA Unregulated State Unregulated State Unregulated State Unregulated State Unregulated State Unregulated
				138 135 136 220 221	Dicamba 2,4 DB 2,4,5 T Bentazon Dichloroprop	ND ND ND ND	ug/L ug/L ug/L ug/L ug/L	0.200 1.000 0.400 0.500 0.500	0.200 1.000 0.400 0.500 0.500 2.000 0.100	500.0	EPA Unregulated State Unregulated State Unregulated State Unregulated State Unregulated State Unregulated State Unregulated State Unregulated State Unregulated State Unregulated

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free http://www.kuotesting.com e-mail: kuotest@atnet.net

DATE COLLECTED

UATE RECEIVED

DAKERLOWE

12/8/2004 SYSTEM COSTORAGE

SENO & PORT TO

12/9/2004

12/23/2004

W.W.B.W.C. PO Box 68

Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

SAME L' NO SECURE AWALYERS JI. 15 15/1 + 1 CONTRACT 8£51.19 8 mg/L Wang 74117 Intake COD 12 0.72 mg/L Wang Intake 74117 TKN as Nitrogen < 0.72 0.044 mg/1. Wang Intake Nitrate as Nitrogen 74117 0.1 mg/L Wang Intake Chloride 74117 1.00 mg/L Wang 74117 Intake Soluble Reactive Phosphoru 0.02 20.3 mg/L Wang Intake Total Disolved Solids 74117 1 MPN/100mL Valley Enviornment Intake Fecal E-Coli 74117

<(0.001): indicates the analyte was not detected at or above the concentration indicated.

ND: None Detected

mg/L:Indicates miltigrams per litre

mpt. Detection Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions MDL. Method Detection Limit

Please check out our new Web Site to http://www.kwotesting.com

Mellydin Dr. Eugene Kuo, Quality Assurance Coordinator

Date

337 South 1st Avenue, Othello, WA 99344 (509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

CATE COLLECTED

12/8/2004

OATL RESERVED

SENS REPORT TO 12/9/2004

S - 14 - H 1 12/23/2004

W.W.B.W.C.

SYS'EM CELLOMIA

PO Box 68

Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

SAMPLE NO	AUSTOLIER BAMPUE NO	5	ANALYSIS	RESULTS	MCa.	1.8911.2	ZPIALVII.»
74117	Intake	*****	COD	12	8	mg/t,	Wang
74117	Intake		TKN as Nitrogen	<0.72	0.72	mg/L	Wang
74117	intake		Nitrate as Nitrogen	0.1	0.044	mg/L	Wang
74117	Intake		Chloride	1.00	0.297	mg/L	Wang
74117	Intake		Soluble Reactive Phosphoru	0.02		mg/L	Wang
74117	Intake		Total Disolved Solids	24	20.3	mg/L	Wang
74117	Intake	News =	Fecal E-Coli	62	i	MPN/100ml	Valley Enviorament

(0.001): indicates the analyte was not detected at or above the concentration indicated. ND: None Detected mgrL:Indicates milligrams per little.

POL=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine isboratory operating conditions

MDL: Method Detection Limit

Please check out our new Web Site of http://www.kugtesting.com

Mellotins for Engent Dr. Eugene Kuo, Quality Assurance Coordinator

Kuo Testing Labs, Inc. 337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

DATE COLLECTED

MATE RECEIVED

DAL DISSELL

12/8/2004

ELIND REPURITO

12/9/2004

12/21/2004

SYSTEM / CUSTICIMER

W.W.B.W.C. PO Box 68

Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

IAMPLE NO	TO LOWER	AKALY56	REP 133	Sign	JP4 T5:	$g \cdot \omega / d \approx \ln e^{4\omega}$
1	SAMPLE NO	COD	<₽	8	mg/L	Wang
74118	OBS Well #1	COD	-0.00	0.72	mg/L	Wang
74118	OBS Well #1	TKN as Nitrogen	<0.72	0.044	mg/I.	Wang
74118	OBS Well #1	Nitrate as Nitrogen	0.1	0.297		The state of the s
	OBS Well #1	Chloride	ND		mg/L	4 9 1 10 1
74118	OBS Well #1	Soluble Reactive Phosphoru	0.06	110-1	mg/L	Wang
74118		The same of the sa	24	20.3	mg/l.	Wang
74118	OBS Well #1	Total Dissolved Solids	34		MPN/100mL	Valley Enviorament
74118	OBS Well #1	Feeal E-Coli			1411 . 10 . 4	

<(0.001): indicates the analyte was not detected at or above the concentration indicated.

ND: None Detected mg/L:Indicates milligrams per litre * PQL=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during mutine laboratory operating conditions

MDL: Method Detection Limit

Please check out our new Web Site at http://www.kuotesting.com

Mollytin for Gugane Dr. Eugene Kuo, Quality Assurance Coordinator

OCI-26-05 WED 9:40 AM

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

DATE COLLECTED

5/19/2005

DATE RECEIVED

DATE REPORTED

SEND REPORT TO

5/20/2005

6/2/2005

W.W.B.W.C. PO Box 68

SYSTEM / CUSTOMER

Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

AMPLE NO	CUSTOMER SAMPLE NO	ANALYSIS	RESULTS	MOL.	UNITS	ANALYSTS
76493	OBS #1	Total Dissolved Solids	48	20.3	mg/L	Wang
76493	OBS #1	Nitrate as Nitrogen	0.11	0.044	mg/L	Wang
76493	OBS #1	TKN as Nitrogen	<0.72	0.72	mg/L	Wang
76493	OBS #1	COD	<8	8	mg/L	Wang
76493	OBS #1	Chloride	ND	0.297	mg/L	Wang
76493	OBS #1	SRP-(Othro-P)	0.155	0.03	mg/L	Wang

001): indicates the analyte was not detected at or above the concentration indicated.

None Detected

L:Indicates milligrams per litre

* PQL=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions MDL: Method Detection Limit

Me at http://www.kuotesting.com

Quality Assurance Coordinator

Appendices I-C

HBDIC Recharge Water Quality Testing: Lab Results, Notes and Records

2005-2006 Recharge Season

Kuo Testing Labs, Inc. Samples *1/2

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free

Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

DATE COLLECTED 1/4/2006

DATE RECEIVED

DATE REPORTED

SEND REPORT TO: 1/5/2006

1/13/2006

SYSTEM / CUSTOMER

W.W.B.W.C. PO Box 68

Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

MPLE NO	CUSTOMER SAMPLE NO.	ANALYSIS	RESULTS	MDL	UNITS	ANALYSTS
80260	Intake	Orthophosphate as P (SRP)	0.06	0.0433	mg/L	Wang
80260	Intake	Total Dissolved Solids	50	21.1	mg/L	Wang
80260	Intake	Nitrate as Nitrogen	0.47	0.084	mg/L	Wang
80260	Intake	TKN as Nitrogen	< 0.72	0.72	mg/L	Wang
80260	Intake	COD	8	8	mg/L	Wang
80260	Intake	Chloride	ND	0.297	mg/L	Wang

<(0.001): indicates the analyte was not detected at or above the concentration indicated.

ND: None Detected

mg/L Indicates milligrams per litre

* PQL=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

NDL: Method Detection Limit

ase check out our new Web Site at http://www.kuotesting.com

Dr. Eugene Kuo, Quality Assurance Coordinator

337 South 1st Avenue, Othello, WA 99344

(509) 488-0112 Phone (509) 488-0118 Fax (800) 328-0112 Toll Free Web Site: http://www.kuotesting.com e-mail: kuotest@atnet.net

DATE COLLECTED

DATE RECEIVED

DATE REPORTED

1/4/2006

SEND REPORT TO: 1/5/2006

1/13/2006

SYSTEM / CUSTOMER

W.W.B.W.C. PO Box 68

Milton Freewater OR

97862

Project Name:

Bob Bower PO Box 68

Milton Freewater OR

97862

Attn:

MPLE NO	CUSTOMER SAMPLE NO.	ANALYSIS	RESULTS	MDL	UNITS	ANALYSTS
80261	HBDIC OBS #1	Orthophosphate as P (SRP)	0.07	0.0433	mg/L	Wang
80261	HBDIC OBS #1	Total Dissolved Solids	72	21.1	mg/L	Wang
80261	HBDIC OBS #1	Nitrate as Nitrogen	0.64	0.084	mg/L	Wang
80261	HBDIC OBS #1	TKN as Nitrogen	< 0.72	0.72	mg/L	Wang
80261	HBDIC OBS #1	COD	10	8	mg/L	Wang
80261	HBDIC OBS #1	Chloride	ND	0.297	mg/L	Wang

<(0.001): indicates the analyte was not detected at or above the concentration indicated.

ND: None Detected

mg/L: Indicates milligrams per litre * PQL=Practical Quantitation Limit is the lowest level that can be achieved within specified limits of precision and accuracy during routine laboratory operating conditions

DL: Method Detection Limit

ase check out our new Web Site at http://www.kuotesting.com

Dr. Eugene Kuo, Quality Assurance Coordinator

01-13-06

Date

Sample, #1/2



11525 Knudson Rd.
Burlington, WA 98233
(800) 755-9295
(360) 757-1400 - FAX (360) 757-1402

January 18, 2006

Page 1 of 1

Bob Bower Walla Walla Basin Watershed Council 810 S Main Street Milton-Freewater, OR 97862

RE: 06-00222 - HBDIC Recharge Project

Dear Bob Bower,

Your project: HBDIC Recharge Project, was received on Friday January 06, 2006.

All samples were analyzed within the accepted holding times, were appropriately preserved and were analyzed according to approved analytical protocols. The quality control data was within laboratory acceptance limits, unless specified in the QA reports.

If you have questions phone me at 800 755-9295.

Respectfully Submitted,

L. J. Henderson, PhD Laboratory Director

Enclosures Data Report

QC Reports

Chain of Custody



11525 Knudson Rd. Burlington, WA 98233 (800) 755-9295 (360) 757-1400 - FAX (360) 757-1402

INVOICE

Client No:

WAL06

Client:

WALLA WALLA BASIN WATERSHED COUNCIL

810 S MAIN STREET

MILTON-FREEWATER, OR 97862

Attn: Bob Bower

Please include this number with payment

Reference: 06-00222

Date: January 19, 2006

Project: HBDIC Recharge Project

Date Received: January 06, 2006

Purchase Order:

	Lab Sample		Client Sample	Type of	Extended
Item	Number	Number	Description	Analysis	Cost
1	449.00	Intake	HBDIC Recharge Project (WWBWC)	Synthetic Organics	\$590.00
2	449.01	Intake	HBDIC Recharge Project (WWBWC)	Chlorophenoxy Herbicides	
3	449.02	Intake	HBDIC Recharge Project (WWBWC)	Carbamates	
4	450.00	OBS well #1	HBDIC Recharge Project (WWBWC)	Synthetic Organics	\$590.00
5	450.01	OBS well #1	HBDIC Recharge Project (WWBWC)	Chlorophenoxy Herbicides	
6	450.02	OBS well #1	HBDIC Recharge Project (WWBWC)	Carbamates	
7	450.03	OBS well #1	HBDIC Recharge Project (WWBWC)	SHIPPING CHARGE	\$5.00

Grand Total:

\$1,185.00

Amount Paid:

\$0.00

Amount Due:

\$1,185.00

Thank You for Your Business

Please pay by February 18, 2006 to avoid a 1.5% per month finance charge.



Burlington, WA 98233

(800) 755-9295

(360) 757-1400 - FAX (360) 757-1402

Page 1 of 1

HERBICIDES IN DRINKING WATER

Client Name: Walla Walla Basin Watershed Council

810 S Main Street

Milton-Freewater, OR 97862

System Name:

System ID Number:

DOH Source Number:

Multiple Sources:

Sample Type:

Sample Purpose: Investigative or Other

Sample Location: HBDIC Recharge Project (WWBWC)

Sampled By: Bob Bower

Sampler Phone:

Reference Number: 06-00222

Project: HBDIC Recharge Project

Field ID: Intake

Lab Number: 04600449

Date Collected: 1/4/2006

Date Extracted: 515 060110

Date Analyzed: 1/11/2006

Report Date: 1/16/2006 Analyst: CMH

Supervisor:

	EPA	Method	515.1	For State	Drinking	Water	Compliance
--	-----	--------	-------	-----------	----------	-------	------------

DOH#	COMPOUNDS	RESULTS	Units	SRL	Trigger	MCL	COMMENT
	EPA Regulated						
37	2,4 - D	ND	ug/L	0.2	0.2	70	
38	2,4,5 - TP (SILVEX)	ND	ug/L	0.4	0.4	50	
134	PENTACHLOROPHENOL	ND	ug/L	0.08	0.08	1	
137	DALAPON	ND	ug/L	2	2	200	
139	DINOSEB	ND	ug/L	0.4	0.4	7	
140	PICLORAM	ND	ug/L	0.2	0.2	500	
	EPA Unregulated						
138	DICAMBA	ND	ug/L	0.2	0.2		
	State Unregulated						
135	2,4 DB	ND	ug/L	1.0	1.0		
136	2,4,5 T	ND	ug/L	0.4	0.4		
220	BENTAZON	ND	ug/L	0.5	0.5		
221	DICHLORPROP	ND	ug/L	0.5	0.5		
223	ACTIFLORFIN	ND	ug/L	2.0	2.0		
225	DACTHAL (DCPA)	ND	ug/L	0.1	0.1		
226	3,5 - DICHLOROBENZOIC ACID	ND	ug/L	0.5	0.5		
					1 2 72		

^{*-} An amount of "ND" indicates that the compound was not detected above the Lab's Method Detection Limit - MDL.

^{**.} Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds. A blank MCL or SAL value indicates a level is not currently established.

^{***-} If a compound is detected > or = to the State Reporting Level, SRL, specified increased monitoring frequencies may occur per DOH.

^{****-} Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.

J - Estimated value.



Burlington, WA 98233

(800) 755-9295

(360) 757-1400 - FAX (360) 757-1402

Page 1 of 1

HERBICIDES IN DRINKING WATER

Client Name: Walla Walla Basin Watershed Council

810 S Main Street

Milton-Freewater, OR 97862

System Name:

System ID Number:

DOH Source Number:

Multiple Sources:

Sample Type:

Sample Purpose: Investigative or Other

Sample Location: HBDIC Recharge Project (WWBWC)

Sampled By: Bob Bower

Sampler Phone:

Reference Number: 06-00222

Project: HBDIC Recharge Project

Field ID: OBS well #1

Lab Number: 04600450 Date Collected: 1/4/2006

Date Extracted: 515 060110 Date Analyzed: 1/11/2006

Report Date: 1/16/2006

Analyst: CMH Supervisor:

FPA Method 515 1 For State Drinking Water Compliance

OOH#	COMPOUNDS	RESULTS	Units	SRL	Trigger	MCL	COMMENT
	EPA Regulated						
37	2,4 - D	ND	ug/L	0.2	0.2	70	
38	2,4,5 - TP (SILVEX)	ND	ug/L	0.4	0.4	50	
134	PENTACHLOROPHENOL	ND	ug/L	0.08	0.08	1	
137	DALAPON	ND	ug/L	2	2	200	
139	DINOSEB	ND	ug/L	0.4	0.4	7	
140	PICLORAM	ND	ug/L	0.2	0.2	500	
	EPA Unregulated						
138	DICAMBA	ND	ug/L	0.2	0.2		
	State Unregulated						
135	2,4 DB	ND	ug/L	1.0	1.0		
136	2,4,5 T	ND	ug/L	0.4	0.4		
220	BENTAZON	ND	ug/L	0.5	0.5		
221	DICHLORPROP	ND	ug/L	0.5	0.5		
223	ACTIFLORFIN	ND	ug/L	2.0	2.0		
225	DACTHAL (DCPA)	ND	ug/L	0.1	0.1		
226	3,5 - DICHLOROBENZOIC ACID	ND	ug/L	0.5	0.5		

^{*-} An amount of "ND" indicates that the compound was not detected above the Lab's Method Detection Limit - MDL.

^{**-} Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds A blank MCL or SAL value indicates a level is not currently established.

^{***-} If a compound is detected > or = to the State Reporting Level, SRL, specified increased monitoring frequencies may occur per DOH.

^{****-} Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.

J - Estimated value.



Burlington, WA 98233

(800) 755-9295

(360) 757-1400 - FAX (360) 757-1402

Page 1 of 2

SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

Client Name: Walla Walla Basin Watershed Council

810 S Main Street

Milton-Freewater, OR 97862

System Name:

System ID Number:

DOH Source Number: Multiple Sources:

Sample Type:

Sample Purpose: Investigative or Other

Sample Location: HBDIC Recharge Project (WWBWC)

Sampled By: Bob Bower

Sampler Phone:

Reference Number: 06-00222

Project: HBDIC Recharge Project

Field ID: Intake

Lab Number: 04600449 Date Collected: 1/4/2006 Date Extracted: 525_060110

Date Analyzed: 1/11/2006 Report Date: 1/13/2006

Analyst: MM

Supervisor:

EPA Method 525.2 For State Drinking Water Compliance

ОН#	COMPOUNDS	RESULTS	Units	SRL	Trigger	MCL	COMMENT
	EPA Regulated						
	HEPTACHLOR EPOXIDE "B"	ND	ug/L	0.02		0.2	
33	ENDRIN	ND	ug/L	0.02	0.02	2	
34	LINDANE (BHC - GAMMA)	ND	ug/L	0.04	0.04	0.2	
35	METHOXYCHLOR	ND	ug/L	0.2	0.2	40	
117	ALACHLOR	ND	ug/L	0.4	0.4	2	
119	ATRAZINE	ND	ug/L	0.2	0.2	3	
120	BENZO(A)PYRENE	ND	ug/L	0.04	0.04	0.2	
122	CHLORDANE, TECHNICAL	ND	ug/L	0.4	0.4	2	
124	DI(ETHYLHEXYL)-ADIPATE	ND	ug/L	1.3	1.3	400	
125	DI(ETHYLHEXYL)-PHTHALATE	ND	ug/L	1.3	1.3	6	
126	HEPTACHLOR	ND	ug/L	0.08	0.08	0.4	
128	HEXACHLOROBENZENE	ND	ug/L	0.2	0.2	1	
129	HEXACHLOROCYCLO-PENTADIENE	ND	ug/L	0.2	0.2	50	
133	SIMAZINE	ND	ug/L	0.15	0.15	4	
	EPA Unregulated		1.7				
118	ALDRIN	ND	ug/L	0.2	0.2		
121	BUTACHLOR	ND	ug/L	0.4	0.4		
123	DIELDRIN	ND	ug/L	0.2	0.2		
130	METOLACHLOR	ND	ug/L	1.0	1.0		
131	METRIBUZIN	ND	ug/L	0.2	0.2		
132	PROPACHLOR	ND	ug/L	0.2	0.2		
	State Unregulated - Other						
179	BROMACIL	ND	ug/L	0.2	0.2		
183	PROMETON	ND	ug/L	0.2	0.2		Qualitative Analysis Only
190	TERBACIL	ND	ug/L	0.2	0.2		
202	DIAZINON	ND	ug/L	0.2	0.2		Unstable in Acidified Sample Matri
208	EPTC	ND	ug/L	0.3	0.3		

⁻ An amount of "ND" indicates that the compound was not detected above the Lab's Method Detection Limit - MDL.

^{**-} Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds. A blank MCL or SAL value indicates a level is not currently established.

^{***-} If a compound is detected > or = to the State Reporting Level, SRL, specified increased monitoring frequencies may occur per DOH.

⁻⁻⁻⁻⁻ Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.

J - Estimated value.





Reference Number: 06-00222

Lab Number: 04600449 Report Date: 1/13/2006

SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

H#	COMPOUNDS	RESULTS	Units	SRL	Trigger	MCL	COMMENT
100	4,4-DDD	ND	ug/L	0.2	0.2		
	4,4-DDE	ND	ug/L	0.2	0.2		
	4,4-DDT	ND	ug/L	0.2	0.2		
	CYANAZINE	ND	ug/L	0.2	0.2		Qualitative Analysis Only
	MALATHION	ND	ug/L	0.2	0.2		
	PARATHION	ND	ug/L	0.2	0.2		
	TRIFLURALIN	ND	ug/L	0.2	0.2		
240	- PAHs	, NE	Ug/L		3.50		
96	NAPTHALENE	ND	ug/L	0.1	0.1		
	FLUORENE	ND	ug/L	0.2	0.2		
	ACENAPHTHYLENE	ND	ug/L	0.2	0.2		
	Contract of the Contract of th	ND	ug/L	0.2	0.2		
	ACENAPHTHENE			0.2	0.2		
	ANTHRACENE	ND	ug/L		0.2		
	BENZ(A)ANTHRACENE	ND	ug/L	0.1			
	BENZO(B)FLUORANTHENE	ND	ug/L	0.2	0.2		
	BENZO(G,H,I)PERYLENE	ND	ug/L	0.2	0.2		
	BENZO(K)FLUORANTHENE	ND	ug/L	0.2	0.2		
251	CHRYSENE	ND	ug/L	0.2	0.2		
252	DIBENZO(A,H)ANTHRACENE	ND	ug/L	0.2	0.2		
253	FLUORANTHENE	ND	ug/L	0.2	0.2		
255	INDENO(1,2,3-CD)PYRENE	ND	ug/L	0.2	0.2		
256	PHENANTHRENE	ND	ug/L	0.2	0.2		
	PYRENE	ND	ug/L	0.2	0.2		
	- Phthalates						
258	BENZYL BUTYL PHTHALATE	ND	ug/L	0.6	0.6		
259	DI-N-BUTYL PHTHALATE	ND	ug/L	0.6	0.6		
	DIETHYL PHTHALATE	ND	ug/L	0.6	0.6		
	DIMETHYL PHTHALATE	ND	ug/L	0.6	0.6		

^{*-} An amount of "ND" indicates that the compound was not detected above the Lab's Method Detection Limit - MDL.

^{**-} Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds. A blank MCL or SAL value indicates a level is not currently established.

[&]quot;"- If a compound is detected > or = to the State Reporting Level, SRL, specified increased monitoring frequencies may occur per DOH.
""- Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.

J - Estimated value.



Burlington, WA 98233

(800) 755-9295

(360) 757-1400 - FAX (360) 757-1402

Page 1 of 2

SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

Client Name: Walla Walla Basin Watershed Council

810 S Main Street

Milton-Freewater, OR 97862

System Name:

System ID Number:

DOH Source Number:

Multiple Sources:

Sample Type:

Sample Purpose: Investigative or Other

Sample Location: HBDIC Recharge Project (WWBWC)

Sampled By: Bob Bower

Sampler Phone:

Reference Number: 06-00222

Project: HBDIC Recharge Project

Field ID: OBS well #1

Lab Number: 04600450

Date Collected: 1/4/2006

Date Extracted: 525_060110

Date Analyzed: 1/11/2006

Report Date: 1/13/2006

Analyst: MM

Supervisor:



EPA	Method	525.2	For	State	Drinking	water	Comp	mance
								Market Company

OOH#	COMPOUNDS	RESULTS	Units	SRL	Trigger	MCL	COMMENT
	EPA Regulated						
	HEPTACHLOR EPOXIDE "B"	ND	ug/L	0.02		0.2	
33	ENDRIN	ND	ug/L	0.02	0.02	2	
34	LINDANE (BHC - GAMMA)	ND	ug/L	0.04	0.04	0.2	
35	METHOXYCHLOR	ND	ug/L	0.2	0.2	40	
	ALACHLOR	ND	ug/L	0.4	0.4	2	
119	ATRAZINE	ND	ug/L	0.2	0.2	3	
120	BENZO(A)PYRENE	ND	ug/L	0.04	0.04	0.2	
122	CHLORDANE, TECHNICAL	ND	ug/L	0.4	0.4	2	
124	DI(ETHYLHEXYL)-ADIPATE	ND	ug/L	1.3	1.3	400	
125	DI(ETHYLHEXYL)-PHTHALATE	ND	ug/L	1.3	1.3	6	
126	HEPTACHLOR	ND	ug/L	0.08	0.08	0.4	
128	HEXACHLOROBENZENE	ND	ug/L	0.2	0.2	1	
129	HEXACHLOROCYCLO-PENTADIENE	ND	ug/L	0.2	0.2	50	
133	SIMAZINE	ND	ug/L	0.15	0.15	4	
	EPA Unregulated		dr.				
118	ALDRIN	ND	ug/L	0.2	0.2		
121	BUTACHLOR	ND	ug/L	0.4	0.4		
123	DIELDRIN	ND	ug/L	0.2	0.2		
130	METOLACHLOR	ND	ug/L	1.0	1.0		
131	METRIBUZIN	ND	ug/L	0.2	0.2		
132	PROPACHLOR	ND	ug/L	0.2	0.2		
	State Unregulated - Other						
179	BROMACIL	ND	ug/L	0.2	0.2		
183	PROMETON	ND	ug/L	0.2	0.2		Qualitative Analysis Only
190	TERBACIL	ND	ug/L	0.2	0.2		
202	DIAZINON	ND	ug/L	0.2	0.2		Unstable in Acidified Sample Matrix
208	EPTC	ND	ug/L	0.3	0.3		

^{*-} An amount of "ND" indicates that the compound was not detected above the Lab's Method Detection Limit - MDL.

^{**-} Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds. A blank MCL or SAL value indicates a level is not currently established.

^{***-} If a compound is detected > or = to the State Reporting Level, SRL, specified increased monitoring frequencies may occur per DOH.

^{****-} Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.

J - Estimated value.





Reference Number: 06-00222

Lab Number: 04600450 Report Date: 1/13/2006

SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

DH#	COMPOUNDS	RESULTS	Units	SRL	Trigger	MCL	COMMENT
232	4,4-DDD	ND	ug/L	0.2	0.2		
233	4,4-DDE	ND	ug/L	0.2	0.2	l Control	
234	4,4-DDT	ND	ug/L	0.2	0.2		
236	CYANAZINE	ND	ug/L	0.2	0.2		Qualitative Analysis Only
239	MALATHION	ND	ug/L	0.2	0.2		
	PARATHION	ND	ug/L	0.2	0.2		
243	TRIFLURALIN	ND	ug/L	0.2	0.2		
	- PAHs						
96	NAPTHALENE	ND	ug/L	0.1	0.1		
	FLUORENE	ND	ug/L	0.2	0.2		
	ACENAPHTHYLENE	ND	ug/L	0.2	0.2		
	ACENAPHTHENE	ND	ug/L	0.2	0.2		
	ANTHRACENE	ND	ug/L	0.2	0.2		
	BENZ(A)ANTHRACENE	ND	ug/L	0.1	0.1		
	BENZO(B)FLUORANTHENE	ND	ug/L	0.2	0.2	100	
	BENZO(G,H,I)PERYLENE	ND	ug/L	0.2	0.2	10000	
	BENZO(K)FLUORANTHENE	ND	ug/L	0.2	0.2		
	CHRYSENE	ND	ug/L	0.2	0.2	1	
	DIBENZO(A,H)ANTHRACENE	ND	ug/L	0.2	0.2		
	FLUORANTHENE	ND	ug/L	0.2	0.2		
	INDENO(1,2,3-CD)PYRENE	ND	ug/L	0.2	0.2		
	PHENANTHRENE	ND	ug/L	0.2	0.2		
	PYRENE	ND	ug/L	0.2	0.2		
201	- Phthalates	No.	ug/L	0.2	V.2		a vight in the
258	BENZYL BUTYL PHTHALATE	ND	ug/L	0.6	0.6		
	DI-N-BUTYL PHTHALATE	ND	ug/L	0.6	0.6		
	DIETHYL PHTHALATE	ND	ug/L	0.6	0.6		
	DIMETHYL PHTHALATE	ND	ug/L	0.6	0.6	To the Te	
201	DIMETRICALATE	ND	ug/L	0.0	0.0		
						1 - 1 - 6	
							- 0.31 P. TE PER
	THE THE Y						
						Tree	

^{*-} An amount of "ND" indicates that the compound was not detected above the Lab's Method Detection Limit - MDL.

^{**-} Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds. A blank MCL or SAL value indicates a level is not currently established.

^{***-} If a compound is detected > or = to the State Reporting Level, SRL, specified increased monitoring frequencies may occur per DOH.
***- Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.

J - Estimated value.



Burlington, WA 98233

(800) 755-9295

(360) 757-1400 - FAX (360) 757-1402

Page 1 of 1

SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

Client Name: Walla Walla Basin Watershed Council

810 S Main Street

System Name:

System ID Number:

Multiple Sources:

DOH Source Number:

Milton-Freewater, OR 97862

Reference Number: 06-00222

Project: HBDIC Recharge Project

Field ID: Intake

Lab Number: 04600449 Date Collected: 1/4/2006 Date Extracted: 508_060110 Date Analyzed: 1/10/2006

Report Date: 1/11/2006

Analyst: MM

Supervisor: ()

Sample Location: HBDIC Recharge Project (WWBWC)

Sample Type:

Sample Purpose: Investigative or Other

Sampled By: Bob Bower Sampler Phone:

OOH#	COMPOUNDS	RESULTS	Units	SRL	Trigger	MCL	COMMENT
	PCBs/Toxaphene						
36	TOXAPHENE	ND	ug/L	2	2	3	
173	AROCLOR 1221	ND	ug/L	20	20		
174	AROCLOR 1232	ND	ug/L	0.5	0.5		
175	AROCLOR 1242	ND	ug/L	0.5	0.3		
176	AROCLOR 1248	ND	ug/L	0.1	0.1		
177	AROCLOR 1254	ND	ug/L	0.1	0.1		
178	AROCLOR 1260	ND	ug/L	0.2	0.2		
180	AROCLOR 1016	ND	ug/L	0.1	0.1		

^{*-} An amount of "ND" indicates that the compound was not detected above the Lab's Method Detection Limit - MDL.

^{**-} Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds.

A blank MCL or SAL value indicates a level is not currently established.

^{***-} If a compound is detected > or = to the State Reporting Level, SRL, specified increased monitoring frequencies may occur per DOH.

^{****.} Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.

J - Estimated value



Burlington, WA 98233

(800) 755-9295

(360) 757-1400 - FAX (360) 757-1402

Page 1 of 1

SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

Client Name: Walla Walla Basin Watershed Council

810 S Main Street

Milton-Freewater, OR 97862

System Name:

System ID Number:

DOH Source Number:

Multiple Sources:

Sample Type:

Sample Purpose: Investigative or Other

Sample Location: HBDIC Recharge Project (WWBWC)

County:

Sampled By: Bob Bower

Sampler Phone:

Reference Number: 06-00222

Project: HBDIC Recharge Project

Field ID: OBS well #1

Lab Number: 04600450

Date Collected: 1/4/2006

Date Extracted: 508_060110

Date Analyzed: 1/10/2006

Report Date: 1/11/2006

Analyst: MM

Supervisor: Com

DOH#	COMPOUNDS	RESULTS	Units	SRL	Trigger	MCL	COMMENT
	PCBs/Toxaphene						
36	TOXAPHENE	ND	ug/L	2	2	3	
173	AROCLOR 1221	ND	ug/L	20	20		
174	AROCLOR 1232	ND	ug/L	0.5	0.5		
175	AROCLOR 1242	ND	ug/L	0.5	0.3		
176	AROCLOR 1248	ND	ug/L	0.1	0.1		
177	AROCLOR 1254	ND	ug/L	0.1	0.1		
178	AROCLOR 1260	ND	ug/L	0.2	0.2		
180	AROCLOR 1016	ND	ug/L	0.1	0.1		

⁻ An amount of "ND" indicates that the compound was not detected above the Lab's Method Detection Limit - MDL.

^{**-} Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds A blank MCL or SAL value indicates a level is not currently established.

^{***-} If a compound is detected > or = to the State Reporting Level, SRL, specified increased monitoring frequencies may occur per DOH.

***- Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.

J - Estimated value.



Burlington, WA 98233

(800) 755-9295

(360) 757-1400 - FAX (360) 757-1402

Page 1 of 1

CARBAMATES IN DRINKING WATER

Client Name: Walla Walla Basin Watershed Council

810 S Main Street

Milton-Freewater, OR 97862

System Name:

System ID Number:

DOH Source Number:

Multiple Sources:

Sample Type:

Sample Purpose: Investigative or Other

Sample Location: HBDIC Recharge Project (WWBWC)

Sampled By: Bob Bower

Sampler Phone:

Reference Number: 06-00222

Project: HBDIC Recharge Project

Field ID: Intake

Lab Number: 04600449

Date Collected: 1/4/2006

Date Extracted: 531_060111 Date Analyzed: 1/11/2006

Report Date: 1/18/2006

Analyst: ,TW

Supervisor

EPA Method 531.2 For State Drinking Water Compliance

DOH#	COMPOUNDS	RESULTS	Units	SRL	Trigger	MCL	COMMENT
	EPA Regulated						
146	CARBOFURAN	ND	ug/L	1.8	1.8	40	
148	OXYMAL	ND	ug/L	4.0	4.0	200	
	EPA Unregulated						
141	3-HYDROXYCARBOFURAN	ND	ug/L	2.0	2.0		
142	ALDICARB	ND	ug/L	1.0	1.0		
143	ALDICARB SULFONE	ND	ug/L	1.6	1.6		
144	ALDICARB SULFOXIDE	ND	ug/L	1.0	1.0		
145	CARBARYL	ND	ug/L	2.0	2.0		
147	METHOMYL	ND	ug/L	1.0	1.0		
	State Unregulated - Other						
326	PROPOXUR (BAYGON)	ND	ug/L	1.0			
327	METHIOCARB	ND	ug/L	4.0			
	NOT in the standard of the standard of the standard of						

^{*-} An amount of "ND" indicates that the compound was not detected above the Lab's Method Detection Limit - MDL.

^{**-} Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds. A blank MCL or SAL value indicates a level is not currently established.

^{***-} If a compound is detected > or = to the State Reporting Level, SRL, specified increased monitoring frequencies may occur per DOH.

^{****-} Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.

J - Estimated value.



Burlington, WA 98233

(800) 755-9295

(360) 757-1400 - FAX (360) 757-1402

Page 1 of 1

CARBAMATES IN DRINKING WATER

Client Name: Walla Walla Basin Watershed Council

810 S Main Street

Milton-Freewater, OR 97862

System Name:

System ID Number:

DOH Source Number:

Multiple Sources:

Sample Type:

Sample Purpose: Investigative or Other

Sample Location: HBDIC Recharge Project (WWBWC)

Sampled By: Bob Bower

Sampler Phone:

Reference Number: 06-00222

Project: HBDIC Recharge Project

Field ID: OBS well #1

Lab Number: 04600450

Date Collected: 1/4/2006

Date Extracted: 531_060111

Date Analyzed: 1/11/2006

Report Date: 1/18/2006

Analyst: TW

Supervisor:

od 531 2 For State Drinking Water Compliance

EPA Regulated CARBOFURAN OXYMAL EPA Unregulated 3-HYDROXYCARBOFURAN ALDICARB ALDICARB SULFONE	ND ND ND ND	ug/L ug/L ug/L	1.8	1.8	40 200	
OXYMAL EPA Unregulated 3-HYDROXYCARBOFURAN ALDICARB ALDICARB SULFONE	ND ND ND	ug/L		2000		
EPA Unregulated 3-HYDROXYCARBOFURAN ALDICARB ALDICARB SULFONE	ND ND		4.0	4.0	200	
3-HYDROXYCARBOFURAN ALDICARB ALDICARB SULFONE	ND	ug/L			1127,012	
ALDICARB ALDICARB SULFONE	ND	ug/L				
ALDICARB SULFONE			2.0	2.0		
		ug/L	1.0	1.0		
	ND	ug/L	1.6	1.6		
ALDICARB SULFOXIDE	ND	ug/L	1.0	1.0		
CARBARYL	ND	ug/L	2.0	2.0		
METHOMYL	ND	ug/L	1.0	1.0		
State Unregulated - Other						
PROPOXUR (BAYGON)	ND	ug/L				
METHIOCARB	ND	ug/L	4.0			
					l	
	METHOMYL State Unregulated - Other PROPOXUR (BAYGON) METHIOCARB	State Unregulated - Other PROPOXUR (BAYGON) METHIOCARB ND ND	METHOMYL State Unregulated - Other PROPOXUR (BAYGON) ND ug/L ug/L ug/L	METHOMYL State Unregulated - Other PROPOXUR (BAYGON) METHIOCARB ND Ug/L 1.0 1.0 Ug/L 1.0 4.0	METHOMYL State Unregulated - Other PROPOXUR (BAYGON) METHIOCARB ND ug/L 1.0 1.0 1.0 1.0 1.0	METHOMYL State Unregulated - Other PROPOXUR (BAYGON) METHIOCARB ND ug/L 1.0 1.0 1.0

^{*-} An amount of "ND" indicates that the compound was not detected above the Lab's Method Dete

^{**-} Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds.

A blank MCL or SAL value indicates a level is not currently established.

^{***-} If a compound is detected > or = to the State Reporting Level, SRL, specified increased monitoring frequencies may occur per DOH.

⁻⁻⁻⁻⁻ Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.







QUALITY CONTROL REPORT SURROGATE REPORT

Reference Number: 06-00222

Report Date: 01/18/06

Analyte	Result Qualifier	Units	Method	Limit
TETRACHLORO-M-XYLENE (SURR)	99	%	508.1	Acceptance Range is 42% to 137%
4.2 DIMETUVI, 2 NITROPENZENE (Sum)	83	0/6	525.2	Acceptance Range is 70% to 130%
			020.2	Acceptance Range is 70% to 130%
				Acceptance Range is 70% to 130%
TRIPHENYLPHOSPHATE (Surr)	93	%		Acceptance Range is 70% to 130%
2,4 - DCAA (SURR)	119	%	515.1	Acceptance Range is 60% to 140%
TETRACHLORO-M-XYLENE (SURR)	90	%	508.1	Acceptance Range is 42% to 137%
1,3-DIMETHYL-2-NITROBENZENE (Surr)	86		525.2	Acceptance Range is 70% to 130%
PYRENE-D10 (Surr)	93			Acceptance Range is 70% to 130%
PERYLENE-D12 (Surr)	99	%		Acceptance Range is 70% to 130%
TRIPHENYLPHOSPHATE (Surr)	92	%		Acceptance Range is 70% to 130%
2,4 - DCAA (SURR)	102	%	515.1	Acceptance Range is 60% to 140%
	TETRACHLORO-M-XYLENE (SURR) 1,3-DIMETHYL-2-NITROBENZENE (Surr) PYRENE-D10 (Surr) PERYLENE-D12 (Surr) TRIPHENYLPHOSPHATE (Surr) 2,4 - DCAA (SURR) TETRACHLORO-M-XYLENE (SURR) 1,3-DIMETHYL-2-NITROBENZENE (Surr) PYRENE-D10 (Surr) PERYLENE-D12 (Surr) TRIPHENYLPHOSPHATE (Surr)	TETRACHLORO-M-XYLENE (SURR) 1,3-DIMETHYL-2-NITROBENZENE (Surr) PYRENE-D10 (Surr) PERYLENE-D12 (Surr) TRIPHENYLPHOSPHATE (Surr) 2,4 - DCAA (SURR) 119 TETRACHLORO-M-XYLENE (SURR) 1,3-DIMETHYL-2-NITROBENZENE (Surr) PYRENE-D10 (Surr) PERYLENE-D12 (Surr) PERYLENE-D12 (Surr) PERYLENE-D12 (Surr) TRIPHENYLPHOSPHATE (Surr) 92	TETRACHLORO-M-XYLENE (SURR) 99 % 1,3-DIMETHYL-2-NITROBENZENE (Surr) 83 % PYRENE-D10 (Surr) 92 % PERYLENE-D12 (Surr) 98 % TRIPHENYLPHOSPHATE (Surr) 93 % 2,4 - DCAA (SURR) 119 % TETRACHLORO-M-XYLENE (SURR) 90 % 1,3-DIMETHYL-2-NITROBENZENE (Surr) 86 % PYRENE-D10 (Surr) 93 % PERYLENE-D12 (Surr) 99 % TRIPHENYLPHOSPHATE (Surr) 99 % TRIPHENYLPHOSPHATE (Surr) 99 %	TETRACHLORO-M-XYLENE (SURR) 1,3-DIMETHYL-2-NITROBENZENE (Surr) PERYLENE-D10 (Surr) PERYLENE-D12 (Surr) TRIPHENYLPHOSPHATE (Surr) 119 119 119 119 119 119 119



11525 Knudson Rd Burlington, WA 98233 (800) 755-9295 (360) 757-1400 - FAX (360) 757-1402



QUALITY CONTROL REPORT BLANK REPORT

Reference Number: 06-00222

Report Date: 01/18/06

Batch A	nalyte	Result	Units	Limit	QC Qualifier Method	Type*	Comments
508 060110 A	ROCLOR 1221	ND	ug/L	0.12	508.1	MB	
- management of the same	ROCLOR 1232	ND	ug/L	0.02	508.1	MB	
A	ROCLOR 1242	ND	ug/L	0.02	508.1	MB	
A	ROCLOR 1248	ND	ug/L	0.02	508.1	MB	
A	ROCLOR 1254	ND	ug/L	0.02	508.1	MB	
A	ROCLOR 1260	ND	ug/L	0.02	508.1	MB	
A	ROCLOR 1016	ND	ug/L	0.02	508.1	MB	
T	ETRACHLORO-M-XYLENE (SURR)	103	%	0.00	508.1	MB	
515_060110 2,	4 - D	ND	ug/L	0.05	515.1	MB	
2,	4,5 - TP (SILVEX)	ND	ug/L	0.10	515.1	MB	
	ENTACHLOROPHENOL	ND	ug/L	0.02	515.1	MB	
D	ALAPON	ND	ug/L	0.50	515.1	MB	
D	INOSEB	ND	ug/L	0.10	515.1	MB	
P	ICLORAM	ND	ug/L	0.05	515.1	MB	
D	ICAMBA	ND	ug/L	0.05	515.1	MB	
2,	4 DB	ND	ug/L	0.25	515.1	MB	
2,	4,5 T	ND	ug/L	0.10	515.1	MB	
	ENTAZON	ND	ug/L	0.12	515.1	MB	
D	ICHLORPROP	ND	ug/L	0.12	515.1	MB	
A	CTIFLORFIN	ND	ug/L	0.50	515.1	MB	
D	ACTHAL (DCPA)	ND	ug/L	0.02	515.1	MB	
2,	4 - DCAA (SURR)	94	%		515.1	MB	
525_060110 н	EPTACHLOR EPOXIDE "B"	ND	ug/L	0.02	525.2	MB	
E	NDRIN	ND	ug/L	0.02	525.2	MB	
L	NDANE (BHC - GAMMA)	ND	ug/L	0.02	525.2	MB	
M	ETHOXYCHLOR	ND	ug/L	0.02	525.2	MB	
A	LACHLOR	ND	ug/L	0.02	525.2	MB	
A	TRAZINE	ND	ug/L	0.02	525.2	MB	
В	ENZO(A)PYRENE	ND	ug/L	0.02	525.2	MB	
C	HLORDANE, TECHNICAL	ND	ug/L	0.02	525.2	MB	
D	I(ETHYLHEXYL)-ADIPATE	ND	ug/L	0.02	525.2	MB	
D	I(ETHYLHEXYL)-PHTHALATE	0.12	ug/L	0.60	525.2	MB	
H	EPTACHLOR	ND	ug/L	0.02	525.2	MB	
Н	EXACHLOROBENZENE	ND	ug/L	0.02	525.2	MB	
H	EXACHLOROCYCLO-PENTADIENE	ND	ug/L	0.02	525.2	MB	
S	IMAZINE	ND	ug/L	0.02	525.2	MB	
A	LDRIN	ND	ug/L	0.05	525.2	MB	

^{*}Notation:

LRB: Laboratory Reagent Blanks are used to determine the background level of the analytes in a laboratory batch. Therefore, this report may include analytes not requested for your submitted samples.



11525 Knudson Rd Burlington, WA 98233 (800) 755-9295

(360) 757-1400 - FAX (360) 757-1402



QUALITY CONTROL REPORT BLANK REPORT

Reference Number: 06-00222

Report Date: 01/18/06

					QC	Water Control	•
Batch	Analyte	Result	Units	Limit	Qualifier Method	Type*	Comments
525_060110	BUTACHLOR	ND	ug/L	0.10	525.2	MB	
	DIELDRIN	ND	ug/L	0.05	525.2	MB	
	METOLACHLOR	ND	ug/L	0.25	525.2	MB	
	METRIBUZIN	ND	ug/L	0.05	525.2	MB	
	PROPACHLOR	ND	ug/L	0.05	525.2	MB	
	BROMACIL	ND	ug/L	0.05	525.2	MB	
	PROMETON	ND	ug/L	0.05	525.2	MB	
	TERBACIL	ND	ug/L	0.05	525.2	MB	
	DIAZINON	ND	ug/L	0.05	525.2	MB	
	EPTC	ND	ug/L	0.07	525.2	MB	
	4,4-DDD	ND	ug/L	0.05	525.2	MB	
	4,4-DDE	ND	ug/L	0.05	525.2	MB	
	4,4-DDT	ND	ug/L	0.05	525.2	MB	
	CYANAZINE	ND	ug/L	0.05	525.2	MB	
	MALATHION	ND	ug/L	0.05	525.2	MB	
	PARATHION	ND	ug/L	0.05	525.2	MB	
	TRIFLURALIN	ND	ug/L	0.05	525.2	MB	
	NAPTHALENE	ND	ug/L	0.02	525.2	MB	
	FLUORENE	ND	ug/L	0.05	525.2	MB	
	ACENAPHTHENE	ND	ug/L	0.05	525.2	MB	
	ANTHRACENE	ND	ug/L	0.05	525.2	MB	
	BENZ(A)ANTHRACENE	ND	ug/L	0.02	525.2	MB	
	BENZO(B)FLUORANTHENE	ND	ug/L	0.05	525.2	MB	
	BENZO(G,H,I)PERYLENE	ND	ug/L	0.05	525.2	MB	
	BENZO(K)FLUORANTHENE	ND	ug/L	0.05	525.2	MB	
	CHRYSENE	ND	ug/L	0.05	525.2	MB	
	DIBENZO(A,H)ANTHRACENE	ND	ug/L	0.05	525.2	MB	
	FLUORANTHENE	ND	ug/L	0.05	525.2	MB	
	INDENO(1,2,3-CD)PYRENE	ND	ug/L	0.05	525.2	MB	
	PHENANTHRENE	ND	ug/L	0.05	525.2	MB	
	PYRENE	ND	ug/L	0.05	525.2	MB	
	BENZYL BUTYL PHTHALATE	ND	ug/L	0.60	525.2	MB	
	DI-N-BUTYL PHTHALATE	0.17	ug/L	0.60	525.2	MB	
	DIETHYL PHTHALATE	ND	ug/L	0.60	525.2	MB	
	DIMETHYL PHTHALATE	ND	ug/L	0.60	525.2	MB	
	1,3-DIMETHYL-2-NITROBENZENE (Sur	84	%		525.2	MB	
	PERYLENE-D12 (Surr)	97	%		525.2	MB	
	PYRENE-D10 (Surr)	93	%		525.2	MB	
	TRIPHENYLPHOSPHATE (Surr)	99	%		525.2	MB	

^{*}Notation:

LRB: Laboratory Reagent Blanks are used to determine the background level of the analytes in a laboratory batch. Therefore, this report may include analytes not requested for your submitted samples.





11525 Knudson Rd Burlington, WA 98233 (800) 755-9295

(360) 757-1400 - FAX (360) 757-1402



QUALITY CONTROL REPORT BLANK REPORT

Reference Number: 06-00222

Report Date: 01/18/06

Batch	Analyte	Result	Units	Limit	QC Qualifier Method	Type*	Comments
531 060111	OXYMAL	ND	ug/L	1.00	531.2	MB	
	CARBOFURAN	ND	ug/L	0.45	531.2	MB	
	ALDICARB SULFOXIDE	ND	ug/L	0.25	531.2	MB	
	ALDICARB SULFONE	ND	ug/L	0.40	531.2	MB	
	METHOMYL	ND	ug/L	0.25	531.2	MB	
	3-HYDROXYCARBOFURAN	ND	ug/L	0.50	531.2	MB	
	ALDICARB	ND	ug/L	0.25	531.2	MB	
	CARBARYL	ND	ug/L	0.50	531.2	MB	
	PROPOXUR (BAYGON)	ND	ug/L	0.25	531.2	MB	
	METHIOCARB	ND	ug/L	1.00	531.2	MB	



LRB: Laboratory Reagent Blanks are used to determine the background level of the analytes in a laboratory batch. Therefore, this report may include analytes not requested for your submitted samples.



11525 Knudson Rd Burlington, WA 98233 (800) 755-9295

(360) 757-1400 - FAX (360) 757-1402

Page 1 of 3



QUALITY CONTROL REPORT QCS/LFB REPORT

Reference Number: 06-00222

Report Date: 01/18/06

			True			%		QC
Batch	Analyte	Result	Value	Units	Method	Recovery	Limits	Qualifier Type* Comme
508_060110	TETRACHLORO-M-XYLENE (SURR)	101		%	508.1	E-	70-130	LFB
515_060110	2,4 - D	2.13	2	ug/L	515.1	107	70-130	LFB
	2,4,5 - TP (SILVEX)	1	1	ug/L	515.1	100	70-130	LFB
	PENTACHLOROPHENOL	1.02	1	ug/L	515.1	102	70-130	LFB
	DALAPON	10.4	13	ug/L	515.1	80	70-130	LFB
	DINOSEB	1.18	2	ug/L	515.1	59	70-130	LFB
	PICLORAM	0.96	1	ug/L	515.1	96	70-130	LFB
	DICAMBA	1.07	1	ug/L	515.1	107	70-130	LFB
	2,4 DB	7.74	8	ug/L	515.1	97	70-130	LFB
	2,4,5 T	0.98	1	ug/L	515.1	98	70-130	LFB
	BENTAZON	2.1	2	ug/L	515.1	105	70-130	LFB
	DICHLORPROP	3.05	3	ug/L	515.1	102	70-130	LFB
	ACTIFLORFIN	0.72	1	ug/L	515.1	72	70-130	LFB
	DACTHAL (DCPA)	1.06	1	ug/L	515.1	106	70-130	LFB
	2,4 - DCAA (SURR)	97		%	515.1	NA	78-130	LFB
525_060110	HEPTACHLOR EPOXIDE "B"	0.76	1	ug/L	525.2	76	70-130	LFB
**************************************	ENDRIN	0.91	1	ug/L	525.2	91	70-130	LFB
	LINDANE (BHC - GAMMA)	0.89	1	ug/L	525.2	89	70-130	LFB
	METHOXYCHLOR	1.03	1	ug/L	525.2	103	70-130	LFB
	ALACHLOR	1.79	2	ug/L	525.2	90	70-130	LFB
	ATRAZINE	1.9	2	ug/L	525.2	95	70-130	LFB
	BENZO(A)PYRENE	0.88	1	ug/L	525.2	88	70-130	LFB
	CHLORDANE, TECHNICAL	0.78	1	ug/L	525.2	78	70-130	LFB
	DI(ETHYLHEXYL)-ADIPATE	0.8	1	ug/L	525.2	80	70-130	LFB
	DI(ETHYLHEXYL)-PHTHALATE	0.92	1	ug/L	525.2	92	70-130	LFB
	HEPTACHLOR	0.88	1	ug/L	525.2	88	70-130	LFB
	HEXACHLOROBENZENE	0.8	1	ug/L	525.2	80	70-130	LFB
	HEXACHLOROCYCLO-PENTADIENE	0.93	1	ug/L	525.2	93	70-130	LFB
	SIMAZINE	0.85	1	ug/L	525.2	85	70-130	LFB
	ALDRIN	0.7	1	ug/L	525.2	70	70-130	LFB
	BUTACHLOR	0.86	1	ug/L	525.2	86	70-130	LFB
	DIELDRIN	0.81	1	ug/L	525.2	81	70-130	LFB
	METOLACHLOR	0.95	1	ug/L	525.2	95	70-130	LFB
	METRIBUZIN	0.61	1	ug/L	525.2	61	70-130	LR LFB

*Notation:

Recovery = (Result of Analysis)/(True Value) * 100

NA = Indicates % Recovery could not be calculated.

QCS: Quality Control Sample, a solution containing known concentrations of method analytes which is used to fortify an aliquot of reagent matrix. The QCS is obtained from an external source and is used to check lab performance.

LFB: Laboratory Fortified Blank, an aliquot of reagent matrix to which known quantities of method analytes are added in the lab. The LFB is analyzed exactly like a sample, and its purpose is to determine whether method performance is within accepted control limits.



11525 Knudson Rd Burlington, WA 98233 (800) 755-9295

Page 2 of 3

(360) 757-1400 - FAX (360) 757-1402



QUALITY CONTROL REPORT QCS/LFB REPORT

Reference Number: 06-00222

Report Date: 01/18/06

			True			%		QC
Batch	Analyte	Result	Value	Units	Method	Recovery	Limits	Qualifier Type* Comment
525_060110	PROPACHLOR	0.95	1	ug/L	525.2	95	70-130	LFB
	BROMACIL	0.88	1	ug/L	525.2	88	70-130	LFB
	PROMETON	0.43	1	ug/L	525.2	43	70-130	QA LFB
	TERBACIL	0.96	1	ug/L	525.2	96	70-130	LFB
	DIAZINON	0.81	1	ug/L	525.2	81	70-130	LFB
	EPTC	0.86	1	ug/L	525.2	86	70-130	LFB
	4,4-DDD	0.74	1	ug/L	525.2	74	70-130	LFB
	4,4-DDE	0.8	1	ug/L	525.2	80	70-130	LFB
	4,4-DDT	0.85	1	ug/L	525.2	85	70-130	LFB
	CYANAZINE	0.85	1	ug/L	525.2	85	70-130	LFB
	MALATHION	0.7	1	ug/L	525.2	70	70-130	LFB
	TRIFLURALIN	0.98	1	ug/L	525.2	98	70-130	LFB
	FLUORENE	0.87	1	ug/L	525.2	87	70-130	LFB
	ACENAPHTHYLENE	0.54	1	ug/L	525.2	54	70-130	LR LFB
	ANTHRACENE	0.75	1	ug/L	525.2	75	70-130	LFB
	BENZ(A)ANTHRACENE	0.88	1	ug/L	525.2	88	70-130	LFB
	BENZO(B)FLUORANTHENE	1.05	1	ug/L	525.2	105	70-130	LFB
	BENZO(G,H,I)PERYLENE	1.22	1	ug/L	525.2	122	70-130	LFB
	BENZO(K)FLUORANTHENE	0.88	1	ug/L	525.2	88	70-130	LFB
	CHRYSENE	0.92	1	ug/L	525.2	92	70-130	LFB
	DIBENZO(A,H)ANTHRACENE	1.07	1	ug/L	525.2	107	70-130	LFB
	FLUORANTHENE	0.96	1	ug/L	525.2	96	70-130	LFB
	INDENO(1,2,3-CD)PYRENE	1.09	1	ug/L	525.2	109	70-130	LFB
	PHENANTHRENE	0.89	1	ug/L	525.2	89	70-130	LFB
	BENZYL BUTYL PHTHALATE	0.94	1	ug/L	525.2	94	70-130	LFB
	DI-N-BUTYL PHTHALATE	1	1	ug/L	525.2	100	70-130	LFB
	DIETHYL PHTHALATE	1.19	1	ug/L	525.2	119	70-130	LFB
	DIMETHYL PHTHALATE	0.81	1	ug/L	525.2	81	70-130	LFB
	1,3-DIMETHYL-2-NITROBENZENE (Surr)	88		%	525.2	NA	70-130	LFB
	PERYLENE-D12 (Surr)	105		%	525.2	NA	70-130	LFB
	PYRENE-D10 (Surr)	98		%	525.2	NA	70-130	LFB
	TRIPHENYLPHOSPHATE (Surr)	97		%	525.2	NA	70-130	LFB
531_060111	OXYMAL	19.1	20	ug/L	531.2	96	70-130	LFB
	CARBOFURAN	18.8	20	ug/L	531.2	94	70-130	LFB
	ALDICARB SULFOXIDE	18.6	20	ug/L	531.2	93	70-130	LFB

*Notation

Recovery = (Result of Analysis)/(True Value) * 100

NA = Indicates % Recovery could not be calculated.

QCS: Quality Control Sample, a solution containing known concentrations of method analytes which is used to fortify an aliquot of reagent matrix. The QCS is obtained from an external source and is used to check lab performance.

LFB: Laboratory Fortified Blank, an aliquot of reagent matrix to which known quantities of method analytes are added in the lab. The LFB is analyzed exactly like a sample, and its purpose is to determine whether method performance is within accepted control limits.



11525 Knudson Rd Burlington, WA 98233 (800) 755-9295

(360) 757-1400 - FAX (360) 757-1402

Page 3 of 3



QUALITY CONTROL REPORT QCS/LFB REPORT

Reference Number: 06-00222

Report Date: 01/18/06

			True			%		QC	
Batch	Analyte	Result	Value	Units	Method	Recovery	Limits	Qualifier Type*	Comment
531 060111	ALDICARB SULFONE	18.2	20	ug/L	531.2	91	70-130	LFB	
	METHOMYL	18.3	20	ug/L	531.2	92	70-130	LFB	
	3-HYDROXYCARBOFURAN	18.2	20	ug/L	531.2	91	70-130	LFB	
	ALDICARB	17.7	20	ug/L	531.2	89	70-130	LFB	
	CARBARYL	18.8	20	ug/L	531.2	94	70-130	LFB	
	PROPOXUR (BAYGON)	18.7	20	ug/L	531.2	94	70-130	LFB	
	METHIOCARB	18.1	20	ug/L	531.2	91	70-130	LFB	

*Notation:

Recovery = (Result of Analysis)/(True Value) * 100

NA = Indicates % Recovery could not be calculated.

QCS: Quality Control Sample, a solution containing known concentrations of method analytes which is used to fortify an aliquot of reagent matrix. The QCS is obtained from an external source and is used to check lab performance.

LFB: Laboratory Fortified Blank, an aliquot of reagent matrix to which known quantities of method analytes are added in the lab. The LFB is analyzed exactly like a sample, and its purpose is to determine whether method performance is within accepted control limits.





Burlington, WA 98233 (360) 757-1400 - FAX (360) 757-1402 QUALITY CONTROL REPORT QUALITY CONTROL REPORT Duplicate and Matrix Spike/Matrix Spike Duplicate Report Sample Analyte Result Result Dunits Outline Analyte Result Result Result Dunits Outline Analyte Result Result Result Dunits Outline Analyte Result Result Result Dunits Outline Analyte Outlin	449 2,4 - DCAA (SURR) 119 109 % 8.8 0-45	0-45	0-45	3.4 0-45	0-45	0-45		CAA (SURR) CAA (SURR) CAA (SURR) ANTHRENE ANTHRENE ANTHROBENZ ME-D10 (Surr) ENE-D12 (Surr)	QUALITY I Matrix Sp Duplicate Result 109 0.08 0.18 86 94	voits ug/L ug/L ug/L % % % % % % % % % % % % %	%RPD 8.8 22.2 36.4 3.4 3.2		ifer	Reference Number: 06-00222 Report Date: 1/18/2006 Comments DUP DUP DUP DUP DUP DUP DUP DUP DUP DU
--	--	------	------	----------	------	------	--	---	---	--	---	--	------	---

Duplicate

515_060110

Batch

525_060110

%RPD = Relative Percent Difference

NA = Indicates %RPD could not be calculated

Matrix Spike (MS)/Matrix Spike Duplicate (MSD) analyses are used to determine the accuracy (MS) and precision (MSD) of a analytical method in a given sample matrix. Therefore, the usefulness of this report is limited to samples of similar matrices analyzed in the same analyzical batch.



Report Date: 1/18/2006 Reference Number: 06-00222 Page 2 of 4

Matrix Spike

Matrix Spike	Spike			Duplicate										
			Spike	Spike	Spike		Percent	Percent Recovery				ac		
Batch	Sample Analyte	Result	Result	Result	Conc	Units	MS	MSD	Limits	%RPD	Limits	Qualifier	Comments	
515 060110														
	450 2,4 - D	QN	2		2	ng/L	100	NA	65-135	NA	09-0	LFM		
	450 2,4,5 - TP (SILVEX)	Q	0.99		-	ng/L	66	NA	65-135	NA	09-0	LFM		
	450 PENTACHLOROPHENOL	Q	1.01		-	ng/L	101	NA	65-135	NA	09-0	LFM		
	450 DALAPON	QN	12		13	ng/L	92	NA	65-135	NA	09-0	LFM		
	450 DINOSEB	N	1.81		2	ng/L	91	NA	65-135	NA	09-0	LFM		
	450 PICLORAM	N	6.0		-	ng/L	90	NA	65-135	NA	09-0	LFM		
	450 DICAMBA	Q	1.01		-	ng/L	101	NA	65-135	NA	09-0	LFM		
	450 2,4 DB	Q	6.77		8	ng/L	85	NA	65-135	NA	09-0	LFM		
	450 2,4,5 T	QN	-		-	ng/L	100	NA	65-135	NA	09-0	LFM		
	450 BENTAZON	N	2.07		2	ng/L	104	NA	65-135	NA	09-0	LFM		
	450 DICHLORPROP	Q	2.94		က	ng/L	86	NA	65-135	NA	09-0	LFM		
	450 ACTIFLORFIN	Q	0.97		-	ng/L	26	NA	65-135	NA	09-0	LFM		
	450 DACTHAL (DCPA)	Q	1.08		-	ng/L	108	NA	65-135	NA	09-0	LFM		
	450 2,4 - DCAA (SURR)	102	88			%		NA	70-130	NA	09-0	LFM		
525 060110														
	602 HEPTACHLOR EPOXIDE "B"	QN	0.78		_	ng/L	78	NA	70-130	NA	0-20	LFM		
	602 ENDRIN	Q	96.0		-	ng/L	96	NA	70-130	NA	09-0	LFM		
	602 LINDANE (BHC - GAMMA)	Q	98.0		-	ng/L	98	NA	70-130	NA	09-0	LFM		
	602 METHOXYCHLOR	Q	1.19		-	ng/L	119	NA	70-130	NA	09-0	LFM		
	602 ALACHLOR	Q	1.94		2	ng/L	26	NA	70-130	NA	09-0	LFM		
	602 ATRAZINE	ND	1.8		2	ng/L	06	NA	70-130	NA	09-0	LFM		
	602 BENZO(A)PYRENE	Q	0.91		-	ng/L	91	NA	70-130	NA	09-0	LFM		
	602 CHLORDANE, TECHNICAL	Q	0.84		-	ng/L	84	NA	70-130	NA	09-0	LFM		
	602 DI(ETHYLHEXYL)-ADIPATE	Q	0.88		-	ng/L	88	NA	70-130	NA	09-0	LFM		
	602 DI(ETHYLHEXYL)-PHTHALATE	Q	0.99		-	ng/L	66	NA	70-130	NA	09-0	LFM		
	602 HEPTACHLOR	N	6.0		-	ng/L	06	NA	70-130	NA NA	09-0	LFM		
	602 HEXACHLOROBENZENE	N	0.83		-	ng/L	83	NA	70-130	NA	09-0	LFM		
	602 HEXACHLOROCYCLO-PENTADIENE	Q	0.92		-	ng/L	92	NA	70-130	NA	09-0	LFM		
	602 SIMAZINE	ND	0.89		-	ng/L	88	NA	70-130	NA	09-0	LFM		
	602 ALDRIN	ND	0.73		-	ng/L	73	NA	70-130	NA	09-0	LFM		
	602 BUTACHLOR	Q	0.98		-	ng/L	86	NA	70-130	NA	09-0	LFM		
	602 DIELDRIN	N	0.84		-	ng/L	84	NA	70-130	NA	09-0	LFM		
	602 METOLACHLOR	Q	0.99			ng/L	66	NA	70-130	NA	09-0	LFM		
	602 METRIBUZIN	Q	6.0		-	ng/L	06	NA	70-130	NA	09-0	LFM		
	602 PROPACHLOR	Q	0.97		-	ng/L	26	NA	70-130	NA	09-0	LFM		
	602 BROMACIL	N	1.12		-	ng/L	112	NA	70-130	NA	09-0	LFM		

%RPD = Relative Percent Difference

NA = Indicates %RPD could not be calculated

Matrix Spike (MS)/Matrix Spike Duplicate (MSD) analyses are used to determine the accuracy (MS) and precision (MSD) of a analytical method in a given sample matrix. Therefore, the usefulness of this report is limited to samples of similar matrices analyzed in the same analytical batch.



Report Date: 1/18/2006 Reference Number: 06-00222 Page 3 of 4

Matrix Spik

Matrix Spike	pike				Duplicate											
				Spike	Spike	Spike		Percent	Percent Recovery				oc			
Batch	Sample	Sample Analyte	Result	Result	Result	Conc	Units	MS	MSD	Limits	%RPD	Limits	Qualifier		Comments	
	602	PROMETON	QN	0.3		1	ng/L	30	NA	70-130	ΝA	09-0	δA	LFM		
	602	TERBACIL	N _O	1.12		-	ng/L	112	NA	70-130	NA	09-0		LFM		
	602	DIAZINON	N O	0.89		-	ng/L	89	NA	70-130	NA	09-0		LFM		
	602	EPTC	N	0.87		-	ng/L	87	NA	70-130	NA	09-0		LFM		
	602	4,4-DDD	N	0.75		+	ng/L	75	NA	70-130	NA	09-0		LFM		
	602	4,4-DDE	Q.	0.79			ng/L	79	NA	70-130	NA	09-0		LFM		
	602	4,4-DDT	Q	8.0			ng/L	80	NA	70-130	NA	09-0		LFM		
	602	CYANAZINE	N	0.75		-	ng/L	75	NA	70-130	NA	09-0		LFM		
	602	MALATHION	N Q	0.78		Ţ.	ng/L	78	NA	70-130	NA	09-0		LFM		
	602	TRIFLURALIN	Q.	1.03		-	ng/L	103	NA	70-130	NA	09-0		LFM		
	602	FLUORENE	QN	6.0		-	ng/L	06	AN	70-130	NA	09-0		LFM		
	602	ACENAPHTHYLENE	Q	0.35		-	ng/L	35	NA	70-130	AN	09-0	R	LFM		
	602	ANTHRACENE	Q	98.0		-	ng/L	98	NA	70-130	NA	09-0		LFM		
	602	BENZ(A)ANTHRACENE	N	1.03		-	ng/L	103	NA	70-130	NA	09-0		LFM		
	602	BENZO(B)FLUORANTHENE	ND	1.12		-	ng/L	112	NA	70-130	NA	09-0		LFM		
	602	BENZO(G,H,I)PERYLENE	ND	1.21		-	ng/L	121	NA	70-130	NA	09-0		LFM		
	602	BENZO(K)FLUORANTHENE	QN	0.85		-	ng/L	85	NA	70-130	NA	09-0		LFM		
	602	CHRYSENE	N	1.06		-	ng/L	106	NA	70-130	NA	09-0		LFM		
	602	DIBENZO(A,H)ANTHRACENE	Q	1.04		-	ng/L	104	NA	70-130	NA	09-0		LFM		
	602	INDENO(1,2,3-CD)PYRENE	Q.	1.13		-	ng/L	113	NA	70-130	NA	09-0		LFM		
	602	PHENANTHRENE	Q	0.93		-	ng/L	93	NA	70-130	NA	09-0		LFM		
	602	PYRENE	Q	0.91		-	ng/L	91	NA	70-130	NA	09-0		LFM		
	602	BENZYL BUTYL PHTHALATE	Q	0.98		-	ng/L	86	NA	70-130	NA	09-0		LFM		
	602	DI-N-BUTYL PHTHALATE	Q	1.05		-	ng/L	105	NA	70-130	NA	09-0		LFM		
	602	2 DIETHYL PHTHALATE	Q	1.09		-	ng/L	109	NA	70-130	NA	09-0		LFM		
	602	DIMETHYL PHTHALATE	N	0.95		-	ng/L	92	NA	70-130	AN	09-0		LFM		
	602	2 1,3-DIMETHYL-2-NITROBENZENE (Surr	87	88			%		NA	70-130	NA	09-0		LFM		
	602	PYRENE-D10 (Surr)	91	92			%		NA	70-130	NA	09-0		LFM		
	602	PERYLENE-D12 (Surr)	96	103			%		NA	70-130	NA	09-0		LFM		
	602	2 TRIPHENYLPHOSPHATE (Surr)	93	86			%		NA	70-130	AN	09-0		LFM		
531_060111																
	420	OXYMAL	Q	20.2	19.4	20	ng/L	101	26	70-130	4.0	0-20		LFM		
	420	CARBOFURAN	Q	18.9	18.3	20	ng/L	92	92	70-130	3.2	0-20		LFM		
	450	ALDICARB SULFOXIDE	Ω	19.7	18.9	20	ng/L	66	92	70-130	4.1	0-20		LFM		
	420	ALDICARB SULFONE	N	20.2	19.4	20	ng/L	101	26	70-130	4.0	0-20		LFM		
	420) METHOMYL	Q	18.8	17.9	20	ng/L	94	06	70-130	4.9	0-20		LFM		
	450	3-HYDROXYCARBOFURAN	ND	19.7	18.9	20	ng/L	66	95	70-130	4.1	0-20		LFM		

%RPD = Relative Percent Difference

NA = Indicates %RPD could not be calculated
Matrix Spike Duplicate (MSD) analyses are used to determine the accuracy (MS) and precision (MSD) of a analytical method in a given sample matrix. Therefore, the usefulness of this report is limited to samples of similar matrices analyzed in the same analytical batch.



Page 4 of 4
Reference Number: 06-00222
Report Date: 1/18/2006

Matrix Spike

Batch

IX Spike			Duplicate	0									
		Spike	Spike	Spike		Percer	Percent Recovery				oc		
Sample Analyte	Result	Result	Result	Conc	Units	MS	MSD	Limits	%RPD	%RPD Limits	Qualifier	Comments	
450 ALDICARB	QN	17.7	16.9	20	ng/L	88	85	70-130	4.6	0-20	LFM		
450 CARBARYL	QN	18.1	17.3	20	ng/L	91	87	70-130	4.5	0-20	LFM		
450 PROPOXUR (BAYGON)	QN	18.9	18.3	20	ng/L	95	92	70-130	3.2	0-20	LFM		
450 METHIOCARB	QN	16.8	15.1	20	ng/L	84	92	70-130	10.7	0-20	LFM		

%RPD = Relative Percent Difference

NA = Indicates %RPD could not be calculated

Matrix Spike (MS)/Matrix Spike Duplicate (MSD) analyses are used to determine the accuracy (MS) and precision (MSD) of a analytical method in a given sample matrix. Therefore, the usefulness of this report is limited to samples of similar matrices analyzed in the same analytical batch.





Qualifier Definitions

Reference Number: 06-00222 Report Date: 01/18/06

Definition
Low recovery can not be accounted for. The continuing calibration checks are within acceptable limits.
Acceptance Limits do not apply. This method is not the primary method for qualitative analysis.

Sample #1/2



Lab ID#

M1873

EPAID#:

Fax: (509) 529-9681

Amount Due: \$75.00 System ID / Name: Walla Walla Basin Watershed Council 6001 Invoice Number: Sampler Bob Bower 1/3/06 Date Collected: Address: P.O. 68 Date Analyzed: 1/3/06 City: Milton Freewater Lab Analyst: Skifstad

Membrane Filtration / Fecal Coliform Analysis Report

97862

Test Methods Are Selected From The Standard Methods For Examination Of Water and Wastewater 20th Edition

Те	st Method 9222D	
Sample ID #1	Results	Units
Intake #1-A	20.0	CFU's/100 mL

Sample ID #2	Results	Units
Intake #1-B	14.0	CFU's/100 mL

Sample ID #3	Results	Units
Well #1 OBS	2.5	CFU's/100 mL

The City of Walla Walla's Mill Creek Water Treatment Laboratory will maintain records pertaining to reconstructing client's data for a minimum of five years from the date of issuance of the final report. Records may be destroyed after that .

OR

State:

Zip Code:

Signature Lab Director: Tom Krels

2-15-06 (date)

City Of Walla Walla Water Plant Laboratory 581 Mill Creek Road Walla Walla, WA 99362



11525 Knudson Rd. Burlington, WA 98233 (800) 755-9295 (360) 757-1400 - FAX (360) 757-1402 Sample #3

Page 1 of 1

INVOICE

Client No:

WAL06

Client:

WALLA WALLA BASIN WATERSHED COUNCIL

810 S MAIN STREET

MILTON-FREEWATER, OR 97862

Attn: Dil Joner

Please include this number with payment

Reference: 06-06951

Date: June 27, 2006

Project: HBDIC Recharge

Date Received: June 02, 2006

Purchase Order:

Item	Lab Sample	Number	Client Sample Description	Type of Analysis	Extended Cost
1	14226.00	OBD#1	OBS#1	Chemical Oxygen Demand	\$32.00
- 1			A TOTAL CONTROL OF THE CONTROL OF TH	Total Kjeldahl Nitrogen	\$29.00
2	14226.00	OBD#1	OBS#1		\$17.00
3	14226.00	OBD#1	OBS#1	Total Dissolved Solids	200
4	14226.00	OBD#1	OBS#1	Chloride	\$18.00
5	14226.00	OBD#1	OBS#1	SHIPPING CHARGE	\$5.00
			Rejected for out of hold time	Nitrate-N	
6	14227.00	OBD#1	The second secon		
7	14227.00	OBD#1	Rejected for out of hold time	ortho-phosphate	0404.00

Grand Total:

\$101.00

Amount Paid:

\$0.00

Amount Due:

\$101.00



11525 Knudson Rd. Burlington, WA 98233 (800) 755-9295

(360) 757-1400 - FAX (360) 757-1402

Page 1 of 1

CARBAMATES IN DRINKING WATER

Client Name: Walla Walla Basin Watershed Council

810 S Main Street

Milton-Freewater, OR 97862

Reference Number: 06-07860

Project: HBDIC

Field ID: HBDIC

Sample Description: OBS#1

Sampled By: Bower

Sample Date: 6/12/2006

Source Type:

Sampler Phone: 509-520-3534

Lab Number: 04616174
Report Date: 6/28/2006
Date Analyzed: 6/27/2006

Extraction Date: 531_060627

Analyst: GO

Supervisor: Analytical Method: 531.2

Carbamates

CAS	COMPOUND	RESULTS	Units	PQL	MDL	MCL	COMMENT
	EPA Regulated						
23135-22-0	OXYMAL	ND	ug/L	1.0	0.81	200	
1563-66-2	CARBOFURAN	ND	ug/L	1.0	0.87	40	
	EPA Unregulated						
1646-87-3	ALDICARB SULFOXIDE	ND	ug/L	1.0	0.71		
1646-88-4	ALDICARB SULFONE	ND	ug/L	1.0	0.83		
16752-77-5	METHOMYL	ND	ug/L	1.0	0.86		
16655-82-6	3-HYDROXYCARBOFURAN	ND	ug/L	1.0	1.0		
116-06-3	ALDICARB	ND	ug/L	1.0	0.88		
63-25-2	CARBARYL	ND	ug/L	1.0	0.53		
	State Unregulated - Other						
114-26-1	PROPOXUR (BAYGON)	ND	ug/L	1.0	0.72		
2032-65-7	METHIOCARB	ND	ug/L	1.0	0.76		

An amount of "ND" indicates that the compound was not detected above the Lab's Method Detection Limit - MDL.

MCL- Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds.

A blank MCL or SAL value indicates a level is not currently established.

A blank MCL or SAL value indicates a level is not currently established.

PQL - Practical Quantitation Limit is the concentration of the standard analyzed during the initial calibration.

MDL - Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.



11525 Knudson Rd. Burlington, WA 98233 (800) 755-9295

(360) 757-1400 - FAX (360) 757-1402

Page 1 of 1

DATA REPORT

Client Name: Walla Walla Basin Watershed Council

810 S Main Street

Milton-Freewater, OR 97862

Reference Number: 06-07860

Project: HBDIC

Field ID: HBDIC

Sample Description: OBS#1

Sampled By: Bower

Sample Date: 6/12/2006

Source Type:

Sampler Phone: 509-520-3534

Lab Number: 04616174 Report Date: 6/28/2006 Date Analyzed: 6/27/2006 Extraction Date: 508_060622

Analyst: JS Supervisor:

Analytical Method: 7508.1

Synthetic Organics

			Units	PQL	MDL	MCL	COMMENT
CAS	COMPOUND	RESULTS	Units	PQL			
mass	PCBs/Toxaphene	ND.	ug/L	0.2		0.5	
1336-36-3	PCBS (Total Aroclors)	ND ND	ug/L	0.1	0.1^		
	AROCLOR 1221	ND ND	ug/L	0.1	0.1^		
	AROCLOR 1232	ND	ug/L	0.1	0.1^		
	AROCLOR 1242	ND	ug/L	0.1	0.1^		
	AROCLOR 1248	ND	ug/L	0.1	0.1^		
	AROCLOR 1254	ND	ug/L	0.1	0.08		
	AROCLOR 1260	ND	ug/L	0.1	0.1		
	AROCLOR 1016	ND	ug/L	1	0.5	3	
8001-35-2	TOXAPHENE						

An amount of "ND" indicates that the compound was not detected above the Lab's Method Detection Limit - MDL.

MCL- Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds.

A blank MCL or SAL value indicates a level is not currently established.

PQL - Practical Quantitation Limit is the concentration of the standard analyzed during the initial calibration. MDL - Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.

J - Estimated value.



Reference Number: 06-07860 Page 2 of 2

Lab Number: 04616174 Report Date: 6/28/2006

SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

CAS	COMPOUND	RESULTS	Units	PQL	MDL	MCL	COMMENT
759-94-4	EPTC	ND	ug/L	0.1	0.028		
72-54-8	4,4-DDD	ND	ug/L	0.1	0.024		
72-55-9	4,4-DDE	ND	ug/L	0.1	0.024		
50-29-3	4,4-DDT	ND	ug/L	0.1	0.022		
	CYANAZINE	ND	ug/L	0.1	0.13		Qualitative Analysis Only
121-75-5	MALATHION	ND	ug/L	0.1	0.015		
56-38-2	PARATHION	ND	ug/L	0.1	0.022		
1582-09-8	TRIFLURALIN	ND	ug/L	0.1	0.024		
	- PAHs						
91-20-3	NAPTHALENE	ND	ug/L	0.1	0.1^		
86-73-7	FLUORENE	ND	ug/L	0.1	0.026		
208-96-8	ACENAPHTHYLENE	ND	ug/L	0.1	0.025		
83-32-9	ACENAPHTHENE	ND	ug/L	0.1	0.1^		
120-12-7	ANTHRACENE	ND	ug/L	0.1	0.012		
56-55-3	BENZ(A)ANTHRACENE	ND	ug/L	0.1	0.012		
205-99-2	BENZO(B)FLUORANTHENE	ND	ug/L	0.1	0.025		
191-24-2	BENZO(G,H,I)PERYLENE	ND	ug/L	0.1	0.025		
207-08-9	BENZO(K)FLUORANTHENE	ND	ug/L	0.1	0.022		
218-01-9	CHRYSENE	ND	ug/L	0.1	0.022		
53-70-3	DIBENZO(A,H)ANTHRACENE	ND	ug/L	0.1	0.024		
206-44-0	FLUORANTHENE	ND	ug/L	0.1	0.1^		
193-39-5	INDENO(1,2,3-CD)PYRENE	ND	ug/L	0.1	0.040		
85-01-8	PHENANTHRENE	ND	ug/L	0.1	0.015		
129-00-0	PYRENE	ND	ug/L	0.1	0.022		
	- Phthalates						
85-68-7	BENZYL BUTYL PHTHALATE	ND	ug/L	0.1	0.022		
84-74-2	DI-N-BUTYL PHTHALATE	ND	ug/L	0.1	0.085		
84-66-2	DIETHYL PHTHALATE	ND	ug/L	0.1	0.044		
131-11-3	DIMETHYL PHTHALATE	ND	ug/L	0.1	0.015		

MCL- Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds.

A blank MCL or SAL value indicates a level is not currently established.

PQL - Practical Quantitation Limit is the concentration of the standard analyzed during the initial calibration.

MDL - Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.



11525 Knudson Rd.

Burlington, WA 98233

(800) 755-9295

(360) 757-1400 - FAX (360) 757-1402

Page 1 of 2

SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

Client Name Walla Walla Basin Watershed Council

810 S Main Street

Milton-Freewater, OR 97862

Reference Number: 06-07860

Poet -800 FRICIO HESTIC

Sample Description: OBS#1

Sampled By: Bower

Sample Date: 6/12/2006

Source Type:

Sampler Phone: 509-520-3534

_at Number 046*6*74

Report Date: 6/28/2006

Date Analyzed: 6/22/2006

Extraction Date: 525 060622

Analyst: &6 Supervisor:

Analytical Method: 525.2

Synthetic Organics

CAS	COMPOUND		100000				Synthetic Organics
CAS	COMPOUND	RESULTS	Units	PQL	MDL	MCL	COMMENT
	EPA Regulated						
72-20-8	ENDRIN	ND	ug/L	0.1	0.030	2	
58-89-9	LINDANE (BHC - GAMMA)	ND	ug/L	0.1	0.028	0.2	
72-43-5	METHOXYCHLOR	ND	ug/L	0.1	0.015	40	
15972-60-8	3 ALACHLOR	ND	ug/L	0.1	0.044	2	
1912-24-9	ATRAZINE	ND	ug/L	0.1	0.030	3	
50-32-8	BENZO(A)PYRENE	ND	ug/L	0.1	0.012	0.2	
57-74-9	CHLORDANE, TECHNICAL	ND	ug/L	0.1	0.3	2	
103-23-1	DI(ETHYLHEXYL)-ADIPATE	ND	ug/L	0.1	0.022	400	
117-81-7	DI(ETHYLHEXYL)-PHTHALATE	ND	ug/L	0.1	0.063	6	
76-44-8	HEPTACHLOR	ND	ug/L	0.1	0.022	0.4	
1024-57-3	HEPTACHLOR EPOXIDE	ND	ug/L	0.1	0.02	0.2	
118-74-1	HEXACHLOROBENZENE	ND	ug/L	0.1	0.025	1	
77-47-4	HEXACHLOROCYCLO-PENTADIENE	ND	ug/L	0.1	0.024	50	
122-34-9	SIMAZINE	ND	ug/L	0.1	0.030	4	
87-86-5	PENTACHLOROPHENOL	ND	ug/L	0.4	0.08	1	screening only / compliance by 515
	EPA Unregulated						sorecring only / compliance by 515
309-00-2	ALDRIN	ND	ug/L	0.1	0.022		
23184-66-9	BUTACHLOR	ND	ug/L	0.1	0.024		
60-57-1	DIELDRIN	ND	ug/L	0.1	0.031		
51218-45-2	METOLACHLOR	ND	ug/L	0.1	0.024		
21087-64-9	METRIBUZIN	ND	ug/L	0.1	0.030		
1918-16-7	PROPACHLOR	ND	ug/L	0.1	0.031		
	State Unregulated - Other		7 .	312	3.001		
314-40-9	BROMACIL	ND	ug/L	0.1	0.031		
5902-51-2	TERBACIL	ND	ug/L	0.1	0.043		
3-41-5	DIAZINON	ND	ug/L	0.1	0.035		Unstable in Acidified Sample Matrix

An amount of "ND" indicates that the compound was not detected above the Lab's Method Detection Limit - MDL.

MCL- Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds. A blank MCL or SAL value indicates a level is not currently established.

PQL - Practical Quantitation Limit is the concentration of the standard analyzed during the initial calibration.

MDL - Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.



11525 Knudson Rd. Burlington, WA 98233 (800) 755-9295 (360) 757-1400 - FAX (360) 757-1402 ·

Page 1 of 1

HERBICIDES IN DRINKING WATER

Client Name: Walla Walla Basin Watershed Council

810 S Main Street

Milton-Freewater, OR 97862

Project: HBDIC

Field ID: HBDIC

Sample Description: OBS#1

Sampled By: Bower

Sample Date: 6/12/2006

Source Type:

Sampler Phone: 509-520-3534

Reference Number: 06-07860

Lab Number: 04616174 Report Date: 7/6/2006

Date Analyzed: 7/5/2006 Extraction Date: 515_060626

Analyst: 15 Supervisor: PM

Analytical Method: 515.1

Chlorophenoxy Herbicides

	Cumpic		Units	PQL	MDL	MCL	COMMENT
CAS	COMPOUND	RESULTS	Offics	FUL			
	EPA Regulated	ND	ug/L	0.2	0.11	70	
94-75-7	2,4 - D	ND	ug/L	0.1	0.02	50	
93-72-1	2,4,5 - TP (SILVEX)	ND	ug/L	0.1	0.044	1	
87-86-5	PENTACHLOROPHENOL	ND	ug/L	1.3	0.80	200	
75-99-0	DALAPON	ND	ug/L	0.2	0.16	7	
88-85-7	DINOSEB	ND	ug/L	0.1	0.089	500	
1918-02-1	PICLORAM						
	EPA Unregulated	ND	ug/L	0.1	0.045		
1918-00-9	DICAMBA						
	State Unregulated	ND	ug/L	0.1	0.089		
1861-32-1	TOTAL DCPA	ND	ug/L	0.1	0.1		
E-14-02-8	DCPA (ACID METABOLITES)	ND	ug/L	0.8	0.10		
94-82-6	2,4 DB	ND	ug/L	0.1	0.044		
93-76-5	2,4,5 T	ND	ug/L	0.2	0.067		
25057-89-		ND	ug/L	0.3	0.089		
120-36-5	DICHLORPROP	ND	ug/L	0.1	0.089		
	6 ACIFLUORFEN	ND	ug/L	0.2	0.2		
133-90-4	CHLORAMBEN	ND	ug/L	0.1	0.044		
51-36-5	3,5 - DICHLOROBENZOIC ACID						

An amount of "ND" indicates that the compound was not detected above the Lab's Method Detection Limit - MDL. MCL- Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds. A blank MCL or SAL value indicates a level is not currently established.

MDL - Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.

J - Estimated value



11525 Knudson Rd. Burlington, WA 98233 (800) 755-9295 (360) 757-1400 - FAX (360) 757-1402

Page 1 of 1

INVOICE

Client No:

WAL06

Client:

WALLA WALLA BASIN WATERSHED COUNCIL

810 S MAIN STREET

MILTON-FREEWATER, OR 97862

Atto

Lob Bower

Please include this number with payment

Reference: 06-07860

Date: July 7, 2006

Date. July 7, 2000

Project: HBDIC

Date Received: June 22, 2006

Purchase Order:

Item	Lab Sample Number	Number	Client Sample Description	Type of Analysis	Extended Cost
1	16174.00	HBDIC	OBS#1	Synthetic Organics	\$590.00
2	16174.00	HBDIC	OBS#1	Chlorophenoxy Herbicides	
3	16174.00	HBDIC	OBS#1	Carbamates	

Grand Total: \$590.00

Amount Paid:

\$0.00

Amount Due:

\$590.00

CHARGE TO Redunge - Alliance



11525 Knudson Rd. Burlington, WA 98233 (800) 755-9295 (360) 757-1400 - FAX (360) 757-1402

Page 1 of 1

Data Report

Client Name: Walla Walla Basin Watershed Council

810 S Main Street

Milton-Freewater, OR 97862

Report Date: 6/26/2006 Reference Number: 06-06951


Project: HBDIC Recharge

Collected By:

Date Received: 6/2/2006 Supervisor

Lab Nun	nber: 14226 San	nple Descripti	on: OBD#	1 - OBS#1	ı			Sample	Date:	5/30/2006	
CAS ID#	Analyte	Result	PQL	MDL	Units	DF	Method	Analyzed	Applicat	Datab	
16887-00-6	CHLORIDE	0.53	20	0.012				Allalyzeu	Analysi	Batch	Comment
E-10173	TOTAL DISSOLVED SOLIDS	1000000	5854	0.012	mg/L	1.0	300.0	6/2/2006	MVP	060602A	
E-10264		76	10	10	mg/L	1.0	SM2540 C	6/7/2006	so	TDS_060607	
	TOTAL KJELDAHL NITROGEN	ND	0.50		mg/L	1.0	CHARGO Non O		55		
E-10117	CHEMICAL OXYGEN DEMAND	ND			mg/L	1.0	SM4500-Norg C	6/21/2006	so	KN-060621	
	OEN DEMAND	ND	8.0		mg/L	1.0	SM5220 D	6/9/2006	so (OD 060609	





Page 1 of 1



QUALITY CONTROL REPORT SURROGATE REPORT

Reference Number: 06-07860

Report Date: 07/06/06

Lab No	Analyte	Result Qualifier	Units	Method	Limit
508_060622 16174	TETRACHLORO-M-XYLENE (SURR)	92	%	508.1	Acceptance Range is 42% to 137%
15_060626 16174	2,4 - DCAA (SURR)	105	%	515.1	Acceptance Range is 60% to 140%
25_060622 16174	1,3-DIMETHYL-2-NITROBENZENE (Surr) PYRENE-D10 (Surr)	95 97	% %	525.2	Acceptance Range is 70% to 130% Acceptance Range is 70% to 130%
	PERYLENE-D12 (Surr) TRIPHENYLPHOSPHATE (Surr)	91 99	% %		Acceptance Range is 70% to 130% Acceptance Range is 70% to 130%



11525 Knudson Rd. Burlington, WA 98233 (800) 755-9295

(360) 757-1400 - FAX (360) 757-1402

Page 1 of 1

CARBAMATES IN DRINKING WATER

Client Name: Walla Walla Basin Watershed Council

810 S Main Street

Milton-Freewater, OR 97862

Project: HBDIC

Field ID: HBDIC

Sample Description: OBS#1

Sampled By: Bower

Sample Date: 6/12/2006

Source Type:

Sampler Phone: 509-520-3534

Lab Number: 04616174

Reference Number: 06-07860

Report Date: 6/28/2006 Date Analyzed: 6/27/2006

Extraction Date: 531_060627

Analyst: CO Supervisor:

Analytical Method: 531.2

Carbamates

CAS	COMPOUND	RESULTS	Units	PQL	MDL	MCL	COMMENT
	EPA Regulated						
23135-22-0	OXYMAL	ND	ug/L	1.0	0.81	200	
1563-66-2	CARBOFURAN	ND	ug/L	1.0	0.87	40	
	EPA Unregulated						
1646-87-3	ALDICARB SULFOXIDE	ND	ug/L	1.0	0.71		
1646-88-4	ALDICARB SULFONE	ND	ug/L	1.0	0.83		
16752-77-5	METHOMYL	ND	ug/L	1.0	0.86		
16655-82-6	3-HYDROXYCARBOFURAN	ND	ug/L	1.0	1.0		
116-06-3	ALDICARB	ND	ug/L	1.0	0.88		
63-25-2	CARBARYL	ND	ug/L	1.0	0.53		
	State Unregulated - Other						
114-26-1	PROPOXUR (BAYGON)	ND	ug/L	1.0	0.72		
2032-65-7	METHIOCARB	ND	ug/L	1.0	0.76		

n amount of "ND" indicates that the compound was not detected above the Lab's Method Detection Limit - MDL.

MCL- Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds.

A blank MCL or SAL value indicates a level is not currently established.

PQL - Practical Quantitation Limit is the concentration of the standard analyzed during the initial calibration.

MDL - Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.

J - Estimated value.



11525 Knudson Rd. Burlington, WA 98233 (800) 755-9295 (360) 757-1400 - FAX (360) 757-1402

Page 1 of 1

DATA REPORT

Client Name: Walla Walla Basin Watershed Council

810 S Main Street

Milton-Freewater, OR 97862

Reference Number: 06-07860

Project: HBDIC

Field ID: HBDIC

Sample Description: OBS#1

Sampled By: Bower

Sample Date: 6/12/2006

Source Type:

Sampler Phone: 509-520-3534

Lab Number: 04616174 Report Date: 6/28/2006 Date Analyzed: 6/27/2006 Extraction Date: 508_060622

> Analyst: JS Supervisor:

Analytical Method: 508.1

Synthetic Organics

CAS	COMPOUND	RESULTS	Units	PQL	MDL	MCL	COMMENT
	PCBs/Toxaphene						
1336-36-3	PCBS (Total Aroclors)	ND	ug/L	0.2		0.5	
11104-28-2	AROCLOR 1221	ND	ug/L	0.1	0.1^		
	AROCLOR 1232	ND	ug/L	0.1	0.1^		
	AROCLOR 1242	ND	ug/L	0.1	0.1^		
	AROCLOR 1248	ND	ug/L	0.1	0.1^		
	AROCLOR 1254	ND	ug/L	0.1	0.1^		
	AROCLOR 1260	ND	ug/L	0.1	0.08		
	AROCLOR 1016	ND	ug/L	0.1	0.1		
8001-35-2	TOXAPHENE	ND	ug/L	1	0.5	3	



Reference Number: 06-07860 Page 2 of 2

Lab Number: 04616174 Report Date: 6/28/2006

SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

CAS	COMPOUND	RESULTS	Units	PQL	MDL	MCL	COMMENT
759-94-4	EPTC	ND	ug/L	0.1	0.028		
72-54-8	4,4-DDD	ND	ug/L	0.1	0.024		
72-55-9	4,4-DDE	ND	ug/L	0.1	0.024		
50-29-3	4,4-DDT	ND	ug/L	0.1	0.022		
21725-46-2	CYANAZINE	ND	ug/L	0.1	0.13		Qualitative Analysis Only
121-75-5	MALATHION	ND	ug/L	0.1	0.015		
56-38-2	PARATHION	ND	ug/L	0.1	0.022		
1582-09-8	TRIFLURALIN	ND	ug/L	0.1	0.024		
	- PAHs				¥.		
91-20-3	NAPTHALENE	ND	ug/L	0.1	0.1^		
86-73-7	FLUORENE	ND	ug/L	0.1	0.026		
208-96-8	ACENAPHTHYLENE	ND	ug/L	0.1	0.025		
83-32-9	ACENAPHTHENE	ND	ug/L	0.1	0.1^		
120-12-7	ANTHRACENE	ND	ug/L	0.1	0.012		
56-55-3	BENZ(A)ANTHRACENE	ND	ug/L	0.1	0.012		
205-99-2	BENZO(B)FLUORANTHENE	ND	ug/L	0.1	0.025		
191-24-2	BENZO(G,H,I)PERYLENE	ND	ug/L	0.1	0.025		
207-08-9	BENZO(K)FLUORANTHENE	ND	ug/L	0.1	0.022		
218-01-9	CHRYSENE	ND	ug/L	0.1	0.022		
53-70-3	DIBENZO(A,H)ANTHRACENE	ND	ug/L	0.1	0.024		
206-44-0	FLUORANTHENE	ND	ug/L	0.1	0.1^		
193-39-5	INDENO(1,2,3-CD)PYRENE	ND	ug/L	0.1	0.040		
85-01-8	PHENANTHRENE	ND	ug/L	0.1	0.015		
129-00-0	PYRENE	ND	ug/L	0.1	0.022		
	- Phthalates						
85-68-7	BENZYL BUTYL PHTHALATE	ND	ug/L	0.1	0.022		
84-74-2	DI-N-BUTYL PHTHALATE	ND	ug/L	0.1	0.085		
84-66-2	DIETHYL PHTHALATE	ND	ug/L	0.1	0.044		
131-11-3	DIMETHYL PHTHALATE	ND	ug/L	0.1	0.015		

PQL - Practical Quantitation Limit is the concentration of the standard analyzed during the initial calibration.

MDL - Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero. J - Estimated value.

11525 Knudson Rd. Burlington, WA 98233

(800) 755-9295

(360) 757-1400 - FAX (360) 757-1402

Page 1 of 2

SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

Client Name: Walla Walla Basin Watershed Council

810 S Main Street

Milton-Freewater, OR 97862

Reference Number: 06-07860

Project: HBDIC

Field ID: HBDIC

Sample Description: OBS#1

Sampled By: Bower

Sample Date: 6/12/2006

Source Type:

Sampler Phone: 509-520-3534

Lab Number: 04616174 Report Date: 6/28/2006 Date Analyzed: 6/22/2006 Extraction Date: 525_060622

> Analyst: & Supervisor:

Analytical Method: 525.2

Synthetic Organics

CAS	COMPOUND	RESULTS	Units	PQL	MDL	MCL	COMMENT
	EPA Regulated						
72-20-8	ENDRIN	ND	ug/L	0.1	0.030	2	
58-89-9	LINDANE (BHC - GAMMA)	ND	ug/L	0.1	0.028	0.2	
72-43-5	METHOXYCHLOR	ND	ug/L	0.1	0.015	40	
15972-60-8	ALACHLOR	ND	ug/L	0.1	0.044	2	
1912-24-9	ATRAZINE	ND	ug/L	0.1	0.030	3	
50-32-8	BENZO(A)PYRENE	ND	ug/L	0.1	0.012	0.2	
57-74-9	CHLORDANE, TECHNICAL	ND	ug/L	0.1	0.3	2	
103-23-1	DI(ETHYLHEXYL)-ADIPATE	ND	ug/L	0.1	0.022	400	
117-81-7	DI(ETHYLHEXYL)-PHTHALATE	ND	ug/L	0.1	0.063	6	
76-44-8	HEPTACHLOR	ND	ug/L	0.1	0.022	0.4	
1024-57-3	HEPTACHLOR EPOXIDE	ND	ug/L	0.1	0.02	0.2	
118-74-1	HEXACHLOROBENZENE	ND	ug/L	0.1	0.025	1	
77-47-4	HEXACHLOROCYCLO-PENTADIENE	ND	ug/L	0.1	0.024	50	
122-34-9	SIMAZINE	ND	ug/L	0.1	0.030	4	
87-86-5	PENTACHLOROPHENOL	ND	ug/L	0.4	0.08	1	screening only / compliance by 515
	EPA Unregulated						
309-00-2	ALDRIN	ND	ug/L	0.1	0.022		
23184-66-9	BUTACHLOR	ND	ug/L	0.1	0.024		
60-57-1	DIELDRIN	ND	ug/L	0.1	0.031		
51218-45-2	METOLACHLOR	ND	ug/L	0.1	0.024		
21087-64-9	METRIBUZIN	ND	ug/L	0.1	0.030		
1918-16-7	PROPACHLOR	ND	ug/L	0.1	0.031		
	State Unregulated - Other						
314-40-9	BROMACIL	ND	ug/L	0.1	0.031		
5902-51-2	TERBACIL	ND	ug/L	0.1	0.043		
333-41-5	DIAZINON	ND	ug/L	0.1	0.035		Unstable in Acidified Sample Matrix

An amount of "ND" indicates that the compound was not detected above the Lab's Method Detection Limit - MDL.

MCL- Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds. A blank MCL or SAL value indicates a level is not currently established.

PQL - Practical Quantitation Limit is the concentration of the standard analyzed during the initial calibration.

MDL - Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.

J - Estimated value.



11525 Knudson Rd. Burlington, WA 98233 (800) 755-9295 (360) 757-1400 - FAX (360) 757-1402

Page 1 of 1

HERBICIDES IN DRINKING WATER

Client Name: Walla Walla Basin Watershed Council

810 S Main Street

Milton-Freewater, OR 97862

Reference Number: 06-07860

Project: HBDIC

Field ID: HBDIC

Sample Description: OBS#1

Sampled By: Bower

Sample Date: 6/12/2006

Source Type:

COMPOUND

Sampler Phone: 509-520-3534

Lab Number: 04616174
Report Date: 7/6/2006
Date Analyzed: 7/5/2006
Extraction Date: 515_060626

Analyst: JS Supervisor: PM

Analytical Method: 515.1

Chlorophenoxy Herbicides

	CAS	COMPOUND	RESULTS	Units	PQL	MDL	MCL	COMMENT
_		EPA Regulated						
	94-75-7	2,4 - D	ND	ug/L	0.2	0.11	70	
	93-72-1	2,4,5 - TP (SILVEX)	ND	ug/L	0.1	0.02	50	
	87-86-5	PENTACHLOROPHENOL	ND	ug/L	0.1	0.044	1	
1	75-99-0	DALAPON	ND	ug/L	1.3	0.80	200	
	88-85-7	DINOSEB	ND	ug/L	0.2	0.16	7	
	1918-02-1	PICLORAM	ND	ug/L	0.1	0.089	500	
		EPA Unregulated						
	1918-00-9	DICAMBA	ND	ug/L	0.1	0.045		
		State Unregulated						
	1861-32-1	TOTAL DCPA	ND	ug/L	0.1	0.089		
	E-14-02-8	DCPA (ACID METABOLITES)	ND	ug/L	0.1	0.1		
	94-82-6	2,4 DB	ND	ug/L	8.0	0.10		
	93-76-5	2,4,5 T	ND	ug/L	0.1	0.044		
	25057-89-0	BENTAZON	ND	ug/L	0.2	0.067		
	120-36-5	DICHLORPROP	ND	ug/L	0.3	0.089		
	50594-66-6	ACIFLUORFEN	ND	ug/L	0.1	0.089		
	133-90-4	CHLORAMBEN	ND	ug/L	0.2	0.2		
	51-36-5	3,5 - DICHLOROBENZOIC ACID	ND	ug/L	0.1	0.044		

An amount of "ND" indicates that the compound was not detected above the Lab's Method Detection Limit - MDL

MCL- Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds.

A blank MCL or SAL value indicates a level is not currently established.

PQL - Practical Quantitation Limit is the concentration of the standard analyzed during the initial calibration.

MDL - Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.

J - Estimated value.



11525 Knudson Rd. Burlington, WA 98233 (800) 755-9295 (360) 757-1400 - FAX (360) 757-1402

Page 1 of 1

Data Report

Client Name: Walla Walla Basin Watershed Council

810 S Main Street

Milton-Freewater, OR 97862

Report Date: 6/26/2006

Reference Number: 06-06951

Project: HBDIC Recharge


Collected By:

Date Received: _6/2/2006

Lab Nun	nber: 14226 San	ple Descripti	on: OBD#	1 - OBS#1				Sample	Date:	5/30/2006	
CAS ID#	Analyte	Result	PQL	MDL	Units	DF	Method	Analyzed	Analys	t Batch	Comments
16887-00-6	CHLORIDE	0.53	20	0.012	mg/L	1.0	300.0	6/2/2006	MVP	1060602A	
E-10173	TOTAL DISSOLVED SOLIDS	76	10	10	mg/L	1.0	SM2540 C	6/7/2006	so	TDS_060607	
E-10264	TOTAL KJELDAHL NITROGEN	ND	0.50		mg/L	1.0	SM4500-Norg C	6/21/2006	so	TKN-060621	
E-10117	CHEMICAL OXYGEN DEMAND	ND	8.0		mg/L	1.0	SM5220 D	6/9/2006	so	COD 060609	

FORM: RESULT

Sample # 3



M1876

EPAID#:

Lab Analyst: Skifstad

System ID / Name: Walla Walla Basin Watershed Council Amount Due: Invoice Number: Sampler Bob Bower Date Collected: 5/30/06 Address: P.O. 68 Date Analyzed: 5/30/06 City: Milton Freewater

Membrane Filtration / Fecal Coliform Analysis Report

97862

Test Methods Are Selected From The Standard Methods For Examination Of Water and Wastewater 20th Edition

Test Method 9222D								
Sample ID #1	Results	Units						
Well #1 OBS	0.0	CFU's/100 mL						

Sample ID #2	Results	Units
Well #1 OBS-Dupl.	0.5	CFU's/100 mL

The City of Walla Walla's Mill Creek Water Treatment Laboratory will maintain records pertaining to reconstructing client's data for a minimum of five years from the date of issuance of the final report. Records may be destroyed after that .

Signature Lab Director:

State:

OR

Zip Code:

Ton Krehs

6-5-06 (date)

City Of Walla Walla Water Plant Laboratory 581 Mill Creek Road Walla Walla, WA 99362

SAMPLE COLLECTION: READ INSTRUCTIONS ON BACK OF GOLDENROD COPY If instructions are not followed, sample will be rejected. DATE COLLECTED TIME COLLECTED COUNTY NAME DAY YEAR IONTH : 03 130 106 □ AM PM Umal TYPE OF SYSTEM IF PUBLIC SYSTEM, COMPLETE: CIRCLE GROUP PUBLIC PUBLIC I.D. No. INDIVIDUAL (serves only 1 residence) B NAME OF SYSTEM SPECIFIC LOCATION WHERE SAMPLE COLLECTED TELEPHONE NO. DAY() EVENING (SYSTEM OWNER/MGR.: (Name) SAMPLE COLLECTED BY: (Name) SOURCE TYPE GROUND WATER UNDER SURFACE INFLUENCE SURFACE WELL or SPRING PURCHASED or COMBINATION INTERTIE OF OTHER SEND REPORT TO: (Print Full Name, Address and Zip Code) WASHINGTON TYPE OF SAMPLE(check only one in this column) Chlorinated (Residual: _ Total Free) DRINKING WATER Filtered Untreated or Other check treatment REPEAT SAMPLE Previous coliform presence Lab # Date RAW SOURCE WATER Source # S | NEW CONSTRUCTION or REPAIRS Total Coliform Fecal Coliform OTHER (Specify) Membrane REMARKS: (LAB USE ONLY) DRINKING WATER RESULTS UNSATISFACTORY, Coliforms present SATISFACTORY Coliforms absent REPEAT ☐ E. Coli present ☐ E. Coli absent SAMPLES ☐ Fecal present Fecal absent REQUIRED OTHER LABORATORY RESULTS TOTAL COLIFORM _ FECAL COLIFORM _ /100 ml E. COLI /100ml 5 /100 ml PLATE COUNT /ml ANOTHER SAMPLE REQUIRED SAMPLE NOT TESTED BECAUSE: TEST UNSUITABLE BECAUSE: Confluent growth Sample too old ☐ Wrong container ☐ TNTC ☐ Incomplete form ☐ Turbid culture Excess debris SEE REVERSE OF GREEN COPY FOR EXPLANATION OF RESULTS LAB NO. (7 DIGITS) DATE, TIME RECEIVED RECEIVED BY 5/30/06 143-03180 339 DM DATE REPORTED LABORATORY: City Of Walla Walla Water Treatment Plant 581 Mill Creek Road Walla Walla, WA 99362

WATER BACTERIOLOGICAL ANALYSIS

SAMPLE COLLECTION: READ INSTRUCTIONS ON BACK OF GOLDENROD COPY If instructions are not followed, sample will be rejected. DATE COLLECTED TIME COLLECTED | COUNTY NAME MONTH DAY YEAR 5 /30 /06 MA M PM TYPE OF SYSTEM IF PUBLIC SYSTEM, COMPLETE: CIRCLE GROUP PUBLIC PUBLIC INDIVIDUAL (serves only 1 residence) I.D. No. B NAME OF SYSTEM TELEPHONE NO. SPECIFIC LOCATION WHERE SAMPLE COLLECTED DAY() EVENING (SAMPLE COLLECTED BY: (Name) SYSTEM OWNER/MGR.: (Name) SOURCE TYPE GROUND WATER UNDER SURFACE INFLUENCE SURFACE WELL or SPRING PURCHASED or COMBINATION OF OTHER SEND REPORT TO: (Print Full Name, Address and Zip Code) TYPE OF SAMPLE(check only one in this column) Chlorinated (Residual: ____Total ____ Filtered DRINKING WATER Untreated or Other_ check treatment REPEAT SAMPLE Previous coliform presence Lab #_ Date RAW SOURCE WATER Source # S NEW CONSTRUCTION or REPAIRS OTHER (Specify) Total Coliform Fecal Coliform REMARKS: (LAB USE ONLY) DRINKING WATER RESULTS UNSATISFACTORY, Coliforms present SATISFACTORY Coliforms absent ☐ E. Coli present ☐ E. Coli absent SAMPLES ☐ Fecal present ☐ Fecal absent REQUIRED OTHER LABORATORY RESULTS TOTAL COLIFORM ______ FECAL COLIFORM ______ E. COLI /100ml PLATE COUNT /ml _/100 ml /100 ml ANOTHER SAMPLE REQUIRED SAMPLE NOT TESTED BECAUSE: TEST UNSUITABLE BECAUSE: Sample too old Confluent growth ☐ Wrong container ☐ TNTC Incomplete form ☐ Turbid culture Excess debris SEE REVERSE OF GREEN COPY FOR EXPLANATION OF RESULTS LAB NO. (7 DIGITS) DATE, TIME RECEIVED RECEIVED BY 5/30/06 143-03179 330 pm DATE REPORTED LABORATORY: City Of Walla Walla Water Treatment Plant 581 Mill Creek Road Walla Walla, WA 99362

WATER BACTERIOLOGICAL ANALYSIS

Appendices I-D

HBDIC Recharge Water Quality Testing: Lab Results, Notes and Records

2006-2007 Recharge Season



581 Mill Creek Road

Walla Walla, WA 99362

Lab ID #:

143

Washington State ID:

M1873

EPA ID#:

WA 01177

Telephone: (509) 522-3775

Fax: (509) 529-9681

Date:

11/30/06

System ID / Name: Walla Walla Basin Watershed Council Amount Due: \$100.00 Sampler Bob Bower Invoice Number: 6005 Date Collected: 11/29/06 Address: P.O. Box 68 Date Analyzed: 11/29/06 City: Milton-Freewater Lab Analyst: Skifstad State: Oregon Zip Code: 97862

Membrane Filtration / Fecal Coliform Analysis Report

Test Methods Are Selected From The Standard Methods For Examination Of Water and Wastewater 20th Edition

	Test Method 9222D	
Sample ID #1	Results	Units
Intake -A	7.0	CFU's/100mL
Sample ID #2	Results	Units
Intake -B	12.0	CFU's/100mL
Sample ID #1	Results	Units
OBS #1-A	0.0	CFU's/100mL
Sample ID #1	Results	Units
OBS #1-B	3.0	CFU's/100mL

The City of Walla Walla's Mill Creek Water Treatment Laboratory will maintain records pertaining to reconstructing client's data for a minimum of five years from the date of issuance of the final report. Records may be destroyed after that .

Signature Lab Director:

Tom Krebs

//-30-06 (date)

City Of Walla Walla Water Plant Laboratory 581 Mill Creek Road Walla Walla, WA 99362



Burlington WA Corporate Office | 1620 S Walnut St - 98233 | 800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225 360.671.0688 • 360.671.1577fax

Page 1 of 1

Data Report

Client Name: Walla Walla Basin Watershed Council

810 S Main Street

TOTAL DISSOLVED SOLIDS

Milton-Freewater, OR 97862

Report Date: 12/20/2006

Reference Number: 06-15463

Project: WWBWC

Collected By:

E-10173

Date Received: 11/29/2006

Supervisor:

	Lab Num	nber: 33112 Sam	ole Description	on: Intake					Sample Date: 11/28/2006			
	CAS ID#	Analyte	Result	PQL	MDL	Units	DF	Method	Analyzed	Analyst	Batch	Comments
_	14797-55-8	NITRATE-N	0.33	0.02	0.015	mg/L	1.0	SM4500-NO3 F	12/6/2006	so	NO3NO2-061206	
	E-10264	TOTAL KJELDAHL NITROGEN	ND	0.5	0.5	mg/L	1.0	SM4500-Norg C	12/12/2006	so	TKN-061211A	
	7723-14-0	TOTAL PHOSPHORUS	ND	0.10	0.010	mg/L	1.0	SM4500-P F	12/4/2006	so	TPHOS-061204	
	E-10117	CHEMICAL OXYGEN DEMAND	ND	8.0	1.00	mg/L	1.0	SM5220 D	12/4/2006	so	COD_061204	
	16887-00-6	CHLORIDE	0.8	20	0.012	mg/L	1.0	300.0	11/29/2006	MVP	1061129A	
	E-10173	TOTAL DISSOLVED SOLIDS	69	10	10	mg/L	1.0	SM2540 C	12/6/2006	so	TDS_061206	
-	Lab Num	nber: 33113 Sam	ple Description	on: OBS #	<u>‡1</u>				Sample	Date:	11/28/2006	
	CAS ID#	Analyte	Result	PQL	MDL	Units	DF	Method	Analyzed	Analyst	Batch	Comment
			0.22	0.02	0.015	mg/L	1.0	SM4500-NO3 F	12/6/2006	so	NO3NO2-061206	
	14/9/-55-8	NITRATE-N	0.33	0.02	0.010							
	14797-55-8 F-10264	NITRATE-N TOTAL KJELDAHL NITROGEN	ND	0.02	0.5	mg/L	1.0	SM4500-Norg C	12/12/2006	so	TKN-061211A	,
	E-10264	TOTAL KJELDAHL NITROGEN					1.0	SM4500-Norg C SM4500-P F	12/12/2006 12/4/2006	0.7.7.2	TKN-061211A TPHOS-061204	
	E-10264 7723-14-0	TOTAL KJELDAHL NITROGEN TOTAL PHOSPHORUS	ND	0.5	0.5	mg/L				so		,
	E-10264	TOTAL KJELDAHL NITROGEN	ND 0.37	0.5 0.10	0.5 0.010	mg/L mg/L	1.0	SM4500-P F	12/4/2006	so so	TPHOS-061204	



Burlington WA | 1620 S Walnut St - 98233 800.755.9295 • 360.757.1400 • 360.757.1402fax Bellingham WA 805 Orchard Dr Suite 4 - 98225 360.671.0688 • 360.671.1577fax

Page 1 of 1

HERBICIDES IN DRINKING WATER

Client Name: Walla Walla Basin Watershed Council

810 S Main Street

Milton-Freewater, OR 97862

Reference Number: 06-15463

Project: WWBWC

Field ID: Intake

Sample Description: Intake

Sampled By:

Sample Date: 11/28/2006

Source Type: Sampler Phone:

Lab Number: 04633112 Report Date: 12/29/2006 Date Analyzed: 12/15/2006 Extraction Date: 515_061211

Analyst: TM

Supervisor: Analytical Method: 515.1

Chlorophenoxy Herbicides

CAS	COMPOUND	RESULTS	Units	PQL	MDL	MCL	COMMENT
	EPA Regulated						
94-75-7	2,4 - D	ND	ug/L		0.16	70	
93-72-1	2,4,5 - TP (SILVEX)	ND	ug/L		0.04	50	
87-86-5	PENTACHLOROPHENOL	ND	ug/L		0.04	1	
75-99-0	DALAPON	ND	ug/L		0.76	200	
88-85-7	DINOSEB	ND	ug/L		0.11	7	
1918-02-1	PICLORAM	ND	ug/L		0.09	500	
	EPA Unregulated						
1918-00-9	DICAMBA	ND	ug/L		0.09		
	State Unregulated	**					
1861-32-1	TOTAL DCPA	ND	ug/L		0.09		
E-14-02-8	DCPA (ACID METABOLITES)	ND	ug/L	0.1	0.1		
94-82-6	2,4 DB	ND	ug/L		0.11		
93-76-5	2,4,5 T	ND	ug/L		0.07		i
25057-89-0		ND	ug/L		0.13		
120-36-5	DICHLORPROP	ND	ug/L		0.11		
50594-66-6	ACIFLUORFEN	ND	ug/L		0.16		
133-90-4	CHLORAMBEN	ND	ug/L	0.2	0.2		
51-36-5	3,5 - DICHLOROBENZOIC ACID	ND	ug/L		0.04		

An amount of "ND" indicates that the compound was not detected above the Lab's Method Detection Limit - MDL.

MCL- Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds

A blank MCL or SAL value indicates a level is not currently established.

PQL - Practical Quantitation Limit is the concentration of the standard analyzed during the initial calibration.

MDL - Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.

J - Estimated value.



Burlington WA | 1620 S Walnut St - 98233 800.755.9295 • 360.757.1400 • 360.757.1402fax Bellingham WA 805 Orchard Dr Suite 4 - 98225 360.671.0688 • 360.671.1577fax

Page 1 of 1

HERBICIDES IN DRINKING WATER

Client Name: Walla Walla Basin Watershed Council

810 S Main Street

Milton-Freewater, OR 97862

Reference Number: 06-15463

Project: WWBWC

Field ID: OBS #1

Sample Description: OBS #1

Sampled By:

Sample Date: 11/28/2006

Source Type: Sampler Phone:

Lab Number: 04633113 Report Date: 12/29/2006 Date Analyzed: 12/15/2006

Extraction Date: 515_061211 Analyst: TM

Supervisor: 0 M Analytical Method: 515.1

Chlorophenoxy Herbicides

CAS	COMPOUND	RESULTS	Units	PQL	MDL	MCL	COMMENT
	EPA Regulated						
94-75-7	2,4 - D	ND	ug/L		0.16	70	
93-72-1	2,4,5 - TP (SILVEX)	ND	ug/L		0.04	50	
87-86-5	PENTACHLOROPHENOL	ND	ug/L		0.04	1	
75-99-0	DALAPON	ND	ug/L		0.76	200	
8-85-7	DINOSEB	ND	ug/L		0.11	7	
1918-02-1	PICLORAM	ND	ug/L		0.09	500	
	EPA Unregulated						
1918-00-9	DICAMBA	ND	ug/L		0.09		
	State Unregulated						
1861-32-1	TOTAL DCPA	ND	ug/L		0.09		
E-14-02-8	DCPA (ACID METABOLITES)	ND	ug/L	0.1	0.1		
94-82-6	2,4 DB	ND	ug/L		0.11		
93-76-5	2,4,5 T	ND	ug/L		0.07		
25057-89-0	BENTAZON	ND	ug/L		0.13		
120-36-5	DICHLORPROP	ND	ug/L		0.11		
50594-66-6	ACIFLUORFEN	ND	ug/L		0.16		
133-90-4	CHLORAMBEN	ND	ug/L	0.2	0.2		
51-36-5	3,5 - DICHLOROBENZOIC ACID	ND	ug/L		0.04		

unt of "ND" indicates that the compound was not detected above the Lab's Method Detection Limit - MDL

MCL- Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds. A blank MCL or SAL value indicates a level is not currently established.

PQL - Practical Quantitation Limit is the concentration of the standard analyzed during the initial calibration.

MDL - Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.



Burlington WA | 1620 S Walnut St - 98233 800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225 360.671.0688 • 360.671.1577fax

Page 1 of 2

SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

Client Name: Walla Walla Basin Watershed Council

810 S Main Street

Milton-Freewater, OR 97862

Reference Number: 06-15463

Project: WWBWC

Field ID: Intake

Sample Description: Intake

Sampled By:

Sample Date: 11/28/2006

Source Type: Sampler Phone:

Lab Number: 04633112 Report Date: 12/27/2006 Date Analyzed: 12/11/2006 Extraction Date: 525_061211 Analyst: CO

Supervisor: Analytical Method: 525.2

Synthetic Organics

							9,111,10115
CAS	COMPOUND	RESULTS	Units	PQL	MDL	MCL	COMMENT
	EPA Regulated						
72-20-8	ENDRIN	ND	ug/L	0.1	0.030	2	
58-89-9	LINDANE (BHC - GAMMA)	ND	ug/L	0.1	0.028	0.2	
72-43-5	METHOXYCHLOR	ND	ug/L	0.1	0.015	40	
15972-60	-8 ALACHLOR	ND	ug/L	0.1	0.044	2	
1912-24-9) ATRAZINE	ND	ug/L	0.1	0.030	3	
50-32-8	BENZO(A)PYRENE	ND	ug/L	0.1	0.012	0.2	
57-74-9	CHLORDANE, TECHNICAL	ND	ug/L	0.1	0.3	2	
103-23-1	DI(ETHYLHEXYL)-ADIPATE	ND	ug/L	0.1	0.022	400	
117-81-7	DI(ETHYLHEXYL)-PHTHALATE	ND	ug/L	0.1	0.063	6	
76-44-8	HEPTACHLOR	ND	ug/L	0.1	0.022	0.4	
1024-57-3	HEPTACHLOR EPOXIDE	ND	ug/L	0.1	0.02	0.2	
118-74-1	HEXACHLOROBENZENE	ND	ug/L	0.1	0.025	1	
77-47-4	HEXACHLOROCYCLO-PENTADIENE	ND	ug/L	0.1	0.024	50	
122-34-9	SIMAZINE	ND	ug/L	0.1	0.030	4	- 11. 4 14. 42.5 11.
87-86-5	PENTACHLOROPHENOL	ND	ug/L	0.4	0.08	1	screening only / compliance by 515.1
	EPA Unregulated						
309-00-2	ALDRIN	ND	ug/L	0.1	0.022		
23184-66	-9 BUTACHLOR	ND	ug/L	0.1	0.024		
60-57-1	DIELDRIN	ND	ug/L	0.1	0.031		
51218-45	-2 METOLACHLOR	ND	ug/L	0.1	0.024		
21087-64	-9 METRIBUZIN	ND	ug/L	0.1	0.030		
1918-16-7	7 PROPACHLOR	ND	ug/L	0.1	0.031		
	State Unregulated - Other						
314-40-9	BROMACIL	ND	ug/L	0.1	0.031		
5902-51-2	2 TERBACIL	ND	ug/L	0.1	0.043		

on amount of "ND" indicates that the compound was not detected above the Lab's Method Detection Limit - MDL.

MCL- Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds. A blank MCL or SAL value indicates a level is not currently established.

PQL - Practical Quantitation Limit is the concentration of the standard analyzed during the initial calibration.

MDL - Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero

J - Estimated value



Reference Number: 06-15463 Page 2 of 2

Lab Number: 04633112 Report Date: 12/27/2006

SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

CAS	COMPOUND	RESULTS	Units	PQL	MDL	MCL	COMMENT WAT
333-41-5	DIAZINON	ND	ug/L	0.1	0.035		Unstable in Acidified Sample Matrix
759-94-4	EPTC	ND	ug/L	0.1	0.028		
72-54-8	4,4-DDD	ND	ug/L	0.1	0.024		
72-55-9	4,4-DDE	ND	ug/L	0.1	0.024		
50-29-3	4,4-DDT	ND	ug/L	0.1	0.022		
21725-46-2	CYANAZINE	ND	ug/L	0.1	0.13		Qualitative Analysis Only
121-75-5	MALATHION	ND	ug/L	0.1	0.015		
56-38-2	PARATHION	ND	ug/L	0.1	0.022		
1582-09-8	TRIFLURALIN	ND	ug/L	0.1	0.024		
	- PAHs						
91-20-3	NAPTHALENE	ND	ug/L	0.1	0.1^		
86-73-7	FLUORENE	ND	ug/L	0.1	0.026		
208-96-8	ACENAPHTHYLENE	ND	ug/L	0.1	0.025		
83-32-9	ACENAPHTHENE	ND	ug/L	0.1	0.1^		
120-12-7	ANTHRACENE	ND	ug/L	0.1	0.012		
56-55-3	BENZ(A)ANTHRACENE	ND ·	ug/L	0.1	0.012		
205-99-2	BENZO(B)FLUORANTHENE	ND	ug/L	0.1	0.025		
191-24-2	BENZO(G,H,I)PERYLENE	ND	ug/L	0.1	0.025		
207-08-9	BENZO(K)FLUORANTHENE	ND	ug/L	0.1	0.022		
?18-01-9	CHRYSENE	ND	ug/L	0.1	0.022		
53-70-3	DIBENZO(A,H)ANTHRACENE	ND	ug/L	0.1	0.024		
206-44-0	FLUORANTHENE	ND	ug/L	0.1	0.1^		
193-39-5	INDENO(1,2,3-CD)PYRENE	ND	ug/L	0.1	0.040		
85-01-8	PHENANTHRENE	ND	ug/L	0.1	0.015		
129-00-0	PYRENE	ND	ug/L	0.1	0.022		
	- Phthalates						
85-68-7	BENZYL BUTYL PHTHALATE	ND	ug/L	0.1	0.022		
84-74-2	DI-N-BUTYL PHTHALATE	ND	ug/L	0.1	0.085		
84-66-2	DIETHYL PHTHALATE	ND	ug/L	0.1	0.044		
131-11-3	DIMETHYL PHTHALATE	ND	ug/L	0.1	0.015		

nount of "ND" indicates that the compound was not detected above the Lab's Method Detection Limit - MDL.

MCL- Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds. A blank MCL or SAL value indicates a level is not currently established.

PQL - Practical Quantitation Limit is the concentration of the standard analyzed during the initial calibration.

MDL - Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero

J - Estimated value.



Microbiology

Burlington WA | 1620 S Walnut St - 98233

800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225 360.671.0688 • 360.671.1577fax

Page 1 of 2

SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

Client Name: Walla Walla Basin Watershed Council

810 S Main Street

Milton-Freewater, OR 97862

Reference Number: 06-15463

Project: WWBWC

Field ID: OBS #1

Sample Description: OBS #1

Sampled By:

Sample Date: 11/28/2006

Source Type: Sampler Phone:

Lab Number: 04633113 Report Date: 12/27/2006 Date Analyzed: 12/11/2006

Extraction Date: 525_061211

Analyst: MM/C(

Supervisor:

Analytical Method: 525/2

Synthetic Organics

CAS	COMPOUND	RESULTS	Units	PQL	MDL	MCL	COMMENT
	EPA Regulated						
72-20-8	ENDRIN	ND	ug/L	0.1	0.030	2	
58-89-9	LINDANE (BHC - GAMMA)	ND	ug/L	0.1	0.028	0.2	
72-43-5	METHOXYCHLOR	ND	ug/L	0.1	0.015	40	
15972-60-8	ALACHLOR	ND	ug/L	0.1	0.044	2	
312-24-9	ATRAZINE	ND	ug/L	0.1	0.030	3	
50-32-8	BENZO(A)PYRENE	ND	ug/L	0.1	0.012	0.2	
57-74-9	CHLORDANE, TECHNICAL	ND	ug/L	0.1	0.3	2	
103-23-1	DI(ETHYLHEXYL)-ADIPATE	ND	ug/L	0.1	0.022	400	
117-81-7	DI(ETHYLHEXYL)-PHTHALATE	ND	ug/L	0.1	0.063	6	
76-44-8	HEPTACHLOR	ND	ug/L	0.1	0.022	0.4	
1024-57-3	HEPTACHLOR EPOXIDE	ND	ug/L	0.1	0.02	0.2	
118-74-1	HEXACHLOROBENZENE	ND	ug/L	0.1	0.025	1	
77-47-4	HEXACHLOROCYCLO-PENTADIENE	ND	ug/L	0.1	0.024	50	
122-34-9	SIMAZINE	ND	ug/L	0.1	0.030	4	
87-86-5	PENTACHLOROPHENOL	ND	ug/L	0.4	0.08	1	screening only / compliance by 515.
	EPA Unregulated						
309-00-2	ALDRIN	ND	ug/L	0.1	0.022		
23184-66-9	BUTACHLOR	ND	ug/L	0.1	0.024		
60-57-1	DIELDRIN	ND	ug/L	0.1	0.031		
51218-45-2	METOLACHLOR	ND	ug/L	0.1	0.024		
21087-64-9	METRIBUZIN	ND	ug/L	0.1	0.030		
1918-16-7	PROPACHLOR	ND	ug/L	0.1	0.031		
	State Unregulated - Other						
	BROMACIL	ND	ug/L	0.1	0.031		
5902-51-2	TERBACIL	ND	ug/L	0.1	0.043		

unt of "ND" indicates that the compound was not detected above the Lab's Method Detection Limit - MDL.

Muc. Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds A blank MCL or SAL value indicates a level is not currently established.

PQL - Practical Quantitation Limit is the concentration of the standard analyzed during the initial calibration.

MDL - Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero. J - Estimated value



Reference Number: 06-15463 Page 2 of 2

Lab Number: 04633113 Report Date: 12/27/2006

SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

	CAS	COMPOUND	RESULTS	Units	PQL	MDL	MCL	COMMENT WAT
	333-41-5	DIAZINON	ND	ug/L	0.1	0.035		Unstable in Acidified Sample Matri
	759-94-4	EPTC	ND	ug/L	0.1	0.028		
	72-54-8	4,4-DDD	ND	ug/L	0.1	0.024		
	72-55-9	4,4-DDE	ND	ug/L	0.1	0.024		
	50-29-3	4,4-DDT	ND	ug/L	0.1	0.022		
	21725-46-2	CYANAZINE	ND	ug/L	0.1	0.13		Qualitative Analysis Only
	121-75-5	MALATHION	ND	ug/L	0.1	0.015		
	56-38-2	PARATHION	ND	ug/L	0.1	0.022		
	1582-09-8	TRIFLURALIN	ND	ug/L	0.1	0.024		
		- PAHs						
	91-20-3	NAPTHALENE	ND	ug/L	0.1	0.1^		
	86-73-7	FLUORENE	ND	ug/L	0.1	0.026		2
	208-96-8	ACENAPHTHYLENE	ND	ug/L	0.1	0.025		
	83-32-9	ACENAPHTHENE	ND	ug/L	0.1	0.1^		
	120-12-7	ANTHRACENE	ND	ug/L	0.1	0.012		
	56-55-3	BENZ(A)ANTHRACENE	ND	ug/L	0.1	0.012		
	205-99-2	BENZO(B)FLUORANTHENE	ND	ug/L	0.1	0.025		
	191-24-2	BENZO(G,H,I)PERYLENE	ND	ug/L	0.1	0.025		
	207-08-9	BENZO(K)FLUORANTHENE	ND	ug/L	0.1	0.022		
1	218-01-9	CHRYSENE	ND	ug/L	0.1	0.022		
	53-70-3	DIBENZO(A,H)ANTHRACENE	ND	ug/L	0.1	0.024		
	206-44-0	FLUORANTHENE	ND	ug/L	0.1	0.1^		
	193-39-5	INDENO(1,2,3-CD)PYRENE	ND	ug/L	0.1	0.040		
	85-01-8	PHENANTHRENE	ND	ug/L	0.1	0.015		
	129-00-0	PYRENE	ND	ug/L	0.1	0.022		
		- Phthalates						
	85-68-7	BENZYL BUTYL PHTHALATE	ND	ug/L	0.1	0.022		
	84-74-2	DI-N-BUTYL PHTHALATE	ND	ug/L	0.1	0.085		
	84-66-2	DIETHYL PHTHALATE	ND	ug/L	0.1	0.044		
	131-11-3	DIMETHYL PHTHALATE	ND	ug/L	0.1	0.015		

An amount of "ND" indicates that the compound was not detected above the Lab's Method Detection Limit - MDL.

MCL- Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds.

A blank MCL or SAL value indicates a level is not currently established.

PQL - Practical Quantitation Limit is the concentration of the standard analyzed during the initial calibration.

MDL - Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.

J - Estimated value.



Burlington WA | 1620 S Walnut St - 98233 800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225 360.671.0688 • 360.671.1577fax

Page 1 of 1

DATA REPORT

Client Name: Walla Walla Basin Watershed Council

810 S Main Street

Milton-Freewater, OR 97862

Reference Number: 06-15463

Project: WWBWC

Field ID: Intake

Sample Description: Intake

Sampled By:

Sample Date: 11/28/2006

Source Type: Sampler Phone:

Lab Number: 04633112 Report Date: 12/27/2006 Date Analyzed: 12/11/2006 Extraction Date: 508_061211

Analyst: MM Supervisor: (4)

Analytical Method: 508.1

Synthetic Organics

198 9							Synthetic Organics
CAS	COMPOUND	RESULTS	Units	PQL	MDL	MCL	COMMENT
	PCBs/Toxaphene						
1336-36-3	PCBS (Total Aroclors)	ND	ug/L	0.2		0.5	
11104-28-2	AROCLOR 1221	ND	ug/L	0.1	0.1^		
11141-16-5	AROCLOR 1232	ND	ug/L	0.1	0.1^		
53469-21-9	AROCLOR 1242	ND	ug/L	0.1	0.1^		
12672-29-6	AROCLOR 1248	ND	ug/L	0.1	0.1^		
11097-69-1	AROCLOR 1254	ND	ug/L	0.1	0.1^		
11096-82-5	AROCLOR 1260	ND	ug/L	0.1	0.08		
12674-11-2	AROCLOR 1016	ND	ug/L	0.1	0.1		
8001-35-2	TOXAPHENE	ND	ug/L	1	0.5	3	

An amount of "ND" indicates that the compound was not detected above the Lab's Method Detection Limit - MDL.

MCL- Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds. A blank MCL or SAL value indicates a level is not currently established

PQL - Practical Quantitation Limit is the concentration of the standard analyzed during the initial calibration.

MDL - Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.

J - Estimated value



Burlington WA | 1620 S Walnut St - 98233 Corporate Office

800.755.9295 • 360.757.1400 • 360.757.1402fax Bellingham WA 805 Orchard Dr Suite 4 - 98225 360.671.0688 • 360.671.1577fax

Page 1 of 1

DATA REPORT

Client Name: Walla Walla Basin Watershed Council

810 S Main Street

Milton-Freewater, OR 97862

Reference Number: 06-15463

Project: WWBWC

Field ID: OBS #1

Sample Description: OBS #1

Sampled By:

Sample Date: 11/28/2006

Source Type: Sampler Phone:

Lab Number: 33113 Report Date: 12/27/2006 Date Analyzed: 12/11/2006

Extraction Date: 508_061211 Analyst: MM

Supervisor:

Analytical Method: 508.1

Synthetic Organics

								-,
	CAS	COMPOUND	RESULTS	Units	PQL	MDL	MCL	COMMENT
		PCBs/Toxaphene						
	1336-36-3	PCBS (Total Aroclors)	ND	ug/L	0.2		0.5	
	11104-28-2	AROCLOR 1221	ND	ug/L	0.1	0.1^		
	11141-16-5	AROCLOR 1232	ND	ug/L	0.1	0.1^		
1	53469-21-9	AROCLOR 1242	ND	ug/L	0.1	0.1^		
	12672-29-6	AROCLOR 1248	ND	ug/L	0.1	0.1^		
	11097-69-1	AROCLOR 1254	ND	ug/L	0.1	0.1^		
	11096-82-5	AROCLOR 1260	. ND	ug/L	0.1	0.08		
	12674-11-2	AROCLOR 1016	ND	ug/L	0.1	0.1		
	8001-35-2	TOXAPHENE	ND	ug/L	1	0.5	3	

An amount of "ND" indicates that the compound was not detected above the Lab's Method Detection Limit - MDL

MCL- Maximum Contaminant Level; maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds.

A blank MCL or SAL value indicates a level is not currently established.

PQL - Practical Quantitation Limit is the concentration of the standard analyzed during the initial calibration.

MDL - Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.



Microbiology

Burlington WA | 1620 S Walnut St - 98233 800.755.9295 • 360.757.1400 • 360.757.1402fax Bellingham WA 805 Orchard Dr Suite 4 - 98225 360.671.0688 • 360.671.1577fax

Page 1 of 1

CARBAMATES IN DRINKING WATER

Client Name: Walla Walla Basin Watershed Council

810 S Main Street

Milton-Freewater, OR 97862

Reference Number: 06-15463

Project: WWBWC

Field ID: Intake

Sample Description: Intake

Sampled By:

Sample Date: 11/28/2006

Source Type: Sampler Phone:

Lab Number: 33112 Report Date: 12/29/2006 Date Analyzed: 12/26/2006

Extraction Date: 531_061221

Analyst: TM/ep

Supervisor: W

Analytical Method: 531.2

							Carbamates
CAS	COMPOUND	RESULTS	Units	PQL	MDL	MCL	COMMENT
	EPA Regulated						
23135-22-0	OXYMAL	ND	ug/L	1.0	0.81	200	
1563-66-2	CARBOFURAN	ND	ug/L	1.0	0.87	40	
	EPA Unregulated						
1646-87-3	ALDICARB SULFOXIDE	ND	ug/L	1.0	0.71		
1646-88-4	ALDICARB SULFONE	ND	ug/L	1.0	0.83		
16752-77-5	METHOMYL	ND	ug/L	1.0	0.86		
16655-82-6	3-HYDROXYCARBOFURAN	ND	ug/L	1.0	1.0		
116-06-3	ALDICARB	ND	ug/L	1.0	0.88		
63-25-2	CARBARYL	ND	ug/L	1.0	0.53		
	State Unregulated - Other						
114-26-1	PROPOXUR (BAYGON)	ND	ug/L	1.0	0.72		
2032-65-7	METHIOCARB	ND	ug/L	1.0	0.76		

An amount of "ND" indicates that the compound was not detected above the Lab's Method Detection Limit - MDL.

MCL- Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds. A blank MCL or SAL value indicates a level is not currently established.

PQL - Practical Quantitation Limit is the concentration of the standard analyzed during the initial calibration.

MDL - Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.

J - Estimated value



Burlington WA | 1620 S Walnut St - 98233

800.755.9295 • 360.757.1400 • 360.757.1402fax Bellingham WA 805 Orchard Dr Suite 4 - 98225

360.671.0688 • 360.671.1577fax

Page 1 of 1

CARBAMATES IN DRINKING WATER

Client Name: Walla Walla Basin Watershed Council

810 S Main Street

Milton-Freewater, OR 97862

Reference Number: 06-15463

Project: WWBWC

Field ID: OBS #1

Sample Description: OBS #1

Sampled By:

Sample Date: 11/28/2006

Source Type: Sampler Phone:

Lab Number: 33113

Report Date: 12/29/2006 Date Analyzed: 12/26/2006 Extraction Date: 531_061221

Analyst: TM/co

Supervisor:

Analytical Method: 531.2

Carbamates

CAS	COMPOUND	RESULTS	Units	PQL	MDL	MCL	COMMENT
	EPA Regulated						
23135-22-0	OXYMAL	ND	ug/L	1.0	0.81	200	
1563-66-2	CARBOFURAN	ND	ug/L	1.0	0.87	40	
	EPA Unregulated						
1646-87-3	ALDICARB SULFOXIDE	ND	ug/L	1.0	0.71		
1646-88-4	ALDICARB SULFONE	ND	ug/L	1.0	0.83		
16752-77-5	METHOMYL	ND	ug/L	1.0	0.86		
16655-82-6	3-HYDROXYCARBOFURAN	ND	ug/L	1.0	1.0		
116-06-3	ALDICARB	ND	ug/L	1.0	0.88		
63-25-2	CARBARYL	ND	ug/L	1.0	0.53		
	State Unregulated - Other						
114-26-1	PROPOXUR (BAYGON)	ND	ug/L	1.0	0.72		
2032-65-7	METHIOCARB	ND	ug/L	1.0	0.76		

An amount of "ND" indicates that the compound was not detected above the Lab's Method Detection Limit - MDL.

MCL- Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds. A blank MCL or SAL value indicates a level is not currently established.

PQL - Practical Quantitation Limit is the concentration of the standard analyzed during the initial calibration.

MDL - Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.







QUALITY CONTROL REPORT SURROGATE REPORT

Reference Number: 06-15463

Report Date: 12/29/06

Lab No	Analyte	Result Qualifier	Units	Method	Limit	alf
515 061211					Littill	
33112	2,4 - DCAA (SURR)	97	%	515.1	Acceptance Rang	e is 60% to 140%
08 061211						
33112	TETRACHLORO-M-XYLENE (SURR)	92	%	508.1	Acceptance Rang	e is 42% to 137%
525_061211				000.1	Acceptance Many	C 13 42 /0 tO 137 /0
33112	1,3-DIMETHYL-2-NITROBENZENE (Surr)	105	%	525.2	Acceptance Rang	e is 70% to 130%
	PYRENE-D10 (Surr)	100	%	020.2	Acceptance Rang	
	PERYLENE-D12 (Surr)	101	%		Acceptance Rang	
	TRIPHENYLPHOSPHATE (Surr)	109	%		Acceptance Rang	
15 061211						
33113	2,4 - DCAA (SURR)	96	%	515.1	Acceptance Rang	e is 60% to 140%
08 061211						
33113	TETRACHLORO-M-XYLENE (SURR)	91	%	500.4		
25_061211	TETTOTO MEXICENE (SOUNT)	91	70	508.1	Acceptance Range	e is 42% to 137%
33113	1,3-DIMETHYL-2-NITROBENZENE (Surr)	105	0/	505.0		
	PYRENE-D10 (Surr)	102	%	525.2	Acceptance Range	
	PERYLENE-D12 (Surr)	103	%		Acceptance Range	
	TRIPHENYLPHOSPHATE (Surr)	108	%		Acceptance Range	
	THE TENTE (SUIT)	100	70		Acceptance Range	e is 70% to 130%







QUALITY CONTROL REPORT SURROGATE REPORT

Reference Number: 06-15463 Report Date: 12/27/06

Lab No 515 061211	Analyte	Result Qualifier	Units	Method	Limit W)		
33112	2,4 - DCAA (SURR)	97	%	515.1	Acceptance Range is 60% to 140%		
08_061211 33112 25_061211	TETRACHLORO-M-XYLENE (SURR)	92	%	508.1	Acceptance Range is 42% to 137%		
33112	1,3-DIMETHYL-2-NITROBENZENE (Surr) PYRENE-D10 (Surr) PERYLENE-D12 (Surr) TRIPHENYLPHOSPHATE (Surr)	105 100 101 109	% % %	525.2	Acceptance Range is 70% to 130% Acceptance Range is 70% to 130% Acceptance Range is 70% to 130% Acceptance Range is 70% to 130%		
5_061211 33113	2,4 - DCAA (SURR)	96	%	515.1	Acceptance Range is 60% to 140%		
8_061211 33113 5_061211	TETRACHLORO-M-XYLENE (SURR)	91	%	508.1	Acceptance Range is 42% to 137%		
33113	1,3-DIMETHYL-2-NITROBENZENE (Surr) PYRENE-D10 (Surr) PERYLENE-D12 (Surr) TRIPHENYLPHOSPHATE (Surr)	105 102 103 108	% % %	525.2	Acceptance Range is 70% to 130% Acceptance Range is 70% to 130% Acceptance Range is 70% to 130% Acceptance Range is 70% to 130%		





Latoralde

581 Mill Creek Road

Walla Walla, WA 99362

Lab ID #:

143

Washington State ID:

M1873

EPA ID#:

WA 01177 Telephone: (509) 522-3775

Fax: (509) 529-9681

05/18/07

Amount Due: \$100.00 System ID / Name: Walla Walla Basin Watershed Council 7001 Invoice Number: Sampler Bob Bower Date Collected: 5/18/07 Address: P.O. Box 68 Date Analyzed: 5/18/07 City: Milton-Freewater Lab Analyst: Skifstad State: Oregon Zip Code: __

Membrane Filtration / Fecal Coliform Analysis Report

Test Methods Are Selected From The Standard Methods For Examination Of Water and Wastewater 20th Edition

ALTERIAL PROPERTY AND A SECOND	Test Method 9222D	
Sample ID #1	Results	Units
Intake -1A	19.0	CFU's/100mL
Sample ID #2	Results	Units
Intake -1B	23.0	CFU's/100mL
Sample ID #1	Results	Units
OBS - 2A	1.0	CFU's/100mL
Sample ID #1	Results	Units
OBS - 2B	0.0	CFU's/100mL

The City of Walla Walla's Mill Creek Water Treatment Laboratory will maintain records pertaining to reconstructing client's data for a minimum of five years from the date of issuance of the final report. Records may be destroyed after that .

Signature Lab Director:

Tom Krebs

5/21/07 (date)

City Of Walla Walla Water Plant Laboratory 581 Mill Creek Road Walla Walla, WA 99362



Burlington WA Corporate Office Bellingham WA

1620 S Walnut St - 98233 800.755.9295 • 360.757.1400 • 360.757.1402fax 805 Orchard Dr Suite 4 - 98225 Microbiology 360.671.0688 • 360.671.1577fax

Page 1 of 1

Data Report

Client Name: Walla Walla Basin Watershed Council

810 S Main Street

Milton-Freewater, OR 97862

Report Date: 5/31/2007 Reference Number: 07-06211

Project: HBDIC Recharge Project

Collected By: Bob Bower

Date Received: 5/18/2007 Supervisor:

Lab Nur	nber: 14513 Sam	ple Descripti	on: OBS #	#1 - Observ	ation Wel	1#1	Sample Date: 5/17/2007					
CAS ID#	Analyte	Result	PQL	MDL	Units	DF	Method	Analyzed	Analyst	Batch	Comments	
14797-55-8	NITRATE-N	0.11	0.100	0.015	mg/L	1.0	300.0	5/18/2007	MVP	1070518A		
E-10264	TOTAL KJELDAHL NITROGEN	ND	0.5	0.1391	mg/L	1.0	SM4500-Norg C			TKN-070529		
E-10117	CHEMICAL OXYGEN DEMAND	ND	8.0	1.00	mg/L	1.0	SM5220 D	5/21/2007		COD 070521		
16887-00-6	CHLORIDE	0.5	20	0.012	mg/L	1.0	300.0	5/18/2007		1070518A		
E-10173	TOTAL DISSOLVED SOLIDS	69	- 10	10	mg/L	1.0	SM2540 C	5/24/2007		TDS 070524		
723-14-0	TOTAL PHOSPHORUS	ND	0.10	0.0282	mg/L	1.0	SM4500-P F/SM 4500-P B			TPHOS-070524		

FORM RESULT



Burlington WA Corporate Office

1620 S Walnut St - 98233

 Corporate Office
 800.755.9295 • 360.757.1400 • 360.757.1402fax

 Bellingham WA
 805 Orchard Dr Suite 4 - 98225

360.671.0688 • 360.671.1577fax

Page 1 of 1

INVOICE

Client No:

Client:

WAL06

WALLA WALLA BASIN WATERSHED COUNCIL

810 S MAIN STREET

MILTON-FREEWATER, OR 97862

Attn:

Please include this number with payment

Reference: 07-06211

Date: May 31, 2007

Project: HBDIC Recharge Project

Date Received: May 18, 2007

Purchase Order:

tem	Lab Sample Number	Number	Client Sample Description	Type of Analysis	Extended
1	14513.00	OBS #1	Observation Well #1	Synthetic Organics	\$590.00
2	14513.00	OBS #1	Observation Well #1	Chlorophenoxy Herbicides	4000.00
3	14513.00	OBS #1	Observation Well #1	Carbamates	
4	14513.00	OBS #1	Observation Well #1	Total Kieldahl Nitrogen	\$29.00
5	5 14513.00 OBS #1		Observation Well #1	Chemical Oxygen Demand	\$32.00
6	14513.00	OBS #1	Observation Well #1	Nitrate-N	\$18.00
7	14513.10	OBS #1	Observation Well #1	Total Phosphorus	\$20.00
8	14513.10	OBS #1	Observation Well #1	Total Dissolved Solids	\$17.00
9	14513.10	OBS #1	Observation Well #1	Chloride	\$18.00
10	14513.10		Shipping Charge	SHIPPING CHARGE	\$5.00
				Grand Total:	\$729.00

Amount Paid: \$0.00 Amount Due: \$729.00

APPROVED TO PAY

CHARGE TO 2010 - 263



Burlington WA

1620 S Walnut St - 98233 800.755.9295 • 360.757.1400 • 360.757.1402fax Bellingham WA 805 Orchard Dr Suite 4 - 98225

360.671.0688 • 360.671.1577fax

Page 1 of 1

HERBICIDES IN DRINKING WATER

Client Name: Walla Walla Basin Watershed Council

810 S Main Street

Milton-Freewater, OR 97862

System Name:

System ID Number:

DOH Source Number:

Multiple Sources:

Sample Type:

County:

Sample Purpose: Investigative or Other

Sample Location: Observation Well #1

Sampler Phone:

Sampled By: Bob Bower

Reference Number: 07-06211

Project: HBDIC Recharge Project

Field ID: OBS #1

Lab Number: 04614513

Date Collected: 5/17/2007

Date Extracted: 515_07521

Date Analyzed: 5/21/2007

Report Date: 5/25/2007

Analyst: HY/CC

Supervisor:

DOH#	COMPOUNDS	RESULTS	Units	SRL	Trigger	MCL	COMMENT
	EPA Regulated						
37	2,4 - D	ND	ug/L	0.2	0.2	70	The same of the sa
38	2,4,5 - TP (SILVEX)	ND	ug/L	0.4	0.4	50	in nomoto 017
134	PENTACHLOROPHENOL	ND	ug/L	0.08	0.08	1	The removal little
137	DALAPON	ND	ug/L	2	2	200	176 Notesta Det
139	DINOSEB	ND	ug/L	0.4	0.4	7	The British W.
140	PICLORAM	ND	ug/L	0.2	0.2	500	ANT READONNE TEL
	EPA Unregulated				and .		- mazon 211
138	DICAMBA	ND	ug/L	0.2	0.2		and stocoper (MT)
	State Unregulated			-	400	1 10	American Section 1
222	TOTAL (DCPA & Metabolites)	ND	ug/L	0.1	0.1		
	DCPA (ACID METABOLITES)	ND	ug/L	0.1	0.1		
135	2,4 DB	ND	ug/L	1.0	1.0		
136	2,4,5 T	ND	ug/L	0.4	0.4		
220	BENTAZON	ND	ug/L	0.5	0.5		
221	DICHLORPROP	ND	ug/L	0.5	0.5		
223	ACIFLUORFEN	ND	ug/L	2.0	2.0		
224	CHLORAMBEN	ND	ug/L	0.2	0.2		
226	3,5 - DICHLOROBENZOIC ACID	ND	ug/L	0.5	0.5		

^{*-} An amount of "ND" indicates that the compound was not detected above the Lab's Method Detection Limit - MDL

^{**-} Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds. A blank MCL or SAL value indicates a level is not currently established.

^{***-} If a compound is detected > or = to the State Reporting Level, SRL, specified increased monitoring frequencies may occur per DOH.

^{****} Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.

J - Estimated value.



Burlington WA Corporate Office

1620 S Walnut St - 98233 800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225 360.671.0688 • 360.671.1577fax

Page 1

SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

Client Name: Walla Walla Basin Watershed Council

810 S Main Street

Milton-Freewater, OR 97862

System Name:

System ID Number:

DOH Source Number:

Multiple Sources:

Sample Type:

Sample Purpose: Investigative or Other Sample Location: Observation Well #1

County:

Sampled By: Bob Bower

Sampler Phone:

Reference Number: 07-06211

Project: HBDIC Recharge Project

Field ID: OBS #1

Lab Number: 04614513

Date Collected: 5/17/2007 Date Extracted: 508 070523

Date Analyzed: 5/23/2007

Report Date: 5/25/2007

Analyst: MM/C(Supervisor:

EPA Method 508.1 For State Drinking Water Compliance

DOH#	COMPOUNDS	THE R. L.	RESULTS	Units	SRL	Trigger	MCL	COMMENT
	PCBs/Toxaphene							
153	PCBS (Total Aroclors)		ND	ug/L	0.2	0.2	0.5	0.4173
173	AROCLOR 1221		ND	ug/L	20	20		Freezenthau R
174	AROCLOR 1232		ND	ug/L	0.5	0.5		de la companya de la
175	AROCLOR 1242		ND	ug/L	0.5	0.3		The same of the sa
176	AROCLOR 1248		ND	ug/L	0.1	0.1		Martin Ser
177	AROCLOR 1254		ND	ug/L	0.1	0.1		and the second of the
178	AROCLOR 1260		ND	ug/L	0.2	0.2		Intelligent ATD
180	AROCLOR 1016		ND	ug/L	0.1	0.1		AMERICAN BUT
36	TOXAPHENE		ND	ug/L	2	2	3	State Venezulation
			1.0			538		22 hors some them
			1.0.	2		CIRC	l Harri	THE REAL PROPERTY.
			0.1		ALC: Y	me .		the same of the sa
			- 6.0	10		- 1111		1 2 2 2 2
			2.0		Age	704		Hartweet Well
			80		20			The second second second
			144	net	4	611	- 12	Acres number 200
				day		Tier .		Terrando of DEL
				No.		- 011	T INDA	Total out the party and
	*							
			The state of				E-12	

^{*-} An amount of "ND" indicates that the compound was not detected above the Lab's Method Detection Limit - MDL

^{*-} Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds.

A blank MCL or SAL value indicates a level is not currently established.

^{***-} If a compound is detected > or = to the State Reporting Level, SRL, specified increased monitoring frequencies may occur per DOH.

^{****-} Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.



Burlington WA | 1620 S Walnut St - 98233 800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225 Microbiology 360.671.0688 • 360.671.1577fax

Page 1 of 1

CARBAMATES IN DRINKING WATER

Client Name: Walla Walla Basin Watershed Council

810 S Main Street

Milton-Freewater, OR 97862

Reference Number: 07-06211

Project: HBDIC Recharge Project

Field ID: OBS #1

Sample Description: Observation Well #1

Sampled By: Bob Bower Sample Date: 5/17/2007

Source Type:

Sampler Phone:

Lab Number: 04614513 Report Date: 5/31/2007

Date Analyzed: 5/29/2007 Extraction Date: 531_070529

Analyst: CO

Supervisor:

Analytical Method: 531.2

CAS	COMPOUND	30	101	RESULTS	Units	PQL	MDL	MCL	COMMENT
	EPA Regulated								burillapid ART
23135-22-0	OXYMAL			ND	ug/L	1.0	0.81	200	
1563-66-2	CARBOFURAN			ND	ug/L	1.0	0.87	40	
	EPA Unregulated								
46-87-3	ALDICARB SULFOXIDE			ND	ug/L	1.0	0.71		
1646-88-4	ALDICARB SULFONE			ND	ug/L	1.0	0.83		
16752-77-5	METHOMYL			ND	ug/L	1.0	0.86		
16655-82-6	3-HYDROXYCARBOFURAN			ND	ug/L	1.0	1.0		
116-06-3	ALDICARB			ND	ug/L	1.0	0.88		
63-25-2	CARBARYL			ND	ug/L	1.0	0.53		
	State Unregulated - Other								
114-26-1	PROPOXUR (BAYGON)			ND	ug/L	1.0	0.72		
2032-65-7	METHIOCARB			ND	ug/L	1.0	0.76		

An amount of "ND" indicates that the compound was not detected above the Lab's Method Detection Limit - MDL.

MCL- Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds. A blank MCL or SAL value indicates a level is not currently established.

PQL - Practical Quantitation Limit is the concentration of the standard analyzed during the initial calibration.

MDL - Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.

J - Estimated value.



Burlington WA | 1620 S Walnut St - 98233

Corporate Office 800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225 Microbiology 360.671.0688 • 360.671.1577fax

Page 1 of 2

SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

Client Name: Walla Walla Basin Watershed Council

810 S Main Street

Milton-Freewater, OR 97862

Reference Number: 07-06211

Project: HBDIC Recharge Project

Field ID: OBS #1

Sample Description: Observation Well #1

Sampled By: Bob Bower Sample Date: 5/17/2007

Source Type: Sampler Phone: Lab Number: 04614513
Report Date: 5/30/2007
Date Analyzed: 5/23/2007
Extraction Date: 525_070523

Analyst: MM/C(Supervisor:

Analytical Method: 525.2 V

Synthetic Organics

CAS	COMPOUND		JOM	RES	ULTS	Units	PQL	Ely	MDL	MCL	COMMENT	
	EPA Regulated										berdugen ASS	_
72-20-8	ENDRIN			ND		ug/L	0.1		0.030	2		
58-89-9	LINDANE (BHC - GAMMA)			ND		ug/L	0.1		0.028	0.2		
72-43-5	METHOXYCHLOR			ND		ug/L	0.1		0.015	40		
15972-60-8	ALACHLOR			ND		ug/L	0.1		0.044	2		
1912-24-9	ATRAZINE			ND		ug/L	0.1		0.030	3		
50-32-8	BENZO(A)PYRENE			ND		ug/L	0.1		0.012	0.2		
57-74-9	CHLORDANE, TECHNICAL			ND		ug/L	0.1		0.3	2		
103-23-1	DI(ETHYLHEXYL)-ADIPATE			ND		ug/L	0.1		0.022	400		
117-81-7	DI(ETHYLHEXYL)-PHTHALATE			ND		ug/L	0.1		0.063	6		
76-44-8	HEPTACHLOR			ND		ug/L	0.1		0.022	0.4		
1024-57-3	HEPTACHLOR EPOXIDE			ND		ug/L	0.1		0.02	0.2		
118-74-1	HEXACHLOROBENZENE			ND		ug/L	0.1		0.025	1		
77-47-4	HEXACHLOROCYCLO-PENTADIE	ENE		ND		ug/L	0.1		0.024	50		
122-34-9	SIMAZINE			ND		ug/L	0.1		0.030	4		
87-86-5	PENTACHLOROPHENOL			ND		ug/L	0.4		0.08	1	screening only / compliance	by 515.1
	EPA Unregulated											
309-00-2	ALDRIN			ND		ug/L	0.1		0.022			
23184-66-9	BUTACHLOR			ND		ug/L	0.1		0.024			
60-57-1	DIELDRIN			ND		ug/L	0.1		0.031			
51218-45-2	METOLACHLOR			ND		ug/L	0.1		0.024			
21087-64-9	METRIBUZIN			ND		ug/L	0.1		0.030			
1918-16-7	PROPACHLOR			ND		ug/L	0.1		0.031			
	State Unregulated - Other											
314-40-9	BROMACIL		1	ND		ug/L	0.1		0.031			
5902-51-2	TERBACIL		1	ND		ug/L	0.1		0.043			

An amount of "ND" indicates that the compound was not detected above the Lab's Method Detection Limit - MDL

MCL- Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds. A blank MCL or SAL value indicates a level is not currently established.

PQL - Practical Quantitation Limit is the concentration of the standard analyzed during the initial calibration.

MDL - Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.

J - Estimated value.



Reference Number: 07-06211 Page 2 of 2

Lab Number: 04614513 Report Date: 5/30/2007

SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

CAS	COMPOUND	RESULTS	Units	PQL	MDL MCL	COMMENT
333-41-5	DIAZINON	ND	ug/L	0.1	0.035	Unstable in Acidified Sample Matrix
759-94-4	EPTC	ND	ug/L	0.1	0.028	
72-54-8	4,4-DDD	ND	ug/L	0.1	0.024	
72-55-9	4,4-DDE	ND	ug/L	0.1	0.024	
50-29-3	4,4-DDT	ND	ug/L	0.1	0.022	
21725-46-2	CYANAZINE	ND	ug/L	0.1	0.13	Qualitative Analysis Only
121-75-5	MALATHION	ND	ug/L	0.1	0.015	
56-38-2	PARATHION	ND	ug/L	0.1	0.022	
1582-09-8	TRIFLURALIN	ND	ug/L	0.1	0.024	
	- PAHs					
91-20-3	NAPTHALENE	ND	ug/L	0.1	0.1^	
86-73-7	FLUORENE	ND	ug/L	0.1	0.026	
208-96-8	ACENAPHTHYLENE	ND	ug/L	0.1	0.025	
83-32-9	ACENAPHTHENE	ND	ug/L	0.1	0.1^	
120-12-7	ANTHRACENE	ND	ug/L	0.1	0.012	
56-55-3	BENZ(A)ANTHRACENE	ND	ug/L	0.1	0.012	
205-99-2	BENZO(B)FLUORANTHENE	ND	ug/L	0.1	0.025	
191-24-2	BENZO(G,H,I)PERYLENE	ND	ug/L	0.1	0.025	
207-08-9	BENZO(K)FLUORANTHENE	ND	ug/L	0.1	0.022	
-01-9	CHRYSENE	ND	ug/L	0.1	0.022	
53-70-3	DIBENZO(A,H)ANTHRACENE	ND	ug/L	0.1	0.024	
206-44-0	FLUORANTHENE	ND	ug/L	0.1	0.1^	
193-39-5	INDENO(1,2,3-CD)PYRENE	ND	ug/L	0.1	0.040	
85-01-8	PHENANTHRENE	ND	ug/L	0.1	0.015	
129-00-0	PYRENE	ND	ug/L	0.1	0.022	
	- Phthalates					
85-68-7	BENZYL BUTYL PHTHALATE	ND	ug/L	0.1	0.022	
84-74-2	DI-N-BUTYL PHTHALATE	ND	ug/L	0.1	0.085	
84-66-2	DIETHYL PHTHALATE	ND	ug/L	0.1	0.044	
131-11-3	DIMETHYL PHTHALATE	ND	ug/L	0.1	0.015	

An amount of "ND" indicates that the compound was not detected above the Lab's Method Detection Limit - MDL.

MCL- Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds.

A blank MCL or SAL value indicates a level is not currently established.

PQL - Practical Quantitation Limit is the concentration of the standard analyzed during the initial calibration.

MDL - Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.

J - Estimated value.







QUALITY CONTROL REPORT SURROGATE REPORT

Reference Number: 07-06211

Report Date: 05/31/07

Lab No	Analyte	Result Qualifier	Units	Method	Limit
508_070523					
14513	TETRACHLORO-M-XYLENE (SURR)	93	%	508.1	Acceptance Limits 70%-130%
515 07521					
14513	2,4 - DCAA (SURR)	100	%	515.1	Acceptance Range is 70 - 130%
525 070523	Sacretina in the control of the cont				
14513	1,3-DIMETHYL-2-NITROBENZENE (Surr)	96	%	525.2	Acceptance Range is 70% to 130%
	PYRENE-D10 (Surr)	106	%		Acceptance Range is 70% to 130%
	PERYLENE-D12 (Surr)	77	%		Acceptance Range is 70% to 130%
	TRIPHENYLPHOSPHATE (Surr)	97	%		Acceptance Range is 70% to 130%

Appendices I-E

HBDIC Recharge Water Quality Testing: Lab Results, Notes and Records

2007-2008 Recharge Season





Burlington WA | 1620 S Walnut St - 98233

800.755.9295 • 360.757.1400 • 360.757.1402fax Bellingham WA 805 Orchard Dr Suite 4 - 98225

360.671.0688 • 360.671.1577fax

Page 1 of 1

DATA REPORT

Client Name: Walla Walla Basin Watershed Council

810 S Main Street

Milton-Freewater, OR 97862

Lab Number: 35783

Field ID: Intake

Sample Description: @HBDIC Recharge

Collect Date: 11/26/2007

Matrix: Water

Extraction Date: 12/7/2007 Extraction Method: 3535

Reference Number: 07-15764

Project: HBDIC Recharge Project

Report Date: 5/2/2008 Date Analyzed: 12/10/2007

Analyst: CO Peer Review: MVA Analytical Method: 525.2

SOC for Walla Walla

CAS ID#	COMPOUNDS	RESULT	Flag	Units	PQL	MDL	D.F.	Batch	COMMENT	
2312-35-8	PROPARGITE	ND		ug/L		-	1.0	525_070120	Qualitative analysis	
60-51-5	DIMETHOATE	ND		ug/L	0.5	0.03	1.0	525_070120	Qualitative analysis	
57837-19-1	METALAXYL	ND		ug/L	0.1	-	1.0		Qualitative analysis	
15299-99-7	NAPROPAMIDE	ND		ug/L	0.1	0.05	1.0		Qualitative analysis	
86-86-2	1-NAPHTHALENEACETAMIDE	ND		ug/L	0.5	-	1.0		Qualitative analysis	
60168-88-9	FENARIMOL	ND		ug/L	0.1	0.03	1.0		Qualitative analysis	
36-34-7	MEVINPHOS	ND		ug/l	0.1	0.03	1.0		Qualitative analysis	
	AZINPHOS-METHYL	ND		ug/L	0.5	0.12	1.0		Qualitative analysis	
2921-88-2	CHLORPYRIFOS	ND		ug/L	0.1	0.04	1.0		Qualitative analysis	
115-32-2	DICOFOL	ND		ug/L	1	-	1.0		Qualitative analysis	
298-00-0	METHYL PARATHION	ND		ug/L	0.5	0.1	1.0		Qualitative analysis	
732-11-6	PHOSMET	ND		ug/L	0.5	-	1.0		Qualitative analysis	
43121-43-3	TRIADIMEFON	ND		ug/L	0.1	0.07	1.0		Qualitative analysis	
68694-11-1	TRIFLUMIZOLE	ND		ug/L	1.0	1.0	1.0		Qualitative analysis	
950-37-8	METHIDATHINON	ND		ug/L	0.5	0.5	1.0		Qualitative analysis	
88671-89-0	MYCLOBUTANIL	ND		ug/L	0.5	0.5	1.0		Qualitative analysis	
51235-04-2	HEXAZINONE	ND		ug/L	0.1	0.05	1.0		Qualitative analysis	
				710-T-110-T-1					C 100 CESOCK LINE VON THE PROPERTY OF LABOUR AND LOCAL PROPERTY.	





Burlington WA | 1620 S Walnut St - 98233 | 800.755.9295 • 360.757.14

800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225 360.671.0688 • 360.671.1577fax

Page 1 of 1

DATA REPORT

Client Name: Walla Walla Basin Watershed Council

810 S Main Street

Milton-Freewater, OR 97862

Lab Number: 449

Field ID: Intake

Sample Description: HBDIC Recharge Project (WWBWC)

Matrix: Drinking Water

Collect Date: 1/4/2006

Extraction Date: 1/10/2006 Extraction Method: 3535

Reference Number: 06-00222

Project: HBDIC Recharge Project

Report Date: 5/2/2008

Date Analyzed: 1/11/2006

Analyst: CO Peer Review: MVA

Analytical Method: 525.2

SOC for Walla Walla

CAS ID#	COMPOUNDS	RESULT	Flag	Units	PQL	MDL	D.F.	Batch	COMMENT	
2312-35-8	PROPARGITE	ND	ug	/L		-	1.0	525_070120	Qualitative analysis	
60-51-5	DIMETHOATE	ND	ug	/L	0.5	0.03	1.0	525_070120	Qualitative analysis	
57837-19-1	METALAXYL	ND	ug	/L	0.1	-	1.0		Qualitative analysis	
15299-99-7	NAPROPAMIDE	ND	ug	/L	0.1	0.05	1.0		Qualitative analysis	
86-86-2	1-NAPHTHALENEACETAMIDE	ND	ug	/L	0.5	-	1.0		Qualitative analysis	
60168-88-9	FENARIMOL	ND	ug	/L	0.1	0.03	1.0		Qualitative analysis	
36-34-7	MEVINPHOS	ND	ug	/1	0.1	0.03	1.0		Qualitative analysis	
-50-0	AZINPHOS-METHYL	ND	ug	/L	0.5	0.12	1.0		Qualitative analysis	
2921-88-2	CHLORPYRIFOS	ND	ug	/L	0.1	0.04	1.0		Qualitative analysis	
115-32-2	DICOFOL	ND	ug	/L	1	-	1.0		Qualitative analysis	
298-00-0	METHYL PARATHION	ND	ug	/L	0.5	0.1	1.0		Qualitative analysis	
732-11-6	PHOSMET	ND	ug	/L	0.5	-	1.0		Qualitative analysis	
43121-43-3	TRIADIMEFON	ND	ug	/L	0.1	0.07	1.0		Qualitative analysis	
68694-11-1	TRIFLUMIZOLE	ND	ug	/L	1.0	1.0	1.0		Qualitative analysis	
950-37-8	METHIDATHINON	ND	ug	/L	0.5	0.5	1.0		Qualitative analysis	
88671-89-0	MYCLOBUTANIL	ND	ug	/L	0.5	0.5	1.0		Qualitative analysis	
51235-04-2	HEXAZINONE	ND	ug	/L	0.1	0.05	1.0		Qualitative analysis	

Result of:

NA - indicates the compound was not analyzed.

Flags are data qualifiers. If there are data qualifiers on your report definitions can be found on an accompanying sheet.

ND - indicates the compound was not detected above the PQL or MDL.

PQL = Practical Quantitation Limit is the lowest level that can be acheived within specified limits of precision and accuracy during routine laboratory operating conditions. D.F. - Dilution Factor





Bellingham WA 805 Orchard Dr Suite 4 - 98225 360.671.0688 • 360.671.1577fax

Page 1 of 1

DATA REPORT

Client Name: KUO Testing Labs Inc

337 S 1st

Othello, WA 99344

Lab Number: 24845

Field ID: 74115

Sample Description: Intake

Matrix: Surface Water Collect Date: 12/8/2004 Extraction Date: 12/20/2004

Extraction Method: 3535

Reference Number: 04-12075

Project: 74115/74116

Report Date: 5/2/2008 Date Analyzed: 12/21/2004

Analyst: CO Peer Review: MVA Analytical Method: 525.2

SOC for Walla Walla

CAS ID#	COMPOUNDS	RESULT	Flag	Units	PQL	MDL	D.F.	Batch	COMMENT	
2312-35-8	PROPARGITE	ND		ug/L		-	1.0	525_070120	Qualitative analysis	
60-51-5	DIMETHOATE	ND		ug/L	0.5	0.03	1.0	525_070120	Qualitative analysis	
57837-19-1	METALAXYL	ND		ug/L	0.1	-	1.0		Qualitative analysis	
15299-99-7	NAPROPAMIDE	ND		ug/L	0.1	0.05	1.0		Qualitative analysis	
86-86-2	1-NAPHTHALENEACETAMIDE	ND		ug/L	0.5	-	1.0		Qualitative analysis	
60168-88-9	FENARIMOL	ND		ug/L	0.1	0.03	1.0		Qualitative analysis	
6-34-7	MEVINPHOS	ND		ug/l	0.1	0.03	1.0		Qualitative analysis	
50-0	AZINPHOS-METHYL	ND		ug/L	0.5	0.12	1.0		Qualitative analysis	
2921-88-2	CHLORPYRIFOS	ND		ug/L	0.1	0.04	1.0		Qualitative analysis	
115-32-2	DICOFOL	ND		ug/L	1	-	1.0		Qualitative analysis	
298-00-0	METHYL PARATHION	ND		ug/L	0.5	0.1	1.0		Qualitative analysis	
732-11-6	PHOSMET	ND		ug/L	0.5	=	1.0		Qualitative analysis	
43121-43-3	TRIADIMEFON	ND		ug/L	0.1	0.07	1.0		Qualitative analysis	
68694-11-1	TRIFLUMIZOLE	ND		ug/L	1.0	1.0	1.0		Qualitative analysis	
950-37-8	METHIDATHINON	ND		ug/L	0.5	0.5	1.0		Qualitative analysis	
88671-89-0	MYCLOBUTANIL	ND		ug/L	0.5	0.5	1.0		Qualitative analysis	
51235-04-2	HEXAZINONE	ND		ug/L	0.1	0.05	1.0		Qualitative analysis	

esult of:

NA - indicates the compound was not analyzed.

Flags are data qualifiers. If there are data qualifiers on your report definitions can be found on an accompanying sheet.

ND - indicates the compound was not detected above the PQL or MDL.

PQL = Practical Quantitation Limit is the lowest level that can be acheived within specified limits of precision and accuracy during routine laboratory operating conditions. D.F. - Dilution Factor.





Burlington WA | 1620 S Walnut St - 98233 | 800.755.9295 • 360.757.14

800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225

360.671.0688 • 360.671.1577fax

Page 1 of 1

DATA REPORT

Client Name: KUO Testing Labs Inc

337 S 1st

Othello, WA 99344

Lab Number: 4659

Field ID: 74116

Sample Description: intake

Matrix: Drinking Water

Collect Date: 4/13/2004 Extraction Date: 4/19/2004

Extraction Method: 3535

Reference Number: 04-2366

Project: 70292

Report Date: 5/2/2008

Date Analyzed: 4/21/2004

Analyst: CO

Peer Review: MVA

Analytical Method: 525.2

SOC for Walla Walla

		SUC IOI W	alla vvalla						
CAS ID#	COMPOUNDS	RESULT Flag	Units	PQL	MDL	D.F.	Batch	COMMENT	
2312-35-8	PROPARGITE	ND	ug/L		٠.	1.0	525_070120	Qualitative analysis	
60-51-5	DIMETHOATE	ND	ug/L	0.5	0.03	1.0	525_070120	Qualitative analysis	
57837-19-1	METALAXYL	ND	ug/L	0.1	-	1.0		Qualitative analysis	
15299-99-7	NAPROPAMIDE	ND	ug/L	0.1	0.05	1.0		Qualitative analysis	
86-86-2	1-NAPHTHALENEACETAMIDE	ND	ug/L	0.5	=	1.0		Qualitative analysis	
60168-88-9	FENARIMOL	ND	ug/L	0.1	0.03	1.0		Qualitative analysis	
36-34-7	MEVINPHOS	ND	ug/l	0.1	0.03	1.0		Qualitative analysis	
-50-0	AZINPHOS-METHYL	ND	ug/L	0.5	0.12	1.0		Qualitative analysis	
2921-88-2	CHLORPYRIFOS	ND	ug/L	0.1	0.04	1.0		Qualitative analysis	
115-32-2	DICOFOL	ND	ug/L	1	-	1.0		Qualitative analysis	
298-00-0	METHYL PARATHION	ND	ug/L	0.5	0.1	1.0		Qualitative analysis	
732-11-6	PHOSMET	ND	ug/L	0.5	-	1.0		Qualitative analysis	
43121-43-3	TRIADIMEFON	ND	ug/L	0.1	0.07	1.0		Qualitative analysis	
68694-11-1	TRIFLUMIZOLE	ND	ug/L	1.0	1.0	1.0		Qualitative analysis	
950-37-8	METHIDATHINON	ND	ug/L	0.5	0.5	1.0		Qualitative analysis	
88671-89-0	MYCLOBUTANIL	ND	ug/L	0.5	0.5	1.0		Qualitative analysis	
51235-04-2	HEXAZINONE	ND	ug/L	0.1	0.05	1.0		Qualitative analysis	

Result of:

NA - indicates the compound was not analyzed.

Flags are data qualifiers. If there are data qualifiers on your report definitions can be found on an accompanying sheet.

ND - indicates the compound was not detected above the PQL or MDL.

PQL = Practical Quantitation Limit is the lowest level that can be acheived within specified limits of precision and accuracy during routine laboratory operating conditions. D.F. - Dilution Factor.

Mil Crea Water Treatment Plant Ludorerory

581 Mill Creek Road

S

Walla Walla, WA 99362

Lab ID#:

143

Washington State ID:

M1873

EPAID#:

WA 01177 Telephone: (509) 522-3775

Fax: (509) 529-9681

Date:


05/28/08

ystem ID / Name:	Walla W	/alla Basin Wat	ershed Council	Amount Due:	\$66.00
Sampler:	Troy Ba	aker		Invoice Number:	8005
Address:	P.O. Bo	x 68		Date Collected:	5/27/08
City:	Milton-F	reewater		Date Analyzed:	5/27/08
State:	OR	Zip Code:	97874	Lab Analyst:	Neher

Test Methods Are Selected From The Standard Methods For Examination Of Water and Wastewater ~ 20th Edition~

Те	est Method 9223B		
Sample ID #1	Results	Units	Lab Number
L-S1	Presence	Presence / Absence	143-05637
	Total Colifo	rm Present / E-Coli Absent	_Present_X_
Sample ID #2	Results	Units	Lab Number
L-S2	Presence	Presence / Absence	143-05638
	Total Colifor	m Present / E-Coli Absent	_PresentX
Sample ID #3	Results	Units	Lab Number
HB/DC OBS-1	Presence	Presence / Absence	143-05639
	Total Colifor	m Present / E-Coli Absent_X	_Present
BETWEEN WAR TO SEE THE SECOND			
nonlinear and the second supplied the second second			
		***************************************	***************************************
HEIDERS EAREN SON THE THE SERVE SON			I STATION OF THE SAME

The City of Walla Walla's Mill Creek Water Treatment Laboratory will maintain records pertaining to reconstructing client's data for a minimum of five years from the date of issuance of the final report. Records may be destroyed after that



Signature Lab Director:

Tom Krela

5/29/08 APPROVED TO PAY

City Of Walla Walla Water Plant Laboratory 581 Mill Creek Road Walla Walla, WA 99362 From Believe CHARGE TO 1 - 7,1 - 2.2

THE REAL PROPERTY. Water Treatment Plant and the start

581 Mill Creek Road

Walla Walla, WA 99362

Lab ID#:

143

Washington State ID:

M1873

EPA ID#:

WA 01177 Telephone: (509) 522-3775

Fax: (509) 529-9681

Date:

05/28/08

system ID / Name:	Walla W	lalla Basin Wate	ershed Council	Amount Due:	\$75.00	
Sampler:	Troy Ba	aker		Invoice Number:	8005	
Address:	P.O. Bo	x 68		Date Collected:	5/27/08	
City:	Milton-F	reewater		Date Analyzed:	5/27/08	
State:	OR	Zip Code:	97874	Lab Analyst:	Neher	

Test Methods Are Selected From The Standard Methods For Examination Of Water and Wastewater ~ 20th Edition~

	Test Method 9222D		
Sample ID #1	Results	Units	Lab Number
L-S1	TNTC	CFU's / 100 mL	143-05637
Sample ID #2	Results	Units	Lab Number
L-S2	TNTC	CFU's / 100 mL	143-05638
Sample ID #3	Results	Units	Lab Number
HB/DC OBS-1	0.0	CFU's / 100 mL	143-05639
			Charles Constitution
			<u> </u>
			A SHIP CHENTE

The City of Walla Walla's Mill Creek Water Treatment Laboratory will maintain records pertaining to reconstructing client's data for a minimum of five years from the date of issuance of the final report. Records may be destroyed after that .

Signature Lab Director:

Tom Krels

5/29/08 (date)

581 Mill Creek Road Walla Walla, WA 99362

City Of Walla Walla Water Plant Laboratory



Burlington WA

1620 S Walnut St - 98233 Corporate Office 800.755.9295 • 360.757.1400 • 360.757.1402tax
Bellingham WA 805 Orchard Dr Suite 4 - 98225 360.671.0688 • 360.671.1577fax

Page 1 of 1

December 6, 2007

Walla Walla Basin Watershed Council 810 S Main Street Milton-Freewater, OR 97862

RE: 07-16056 - Replacement Sample

Dear Project Manager,

Your project: Replacement Sample, was received on Tuesday December 04, 2007.

All samples were analyzed within the accepted holding times, were appropriately preserved and were analyzed according to approved analytical protocols. The quality control data was within laboratory acceptance limits, unless specified in the QA reports.

If you have questions phone me at 800 755-9295.

Respectfully Submitted,

Lawrence J Henderson, PhD Director of Laboratories

Enclosures Data Report

QC Reports

Chain of Custody



Burlington WA Corporate Office

1620 S Walnut St - 98233

800.755.9295 • 360.757.1400 • 360.757.1402fax 805 Orchard Dr Suite 4 - 98225

Bellingham WA Microbiology

360.671.0688 • 360.671.1577fax

Page 1 of 1

Data Report

Client Name: Walla Walla Basin Watershed Council

810 S Main Street

Milton-Freewater, OR 97862

Report Date: 12/6/2007

Reference Number: 07-16056

Project: Replacement Sample

Collected By:

Date Received: 12/4/2007 Peer Review: 300

Lab Nun	nber: 36408	Sample Description	on: WWB	WC - (R15	95)			Sample	Date:	12/3/2007	
CAS ID#	Analyte	Result	PQL	MDL	Units	DF	Method	Analyzed	Analysi	Batch	Comments
14797-55-8	NITRATE-N	0.21	0.100	0.015	mg/L	1.0	300.0	12/4/2007	ВЈ	1071204A	
16887-00-6	CHLORIDE	0.8	0.1	0.0097	mg/L	1.0	300.0	12/4/2007	BJ	1071204A	
14265-44-2	ORTHO-PHOSPHATE	0.54	0.01	0.005	mg/L	1.0	SM4500-P F	12/5/2007	so	OPHOS-071205A	



Burlington WA | 1620 S Walnut St - 98233

800.755.9295 • 360.757.1400 • 360.757.1402fax Bellingham WA 805 Orchard Dr Suite 4 - 98225

Microbiology

360.671.0688 • 360.671.1577fax

Page 1 of 4



SAMPLE INDEPENDENT QUALITY CONTROL REPORT

Laboratory Fortified Blank

Reference Number: 07-16056

Report Date: 12/06/07

			True			%		QC		
Batch	Analyte	Result	Value	Units	Method	Recovery	Limits	Qualifier Type*	Comment	
OPHOS-071205A	ORTHO-PHOSPHATE	1.05	1.00	mg/L	SM4500-P F	105	70-130	LFB		-11-

covery = (Result of Analysis)/(True Value) * 100 Indicates % Recovery could not be calculated.

QCS: Quality Control Sample, a solution containing known concentrations of method analytes which is used to fortify an aliquot of reagent matrix. The QCS is obtained from an external source and is used to check lab performance.

LFB: Laboratory Fortified Blank, an aliquot of reagent matrix to which known quantities of method analytes are added in the lab. The LFB is analyzed exactly like a sample, and its purpose is to determine whether method performance is within accepted control limits.



Burlington WA | 1620 S Walnut St - 98233 800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225 360.671.0688 • 360.671.1577fax Page 2 of 4



SAMPLE INDEPENDENT QUALITY CONTROL REPORT

Laboratory Reagent Blank

Reference Number: 07-16056

Report Date: 12/06/07

			True			%	QC		
Batch	Analyte	Result	Value	Units	Method	Recovery Limits	Qualifier Type*	Comment	
I071204A	CHLORIDE	ND		mg/L	300.0	0.1000	0 LRB		
	NITRATE-N	ND		mg/L	300.0	0.1000	0		
OPHOS-071205A	ORTHO-PHOSPHATE	ND		mg/L	SM4500-P F	0.10000) LRB		

*Notation:

% Recovery = (Result of Analysis)/(True Value) * 100

NA = Indicates % Recovery could not be calculated.

QCS: Quality Control Sample, a solution containing known concentrations of method analytes which is used to fortify an aliquot of reagent matrix. The QCS is obtained from an external source and is used to check lab performance.

LFB: Laboratory Fortified Blank, an aliquot of reagent matrix to which known quantities of method analytes are added in the lab. The LFB is analyzed exactly like a sample, and its purpose is to determine whether method performance is within accepted control limits.



Burlington WA | 1620 S Walnut St - 98233

800.755.9295 • 360.757.1400 • 360.757.1402fax

Microbiology

Bellingham WA 805 Orchard Dr Suite 4 - 98225 360.671.0688 • 360.671.1577fax Page 3 of 4



SAMPLE INDEPENDENT QUALITY CONTROL REPORT

Method Blank

Reference Number: 07-16056

Report Date: 12/06/07

			True			%	QC	
Batch	Analyte	Result	Value	Units	Method	Recovery Limits	Qualifier Type*	Comment
OPHOS-071205A	ORTHO-PHOSPHATE	ŅD		mg/L	SM4500-P F	0.10000) MB	

*Notation:

Recovery = (Result of Analysis)/(True Value) * 100

\(= \text{Indicates \% Recovery could not be calculated.} \)

QCS: Quality Control Sample, a solution containing known concentrations of method analytes which is used to fortify an aliquot of reagent matrix. The QCS is obtained from an external source and is used to check lab performance.

LFB: Laboratory Fortified Blank, an aliquot of reagent matrix to which known quantities of method analytes are added in the lab. The LFB is analyzed exactly like a sample, and its purpose is to determine whether method performance is within accepted control limits.



Microbiology

Burlington WA | 1620 S Walnut St - 98233

800.755.9295 • 360.757.1400 • 360.757.1402fax Bellingham WA 805 Orchard Dr Suite 4 - 98225

360.671.0688 • 360.671.1577fax

Page 4 of 4



SAMPLE INDEPENDENT QUALITY CONTROL REPORT

Quality Control Sample

Reference Number: 07-16056

Report Date: 12/06/07

			True			%		QC	
Batch	Analyte	Result	Value	Units	Method	Recovery	Limits	Qualifier Type*	Comment
I071204A	CHLORIDE	29	30.0	mg/L	300.0	97	80-120	QCS	
	NITRATE-N	2.36	2.50	mg/L	300.0	94	80-120		
OPHOS-071205A	ORTHO-PHOSPHATE	0.48	0.48	mg/L	SM4500-P F	100	70-130	QCS	

*Notation:

% Recovery = (Result of Analysis)/(True Value) * 100

NA = Indicates % Recovery could not be calculated.

QCS: Quality Control Sample, a solution containing known concentrations of method analytes which is used to fortify an aliquot of reagent matrix. The QCS is obtained from an external source and is used to check lab performance.

LFB: Laboratory Fortified Blank, an aliquot of reagent matrix to which known quantities of method analytes are added in the lab. The LFB is analyzed exactly like a sample, and its purpose is to determine whether method performance is within accepted control limits.



Burlington WA 1620 S Wahrut St. - 98233 Corporate Office 800.755,9295 • 360.757,1400 • 360.757,1402tax Bellingham WA 805 Orchard Dr Suite 4 - 98225 Microbiology 360.671,0688 • 360.671,1577fax



Page 1 of 2

QUALITY CONTROL REPORT

Duplicate and Matrix Spike/Matrix Spike Duplicate Report

07-16056	12/6/2007
Kererence Number:	Report Date:

	IdnO	Duplicate			oc	
Batch Sample Analyte	Result Result	Ħ	Units	%RPD Limits Qualifier Comments	Qualifier	Comments
DPHOS-071205A						
36408 ORTHO-PHOSPHATE	0.54 0.54		mg/L	0.0 0-50	DUP	0

%RPD = Relative Percent Difference

NA = Indicates %RPD could not be calculated

Matrix Spike (MS)/Matrix Spike Duplicate (MSD) analyses are used to determine the accuracy (MS) and precision (MSD) of a analytical method in a given sample matrix. Therefore, the usefulness of this report is limited to samples of similar matrices analyzed in the same analytical batch.

Only Duplicate sample w" "etections are listed in this report



Matrix

, Page 2 of 2

Report Date: 12/6/2007 Reference Number: 07-16056

Spike Spike <th< th=""><th>Matrix Spike</th><th></th><th></th><th>Duplicate</th><th></th><th></th><th></th><th></th><th></th><th></th><th></th><th></th><th></th><th></th></th<>	Matrix Spike			Duplicate										
Sample Analyte Result Result Result Conc Units MSD Limits %RPD Limits Qualifier A 36408 ORTHO-PHOSPHATE 0.54 1.47 1.50 1.00 mg/L 93 96 70-130 3.2 0-50 LFM			Spike		Spike		Percen	Recovery				oc		
A 36408 ORTHO-PHOSPHATE 0.54 1.47 1.50 1.00 mg/L 93 96 70-130 3.2 0-50	Sample Analyte	Result	Result		Conc	Units	MS	MSD	Limits	%RPD	Limits	Qualifier	Comments	
0.54 1.47 1.50 1.00 mg/L 93 96 70-130 3.2 0-50	PHOS-071205A													
	36408 ORTHO-PHOSPHATE	0.54	1.47	1.50	1.00	mg/L	93	96	70-130	3.2	0-20	LFIN		

%RPL = Relative Percent Difference

NA = Indicates %RPD could not be calculated

Matrix Spike Duplicate (MSD) analyses are used to determine the accuracy (MS) and precision (MSD) of a analytical method in a given sample matrix. Therefore, the usefulness of this report is limited to samples of similar matrices analyzed in the same analytical batch.

Only Duplicate governe with detections are listed in this report



Burlington WA | 1620 S Walnut St - 98233

800 755 9295 • 360 757 1400 • 360 757 1402fax

Bellingham WA | 805 Orchard Dr Suite 4 | 98225 Microbiology 360.671.0688 • 360.671.1577fax

Page 1 of 1

CARBAMATES IN DRINKING WATER

Client Name: Walla Walla Basin Watershed Council

810 S Main Street

Milton-Freewater, OR 97862

Reference Number: 07-15764

Project: HBDIC Recharge Project

Field ID: Observation well #1

Sample Description: @HBDIC Recharge

Sampled By:

Sample Date: 11/26/2007

Source Type: Sampler Phone:

Lab Number: 04635782 Report Date: 11/29/2007 Date Analyzed: 11/28/2007 Extraction Date: 531_071128

Analyst: CO Peer Review: WK Analytical Method: 531.2

Carbamates

CAS	COMPOUND		RESULTS	Units	PQL	MDL	MCL	COMMENT
	EPA Regulated							
23135-22-0	OXYMAL		ND	ug/L	1.0	0.81	200	
1563-66-2	CARBOFURAN		ND	ug/L	1.0	0.87	40	
	EPA Unregulated							
1646-87-3	ALDICARB SULFOXIDE		ND	ug/L	1.0	0.71		
646-88-4	ALDICARB SULFONE	- 27	ND	ug/L	1.0	0.83		
16752-77-5	METHOMYL		ND .	ug/L	1.0	0.86		
16655-82-6	3-HYDROXYCARBOFURAN		ND	ug/L	1.0	1.0		
116-06-3	ALDICARB		ND	ug/L	1.0	0.88		
63-25-2	CARBARYL		ND	ug/L	1.0	0.53		
	State Unregulated - Other							
114-26-1	PROPOXUR (BAYGON)		ND	ug/L	1.0	0.72		
2032-65-7	METHIOCARB		ND	ug/L	1.0	0.76		

4ot detected above the listed practical quantitation limit (PQL) or not above the Method Detection Limit (MDL), if requested.

Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds.

A blank MCL or SAL value indicates a level is not currently established.

PQL - Practical Quantitation Limit is the concentration of the standard analyzed during the initial calibration.

MDL - Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.

J - Estimated value



Burlington WA | 1620 S Walnut St - 98233

800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225

360.671.0688 • 360.671.1577fax

Page 1 of 1

DATA REPORT

Client Name: Walla Walla Basin Watershed Council

810 S Main Street

Milton-Freewater, OR 97862

Reference Number: 07-15764

Project: HBDIC Recharge Project

Field ID: Observation well #1

Sample Description: @HBDIC Recharge

Sampled By:

Sample Date: 11/26/2007

Source Type: Sampler Phone:

Lab Number: 04635782 Report Date: 12/14/2007 Date Analyzed: 12/13/2007 Extraction Date: 508_071207

Analyst: MM/C0 Peer Review: MVA Analytical Method: 508.1

Synthetic Organics

	CAS	COMPOUND	RESULTS	Units	PQL	MDL	MCL	COMMENT
_		PCBs/Toxaphene					- 1	
	1336-36-3	PCBS (Total Aroclors)	ND	ug/L	0.2		0.5	
	11104-28-2	AROCLOR 1221	ND	ug/L	0.1	0.1^		
	11141-16-5	AROCLOR 1232	ND	ug/L	0.1	0.1^		
	53469-21-9	AROCLOR 1242	ND	ug/L	0.1	0.1^		
1	12672-29-6	AROCLOR 1248	ND	ug/L	0.1	0.1^		
	11097-69-1	AROCLOR 1254	ND	ug/L	0.1	0.1^		
	11096-82-5	AROCLOR 1260	ND	ug/L	0.1	0.08		
	12674-11-2	AROCLOR 1016	ND	ug/L	0.1	0.1		
	8001-35-2	TOXAPHENE	ND	ug/L	1	0.5	3	

⁼ Not detected above the listed practical quantitation limit (PQL) or not above the Method Detection Limit (MDL), if requested

MCL- Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds.

A blank MCL or SAL value indicates a level is not currently established.

PQL - Practical Quantitation Limit is the concentration of the standard analyzed during the initial calibration.

MDL - Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.



Burlington WA | 1620 S Walnut St - 98233 Corporate Office

800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225 360.671.0688 • 360.671.1577fax

Page 1 of 2

SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

Client Name: Walla Walla Basin Watershed Council

810 S Main Street

Milton-Freewater, OR 97862

Reference Number: 07-15764

Project: HBDIC Recharge Project

Field ID: Observation well #1

Sample Description: @HBDIC Recharge

Sampled By:

Sample Date: 11/26/2007

Source Type: Sampler Phone:

Lab Number: 04635782 Report Date: 12/13/2007 Date Analyzed: 12/10/2007 Extraction Date: 525_071207

Analyst: MM/C(Peer Review: MVA Analytical Method: 525.2

Synthetic Organics

CAS	COMPOUND	RESULTS	Units	PQL	MDL	MCL	COMMENT
	EPA Regulated						
72-20-8	ENDRIN	ND	ug/L	0.1	0.030	2	
58-89-9	LINDANE (BHC - GAMMA)	ND	ug/L	0.1	0.028	0.2	
72-43-5	METHOXYCHLOR	ND	ug/L	0.1	0.015	40	
15972-60-8	ALACHLOR	ND	ug/L	0.1	0.044	2	
1912-24-9	ATRAZINE	ND	ug/L	0.1	0.030	3	
50-32-8	BENZO(A)PYRENE	ND	ug/L	0.1	0.012	0.2	
57-74-9	CHLORDANE, TECHNICAL	ND	ug/L	0.1	0.3	2	
103-23-1	DI(ETHYLHEXYL)-ADIPATE	ND	ug/L	0.1	0.022	400	
117-81-7	DI(ETHYLHEXYL)-PHTHALATE	ND	ug/L	0.1	0.063	6	
76-44-8	HEPTACHLOR	ND	ug/L	0.1	0.022	0.4	
1024-57-3	HEPTACHLOR EPOXIDE	ND	ug/L	0.1	0.02	0.2	
118-74-1	HEXACHLOROBENZENE	ND	ug/L	0.1	0.025	1	
77-47-4	HEXACHLOROCYCLO-PENTADIENE	ND	ug/L	0.1	0.024	50	
122-34-9	SIMAZINE	ND	ug/L	0.1	0.030	4	
87-86-5	PENTACHLOROPHENOL	ND	ug/L	0.4	0.08	1	screening only / compliance by 515
	EPA Unregulated						
309-00-2 .	ALDRIN	ND	ug/L	0.1	0.022	7	
23184-66-9	BUTACHLOR	ND	ug/L	0.1	0.024		
60-57-1	DIELDRIN	ND	ug/L	0.1	0.031		
51218-45-2	METOLACHLOR	ND	ug/L	0.1	0.024		
21087-64-9	METRIBUZIN	ND	ug/L	0.1	0.030		
1918-16-7	PROPACHLOR	ND	ug/L	0.1	0.031		
	State Unregulated - Other						
314-40-9	BROMACIL	ND	ug/L	0.1	0.031		
5902-51-2	TERBACIL	ND	ug/L	0.1	0.043		

ND = Not detected above the listed practical quantitation limit (PQL) or not above the Method Detection Limit (MDL), if requested.

MCL- Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds.

A blank MCL or SAL value indicates a level is not currently established.

PQL - Practical Quantitation Limit is the concentration of the standard analyzed during the initial calibration.

MDL - Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.

J - Estimated value



Reference Number: 07-15764 Page 2 of 2

Lab Number: 04635782 Report Date: 12/13/2007

SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

CAS	COMPOUND	RESULTS	Units	PQL	MDL	MCL	COMMENT
333-41-5	DIAZINON	ND	ug/L	0.1	0.035		Unstable in Acidified Sample Matri
759-94-4	EPTC	ND	ug/L	0.1	0.028		
72-54-8	4,4-DDD	ND	ug/L	0.1	0.024		
72-55-9	4,4-DDE	ND	ug/L	0.1	0.024		
50-29-3	4,4-DDT	ND	ug/L	0.1	0.022		
21725-46-2	CYANAZINE	ND	ug/L	0.1	0.13		Qualitative Analysis Only
121-75-5	MALATHION	ND	ug/L	0.1	0.015		
56-38-2	PARATHION	ND	ug/L	0.1	0.022		
1582-09-8	TRIFLURALIN	ND	ug/L	0.1	0.024		
	- PAHs						
91-20-3	NAPTHALENE	ND	ug/L	0.1	0.1^		
86-73-7	FLUORENE	ND	ug/L	0.1	0.026		
208-96-8	ACENAPHTHYLENE	ND	ug/L	0.1	0.025		
83-32-9	ACENAPHTHENE	ND	ug/L	0.1	0.1^		
120-12-7	ANTHRACENE	ND	ug/L	0.1	0.012		
56-55-3	BENZ(A)ANTHRACENE	ND	ug/L	0.1	0.012		
205-99-2	BENZO(B)FLUORANTHENE	ND	ug/L	0.1	0.025		
191-24-2	BENZO(G,H,I)PERYLENE	ND	ug/L	0.1	0.025		
207-08-9	BENZO(K)FLUORANTHENE	ND	ug/L	0.1	0.022		
218-01-9	CHRYSENE	ND	ug/L	0.1	0.022		
53-70-3	DIBENZO(A,H)ANTHRACENE	ND	ug/L	0.1	0.024		
206-44-0	FLUORANTHENE	ND	ug/L	0.1	0.1^		
193-39-5	INDENO(1,2,3-CD)PYRENE	ND	ug/L	0.1	0.040		
85-01-8	PHENANTHRENE	ND	ug/L	0.1	0.015		
129-00-0	PYRENE	ND	ug/L	0.1	0.022		
	- Phthalates						
85-68-7	BENZYL BUTYL PHTHALATE	ND	ug/L	0.1	0.022		
84-74-2	DI-N-BUTYL PHTHALATE	ND	ug/L	0.1	0.085		
84-66-2	DIETHYL PHTHALATE	ND	ug/L	0.1	0.044		
131-11-3	DIMETHYL PHTHALATE	ND	ug/L	0.1	0.015		

⁻ Not detected above the listed practical quantitation limit (PQL) or not above the Method Detection Limit (MDL), if requested.

MCL- Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds. A blank MCL or SAL value indicates a level is not currently established.

PQL - Practical Quantitation Limit is the concentration of the standard analyzed during the initial calibration.

MDL - Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.



Burlington WA | 1620 S Walnut St - 98233

Corporate Office 800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225 360.671.0688 • 360.671.1577fax

Page 1 of 1

HERBICIDES IN DRINKING WATER

Client Name: Walla Walla Basin Watershed Council

810 S Main Street

Milton-Freewater, OR 97862

Reference Number: 07-15764

Project: HBDIC Recharge Project

Field ID: Observation well #1

Sample Description: @HBDIC Recharge

Sampled By:

Sample Date: 11/26/2007

Source Type: Sampler Phone: Lab Number: 04635782 Report Date: 12/14/2007 Date Analyzed: 12/13/2007 Extraction Date: 515_071210

Analyst: JH/CO
Peer Review: MV Å
Analytical Method: 515.1

Chlorophenoxy Herbicides

CAS	COMPOUND	RESULTS	Units	PQL	MDL	MCL	COMMENT
	EPA Regulated						
94-75-7	2,4 - D	ND	ug/L	0.2	0.11	70	
93-72-1	2,4,5 - TP (SILVEX)	ND	ug/L	0.1	0.02	50	
87-86-5	PENTACHLOROPHENOL	ND	ug/L	0.1	0.044	1	
75-99-0	DALAPON	ND	ug/L	1.3	0.80	200	
88-85-7	DINOSEB	ND	ug/L	0.2	0.16	7	
1918-02-1	PICLORAM	ND	ug/L	0.1	0.089	500	
	EPA Unregulated						
1918-00-9	DICAMBA	ND	ug/L	0.1	0.045		
	State Unregulated						
1861-32-1	TOTAL (DCPA & Metabolites)	ND	ug/L	0.1	0.089		
E-14-02-8	DCPA (ACID METABOLITES)	ND	ug/L	0.1	0.1		
94-82-6	2,4 DB	ND	ug/Ĺ	0.8	0.10		
93-76-5	2,4,5 T	ND	ug/L	0.1	0.044		
25057-89-0	BENTAZON	ND	ug/L	0.2	0.067		
120-36-5	DICHLORPROP	ND	ug/L	0.3	0.089		
50594-66-6	ACIFLUORFEN	ND	ug/L	0.1	0.089		
133-90-4	CHLORAMBEN	ND	ug/L	0.2	0.2		
51-36-5	3.5 - DICHLOROBENZOIC ACID	ND	ug/L	0.1	0.044		

A blank MCL or SAL value indicates a level is not currently established.

PQL - Practical Quantitation Limit is the concentration of the standard analyzed during the initial calibration.

J - Estimated value.

Not detected above the listed practical quantitation limit (PQL) or not above the Method Detection Limit (MDL), if requested.

MCL- Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds.

MDL - Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.



Burlington WA Corporate Office | 1620 S Walnut St - 98233 | 800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225 360.671.0688 • 360.671.1577fax

Page 1 of 1

CARBAMATES IN DRINKING WATER

Client Name: Walla Walla Basin Watershed Council

810 S Main Street

Milton-Freewater, OR 97862

Reference Number: 07-15764

Lab Number: 04635783

Report Date: 11/29/2007 Date Analyzed: 11/28/2007

Project: HBDIC Recharge Project

Field ID: Intake

Sample Description: @HBDIC Recharge

Sampled By:

Sample Date: 11/26/2007

Source Type: Sampler Phone: Extraction Date: 531_071128

Analyst: CO Peer Review: NX X Analytical Method: 531.2

Carbamates

	CAS	COMPOUND	RESULTS	Units	PQL	MDL	MCL	COMMENT
_		EPA Regulated						
	23135-22-0	OXYMAL	ND	ug/L	1.0	0.81	200	
	1563-66-2	CARBOFURAN	ND	ug/L	1.0	0.87	40	
		EPA Unregulated						
	1646-87-3	ALDICARB SULFOXIDE	ND	ug/L	1.0	0.71		
1	1646-88-4	ALDICARB SULFONE	ND	ug/L	1.0	0.83		
	16752-77-5	METHOMYL	ND	ug/L	1.0	0.86		
	16655-82-6	3-HYDROXYCARBOFURAN	ND	ug/L	1.0	1.0		
	116-06-3	ALDICARB	ND	ug/L	1.0	0.88		
	63-25-2	CARBARYL	ND	ug/L	1.0	0.53		
		State Unregulated - Other						
	114-26-1	PROPOXUR (BAYGON)	ND	ug/L	1.0	0.72		
	2032-65-7	METHIOCARB	ND	ug/L	1.0	0.76		

J - Estimated value

⁼ Not detected above the listed practical quantitation limit (PQL) or not above the Method Detection Limit (MDL), if requested.

CL- Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds. A blank MCL or SAL value indicates a level is not currently established.

PQL - Practical Quantitation Limit is the concentration of the standard analyzed during the initial calibration.

MDL - Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.



Corporate Office 800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225 Microbiology 360.671.0688 • 360.671.1577fax

Page 1 of 1

DATA REPORT

Client Name: Walla Walla Basin Watershed Council

810 S Main Street

Milton-Freewater, OR 97862

Reference Number: 07-15764

Project: HBDIC Recharge Project

Field ID: Intake

Sample Description: @HBDIC Recharge

Sampled By:

Sample Date: 11/26/2007

Source Type: Sampler Phone:

Lab Number: 04635783 Report Date: 12/14/2007 Date Analyzed: 12/13/2007 Extraction Date: 508_071207

Analyst: MM/C(Peer Review: MVA

Analytical Method: 508.1

Synthetic Organics

-	CAS	COMPOUND	RESULTS	Units	PQL	MDL	MCL	COMMENT
		PCBs/Toxaphene						
	1336-36-3	PCBS (Total Aroclors)	ND	ug/L	0.2		0.5	
	11104-28-2	AROCLOR 1221	ND	ug/L	0.1	0.1^		
	11141-16-5	AROCLOR 1232	ND	ug/L	0.1	0.1^		
	53469-21-9	AROCLOR 1242	ND	ug/L	0.1	0.1^		
1	12672-29-6	AROCLOR 1248	ND	ug/L	0.1	0.1^		
	11097-69-1	AROCLOR 1254	ND	ug/L	0.1	0.1^		
	11096-82-5	AROCLOR 1260	ND	ug/L	0.1	0.08		
	12674-11-2	AROCLOR 1016	ND	ug/L	0.1	0.1		
	8001-35-2	TOXAPHENE	ND	ug/L	1	0.5	3	

⁼ Not detected above the listed practical quantitation limit (PQL) or not above the Method Detection Limit (MDL), if requested.

MCL- Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds.

A blank MCL or SAL value indicates a level is not currently established.

PQL - Practical Quantitation Limit is the concentration of the standard analyzed during the initial calibration.

MDL - Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero. J - Estimated value.



Corporate Office 800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225 Microbiology 360.671.0688 • 360.671.1577fax

Page 1 of 2

SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

Client Name: Walla Walla Basin Watershed Council

810 S Main Street

Milton-Freewater, OR 97862

Reference Number: 07-15764

Project: HBDIC Recharge Project

Field ID: Intake

Sample Description: @HBDIC Recharge

Sampled By:

Sample Date: 11/26/2007

Source Type: Sampler Phone:

Lab Number: 04635783 Report Date: 12/13/2007 Date Analyzed: 12/10/2007 Extraction Date: 525_071207 Analyst: MM/C(

Peer Review: MVA Analytical Method: 525.2

Synthetic Organics

							ejiiaioao eigainoo
CAS	COMPOUND	RESULTS	Units	PQL	MDL	MCL	COMMENT
	EPA Regulated						
72-20-8	ENDRIN	ND	ug/L	0.1	0.030	2	
58-89-9	LINDANE (BHC - GAMMA)	ND	ug/L	0.1	0.028	0.2	
72-43-5	METHOXYCHLOR	ND	ug/L	0.1	0.015	40	
15972-60-8	ALACHLOR	ND	ug/L	0.1	0.044	2	
1912-24-9	ATRAZINE	ND	ug/L	0.1	0.030	3	
50-32-8	BENZO(A)PYRENE	ND	ug/L	0.1	0.012	0.2	
57-74-9	CHLORDANE, TECHNICAL	ND	ug/L	0.1	0.3	2	
103-23-1	DI(ETHYLHEXYL)-ADIPATE	ND	ug/L	0.1	0.022	400	
117-81-7	DI(ETHYLHEXYL)-PHTHALATE	ND	ug/L	0.1	0.063	6	
76-44-8	HEPTACHLOR	ND	ug/L	0.1	0.022	0.4	
1024-57-3	HEPTACHLOR EPOXIDE	ND	ug/L	0.1	0.02	0.2	
118-74-1	HEXACHLOROBENZENE	ND	ug/L	0.1	0.025	1	
77-47-4	HEXACHLOROCYCLO-PENTADIENE	ND	ug/L	0.1	0.024	50	
122-34-9	SIMAZINE	ND	ug/L	0.1	0.030	4	
87-86-5	PENTACHLOROPHENOL	ND	ug/L	0.4	0.08	1	screening only / compliance by 515.
	EPA Unregulated						
309-00-2	ALDRIN	ND	ug/L	0.1	0.022		
23184-66-9	BUTACHLOR	ND	ug/L	0.1	0.024		
60-57-1	DIELDRIN	ND	ug/L	0.1	0.031		
51218-45-2	METOLACHLOR	ND	ug/L	0.1	0.024		
21087-64-9	METRIBUZIN	ND	ug/L	0.1	0.030		
1918-16-7	PROPACHLOR	ND	ug/L	0.1	0.031		
	State Unregulated - Other						
314-40-9	BROMACIL	ND	ug/L	0.1	0.031		
5902-51-2	TERBACIL	ND	ug/L	0.1	0.043		
			10000000				

⁼ Not detected above the listed practical quantitation limit (PQL) or not above the Method Detection Limit (MDL), if requested

J - Estimated value

MCL- Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds A blank MCL or SAL value indicates a level is not currently established.

PQL - Practical Quantitation Limit is the concentration of the standard analyzed during the initial calibration.

MDL - Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.



3

Reference Number: 07-15764 Page 2 of 2

Lab Number: 04635783 Report Date: 12/13/2007

SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

CAS	COMPOUND	RESULTS	Units	PQL	MDL	MCL	COMMENT
333-41-5	DIAZINON	ND	ug/L	0.1	0.035		Unstable in Acidified Sample Matr
759-94-4	EPTC	ND	ug/L	0.1	0.028		The same of the sample was
72-54-8	4,4-DDD	ND	ug/L	0.1	0.024		
72-55-9	4,4-DDE	ND	ug/L	0.1	0.024		
50-29-3	4,4-DDT	ND	ug/L	0.1	0.022		
21725-46-2	CYANAZINE	ND	ug/L	0.1	0.13		Qualitative Analysis Only
121-75-5	MALATHION	ND	ug/L	0.1	0.015		and that you only
56-38-2	PARATHION	ND	ug/L	0.1	0.022		
1582-09-8	TRIFLURALIN	ND	ug/L	0.1	0.024		
	- PAHs						
91-20-3	NAPTHALENE	ND	ug/L	0.1	0.1^		
86-73-7	FLUORENE	ND	ug/L	0.1	0.026		
208-96-8	ACENAPHTHYLENE	ND	ug/L	0.1	0.025		
83-32-9	ACENAPHTHENE	ND	ug/L	0.1	0.1^		
120-12-7	ANTHRACENE	ND	ug/L	0.1	0.012		
56-55-3	BENZ(A)ANTHRACENE	ND	ug/L	0.1	0.012		
205-99-2	BENZO(B)FLUORANTHENE	ND	ug/L	0.1	0.025		
191-24-2	BENZO(G,H,I)PERYLENE	ND	ug/L	0.1	0.025		
207-08-9	BENZO(K)FLUORANTHENE	ND	ug/L	0.1	0.022		
218-01-9	CHRYSENE	ND	ug/L	0.1	0.022		
53-70-3	DIBENZO(A,H)ANTHRACENE	ND	ug/L	0.1	0.024		
206-44-0	FLUORANTHENE	ND	ug/L	0.1	0.1^		
193-39-5	INDENO(1,2,3-CD)PYRENE	ND	ug/L	0.1	0.040		
85-01-8	PHENANTHRENE	ND	ug/L	0.1	0.015		
129-00-0	PYRENE	ND	ug/L	0.1	0.022		
	- Phthalates				0.022		
85-68-7 E	BENZYL BUTYL PHTHALATE	ND	ug/L	0.1	0.022		
84-74-2	DI-N-BUTYL PHTHALATE	ND	ug/L	0.1	0.022		
84-66-2	DIETHYL PHTHALATE	ND	ug/L	0.1	0.044		
131-11-3	DIMETHYL PHTHALATE	9870	-5'-	J. 1	0.044		

ND = Not detected above the listed practical quantitation limit (PQL) or not above the Method Detection Limit (MDL): if requested

⁻ Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds. A blank MCL or SAL value indicates a level is not currently established.

PQL - Practical Quantitation Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.



Corporate Office 800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225 360.671.0688 • 360.671.1577fax Microbiology

Page 1 of 1

HERBICIDES IN DRINKING WATER

Client Name: Walla Walla Basin Watershed Council

810 S Main Street

Milton-Freewater, OR 97862

Reference Number: 07-15764

Lab Number: 04635783

Report Date: 12/14/2007

Date Analyzed: 12/13/2007

Project: HBDIC Recharge Project

Field ID: Intake

Sample Description: @HBDIC Recharge

Sampled By:

Sample Date: 11/26/2007

Source Type: Sampler Phone:

Extraction Date: 515_071210 Analyst: JH/CO Peer Review: MVA

Analytical Method: 515.1

Chlorophenoxy Herbicides

CAS	COMPOUND	RESULTS	Units	PQL	MDL	MCL	COMMENT
	EPA Regulated						
94-75-7	2,4 - D	ND	ug/L	0.2	0.11	70	
93-72-1	2,4,5 - TP (SILVEX)	ND	ug/L	0.1	0.02	50	
87-86-5	PENTACHLOROPHENOL	ND	ug/L	0.1	0.044	. 1	
75-99-0	DALAPON	ND	ug/L	1.3	0.80	200	
88-85-7	DINOSEB	ND	ug/L	0.2	0.16	7	
1918-02-1	PICLORAM	ND	ug/L	0.1	0.089	500	
	EPA Unregulated						
1918-00-9	DICAMBA	ND	ug/L	0.1	0.045		
	State Unregulated						
1861-32-1	TOTAL (DCPA & Metabolites)	ND	ug/L	0.1	0.089		
E-14-02-8	DCPA (ACID METABOLITES)	ND	ug/L	0.1	0.1		
94-82-6	2,4 DB	ND	ug/L	8.0	0.10		
93-76-5	2,4,5 T	ND	ug/L	0.1	0.044		
25057-89-0	BENTAZON	ND	ug/L	0.2	0.067		
120-36-5	DICHLORPROP	ND	ug/L	0.3	0.089		
50594-66-6	ACIFLUORFEN	ND	ug/L	0.1	0.089		
133-90-4	CHLORAMBEN	ND ·	ug/L	0.2	0.2		
51-36-5	3,5 - DICHLOROBENZOIC ACID	ND	ug/L	0.1	0.044		

J - Estimated value

Not detected above the listed practical quantitation limit (PQL) or not above the Method Detection Limit (MDL), if requested,

⁻ Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds.

A blank MCL or SAL value indicates a level is not currently established.

PQL - Practical Quantitation Limit is the concentration of the standard analyzed during the initial calibration.

MDL - Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.

Full 2007 HBOIC WG

11 21 2007 Lewis ND ND ND ND ND ND ND ND ND ND ND ND ND	11 11 12 12 13 13 14 15 15 15 15 15 15 15		18,				Total		Nitrate-					Feeal Coliforms	EPA 525 SOC Package Feeal Califorms (EPA databang tester	
11/26/2007 9:15 11/27/2007 Befeet/Lewis ND ND X 77.6 73 X 11/140 ND Decedions 11/26/2007 9:00 12/4/2007 Befeet/Lewis ND ND ND 79:9 68 0.7 0:57 (deplicate) No Decedions 12/3/2007 9:00 12/4/2007 Lewis 0.21 0.21 0.21 0.24 (deplicate) No Decedions 0.24 (deplicate) NO Decedions 0.24 (deplicate) NO Decedions 0.24 (deplicate) NO Decedions 0.24 (deplicate) NO Decedions 0.24 (deplicate) NO Decedions 0.24 (deplicate) NO Decedions 0.24 (deplicate) NO Decedions 0.24 (deplicate) NO Decedions 0.24 (deplicate) NO Decedions 0.24 (deplicate) NO Decedions 0.24 (deplicate) NO Decedions 0.24 (deplicate) NO Decedions 0.24 (deplicate) NO Decedions 0.24 (deplicate) NO Decedions 0.24 (deplicate) NO Decedions 0.	11/26/2007 9:15 11/27/2007 Befeet/Lewis ND ND X 77.6 73 X 11/140 11/26/2007 9:00 11/27/2007 Bovec/Lewis ND ND ND ND 79:9 68 0:7 0:57 (daplicate) No Descritors 12/3/2007 9:00 12/4/2007 Lewis 0.21 0.21 0.28 0.54	roject	Date Collected	Time	Date Received	Who	Nitrogen	COD	z	Conductivity	SQL	Chloride	Orthophosphate	(CFUs)	525, 515,508, 531)	Comments Bottle mix up orginally marked OBS 1 as Intake
11/26/2007 9:30 11/21/2007 Bower(Lewis ND ND ND 79.9 68 0.7 0.57 (displicate) No Detections 12/3/2007 9:00 12/4/2007 Lewis 0.21 0.21 0.21 0.8 0.54 (displicate) No Detections 0.21 0.21 0.21 0.21 0.21 0.21 0.21 0.21	11/26/2007 9:00 11/21/2007 Bower/Lewis ND ND ND 79.9 68 0.7 0.57 (duplicate) No Detections 12/4/2007 9:00 12/4/2007 Lewis 0.21 (duplicate) No Detections 0.8 0.54 (duplicate) No Detections 0.8	O u C	11/26/2007	9:15	11/27/2007	Bower/Lewis	2	2	×	9.77	73	×	34:	11/140	No Detections	Edge, Missing bottes mean missing some La Resampled the next week
12/3/2007 3-00 12/4/2007 Lewis 0.21 0.8 0.54 HBOLL	12/3/2007 3-00 12/4/2007 Lewis 0.21 0.8 0.54 HBOLL HBOLL HBOLL HBOLL HBOLL	y u 0	11/26/2007	9:30		Bower/Lewis	2	2	2	79.9	89	0.7	0.57	(duplicate)	No Detections	ж
7 3	7 3	nos.	12/3/2007	9:00	12/4/2007	Lewis			0.21			8.0	0.54			Quality Control Lab report included in app
	77								9	(3	I 3	3	3 = 3			



Corporate Office

Burlington WA | 1620 S Walnut St - 98233

800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225 360.671.0688 • 360.671.1577fax

Page 1 of 1

Data Report

Client Name: Walla Walla Basin Watershed Council

810 S Main Street

Milton-Freewater, OR 97862

Report Date: 12/14/2007

Reference Number: 07-15764

Project: HBDIC Recharge Project

Collected By:

Date Received: 11/27/2007

Peer Review:

Lab Nur	mber: 35782 San	ple Descripti	on: Obser	vation well	#1 - @HE	BDIC I	Recharge	Sample	Date:	11/26/2007	,
CAS ID#	Analyte	Result	PQL	MDL	Units	DF	Method	Analyzed	Analys	t Batch	Comments
E-10264	TOTAL KJELDAHL NITROGEN	ND	0.5	0.1391	mg/L	1.0	SM4500-Norg C	12/4/2007	so	TKN-071204	
E-10117	CHEMICAL OXYGEN DEMAND	ND	8.0	1.00	mg/L	1.0	SM5220 D	12/4/2007	MAK	COD_071204	
E-10184	ELECTRICAL CONDUCTIVITY	77.6	10	10	uS/cm	1.0	SM2510 B	11/30/2007		EC 071130	
E-10173	TOTAL DISSOLVED SOLIDS	73	10	10	mg/L	1.0	SM2540 C	11/30/2007	CCN	TDS 071130	

Lab Nun	nber: 35783 Sam	ple Descripti	on: Intake	- @HBDIC	C Recharg	е		Sample	Date:	11/26/2007	K.
CAS ID#	Analyte	Result	PQL	MDL	Units	DF	Method	Analyzed	Analyst	Batch	Comments
E-10264	TOTAL KJELDAHL NITROGEN	ND	0.5	0.1391	mg/L	1.0	SM4500-Norg C	12/4/2007	so	TKN-071204	
E-1011	CHEMICAL OXYGEN DEMAND	ND	8.0	1.00	mg/L	1.0	SM5220 D	12/4/2007		COD 071204	
14797-55-8	NITRATE-N	ND	0.100	0.015	mg/L	1.0	300.0	11/27/2007		1071127A	
16887-00-6	CHLORIDE	0.7	0.1	0.0097	mg/L	1.0	300.0	11/27/2007		1071127A	
E-10184	ELECTRICAL CONDUCTIVITY	79.9	10	10	uS/cm	1.0	SM2510 B	11/28/2007		EC 071128	
E-10173	TOTAL DISSOLVED SOLIDS	68	10	10	mg/L	1.0	SM2540 C	11/30/2007		TDS 071130	
14265-44-2	ORTHO-PHOSPHATE	0.57	0.01	0.005	ma/l	1.0	SM4500-P F	11/20/2007	ATTACK S	000000000000000000000000000000000000000	

548.2 Endothall 547 Glyphosate 549 Diquat LOMB 2 List 1 (EDA 597, 500) LOMB 2 List 2 (EPA 525.2, 535, 521) Nitrosamines (521) for DSMRT Questions for State Regulations

Questions regarding drinking water regulations, system monitoring requirements, and sampling information as to location, source type or method should be directed to.

Instructions

\$130

\$118 \$141

\$575 \$865 \$300 Nitrate

Chloride

Arsenic

SW Regional Office – Belle Fuchs (360) 586-5179 NW Regional Office – Steve Hulsman (253) 395-6750

\$18

\$18

\$18

\$22 #35 \$289

0 0

Lead and Copper Rule (Special Sampling)
Total Organic Garbon (100)
Complete Inorganics

IO

əd

əţŧ Ву uo IL SC.



Burlington WA Corporate Office Bellingham WA 1620 S. Walnut St. - 98233 800.755.9295 • 360.757.1400 • 360.757.1402fax

805 Orchard Dr Suite 4 - 98225 360.715-1212 360.671.1577fax Water Sample Information (WSI) Inorganic & Organic Chemical Analysis

ent & Billing Information	
Report To: Bob Bower	Bill To: Walla Walla Basin Watershed Council
Ship Address: 810 S Main Street	Address: 810 S Main Street
	City: Milton-Freewater St: OR Zip: 97862
Table 20172	Phone:
Phone: 541.938-2170 Fax:	
Email: bob.bower@wwwbwc.org	P.O.#
Contact: Bob Bower	VISA WIFE EXPINE
Project	Card #
General Sampling Information	
1. Date Collected: 11012 Time Collected: 9:3	S-9:50 K AM PM
2. Collected By: W Lewis	Telephone: 541 43 8 21 70
3. Specific Location: INTAKE STOCKET	c c 11.010 tab = 1.010E t
Public Water System (Fill out Form Completely)	
4. System ID Number:	
5. DOH Source Number:	Check here if this a New Source.
(If sample is blended form more than one source, list all.)	Office in this a vew obtained.
6. Group: A B	
7. System Name:	
8. Source Type: Surface Well/Ground Water	Well Field Spring Purchased
9. County: Umafilla	(Deplete will be contained and the State)
	ations for Public Water Systems. (Resluts will be sent to you and the State.)
11. Sample taken: Before Treatment After Treatm	ment No Treatment In Distribution
12. Utility's Name for this source:	
13. Treatment Type: None Aeration Filration	Chlorination Fluoridation Softener Other
14. COMPOSITE INFORMATION (Applies to Multiple Sources Only) If	sample is to be composited in lab, list all sources.
If you want the lab to composite samples from your system INITIAL	
1. 2. 3.	4. 5. 6.
15. Remarks:	
	STATE OF THE SAME
Analysis To Perform (Please Check Box) Frequently requested	d tests are listed below. For others, please list under Other Analysis.
_ CCC donage (class) company	Snohomish County Building Permit \$157 Radium 228 \$90
	Whatcom County Building Permit \$157 ☐ Gross Alpha & Beta \$95 Skagit County Building Permit \$157 ☐ EWS Well Report \$21
	sland County Building Permit \$44
	San Juan County Building Permit \$93
☐ 504.1 EDB, DBCP/1,2,3-TCP \$105 ☐ K	King County Building Permit \$34
☐ 552.2 Haloacetic Acids \$140 ☐ D	Discounted Nuisance Test \$18
T 524.2 Tribalomethanes (THM) \$81 (0	Only with Snohomish, Whatcom, Skagit or San Juan Bldg. Permit)
☐ 510 1 Maximum Total Trihalomethanes Potential \$125 ☐ N	Nuisance Test (Hardness, Iron, Manganese, pH) \$44
□ 548.2 Endothall \$130 □ N	vitrate \$18
☐ 547 Glyphosate \$118 ☐ C	Chloride \$18
☐ 549 Diquat \$141 ☐ A	Arsenic \$18
☐ UCMR 2 List 1(EPA 527, 529) \$575 ☐ ☐	ead and Copper Rule (Special Sampling) \$22
□ LICMR 2 List 2 (EPA 525 2 535 521) \$865 □ □	Total Organic Carbon (TOC) \$38
□ Nitrosamines (521) for DSMRT \$300 □ □	Complete Inorganics \$289 CO002680

Questions for State Regulations

Questions regarding drinking water regulations, system monitoring requirements, and sampling information as to location, source type or method should be directed to:

SW Regional Office – Belle Fuchs (360) 586-5179 NW Regional Office – Steve Hulsman (253) 395-6750 Eastern Regional Office – Anita Waterman (509) 456-2475



Burlington WA
Corporate Office
Bellingham WA

| 1620 S. Walnut St. - 98233 | 800.755.9295 • 360.757.1400 • 360.757.1402fax

805 Orchard Dr Suite 4 - 98225 360.715-1212• 360.671.1577fax Water Sample Information (WSI) Inorganic & Organic Chemical Analysis

ent & Billing Information	Bill To: Walla Walla Basin Watershed Council
Report To: Bob Bower	
Ship Address: 810 S Main Street	Address: 810 S Main Street
City: Milton-Freewater St: OR Zip: 97862	City: Milton-Freewater St: OR Zip: 97862
Phone: 541.938-2170 Fax:	Phone:
Email: bob.bower@wwwbwc.org	P.O.#
Contact: Bob Bower	Visa M/C A/E Expires /
Project	Card #
General Sampling Information	
1. Date Collected: (1/27/7 Time Collected: 9:15	
2. Collected By: W Lewis	Telephone: 5414392170
3. Specific Location: OBSERVATION WELL	- #1 @ HBDIC Necharge Project
Public Water System (Fill out Form Completely)	
4. System ID Number:	
5. DOH Source Number:	
	Check here if this a New Source.
(If sample is blended form more than one source, list all.)	
6. Group: A B	
7. System Name: HBDiE Recharge	
8. Source Type: Surface Well/Ground Water	Well Field Spring Purchased
9. County:	
0. Check here if this analysis is for Compliance with State regula	ations for Public Water Systems. (Resluts will be sent to you and the State.)
11. Sample taken:	nent No Treatment In Distribution
12. Utility's Name for this source:	
13. Treatment Type: None Aeration Filration	Chlorination Fluoridation Softener Other
14. COMPOSITE INFORMATION (Applies to Multiple Sources Only) If s	sample is to be composited in lab, list all sources.
If you want the lab to composite samples from your system INITIAL	here
1. 2. 3.	4. 5. 6.
15. Remarks:	
Analysis To Perform (Please Check Box) Frequently requested	d tests are listed below. For others, please list under Other Analysis.
	Snohomish County Building Permit \$157 Radium 228 \$90
☐ 525.2 Pesticides \$295 ☐ V	Whatcom County Building Permit \$157 ☐ Gross Alpha & Beta \$95 Gragit County Building Permit \$157 ☐ EWS Well Report \$210
TO STOLLT ICIDIOLOGO	Skagit County Building Permit \$157 EWS Well Report \$210 sland County Building Permit \$44 Other Analysis (Please List)
	San Juan County Building Permit \$93
The service volume organic outper	King County Building Permit \$34
[] OO 11.1 EDD, DEG. 7.1,=,=	Discounted Nuisance Test \$18
532.2 Transdection fords T 534.2 Tribalomothanes (THM) \$81	Only with Snohomish, Whatcom, Skagit or San Juan Bldg. Permit)
524.2 Trihalomethanes (THM) \$81 \$125 \$125 \$125	Nuisance Test (Hardness, Iron, Manganese, pH) \$44
510.1 Maximum Total Timalometrianes Fotomata \$120	Nitrate \$18
1 548.2 Endotriali	Chloride \$18
L 547 Glyphosale	Arsenic \$18
1 549 Diquat	ead and Copper Rule (Special Sampling) \$22
TE OCIVITY Z LIST ((LTA 327, 323)	Total Organic Carbon (TOC) \$38
DOM 2 LIST 2 (LI A 323.2, 303, 321)	Complete Inorganics \$289 CO002680
☐ Nitrosamines (521) for DSMRT \$300 ☐ S	

Questions for State Regulations

Questions regarding drinking water regulations, system monitoring requirements, and sampling information as to location, source type or method should be directed to:

SW Regional Office – Belle Fuchs (360) 586-5179 NW Regional Office – Steve Hulsman (253) 395-6750 Eastern Regional Office – Anita Waterman (509) 456-2475

143 Lab ID#:

Washington State ID: EPA ID#:

M1873 WA 01177

Telephone: (509) 522-3775

Fax: (509) 529-9681

581 Mill Creek Road

Walla Walla, WA 99362

Date: 12/18/07

\$75.00 Walla Walla Basin Watershed Council Amount Due: System ID / Name: Invoice Number: **Bob Bower** Sampler 11/26/07 Date Collected: P.O. Box 68 Address: Date Analyzed: 11/26/07 Milton-Freewater City: Skifstad Lab Analyst: Zip Code: 97862 Oregon State:

> Test Methods Are Selected From The Standard Methods For Examination Of Water and Wastewater ~ 20th Edition~

	Test Method 9222D		产型的基础表现的
Sample ID #1	Results	Units	Lab Number
OBS #1	1.0	CFU's / 100 mL	143-04967
		Units	Lab Number
Sample ID #2	Results		
Intake #1A	11.0	CFU's / 100 mL	143-04968
			A CHISTING THREE THE SELL
Sample ID #3	Results	Units	Lab Number
Intake #1B	14.0	CFU's / 100 mL	143-04969
make #15			
			III NOOMA III AMARKA AAAAA AAAAA AAAAA
	日本会員 自用信息 表现		
	NOTES IN LANGUAGE MORE THAN		
The second secon			

The City of Walla Walla's Mill Creek Water Treatment Laboratory will maintain records pertaining to reconstructing client's data for a minimum of five years from the date of issuance of the final report. Records may be destroyed after that .

Signature Lab Director:

Tone Krels

/2/19/07 (date)

City Of Walla Walla Water Plant Laboratory 581 Mill Creek Road Walla Walla, WA 99362





MILL CREEK WATER TREATMENT PLANT
581 Mill Creek Road · Walla Walla, WA 99362
Phone 509/522-3775 · Fax 509/529-9681

COLIFORM BACTERIA ANALYSIS

If instruction		
Date Sample Collected	Time Sample	County
1112607	Collected SCAM	Walla Walla
Month Day Year	PM	The second secon
Type of Water System (chec ☑ Group A Public		ivate Household
☐ Group B Public	i ot	
Group A and Group B Syste	ms - Provide from Wate	r Facilities Inventory (WFI):
D# 9 2 5 0		
System Name: Walla \		
Contact Person: Tom K	rebs	
Day Phone: (509) 522	-3775 Cell Ph	none: (509) 520-6059
Eve. Phone: (509) 529	-8555 FAX: (509) 529-9681
Send results to: (Print full na		
City of Walla Wa	lla (Water Dept	.)
P.O. Box 478		
Walla Walla, WA	99362	
Comple collected by (seems)	SAMPLE INFORMA	HUN
Sample collected by (name) BOB BOW		
		r sample site, and type of faucet):
TNTAKE	pro contouco (accineca	
Special instructions or comm	nents:	
1. ☐ Routine Distribution Provide information below. Chlorinated: Yes No	Sample 2. □Re to Provide	epeat Sample (follow-up an unsatisfactory sample) information below.
1. ☐ Routine Distribution Provide information below. Chlorinated: Yes No_ Chlorine Residual: Total 3. ☐ Raw Water Source Si Required for Surface Water, some Spring Sources) S ☐ ☐ Public Systems must provide Source I	Sample 2. □R to Provide Unsatisition Total Coliform Sumber from (WFI) Chlorine	epeat Sample (follow-up an unsatisfactory sample) information below. factory routine lab number: factory routine collect date: / / ted: Yes No Residual: Total Free
1. □ Routine Distribution Provide information below. Chlorinated: Yes No. Chlorine Residual: Total 3. □ Raw Water Source Si Required for Surface Water, some Spring Sources) S □ □ Public Systems must provide Source No.	Sample 2.	epeat Sample (follow-up an unsatisfactory sample) information below. factory routine lab number: factory routine collect date: /
Chlorine Residual: Total 3. Raw Water Source Si Required for Surface Water, some Spring Sources) S Public Systems must provide Source I	Sample 2.	epeat Sample (follow-up an unsatisfactory sample) information below. factory routine lab number: factory routine collect date: /
1. □ Routine Distribution Provide information below. Chlorinated: Yes	Sample Free Unsatisfactor Freal Coliform Fecal Coliform Fecal Coliform Fundamber from (WFI) Information Only rs Private Resid	epeat Sample (follow-up an unsatisfactory sample) information below. factory routine lab number: factory routine collect date: / / / ted: Yes No Residual: Total Free Chuff C / dence Other ESULTS AB USE ONLY ory n Present and
1. □ Routine Distribution Provide information below. Chlorinated: Yes	Sample Free Unsatisfactor Chlorina Chlorina Information Only Total Coliform Chlorina Unsatisfactor Chlorina Unsatisfactor Chlorina Electric Chlorina Chlorina	epeat Sample (follow-up an unsatisfactory sample) information below. factory routine lab number: factory routine collect date: / / / ted: Yes No Residual: Total Free Chuff C / dence Other ESULTS AB USE ONLY ory n Present and
1. □ Routine Distribution Provide information below. Chlorinated: Yes	Sample 2.	epeat Sample (follow-up an unsatisfactory sample) information below. factory routine lab number: factory routine collect date: // /
1. □ Routine Distribution Provide information below. Chlorinated: Yes	Sample Free Provide Unsatisition Only Total Coliform (WFI) Information Only Private Resident Coliform Chlorine Unsatisition Only Total Coliform Chlorine Unsatisition Only The Chlorine Chlorine Chlo	epeat Sample (follow-up an unsatisfactory sample) information below. factory routine lab number: factory routine collect date: / / / ted: Yes No Residual: Total Free No
1. Routine Distribution Provide information below. Chlorinated: Yes	Sample Free Provide Unsatisition of the following provide Unsatisition of the following provide Unsatisition of the following Unsatisition of the following Unsatisfactor Total Coliform Precal coliform Pecal coliform Pecal coliform Unsatisfactor Unsatisf	epeat Sample (follow-up an unsatisfactory sample) information below. factory routine lab number: factory routine collect date: / / / ted: Yes No Residual: Total Free dence Other The C / Jan Present and E.coli absent present Fecal coliform absent uitable because: d culture ml. E.coli/100ml.
1. Routine Distribution Provide information below. Chlorinated: Yes	Sample Free Provide Unsatis Unsatis Unsatis Unsatis Unsatis Unsatis Unsatis Chlorine Ch	epeat Sample (follow-up an unsatisfactory sample) information below. factory routine lab number: factory routine collect date: /
1. Routine Distribution Provide information below. Chlorinated: YesNo. Chlorinated: YesNo. Chlorinated: YesNo. Chlorinated: YesNo. Chlorinated: YesNo. Chlorinated: YesNo. Chlorinated: YesNo. Chlorinated: YesNo. Required for Surface Water, some Spring Sources of Source o	Sample Free Provide Unsatisity of the following provide Unsatisity of the following provide Unsatisity of the following Unsatisity of the following Unsatisity of the following Unsatisity of the following Unsatisfactor Total Coliform Private Residual Private Residual Unsatisfactor Total Coliform Provide Unsatisfactor Total Coliform Provide Unsatisfactor Total Coliform Provide Unsatisfactor Total Coliform Provide Unsatisfactor Total Coliform Provide Unsatisfactor Total Coliform Private Residual Unsatisfactor Total Coliform	pepat Sample (follow-up an unsatisfactory sample) information below. factory routine lab number: factory routine collect date:

DOH Form #331-319 (revised 5/06) SEE REVERSE OF GREEN COPY FOR EXPLANATION OF RESULTS WATER SUPPLIER COPY

143-04968



If instruction Date Sample Collected	Time Sam	ole	County
11 12610B	Collecte	d	
	9:15	AM PM	Walla Walla
Month Day Year Type of Water System (check			
☐ Group A Public ☐ Group B Public		☐ Privat	
Group A and Group B Syste	0 2	om Water F	acilities Inventory (WFI):
System Name: Walla			
Contact Person: Tom K	rebs		
Day Phone: (509) 522	2-3775	Cell Phon	e: (509) 520-6059
Eve. Phone: (509) 529	9-8555	FAX: (50	19) 529-9681
Send results to: (Print full na			
City of Walla Wa	ılla (Water	Dept.)	
P.O. Box 478			
Walla Walla, WA	99362		
	SAMPLE IN	FORMATIO	ON
Sample collected by (name	13		omple site, and type of faucet)
Specific location where san	ments:		
Specific location where san	ments: ick only one box i Sample	of #1 throu 2. □ Rep to al	
Specific location where san Special instructions or com Type of Sample (must che 1. Routine Distribution Provide information below. Chlorinated: Yes No. Chlorine Residual: Total 3. Raw Water Source S Required for Surface Wate some Spring Sources) S [S] S [S] S [S	ck only one box n Sample Free Sample r, GWI, and Total Coliform Fecal Coliform	of #1 throu 2. □Rep to al Provide in Unsatisfac Unsatisfac Chlorinate	gh #4 listed below) eat Sample (follow-up n unsatisfactory sample) formation below. ettory routine lab number: ettory routine collect date:
Specific location where san Special instructions or com Type of Sample (must che 1. Routine Distribution Provide information below. Chlorinated: Yes Nc Chlorine Residual: Total 3. Raw Water Source S Required for Surface Wate some Spring Sources)	ck only one box n Sample Free Sample r, GWI, and Total Coliform Fecal Coliform	of #1 throu 2. □ Rep to al Provide in Unsatisfac Unsatisfac Chlorinate	gh #4 listed below) eat Sample (follow-up n unsatisfactory sample) formation below. etory routine lab number: etory routine collect date:
Specific location where san Special instructions or com Type of Sample (must che 1. Routine Distribution Provide information below. Chlorinated: Yes No. Chlorine Residual: Total 3. Raw Water Source S Required for Surface Wate some Spring Sources) S [S] S [S] S [S	ck only one box n Sample D Free Sample Total Coliform P Foundard Coliform Number from (WFI)	of #1 throu 2. □ Rep to au Provide in Unsatisfac Chlorinate Chlorine R	gh #4 listed below) eat Sample (follow-up n unsatisfactory sample) formation below. etory routine lab number: etory routine collect date: // d: Yes No esidual: Total Free
Specific location where san Special instructions or com Type of Sample (must che 1. Routine Distribution Provide information below. Chlorinated: Yes No. Chlorinated: Yes No. Chlorinated: Yes No. Sample (must che 1. Routine Distribution Provide information below. Chlorinated: Yes No. Chlorinated: Yes No. Chlorinated: Yes No. Chlorinated: Yes No. Required for Surface Watesome Spring Sources) S	ck only one box n Sample D Free Sample Total Coliform P Foundard Coliform Number from (WFI)	of #1 throu 2. □ Rep to au Provide in Unsatisfac Unsatisfac Chlorinate Chlorine R	gh #4 listed below) eat Sample (follow-up n unsatisfactory sample) formation below. etory routine lab number: etory routine collect date: // d: Yes No esidual: Total Free
Specific location where san Special instructions or com Type of Sample (must che 1. Routine Distribution Provide information below. Chlorinated: Yes No. Chlorine Residual: Total 3. Raw Water Source S Required for Surface Wate some Spring Sources) S Public Systems must provide Source 4. Sample Collected for Construction Rep	ck only one box n Sample D Free Sample r, GWI, and Total Coliform Pecal Coliform Number from (WFI) or Information 0 airs Pri	of #1 throu 2. □ Rep to at Provide in Unsatisfac Chlorinate Chlorine R Only vate Reside atisfactor 1 Coliform Ii	gh #4 listed below) eat Sample (follow-up n unsatisfactory sample) formation below. ettory routine lab number: ettory routine collect date: // d: Yes No esidual: Total Free nce OtherX
Specific location where san Special instructions or com Type of Sample (must che 1. Routine Distribution Provide information below. Chlorinated: Yes Nc Chlorine Residual: Total 3. Raw Water Sources Required for Surface Wate some Spring Sources) S	ck only one box n Sample D Free Sample r, GWI, and Total Coliform Fecal Coliform Prevail Coliform Information Cairs Uns Total E.col	of #1 throu 2. □ Rep to at Provide in Unsatisfac Chlorinate Chlorine R Only vate Reside atisfactor 1 Coliform Ii	gh #4 listed below) eat Sample (follow-up n unsatisfactory sample) formation below. ettory routine lab number: ettory routine collect date: // d: YesNo esidual: TotalFree nceOtherX / / / / / / / / / / / / / / / / /

DOH Form #331-319 (revised 5/06) SEE REVERSE OF GREEN COPY FOR EXPLANATION OF RESULTS WATER SUPPLIER COPY

_/ml. E.coli__ _/100ml. Fecal Coliform_____/___/100ml.

Date and Time Received:

11/06/07@ Date Reported:

Lab Use:

_/100ml.

Bacterial Density Results: Plate Count_

□ 1340 □ 2720

Date Analyzed: 11 76/07 (CS

Total Coliform__

MICR Method Code:

Lab/Sample Number

143-04967

089,-	7000		ANALT LCAL The lab you can trust!	1620 S. Walnut St.	Burlington, WA 98233 1.800.755.9295	A Chin O and Landan O MI 200	Bellingham, WA 98225		SIS	or of Containe	Special Instructions Conditions on Receipt	I puplicate on Thro										Containers		Yes No N/A	C satisfactory	ct C	bels agree
ections)	For Lab Use Only		Check Regulatory Program	Safe Drinking Water Act	Clean Water Act	RCRA / CERCLA	Other	Analyses Requested														bob bower & w		Time Custody seals intact	Sample temp C	Samples received intact	Chain of custody & labels agree
e complete all applicable shaded sections)		Ref#	Zip: 97862 Che			res /		Analyses		00D 0-PO4, Cl, TD HCL Green cs		N N		N N								Email:		Date			
(Please complete all	Walla Walla Basin Watershed Counc	810 S Main Street	Milton-Freewe st. OR	FAX:	Attn:	☐ M/C ☐ A/E Expires			Required	Standard Half-time (50% surcharge) Quickest (100% surcharge)	Date Time	11/26/2 9:30 X		14 14 9:17 K								2 FAX: Same		vd			
s Request	Bill to:	Address:	City:	Phone:	P.O.#:	☐ Visa	Card#:		Turn Around Time Required	Standard Half-time (5 Quickest (1	Grab/ Comp. Matrix	HBDIC RECHMESE	*	mell (584 MI 938	r Email)	Time Received hy			
dy / Analysi	Walla Walla Basin Watershed Cour	Street	ve St: OR Zip: 97862		70 FAX:	bob.bower@wwwbwc.org			<u>o</u>	requests. be performed for iners.	Location	INTAKE AT HODIG		of servention to								Phone: 3	(Must include FAX or	Date C			
Chain of Custody / Analysis Request	Report to: Walla Walla	Ship Address: 810 S Main Street	City: Milton-Freews St:	Attn: Bob Bower	Phone: 541.938-2170 FAX:	Email: bob.bower@	Project		Instructions Use one line per sample.	 Be specific in analysis requests. Check off analyses to be performed for each sample. Enter number of containers. 	Field ID	1 TNTAKE 1	2 observation	3 Weil #1 (00)	4	5	9	7	8	6	10	Sampled by: Will Letnis	Re	Relinquished by			



Corporate Office 800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225 Microbiology 360.671.0688 • 360.671.1577fax

July 9, 2008

Page 1 of 1

Bob Bower Walla Walla Basin Watershed Council '810 S Main Street Milton-Freewater, OR 97862

RE: 08-07095 - Locker/Hall Wetland/HBBIC

Dear Bob Bower,

Your project: Locker/Hall Wetland/HBBIC, was received on Wednesday May 28, 2008.

All samples were analyzed within the accepted holding times, were appropriately preserved and were analyzed according to approved analytical protocols. The quality control data was within laboratory acceptance limits, unless specified in the QA reports.

If you have questions phone me at 800 755-9295.

Respectfully Submitted,

Lawrence J Henderson, PhD Director of Laboratories

Enclosures Data Report

QC Reports

Chain of Custody



Burlington WA

1620 S Walnut St - 98233 800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225

360.671.0688 • 360.671.1577fax

Page 1 of 4

Data Report

Client Name: Walla Walla Basin Watershed Council

810 S Main Street

Milton-Freewater, OR 97862

Report Date: 6/16/2008

Reference Number: 08-07095

Project: Locker/Hall Wetland/HBBIC

Collected By: T. Baker

Date Received: 5/28/2008 Peer Review

ŧ									70	-	
Lab Num	nber: 15124 Sam	ple Description	on: HBDIC	OBS1 - H	IBDIC			Sample	Date:	5/27/2008	
CAS ID#	Analyte	Result	PQL	MDL	Units	DF	Method	Analyzed	Analyst	Batch	Comme
14797-55-8	NITRATE-N	0.17	0.01	0.0007	mg/L	1.0	SM4500-NO3 F	5/28/2008	so	NO3NO2-080528	
15541-45-4	BROMATE	ND	0.5	0.068	ug/L	1.0	317.0	6/6/2008	MVP	317_080606A	
E-11778	HARDNESS	22.1	3.30	0.055	mg CaC(1.0	200.7	5/30/2008	₿J	200.7-080530A	
E-10117	CHEMICAL OXYGEN DEMAND	11	8.0	2.0	mg/L	1.0	SM5220 D	6/4/2008	MAK	COD_080604	
E-10139	HYDROGEN ION (pH)	7.18			pH Units	1.0	SM4500-H+ B	5/28/2008	CCN	PH_080528	
E-10184	ELECTRICAL CONDUCTIVITY	63.4	10		uS/cm	1.0	SM2510 B	6/2/2008	CCN	EC_080602	
E-10617	TURBIDITY	0.88	0.05	0.02	NTU	1.0	180.1	5/28/2008	CCN	TURB_080528	
16887-00-6	CHLORIDE	0.5	0.1	0.012	mg/L	1.0	300.0	5/28/2008	BJ	ID80528A	
E-10173	TOTAL DISSOLVED SOLIDS	61	10		mg/L	1.0	SM2540 C	6/2/2008	CCN	TDS_080802	
14265-44-2	ORTHO-PHOSPHATE	0.17	0.01	0.005	mg/L	1.0	SM4500-P F	5/28/2008	50	OPHOS-080528	
Lab Nun	nber: 15125 Sam	ple Description	on: L-1 - L	ocker Rd				Sample	Date:	5/27/2008	
CAS ID#	Analyte	Result	PQL	MDL	Units	DF	Method	Analyzed	Analys	t Batch	Comme
14797-55-8	NITRATE-N	5.86	0.05	0.0007	mg/L.	5.0	SM4500-NO3 F	5/28/2008	SD ²	NO3NO2-080528	
16887-00-6	CHLORIDE	6.7	0.1	0.012	mg/L	1.0	300.0	5/28/2008	BJ	1080528A	
E-10173	TOTAL DISSOLVED SOLIDS	262	10		mg/L	1.0	SM2540 C	6/2/2008	CCN	TDS_080602	
15541-45-4	BROMATE	ND	0.5	0.068	ug/L	1.0	317.0	6/6/2008	MVP	317_080606A	
E-11778	HARDNESS	156	3.30	0.055	mg CaCt	1.0	200.7	5/30/2008	₿J	200.7-080530A	
E-10117	CHEMICAL OXYGEN DEMAND	ND	8.0	2.0	mg/L	1.0	SM5220 D	6/4/2008	MAK	COD_080604	
E-10139	HYDROGEN ION (pH)	7.00			pH Units	1.0	SM4500-H+ B	5/28/2008	CCN	PH_080528	
E-10184	ELECTRICAL CONDUCTIVITY	401	10		uS/cm	1.0	SM2510 B	6/2/2008	CCN	EC_080602	
E-10617	TURBIDITY	0.79	0.05	0.02	NTU	1.0	180.1	5/28/2008	CCN	TURB_080528	
14265-44-2	ORTHO-PHOSPHATE	0.27	0.01	0.005	mg/L	1.0	SM4500-P F	5/28/2008	so	OPHOS-080528	
Lab Nur	nber: 15126 San	nple Descripti	on: L-2 - l	ocker Rd				Sample	Date:	5/27/2008	*****
CAS ID#	Analyte	Result	PQL	MDL	Units	DF	Method	Analyzed	Analys	t Batch	Comme
14797-55-8	NITRATE-N	5.96	0.05	0.0007	mg/L	5.0	SM4500-NO3 F	5/28/2008	so	NO3NO2-080528	
16887-00-6	CHLORIDE	6.5	0.1	0.012	mg/L	1.0	300.0	5/28/2008	BJ	1080528A	
E-10173	TOTAL DISSOLVED SOLIDS	205	10		mg/L	1.0	SM2540 C	<i>8/2/</i> 2008	CCN	TDS_080602	
15541-45-4	BROMATE	ND	0.5	0.068	ug/L	1.0	317.0	6/11/2008	MVP	317_080611A	
E-11778	HARDNESS	117	3.30	0.055	mg CaC	0.1	200.7	5/30/2008	BJ	200.7-080530A	
					_						

PQL = Practical Quantitation Limit is the lowest level that can be acheived within specified limits of precision and accuracy during routine laboratory operating conditions.

8.0

2.0

mg/L

ND = Not detected above the listed practical quantitation limit (PQL) or not above the Method Detection Limit (MDL), if requested

10

6.93

CHEMICAL OXYGEN DEMAND

HYDROGEN ION (pH)

D.F. - Dilution Factor

E-10117

E-10139

WSDOE Lab C1251 WSDOH Lab 046

COD_080604

PH_080528

SM5220 D

SM4500-H+ B

6/4/2008

5/28/2008

мак

CCN



Corporate Office

800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225 360.671.0688 • 360.671.1577fax

Page 1 of 1

DATA REPORT

Client Name: Walla Walla Basin Watershed Council

810 S Main Street

Milton-Freewater, OR 97862

Reference Number: 08-07095

Project: Locker/Hall Wetland/HBBIC

Field ID: HBDIC OBS1

Sample Description: HBDIC

Sampled By: T. Baker

Sample Date: 5/27/2008

Source Type:

Sampler Phone:

Lab Number: 04615124 Report Date: 6/10/2008 Date Analyzed: 6/9/2008 Extraction Date: 508_080609

Analyst: GEB

Peer Review: Analytical Method: 508.1

Synthetic Organics

CAS	COMPOUND	RESULTS	Units	PQL	MDL	MCL	COMMENT
	PCBs/Toxaphene						
1336-36-3	PCBS (Total Aroclors)	ND	ug/L	0.2		0.5	•
11104-28-2	AROCLOR 1221	ND	ug/L	0.1	0.1^		
11141-16-5	AROCLOR 1232	ND	ug/L	0.1	0.1^		
53469-21-9	AROCLOR 1242	ND	ug/L	0.1	0.1^		
12672-29-6	AROCLOR 1248	ND	ug/L	0.1	0.1^	•	
11097-69-1	AROCLOR 1254	ND	ug/L	0.1	0.1^		
11096-82-5	AROCLOR 1260	ND	ug/L	0.1	80.0		
12674-11-2	AROCLOR 1016	ND	ug/L	0.1	0.1		
8001-35-2	TOXAPHENE	ND	ug/L	1	0.5	3	

ND = Not detected above the listed practical quantitation limit (PQL) or not above the Method Detection Limit (MDL), if requested

A blank MCL, or SAL value indicates a level is not currently established.

PQL - Practical Quantitation Limit is the concentration of the standard analyzed during the initial calibration.

MDL - Melhod Detection Limit is the labs minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.

J - Estimated value

MCL- Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds



Burlington WA | 1620 S Walnut St - 98233 | 800.755.9295 • 360.757.1

800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225 360.671.0688 • 360.671.1577fax

Page 1 of 1

CARBAMATES IN DRINKING WATER

Client Name: Walla Walla Basin Watershed Council

810 S Main Street

Milton-Freewater, OR 97862

Reference Number: 08-07095

Project: Locker/Hall Wetland/HBBIC

Field ID: HBDIC OBS1

Sample Description: HBDIC

Sampled By: T. Baker

Sample Date: 5/27/2008

Source Type: Sampler Phone:

Lab Number: 04615124 Report Date: 6/16/2008 Date Analyzed: 6/11/2008 Extraction Date: 531 080611

Analyst: CO Peer Review: MUA

Analytical Method: 531.2

Carbamates

CAS	COMPOUND	RESULTS	Units	PQL	MDL	MCL	COMMENT
	EPA Regulated						
23135-22-0	OXYMAL	ND	ug/L	1.0	0.81	200	
1563-66-2	CARBOFURAN	ND	ug/L	1.0	0.87	40	
	EPA Unregulated						
1646-87-3	ALDICARB SULFOXIDE	ND	ug/L	1.0	0.71		
1646-88-4	ALDICARB SULFONE	ND	ug/L	1.0	0.83	•	
16752-77-5	METHOMYL	ND	ug/L	1.0	0.86		
16655-82-6	3-HYDROXYCARBOFURAN	ND	ug/L	1.0	1.0		
116-06-3	ALDICARB	ND	ug/L	1.0	0.88		
63-25-2	CARBARYL	ND	ug/L	1.0	0.53		
	State Unregulated - Other						
114-26-1	PROPOXUR (BAYGON)	ND	ug/L	1.0	0.72		
2032-65-7	METHIOCARB	ND	ug/L	1.0	0.76		

PQL - Practical Quantitation Limit is the concentration of the standard analyzed during the initial calibration.

J - Estimated value.

MDL - Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.



800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225 Microbiology 360.671.0688 • 360.671.1577fax

Page 1 of 1

HERBICIDES IN DRINKING WATER

Client Name: Walla Walla Basin Watershed Council

810 S Main Street

Milton-Freewater, OR 97862

Reference Number: 08-07095

Project: Locker/Hall Wetland/HBBIC

Field ID: HBDIC OBS1

Sample Description: HBDIC

Sampled By: T. Baker

Sample Date: 5/27/2008

Source Type: Sampler Phone:

Report Date: 6/26/2008 Date Analyzed: 6/18/2008 Extraction Date: 515_080602

Analyst: CO

Lab Number: 04615124

Peer Review: MU A Analytical Method: 515.1

Chlorophenoxy Herbicides

CAS	COMPOUND	RESULTS	Units	PQL	MDL	MCL	COMMENT
	EPA Regulated						
94-75-7	2,4 - D	ND	ug/L	0.2	0.11	70	
93-72-1	2,4,5 - TP (SILVEX)	ND	ug/L	0.1	0.02	50	
87-86-5	PENTACHLOROPHENOL	ND	ug/L	0.1	0.044	1	
75-99-0	DALAPON	ND	ug/L	1.3	0.80	200	
88-85-7	DINOSEB	ND	ug/L	0.2	0.16	7	
1918-02-1	PICLORAM	ND	ug/L	0.1	0.089	500	
	EPA Unregulated						
1918-00-9	DICAMBA	ND	ug/L	0.1	0.045		
	State Unregulated						
1861-32-1	TOTAL (DCPA & Metabolites)	ND	ug/L	0.1	0.089		
E-14-02-8	DCPA (ACID METABOLITES)	ND	ug/L	0.1	0.1		
94-82-6	2,4 DB	ND	ug/L	8.0	0.10		
93-76-5	2,4,5 T	ND	ug/L	0.1	0.044		
25057-89-0	BENTAZON	ND	ug/L	0.2	0.067		
120-36-5	DICHLORPROP	ND	ug/L	0.3	0.089		
50594-66-6	ACIFLUORFEN	ND	ug/L	0.1	0.089		
133-90-4	CHLORAMBEN	ND	ug/L	0.2	0.2		
51-36-5	3,5 - DICHLOROBENZOIC ACID	ND	ug/L	0.1	0.044		

A blank MCL or SAL value indicates a level is not currently established.

PQL - Practical Quantitation Limit is the concentration of the standard analyzed during the initial calibration.

ND = Not detected above the listed practical quantitation limit (PQL) or not above the Method Detection Limit (MDL), if requested.

MCL- Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds.

MDL - Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.



Corporate Office 800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225

Microbiology 360.671.0688 • 360.671.1577fax

Page 1 of 2

SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

Client Name: Walla Walla Basin Watershed Council

810 S Main Street

Milton-Freewater, OR 97862

Reference Number: 08-07095

Project: Locker/Hall Wetland/HBBIC

Field ID: HBDIC OBS1

Sample Description: HBDIC

Sampled By: T. Baker

Sample Date: 5/27/2008

Source Type:

Sampler Phone:

Lab Number: 15124 Report Date: 7/3/2008

Report Date: 7/3/2008

Date Analyzed: 6/16/2008

Extraction Date: 525 080609

Analyst: CO Peer Review: MVA

Analytical Method: 525.2

Synthetic Organics

CAS	COMPOUND	RESULTS	Units	PQL	MDL	MCL	COMMENT
	EPA Regulated						
72-20-8	ENDRIN	ND	ug/L	0.1 .	0.030	2	
58-89-9	LINDANE (BHC - GAMMA)	ND	ug/L	0.1	0.028	0.2	
72-43-5	METHOXYCHLOR	ND	ug/L	0.1	0.015	40	
15972-60-8	ALACHLOR	ND	ug/L	0.1	0.044	2	
1912-24-9	ATRAZINE	ND	ug/L	0.1	0.030	3	
50-32-8	BENZO(A)PYRENE	ND	ug/L	0.1	0.012	0.2	
57-74-9	CHLORDANE, TECHNICAL	ND	ug/L	0.1	0.3	2	
103-23-1	DI(ETHYLHEXYL)-ADIPATE	ND	ug/L	0.1	0.022	400	
117-81-7	DI(ETHYLHEXYL)-PHTHALATE	ND	ug/L	0.1	0.063	6	
76-44-8	HEPTACHLOR ¹	ND	ug/L	0.1	0.022	0.4	
1024-57-3	HEPTACHLOR EPOXIDE	ND	ug/L	0.1	0.02	0.2	
118-74-1	HEXACHLOROBENZENE	ND	ug/L	0.1	0.025	1	
77-47-4	HEXACHLOROCYCLO-PENTADIENE	ND	ug/L	0.1	0.024	50	
122-34-9	SIMAZINE	ND	ug/L	0.1	0.030	4	
87-86-5	PENTACHLOROPHENOL	ND	ug/L	0.4	0.08	1	screening only / compliance by 51
	EPA Unregulated						
309-00-2	ALDRIN	ND	ug/L	0.1	0.022		
23184-66-9	BUTACHLOR	ND	ug/L	0.1	0.024		
60-57-1	DIELDRIN	ND	ug/L	0.1	0.031		
51218-45-2	METOLACHLOR	ND	ug/L	0.1	0.024		
21087-64-9	METRIBUZIN	ND	ug/L	0.1	0.030	w ² 3	
1918-16-7	PROPACHLOR	ND	ug/L.	0.1	0.031		,
	State Unregulated - Other						
314-40-9	BROMACIL	ND	ug/L	0.1	0.031		
5902-51-2	TERBACIL	ND	ug/L	0.1	0.043		

ND = Not detected above the listed practical quantitation limit (PQL) or not above the Method Detection Limit (MDL), if requested.

A blank MCL or SAL value indicates a level is not currently established.
PQL - Practical Quantitation Limit is the concentration of the standard analyzed during the initial calibration.

MCL- Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds.

MDL - Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.

J - Estimated value.



Reference Number: 08-07095 Page 2 of 2

Lab Number: 15124 Report Date: 7/3/2008

SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

CAS	COMPOUND	RESULTS	Units	PQL	MDL	MCL	COMMENT
333-41-5	DIAZINON	ND	ug/L	0.1	0.035		Unstable in Acidified Sample Matrix
759-94-4	EPTC	ND	ug/L	0.1	0.028		
72-54-8	4,4-DDD	ND	ug/L	0.1	0.024		
72 - 55-9	4,4-DDE	ND	ug/L	0.1	0.024		
50-29-3	4,4-DDT	ND	ug/L	0.1	0.022		
21725-46-2	CYANAZINE	ND	ug/L	0.1	0.13		Qualitative Analysis Only
121-75-5	MALATHION	ND	ug/L	0.1	0.015		
56-38-2	PARATHION	ND	ug/L	0.1	0.022		
1582-09-8	TRIFLURALIN	ND	ug/L	0.1	0.024		
•	- PAHs						•
91-20-3	NAPTHALENE	ND	ug/L	0.1	0.1^		
86-73-7	FLUORENE	ND	ug/L	0.1	0.026		
208-96-8	ACENAPHTHYLENE	ND	μg/L	0.1	0.025		
83-32-9	ACENAPHTHENE	ND	ug/L	0.1	0.1^		
120-12-7	ANTHRACENE	ND	μg/L	0.1	0.012		
56-55-3	BENZ(A)ANTHRACENE	ND	ug/L	0.1	0.012		
205-99-2	BENZO(B)FLUORANTHENE	ND	ug/L	0.1	0.025		ę p
191-24-2	BENZO(G,H,I)PERYLENE	ND	ug/L	0.1	0.025		
207-08-9	BENZO(K)FLUORANTHENE	ND	ug/L	0.1	0.022		
218-01-9	CHRYSENE	ND	ug/L	0.1	0.022		
53-70-3	DIBENZO(A,H)ANTHRACENE	ND	ug/L	0.1	0.024		
206-44-0	FLUORANTHENE	ND	ug/L	0.1	0.1^		
193-39-5	INDENO(1,2,3-CD)PYRENE	ND	ug/L	0.1	0.040		
85-01-8	PHENANTHRENE	ND	ug/L	0.1	0.015		
129-00-0	PYRENE	ND	ug/L	0.1	0.022		
	- Phthalates						
85-68-7	BENZYL BUTYL PHTHALATE	ND	ug/L	0.1	0.022		
84-74-2	DI-N-BUTYL PHTHALATE	ND	ug/L	0.1	0.085		
84-66-2	DIETHYL PHTHALATE	ND	ug/L	0.1	0.044		
131-11-3	DIMETHYL PHTHALATE	ND	ug/L	0.1	0.015		

ND = Not detected above the listed practical quantitation limit (PQL) or not above the Method Detection Limit (MDL), if requested.

A blank MCL or SAL value indicates a fevel is not currently established.

PQL - Practical Quantitation Limit is the concentration of the standard analyzed during the initial calibration.

MDL - Method Detection Limit is the lab's minimum concentration a compound can be measured and reported with 99% confidence that the compound concentration is greater than zero.

J - Estimated value.

MCL- Maximum Contaminant Level, maximum permissible level of a contaminant in water established by EPA, NPDWR. State Advisory Level (SAL) for Unregulated compounds.





Burlington WA | 1620 S Walnut St - 98233 | 800.755.9295 • 360.757.14 800.755.9295 • 360.757.1400 • 360.757.1402fax

Microbiology

Bellingham WA 805 Orchard Dr Suite 4 - 98225 360,671,0688 • 360,671,1577fax

Page 1 of 1

DATA REPORT

Client Name: Walla Walla Basin Watershed Council

810 S Main Street

Milton-Freewater, OR 97862

Lab Number: 15124

Field ID: HBDIC OBS1

Sample Description: HBDIC

Matrix: Water

Collect Date: 5/27/2008

Extraction Date: 6/9/2008

Extraction Method: 3535

Reference Number: 08-07095

Project: Locker/Hall Wetland/HBBIC

Report Date: 7/9/2008

Date Analyzed: 6/25/2008

Analyst: CO Peer Review: MVA

Analytical Method: 525.2

SOC for Walla Walla

CAS ID#	COMPOUNDS	RESULT	Flag Units	PQL	MDL	D.F.	Batch	COMMENT
	%8							
2312-35-8	PROPARGITE	ND	ug/L		-	1.0	525X_080609	Qualitative analysis
80-05-7	BISPHENOL-A	0.5	ug/L	0.1		1.0	525X_080609	
60-51-5	DIMETHOATE	ND	ug/L	0.5	0.03	1.0		
57837-19-1	METALAXYL	ND	ug/L	0.1	-	1.0		
15299-99-7	NAPROPAMIDE	ND	ug/L	0.1	0.05	1.0		
122-34-9	SIMAZINE	ND	ug/L	0.1	0.03	1.0		
86-86-2	1-NAPHTHALENEACETAMIDE	ND	ug/L	0.5	-	1.0		
333-41-5	DIAZINON	ND	ug/L	0.1	0.04	1.0		
60168-88-9	FENARIMOL	ND	.ug/L	0.1	0.03	1.0		
58-89-9	LINDANE (BHC - GAMMA)	ND	ug/L	0.1	0.03	1.0		
7786-34-7	MEVINPHOS	ND	ug/l	0.1	0.03	1.0		
86-50-0	AZINPHOS-METHYL	ND	ug/L	0.5	0.12	1.0		
2921-88-2	CHLORPYRIFOS	ND	ug/L	0.1	0.04	1.0		
72-54-8	4,4-DDD .	ND	ug/L	0.1	0.02	1.0		
72-55-9	4,4-DDE	ND	ug/L	0.1	0.02	1.0		
50-29-3	4,4-DDT	ND	ug/L	0.1	0.03	1.0		
115-32-2	DICOFOL	ND	ug/L	1	-	1,0		
121-75-5	MALATHION	ND	ug/L	0.1	0.05	1.0		
298-00-0	METHYL PARATHION	ND	ug/L	0.5	0.1	1.0		
56-38-2	PARATHION-ETHYL	ND	ug/L	0.1	0.05	1.0		
732-11-6	PHOSMET	ND	ug/L	0.5	-	1.0		
43121-43-3	TRIADIMEFON	ND	ug/L	0.1	0.07	1.0		
68694-11-1	TRIFLUMIZOLE	ND	ug/L	1.0	1.0	1.0		
950-37-8	METHIDATHINON	ND	ug/L	0.5	0.5	1.0		
88671-89-0	MYCLOBUTANIL	ND	ug/L	0.5	0.5	1.0		
51235-04-2	HEXAZINONE	ND	ug/L	0.1	0.05	1.0		

Result of:

NA - indicates the compound was not analyzed.

Flags are data qualifiers. If there are data qualifiers on your report definitions can be found on an accompanying sheet.

ND - indicates the compound was not detected above the PQL or MDL.

PQL = Practical Quantitation Limit is the lowest level that can be acheived within specified limits of precision and accuracy during routine laboratory operating conditions. D.F. - Dilution Factor.



Corporate Office

Burlington WA 1620 S Walnut St - 98233

800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225 360.671.0688 • 360.671.1577fax Page 1 of 12



SAMPLE INDEPENDENT QUALITY CONTROL REPORT

Laboratory Fortified Blank

Reference Number: 08-07095 Report Date: 07/09/08

			True			%		QC	
Batch	Analyte	Result	Value	Units	Method	Recovery	Limits	Qualifier Type*	Comment
200.7-080530A	HARDNESS	70	69.5	mg/L	200.7	101	80-120	LFB	
508_080609	AROCLOR 1260	2.3	2	ug/L	508.1	115	60-140	LFB	
_	TETRACHLORO-M-XYLENE (SURR)	93		%	508.1		70-130		
515_080602	2,4 - D	2.08	2	ug/L	515.1	104	70-130	LFB	
	2,4 - DCAA (SURR)	113		%	515.1		70-130		
	2,4 DB	9.55	8	ug/L	515.1	119	70-130		
	2,4,5 - TP (SILVEX)	1.11	1	ug/L	515.1	111	70-130		
	2,4,5 T	1	1	ug/L	515.1	100	70-130		
	ACIFLUORFEN	1.22	1	ug/L	515.1	122	70-130		
	BENTAZON	2.17	2	ug/L	515.1	109	70-130		
	CHLORAMBEN	0.91	1	ug/L	515.1	91	70-130		
	DALAPON	12.5	13	ug/L	515.1	96	70-130		
	DICAMBA	1.03	1	ug/L	515.1	103	70-130		
	DICHLORPROP	2.78	3	ug/L	515.1	93	70-130		
	DINOSEB	2.66	2	ug/L	515.1	133	70-130	AH	
	PENTACHLOROPHENOL ,	0.99	1	ug/L	515.1	99	70-130		
	PICLORAM	0.95	1	ug/L	515.1	95	70-130		
	TOTAL (DCPA & Metabolites)	1.16	1	ug/L	515.1	116	70-130		
525_080609	1,3-DIMETHYL-2-NITROBENZENE (Surr)	96		%	525.2		70-130	LFB	
	4,4-DDD	1.02	1	ug/L	525.2	102	70-130		
	4,4-DDE	1.03	1	ug/L	525.2	103	70-130		
	4,4-DDT	1.05	1	ug/L	525.2	105	70-130		
	ACENAPHTHYLENE	0.98	1	ug/L	525.2	98	70-130		
	ALACHLOR	2	2	ug/L	525.2	100	70-130		
	ALDRIN	0.98	1	ug/L	525.2	98	70-130		
	ANTHRACENE	0.68	1	ug/L	525.2	68	70-130	CC	
	ATRAZINE	2.09	2	ug/L	525.2	105	70-130		
	BENZ(A)ANTHRACENE	0.92	1	ug/L	525.2	92	70-130		
	BENZO(A)PYRENE	0.75	1	ug/L	525.2	75	70-130	,	
	BENZO(B)FLUORANTHENE	0.88	1	ug/L	525.2	88	70-130		

^{*}Notation:

[%] Recovery = (Result of Analysis)/(True Value) * 100

NA = Indicates % Recovery could not be calculated.

QCS: Quality Control Sample, a solution containing known concentrations of method analytes which is used to fortify an aliquot of reagent matrix. The QCS is obtained from an external source and is used to check lab performance.

LFB: Laboratory Fortified Blank, an aliquot of reagent matrix to which known quantities of method analytes are added in the lab. The LFB is analyzed exactly like a sample, and its purpose is to determine whether method performance is within accepted control limits.

MB or LRB; Method Blank or Laboratory Reagent Blank, an aliquot of reagent matrix is analyzed exactly like a sample, and its purpose is to determine if there is background contamination.



Corporate Office 800.755.9295 • 360.757,1400 • 360.757,1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225

Microbiology 360.671,0688 • 360.671.1577fax

Page 2 of 12



SAMPLE INDEPENDENT QUALITY CONTROL REPORT

Laboratory Fortified Blank

Reference Number: 08-07095

			Тгие			%		QC	
Batch	Analyte	Result	Value	Units	Method	Recovery	Limits	QualifierType*	Comment
525_080609	BENZO(G,H,I)PERYLENE	0.92	1	ug/L	525.2	92	70-130	LFB	***************************************
	BENZO(K)FLUORANTHENE	0.96	1	ug/L	525.2	96	70-130	_	
	BENZYL BUTYL PHTHALATE	1.05	1	ug/L	525.2	105	70-130		
	BROMACIL	1.03	1	ug/L	525.2	103	70-130		
	BUTACHLOR	1.02	1	ug/L	525.2	102	70-130		
	CHLORDANE, TECHNICAL	0.97	1	ug/L	525.2	97	70-130		
	CHRYSENE	1.03	1	ug/L	525.2	103	70-130		
	CYANAZINE	0.85	1	ug/L	525.2	85	70-130		
	DI(ETHYLHEXYL)-ADIPATE	1.04	1	ug/L	525.2	104	70-130		
	DI(ETHYLHEXYL)-PHTHALATE	1.23	1	ug/L	525.2	123	70-130		
	DIAZINON	1	1	ug/L	525.2	100	70-130		
	DIBENZO(A,H)ANTHRACENE	0.96	1	ug/L	525.2	96	70-130		
	DIELDRIN	0.99	1	ug/L	525.2	99	70-130		
	DIETHYL PHTHALATE	1.1	1	ug/L	525.2	1.10	70-130		
	DIMETHYL PHTHALATE	1.06	1	ug/L	525.2	106	70-130		
	DI-N-BUTYL PHTHALATE	1.14	1	ug/L	525.2	114	70-130		
	ENDRIN	0.96	1	ug/L	525.2	96	70-130		
	EPTC	0.96	1	ug/L	525.2	96	70-130		
	FLUORENE	1.04	1	ug/L	525.2	104	70-130		
	HEPTACHLOR	0.96	1	ug/L	525.2	96	70-130		
	HEPTACHLOR EPOXIDE	0.94	1	ug/L	525.2	94	70-130		
	HEXACHLOROBENZENE	0.97	1	ug/L	525.2	97	70-130		
	HEXACHLOROCYCLO-PENTADIENE	0.92	1	ug/L	525.2	92	70-130		
	INDENO(1,2,3-CD)PYRENE	0.95	1	ug/L	525.2	95	70-130		
	LINDANE (BHC - GAMMA)	0.97	1	ug/L	525.2	97	70-130		
	MALATHION	1.01	1	ug/L	525.2	101	70-130		
	METHOXYCHLOR	1.08	1	ug/L	525.2	108	70-130		
	METOLACHLOR	1.06	1	ug/L	525.2	106	70-130		
	METRIBUZIN	0.81	1	ug/L	525.2	81	70-130		
	PARATHION	0.83	1	ug/L	525.2	83	70-130		
	PENTACHLOROPHENOL	4.87	4	ug/L	525.2	122	70-130		
	PERYLENE-D12 (Surr)	101		%	525.2		70-130		
	PHENANTHRENE	1	1	ug/L	525.2	100	70-130		
	PROPACHLOR	1.02	1	ug/L	525.2	102	70-130		
	PYRENE	1	1	ug/L	525.2	100	70-130	ē	
	PYRENE-D10 (Surr)	94		%	525.2	•	70-130		

^{*}Notation:

[%] Recovery = (Result of Analysis)/(True Value) * 100

NA = Indicates % Recovery could not be calculated.

QCS: Quality Control Sample, a solution containing known concentrations of method analytes which is used to fortify an aliquot of reagent matrix. The QCS is obtained from an external source and is used to check lab performance.

LFB: Laboratory Fortified Blank, an aliquot of reagent matrix to which known quantities of method analytes are added in the tab. The LFB is analyzed exactly like a sample, and its purpose is to determine whether method performance is within accepted control limits.

MB or LRB: Method Blank or Laboratory Reagent Blank, an aliquot of reagent matrix is analyzed exactly like a sample, and its purpose is to determine if there is background contamination.



Burlington WA | 1620 S Walnut St - 98233 Corporate Office

800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225 360.671.0688 • 360.671.1577fax Page 3 of 12



SAMPLE INDEPENDENT **QUALITY CONTROL REPORT**

Laboratory Fortified Blank

Reference Number: 08-07095

			True			%		QC	
Batch	Analyte	Result	Value	Units	Method	Recovery	Limits	Qualifier Type*	Comment
525_080609	SIMAZINE	0.96	1	ug/L	525.2	96	70-130	LFB	
•	TERBACIL	0.99	1	ug/L	525.2	99	70-130	_	
	TRIFLURALIN	0.91	1	ug/L	525.2	91	70-130		
	TRIPHENYLPHOSPHATE (Surr)	100		%	525.2		70-130		
525X_080609	1-NAPHTHALENEACETAMIDE	2.37	2	ug/L	525.2	119	70-130	LFB	
	CHLORPYRIFOS	0.84	1	ug/L	525.2	84	70-130		
	DICOFOL	2.09	2	ug/L	525.2	105	70-130		
	FENARIMOL	0.9	1	ug/L	525.2	90	70-130		
	HEXAZINONE	1.2	1	ug/L	525.2	120	70-130		
	METALAXYL	2.01	2	ug/L	525.2	101	70-130		
	METHIDATHINON	2.18	2	ug/L	525.2	109	85-115		
	MEVINPHOS	0.99	1	ug/L	525.2	99	70-130		
	MYCLOBUTANIL	2.54	2	ug/L	525.2	127	85-115		
	NAPROPAMIDE	0.59	1	ug/L	525.2	59	70-130		
	PHOSMET	2.04	2	ug/L	525.2	102	70-130		
	PROPARGITE	2.16	2	ug/L	525.2	108	85-115		
	TRIADIMEFON	0.73	1	ug/L	525.2	73	70-130		
	TRIFLUMIZOLE ;	1.68	2	ug/L	525.2	84	85-115		
531_080611	3-HYDROXYCARBOFURAN	9.3	10	ug/L	531.2	93	70-130	LFB	
	ALDICARB	8.5	10	ug/L	531.2	85	70-130		
	ALDICARB SULFONE	8.8	10	ug/L	531.2	88	70-130		
	ALDICARB SULFOXIDE	8.3	10	ug/L	531.2	83	70-130		
	CARBARYL	9.3	10	ug/L	531.2	93	70-130		
	CARBOFURAN	9.4	10	ug/L	531.2	94	70-130		
	METHIOCARB	9.1	10	ug/L	531.2	91	70-130		
	METHOMYL	10	10	ug/L	531.2	100	70-130		
	OXYMAL	9.3	10	ug/L	531.2	93	70-130		
	PROPOXUR (BAYGON)	9.5	10	ug/L	531.2	95	70-130		
531_080611	3-HYDROXYCARBOFURAN	20	20	ug/L	531.2	100	70-130	LFB	
	ALDICARB	19	20	ug/L	531.2	95	70-130		
	ALDICARB SULFONE	19	20	ug/L	531.2	95	70-130	•	
	ALDICARB SULFOXIDE	18	20	ug/L	531.2	90	70-130		

[%] Recovery = (Result of Analysis)/(True Value) * 100

NA = Indicates % Recovery could not be calculated.

QCS: Quality Control Sample, a solution containing known concentrations of method analytes which is used to fortify an aliquot of reagent matrix. The QCS is obtained from an external source and

LFB: Laboratory Fortified Blank, an aliquot of reagent matrix to which known quantities of method analytes are added in the lab. The LFB is analyzed exactly like a sample, and its purpose is to determine whether method performance is within accepted control limits.

MB or LRB: Method Blank or Laboratory Reagent Blank, an aliquot of reagent matrix is analyzed exactly like a sample, and its purpose is to determine if there is background contamination.



Corporate Office 800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225 Microbiology 360.671.0688 • 360.671.1577fax Page 4 of 12



SAMPLE INDEPENDENT QUALITY CONTROL REPORT

Laboratory Fortified Blank

Reference Number: 08-07095 Report Date: 07/09/08

			True			%		QC	
Batch	Analyte	Result	Value	Units	Method	Recovery	Limits	Qualifier Type*	Comment
531_080611	CARBARYL	19.5	20	ug/L	531.2	98	70-130	LFB	
*	CARBOFURAN	20	20	ug/L	531.2	100	70-130	-	
	METHIOCARB	19	20	ug/L	531.2	95	70-130		
	METHOMYL	21	20	ug/L	531.2	105	70-130		
	OXYMAL	19.5	20	ug/L	531.2	98	70-130		
	PROPOXUR (BAYGON)	20	20	ug/L	531.2	100	70-130		
531_080611	3-HYDROXYCARBOFURAN	1 -	1	ug/L	531.2	100	70-130	LFB	
	ALDICARB	0.6	1	ug/L	531.2	60	70-130		Limits 50-150% at PQL
	ALDICARB SULFONE	0.75	1	ug/L	531.2	75	70-130		
	ALDICARB SULFOXIDE	1	1	ug/L	531.2	100	70-130	•	
	CARBARYL	0.9	1	ug/L	531.2	90	70-130		
	CARBOFURAN	1	1	ug/L	531.2	100	70-130		
	METHIOCARB	1	1	ug/L	531.2	100	70-130		
	METHOMYL	8.0	1	ug/L	531.2	08	70-130		
	OXYMAL	1	1	ug/L	531.2	100	70-130		
	PROPOXUR (BAYGON)	1	1	ug/L	531.2	100	70-130		
549_080603	PARAQUAT ;	14.1	20	ug/L	549.2	71	70-130	LFB	
COD_080604	CHEMICAL OXYGEN DEMAND	51	50	mg/L	SM5220 D	102	80-120	LFB	
OPHOS-080528	ORTHO-PHOSPHATE	1.02	1.00	mg/L	SM4500-P F	102	70-130	LFB	
tds_080602	TOTAL DISSOLVED SOLIDS	500	500	mg/L	SM2540 C	100	80-120	LFB	
tds080602	TOTAL DISSOLVED SOLIDS	488	500	mg/L	SM2540 C	98	80-120	LFB	
tds_080602	TOTAL DISSOLVED SOLIDS	523	500	mg/L	SM2540 C	105	80-120	LFB	

[&]quot;Notation:

[%] Recovery = (Result of Analysis)/(True Value) * 100

NA = Indicates % Recovery could not be calculated.

QCS: Quality Control Sample, a solution containing known concentrations of method analytes which is used to fortify an aliquot of reagent matrix. The QCS is obtained from an external source and is used to check lab performance.

LFB: Laboratory Fortified Blank, an aliquot of reagent matrix to which known quantities of method analytes are added in the lab. The LFB is analyzed exactly like a sample, and its purpose is to determine whether method performance is within accepted control limits.

MB or LRB: Method Blank or Laboratory Reagent Blank, an aliquot of reagent matrix is analyzed exactly like a sample, and its purpose is to determine if there is background contamination.



Burlington WA | 1620 S Walnut St - 98233 Corporale Office

800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225 360.671.0688 • 360.671.1577fax Page 5 of 12



SAMPLE INDEPENDENT QUALITY CONTROL REPORT

Laboratory Reagent Blank

Reference Number: 08-07095

			Тгие			%	QC	
Batch	Analyte	Result	Value	Units	Method	Recovery Limits	Qualifier Type*	Comment
200.7-080530A	HARDNESS	ND		mg/L	200.7	10.00	DOC LRB	352500
317_080606A	BROMATE	ND		ug/L	317.0	0.000	00 LRB	
317_080611A	BROMATE	ND		ug/L	317.0	0.000	00 LRB	
317_080612A	BROMATE	ND		ug/L	317.0	0.000	00 LRB	
COD_080604	CHEMICAL OXYGEN DEMAND	ND		mg/L	SM5220 D	4.000	00 LRB	
1080528A	CHLORIDE	ND		mg/L	300.0	0.100	00 LRB	
OPHOS-080528	ORTHO-PHOSPHATE	ND		mg/L	SM4500-P F	0.100	00 LRB	

^{*}Notation:

[%] Recovery = (Result of Analysis)/(True Value) * 100

NA = Indicates % Recovery could not be calculated.

QCS: Quality Control Sample, a solution containing known concentrations of method analytes which is used to fortify an aliquot of reagent matrix. The QCS is obtained from an external source and is used to check lab performance.

LFB: Laboratory Fortified Blank, an aliquot of reagent matrix to which known quantities of method analytes are added in the lab. The LFB is analyzed exactly like a sample, and its purpose is to determine whether method performance is within accepted control limits.

MB or LRB: Method Blank or Laboratory Reagent Blank, an aliquot of reagent matrix is analyzed exactly like a sample, and its purpose is to determine if there is background contamination.



Burlington WA | 1620 S Walnut St - 98233 Corporate Office

800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225 360.671.0688 • 360.671.1577fax Page 6 of 12



SAMPLE INDEPENDENT QUALITY CONTROL REPORT

Method Blank

Reference Number: 08-07095

AROCLOR 1016				True			%		QC	
SOB_08089 AROCLOR 1016 ND	Batch	Analyte	Result	Value	Units	Method	Recovery	Limits	Qualifier Type*	Comment
AROCLOR 1221 ND ug/L 508.1 0.12000 AROCLOR 1232 ND ug/L 508.1 0.02000 AROCLOR 1242 ND ug/L 508.1 0.02000 AROCLOR 1248 ND ug/L 508.1 0.02000 AROCLOR 1248 ND ug/L 508.1 0.02000 AROCLOR 1254 ND ug/L 508.1 0.02000 AROCLOR 1254 ND ug/L 508.1 0.02000 AROCLOR 1254 ND ug/L 508.1 0.02000 TETRACHLORO-M-XYLENE (SURR) 86 508.1 0.00000 TETRACHLORO-M-XYLENE (SURR) 86 508.1 0.00000 ***Solid *	200.7-080530A	HARDNESS	ND		mg/L	200.7		0.82000	MB	
AROCLOR 1221 ND ug/L 508.1 0.12000 AROCLOR 1232 ND ug/L 508.1 0.02000 AROCLOR 1242 ND ug/L 508.1 0.02000 AROCLOR 1248 ND ug/L 508.1 0.02000 AROCLOR 1248 ND ug/L 508.1 0.02000 AROCLOR 1254 ND ug/L 508.1 0.02000 AROCLOR 1254 ND ug/L 508.1 0.02000 AROCLOR 1254 ND ug/L 508.1 0.02000 TETRACHLORO-M-XYLENE (SURR) 86 508.1 0.00000 TETRACHLORO-M-XYLENE (SURR) 86 508.1 0.00000 ***Solid *									_	
AROCLOR 1221 ND ug/L 508.1 0.12000 AROCLOR 1232 ND ug/L 508.1 0.02000 AROCLOR 1242 ND ug/L 508.1 0.02000 AROCLOR 1248 ND ug/L 508.1 0.02000 AROCLOR 1248 ND ug/L 508.1 0.02000 AROCLOR 1254 ND ug/L 508.1 0.02000 AROCLOR 1254 ND ug/L 508.1 0.02000 AROCLOR 1254 ND ug/L 508.1 0.02000 TETRACHLORO-M-XYLENE (SURR) 86 508.1 0.00000 TETRACHLORO-M-XYLENE (SURR) 86 508.1 0.00000 ***Solid *	508 080609	AROCLOR 1016	ND		บสป	50B 1		ก กวกถก	MR	
AROCLOR 1232 ND ug/L 508.1 0.02000 AROCLOR 1242 ND ug/L 508.1 0.02000 AROCLOR 1248 ND ug/L 508.1 0.02000 AROCLOR 1248 ND ug/L 508.1 0.02000 AROCLOR 1254 ND ug/L 508.1 0.02000 AROCLOR 1254 ND ug/L 508.1 0.02000 TETRACHLOROM-XYLENE (SURR) 86 % 508.1 0.00000 515_080802 2,4 - D ND ug/L 515.1 0.05000 2,4 - DCAA (SURR) 110 % 515.1 0.50000 2,4,5 - TP (SILVEX) ND ug/L 515.1 0.10000 2,4,5 - TP (SILVEX) ND ug/L 515.1 0.10000 AGIFLUORFEN ND ug/L 515.1 0.50000 BENTAZON ND ug/L 515.1 0.50000 GHLORAMBEN ND ug/L 515.1 0.20000 CHLORAMBEN ND ug/L 515.1 0.50000 DIALAPON ND ug/L 515.1 0.50000 DICAMBA ND ug/L 515.1 0.50000 DICAMBA ND ug/L 515.1 0.50000 DICAMBA ND ug/L 515.1 0.50000 DICAMBA ND ug/L 515.1 0.50000 DICAMBA ND ug/L 515.1 0.50000 DICAMBA ND ug/L 515.1 0.50000 DICAMBA ND ug/L 515.1 0.50000 DICAMBA ND ug/L 515.1 0.50000 DICAMBA ND ug/L 515.1 0.50000 DICAMBA ND ug/L 515.1 0.50000 DICAMBA ND ug/L 515.1 0.50000 DICAMBA ND ug/L 515.1 0.00000 DICAMBA ND ug/L 515.1 0.00000 DICAMBA ND ug/L 515.1 0.00000 DICAMBA ND ug/L 515.1 0.00000 DICAMBA ND ug/L 515.1 0.00000 DICHORPOP ND ug/L 515.1 0.00000 DICHORPOP ND ug/L 515.1 0.00000 DICHORPOP ND ug/L 515.1 0.00000 DICHORPOP ND ug/L 515.1 0.00000 DICHORPOP ND ug/L 515.1 0.00000 DICHORPOP ND ug/L 515.1 0.00000 DICHORPOP ND ug/L 515.1 0.00000 DICHORPOP ND ug/L 515.1 0.00000 DICHORPOP ND ug/L 515.1 0.00000 DICHORPOP ND ug/L 515.1 0.00000 DICHORPOP ND ug/L 515.1 0.00000 DICHORPOP ND ug/L 515.1 0.00000 DICHORPOP ND ug/L 515.1 0.00000 DICHORPOP ND ug/L 515.1 0.00000 DICHORPOP ND ug/L 515.1 0.00000 DICHORPOP ND ug/L 515.1 0.00000 DICHORPOP ND ug/L 515.1 0.00000 DICHORPOP ND ug/L 525.2 0.00000 DICHORPOP ND ug/L 525.2 0.00000	200_00000				_					
AROCLOR 1242 ND Ug/L 508.1 0.02000 AROCLOR 1248 ND Ug/L 508.1 0.02000 AROCLOR 1250 ND Ug/L 508.1 0.02000 TETRACHLORO-M-XYLENE (SURR) 86 % 508.1 0.02000 TETRACHLORO-M-XYLENE (SURR) 86 % 508.1 0.02000 TETRACHLORO-M-XYLENE (SURR) 86 % 508.1 0.02000 515_080602 2,4 - D ND Ug/L 515.1 0.05000 MB 2,4 - DCAA (SURR) 110 % 515.1 0.25000 2,4,5 - TP (SILVEX) ND Ug/L 515.1 0.10000 2,4,5 - TP (SILVEX) ND Ug/L 515.1 0.10000 36 ENTAZON ND Ug/L 515.1 0.10000 BENTAZON ND Ug/L 515.1 0.50000 GHLORAMBEN ND Ug/L 515.1 0.20000 GHLORAMBEN ND Ug/L 515.1 0.50000 DCALAPON ND Ug/L 515.1 0.50000 DCPA (ACID METABOLITES) ND Ug/L 515.1 0.50000 DICAMBA ND Ug/L 515.1 0.50000 DICAMBA ND Ug/L 515.1 0.0500000										
AROCLOR 1248 ND ug/L 508.1 0.02000 AROCLOR 1254 ND ug/L 508.1 0.02000 TETRACHLORO-M-XYLENE (SURR) 86 % 508.1 0.00000 515_080602 2,4 - D ND ug/L 515.1 0.00000 52,4 - DCAA (SURR) 110 % 515.1 0.00000 2,4 - DCAA (SURR) ND ug/L 515.1 0.00000 2,4 - DCAA (SURR) ND ug/L 515.1 0.10000 2,4,5 - TP (SILVEX) ND ug/L 515.1 0.10000 2,4,5 - TP (SILVEX) ND ug/L 515.1 0.10000 ACIPLUORFEN ND ug/L 515.1 0.50000 BENTAZON ND ug/L 515.1 0.50000 BENTAZON ND ug/L 515.1 0.20000 CHLORAMBEN ND ug/L 515.1 0.20000 DCPA (ACID METABOLITES) ND ug/L 515.1 0.00000 DCPA (ACID METABOLITES) ND ug/L 515.1 0.00000 DCPA (ACID METABOLITES) ND ug/L 515.1 0.00000 DICAMBA ND ug/L 515.1 0.00000 DICHLORPOP ND ug/L 515.1 0.00000 DICHLORPOP ND ug/L 515.1 0.00000 PENTACHLOROPHENOL ND ug/L 515.1 0.10000 PENTACHLOROPHENOL ND ug/L 515.1 0.00000 PENTACHLOROPHENOL ND ug/L 515.1 0.00000 PENTACHLOROPHENOL ND ug/L 515.1 0.00000 PICLORAM ND ug/L 515.1 0.00000 PICLORAM ND ug/L 515.1 0.00000 PICLORAM ND ug/L 515.1 0.00000 PICLORAM ND ug/L 515.1 0.00000 AUDINOSEB ND ug/L 515.1 0.00000 PICLORAM ND ug/L 515.1 0.00000 PICLORAM ND ug/L 515.1 0.00000 AUDINOSEB ND ug/L 515.1 0.00000 PICLORAM ND ug/L 515.1 0.00000 AUDINOSEB ND ug/L 515.1 0.00000 PICLORAM ND ug/L 515.1 0.00000 AUDINOSEB ND ug/L 515.1 0.00000 AUDINOSEB ND ug/L 515.1 0.00000 AUDINOSEB ND ug/L 515.1 0.00000 AUDINOSEB ND ug/L 515.1 0.00000 AUDINOSEB ND ug/L 515.1 0.00000 AUDINOSEB ND ug/L 515.1 0.00000 AUDINOSEB ND ug/L 515.1 0.00000 AUDINOSEB ND ug/L 515.1 0.00000 AUDINOSEB ND ug/L 515.1 0.00000 AUDINOSEB ND ug/L 515.1 0.00000 AUDINOSEB ND ug/L 515.1 0.00000 AUDINOSEB ND ug/L 515.1 0.00000 AUDINOSEB ND ug/L 515.1 0.00000 AUDINOSEB ND ug/L 515.1 0.00000 AUDINOSEB ND ug/L 515.1 0.00000 AUDINOSEB ND ug/L 515.1 0.00000 AUDINOSEB ND ug/L 515.1 0.00000 AUDINOSEB ND ug/L 515.1 0.00000										
AROCLOR 1254 AROCLOR 1258 ND Ug/L 508.1 0.02200 TETRACHLORO-M-XYLENE (SURR) 86 ND Ug/L 508.1 0.02000 TETRACHLORO-M-XYLENE (SURR) 86 ND Ug/L 515.1 0.05000 MB 2.4 - D AROCLOR 1250 ND Ug/L 515.1 0.05000 MB 2.4 - D AROCLOR (SURR) 110 % 515.1 0.25000 2.4.5 - TP (SILVEX) ND Ug/L 515.1 0.10000 2.4.5 - TP (SILVEX) ND Ug/L 515.1 0.10000 ACIFLUORTEN ND Ug/L 515.1 0.10000 CHLORAMBEN ND Ug/L 515.1 0.20000 CHLORAMBEN ND Ug/L 515.1 0.50000 DDCPA (ACID METABOLITES) ND Ug/L 515.1 0.50000 DICAMBA ND Ug/L 515.1 0.50000 DICAMBA ND Ug/L 515.1 0.50000 DICAMBA ND Ug/L 515.1 0.05000					_					
AROCLOR 1280 TETRACHLORO-M-XYLENE (SURR) 86 % 508.1 0.00000 MB 2.4 - DCAA (SURR) 110 % 515.1 0.05000 MB 2.4.5 - TP (SILVEX) ND 0.4.5 TP (SILVEX) ND 0.4.5 TP (SILVEX) ND 0.4.5 TP (SILVEX) ND 0.4.6 TF (SILVEX) ND 0.4.6 TF (SILVEX) ND 0.4.6 TF (SILVEX) ND 0.4.6 TF (SILVEX) ND 0.4.6 TF (SILVEX) ND 0.4.6 TF (SILVEX) ND 0.4.6 TF (SILVEX) ND 0.4.6 TF (SILVEX) ND 0.50000 0.500										
TETRACHLORO-M-XYLENE (SURR) 86 % 508.1 0.00000 515_080602 2,4 - D ND ug/L 515.1 0.05000 MB 2,4 - DCAA (SURR) 110 % 515.1 0.25000 2,4 - DCAA (SURR) 110 % 515.1 0.25000 2,4.5 - TP (SILVEX) ND ug/L 515.1 0.10000 2,4.5 - TP (SILVEX) ND ug/L 515.1 0.10000 2,4.5 T ND ug/L 515.1 0.50000 BENTAZON ND ug/L 515.1 0.50000 BENTAZON ND ug/L 515.1 0.50000 CHLORAMBEN ND ug/L 515.1 0.50000 CHLORAMBEN ND ug/L 515.1 0.50000 DALAPON ND ug/L 515.1 0.50000 DCPA (ACID METABOLITES) ND ug/L 515.1 0.10000 DICAMBA ND ug/L 515.1 0.10000 DICAMBA ND ug/L 515.1 0.10000 DICHORPROP ND ug/L 515.1 0.10000 DINOSEB ND ug/L 515.1 0.10000 PENTACHLOROPHENOL ND ug/L 515.1 0.05000 PENTACHLOROPHENOL ND ug/L 515.1 0.05000 TOTAL (DCPA & Metabolites) ND ug/L 515.1 0.050000 1,3-DIMETHYL-2-NITROBENZENE (Surr) 97 % 525.2 MB					-					
2.4 - D					_					
2.4 - DCAA (SURR) 2.4 DB ND Ug/L 515.1 0.25000 2.4.5 - TP (SILVEX) ND Ug/L 515.1 0.10000 2.4.5 T ND Ug/L 515.1 0.10000 0.2.4.5 T ND Ug/L 515.1 0.50000 0.5000 0.50000		TETTA COTACOTA IN ATTEMPT (COTAC)	00		70	300.1		0.00000		
2.4 - DCAA (SURR) 2.4 DB ND Ug/L 515.1 0.25000 2.4.5 - TP (SILVEX) ND Ug/L 515.1 0.10000 2.4.5 T ND Ug/L 515.1 0.10000 0.2.4.5 T ND Ug/L 515.1 0.50000 0.5000 0.50000										
2.4 DB ND ug/L 515.1 0.25000 2.4.5 - TP (SILVEX) ND ug/L 515.1 0.10000 2.4.5 T ND ug/L 515.1 0.10000 2.4.5 T ND ug/L 515.1 0.10000 ACIFLUORFEN ND ug/L 515.1 0.50000 BENTAZON ND ug/L 515.1 0.2000 CHLORAMBEN ND ug/L 515.1 0.2000 DALAPON ND ug/L 515.1 0.50000 DICAMBA ND ug/L 515.1 0.50000 DICAMBA ND ug/L 515.1 0.05000 DICHLORPROP ND ug/L 515.1 0.10000 DICHLORPROP ND ug/L 515.1 0.10000 DINOSEB ND ug/L 515.1 0.10000 PENTACHLOROPHENOL ND ug/L 515.1 0.10000 PENTACHLOROPHENOL ND ug/L 515.1 0.05000 TOTAL (DCPA & Metabolites) ND ug/L 515.1 0.05000 TOTAL (DCPA & Metabolites) ND ug/L 515.1 0.05000 TOTAL (DCPA & Metabolites) ND ug/L 515.1 0.05000 TOTAL (DCPA & Metabolites) ND ug/L 515.1 0.05000 TOTAL (DCPA & Metabolites) ND ug/L 525.2 0.05000 4.4-DDE ND ug/L 525.2 0.05000	515_080602				ug/L	515.1		0.05000	MB	
2.4.5 - TP (SILVEX) 2.4.5 T ND Ug/L 515.1 0.10000 2.4.5 T ND Ug/L 515.1 0.50000 BENTAZON ND Ug/L 515.1 0.12000 CHLORAMBEN ND Ug/L 515.1 0.20000 DALAPON DCPA (ACID METABOLITES) ND Ug/L DICHLORPROP ND Ug/L 515.1 0.050000 DICHLORPROP ND Ug/L 515.1 0.10000 DINOSEB ND Ug/L 515.1 0.12000 DINOSEB ND Ug/L 515.1 0.12000 DINOSEB ND Ug/L 515.1 0.10000 DICLORAM ND Ug/L 515.1 0.10000 DIOSEB ND Ug/L 515.1 0.10000 DIOSEB ND Ug/L 515.1 0.10000 PENTACHLOROPHENOL ND Ug/L 515.1 0.02000 PICLORAM ND Ug/L 515.1 0.02000 PICLORAM ND Ug/L 515.1 0.02000 PICLORAM ND Ug/L 515.1 0.05000 TOTAL (DCPA & Metabolites) ND Ug/L 515.1 0.05000 MB		•			%	515.1				
2,4,5 T ND ug/L 515.1 0.10000 ACIFLUORFEN ND ug/L 515.1 0.50000 BENTAZON ND ug/L 515.1 0.12000 CHLORAMBEN ND ug/L 515.1 0.20000 DALAPON ND ug/L 515.1 0.50000 DCPA (ACID METABOLITES) ND ug/L 515.1 0.10000 DICAMBA ND ug/L 515.1 0.050000 DICHLORPROP ND ug/L 515.1 0.050000 DIONOSEB ND ug/L 515.1 0.10000 PENTACHLOROPHENOL ND ug/L 515.1 0.10000 PENTACHLOROPHENOL ND ug/L 515.1 0.00000 PICLORAM ND ug/L 515.1 0.00000 TOTAL (DCPA & Metabolites) ND ug/L 515.1 0.00000 TOTAL (DCPA & Metabolites) ND ug/L 515.1 0.00000 TOTAL (DCPA & Metabolites) ND ug/L 515.1 0.00000 TOTAL (DCPA & Metabolites) ND ug/L 515.1 0.00000 TOTAL (DCPA & Metabolites) ND ug/L 525.2 0.05000 4,4-DDD ND ug/L 525.2 0.05000 4,4-DDE ND ug/L 525.2 0.05000					ug/L	515.1		0.25000		
ACIFLUORFEN ND ug/L 515.1 0.50000 BENTAZON ND ug/L 515.1 0.12000 CHLORAMBEN ND ug/L 515.1 0.20000 DALAPON ND ug/L 515.1 0.50000 DCPA (ACID METABOLITES) ND ug/L 515.1 0.10000 DICAMBA ND ug/L 515.1 0.050000 DICAMBA ND ug/L 515.1 0.12000 DICHLORPROP ND ug/L 515.1 0.12000 DINOSEB ND ug/L 515.1 0.10000 PENTACHLOROPHENOL ND ug/L 515.1 0.00000 PICLORAM ND ug/L 515.1 0.00000 PICLORAM ND ug/L 515.1 0.00000 TOTAL (DCPA & Metabolites) ND ug/L 515.1 0.00000 1,3-DIMETHYL-2-NITROBENZENE (Surr) 97 % 525.2 MB 4,4-DDD ND ug/L 525.2 0.05000 4,4-DDE ND ug/L 525.2 0.05000		2,4,5 - TP (SILVEX)	ND		ug/L	515.1		0.10000		
BENTAZON ND ug/L 515.1 0.12000 CHLORAMBEN ND ug/L 515.1 0.20000 DALAPON ND ug/L 515.1 0.50000 DCPA (ACID METABOLITES) ND ug/L 515.1 0.10000 DICAMBA ND ug/L 515.1 0.05000 DICHLORPROP ND ug/L 515.1 0.12000 DINOSEB ND ug/L 515.1 0.10000 PENTACHLOROPHENOL ND ug/L 515.1 0.10000 PICLORAM ND ug/L 515.1 0.02000 PICLORAM ND ug/L 515.1 0.05000 TOTAL (DCPA & Metabolites) ND ug/L 515.1 0.05000 TOTAL (DCPA & Metabolites) ND ug/L 515.1 0.02000 525_080609 1,3-DIMETHYL-2-NITROBENZENE (Surr) 97 % 525.2 MB 4,4-DDD ND ug/L 525.2 0.05000 4,4-DDE ND ug/L 525.2 0.05000		2,4,5 T	ND		ug/L	515.1		0.10000		
CHLORAMBEN DALAPON ND Ug/L 515.1 0.20000 DCPA (ACID METABOLITES) ND Ug/L 515.1 0.10000 DICAMBA ND Ug/L 515.1 0.10000 DICHLORPROP ND Ug/L 515.1 0.12000 DICHLORPROP ND Ug/L 515.1 0.12000 DINOSEB ND Ug/L 515.1 0.10000 PENTACHLOROPHENOL ND Ug/L 515.1 0.02000 PICLORAM ND Ug/L 515.1 0.02000 PICLORAM ND Ug/L 515.1 0.02000 PICLORAM ND Ug/L 515.1 0.02000 MB 4.4-DDD ND Ug/L 525.2 0.05000 MB		ACIFLUORFEN	ND		ug/L	515.1		0.50000		
DALAPON ND ug/L 515.1 0.50000 DCPA (ACID METABOLITES) ND ug/L 515.1 0.10000 DICAMBA ND ug/L 515.1 0.05000 DICHLORPROP ND ug/L 515.1 0.12000 DINOSEB ND ug/L 515.1 0.10000 PENTACHLOROPHENOL ND ug/L 515.1 0.02000 PICLORAM ND ug/L 515.1 0.05000 TOTAL (DCPA & Metabolites) ND ug/L 515.1 0.02000 **TOTAL (DCPA & Metabolites) ND ug/L 525.2 0.05000 4.4-DDD ND ug/L 525.2 0.05000 4.4-DDT ND ug/L 525.2 0.05000		BENTAZON ;	ND		ug/L	515.1		0.12000		
DCPA (ACID METABOLITES) DICAMBA ND Ug/L 515.1 0.10000 DICHLORPROP ND Ug/L 515.1 0.12000 DINOSEB ND Ug/L 515.1 0.12000 DINOSEB ND Ug/L 515.1 0.02000 PENTACHLOROPHENOL ND Ug/L 515.1 0.02000 PICLORAM ND Ug/L 515.1 0.05000 TOTAL (DCPA & Metabolites) ND Ug/L 515.1 0.02000 MB 525_080609 1,3-DIMETHYL-2-NITROBENZENE (Surr) ND Ug/L 525.2 0.05000 4,4-DDE 4,4-DDT ND Ug/L 525.2 0.05000		CHLORAMBEN	ND		ug/L	515.1		0.20000		
DICAMBA ND Ug/L 515.1 0.05000 DICHLORPROP ND Ug/L 515.1 0.12000 DINOSEB ND Ug/L 515.1 0.10000 PENTACHLOROPHENOL ND Ug/L 515.1 0.02000 PICLORAM ND Ug/L 515.1 0.02000 PICLORAM TOTAL (DCPA & Metabolites) ND Ug/L 515.1 0.02000 MB 4,4-DDD ND Ug/L 525.2 0.05000 4,4-DDE ND Ug/L 525.2 0.05000		DALAPON	ND		ug/L	515.1		0.50000		
DICHLORPROP ND ug/L 515.1 0.12000 DINOSEB ND ug/L 515.1 0.10000 PENTACHLOROPHENOL ND ug/L 515.1 0.02000 PICLORAM ND ug/L 515.1 0.05000 TOTAL (DCPA & Metabolites) ND ug/L 515.1 0.02000 1,3-DIMETHYL-2-NITROBENZENE (Surr) 97 % 525.2 MB 4,4-DDD ND ug/L 525.2 0.05000 4,4-DDE ND ug/L 525.2 0.05000		DCPA (ACID METABOLITES)	ND		ug/L	515.1		0.10000		
DINOSEB ND ug/L 515.1 0.10000 PENTACHLOROPHENOL ND ug/L 515.1 0.02000 PICLORAM ND ug/L 515.1 0.05000 TOTAL (DCPA & Metabolites) ND ug/L 515.1 0.02000 MB 4,4-DDD ND ug/L 525.2 0.05000 4,4-DDE ND ug/L 525.2 0.05000 4,4-DDT ND ug/L 525.2 0.05000		DICAMBA	ND		ug/L	515.1		0.05000		
PENTACHLOROPHENOL ND ug/L 515.1 0.02000 PICLORAM ND ug/L 515.1 0.05000 TOTAL (DCPA & Metabolites) ND ug/L 515.1 0.02000 525_080609 1,3-DIMETHYL-2-NITROBENZENE (Surr) 97 % 525.2 MB 4,4-DDD ND ug/L 525.2 0.05000 4,4-DDE ND ug/L 525.2 0.05000 4,4-DDT ND ug/L 525.2 0.05000		DICHLORPROP	ND		ug/L	515.1		0.12000		
PICLORAM ND ug/L 515.1 0.05000 TOTAL (DCPA & Metabolites) ND ug/L 515.1 0.02000 1,3-DIMETHYL-2-NITROBENZENE (Surr) 97 % 525.2 MB 4,4-DDD ND ug/L 525.2 0.05000 4,4-DDE ND ug/L 525.2 0.05000 4,4-DDT ND ug/L 525.2 0.05000		DINOSEB	ND		ug/L	515.1		0.10000		
TOTAL (DCPA & Metabolites) ND ug/L 515.1 0.02000 1,3-DIMETHYL-2-NITROBENZENE (Surr) 97 % 525.2 MB 4,4-DDD 4,4-DDE ND ug/L 525.2 0.05000 4,4-DDT ND ug/L 525.2 0.05000		PENTACHLOROPHENOL	ND		ug/L	515.1		0.02000		
525_080609		PICLORAM	ND		ug/L	515.1		0.05000		
4,4-DDD ND ug/L 525.2 0.05000 4,4-DDE ND ug/L 525.2 0.05000 4,4-DDT ND ug/L 525.2 0.05000		TOTAL (DCPA & Metabolites)	ND		ug/L	515.1		0.02000		
4,4-DDD ND ug/L 525.2 0.05000 4,4-DDE ND ug/L 525.2 0.05000 4,4-DDT ND ug/L 525.2 0.05000										
4,4-DDE ND ug/L 525.2 0.05000 4,4-DDT ND ug/L 525.2 0.05000	525_080609	1,3-DIMETHYL-2-NITROBENZENE (Surr)	97		%	525.2			МВ	
4,4-DDT ND ug/L 525.2 0.05000		4,4-DDD	ND		ug/L	525.2	•	0.05000		
4,4-DDT ND ug/L 525.2 0.05000		4,4-DDE	ND		ug/L	525.2	\mathcal{N}_{g}^{r}	0.05000		
ACENAPHTHENE ND ug/L 525.2 0.05000		4,4-DDT	ND		ug/L	525.2				
		ACENAPHTHENE	ND		ug/L	525.2		0.05000		

^{*}Notation:

[%] Recovery = (Result of Analysis)/(True Value) * 100

NA = Indicates % Recovery could not be calculated.

QCS: Quality Control Sample, a solution containing known concentrations of method analytes which is used to fortify an aliquot of reagent matrix. The QCS is obtained from an external source and is used to check lab performance.

LFB: Laboratory Fortified Blank, an aliquot of reagent matrix to which known quantities of method analytes are added in the lab. The LFB is analyzed exactly like a sample, and its purpose is to determine whether method performance is within accepted control fimits.

MB or LRB: Method Blank or Laboratory Reagent Blank, an aliquot of reagent matrix is analyzed exactly like a sample, and its purpose is to determine if there is background contamination.



800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225 360.671.0688 • 360.671.1577fax Page 7 of 12



SAMPLE INDEPENDENT QUALITY CONTROL REPORT

Method Blank

Reference Number: 08-07095

			True			%	QC	
Batch	Analyte	Result	Value	Units	Method	Recovery Limits	Qualifier Type*	Comment
525_080609	ALACHLOR	ND		ug/L	525.2	0.0200	O MB	······································
	ALDRIN	ND		ug/L	525.2	0.0500	0	
	ANTHRACENE	ND		ug/L	525.2	0.0500	0	
	ATRAZINE	ND		ug/L	525.2	0.0200	10	
	BENZ(A)ANTHRACENE	ND		ug/L	525.2	0.0200	0	
	BENZO(A)PYRENE	ND		ug/L	525.2	0.0200	0	
	BENZO(B)FLUORANTHENE	ND		ug/L	525.2	0.0500	0	
	BENZO(G,H,I)PERYLENE	ND		ug/L	525.2	0.0500	0	
	BENZO(K)FLUORANTHENE	ND		ug/L	525.2	0.0500	0	
	BENZYL BUTYL PHTHALATE	ND		ug/L	525.2	0.6000	0	
	BROMACIL	ND		ug/L	525.2	0.0500	D	
	BUTACHLOR	ND		ug/L	525.2	0.1000	0	
	CHLORDANE, TECHNICAL	ND		ug/L	525.2	0.0200	0	
	CHRYSENE	ND		ug/L	525.2	. 0.0500	0	
	CYANAZINE	ND		ug/L	525.2	0.0500	0	
	DI(ETHYLHEXYL)-ADIPATE	ND		ug/L	525.2	0.0200	0	
	DI(ETHYLHEXYL)-PHTHALATE	0.13		ug/L	525.2	0.6000	0	
	DIAZINON	ND		ug/L	525.2	0.0500	0	
	DIBENZO(A,H)ANTHRACENE	ND		ug/L	525.2	0.0500	0	
	DIELDRIN ;	ND		ug/L	525.2	0.0500	0	
	DIETHYL PHTHALATE	ND		ug/L	525.2	0.6000	0	
	DIMETHYL PHTHALATE	ND		ug/L	525.2	0.6000	0	
	DI-N-BUTYL PHTHALATE	ND		ug/L	525.2	0.6000	0	
	ENDRIN	ND		ug/L	525.2	0.0200	0	
	EPTC	ND		ug/L	525.2	0.0700	0	
	FLUORANTHENE	ND		ug/L	525.2	0.0500	0	
	FLUORENE	ND		ug/L	525.2	0.0500	0	
	HEPTACHLOR	ND		ug/L	525.2	0.0200	0	
	HEPTACHLOR EPOXIDE	ND		ug/L	525.2	0.0200	0	
	HEXACHLOROBENZENE	ND		ug/L	525.2	0.0200	0	
	HEXACHLOROCYCLO-PENTADIENE	ND		ug/L	525.2	0.0200	0	
	INDENO(1,2,3-CD)PYRENE	ND		ug/L	525.2	0.0500	0	
	LINDANE (BHC - GAMMA)	ND		ug/L	525.2	0.0200	0	
	MALATHION	ND		ug/L	525.2	0.0500	0	
	METHOXYCHLOR	ND		ug/L	525.2	0.0200	0	
	METOLACHLOR	ND		ug/L	525.2	0.2500	0	

^{*}Notation:

[%] Recovery = (Result of Analysis)/(True Value) * 100

NA = Indicates % Recovery could not be calculated.

QCS: Quality Control Sample, a solution containing known concentrations of method analytes which is used to fortify an aliquot of reagent matrix. The QCS is obtained from an external source and is used to check lab performance.

LFB: Laboratory Fortified Blank, an aliquot of reagent matrix to which known quantities of method analytes are added in the lab. The LFB is analyzed exactly like a sample, and its purpose is to determine whether method performance is within accepted control limits.

MB or LRB: Method Blank or Laboratory Reagent Blank, an aliquot of reagent metrix is analyzed exactly like a sample, and its purpose is to determine if there is background contamination.



Corporate Office

Burlington WA 1620 S Walnut St - 98233

800.755.9295 • 360.757.1400 • 360.757.1402fax Bellingham WA 805 Orchard Dr Suite 4 - 98225

360.671.0688 • 360.671.1577tax

Page 8 of 12



SAMPLE INDEPENDENT QUALITY CONTROL REPORT

Method Blank

Reference Number: 08-07095

00

			True			%		QC	
Batch	Analyte	Result	Value	Units	Method	Recovery	Limits	Qualifier Type*	Comment
525_080609	METRIBUZIN	ND		ug/L	525.2		0.05000	MB	
,	NAPTHALENE	ND		ug/L	525.2		0.02000	•	
	PARATHION	ND		ug/L	525.2		0.05000		
	PENTACHLOROPHENOL	ND		ug/L	525.2		0.04000		
	PERYLENE-D12 (Surr)	95		%	525.2				
	PHENANTHRENE	ND		ug/L	525.2		0.05000		
	PROPACHLOR	ND		ug/L	525.2		0.05000		
	PYRENE	ND		ug/L	525.2		0.05000		
	PYRENE-D10 (Surr)	98		%	525.2				
	SIMAZINE	ND		ug/L	525.2		0.02000		
	TERBACIL	ND		ug/L	525.2		0.05000		
	TRIFLURALIN	ND		ug/L	525.2		0.05000		
	TRIPHENYLPHOSPHATE (Surr)	106		%	525.2				
						,			
525X_080609	1-NAPHTHALENEACETAMIDE	ND		ug/L	525.2		0.10000	MB	
	AZINPHOS-METHYL	ND		ug/L	525.2		0.00000		
	CHLORPYRIFOS	ND		ug/L	525.2		0.00000		
	DICOFOL	ND		ug/L	525.2		0.00000		
	DIMETHOATE ;	ND		ug/L	525.2		0.00000		
	FENARIMOL	ND		ug/L	525.2		0.00000		
	HEXAZINONE	ND		ug/L	525.2		0.00000		
	MALATHION	ND		ug/L	525.2		0.05000		
	METALAXYL	ND		ug/L	525.2		0.10000		
	METHIDATHINON	ND		ug/L	525.2		0.50000		
	METHYL PARATHION	ND		ug/L	525.2		0.00000		
	MEVINPHOS	ND		ug/L	525.2		0.00000		
	MYCLOBUTANIL	ND		ug/L	52 5.2		0.50000		
	NAPROPAMIDE	ND		ug/L	525.2		0.00000		
	PARATHION-ETHYL	ND		ug/L	525.2		0.05000		
	PHOSMET	ND		ug/L	525.2		0.10000		
	PROPARGITE	ND		ug/L	525.2		0.00000		
	TRIADIMEFON	ND		ug/L	525.2		0.00000		
	TRIFLUMIZOLE	ND		ug/L	525.2	- C.	1.00000		

^{*}Notation:

[%] Recovery = (Result of Analysis)/(True Value) * 100

NA = Indicates % Recovery could not be calculated.

QCS: Quality Control Sample, a solution containing known concentrations of method analytes which is used to fortify an aliquot of reagent matrix. The QCS is obtained from an external source and is used to check lab performance.

LFB: Laboratory Fortified Blank, an aliquot of reagent matrix to which known quantities of method analytes are added in the lab. The LFB is analyzed exactly like a sample, and its purpose is to determine whether method performance is within accepted control limits.

MB or LRB: Method Blank or Laboratory Reagent Blank, an aliquot of reagent matrix is analyzed exactly like a sample, and its purpose is to determine if there is background contamination.



Burlington WA | 1620 S Walnut St - 98233 Corporate Office

800.755.9295 • 360.757.1400 • 360.757.1402fax Bellingham WA 805 Orchard Dr Suite 4 - 98225

360.671.0688 • 360.671.1577fax

Page 9 of 12



SAMPLE INDEPENDENT QUALITY CONTROL REPORT

Method Blank

Reference Number: 08-07095

			True			%		QC	
Batch	Analyte	Result	Value	Units	Method	Recovery	Limits	Qualifier Type*	Comment
531_080611	3-HYDROXYCARBOFURAN	ND		ug/L	531.2	,	0.50000	MB	
	ALDICARB	ND		ug/L	531.2		0.25000	-	
	ALDICARB SULFONE	ND		ug/L	531.2		0.40000		
	ALDICARB SULFOXIDE	ND		ug/L	531.2		0.25000		
	CARBARYL	ND		ug/L	531.2		0.50000		
	CARBOFURAN	ND		ug/L	531.2		0.45000		
	METHIOCARB	ND		ug/L	531.2		1.00000		
	METHOMYL	ND		ug/L	531.2		0.25000		
	OXYMAL	ND		ug/L	531.2		1.00000		
	PROPOXUR (BAYGON)	ND		ug/L	531.2		0.25000		
549_080603	PARAQUAT	ND		ug/L	549.2		0.50000	MB	
ec_080602	ELECTRICAL CONDUCTIVITY	ND		uS/cm	SM2510 B		2.50000	МВ	
ec_080602	ELECTRICAL CONDUCTIVITY	ND		uS/cm	SM2510 B		2.50000	МВ	
ec_080602	ELECTRICAL CONDUCTIVITY	ND		uS/cm	SM2510 B		2.50000	МВ	
ec_080602	ELECTRICAL CONDUCTIVITY	ND		uS/cm	SM2510 B		2.50000	MB	
ec_080613	ELECTRICAL CONDUCTIVITY	ND		uS/cm	SM2510 B		2.50000	MB	
_				dorom	OWIZO TO D		2.00000	WID	
ec_080613	ELECTRICAL CONDUCTIVITY	ND		uS/cm	SM2510 B		2.50000	MB	
ec_080613	ELECTRICAL CONDUCTIVITY	ND		uS/cm	SM2510 B		2.50000	МВ	
ec_080613	ELECTRICAL CONDUCTIVITY	ND		uS/cm	SM2510 B		2.50000	MB	
OPHOS-080528	ORTHO-PHOSPHATE	ND		mg/L	SM4500-P F		0.10000	МВ	
tds_080602	TOTAL DISSOLVED SOLIDS	ND		mg/L	SM2540 C	eret g	2.50000	МВ	
tds_080602	TOTAL DISSOLVED SOLIDS	ND		mg/L	SM2540 C	•	2.50000	МВ	

^{*}Notation:

[%] Recovery = (Result of Analysis)/(True Value) * 100

NA = Indicates % Recovery could not be calculated.

QCS: Quality Control Sample, a solution containing known concentrations of method analytes which is used to fortify an aliquot of reagent matrix. The QCS is obtained from an external source and is used to check lab performance.

LFB: Laboratory Fortified Blank, an aliquot of reagent matrix to which known quantities of method analytes are added in the lab. The LFB is analyzed exactly like a sample, and its purpose is to determine whether method performance is within accepted control limits.

MB or LRB: Method Blank or Laboratory Reagent Blank, an aliquot of reagent matrix is analyzed exactly like a sample, and its purpose is to determine if there is background contamination.



Corporate Office 800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225 360.671.0688 • 360.671.1577fax

Page 10 of 12



SAMPLE INDEPENDENT QUALITY CONTROL REPORT

Method Blank

Reference Number: 08-07095

Report Date: 07/09/08

			True			%	QC	
Batch	Analyte	Result	Value	Units	Method	Recovery Limits	Qualifier Type*	Comment
tds_080602	TOTAL DISSOLVED SOLIDS	ND	MAPPINIA CONTRACTOR OF THE CON	mg/L	SM2540 C	2.5000) MB -	
turb_080528	TURBIDITY	ND		NTU	180.1	0.0200) MB	

*Notation:

[%] Recovery = (Result of Analysis)/(True Value) * 100

NA = Indicates % Recovery could not be calculated.

QCS: Quality Control Sample, a solution containing known concentrations of method analytes which is used to fortify an aliquot of reagent matrix. The QCS is obtained from an external source and is used to check lab performance.

LFB: Laboratory Fortified Blank, an aliquot of reagent matrix to which known quantities of method analytes are added in the lab. The LFB is analyzed exactly like a sample, and its purpose is to determine whether method performance is within accepted control limits.

MB or LRB: Method Blank or Laboratory Reagent Blank, an aliquot of reagent matrix is analyzed exactly like a sample, and its purpose is to determine if there is background contamination.



Corporate Office

Burlington WA | 1620 S Walnut St - 98233

800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225 360.671.0688 • 360.671.1577fax Page 11 of 12



SAMPLE INDEPENDENT QUALITY CONTROL REPORT

Quality Control Sample

Reference Number: 08-07095

			True			%		QC	
Batch	Analyte	Result	Value	Units	Method	Recovery	Limits	Qualifier Type*	Comment
200,7-080530A	HARDNESS	129	132.3	mg/L	200.7	98	80-120	QCS	
317_080606A	BROMATE	38.2	40.8	ug/L	317.0	94	70-130	QCS	
317_000000A	DIOMATE	2.00	40.0	ugre	011.0	0,	,,,,,,,,		
317_080611A	BROMATE	37.8	40.8	ug/L	317.0	93	70-130	QCS	
247 0000404	PROMATE	20	40.8		247.0	96	70-130	QCS	
317_080612A	BROMATE	39	40.0	ug/L	31,7.0	30	10-130	ų03	
531_080611	3-HYDROXYCARBOFURAN	36.7	34.2	ug/L	531.2	107	70-130	QCS	
	ALDICARB	27.4	26	ug/L	531.2	105	70-130		
	ALDICARB SULFONE	33.8	30	ug/L	531.2	113	70-130		
	ALDICARB SULFOXIDE	18.5	16.6	ug/L	531.2	111	70-130		
	CARBARYL	32.4	30	ug/L	531.2	108	70-130		
	CARBOFURAN	104	100	ug/L	531.2	104	70-130		
	METHIOCARB	65.6	90.1	ug/L	531.2	73	70-130		
	METHOMYL	60	60.1	ug/L	531.2	100	70-130		
	OXYMAL	46.7	44.2	ug/L	531.2	106	70-130		
	PROPOXUR (BAYGON)	83.9	80.3	ug/L	531.2	104	70-130		
	•			_					
549_080603	PARAQUAT	3.2	4.8	ug/L	549.2	67	70-130	QCS	
	•								
COD_080604	CHEMICAL OXYGEN DEMAND	138	133	mg/L	SM5220 D	104	80-120	QCS	
*****				_					
ec_080602	ELECTRICAL CONDUCTIVITY	175	169	u\$/cm	SM2510 B	104	80-120	QCS	
ec_080602	ELECTRICAL CONDUCTIVITY	175	169	uS/cm	SM2510 B	104	80-120	QCS	
ec_080602	ELECTRICAL CONDUCTIVITY	173	169	υS/cm	SM2510 B	102	80-120	QCS	
ec 080602	ELECTRICAL CONDUCTIVITY	172	169	uS/cm	SM2510 B	102	80-120	'QCS	
20_000002	man menters were to the property theory and the man and and the test of			acron			20		

^{*}Notation:

[%] Recovery = (Result of Analysis)/(True Value) * 100

NA = Indicates % Recovery could not be calculated.

QCS: Quality Control Sample, a solution containing known concentrations of method analytes which is used to fortify an aliquot of reagent matrix. The QCS is obtained from an external source and is used to check lab performance.

LFB: Laboratory Fortified Blank, an aliquot of reagent matrix to which known quantities of method analytes are added in the lab. The LFB is analyzed exactly like a sample, and its purpose is to determine whether method performance is within accepted control limits.

MB or LRB: Method Blank or Laboratory Reagent Blank, an aliquot of reagent matrix is analyzed exactly like a sample, and its purpose is to determine if there is background contamination.



Burlington WA Corporate Office

Microbiology

1620 S Walnut St - 98233

800.755.9295 • 360.757.1400 • 360.757.1402fax Bellingham WA 805 Orchard Dr Suite 4 - 98225

360.671.0688 • 360.671.1577fax

Page 12 of 12



SAMPLE INDEPENDENT QUALITY CONTROL REPORT

Quality Control Sample

Reference Number: 08-07095

			True			%		QC	
Batch	Analyte	Result	Value	Units	Method	Recovery	Limits	Qualifier Type*	Comment
*		A PARLEMENT OF THE PROPERTY OF THE PARLE OF						\ <u>\</u>	
ec_080613	ELECTRICAL CONDUCTIVITY	168	169	uS/cm	SM2510 B	99	80-120	QCS	
ec_080613	ELECTRICAL CONDUCTIVITY	168	169	uS/cm	SM2510 B	99	80-120	acs	
ec_080613	ELECTRICAL CONDUCTIVITY	168	169	uS/cm	SM2510 B	99	80-120	qcs	
ec_080613	ELECTRICAL CONDUCTIVITY	168	169	uS/cm	SM2510 B	99	80-120	QCS	
I080528A	CHLORIDE	29.1	30.0	mg/L	300.0	97	80-120	QCS	
OPHOS-080528	ORTHO-PHOSPHATE	0.50	0.49	mg/L	SM4500-P F	102	70-130	QCS	
						•			
ph_080528	HYDROGEN ION (pH)	8.09	8.00	pH Units	SM4500-H+ B	101	80-120	QCS	
	HYDROGEN ION (pH)	8.20	8.00	pH Units	SM4500-H+ B	103	80-120		
ph_080528	HYDROGEN ION (pH)	8.19	8.00	pH Units	SM4500-H+ B	102	80-120	qcs	
	ì								
turb_080528	TURBIDITY	1.00	1.00	NTU	180.1	100	70-130	qcs	

^{*}Notation:

[%] Recovery = (Result of Analysis)/(True Value) * 100

NA = Indicates % Recovery could not be calculated.

QCS: Quality Control Sample, a solution containing known concentrations of method analytes which is used to fortify an aliquot of reagent matrix. The QCS is obtained from an external source and is used to check lab performance.

LFB: Laboratory Fortified Blank, an aliquot of reagent matrix to which known quantities of method analytes are added in the lab. The LFB is analyzed exactly like a sample, and its purpose is to determine whether method performance is within accepted control limits.

MB or LRB; Method Blank or Laboratory Reagent Blank, an aliquot of reagent matrix is analyzed exactly like a sample, and its purpose is to determine if there is background contamination.



800,755.9295 • 360.757.1400 • 360.757.1402fax Bellingham WA 805 Orchard Dr Suite 4 - 98225 Merchiniogy 360.671.0688 • 360.671.1577fax Burlington WA 1620 S Walnut St - 98233 coporate Office 800,755,9295 • 360,755.1



Page 1 of 6

Reference Number: 08-07095

Report Date: 7/9/2008

QUALITY CONTROL REPORT

Duplicate and Matrix Spike/Matrix Spike Duplicate Report

Duplicate			į					
			Duplicate			σ	ac	
Batch	Sample Analyte	Result	Result	Units	%RPD Limits		Qualifier	Comments
200.7-080530A				WARRANTA THE TAXABLE THE TAXAB				
	15125 HARDNESS	156	156	mg CaCO3/L	0.0	0-45	DUP	
	15169 HARDNESS	79.8	81.1	mg CaCO3/L	1.6	0-45	PUG	
317_080606A								
317_080611A								
317_080612A								
	15036 BROMATE	6.5	6.7	ng/L	3.0	0-20	DUP	
515_080602								
525_080609								
l	15132 1,3-DIMETHYL-2-NITROBENZENE (Sur	98	96	%	2:1	0-45	PUP	
	15132 PYRENE-D10 (Surt)	96	98	%	0.0	545	PUP	
	15132 PERYLENE-D12 (Surr)	103	102	%	1.0	0-45	DUP	
	15132 TRIPHENYLPHOSPHATE (Surt)	108	112	%	3.6	0-45	DUP	
	15132 1,3-DIMETHYL-2-NITROBENZENE (Sur	98	96	. %	2.1	0-45	P	
	15132 PYRENE-D10 (Surr)	96	96	%	0.0	0.45	DUP	
	15132 PERYLENE-D12 (Surr)	103	102	%	1.0	0-45	DUP	
	15132 TRIPHENYLPHOSPHATE (Surr)	108	112	%	3.6	0-45	DUP	
525X_080609	15132 BISPHENOL-A	0.6	0.6	ug/L	0.0	0-20	DUP	
COD_080604								
	15260 CHEMICAL OXYGEN DEMAND	8900	8850	mg/L	9.0	0-45	DUP	
EC_080602								
	15127 ELECTRICAL CONDUCTIVITY	129	129	ns/sm	0.0	0-45	DUP	
	15147 ELECTRICAL CONDUCTIVITY	400	403	uS/cm	0.7	0-45	DUP	
	15483 ELECTRICAL CONDUCTIVITY	732	732	uS/cm	0.0	0-45	DUP	
EC_080613		č	, C		(- (
	16628 ELECTRICAL CONDUCTIVITY	505	301	us/sm	0:0	3	DOP	

%RPD = Relative Percent Difference

NA = Indicates %RPD could not be calculated

Matrix Spike (MS)/Matrix Spike Duplicate (MSD) analyses are used to determine the accuracy (MS) and precision (MSD) of a analytical method in a given sample matrix. Therefore, the usefulness of this report is limited to samples of similar matrices analyzed in the same analytical batch.

Only Duplicate sample with detections are listed in this report



Reference Number: 08-07095 Report Date: 7/9/2008

σ

Page 2 of

Duplicate

Comments B PUP PUP 물 PUP PUP 占 7 100 100 DUP 吕 Qualifier 8 Limits 0-45 0-45 3 0-45 0-45 0-45 0-20 0-20 0-50 0-20 0-50 0-20 %RPD 0.0 0.0 0.1 0.0 3.1 0.7 pH Units pH Units uS/cm ш2/Sn Units mg/L mg/L mg/L mg/L mg/L mg/≟ mg/L mg/L Duplicate Result 0.04 1.10 0.33 6.70 0.23 743 0.54 237 31 Result 0.54 0.32 6.75 8.10 1.7 0.23 744 237 31 16978 ELECTRICAL CONDUCTIVITY 17042 ELECTRICAL CONDUCTIVITY 15133 ORTHO-PHOSPHATE ORTHO-PHOSPHATE 15060 ORTHO-PHOSPHATE 15131 HYDROGEN ION (pH) 15169 HYDROGEN ION (pH) 15050 NITRATE-N 15060 NITRATE-N 15133 NITRATE-N 15147 CHLORIDE 15169 CHLORIDE Sample Analyte 15128 NO3NO2-080528 OPHOS-080528 PH_080528 1080528A Batch

0-45

5

2.5

mg/l⁻ mg/l

117

120 50

TOTAL DISSOLVED SOLIDS 15509 TOTAL DISSOLVED SOLIDS

15133

TDS_080602

95 95

0-20

0-20

2.8

E E

5.15

8.22

8.45

15133 TURBIDITY 15147 TURBIDITY

TURB_080528

[%]RPD = Relative Percent Difference

NA = Indicates %RPD could not be calculated

Matrix Spike (MS)/Matrix Spike Duplicate (MSD) analyses are used to determine the accuracy (MS) and precision (MSD) of a analytical method in a given sample matrix. Therefore, the usefulness of this report is limited to samples of similar matrices analyzed in the same analytical batch.



Page 3 of 6

Reference Number: 08-07095 Report Date: 7/9/2008

Simple Analyte	Matrix Spike	oike			Duplicate										
Simple Analyse Size Horoverse Rosal				Spike	Spike	Spike		Percent F	Recovery				၁၀		
1512B HARDNESS 156 220 221 685 mg CaCO30L 25 94 60-120 15 66 66 1647B BROMATE ND 3.3 146 146 985 mg CaCO30L 85 96 60-120 0.0 60 60 1637B BROMATE ND 7.6 10 ug/L 76 NA 70-130 NA 0-50 1593B BROMATE ND 1.0 ug/L 76 NA 70-130 NA 0-50 1592B BROMATE ND 1.0 ug/L 176 NA 70-130 NA 0-50 1592B BROMATE ND 1.0 1.0 ug/L 176 NA 70-130 NA 0-50 1592B BROMATE ND 1.0 1.0 ug/L 176 NA 70-130 NA 0-50 14221 LAG-L ND 1.1 1.0 ug/L 179 <td< th=""><th>Batch</th><th>Sample Analyte</th><th>Result</th><th>Result</th><th>Result</th><th>Conc</th><th>Units</th><th>MS</th><th>MSD</th><th>Limits</th><th>%RPD</th><th>Limits</th><th>Qualifier</th><th>ö</th><th>omments</th></td<>	Batch	Sample Analyte	Result	Result	Result	Conc	Units	MS	MSD	Limits	%RPD	Limits	Qualifier	ö	omments
15172 HARDNESS 158 220 221 695 mg CacCo34 95 95 691-720 15 0.60 4 4879 BROMATE ND 9.3 16 146	0.7-080530A														- TAN-AMAMAMAMAMAMAMAMAMAMAMAMAMAMAMAMAMAMA
4 (4578) BROMATE 146		15125 HARDNESS	156	220	221	69.5	тв СасОЗ/L	92	94	80-120	1.6	0-60		LFM	•
A 1477 B ROMATE ND 9.3 10.0 ug/L 76 NA 70-130 NA 0-50 A 1457 B ROMATE ND 7.8 10 ug/L 76 NA 70-130 NA 0-50 A 500 B ROMATE ND 7.8 10 ug/L 115 NA 70-130 NA 0-50 15572 B ROMATE ND 1.0 10.9 10 ug/L 118 NA 70-130 NA 0-50 1422 L 4-D ND 1.0 1.0 ug/L 118 NA 70-130 NA 0-50 1422 L 4-D ND 1.0 1.0 ug/L 118 NA 70-130 NA 0-50 1422 L 4-D ND 1.1 1.0 ug/L 118 NA 70-130 NA 0-50 1422 L 2-D ND 1.2 1 ug/L 118 NA 70-130 NA 0-50 1422 L 2-D ND 1.2 1 <		15169 HARDNESS	79.8	146	146	69.5	тв СаСОЗ/L	95	95	80-120	0.0	09-0		LFM	
A 15130 BROMATE ND 3.3 10.0 ugl. 33 NA 70-130 NA 0-60 4 5130 BROMATE ND 7.5 10 ugl. 78 NA 70-130 NA 0-60 4 5130 BROMATE ND 1.0 ugl. 115 NA 70-130 NA 0-60 1503 BROMATE ND 1.0 ugl. 116 ugl. 108 NA 70-130 NA 0-60 1422 LA-D ND 1.19 1 ugl. 118 NA 70-130 NA 0-60 1422 LA-D ND 1.19 1 ugl. 118 NA 0-60 A 0-60 1422 LA-D ND 1.19 1 ugl. 198 NA 0-60 A 0606A</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td>	7_080606A														
1573 BROMATE ND 7.6 10 ug/L 115 NA 70-130 NA 0-50 10 ug/L 115 NA 70-130 NA 0-50 10 ug/L 115 NA 70-130 NA 0-50 10 ug/L 115 NA 70-130 NA 0-50 10 ug/L 115 NA 70-130 NA 0-50 10 ug/L 115 NA 70-130 NA 0-50 10 ug/L 115 NA 70-130 NA 0-50 10 ug/L 115 NA 10-130 NA 0-50 10 ug/L 115 NA 0-50 10 u		14879 BRÖMATE	Q	9.3	ì	10.0	ng/L	93	NA	70-130	Ν	0-20		LFM	
4512 BROMATE ND 7.6 10 19/L 76 NA 70-130 NA 0-50 NA 1-50 NA	7_080611A														
A 1532 BROMATE		15130 BROMATE	P	7.6		10	ng/L	92	NA	70-130	ΑN	0-20		LFM	
1503B BROMATE 6.5 18 10 ug/L 155 NA 70-130 NA 6-5 15512 BROMATE ND 1.09 10.9 10.9 NA 70-130 NA 6-50 14221 24.5-TP (SILVEX) ND 2.16 2 ug/L 179 NA 65-135 NA 0-60 14221 24.5-TP (SILVEX) ND 1.19 1 ug/L 179 NA 65-135 NA 0-60 14221 DALLAPON ND 2.16 2 ug/L 179 NA 65-135 NA 0-60 14221 DALPON ND 2.81 2 ug/L 179 NA 6-60 AH 14221 DINOSEB ND 2.81 1 ug/L 178 NA 6-60 AH 0-60 14221 DINOSEB ND 1.65 1 ug/L 178 NA 6-61 AH 0-60	7_080612A														
14221 BROMATE ND 10.9 10 ug/L 109 NA 70-130 NA 6-50 14221 24-D Ug/L 119 NA 65-135 NA 6-60 14221 24-D Ug/L 119 NA 65-135 NA 6-60 14221 PAN ACHLOROPHENOL ND 1.19 1 ug/L 116 NA 65-135 NA 0-60 14221 PENTACHLOROPHENOL ND 1.26 1 ug/L 116 NA 65-135 NA 0-60 14221 DALAPON ND 1.21 1 ug/L 106 NA 65-135 NA 0-60 14221 DALADON ND 1.21 ug/L 105 NA 6-60 AH 14221 DALAMBA ND 1.19 1 ug/L 105 NA 0-60 14221 DALAMBA ND 1.10 1 ug/L 106 NA			6.5	48		10	ng/L	115	NA	70-130	Ą	0-20		LFM	
14221 2,4-D 14221 2,4-D 14221 PENTACHLOROPHENOL 10 1,169 1 1 ug/L 14221 DALAPON 14221		15512 BROMATE	9	10.9		10	ng/L	109	NA	70-130	AN	0-20		LFM	
44221 24D ND 216 2 ug/L 108 65-135 NA 65-136 NA 66-136 NA	5 080602														
44221 24.5 - TP (SILVEX) ND 1.19 N 65-135 NA 65-135 NA 66-035 44221 PENTAGHLOROPHENOL ND 1.06 1 ug/L 166 NA 65-135 NA 6-60 44221 DALADON ND 1.2.1 13 ug/L 142 NA 65-135 NA 0-60 14221 DICAMBA ND 1.05 1 ug/L 165 NA 65-135 NA 0-60 14221 DICAMBA ND 1.05 1 ug/L 165 NA 65-135 NA 0-60 14221 DICALORABA ND 1.05 1 ug/L 195 NA 65-135 NA 0-60 14221 DICALORABA ND 1.06 1 ug/L 135 NA 65-135 NA 0-60 14221 DICHLORABA ND 1.06 1 ug/L 13 NA 65-135 NA			Q	2.16		2	ng/L	108	ΝΑ	65-135	Ϋ́	0-60		LFM	
14221 PENTACHLOROPHENOL ND 1.06 1.0 1.0 1.0 1.0 09/L 99/L 96-135 NA 66-135 NA 0-60 14221 DIOAGER ND 12.1 13 ug/L 94 NA 65-135 NA 0-60 AH 14221 DIOAGERAM ND 2.81 2 ug/L 144 NA 65-135 NA 0-60 AH 14221 PICLORAMA ND 1.05 1 ug/L 175 NA 65-135 NA 0-60 AH 14221 LADRAMA ND 1.05 1 ug/L 175 NA 65-135 NA 0-60 AH 14221 LADRAMA ND 1.06 1 ug/L 176 NA 65-135 NA 0-60 AH 14221 LADRAMA ND 1.06 1 ug/L 176 NA 65-135 NA 0-60 AH			9	1.19		_	ng/L	119	ΑN	65-135	Ϋ́	0-90		LFM	
14221 DALAPON ND 12.1 13 ug/L 93 NA 65-135 NA 0-60 AH 14221 DINOSEB ND 281 2 ug/L 141 NA 65-135 NA 0-60 AH 14221 DICAMBA ND 1.05 1 ug/L 149 NA 65-135 NA 0-60 AH 14221 DICAMBA ND 1.05 1 ug/L 149 NA 65-135 NA 0-60 AH 14221 LADB ND 1.05 1 ug/L 173 NA 65-135 NA 0-60 AH 14221 LADB ND 1.06 1 ug/L 173 NA 65-135 NA 0-60 AH 14221 LADB ND 1.06 1 ug/L 173 NA 65-135 NA 0-60 AH 14221 LALDHORPANDRE ND 1.25 <t< td=""><td></td><td></td><td>9</td><td>1.06</td><td></td><td>_</td><td>ng/L</td><td>106</td><td>ΝΑ</td><td>65-135</td><td>Ϋ́</td><td>09-0</td><td></td><td>LFM</td><td></td></t<>			9	1.06		_	ng/L	106	ΝΑ	65-135	Ϋ́	09-0		LFM	
14221 DINOSEBB ND 281 2 ug/L 141 NA 65-135 NA 0-60 AH 14221 PICICDRAMB ND 0.96 1 ug/L 106 NA 65-135 NA 0-60 14221 PICICDRAMBA ND 1.05 1 ug/L 133 NA 65-135 NA 0-60 14221 TOTAL (DCPA & Melaboliles) ND 1.06 1 ug/L 133 NA 65-135 NA 0-60 14221 Z-4 DB ND 1.06 1 ug/L 106 NA 65-135 NA 0-60 14221 Z-4 DB ND 1.06 1 ug/L 106 NA 65-135 NA 0-60 14221 CHLORAMBEN ND 2.26 2 ug/L 76 NA 65-135 NA 0-60 14221 CHLORAMBEN ND 1.29 1 ug/L 76 NA 65-1			2	12.1		13	ug/L	93	ΝΑ	65-135	Ϋ́	0-60		LFM	
14221 PICLORAM ND 0.96 1 ug/L 96 NA 65-135 NA 0-60 14221 DICAMBA ND 1.05 1 ug/L 105 NA 65-135 NA 0-60 14221 DICAMBA ND 1.19 1 ug/L 105 NA 65-135 NA 0-60 14221 2.4 DB ND 1.06 1 ug/L 178 NA 65-135 NA 0-60 14221 2.4 DB ND 1.06 1 ug/L 178 NA 65-135 NA 0-60 14221 BENTAZON ND 2.26 2 ug/L 178 NA 65-135 NA 0-60 14221 ACILORAMBEN ND 1.29 1 ug/L 176 NA 0-60 0-60 14221 CHLORAMBEN ND 1.76 1 ug/L 179 NA 0-61 0-60 14323			Q	2.81		23	ng/L	141	AM	65-135	ΑN	09-0	ΑH	LFM	
14221 DICAMBA ND 1.05 1 ug/L 105 NA 65-135 NA 0-60 14221 TOTAL (DCPA & Metabolites) ND 1.19 1 ug/L 179 NA 65-135 NA 0-60 14221 2.4 DB ND 1.06 1 ug/L 173 NA 65-135 NA 0-60 14221 2.4 DB ND 1.06 1 ug/L 178 NA 65-135 NA 0-60 14221 2.4.5 T ND 1.26 2 ug/L 178 NA 65-135 NA 0-60 14221 DICHLORPROP ND 2.28 2 ug/L 178 NA 0-60 NA 0-60 14221 CHLORAMBEN ND 1.29 1 ug/L 76 NA 65-135 NA 0-60 14221 CHLORAMBEN ND 1.29 1 ug/L 76 NA 70-130 NA <td></td> <td></td> <td>g</td> <td>96.0</td> <td></td> <td>-</td> <td>ng/l</td> <td>96</td> <td>AN</td> <td>65-135</td> <td>Ϋ́</td> <td>09-0</td> <td></td> <td>LFM</td> <td></td>			g	96.0		-	ng/l	96	AN	65-135	Ϋ́	09-0		LFM	
14221 TOTAL (DCPA & Metabolities) ND 1.19 1 ug/L 119 NA 65-135 NA 0-60 14221 2.4 DB ND 1.06 1 ug/L 133 NA 65-135 NA 0-60 14221 2.4 DB ND 1.06 1 ug/L 133 NA 65-135 NA 0-60 14221 2.4.5 T ND 2.26 2 ug/L 136 NA 65-135 NA 0-60 14221 DICHLORPROP ND 2.28 3 ug/L 136 NA 65-135 NA 0-60 14221 DICHLORPROP ND 1.29 1 ug/L 76 NA 65-135 NA 0-60 14221 CHLORAMBEN ND 0.76 1 ug/L 76 NA 70-130 NA 0-60 15133 LINDANE (BHC- CAMMA) ND 1 ug/L 10g NA 70-130 NA			2	1.05		_	ug/L	105	Ϋ́	65-135	Ν	0-60		L'FIM	
4221 24 DB ND 10.6 B ug/L 133 NA 65-135 NA 6-60 14221 24,5 T ND 1.06 1 ug/L 106 NA 65-135 NA 6-60 14221 BENTAZON ND 2.26 2 ug/L 173 NA 65-135 NA 6-60 14221 DICHLORPROPP ND 2.26 2 ug/L 173 NA 65-135 NA 6-60 14221 CICLLORPROPP ND 1.29 1 ug/L 176 NA 65-135 NA 6-60 14221 CHLORAMBEN ND 0.76 1 ug/L 76 NA 65-135 NA 6-60 14221 CHLORAMBEN ND 0.76 1 ug/L 76 NA 70-130 NA 6-60 14213 LINDANE (BHC-CAMMA) ND 1.14 N 70-130 NA 70-130 NA 6-60			Q	1,19		_	ng/L	119	ΑĀ	65-135	ΑN	09-0		LFM	
14221 24,5 T ND 1.06 1 ug/L 106 NA 65-135 NA 0-60 14221 BENTAZON ND 2.26 2 ug/L 113 NA 65-135 NA 0-60 14221 DICHLORPROP ND 2.28 3 ug/L 129 NA 65-135 NA 0-60 14221 ACIFLUORFEN ND 1.29 1 ug/L 129 NA 65-135 NA 0-60 14221 CHLORAMBEN ND 0.76 1 ug/L 76 NA 65-135 NA 0-60 14221 CHLORAMBEN ND 0.76 1 ug/L 76 NA 65-135 NA 0-60 14221 CHLORAMBEN ND 1.76 1 ug/L 76 NA 70-130 NA 0-60 15133 LINDANE (BHC-GAMMA) ND 1.14 1 ug/L 104 NA 70-130 NA			Q	10.6		80	ng/L	133	ΑĀ	65-135	AN	09-0		LFM	
14221 BENTAZON ND 2.26 2 ug/L 113 NA 65-135 NA 0-60 14221 DICHLORPROP ND 2.89 3 ug/L 96 NA 65-135 NA 0-60 14221 ACIFLUORPEN ND 0.76 1 ug/L 76 NA 65-135 NA 0-60 14221 CHLORAMBEN ND 0.76 1 ug/L 76 NA 65-135 NA 0-60 14221 CHLORAMBEN ND 0.76 1 ug/L 76 NA 65-135 NA 0-60 14221 CHLORAMBEN ND 0.79 1 ug/L 70 NA 70-130 NA 0-60 15133 ENDRIN ND 1.14 1 ug/L 10 NA 70-130 NA 0-60 15133 METACHLOR ND 2.08 2 ug/L 114 NA 70-130 NA			2	1.06		-	ug/l.	106	NA.	65-135	Ą	09-0		LFM	
14221 DICHLORPROP ND 2.89 3 ug/L 96 NA 65-135 NA 0-60 14221 ACIFLUORFEN ND 1.29 1 ug/L 129 NA 65-135 NA 0-60 14221 CHLORAMBEN ND 0.76 1 ug/L 76 NA 65-135 NA 0-60 14221 CHLORAMBEN ND 1.16 1 ug/L 76 NA 65-135 NA 0-60 14221 CHLORAMBEN ND 1.16 1 ug/L 70-130 NA 0-60 15133 LINDANE (BHC - GAMMA) ND 1.14 1 ug/L 104 NA 70-130 NA 0-60 15133 METHOXYCHLOR ND 1.14 1 ug/L 104 NA 70-130 NA 0-60 15133 ALCHLOR ND 2.08 2 ug/L 104 NA 70-130 NA 0-60 </td <td></td> <td></td> <td>2</td> <td>2.26</td> <td></td> <td>2</td> <td>ug/Ł</td> <td>113</td> <td>¥</td> <td>65-135</td> <td>Y V</td> <td>09-0</td> <td></td> <td>LFM</td> <td></td>			2	2.26		2	ug/Ł	113	¥	65-135	Y V	09-0		LFM	
14221 ACIFLUORFEN ND 1.29 1 ug/L 76 NA 65-135 NA 0-60 14221 CHLORAMBEN ND 0.76 1 ug/L 76 NA 65-135 NA 0-60 14221 2.4 - DCAA (SURR) 108 116 % NA 70-130 NA 0-60 15133 ENDRIN ND 0.39 1 ug/L 100 NA 70-130 NA 0-60 15133 ENDRIN ND 1.14 1 ug/L 100 NA 70-130 NA 0-60 15133 ALCHOXYCHLOR ND 1.14 1 ug/L 104 NA 70-130 NA 0-60 15133 ALCHOXYCHLOR ND 1.14 N 70-130 NA 0-60 15133 ALCALOR ND 2.25 ug/L 103 NA 70-130 NA 0-60 15133 CHLORDANE, TECHNICAL ND			9	2.89		က	ng/L	96	AN	65-135	AN	09-0		LFM	
14221 CHLORAMBEN ND 0.76 1 ug/L 76 NA 65-135 NA 0-50 14221 2.4 - DCAA (SURR) 108 116 % NA 70-130 NA 0-60 15133 ENDRIN ND 0.99 1 ug/L 100 NA 70-130 NA 0-60 15133 ENDRIN ND 1.14 1 ug/L 100 NA 70-130 NA 0-60 15133 ENDRIN ND 1.14 1 ug/L 104 NA 70-130 NA 0-60 15133 ALCHLORR ND 1.14 1 ug/L 104 NA 70-130 NA 0-60 15133 ATRAZINE ND 0.75 1 ug/L 13 NA 70-130 NA 0-60 15133 BENZO(A)PYRENE ND 0.75 1 ug/L 15 NA 70-130 NA 0-60			Ω	1.29			ug/Ł	129	AN A	65-135	AN	09-0		LFM	
14221 2,4 - DCAA (SURR) 108 116 % NA 70-130 NA 0-60 15133 ENDRIN ND 0.99 1 ug/L 99 NA 70-130 NA 0-60 15133 LINDANE (BHC-GAMMA) ND 1.14 1 ug/L 100 NA 70-130 NA 0-60 15133 ALCHOXYCHLOR ND 1.14 1 ug/L 104 NA 70-130 NA 0-60 15133 ALCACHLOR ND 2.08 2 ug/L 104 NA 70-130 NA 0-60 15133 ALCACHLOR ND 2.25 2 ug/L 13 NA 70-130 NA 0-60 15133 BENZO(A)PYRENE ND 0.75 1 ug/L 75 NA 70-130 NA 0-60 15133 CHLORDANE, TECHNICAL ND 1.02 1 ug/L 109 NA 70-130 NA 0-60			2	0.76		τ-	ug/L	76	Υ	65-135	N	0-20		LFM	
15133 ENDRIN ND 0.99 1 ug/L 99 NA 70-130 NA 0-60 15133 LINDANE (BHC-GAMMA) ND 1 1 ug/L 100 NA 70-130 NA 0-60 15133 ALTHOXYCHLOR ND 1.14 1 ug/L 114 NA 70-130 NA 0-60 15133 ALACHLOR ND 2.08 2 ug/L 113 NA 70-130 NA 0-60 15133 ALRAZINE ND 0.75 1 ug/L 113 NA 70-130 NA 0-60 15133 BENZO(A)PYRENE ND 0.75 1 ug/L 75 NA 70-130 NA 0-60 15133 CHLORDANE, TECHNICAL ND 1.02 1 ug/L 102 NA 70-130 NA 0-60 15133 DI(ETHYLLEXYL)-ADIPATE ND 1.09 1 ug/L 109 NA 70-1			108	116			. %		NA	70-130	ΝΑ	0-60		LFM	
15133 ENDRINA ND 0.99 1 ug/L 99 NA 70-130 NA 0-60 15133 LINDANE (BHC - GAMMA) ND 1 1 ug/L 100 NA 70-130 NA 0-60 15133 ACHLOR ND 1.14 1 ug/L 104 NA 70-130 NA 0-60 15133 ATRAZINE ND 2.26 ug/L 113 NA 70-130 NA 0-60 15133 BENZO(A)PYRENE ND 0.75 1 ug/L 75 NA 70-130 NA 0-60 15133 CHLORDANE, TECHNICAL ND 1.02 1 ug/L 75 NA 70-130 NA 0-60 15133 DI(ETHYLLEXYL)-ADIPATE ND 1.09 1 ug/L 109 NA 70-130 NA 0-60	080609														
LINDANE (BHC-GAMMA) ND 1 ug/L 100 NA 70-130 NA 0-60 METHOXYCHLOR ND 1.14 1 ug/L 14 NA 70-130 NA 0-60 ALACHLOR ND 2.08 2 ug/L 104 NA 70-130 NA 0-60 ATRAZINE ND 0.75 1 ug/L 75 NA 70-130 NA 0-60 CHLORDANE, TECHNICAL ND 1.02 1 ug/L 102 NA 70-130 NA 0-60 CHLORDANE, TECHNICAL ND 1.02 1 ug/L 102 NA 70-130 NA 0-60			9	0.99			ng/L	66	AN	70-130	NA	0-90		LFM	
METHOXYCHLOR ND 1.14 1 ug/L 14 NA 70-130 NA 0-60 ALACHLOR ND 2.08 2 ug/L 104 NA 70-130 NA 0-60 ATRAZINE ND 2.25 2 ug/L 113 NA 70-130 NA 0-60 BENZO(A)PYRENE ND 0.75 1 ug/L 75 NA 70-130 NA 0-60 CHLORDANE, TECHNICAL ND 1.02 1 ug/L 109 NA 70-130 NA 0-60 DI(ETHYLHEXYL)-ADIPATE ND 1.09 1 ug/L 109 NA 70-130 NA 0-60			2	*		-	ug/L	100	NA	70-130	ΑN	0-60		LFM	
ALACHLOR ND 2.08 2 ug/L 104 NA 70-130 NA 0-60 ATRAZINE ND 2.25 2 ug/L 13 NA 70-130 NA 0-60 BENZO(A)PYRENE ND 0.75 1 ug/L 75 NA 70-130 NA 0-60 CHLORDANE, TECHNICAL ND 1.02 1 ug/L 102 NA 70-130 NA 0-60 DI(ETHYLHEXYL)-ADIPATE ND 1.09 1 ug/L 109 NA 70-130 NA 0-60			Ñ	1.14		+	ng/L	114	AA	70-130	Ν	09-0		LFM	
ATRAZINE ND 2.25 2 ug/L 113 NA 70-130 NA 0-60 BENZO(A)PYRENE ND 0.75 1 ug/L 75 NA 70-130 NA 0-60 CHLORDANE, TECHNICAL ND 1.02 1 ug/L 102 NA 70-130 NA 0-60 DI(ETHYLHEXYL)-ADIPATE ND 1.09 1 ug/L 109 NA 70-130 NA 0-60			2	2.08		2	ng/L	104	ΝΑ	70-130	Ϋ́	0-60		LFM	
BENZO(A)PYRENE ND 0.75 1 ug/L 75 NA 70-130 NA 0-60 CHLORDANE, TECHNICAL ND 1.02 1 ug/L 102 NA 70-130 NA 0-60 DI(ETHYLHEXYL)-ADIPATE ND 1.09 1 ug/L 109 NA 70-130 NA 0-60			2	2.25		7	ug/L	113	ΑA	70-130	Ϋ́	0-60		LFM	
CHLORDANE, TECHNICAL ND 1.62 1 ug/L 102 NA 70-130 NA 0-60 DI(ETHYLHEXYL)-ADIPATE ND 1.09 1 ug/L 109 NA 70-130 NA 0-60			2	0.75		_	ng/L	75	ΑN	70-130	Ϋ́	09-0		LFM	
DI(ETHYLHEXYL)-ADIPATE ND 1.09 1 ug/L 109 NA 70-130 NA 6-60			ON	1.02		_	ug/L	102	Ä	70-130	Ϋ́	09-0		LFM	
			N	1.09		_	ug/L	109	AA	70-130	Ą	0-60		LFM	

%RPD = Relative Percent Difference

NA = Indicates %RPD could not be calculated

Matrix Spike (MS)/Matrix Spike Duplicate (MSD) analyses are used to determine the accuracy (MS) and precision (MSD) of a analytical method in a given sample matrix. Therefore, the usefulness of this report is limited to samples of similar matrices analyzed in the same analytical batch.

Only Duplicate sample with detections are listed in this report



Batch

Page 4 of 6 Reference Number: 08-07095

Report Date: 7/9/2008

		Comments																																		
		h	LFM	LFM	LΕ	Z :		LF	LFM	LFM	LFM	LFM	LFM	LFIM	LFM	LFM	LFM	LFM	ĽΕΜ	LFM	LFM	LFM	Z L	Z L			F	LFM	LF	LF.	LFM	EF.	LFM	LFM	LFI	F
	မွ	Qualifier	g																																ပ္ပ	
		Limits	09-0	09-0	0-20	0-60		0-20	09-0	09-0	09-0	09-0	09-0	09-0	09-0	0-90	09-0	09-0	09-0	09-0	09-0	09-0	09-0	09-0	ල ල	990	0-60	09-0	09-0	09-0	09-0	09-0	09-0	0-60	0,-60	09-0
		%RPD	AN	ΝA	ΥN	¥ :	¥ ¥	¥	¥	ΝA	NA	NA	AN	NA	ΝΑ	Ą	ΨN	ΑN	Ϋ́	Υ	Ϋ́	٧	NA NA	A A	X 2	¥ ¥	¥	Ą	NA	Y.	NA	NA	ΑN	Ą	ΑN	¥
		Limits	70-130	70-130	70-130	70-130	70-130	70-130	70-130	70-130	70-130	70-130	70-130	70-130	70-130	70-130	70-130	70-130	70-130	70-130	70-130	70-130	70-130	70-130	70-130	70-130	70-130	70-130	70-130	70-130	70-130	70-130	70-130	70-130	70-130	70-130
	Percent Recovery	MSD	NA	NA A	NA	¥ :	S S	Ϋ́	ΑN	Ϋ́	NA A	NA N	ΝΑ	ΑĀ	NA	Ϋ́	Ϋ́	Ϋ́	Ą	ΑĀ	ΝΑ	NA A	¥ :	¥ :	Y X	Z Z	AA	A	ΑA	NA	A	¥.	ΑA	AN	Ϋ́	Ϋ́
	Percent	MS	133	102	98	105	102	133	96	108	102	106	93	Ŧ	112	110	107	102	101	107	106	104	100	30L	89	88	106	106	104	108	110	86	137	102	48	9
		Units	ug/L	ng/L	ug/L	ng/L	ug/L	- rig/L	ug/L	ug/L	ug/t.	ng/L	ng/L	ng/L	ug/L	ng/L	ng/L	ng/L	ng/L	ng/l.	ng/L	ng/L	ug/t.	ng/L	ug/L	ug/L	. T/Gn	ug/L	ug/L	ng/t	ng/t.	ng/L	ng/L	ng/L	ng/L	ng/L
m	Spike	Conc	·	-	-			4	-	-	-		~	₩.	-	-	_	_	~	.	-	τ	4 ,	. -	- -		-	-	₩.		1			_	-	_
Duplicate	Spike	Result					:																													
	Spike	Result	1.33	1.02	ထ																															
				γ	0.98	1.05	1.02	5.3	96.0	1.08	1.02	1.06	0.93	<u></u>	1.12	Ξ	1.07	1.02	1.01	1.07	1.06	1.04	 ,	1.08	1.89	0.98	1.06	1.06	1.04	1.08	1.1	0.98	1.11	1.02	0.48	0.91
		Result	QN			ON 1.05	•	ND 5.3	ND 0.96	·	•	•			-			•	•			•			ND 0.89				•	•	ζ-		•	•		ND 0.91
		Analyte	15133 DI(ETHYLHEXYL)-PHTHALATE ND	HEPTACHLOR	HEPTACHLOR EPOXIDE ND		SIMAZINE		QN	BUTACHLOR	DIELDRIN	METOLACHLOR	METRIBUZIN	PROPACHLOR ND	BROMACIL. ND	TERBACIL	DIAZINON	SIMAZINE	EPTC	DIAZINON	4,4-DDD ND	4,4-DDE	LINDANE (BHC - GAMMA) ND	4,4-UU NU		PARATHION		4,4-DDD	4,4-DDE	4,4-DDT	MALATHION	PARATHION-ETHYL ND	FLUORENE	ACENAPHTHYLENE ND	ANTHRACENE	

%RPD = Relative Percent Difference

NA = Indicates %RPD could not be calculated

Matrix Spike (MS)/Matrix Spike Duplicate (MSD) analyses are used to determine the accuracy (MS) and precision (MSD) of a analytical method in a given sample matrix. Therefore, the usefulness of this report is limited to samples of similar matrices analyzed in the same analytical batch.

Only Duplicate sample with detections are listed in this report



Page 5 of 6

Reference Number: 08-07095 Report Date: 7/9/2008

иатих эріке	pike	-	Spike	Duplicate Soike Sr	Spike		Percent 6	Percent Recovery				S	
Hatch	Sample Applying	1	de a de			-, -, -, -, -, -, -, -, -, -, -, -, -, -	AAC.	TOW CLOSE	1	5000	<u> </u>	2	
	Salispie Frielyte	Ineau	lineau!	- 1	- 1		6	USM	TIMES	OHA!	CIMITS	Qualifier	Comments
		2	96.0	_	_	- -	96	ΑĀ	70-130	ž	0-60	LFM	
	15133 BENZO(G,H,I)PERYLENE	9	_	•	_	ug/t ,	100	NA	70-130	NA	09-0	LFM	•
	15133 BENZO(K)FLUORANTHENE	Q.	1.02	-	_	ug/L ,	102	NA	70-130	NA	0-60	LFM	,
	15133 CHRYSENE	Ð	1.07	4	-	. J/Sn	107	NA	70-130	Ä	0-90	LFM	
	15133 DIBENZO(A,H)ANTHRACENE	Q	1.01	ţ	_	ng/L	5	¥.	70-130	Ä	09-0	LFM	
	15133 INDENO(1,2,3-CD)PYRENE	Ñ	1.04	4	_	ug/L ,	104	NA	70-130	A A	0-60	LFM	
	15133 PHENANTHRENE	9	1.04	-	٠	. ng/L	104	NA	70-130	Ν	0-90	LFM	
	15133 PYRENE	9	1.04	_		ng/L ,	104	NA	70-130	Ϋ́	0-60	LFM	
	15133 BENZYL BUTYL PHTHALATE	S	1.1	_		, ng/L	111	ΝΑ	70-130	Ϋ́	0-60	LFM	
	15133 DI-N-BUTYL PHTHALATE	Q.	1.23	-	۰	•	123	NA	70-130	¥	09-0	LFM	
	15133 DIETHYL PHTHALATE	S	1.2	-	ر	ra/L	120	AN	70-130	Ä	09-0	LFM	
	15133 DIMETHYL PHTHALATE	Ö	7.	-	_		110	ΝΑ	70-130	Ą	09-0	LFM	
	15133 1,3-DIMETHYL-2-NITROBENZENE (Surr	88	88		ים	%		AN	70-130	ΥN	0-0	LFM	
	15133 PYRENE-D10 (Surr)	92	94		6	%		ΝA	70-130	ΑN	09-0	LFM	
	15133 PERYLENE-D12 (Surr)	102	66		-0	%		NA	70-130	ΑN	09-0	LFM	
	15133 TRIPHENYLPHOSPHATE (Surr)	108	102		6-	%		ΑN	70-130	¥	09-0	LFM	
525X_080609													
	15133 PROPARGITE	Q	2.3	2	_	ng/L ,	15	NA	70-130	N A	0-30	LFM	
	15133 METALAXYL	Ð	2.06	2	_	ng/L	103	NA	70-130	N	0-20	LFM	
		9	0.61	***	~	ug/L. (61	NA	70-130	Ν	0-20	LFM	
	15133 1-NAPHTHALENEACETAMIDE	8	2.64	2	_	ng/L	132	NA	70-130	N	0-50	LFM	
	15133 FENARIMOL	9	0.99	-	_		66	AX	70-130	Ą	0-20	LFM	
	15133 MEVINPHOS	Q	1.08	2	_	ng/L t	54	NA	70-130	AN	0-20	LFM	
		Q	0.94	_	.	ng/L (94	NA	70-130	Ą	0-20	LFM	
	15133 DICOFOL	9	2.24	2	3	ug/L ,	112	Y A	70-130	Ą V	0-20	LFM	
	15133 PHOSMET	g	2.26	7	_	, T/6n	113	NA	70-130	ΑN	0-20	LFM	
	15133 TRIADIMEFON	9	8.0	-	_	ng/L {	80	NA	70-130	ΝA	0-20	LFM	
		9	1.81	2	_	ng/L ç	91	NA	70-130	ΝA	0-20	LFM	
		2	2.32	2	7		116	NA	70-130	٧	0-20	LFM	
	15133 MYCLOBUTANIL	9	2.65	2	_	ug/t. 1	133	NA	70-130	ΝA	0-20	LFM	
	15133 HEXAZINONE	9	1.25	₹~	_	, J/Gr	125	NA	70-130	NA	0-20	LFM	
531_080611													
	13899 OXYMAL	9	8.7	10			87	NA	70-130	Ā	0-20	LFM	
		문	8.8	5			88	NA	70-130	ΝĀ	0-20	LFM	
	13899 ALDICARB SULFOXIDE	9	7.8	10		ug/L 7	. 82	AN	70-130	Ϋ́	0-20	LFM	
	13899 ALDICARB SULFONE	S	8.5	10		3 T√Gn	85	NA	70-130	Ą	0-20	LFM	

%RPD = Relative Percent Difference

NA = Indicates %RPD could not be calculated
Matrix Spike Duplicate (MSD) analyses are used to determine the accuracy (MS) and precision (MSD) of a analytical method in a given sample matrix. Therefore, the usefulness of this report is limited to samples of similar matrices analyzed in the same analytical batch.



Reference Number: 08-07095 Report Date: 7/9/2008 Page 6 of 6

Matrix Spike	pike				숊										
			>	Spike	Spike	Spike		Percent Recovery	Recovery				ac		
Batch	Sample Analyte	lyte	Result	Result	Result	Conc	Units	MS	MSD	Limits	%RPD	Limits	Qualifier	Comments	
	13899 ME	METHOMYL	2	9.4		10	ng/L	94	AM	70-130	ξ	0-20	LFM	Whiteman was a second of the s	
	13899 3-H	3-HYDROXYCARBOFURAN	Q	8.9		10	ug/l.	68	N A	70-130	Ϋ́	0-20	LFM	^	
	13899 ALE	ALDICARB	2	ю		10	ng/L	80	NA	70-130	ΑĀ	0-50	LFM		
	13899 CAF	CARBARYL	2	8.8		10	ng/L	88	NA	70-130	Ä	0-20	LFM		
	13899 PR0	PROPOXUR (BAYGON)	2	6	ì	10	ng/L	90	NA	70-130	Α̈́	0-50	LFM		
	13899 ME	METHIOCARB	2	8.1		10	ug/L	81	NA A	70-130	ΑĀ	0-20	LFM		
	15128 OX	OXYMAL	2	8.5	7.6	10	ng/L	85	76	70-130	11.2	0-20	LFM		
	15128 CAF	CARBOFURAN	9	8.8	7.9	10	ng/L	88	79	70-130	10.8	0-20	LFM		
	15128 ALC	ALDICARB SULFOXIDE	2	7.8	7	10	ng/L	78	79	70-130	10.8	0-50	LFM		
	15128 ALE	ALDICARB SULFONE	2	8.7	7.2	10	ug/L	87	72	70-130	18.9	0-20	LFM		
	15128 ME	METHOMYL	2	8.8	8.2	10	ng/L	88	82	70-130	7.1	0-20	LFM		
	15128 3-H	3-HYDROXYCARBOFURAN	9	9.6	8.6	10	ng/L	96	98	70-130	11.0	0-20	LFM		
	15128 ALC	ALDICARB	2	8.3	7	10	ng/L	83	70	70-130	17.0	0-20	LFM		
	15128 CAF	CARBARYL	9	8.8	7.6	10	ug/L	88	92	70-130	14.6	0-20	LFM		
	15128 PR(PROPOXUR (BAYGON)	2	9.3	7.9	10	ug/L	93	79	70-130	16.3	0-20	LFM		
	15128 ME	METHIOCARB	9	8.6	7.4	10	ng/L	98	74	70-130	15.0	0-20	LFM		
COD_080604															
	15131 CH	CHEMICAL OXYGEN DEMAND	2	57	57	50	mg/L	114	114	80-120	0.0	0-60	LFM		
	15260 CHE	CHEMICAL OXYGEN DEMAND	8900	11300	11300	2500	mg/L	96	96	80-120	0.0	09-0	LFM		
1080528A															
	15147 CHI	CHLORIDE	31	32		1.00	mg/L	100	N A	80-120	ΝΑ	09-0	LFM		
	15169 CHI	CHLORIDE	26	47		20.00	mg/L	105	AN	80-120	Ν	09-0	LFM		
NO3NO2-080528	128														
	15050 NIT	NITRATE-N	0.54	1.56	1.54	1.00	mg/L	102	100	90-110	2.0	0-20	LFM		
	15060 NIT	NITRATE-N	0.04	1.07	1.05	1.00	mg/L	103	101	90-110	2.0	0-20	LFM		
	15061 NIT	NITRATE-N	0.56	1.59	1.56	1.00	mg/L .	103	100	90-110	3.0	0-20	LFM		
	15133 NIT	NITRATE-N	<u></u>	2.11	2.09	1.00	mg/L	100	98	90-110	2.0	0-20	LFM		
OPHOS-080528	8;														
	15050 OR	ORTHO-PHOSPHATE	9	1.09	1.06	1.00	mg/L	109	106	70-130	2.8	0-20	LFM		
	15060 OR'	ORTHO-PHOSPHATE	0.32	1.39	1.36	1.00	mg/L	107	104	70-130	2.8	0-20	LFM		
	15128 OR	ORTHO-PHOSPHATE	0.12	1.17	1.16	1.00	mg/L	105	104	70-130	7.0	0-20	LFM		
	15133 OR	ORTHO-PHOSPHATE	0.23	1.27	1.30	1.00	mg/L	104	107	70-130	2.8	0-20	LFM		

%RPD = Relative Percent Difference

NA = Indicates %RPD could not be calculated
Matrix Spike (MSI)/Matrix Spike Duplicate (MSD) analyses are used to determine the accuracy (MS) and precision (MSD) of a analytical method in a given sample matrix. Therefore, the usefulness of this report is limited to samples of similar matrices analyzed in the same analytical batch.







QUALITY CONTROL REPORT SURROGATE REPORT

Reference Number: 08-07095 Report Date: 07/09/08

	· control				
Lab No	Analyte	Result Qualifier	Units	Method	Limit
515_080602 15124	2,4 - DCAA (SURR)	108	%	515.1	Acceptance Range is 70 - 130%
508_080609 15124	TETRACHLORO-M-XYLENE (SURR)	86	%	508.1	Acceptance Limits 70%-130%
525_080609 15124	1,3-DIMETHYL-2-NITROBENZENE (Surr) PYRENE-D10 (Surr) PERYLENE-D12 (Surr) TRIPHENYLPHOSPHATE (Surr)	100 96 106 108	% % %	525.2	Acceptance Range is 70% to 130% Acceptance Range is 70% to 130% Acceptance Range is 70% to 130% Acceptance Range is 70% to 130%
515_080602 15125	2,4 - DCAA (SURR)	112	% _	515.1	Acceptance Range is 70 - 130%
515_080602 15126	2,4 - DCAA (SURR)	107	% .	515.1	Acceptance Range is 70 - 130%
515_080602 15127	2,4 - DCAA (SURR)	109	%	515.1	Acceptance Range is 70 - 130%
515_080602 15128	2,4 - DCAA (SURR)	108	%	515.1	Acceptance Range is 70 - 130%
515_080602 15129	2,4 - DCAA (SURR)	105	%	515.1	Acceptance Range is 70 - 130%
515_080602 15130	2,4 - DCAA (SURR)	117	%	515.1	Acceptance Range is 70 - 130%
515_080602 15131	; 2,4 - DCAA (SURR)	117	%	515.1	Acceptance Range is 70 - 130%
508_080609 15131 525_080609	TETRACHLORO-M-XYLENE (SURR)	80	%	508.1	Acceptance Limits 70%-130%
15131	1,3-DIMETHYL-2-NITROBENZENE (Surr) PYRENE-D10 (Surr) PERYLENE-D12 (Surr) TRIPHENYLPHOSPHATE (Surr)	99 93 103 110	% % %	525.2	Acceptance Range is 70% to 130% Acceptance Range is 70% to 130% Acceptance Range is 70% to 130% Acceptance Range is 70% to 130%
515_080602 15132	2,4 - DCAA (SURR)	107	%	515.1	Acceptance Range is 70 - 130%
508_080609 15132 525_080609	TETRACHLORO-M-XYLENE (SURR)	82	%	508.1	Acceptance Limits 70%-130%
15132	1,3-DIMETHYL-2-NITROBENZENE (Surr) PYRENE-D10 (Surr) PERYLENE-D12 (Surr) TRIPHENYLPHOSPHATE (Surr)	98 96 103 108	% % %	525.2	Acceptance Range is 70% to 130% Acceptance Range is 70% to 130% Acceptance Range is 70% to 130% Acceptance Range is 70% to 130%
515_080602 15133	2,4 - DCAA (SURR)	112	%	515.1	Acceptance Range is 70 - 130%
508_080609 15133	TETRACHLORO-M-XYLENE (SURR)	80	%	508.1	Acceptance Limits 70%-130%

^{*}Notation:

A surrogate is a pure compound added to a sample in the laboratory just before processing so that the overall efficiency of a method can be determined.







QUALITY CONTROL REPORT SURROGATE REPORT

Reference Number: 08-07095

Report Date: 07/09/08

Lab No	Analyte	Result Qualifier	Units	Method	Limit
525 080609					
15133	1,3-DIMETHYL-2-NITROBENZENE (Surr)	98	%	525.2	Acceptance Range is 70% to 130%
	PYRENE-D10 (Surr)	95	%		Acceptance Range is 70% to 130%
	PERYLENE-D12 (Surr)	102	%		Acceptance Range is 70% to 130%
Ł	TRIPHENYLPHOSPHATE (Surr)	108	% -		Acceptance Range is 70% to 130%



Page 1 of 1

Qualifier Definitions

Reference Number: 08-07095

Report Date: 07/09/08

Qualifier	Definition
АН	Result was high for this analyte in the end standard, indicating an increase in detector response. N detection of this analyte was found in samples, therefore no further action taken.
BQ	Indicates that an analyte has been detected in the laboratory method blank. This flag denotes possible contribution of laboratory background.
, CC	Continuing calibration check standard was within acceptance limits. Low recovery for a PAH may possibly be a result of photo-degradation.

Note: Some qualifier definitions found on this page may pertain to results or QC data which are not printed with this report.

FORM: QualifierDefs

4

not presented with Hell - olang pur

5255

Appendices I-F

HBDIC Recharge Water Quality Testing: Lab Results, Notes and Records

2008-2009 Recharge Season



 Burlington WA
 1620 S Walnut St - 98233

 Corporate Office
 800.755.9295 • 360.757.1400 • 360.757.1402fax

 Bellingham WA
 805 Orchard Dr Suite 4 - 98225

 Microbiology
 360.671.0688 • 360.671.1577fax

July 14, 2009

Page 1 of 1

Mr. Bob Bower Walla Walla Basin Watershed Council 810 South Main Street Milton-Freewater, OR 97862

RE: 09-07724 - HBDIC Recharge Project

Dear Mr. Bob Bower,

Your project: HBDIC Recharge Project, was received on Friday May 29, 2009.

All samples were analyzed within the accepted holding times, were appropriately preserved and were analyzed according to approved analytical protocols. The quality control data was within laboratory acceptance limits, unless specified in the QA reports.

If you have questions phone me at 800 755-9295.

Respectfully Submitted,

Lawrence J Henderson, PhD Director of Laboratories

Enclosures Data Report

QC Reports Chain of Custody



Microbiology

Burlington WA | 1620 S Walnut St - 98233 800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225 360.671.0688 • 360.671.1577fax

Page 1 of 1

Data Report

Client Name: Walla Walla Basin Watershed Council

810 South Main Street

Milton-Freewater, OR 97862

Reference Number: 09-07724

Project: HBDIC Recharge Project

Report Date: 7/14/09

Date Received: 5/29/09

Peer Review:

	eription: HBDIC OBS #1 - Observat umber: 16045	ion Well #1						le Date: { cted By:	5/27/09		
CAS ID#	Parameter	Result	PQL	MDL	Units	DF	Method	Analyzed	Analys	t Batch	Comment
14797-55-8	NITRATE-N	0.12	0.100	0.015	mg/L	1	300.0	5/29/09	ВЈ	1090529A	
E-10173	TOTAL DISSOLVED SOLIDS	59	10		mg/L	1	SM2540 C	6/3/09	CCN	TDS_090603	
14265-44-2	ORTHO-PHOSPHATE	0.18	0.01	0.002	mg/L	1	SM4500-P F	5/29/09	so	OPHOS-090529B	
16887-00-6	CHLORIDE	0.4	0.1	0.012	mg/L	1	300.0	5/29/09	BJ	1090529A	
E-10264	TOTAL KJELDAHL NITROGEN	0.34	0.30	0.0486	mg/L	1	SM4500-Norg C	6/3/09	so	TKN-090603	
E-10162	TOTAL SUSPENDED SOLIDS	ND	4	1.68	mg/L	1	SM2540 D	5/29/09	MAK	TSS_090529	
E-10195	TOTAL ORGANIC CARBON	1.14	0.50	0.07	mg/L	1	SM5310 B	6/2/09	BJ	TOC_090602	
E-10117	CHEMICAL OXYGEN DEMAND	ND	8.0	2.47	mg/L	1	SM5220 D	6/2/09	MAK	COD_090602	

	cription: HBDIC OBS #1 - Duplicated lumber: 16046							mple Date: llected By:	5/27/09		
CAS ID#	Parameter	Result	PQL	MDL	Units	DF	Method	Analyzed	Analyst	Batch	Cor
14797-55-8	NITRATE-N	0.13	0.100	0.015	mg/L	1	300.0	5/29/09	BJ 10	090529A	

CAS ID#	Parameter	Result	PQL	MDL	Units	DF	Method	Analyzed	Analys	t Batch	Comment
14797-55-8	NITRATE-N	0.13	0.100	0.015	mg/L	1	300.0	5/29/09	ВЈ	1090529A	
E-10173	TOTAL DISSOLVED SOLIDS	60	10		mg/L	1	SM2540 C	6/3/09	CCN	TDS_090603	
14265-44-2	ORTHO-PHOSPHATE	0.18	0.01	0.002	mg/L	1	SM4500-P F	5/29/09	so	OPHOS-090529B	
16887-00-6	CHLORIDE	0.4	0.1	0.012	mg/L	1	300.0	5/29/09	BJ	1090529A	
E-10264	TOTAL KJELDAHL NITROGEN	0.38	0.30	0.0486	mg/L	1	SM4500-Norg C	6/3/09	so	TKN-090603	
E-10162	TOTAL SUSPENDED SOLIDS	ND	4	1.68	mg/L	1	SM2540 D	5/29/09	MAK	TSS_090529	
E-10195	TOTAL ORGANIC CARBON	1.18	0.50	0.07	mg/L	1	SM5310 B	6/2/09	ВЈ	TOC_090602	
E-10117	CHEMICAL OXYGEN DEMAND	ND	8.0	2.47	mg/L	1	SM5220 D	6/2/09	MAK	COD_090602	

Not detected above the listed practical quantitation limit (PQL) or not above the Method Detection Limit (MDL), if requested.

⁻QL = Practical Quantitation Limit is the lowest level that can be acheived within specified limits of precision and accuracy during routine laboratory operating conditions.



Burlington WA | 1620 S Walnut St - 98233

800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225 360.671.0688 • 360.671.1577fax

Page 1 of 1

CARBAMATES IN DRINKING WATER

Client Name: Walla Walla Basin Watershed Council

810 South Main Street

Milton-Freewater, OR 97862

Project::

Field ID: HBDIC OBS #1

Sample Description: Observation Well #1

Sampled By:

Sample Date: 5/27/09

Source Type: Sampler Phone:

Reference Number: 09-07724

Project: HBDIC Recharge Project

Lab Number: 16045 Report Date: 6/4/09 Date Analyzed: 06/03/09

Date Extracted: 531_090603

Analyst: CO7 Peer Review: Analytical Method: \$31.2

Carbamates

CAS	COMPOUND	RESULTS	UNITS	PQL	MDL	MCL	COMMENT
EPA Re	egulated						
23135-22-0	OXYMAL	ND	ug/L	1.0	0.3	200	
1563-66-2	CARBOFURAN	ND	ug/L	1.0	0.2	40	
PA U	regulated						
1646-87-3	ALDICARB SULFOXIDE	ND	ug/L	1.0	0.3		
1646-88-4	ALDICARB SULFONE	ND	ug/L	1.0	0.3		
16752-77-5	METHOMYL	ND	ug/L	1.0	0.3		
16655-82-6	3-HYDROXYCARBOFURAN	ND	ug/L	1.0	0.3		
116-06-3	ALDICARB	ND	ug/L	1.0	0.3		
63-25-2	CARBARYL	ND	ug/L	1.0	0.2		
State U	Inregulated - Other						
114-26-1	PROPOXUR (BAYGON)	ND	ug/L	1.0	0.4		
2032-65-7	METHIOCARB	ND	ug/L	1.0	0.3		

ND (Not Detected): indicates that the parameter was not detected above the State Reporting Limit (SRL).



Bellingham WA 805 Orchard Dr Suite 4 - 98225

360.671.0688 • 360.671.1577fax

Page 1 of 1

CARBAMATES IN DRINKING WATER

Client Name: Walla Walla Basin Watershed Council

810 South Main Street

Milton-Freewater, OR 97862

Project::

Field ID: HBDIC OBS #1

Sample Description: Duplicated

Sampled By:

Sample Date: 5/27/09

Source Type: Sampler Phone:

Reference Number: 09-07724

Project: HBDIC Recharge Project

Lab Number: 16046 Report Date: 6/4/09 Date Analyzed: 06/03/09

Date Extracted: 531_090603

Analyst: CO) Peer Review: Analytical Method: \$31.2

Carbamates

CAS	COMPOUND	RESULTS	UNITS	PQL	MDL	MCL	COMMENT
EPA Re	gulated						
135-22-0	OXYMAL	ND	ug/L	1.0	0.3	200	
63-66-2	CARBOFURAN	ND	ug/L	1.0	0.2	40	
PA Ur	nregulated						
46-87-3	ALDICARB SULFOXIDE	ND	ug/L	1.0	0.3		
16-88-4	ALDICARB SULFONE	ND	ug/L	1.0	0.3		
752-77-5	METHOMYL	ND	ug/L	1.0	0.3		
55-82-6	3-HYDROXYCARBOFURAN	ND	ug/L	1.0	0.3		
06-3	ALDICARB	ND	ug/L	1.0	0.3		
25-2	CARBARYL	ND	ug/L	1.0	0.2		
State L	nregulated - Other						
4-26-1	PROPOXUR (BAYGON)	ND	ug/L	1.0	0.4		
2-65-7	METHIOCARB	ND	ug/L	1.0	0.3		

ND (Not Detected): indicates that the parameter was not detected above the State Reporting Limit (SRL).

Note: Trigger Level: DOH Drinking Water Response level. Systems with compounds detected in excess of this level are required to take additional samples. Contact your regional DOH office.



Burlington WA | 1620 S Walnut St - 98233 Corporate Office

Microbiology

800.755.9295 • 360,757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225 360.671.0688 • 360.671.1577fax

Page 1 of 1

HERBICIDES IN DRINKING WATER

Client Name: Walla Walla Basin Watershed Council

810 South Main Street

Milton-Freewater, OR 97862

Project::

Field ID: HBDIC OBS #1

Sample Description: Observation Well #1

Sampled By:

Sample Date: 5/27/09

Source Type: Sampler Phone:

Reference Number: 09-07724

Project: HBDIC Recharge Project

Lab Number: 16045 Report Date: 6/10/09 Date Analyzed: 06/04/09

Date Extracted: 515.4_090603

Analyst: CQ Peer Review: Analytical Method: 515.4

Herbicides in Drinking Water

CAS	COMPOUND	RESULTS	UNITS	PQL	MDL	MCL	COMMENT
EPA Re	gulated						
-75-7	2,4 - D	ND	ug/L	0.5	0.2	70	
72-1	2,4,5 - TP (SILVEX)	ND	ug/L	0.25	0.04	50	
6-5	PENTACHLOROPHENOL	ND	ug/L	0.25	0.05	1	
0	DALAPON	ND	ug/L	3.25	0.9	200	
5-7	DINOSEB	ND	ug/L	0.5	0.2	7	
8-02-1	PICLORAM	ND	ug/L	0.25	0.07	500	
ther							
28	DCPA (ACID METABOLITES)	ND	ug/L	0.25	0.1		
-00-9	DICAMBA	ND	ug/L	0.25	0.05		
2-6	2,4 DB	ND	ug/L	2	2		
6-5	2,4,5 T	ND	ug/L	0.25	0.04		
57-89-0	BENTAZON	ND	ug/L	0.5	0.2		
-36-5	DICHLORPROP	ND	ug/L	0.75	0.5		
94-66-6	ACIFLUORFEN	ND	ug/L	0.25	0.1		
-90-4	CHLORAMBEN	ND	ug/L		0.3		qualitiative analysis
6-5	3,5 - DICHLOROBENZOIC ACID	ND	ug/L	0.25	0.2		

Trigger Level: DOH Drinking Water Response level. Systems with compounds detected in excess of this level are required to take additional samples. Contact your regional DOH office. ND (Not Detected): indicates that the parameter was not detected above the State Reporting Limit (SRL).

bund is detected > or = to the State Reporting Level, SRL, specified increased monitoring frequencies may occur per DOH.

| Simum Contaminant Level) maximum permissible level of a contaminant in water established by EPA; Federal Action Levels are 0.015 mg/L for Lead and 1.3 mg/L for Copper. Sodium has a recommended limit of 20 mg/L. A blank w/CL value indicates a level is not currently established.



Burlington WA | 1620 S Walnut St - 98233

Microbiology

800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225 360.671.0688 • 360.671.1577fax

Page 1 of 1

HERBICIDES IN DRINKING WATER

Client Name: Walla Walla Basin Watershed Council

810 South Main Street

Milton-Freewater, OR 97862

Project::

Field ID: HBDIC OBS #1

Sample Description: Duplicated

Sampled By:

Sample Date: 5/27/09

Source Type: Sampler Phone: Reference Number: 09-07724

Project: HBDIC Recharge Project

Lab Number: 16046 Report Date: 6/10/09 Date Analyzed: 06/04/09

Date Extracted: 515.4_090603

Analyst: CO Peer Review: 1771
Analytical Method: 515.4

Herbicides in Drinking Water

CAS	COMPOUND	RESULTS	UNITS	PQL	MDL	MCL	COMMENT
EPA Re	gulated						
4-75-7	2,4 - D	ND	ug/L	0.5	0.2	70	
3-72-1	2,4,5 - TP (SILVEX)	ND	ug/L	0.25	0.04	50	
-86-5	PENTACHLOROPHENOL	ND	ug/L	0.25	0.05	1	
-0	DALAPON	ND	ug/L	3.25	0.9	200	
s-o5-7	DINOSEB	ND	ug/L	0.5	0.2	7	
18-02-1	PICLORAM	ND	ug/L	0.25	0.07	500	
Other							
4028	DCPA (ACID METABOLITES)	ND	ug/L	0.25	0.1		
8-00-9	DICAMBA	ND	ug/L	0.25	0.05		
32-6	2,4 DB	ND	ug/L	2	2		
76-5	2,4,5 T	ND	ug/L	0.25	0.04		
057-89-0	BENTAZON	ND	ug/L	0.5	0.2		
0-36-5	DICHLORPROP	ND	ug/L	0.75	0.5		
594-66-6	ACIFLUORFEN	ND	ug/L	0.25	0.1		
3-90-4	CHLORAMBEN	ND	ug/L		0.3		qualitiative analysi
36-5	3,5 - DICHLOROBENZOIC ACID	ND	ug/L	0.25	0.2		
		1					

NOTES:

Trigger Level: DOH Drinking Water Response level. Systems with compounds detected in excess of this level are required to take additional samples. Contact your regional DOH office. ND (Not Detected): indicates that the parameter was not detected above the State Reporting Limit (SRL).

yund is detected > or = to the State Reporting Level, SRL, specified increased monitoring frequencies may occur per DOH.
ximum Contaminant Level) maximum permissible level of a contaminant in water established by EPA; Federal Action Levels are 0.015 mg/L for Lead and 1.3 mg/L for Copper. Sodium has a recommended limit of 20 mg/L. A
...C.L value indicates a level is not currently established.



Burlington WA | 1620 S Walnut St - 98233 800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225 360.671.0688 • 360.671.1577fax

WSDOE Lab C1251

DATA REPORT

Page 1 of 2

Client Name: Walla Walla Basin Watershed Council

810 South Main Street

Milton-Freewater, OR 97862

Lab Number: 16045

Field ID: HBDIC OBS #1

Sample Description: Observation Well #1

Matrix: Water

Sample Date: 5/27/09

Extraction Date: 6/9/09 Extraction Method: 3535

Reference Number: 09-07724

Project: HBDIC Recharge Project

Report Date: 7/14/09 Date Analyzed: 7/6/09

Analyst: CO Peer Review:

Analytical Method: 525.2

Batch: 525X_090609

CAS	Compound	RESULT	Flag	UNITS	PQL	MDL D	.F. COMMENT	
80-05-7	BISPHENOL-A	3.2		ug/L	1		1.00	
60-51-5	DIMETHOATE	ND		ug/L	0.5	0.03	1.00	
37-19-	METALAXYL	ND		ug/L	0.1		1.00	
15299-99-	NAPROPAMIDE	ND		ug/L	0.1	0.05	1.00	
122-34-9	SIMAZINE	ND		ug/L	0.1	0.03	1.00	
86-86-2	1-NAPHTHALENEACETAMIDE	ND		ug/L	0.5	-	1.00	
333-41-5	DIAZINON	ND		ug/L	0.1	0.04	1.00	
60168-88-	FENARIMOL	ND		ug/L	0.1	0.03	1.00	
58-89-9	LINDANE (BHC - GAMMA)	ND		ug/L	0.1	0.03	1.00	
7786-34-7	MEVINPHOS	ND		ug/l	0.1	0.03	1.00	
86-50-0	AZINPHOS-METHYL	ND		ug/L	0.5	0.12	1.00	
2921-88-2	CHLORPYRIFOS	ND		ug/L	0.1	0.04	1.00	
72-54-8	4.4-DDD	ND		ug/L	0.1	0.02	1.00	
72-55-9	4,4-DDE	ND		ug/L	0.1	0.02	1.00	
50-29-3	4,4-DDT	ND		ug/L	0.1	0.03	1.00	
115-32-2	DICOFOL	ND		ug/L	1	-	1.00	
121-75-5	MALATHION	ND		ug/L	0.1	0.05	1.00	
298-00-0	METHYL PARATHION	ND		ug/L	0.5	0.1	1.00	
56-38-2	PARATHION-ETHYL	ND		ug/L	0.1	0.05	1.00	
732-11-6	PHOSMET	ND		ug/L	0.5		1.00	
43121-43-	TRIADIMEFON	ND		ug/L	0.1	0.07	1.00	
68694-11-		ND		ug/L	1.0	1.0	1.00	
950-37-8	METHIDATHINON	ND		ug/L	0.5	0.5	1.00	
950-37-8 88671-89-	MYCLOBUTANIL	ND		ug/L	0.5	0.5	1.00	

es:

Flags are data qualifiers. If there are data qualifiers on your report definitions can be found on an accompanying sheet.

ND - indicates the compound was not detected above the PQL or MDL.

PQL = Practical Quantitation Limit is the lowest level that can be acheived within specified limits of precision and accuracy during routine laboratory operating conditions.

D.F. - Dilution Factor.



Reference Number: 09-07724

Lab Number: 16045 Report Date: 7/14/09 Page 2 of 2

CAS	Compound	RESULT	Flag	UNITS	PQL	MDL D.I	F. COMMENT
51235-04-	HEXAZINONE	ND		ug/L	0.1	0.05	1.00
2312-35-8	PROPARGITE	ND		ug/L		-	1.00 Qualitative analysis



Burlington WA 1620 S Walnut St - 98233 800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225 360.671.0688 • 360.671.1577fax

WSDOE Lab C1251

DATA REPORT

Page 1 of 2

Client Name: Walla Walla Basin Watershed Council

810 South Main Street

Milton-Freewater, OR 97862

Lab Number: 16046

Field ID: HBDIC OBS #1

Sample Description: Duplicated

Matrix: Water

Sample Date: 5/27/09

Extraction Date: 6/9/09 Extraction Method: 3535

Reference Number: 09-07724

Project: HBDIC Recharge Project

Report Date: 7/14/09 Date Analyzed: 7/6/09

Analyst: CO Peer Review:

Analytical Method: 525.2

Batch: 525X 090609

CAS	Compound	RESULT	Flag	UNITS	PQL	MDL [D.F. (COMMENT
80-05-7	BISPHENOL-A	1.5		ug/L	1		1.00	
60-51-5	DIMETHOATE	ND		ug/L	0.5	0.03	1.00	
57837-19-	METALAXYL	ND		ug/L	0.1		1.00	
299-99-	NAPROPAMIDE	ND		ug/L	0.1	0.05	1.00	
122-34-9	SIMAZINE	ND		ug/L	0.1	0.03	1.00	
86-86-2	1-NAPHTHALENEACETAMIDE	ND		ug/L	0.5	= 2	1.00	
333-41-5	DIAZINON	ND		ug/L	0.1	0.04	1.00	
60168-88-	FENARIMOL	ND		ug/L	0.1	0.03	1.00	
58-89-9	LINDANE (BHC - GAMMA)	ND		ug/L	0.1	0.03	1.00	
7786-34-7	MEVINPHOS	ND		ug/l	0.1	0.03	1.00	
86-50-0	AZINPHOS-METHYL	ND		ug/L	0.5	0.12	1.00	
2921-88-2	CHLORPYRIFOS	ND		ug/L	0.1	0.04	1.00	
72-54-8	4,4-DDD	ND		ug/L	0.1	0.02	1.00	
72-55-9	4,4-DDE	ND		ug/L	0.1	0.02	1.00	
50-29-3	4,4-DDT	ND		ug/L	0.1	0.03	1.00	
115-32-2	DICOFOL	ND		ug/L	1	- 2	1.00	
121-75-5	MALATHION	ND		ug/L	0.1	0.05	1.00	
298-00-0	METHYL PARATHION	ND		ug/L	0.5	0.1	1.00	
56-38-2	PARATHION-ETHYL	ND		ug/L	0.1	0.05	1.00	
732-11-6	PHOSMET	ND		ug/L	0.5	-	1.00	
43121-43-	TRIADIMEFON	ND		ug/L	0.1	0.07	1.00	
68694-11-	TRIFLUMIZOLE	ND		ug/L	1.0	1.0	1.00	
950-37-8	METHIDATHINON	ND		ug/L	0.5	0.5	1.00	
88671-89-	MYCLOBUTANIL	ND		ug/L	0.5	0.5	1.00	

tes:

[.]gs are data qualifiers. If there are data qualifiers on your report definitions can be found on an accompanying sheet.

ND - indicates the compound was not detected above the PQL or MDL.

PQL = Practical Quantitation Limit is the lowest level that can be acheived within specified limits of precision and accuracy during routine laboratory operating conditions. D.F. - Dilution Factor.



Reference Number: 09-07724

Lab Number: 16046 Report Date: 7/14/09 Page 2 of 2

CAS	Compound	RESULT Flag	UNITS	PQL	MDL D.F. COMMENT	
51235-04-	HEXAZINONE	ND	ug/L	0.1	0.05 1.00	
2312-35-8	PROPARGITE	ND	ug/L		- 1.00 Qualitative analysis	

.es:

Flags are data qualifiers. If there are data qualifiers on your report definitions can be found on an accompanying sheet. ND - indicates the compound was not detected above the PQL or MDL.

PQL = Practical Quantitation Limit is the lowest level that can be acheived within specified limits of precision and accuracy during routine laboratory operating conditions. D.F. - Dilution Factor.



Burlington WA 1620 S Walnut St - 98233 800.755.9295 • 360.757.1

800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225 360.671.0688 • 360.671.1577fax Page 1 of 10



SAMPLE INDEPENDENT QUALITY CONTROL REPORT

Laboratory Fortified Blank

Reference Number: 09-07724 Report Date: 07/14/09

			True			%		QC
Batch	Analyte	Result	Value	Units	Method	Recovery	Limits	QualifierType* Comment
515.4_090603	2,4 - D	8.9	10	ug/L	515.4	89	70-130	LFB
	2,4 - DCAA (SURR)	93		%	515.4		70-130	
	2,4 DB	33.9	40	ug/L	515.4	85	70-130	
	2,4,5 - TP (SILVEX)	5.17	5	ug/L	515.4	103	70-130	
	2,4,5 T	5.35	5	ug/L	515.4	107	70-130	
	ACIFLUORFEN	5.1	5	ug/L	515.4	102	70-130	
	BENTAZON	10.6	10	ug/L	515.4	106	70-130	
	CHLORAMBEN	0.17	0.25	ug/L	515.4	68	70-130	C1
	DALAPON	59.3	65	ug/L	515.4	91	70-130	
	DCPA (ACID METABOLITES)	4.92	5	ug/L	515.4	98	70-130	
	DICAMBA	4.8	5	ug/L	515.4	96	70-130	
	DICHLORPROP	13.3	15	ug/L	515.4	89	70-130	
	DINOSEB	10.4	10	ug/L	515.4	104	70-130	
	PENTACHLOROPHENOL	4.92	5	ug/L	515.4	98	70-130	
	PICLORAM	5.55	5	ug/L	515.4	111	70-130	
525_090609	1,3-DIMETHYL-2-NITROBENZENE (Surr)	90		%	525.2		70-130	LFB
	4,4-DDD	0.9	1	ug/L	525.2	90	70-130	
	4,4-DDE	0.95	1	ug/L	525.2	95	70-130	
	4,4-DDT	0.86	1	ug/L	525.2	86	70-130	
	LINDANE (BHC - GAMMA)	0.92	1	ug/L	525.2	92	70-130	
	PERYLENE-D12 (Surr)	96		%	525.2		70-130	
	PYRENE-D10 (Surr)	101		%	525.2		70-130	
	SIMAZINE	1.05	1	ug/L	525.2	105	70-130	
	TRIPHENYLPHOSPHATE (Surr)	102		%	525.2		70-130	
525X_090609	1-NAPHTHALENEACETAMIDE	1.5	2	ug/L	525.2	75	70-130	LFB
	AZINPHOS-METHYL	1	1	ug/L	525.2	100	70-130	
	BISPHENOL-A	4.9	5	ug/L	525.2	98	85-115	
	CHLORPYRIFOS	2.7	3	ug/L	525.2	90	70-130	
	DICOFOL	1.6	2	ug/L	525.2	80	70-130	
	DIMETHOATE	0.2	1	ug/L	525.2	20	70-130	N1
	FENARIMOL	0.8	1	ug/L	525.2	80	70-130	
	HEXAZINONE	0.9	1	ug/L	525.2	90	70-130	

*Notation:

Recovery = (Result of Analysis)/(True Value) * 100

^{. =} Indicates % Recovery could not be calculated.

QCS: Quality Control Sample, a solution containing known concentrations of method analytes which is used to fortify an aliquot of reagent matrix. The QCS is obtained from an external source and is used to check lab performance.

LFB: Laboratory Fortified Blank, an aliquot of reagent matrix to which known quantities of method analytes are added in the lab. The LFB is analyzed exactly like a sample, and its purpose is to determine whether method performance is within accepted control limits.

MB or LRB: Method Blank or Laboratory Reagent Blank, an aliquot of reagent matrix is analyzed exactly like a sample, and its purpose is to determine if there is background contamination.



Burlington WA | 1620 S Walnut St - 98233 Corporate Office

800.755.9295 • 360.757.1400 • 360.757.1402fax

Microbiology

Bellingham WA 805 Orchard Dr Suite 4 - 98225 360.671.0688 • 360.671.1577fax Page 2 of 10



SAMPLE INDEPENDENT QUALITY CONTROL REPORT

Laboratory Fortified Blank

Reference Number: 09-07724 Report Date: 07/14/09

			True			%		QC	
Batch	Analyte	Result	Value	Units	Method	Recovery	Limits	Qualifier Type*	Comment
525X_090609	MALATHION	2.2	2	ug/L	525.2	110	70-130	LFB	
	METALAXYL	1.9	2	ug/L	525.2	95	70-130		
	METHIDATHINON	1.9	2	ug/L	525.2	95	85-115		
	METHYL PARATHION	0.85	1	ug/L	525.2	85	70-130		
	MEVINPHOS	1.6	2	ug/L	525.2	80	70-130		
	MYCLOBUTANIL	1.85	2	ug/L	525.2	93	85-115		
	NAPROPAMIDE	0.85	1	ug/L	525.2	85	70-130		
	PARATHION-ETHYL	1.8	2	ug/L	525.2	90	70-130		
	PHOSMET	1.8	2	ug/L	525.2	90	70-130		
	PROPARGITE	1.9	2	ug/L	525.2	95	85-115		
	TRIADIMEFON	0.7	1	ug/L	525.2	70	70-130		
	TRIFLUMIZOLE	1.6	2	ug/L	525.2	80	85-115		
525X_090609	1-NAPHTHALENEACETAMIDE	2.5	2	ug/L	525.2	125	70-130	LFB	
	AZINPHOS-METHYL	1.5	1	ug/L	525.2	150	70-130		
	CHLORPYRIFOS	3.7	3	ug/L	525.2	123	70-130		
	DICOFOL	3.5	3	ug/L	525.2	117	70-130		
	DIMETHOATE	0.8	1	ug/L	525.2	80	70-130		
	FENARIMOL	2.3	2	ug/L	525.2	115	70-130		
	HEXAZINONE	1.2	1	ug/L	525.2	120	70-130		
	MALATHION	4.3	4	ug/L	525.2	108	70-130		
	METALAXYL	2.3	2	ug/L	525.2		70-130		
	METHIDATHINON	3.8	2	ug/L	525.2	190	85-115		
	METHYL PARATHION	1.6	2	ug/L	525.2		70-130		
	MEVINPHOS	2.8	2	ug/L	525.2	140	70-130		
	MYCLOBUTANIL	2.7	2	ug/L	525.2	135	85-115		
	NAPROPAMIDE	1.1	1	ug/L	525.2	110	70-130		
	PARATHION-ETHYL	2.3	3	ug/L	525.2		70-130		
	PHOSMET	3.3	2	ug/L	525.2		70-130		
	PROPARGITE	3.5	2	ug/L	525.2		85-115		
	TRIADIMEFON	2.3	2	ug/L	525.2		70-130		
	TRIFLUMIZOLE	2.3	2	ug/L	525.2		85-115		
31_090603	3-HYDROXYCARBOFURAN	10.7	10	ug/L	531.2	107	70-130	LFB	
-347K-447T-750P-545 (8-2	ALDICARB	10.3	10	ug/L	531.2		70-130		
	ALDICARB SULFONE	11.5	10	ug/L	531.2		70-130		

*Notation:

ARECOVERY = (Result of Analysis)/(True Value) * 100

Indicates % Recovery could not be calculated.

S: Quality Control Sample, a solution containing known concentrations of method analytes which is used to fortify an aliquot of reagent matrix. The QCS is obtained from an external source and is used to check lab performance.

LFB: Laboratory Fortified Blank, an aliquot of reagent matrix to which known quantities of method analytes are added in the lab. The LFB is analyzed exactly like a sample, and its purpose is to determine whether method performance is within accepted control limits.

MB or LRB: Method Blank or Laboratory Reagent Blank, an aliquot of reagent matrix is analyzed exactly like a sample, and its purpose is to determine if there is background contamination.



Microbiology

Burlington WA | 1620 S Walnut St - 98233

800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225 360.671.0688 • 360.671.1577fax Page 3 of 10



SAMPLE INDEPENDENT QUALITY CONTROL REPORT

Laboratory Fortified Blank

Reference Number: 09-07724 Report Date: 07/14/09

			True			%		QC	
Batch	Analyte	Result	Value	Units	Method	Recovery	Limits	Qualifier Type*	Comment
	ALDICARB SULFOXIDE	10.3	10	ug/L	531.2	103	70-130	LFB	
	BDMC (SURR)	110		%	531.2		70-130		
	CARBARYL	10.4	10	ug/L	531.2	104	70-130		
	CARBOFURAN	10.5	10	ug/L	531.2	105	70-130		
	METHIOCARB	11.1	10	ug/L	531.2	111	70-130		
	METHOMYL	10.2	10	ug/L	531.2	102	70-130		
	OXYMAL	12.8	10	ug/L	531.2	128	70-130		
	PROPOXUR (BAYGON)	10.9	10	ug/L	531.2	109	70-130		
531_090603	3-HYDROXYCARBOFURAN	20	20	ug/L	531.2	100	70-130	LFB	
	ALDICARB	18.5	20	ug/L	531.2	93	70-130		
	ALDICARB SULFONE	21.6	20	ug/L	531.2	108	70-130		
	ALDICARB SULFOXIDE	19	20	ug/L	531.2	95	70-130		
	BDMC (SURR)	106		%	531.2		70-130		
	CARBARYL	18.7	20	ug/L	531.2	94	70-130		
	CARBOFURAN	19.5	20	ug/L	531.2	98	70-130		
	METHIOCARB	19.6	20	ug/L	531.2	98	70-130		
	METHOMYL	20.2	20	ug/L	531.2	101	70-130		
	OXYMAL	22.5	20	ug/L	531.2	113	70-130		
	PROPOXUR (BAYGON)	20.2	20	ug/L	531.2	101	70-130		
COD_090602	CHEMICAL OXYGEN DEMAND	47	50	mg/L	SM5220 D	94	80-120	LFB	
OPHOS-090529B	ORTHO-PHOSPHATE	0.96	1.00	mg/L	SM4500-P F	96	80-120	LFB	
tds_090603	TOTAL DISSOLVED SOLIDS	494	500	mg/L	SM2540 C	99	80-120	LFB	
tds_090603	TOTAL DISSOLVED SOLIDS	464	500	mg/L	SM2540 C	93	80-120	LFB	
TKN-090603	TOTAL KJELDAHL NITROGEN	3.20	3.00	mg/L	SM4500-Norg C	107	80-120	LFB	
TOC_090602	TOTAL ORGANIC CARBON	1.04	1.00	mg/L	SM5310 B	104	90-110	LFB	

Recovery = (Result of Analysis)/(True Value) * 100

⁼ Indicates % Recovery could not be calculated.

QCS: Quality Control Sample, a solution containing known concentrations of method analytes which is used to fortify an aliquot of reagent matrix. The QCS is obtained from an external source and is used to check lab performance.

LFB: Laboratory Fortified Blank, an aliquot of reagent matrix to which known quantities of method analytes are added in the lab. The LFB is analyzed exactly like a sample, and its purpose is to determine whether method performance is within accepted control limits.

MB or LRB: Method Blank or Laboratory Reagent Blank, an aliquot of reagent matrix is analyzed exactly like a sample, and its purpose is to determine if there is background contamination.



Microbiology

Burlington WA | 1620 S Walnut St - 98233

800.755.9295 • 360.757.1400 • 360.757.1402fax Bellingham WA 805 Orchard Dr Suite 4 - 98225

360.671.0688 • 360.671.1577fax

Page 4 of 10



SAMPLE INDEPENDENT QUALITY CONTROL REPORT

Laboratory Fortified Blank

Reference Number: 09-07724

Report Date: 07/14/09

			True			%		QC	
Batch	Analyte	Result	Value	Units	Method	Recove	ery Limits	Qualifier Type*	Comment
TSS_090529	TOTAL SUSPENDED SOLIDS	480	500	mg/L	SM2540 D	96	80-120	LFB	
TSS_090529	TOTAL SUSPENDED SOLIDS	480	500	mg/L	SM2540 D	96	80-120	LFB	
TSS_090529	TOTAL SUSPENDED SOLIDS	480	500	mg/L	SM2540 D	96	80-120	LFB	

*Notation:

Recovery = (Result of Analysis)/(True Value) * 100

⁼ Indicates % Recovery could not be calculated.

QCS: Quality Control Sample, a solution containing known concentrations of method analytes which is used to fortify an aliquot of reagent matrix. The QCS is obtained from an external source and is used to check lab performance.

LFB: Laboratory Fortified Blank, an aliquot of reagent matrix to which known quantities of method analytes are added in the lab. The LFB is analyzed exactly like a sample, and its purpose is to determine whether method performance is within accepted control limits.

MB or LRB: Method Blank or Laboratory Reagent Blank, an aliquot of reagent matrix is analyzed exactly like a sample, and its purpose is to determine if there is background contamination.



Burlington WA | 1620 S Walnut St - 98233

800.755.9295 • 360.757.1400 • 360.757.1402fax Bellingham WA 805 Orchard Dr Suite 4 - 98225

Microbiology 360.671.0688 • 360.671.1577fax Page 5 of 10



SAMPLE INDEPENDENT QUALITY CONTROL REPORT

Low Level Laboratory Fortified Blank

Reference Number: 09-07724 Report Date: 07/14/09

			True			%		QC	
Batch	Analyte	Result	Value	Units	Method	Recovery	Limits	Qualifier Type*	Comment
515.4_090603	2,4 - D	0.34	0.25	ug/L	515.4	136	50-150	LFBD	
	2,4 - DCAA (SURR)	104		%	515.4		70-130		
	2,4 DB	1.6	2	ug/L	515.4	80	50-150		
	2,4,5 - TP (SILVEX)	0.12	0.125	ug/L	515.4	96	50-150		
	2,4,5 T	0.14	0.125	ug/L	515.4	112	50-150		
	ACIFLUORFEN	0.28	0.25	ug/L	515.4	112	50-150		
	BENTAZON	0.36	0.5	ug/L	515.4	72	50-150		
	DALAPON	1.59	1.6	ug/L	515.4	99	50-150		
	DCPA (ACID METABOLITES)	0.2	0.125	ug/L	515.4	160	50-150	C1	
	DICAMBA	0.13	0.125	ug/L	515.4	104	50-150		
	DICHLORPROP	0.47	0.375	ug/L	515.4	125	50-150		
	DINOSEB	0.24	0.25	ug/L	515.4	96	50-150		
	PENTACHLOROPHENOL	0.11	0.125	ug/L	515.4	88	50-150		
	PICLORAM	0.13	0.125	ug/L	515.4	104	50-150		
531_090603	3-HYDROXYCARBOFURAN	0.97	1	ug/L	531.2	97	50-150	LFBD	
	ALDICARB	0.95	1	ug/L	531.2		50-150		
	ALDICARB SULFONE	0.98	1	ug/L	531.2		50-150		
	ALDICARB SULFOXIDE	0.75	1	ug/L	531.2		50-150		
	BDMC (SURR)	105		%	531.2		50-150		
	CARBARYL	0.93	1	ug/L	531.2		50-150		
	CARBOFURAN	1	1	ug/L	531.2		50-150		
	METHIOCARB	0.98	1	ug/L	531.2		50-150		
	METHOMYL	1	1	ug/L	531.2		50-150		
	OXYMAL	1.2	1	ug/L	531.2		50-150		
	PROPOXUR (BAYGON)	1	1	ug/L	531.2		50-150		

*Notation:

Recovery = (Result of Analysis)/(True Value) * 100

^{\ =} Indicates % Recovery could not be calculated.

QCS: Quality Control Sample, a solution containing known concentrations of method analytes which is used to fortify an aliquot of reagent matrix. The QCS is obtained from an external source and is used to check lab performance.

LFB: Laboratory Fortified Blank, an aliquot of reagent matrix to which known quantities of method analytes are added in the lab. The LFB is analyzed exactly like a sample, and its purpose is to determine whether method performance is within accepted control limits.

MB or LRB: Method Blank or Laboratory Reagent Blank, an aliquot of reagent matrix is analyzed exactly like a sample, and its purpose is to determine if there is background contamination.



Burlington WA Corporate Office

Burlington WA | 1620 S Walnut St - 98233

800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225 360.671.0688 • 360.671.1577fax

Page 6 of 10



SAMPLE INDEPENDENT QUALITY CONTROL REPORT

Laboratory Reagent Blank

Reference Number: 09-07724

Report Date: 07/14/09

			True			%	QC	
Batch	Analyte	Result	Value	Units	Method	Recovery Limits	Qualifier Type*	Comment
COD_090602	CHEMICAL OXYGEN DEMAND	ND		mg/L	SM5220 D	4.00000	LRB	
1090529A	CHLORIDE	ND		mg/L	300.0	0.10000	LRB	
	NITRATE-N	ND		mg/L	300.0	0.10000		
OPHOS-090529B	ORTHO-PHOSPHATE	ND		mg/L	SM4500-P F	0.10000	LRB	
TKN-090603	TOTAL KJELDAHL NITROGEN	ND		mg/L	SM4500-Norg C	1.00000	LRB	

*Notation:

Recovery = (Result of Analysis)/(True Value) * 100

⁼ Indicates % Recovery could not be calculated.

uCS: Quality Control Sample, a solution containing known concentrations of method analytes which is used to fortify an aliquot of reagent matrix. The QCS is obtained from an external source and is used to check lab performance.

LFB: Laboratory Fortified Blank, an aliquot of reagent matrix to which known quantities of method analytes are added in the lab. The LFB is analyzed exactly like a sample, and its purpose is to determine whether method performance is within accepted control limits.

MB or LRB: Method Blank or Laboratory Reagent Blank, an aliquot of reagent matrix is analyzed exactly like a sample, and its purpose is to determine if there is background contamination.



Burlington WA | 1620 S Walnut St - 98233 800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225

360.671.0688 • 360.671.1577fax

Page 7 of 10



SAMPLE INDEPENDENT QUALITY CONTROL REPORT

Method Blank

Reference Number: 09-07724

Report Date: 07/14/09

			True			%	QC	
Batch	Analyte	Result	Value	Units	Method	Recovery Limits	Qualifier Type*	Comment
15.4_090603	2,4 - D	ND		ug/L	515.4	0.10000	MB	
	2,4 - DCAA (SURR)	87		%	515.4			
	2,4 DB	ND		ug/L	515.4	0.60000		
	2,4,5 - TP (SILVEX)	ND		ug/L	515.4	0.08000		
	2,4,5 T	ND		ug/L	515.4	0.08000		
	ACIFLUORFEN	ND		ug/L	515.4	0.08000		
	BENTAZON	ND		ug/L	515.4	0.10000		
	CHLORAMBEN	ND		ug/L	515.4	0.08000		
	DALAPON	ND		ug/L	515.4	1.00000		
	DCPA (ACID METABOLITES)	ND		ug/L	515.4	0.08000		
	DICAMBA	ND		ug/L	515.4	0.08000		
	DICHLORPROP	ND		ug/L	515.4	0.20000		
	DINOSEB	ND		ug/L	515.4	0.10000		
	PENTACHLOROPHENOL	ND		ug/L	515.4	0.08000		
	PICLORAM	ND		ug/L	515.4	0.08000		
525_090609	1,3-DIMETHYL-2-NITROBENZENE (Surr)	89		%	525.2		MB	
	4,4-DDD	ND		ug/L	525.2	0.05000		
	4,4-DDE	ND		ug/L	525.2	0.05000		
	4,4-DDT	ND		ug/L	525.2	0.05000		
	LINDANE (BHC - GAMMA)	ND		ug/L	525.2	0.02000		
	PERYLENE-D12 (Surr)	87		%	525.2			
	PYRENE-D10 (Surr)	100		%	525.2			
	SIMAZINE	ND		ug/L	525.2	0.02000		
	TRIPHENYLPHOSPHATE (Surr)	126		%	525.2			
525X_090609	1-NAPHTHALENEACETAMIDE	ND		ug/L	525.2	0.10000	МВ	
	AZINPHOS-METHYL	ND		ug/L	525.2	0.00000		
	CHLORPYRIFOS	ND		ug/L	525.2	0.00000		
	DICOFOL	ND		ug/L	525.2	0.00000		
	DIMETHOATE	ND		ug/L	525.2	0.00000		
	FENARIMOL	ND		ug/L	525.2	0.00000		
	HEXAZINONE	ND		ug/L	525.2	0.00000		
	MALATHION	ND		ug/L	525.2	0.05000		

*Notation:

Recovery = (Result of Analysis)/(True Value) * 100

_λ = Indicates % Recovery could not be calculated.

QCS: Quality Control Sample, a solution containing known concentrations of method analytes which is used to fortify an aliquot of reagent matrix. The QCS is obtained from an external source and is used to check lab performance.

LFB: Laboratory Fortified Blank, an aliquot of reagent matrix to which known quantities of method analytes are added in the lab. The LFB is analyzed exactly like a sample, and its purpose is to determine whether method performance is within accepted control limits.

MB or LRB: Method Blank or Laboratory Reagent Blank, an aliquot of reagent matrix is analyzed exactly like a sample, and its purpose is to determine if there is background contamination.



Microbiology

Burlington WA | 1620 S Walnut St - 98233

800.755.9295 • 360.757.1400 • 360.757.1402fax Bellingham WA 805 Orchard Dr Suite 4 - 98225

360.671.0688 • 360.671.1577fax

Page 8 of 10



SAMPLE INDEPENDENT QUALITY CONTROL REPORT

Method Blank

Reference Number: 09-07724

Report Date: 07/14/09

			True			%	C)C	
Batch	Analyte	Result	Value	Units	Method	Recovery Limit	s C	Qualifier Type*	Comment
525X_090609	METALAXYL	ND		ug/L	525.2	0.100	000	MB	
	METHIDATHINON	ND		ug/L	525.2	0.500	000		
	METHYL PARATHION	ND		ug/L	525.2	0.000	000		
	MEVINPHOS	ND		ug/L	525.2	0.000	000		
	MYCLOBUTANIL	ND		ug/L	525.2	0.500	000		
	NAPROPAMIDE	ND		ug/L	525.2	0.000	000		
	PARATHION-ETHYL	ND		ug/L	525.2	0.050	000		
	PHOSMET	ND		ug/L	525.2	0.100	000		
	PROPARGITE	ND		ug/L	525.2	0.000	000		
	TRIADIMEFON	ND		ug/L	525.2	0.00	000		
	TRIFLUMIZOLE	ND		ug/L	525.2	1.00	000		
1_090603	3-HYDROXYCARBOFURAN	ND		ug/L	531.2	0.50	000	MB	
	ALDICARB	ND		ug/L	531.2	0.25	000		
	ALDICARB SULFONE	ND		ug/L	531.2	0.40	000		
	ALDICARB SULFOXIDE	ND		ug/L	531.2	0.25	000		
	CARBARYL	ND		ug/L	531.2	0.50	000		
	CARBOFURAN	ND		ug/L	531.2	0.45	000		
	METHIOCARB	ND		ug/L	531.2	1.00	000		
	METHOMYL	ND		ug/L	531.2	0.25	000		
	OXYMAL	ND		ug/L	531.2	1.00	000		
	PROPOXUR (BAYGON)	ND		ug/L	531.2	0.25	000		
OPHOS-090529B	ORTHO-PHOSPHATE	ND		mg/L	SM4500-P F	0.10	000	МВ	
tds_090603	TOTAL DISSOLVED SOLIDS	ND		mg/L	SM2540 C	2.50	000	MB	
tds_090603	TOTAL DISSOLVED SOLIDS	ND		mg/L	SM2540 C	2.50	000	МВ	
TKN-090603	TOTAL KJELDAHL NITROGEN	ND		mg/L	SM4500-Norg C	0.12	2000	МВ	
TOC_090602	TOTAL ORGANIC CARBON	ND		mg/L	SM5310 B	0.12	2000	МВ	

^{*}Notation:

Recovery = (Result of Analysis)/(True Value) * 100

⁼ Indicates % Recovery could not be calculated.

QCS: Quality Control Sample, a solution containing known concentrations of method analytes which is used to fortify an aliquot of reagent matrix. The QCS is obtained from an external source and is used to check lab performance.

LFB: Laboratory Fortified Blank, an aliquot of reagent matrix to which known quantities of method analytes are added in the lab. The LFB is analyzed exactly like a sample, and its purpose is to determine whether method performance is within accepted control limits.

MB or LRB: Method Blank or Laboratory Reagent Blank, an aliquot of reagent matrix is analyzed exactly like a sample, and its purpose is to determine if there is background contamination.



Burlington WA Corporate Office

Burlington WA | 1620 S Walnut St - 98233

800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225

Microbiology 360.671.0688 • 360.671.1577fax

Page 9 of 10



SAMPLE INDEPENDENT QUALITY CONTROL REPORT

Method Blank

Reference Number: 09-07724

Report Date: 07/14/09

			True			%	QC	
Batch	Analyte	Result	Value	Units	Method	Recovery Limits	Qualifier Type*	Comment
TSS_090529	TOTAL SUSPENDED SOLIDS	ND		mg/L	SM2540 D	1.00000) MB	
TSS_090529	TOTAL SUSPENDED SOLIDS	ND		mg/L	SM2540 D	1.00000	МВ	
TSS_090529	TOTAL SUSPENDED SOLIDS	ND		mg/L	SM2540 D	1.00000		

*Notation:

[%] Recovery = (Result of Analysis)/(True Value) * 100

⁼ Indicates % Recovery could not be calculated.

Quality Control Sample, a solution containing known concentrations of method analytes which is used to fortify an aliquot of reagent matrix. The QCS is obtained from an external source and is used to check lab performance.

LFB: Laboratory Fortified Blank, an aliquot of reagent matrix to which known quantities of method analytes are added in the lab. The LFB is analyzed exactly like a sample, and its purpose is to determine whether method performance is within accepted control limits.

MB or LRB: Method Blank or Laboratory Reagent Blank, an aliquot of reagent matrix is analyzed exactly like a sample, and its purpose is to determine if there is background contamination.



Burlington WA Corporate Office 1620 S Walnut St - 98233 800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225 360.671.0688 • 360.671.1577fax

Page 10 of 10



SAMPLE INDEPENDENT QUALITY CONTROL REPORT

Quality Control Sample

Reference Number: 09-07724

Report Date: 07/14/09

			True			%		QC	
Batch	Analyte	Result	Value	Units	Method	Recovery	Limits	Qualifier Type*	Comment
531_090603	3-HYDROXYCARBOFURAN	54.5	46.9	ug/L	531.2	116	70-130	QCS	
	ALDICARB	29.8	29.5	ug/L	531.2	101	70-130		
	ALDICARB SULFONE	26.9	25.5	ug/L	531.2	105	70-130		
	ALDICARB SULFOXIDE	45.8	40	ug/L	531.2	115	70-130		
	BDMC (SURR)	113		%	531.2		70-130		
	CARBARYL	59.8	57.8	ug/L	531.2	103	70-130		
	CARBOFURAN	84.6	81.2	ug/L	531.2	104	70-130		
	METHIOCARB	64.9	58.1	ug/L	531.2	112	70-130		
	METHOMYL	57.7	53.7	ug/L	531.2	107	70-130		
	OXYMAL	52.5	51.2	ug/L	531.2	103	70-130		
	PROPOXUR (BAYGON)	96.9	91.2	ug/L	531.2	106	70-130		
D_090602	CHEMICAL OXYGEN DEMAND	92	92	mg/L	SM5220 D	100	80-120	QCS	
I090529A	CHLORIDE	30.3	30.0	mg/L	300.0	101	80-120	QCS	
	NITRATE-N	2.39	2.50	mg/L	300.0	96	80-120		
OPHOS-090529B	ORTHO-PHOSPHATE	0.46	0.49	mg/L	SM4500-P F	94	80-120	QCS	
TKN-090603	TOTAL KJELDAHL NITROGEN	3.08	3.00	mg/L	SM4500-Norg C	103	80-120	QCS	
TOC_090602	TOTAL ORGANIC CARBON	4.62	4.50	mg/L	SM5310 B	103	90-110	QCS	

^{*}Notation:

Recovery = (Result of Analysis)/(True Value) * 100

⁼ Indicates % Recovery could not be calculated.

QCS: Quality Control Sample, a solution containing known concentrations of method analytes which is used to fortify an aliquot of reagent matrix. The QCS is obtained from an external source and is used to check lab performance.

LFB: Laboratory Fortified Blank, an aliquot of reagent matrix to which known quantities of method analytes are added in the lab. The LFB is analyzed exactly like a sample, and its purpose is to determine whether method performance is within accepted control limits.

MB or LRB: Method Blank or Laboratory Reagent Blank, an aliquot of reagent matrix is analyzed exactly like a sample, and its purpose is to determine if there is background contamination.



800.755.9295 • 360.757.1400 • 360.757.1402fax Burlington WA 1620 S Walnut St - 98233 corporate Office 800.755.9295 • 360.757.1400 • 3 Bellingham WA 805 Orchard Dr Suite 4 - 98225 Microbiology 800.671.0688 • 360.671.1577fax



Page 1 of 4

QUALITY CONTROL REPORT

Duplicate and Matrix Spike/Matrix Spike Duplicate Report

Reference Number: 09-07724

Report Date: 7/14/2009

Duplicate								
			Duplicate				oc	
Batch 8	Sample Analyte	Result	Result	Units	%RPD	Limits	Qualifier	Comments
525_090609						1		
	16046 1,3-DIMETHYL-2-NITROBENZENE (Surr	06	06	%	0.0	0-45	DUP	
	16046 PYRENE-D10 (Surr)	86	101	%	3.0	0-45	DUP	
	16046 PERYLENE-D12 (Surr)	89	86	%	9.6	0-45	DUP	
	16046 TRIPHENYLPHOSPHATE (Surr)	112	108	%	3.6	0-45	DUP	
525X 090609								
li.	16046 BISPHENOL-A	1.5	1.2	ng/L	22.2	0-50	PUP	
	16046 1,3-DIMETHYL-2-NITROBENZENE (Surr	06	06	%	0.0	0-45	DUP	
	16046 PYRENE-D10 (Surr)	86	94	%	4.2	0-45	DUP	
	16046 PERYLENE-D12 (Surr)	89	92	%	3.3	0-45	PUP	
	16046 TRIPHENYLPHOSPHATE (Surr)	112	107	%	4.6	0-45	DUP	
COD_090602								
I090529A								
	16045 NITRATE-N	0.12	0.12	mg/L	0.0	0-45	DUP	
	16045 CHLORIDE	0.4	0.4	mg/L	0.0	0-45	DUP	
	16095 NITRATE-N	7.07	7.06	mg/L	0.1	0-45	DUP	
	16095 CHLORIDE	7.26	7.25	mg/L	0.1	0-45	DUP	
	16104 NITRATE-N	1.33	1.33	mg/L	0.0	0-45	DUP	
	16104 CHLORIDE	110	110	mg/L	0.0	0-45	PUG	
OPHOS-090529B								
	16102 ORTHO-PHOSPHATE	0.24	0.22	mg/L	8.7	0-20	DUP	
	16103 ORTHO-PHOSPHATE	0.24	0.23	mg/L	4.3	0-20	DUP	
TDS_090603								
	16530 TOTAL DISSOLVED SOLIDS	155	144	mg/L	7.4	0-45	DUP	
TKN-090603	15417 TOTAL KJELDAHL NITROGEN	40.6	40.8	mg/L	0.5	0-45	PUG	
	15714 TOTAL KJELDAHL NITROGEN	99.0	0.62	mg/L	9.2	0-45	DUP	0

%RPD = Relative Percent Difference

NA = Indicates %RPD could not be calculated

Matrix Spike Duplicate (MSD) analyses are used to determine the accuracy (MS) and precision (MSD) of a analytical method in a given sample matrix. Therefore, the usefulness of this report is limited to samples of similar matrices analyzed in the same analytical batch.



Page 2 of 4
Reference Number: 09-07724
Report Date: 7/14/2009

Duplicate

Comments DUP DUP DUP DUP DUP Qualifier 90 Limits 0-50 0-20 0-45 0-20 %RPD 1.1 6.7 mg/L mg/L mg/L Units mg/L mg/L Duplicate Result 2.13 4.29 1.67 0.94 29.0 Result 2.16 1.68 31.0 0.95 15999 TOTAL KJELDAHL NITROGEN 16209 TOTAL ORGANIC CARBON 15883 TOTAL ORGANIC CARBON 16085 TOTAL ORGANIC CARBON 16124 TOTAL ORGANIC CARBON Sample Analyte TOC_090602 Batch

TSS_090529

%RPD = Relative Percent Difference

NA = Indicates %RPD could not be calculated

Matrix Spike (MS)/Matrix Spike Duplicate (MSD) analyses are used to determine the accuracy (MS) and precision (MSD) of a analytical method in a given sample matrix. Therefore, the usefulness of this report is limited to samples of similar matrices analyzed in the same analytical batch.



Matrix Spike

Report Date: 7/14/2009 Reference Number: 09-07724 Page 3 of 4

Matrix Spike	pike			Duplicate										
			Spike	Spike	Spike		Percent	Percent Recovery				oo		
Batch	Sample Analyte	Result	Result	Result	Conc	Units	MS	MSD	Limits	%RPD	Limits	Qualifier	Comments	
515.4_090603														
	15704 2,4-D	QN	4.27	4.34	2	ug/L	85	87	70-130	1.6	0-20	LFM		
	15704 2,4,5 - TP (SILVEX)	ND	2.42	2.51	2.5	ug/L	26	100	70-130	3.7	0-20	LFM		
	15704 PENTACHLOROPHENOL	Q	2.45	2.44	2.5	ng/L	86	86	70-130	0.4	0-20	LFM		
	15704 DALAPON	QN	26.6	27.4	32.5	ng/L	82	84	70-130	3.0	0-20	LFM		
	15704 DINOSEB	Q	4.89	5.02	2	ng/L	86	100	70-130	5.6	0-20	LFM		
	15704 PICLORAM	Q	2.79	5.9	2.5	ng/L	112	116	70-130	3.9	0-20	LFM		
	15704 DICAMBA	Q	2.52	2.39	2.5	ng/L	101	96	70-130	5.3	0-20	LFM		
	15704 DCPA (ACID METABOLITES)	Q	2.44	2.52	2.5	ng/L	86	101	70-130	3.2	0-20	LFM		
	15704 2,4 DB	Q	19.9	20.8	20	ng/L	100	104	70-130	4.4	0-20	LFM		
	15704 2,4,5 T	Q.	2.45	2.52	2.5	ug/L	86	101	70-130	2.8	0-20	LFM		
	15704 BENTAZON	ND	4.96	4.89	2	ng/L	66	86	70-130	1.4	0-20	LFM		
	15704 DICHLORPROP	N	6.48	6.61	7.2	ng/L	90	92	70-130	2.0	0-20	LFM		
	15704 ACIFLUORFEN	ND	2.79	2.9	2.5	ng/L	112	116	70-130	3.9	0-20	LFM		
	15704 CHLORAMBEN	Q	2.14	1.98	2.5	ug/L	98	79	70-130	7.8	0-20	LFM		
	15704 2,4 - DCAA (SURR)	26	87	95		%		NA	70-130	NA	0-20	LFM		
525_090609														
	16530 SIMAZINE	Q	1.12		-	mg/L	112	NA	70-130	NA	09-0	LFM		
	16530 LINDANE (BHC - GAMMA)	Q	0.92		-	ng/L	92	NA	70-130	NA	09-0	LFM		
	16530 4,4-DDD	ND	0.91		-	ng/L	91	NA	70-130	NA	09-0	LFM		
	16530 4,4-DDE	ND	0.94		-	ng/L	94	NA	70-130	NA	09-0	LFM		
	16530 4,4-DDT	ND	98.0		1	ng/L	98	NA	70-130	NA	09-0	LFM		
	16530 MALATHION	Q.	2.28		2	ng/L	114	NA	70-130	NA	09-0	LFM		
	16530 PARATHION-ETHYL	ND	1.89			ng/L	98	NA	70-130	NA	09-0	LFM		
	16530 1,3-DIMETHYL-2-NITROBENZENE (Surr	91	91			%		NA	70-130	AN	09-0	LFM		
	16530 PYRENE-D10 (Surr)	66	92			%		NA	70-130	NA	09-0	LFM		
	16530 PERYLENE-D12 (Surr)	98	95			%		NA	70-130	NA	09-0	LFM		
	16530 TRIPHENYLPHOSPHATE (Surr)	130	104			%		NA	70-130	NA	09-0	LFM		
531_090603														
	13727 OXYMAL	ND	o	10.3	10	ng/L	06	103	70-130	13.5	0-20	LFM		
	13727 CARBOFURAN	Q	9.3	6.6	10	ng/L	93	66	70-130	6.3	0-20	LFM		
	13727 ALDICARB SULFOXIDE	Q	8.3	8.9	10	ng/L	83	89	70-130	0.7	0-20	LFM		
		Q	6	10.4	10	ng/L	06	104	70-130	14.4	0-20	LFM		
		Q.	6	6	10	ng/L	06	06	70-130	0.0	0-20	LFM		
		N	9.1	7.6	10	ng/L	91	26	70-130	6.4	0-20	LFM		
	13727 ALDICARB	Ω	8.7	9.4	10	ng/L	87	94	70-130	7.7	0-20	LFM		

%RPD = Relative Percent Difference

NA = Indicates %RPD could not be calculated
Matrix Spike (MS)/Matrix Spike Duplicate (MSD) analyses are used to determine the accuracy (MS) and precision (MSD) of a analytical method in a given sample matrix. Therefore, the usefulness of this report is limited to samples of similar matrices analyzed in the same analytical batch.



Report Date: 7/14/2009 Reference Number: 09-07724 Page 4 of 4

%RPD = Relative Percent Difference

NA = Indicates %RPD could not be calculated

Matrix Spike Duplicate (MSD) analyses are used to determine the accuracy (MS) and precision (MSD) of a analytical method in a given sample matrix. Therefore, the usefulness of this report is limited to samples of similar matrices analyzed in the same analytical batch.





Qualifier Definitions

Reference Number: 09-07724

Report Date: 07/14/09

Qualifier	Definition
B1	The source of the contamination has been identified as a contaminate in the lab purified water. Data for this compound is suspect if reported.
C1	The compound is co-eluting and increases the amount of error with quantitation.
М	Matrix induced bias assumed.
ME	Matrix spike shows a possible matrix induced bias. The LFB was within acceptance limits, result for this compound are suspect.
N1	Acceptance limits have not been established, the limits listed are for guidance only.







QUALITY CONTROL REPORT SURROGATE REPORT

Reference Number: 09-07724

Report Date: 07/14/09

Lab No	Analyte	Result Qualifier	Units	Method	Limit
515.4_090603		59854	0.00	outure of	
16045	2,4 - DCAA (SURR)	99	%	515.4	Acceptance Range is 70 - 130%
25 090609				100.0	
16045	1,3-DIMETHYL-2-NITROBENZENE (Surr)	91	%	525.2	Acceptance Range is 70% to 130%
45542	PYRENE-D10 (Surr)	98	%		Acceptance Range is 70% to 130%
	PERYLENE-D12 (Surr)	86	%		Acceptance Range is 70% to 130%
	TRIPHENYLPHOSPHATE (Surr)	102	%		Acceptance Range is 70% to 130%
31 090603					
16045	BDMC (SURR)	113	%	531.2	
515.4_090603					
	2.4 - DCAA (SURR)	96	%	515.4	Acceptance Range is 70 - 130%
16046	2,4 - DOAA (SURK)	00			
525_090609	1.3-DIMETHYL-2-NITROBENZENE (Surr)	90	%	525.2	Acceptance Range is 70% to 130%
16046	[전투 구입 100 전환경 100 전 12 전 20 전 20 전 20 전 20 전 20 전 20	98	%		Acceptance Range is 70% to 130%
	PYRENE-D10 (Surr)	89	%		Acceptance Range is 70% to 130%
	PERYLENE-D12 (Surr)	112	%		Acceptance Range is 70% to 130%
	TRIPHENYLPHOSPHATE (Surr)	112	70		
531_090603		100	0/	531.2	
16046	BDMC (SURR)	109	%	551.2	



Pageor			ANALY IICAL LABORATORIES	_	Burlington, WA 98233 1.800.755.9295	805 W. Orchard Dr. Suite 4	Bellingham, WA 98225		Der of Containers	Special Instructions Z Conditions on Receipt	Love					200	1000	T. d more		Total Containers		Yes No N/A	S satisfactory	T D	bels agree
ded sections)	For Lab Use Only	Ref#	Check Regulatory Program	Safe Drinking Water Act	Clean Water Act	ACKA / CERCLA	Other Is charge	Analyses Requested	0 \ 2 \ 2 \	TOC 158				NG-772A	16045 - 16046		8/ nous 509-52			semall soluplicated	ater WW - waste water OL - oil	Time Custody seals intact	Sample temp C C	Samples received intact	Chain of custody & labels agree
(Please complete all applicable shaded sections)		6	Zip:			Expires /		Anal	СОО СОО СОО СОО СОО СОО СОО СОО СОО СОО		D D									45/8	SW - surface v	Date			5.45
			St	FAX:	Attn:	□ M/C □ A/E		3	Standard Half-time (50% surcharge) Quickest (100% surcharge)	Sample Date Time	5-27-9 5:35	5-27.9 5:4								FAX:	* W - water DW - drinking water	Received by			0
is Redile	Our bill to:		97862 City:		P.O.#.	Visa	Card#;		Yunn Around Time Required X-Standard Half-time (50% surchs Quickest (100% surch Other		_	1 12								le:	X or Email)	Time	4000; 9 b.		
sylen / Analys	Walla Walla Basin Watershed Cour	Street	OR Zip:		70 FAX:	bob.bower@wwbwc.org	HBDIC Recharge Project		tple Location. s requests. b be performed for in.	Location	のないしんれるかいいけん	" - poplicated								Phone:	est (Must include FAX	Date	1.7.7		
hain of Custody / Analysis Reduest	Seport to: Walla Walls	ess:	Sity: Milton-Freews St.		Phone: 541,938-2170 FAX:	Email: bob.bower(Project HBDIC Rec	V	Istructions Use one line per sample Location. Be specific in analysis requests. Check off analyses to be performed for each sample Loaction. Enter number of containers.	Field ID	1 HBDIC OBSAL	2 (1 11	3	4	2	9	7	8	o S	sampled by:	Sample Receipt Request (Must include FAX or Email)	Relinquished by	R. RINGT	2 2 1 2)	



MILL CREEK WATER TREATMENT PLANT 581 Mill Creek Road • Walla Walla, WA 99362 Phone 509/522-3775 • Fax 509/529-9681

COLIFORM BACTERIA ANALYSIS SAMPLE COLLECTION: READ INSTRUCTIONS ON BACK OF GOLDEN ROD COPY

If instructions are not follow	ved, sample will be rejected.						
Date Sample Collected Time Sai	mple County						
11/19/08 Collect	ed						
Month Day Year 10:45	S AM						
Type of Water System (check only one box	0						
☐ Group A Public	☐ Private Household						
☐ Group B Public	Other ASR						
Group A and Group B Systems - Provide 1	from Water Facilities Inventory (WFI):						
ID#							
System Name: NW BWC							
70							
Contact Person: BB BOWER							
Day Phone: (541) 938-2170	Cell Phone: (509) 530-3534						
Eve. Phone: ()	FAX: ()						
Send results to: (Print full name, address a							
WALLA WALLA BASIN W	ATERSHED CHUNCIL						
SIO SO. WAIN P.C). BOX 68						
MILTON-FREEWATCH,	DR 97867						
SAMPLEIN	IFORMATION						
Sample collected by (name):							
BOB BOURS							
.000	address or sample site, and type of faucet):						
TUTALE							
Special instructions or comments:							
Special instructions of confinents.							
Type of Sample (must check only one box	x of #1 through #4 listed below)						
Routine Distribution Sample Provide information below.	□ Repeat Sample (follow-up to an unsatisfactory sample)						
Chlorinated: Yes No	The second secon						
Chlorinated: YesNo Provide information below. Chlorine Residual: Total Free Unsatisfactory routine lab number:							
3. Raw Water Source Sample	Oriodatolatory rodano lab nambor.						
Required for Surface Water, GWI, and	Unsatisfactory routine collect date:						
some Spring Sources) Total Coliform	Orisalistaciony rodune conect date.						
1 0 1 1							
L 1 ecal Colliditi	Chlorinated: Yes No						
Public Systems must provide Source Number from (WFI)	Chlorine Residual: Total Free						
4. ☐ Sample Collected for Information	Only						
Construction Repairs Pri	vate Residence Other						
CONSTRUCTION CONTRACTOR OF THE							
LAB USE ONLY DRINKING W	ATER RESULTS LAB USE ONLY						
	atisfactory						
1010	Coliform Present and						
	li present ☐ E.coli absent Il coliform present ☐ Fecal coliform absent						
	Toomorm product to recar comorm absent						
☐ Replacement Sample Required							
Sample not tested because:	Test unsuitable because:						
Sample too old (>30 hours)	☐ TNTC ☐ Turbid culture						
☐ Improper container	urbid culture						
Bacterial Density Possulton Plate Count	/ml, E.coli /100ml,						
Bacterial Density Results: Plate Count	100						
Total Coliform/100ml. Fe							
MICR Method Code:	Date and Time Received:						
1 1140 □ 1340 □ 2720	11/19/08 @ 12 An						
Date Analyzed: 11 19 109 (S)	Date Reported: 11 20/08						
Lab/Sample Number	110000						
A series and the seri	Lab Use:						
143- 06246							



MILL CREEK WATER TREATMENT PLANT
581 Mill Creek Road · Walla Walla, WA 99362
Phone 509/522-3775 · Fax 509/529-9681

COLIFORM BACTERIA ANALYSIS

SAMPLE COLLECTION: READ INSTRUCTIONS ON BACK OF GOLDEN ROD COPY
If instructions are not followed, sample will be rejected.

If it structions are not folic	owed, sample will be rejected.						
Date Sample Collected Time S	The state of the s						
[[/ [9 / 08] College	cted AM						
Month Day Year 11:00	J □PM						
Type of Water System (check only one be							
☐ Group A Public ☐ Group B Public	Private Household Other						
	, , , , ,						
Group A and Group B Systems – Provide	from water Facilities Inventory (WFI):						
ID#	Over II Marganes A Jan						
V	BASIN WARERSHED COUNCIL						
Contact Person: BOB BOWG							
Day Phone: (541) 938 - 2170							
Eve. Phone: ()	FAX: ()						
Send results to: (Print full name, address							
	WATERSHED COUNCIL						
SID SO MAIN P.	0. 60x 68						
MUTON-FREEWATE	L, OR 97862						
The second secon	10-20-20-20-20-20-20-20-20-20-20-20-20-20						
	NFORMATION						
Sample collected by (name):							
Specific leasting where comple collected	(address or sample site, and type of faucet):						
Specific location where sample collected	(address of sample site, and type of faucet):						
Considerations of some of the							
Special instructions or comments:							
Type of Sample (must check only one bo	ox of #1 through #4 listed below)						
1. ☐ Routine Distribution Sample	2. □ Repeat Sample (follow-up						
Provide information below.	to an unsatisfactory sample)						
Chlorinated: Yes No	Provide information below.						
Chlorine Residual: Total Free Unsatisfactory routine lab number:							
3. Raw Water Source Sample							
Required for Surface Water, GWI, and some Spring Sources)	Unsatisfactory routine collect date:						
L Total Comoni							
S Fecal Coliform	Chlorinated: Yes No						
Public Systems must provide Source Number from (WF	Chlorine Residual: Total Free						
4. ☐ Sample Collected for Information	Only						
	rivate Residence Other						
LAB USE ONLY DRINKING W	ATER RESULTS LAB USE ONLY						
	satisfactory						
	al Coliform Present and						
□ E.c	oli present						
□ Fed	cal coliform present Fecal coliform absent						
☐ Replacement Sample Required							
Sample not tested because:	Test unsuitable because:						
☐ Sample too old (>30 hours)	☐ TNTC						
☐ Improper container	☐ Turbid culture						
	/ml. E.coli /100ml.						
Bacterial Density Results: Plate Count	ecal Coliform \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \						
	ecai comorni						
MICR Method Code:	Date and Time Received:						
21140 🗆 1340 🗆 2720	11/19/08@ 1-pm						
Date Analyzed: \\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\	Date Reported: 11/20/08						
Lab/Sample Number	Lab Use:						
143- 06248							



MILL CREEK WATER TREATMENT PLANT 581 Mill Creek Road • Walla Walla, WA 99362 Phone 509/522-3775 • Fax 509/529-9681

COLIFORM BACTERIA ANALYSIS
SAMPLE COLLECTION: READ INSTRUCTIONS ON BACK OF GOLDEN ROD COPY
If Instructions are not followed sample will be released.

II Ilistruction	is are not lonow	eu, sampre	will be rejected.
Date Sample Collected	Time San Collecte		County
Month Day Year	11:00	PM	
Type of Water System (che	ck only one box)	
☐ Group A Public ☐ Group B Public		☐ Pri	vate Household ner_ASR
Group A and Group B Syste	ems – Provide fr	om Water	Facilities Inventory (WFI):
	MALINE	MIN	WARTERSHED COUNCI
Contact Person:			WANDONG) (DUNU
	3-2170		one: (59) 520 -3534
Eve. Phone: ()	2-4170	FAX: (Olic. (201) 040 -7274
Send results to: (Print full no	ama addrass a	100000000000000000000000000000000000000	(a)
WALLA WALLA	BLAN L	WATE	eshed council
810 5. MAIN	1		2
MUCON-FREE	SMARION	-,0	2,97862
	SAMPLE IN	FÓRMAT	TON
Sample collected by (name):		
BOB BOW	CR.		
Specific location where sam		ddress or	sample site, and type of faucet):
OBS# A			
Special instructions or comr	nents:		
Type of Sample (must chec	ck only one box	of #1 thro	ugh #4 listed below)
1. ☐ Routine Distribution	Sample	The Charles of the Charles	peat Sample (follow-up
Provide information below. Chlorinated: Yes No			an unsatisfactory sample)
Chlorine Residual: Total	Free	111111111111111111111111111111111111111	nformation below.
3. X Raw Water Source S		Ulisausia	actory routine lab number:
Required for Surface Water		Unsatisfa	actory routine collect date:
	Fecal Coliform	Chlorinat	adi Vae Ne
Public Systems must provide Source	Number from (WFI)	Chlorinat	ed: Yes No Residual: Total Free
	1 9		residual. Iotal riee
4. ☐ Sample Collected for		. E	Mark Control of the C
ConstructionRepa	irsPriv	ate Resid	enceOther
Exception and the second of 1 per			AND THE RESERVE OF THE PARTY OF
	RINKING WA	TER RE	SULTS LAB USE ONLY
□ Satisfactory		atisfactor	
Total Coliform Absent			Present and
		present coliform o	☐ E.coli absent resent ☐ Fecal coliform absent
D Doubers and Committee		Jometin p	
Replacement Sample R			anaw-ac-s-m
Sample not tested because Sample too old (>30 hours)		Test unsui	itable because:
Improper container		☐ Turbid	culture
Bacterial Density Results: F	Plate Count	/n	nl. E.coli/100ml.
Total Coliform	/100ml. Fed	al Coliforn	n_ 3. O_/100ml.
MICR Method Code:		Date and	Time Received;
1140 □ 1340	□ 2720	11/10/	200 140 an
Date Analyzed: 11 19	00 00	Date Re	ported: 17 /2 /
11111	ON CO	0	11100100
Lab/Sample Number		Lab Use	
143- 06247			



Burlington WA | 1620 S Walnut St - 98233

 Corporate Office
 800.755.9295 • 360.757.1400 • 360.757.1402fax

 Bellingham WA
 805 Orchard Dr Suite 4 - 98225

360.671.0688 • 360.671.1577fax

December 10, 2008

Page 1 of 1

Mr. Bob Bower Walla Walla Basin Watershed Council 810 S Main Street Milton-Freewater, OR 97862

RE: 08-16537 - HBDIC Recharge Project

Dear Mr. Bob Bower,

Your project: HBDIC Recharge Project, was received on Thursday November 20, 2008. All samples were analyzed within the accepted holding times, were appropriately preserved and were analyzed according to approved analytical protocols. The quality control data was within laboratory acceptance limits, unless specified in the QA reports.

If you have questions phone me at 800 755-9295.

For LJH

Respectfully Submitted,

Lawrence J Henderson, PhD Director of Laboratories

Enclosures Data Report

QC Reports

Chain of Custody



Burlington, WA 98233 (360) 757-1400 - FAX (360) 757-1402

Project Sheet

Client Name:

Walla Walla Basin Watershed Council

810 S Main Street

Milton-Freewater, OR 97862

Date: 11/20/2008

Reference Number: 08-16537

Project: HBDIC Recharge Project

Date Received: 11/20/2008

QC Level:

Turnaround: Standard Date Due: 12/4/2008

Project Notes:

Lab Number	Sample Number	Sample Description	Lab Method	Matrix	Date Sampled	Status
34917.00	OBS #1	Observation Well #1	NO3-N	W	11/19/2008	Pending
34917.00	OBS #1	Observation Well #1	CI	W	11/19/2008	Pending
34917.00	OBS #1	Observation Well #1	TDS	W	11/19/2008	Pending
34917.00	OBS #1	Observation Well #1	P04-P	W	11/19/2008	Pending
34917.00	OBS #1	Observation Well #1	525.Walla	W	11/19/2008	Pending
34917.10	OBS #1	Observation Well #1	531 ?	W	11/19/2008	Pending
34917.10	OBS #1	Observation Well #1	515	W	11/19/2008	Pending
34917.10	OBS #1	Observation Well #1	TKN	W	11/19/2008	Pending
34917.10	OBS #1	Observation Well #1	COD	W	11/19/2008	Pending
34917.10	OBS #1	Observation Well #1	TOC	W	11/19/2008	Pending
34917.10	OBS #1	Observation Well #1	TSS	W	11/19/2008	Pending
34918.00	Intake	HBDIC Intake	NO3-N	W	11/19/2008	Pending
34918.00	Intake	HBDIC Intake	CI	W	11/19/2008	Pending
34918.00	Intake	HBDIC Intake	TDS	W	11/19/2008	Pending
34918.00	Intake	HBDIC Intake	P04-P	W	11/19/2008	Pending
34918.00	Intake	HBDIC Intake	525.Walla	W	11/19/2008	Pending
34918.10	Intake	HBDIC Intake	531	W	11/19/2008	Pending
34918.10	Intake	HBDIC Intake	518	W	11/19/2008	Pending
34918.10	Intake	HBDIC Intake	TKN	W	11/19/2008	Pending
34918.10	Intake	HBDIC Intake	COD	W	11/19/2008	Pending
34918.10	Intake	HBDIC Intake	TOC	W	11/19/2008	Pending
34918.10	Intake	HBDIC Intake	TSS	W	11/19/2008	Pending
34918.10		Shipping Charge	SHIPPING	NA		Completed



Burlington WA Corporate Office

1620 S Walnut St - 98233

800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225 360.671.0688 • 360.671.1577fax

Page 1 of 1

Data Report

Client Name: Walla Walla Basin Watershed Council

810 S Main Street

Milton-Freewater, OR 97862

Reference Number: 08-16537

Project: HBDIC Recharge Project

Report Date: 12/2/08

Date Received: 11/20/08

Peer Review:

Sample Description: OBS #1 - Observation Well #1

Sample Date: 11/19/08 Collected By: Unknown

Lab N	umber: 34917						Collec	cted By:	Unknow	/n	
CAS ID#	Parameter	Result	PQL	MDL	Units	DF	Method	Analyzed	Analys	t Batch	Comment
14797-55-8	NITRATE-N	0.16	0.100	0.015	mg/L	1	300.0	11/20/08	BJ	I081120A	
16887-00-6	CHLORIDE	0.6	0.1	0.012	mg/L	.1	300.0	11/20/08	BJ	I081120A	
E-10173	TOTAL DISSOLVED SOLIDS	61	10	6	mg/L	1	SM2540 C	11/25/08	CCN	TDS_081125	
14265-44-2	ORTHO-PHOSPHATE	0.13	0.01	0.002	mg/L	1	SM4500-P F	11/20/08	so	OPHOS-081120	
E-10264	TOTAL KJELDAHL NITROGEN	0.22	0.2	0.0486	mg/L	1	SM4500-Norg C	11/21/08	so	TKN-081121	
E-10162	TOTAL SUSPENDED SOLIDS	ND	4	1.55	mg/L	1	SM2540 D	11/24/08	MAK	TSS_081124	
E-10195	TOTAL ORGANIC CARBON	0.91	0.50	0.0981	mg/L	1	SM5310 B	11/25/08	ВЈ	TOC_081125	
-10117	CHEMICAL OXYGEN DEMAND	ND	8	2	mg/L	1	SM5220 D	11/26/08	MAK	COD_081126	

and the same of th	oription: Intake - HBDIC Intake umber: 34918							le Date: cted By:			
CAS ID#	Parameter	Result	PQL	MDL	Units	DF	Method	Analyzed	Analys	Batch	Comment
14797-55-8	NITRATE-N	ND	0.100	0.015	mg/L	1	300.0	11/20/08	BJ	1081120A	
16887-00-6	CHLORIDE	0.6	0.1	0.012	mg/L	1	300.0	11/20/08	BJ	1081120A	
E-10173	TOTAL DISSOLVED SOLIDS	56	10	6	mg/L	1	SM2540 C	11/25/08	CCN	TDS_081125	
14265-44-2	ORTHO-PHOSPHATE	0.11	0.01	0.002	mg/L	1	SM4500-P F	11/20/08	so	OPHOS-081120	
E-10264	TOTAL KJELDAHL NITROGEN	0.24	0.2	0.0486	mg/L	1	SM4500-Norg C	11/21/08	so	TKN-081121	
E-10162	TOTAL SUSPENDED SOLIDS	8	4	1.55	mg/L	1	SM2540 D	11/24/08	MAK	TSS_081124	
E-10195	TOTAL ORGANIC CARBON	0.90	0.50	0.0981	mg/L	-31	SM5310 B	11/25/08	BJ	TOC_081125	
E-10117	CHEMICAL OXYGEN DEMAND	ND	8	2	mg/L	1	SM5220 D	11/26/08	MAK	COD_081126	

D.F. - Dilution Factor

^{*}D = Not detected above the listed practical quantitation limit (PQL) or not above the Method Detection Limit (MDL), if requested.

PQL = Practical Quantitation Limit is the lowest level that can be acheived within specified limits of precision and accuracy during routine laboratory operating conditions.



Burlington WA | 1620 S Walnut St - 98233

800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225 360.671.0688 • 360.671.1577fax

Page 1 of 1

HERBICIDES IN DRINKING WATER

Client Name: Walla Walla Basin Watershe

810 S Main Street

Milton-Freewater, OR 97862

Project::

Field ID: OBS #1

Sample Description: Observation Well #1

Sampled By: Unknown Sample Date: 11/19/08

Source Type: Sampler Phone: Reference Number: 08-16537

Project: HBDIC Recharge Project

Lab Number: 046-34917 Report Date: 12/5/08 Date Analyzed: 12/04/08 Date Extracted: 515_081201

Analyst: GO Peer Review: 1M

Analytical Method: 515.1

Chlorophenoxy Herbicides

CAS	COMPOUND	RESULTS	UNITS	PQL	MDL	MCL	COMMENT
EPA Re	egulated						
94-75-7	2,4 - D	ND	ug/L	0.2	0.11	70	HBDIC TARGET
93-72-1	2,4,5 - TP (SILVEX)	ND	ug/L	0.1	0.02	50	
F -5	PENTACHLOROPHENOL	ND	ug/L	0.1	0.044	1	
72 23-0	DALAPON	ND	ug/L	1.3	0.80	200	
88-85-7	DINOSEB	ND	ug/L	0.2	0.16	7	
1918-02-1	PICLORAM	ND	ug/L	0.1	0.089	500	
EPA U	nregulated						
1918-00-9	DICAMBA	ND	ug/L	0.1	0.045		
State U	Inregulated						
1861-32-1	TOTAL (DCPA & Metabolites)	ND	ug/L	0.1	0.089		
E-14028	DCPA (ACID METABOLITES)	ND	ug/L	0.1	0.1		
94-82-6	2,4 DB	ND	ug/L	0.8	0.10		
93-76-5	2,4,5 T	ND	ug/L	0.1	0.044		
25057-89-0	BENTAZON	ND	ug/L	0.2	0.067		
120-36-5	DICHLORPROP	ND	ug/L	0.3	0.089		
50594-66-6	ACIFLUORFEN	ND	ug/L	0.1	0.089		
133-90-4	CHLORAMBEN	ND	ug/L	0.2	0.2		
51-36-5	3,5 - DICHLOROBENZOIC ACID	ND	ug/L	0.1	0.044		

ND (Not Detected): indicates that the parameter was not detected above the State Reporting Limit (SRL).

L = upound is detected > or = to the State Reporting Level, SRL, specified increased monitoring frequencies may occur per DOH.

MCL (Maximum Contaminant Level) maximum permissible level of a contaminant in water established by EPA; Federal Action Levels are 0.015 mg/L for Lead and 1.3 mg/L for Copper. Sodium has a recommended limit of 20 mg/L. A blank MCL value indicates a level is not currently established.

Trigger Level: DOH Drinking Water Response level. Systems with compounds detected in excess of this level are required to take additional samples. Contact your regional DOH office.



Burlington WA | 1620 S Walnut St - 98233

800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225 360.671.0688 • 360.671.1577fax

Page 1 of 1

HERBICIDES IN DRINKING WATER

Client Name: Walla Walla Basin Watershe

810 S Main Street

Milton-Freewater, OR 97862

Project::

Field ID: Intake

Sample Description: HBDIC Intake

Sampled By: Unknown

Sample Date: 11/19/08

Source Type:

Sampler Phone:

Reference Number: 08-16537

Project: HBDIC Recharge Project

Lab Number: 046-34918

Report Date: 12/5/08

Date Analyzed: 12/04/08

Date Extracted: 515_081201

Analyst: CO

Peer Review: Analytical Method: 515.1

Chlorophenoxy Herbicides

CAS	COMPOUND	RESULTS	UNITS	PQL	MDL	MCL	COMMENT
EPA R	egulated						
4-75-7	2,4 - D	ND	ug/L	0.2	0.11	70	HBDIC TARGE
3-72-1	2,4,5 - TP (SILVEX)	ND	ug/L	0.1	0.02	50	
3-5	PENTACHLOROPHENOL	ND	ug/L	0.1	0.044	1	
~ ⊃9-0	DALAPON	ND	ug/L	1.3	0.80	200	
8-85-7	DINOSEB	ND	ug/L	0.2	0.16	7	
918-02-1	PICLORAM	ND	ug/L	0.1	0.089	500	
EPA U	nregulated						
918-00-9	DICAMBA	ND	ug/L	0.1	0.045		
State L	Inregulated						
861-32-1	TOTAL (DCPA & Metabolites)	ND	ug/L	0.1	0.089		
-14028	DCPA (ACID METABOLITES)	ND	ug/L	0.1	0.1		
1-82-6	2,4 DB	ND	ug/L	0.8	0.10		
3-76-5	2,4,5 T	ND	ug/L	0.1	0.044		
5057-89-0	BENTAZON	ND	ug/L	0.2	0.067		
20-36-5	DICHLORPROP	ND	ug/L	0.3	0.089		
0594-66-6	ACIFLUORFEN	ND	ug/L	0.1	0.089		
33-90-4	CHLORAMBEN	ND	ug/L	0.2	0.2		
1-36-5	3,5 - DICHLOROBENZOIC ACID	ND	ug/L	0.1	0.044		

ND (Not Detected): indicates that the parameter was not detected above the State Reporting Limit (SRL).

L Expound is detected > or = to the State Reporting Level, SRL, specified increased monitoring frequencies may occur per DOH.
MCL (Maximum Contaminant Level) maximum permissible level of a contaminant in water established by EPA; Federal Action Levels are 0.015 mg/L for Lead and 1.3 mg/L for Copper. Sodium has a recommended limit of 20 mg/L. A blank MCL value indicates a level is not currently established.

Trigger Level: DOH Drinking Water Response level. Systems with compounds detected in excess of this level are required to take additional samples. Contact your regional DOH office.



Burlington WA | 1620 S Walnut St - 98233

800.755.9295 • 360.757.1400 • 360.757.1402fax Bellingham WA 805 Orchard Dr Suite 4 - 98225 360.671.0688 • 360.671.1577fax

Page 1 of 1

CARBAMATES IN DRINKING WATER

Client Name: Walla Walla Basin Watershe

810 S Main Street

Milton-Freewater, OR 97862

Project::

Field ID: OBS #1

Sample Description: Observation Well #1

Sampled By: Unknown Sample Date: 11/19/08

Source Type: Sampler Phone: Reference Number: 08-16537

Project: HBDIC Recharge Project

Lab Number: 046-34917

Report Date: 11/25/08

Date Analyzed: 11/19/08 Date Extracted: 531_081119

Analyst: CO

Peer Review: Analytical Method: 531.2

Carbamates

CAS	COMPOUND	RESULTS	UNITS	PQL	MDL	MCL	COMMENT
EPA Re	egulated						
23135-22-0	OXYMAL	ND	ug/L	1.0	0.3	200	
1563-66-2	CARBOFURAN	ND	ug/L	1.0	0.2	40	
EPA Ur	regulated						
1646-87-3	ALDICARB SULFOXIDE	ND	ug/L	1.0	0.3		
1646-88-4	ALDICARB SULFONE	ND	ug/L	1.0	0.3		
2-77-5	METHOMYL	ND	ug/L	1.0	0.3		
16655-82-6	3-HYDROXYCARBOFURAN	ND	ug/L	1.0	0.3		
116-06-3	ALDICARB	ND	ug/L	1.0	0.3		
63-25-2	CARBARYL	ND	ug/L	1.0	0.2		
State U	nregulated - Other						
114-26-1	PROPOXUR (BAYGON)	ND	ug/L	1.0	0.4		
2032-65-7	METHIOCARB	ND	ug/L	1.0	0.3		



Burlington WA | 1620 S Walnut St - 98233 800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225

360.671.0688 • 360.671.1577fax

Page 1 of 1

CARBAMATES IN DRINKING WATER

Client Name: Walla Walla Basin Watershe

810 S Main Street

Milton-Freewater, OR 97862

Project::

Field ID: Intake

Sample Description: HBDIC Intake

Sampled By: Unknown

Source Type:

Sample Date: 11/19/08

Sampler Phone:

Reference Number: 08-16537

Project: HBDIC Recharge Project

Lab Number: 046-34918 Report Date: 11/25/08

Date Analyzed: 11/19/08 Date Extracted: 531_081119

Analyst: CQ Peer Review:

Analytical Method: 531.2

Carbamates

CAS	COMPOUND	RESULTS	UNITS	PQL	MDL	MCL	COMMENT
EPA Re	egulated						
23135-22-0	OXYMAL	ND	ug/L	1.0	0.3	200	
1563-66-2	CARBOFURAN	ND	ug/L	1.0	0.2	40	
EPA Ur	regulated						
1646-87-3	ALDICARB SULFOXIDE	ND	ug/L	1.0	0.3		
1646-88-4	ALDICARB SULFONE	ND	ug/L	1.0	0.3		
2-77-5	METHOMYL	ND	ug/L	1.0	0.3		
16655-82-6	3-HYDROXYCARBOFURAN	ND	ug/L	1.0	0.3		
116-06-3	ALDICARB	ND	ug/L	1.0	0.3		
63-25-2	CARBARYL	ND	ug/L	1.0	0.2		
State U	nregulated - Other						
114-26-1	PROPOXUR (BAYGON)	ND	ug/L	1.0	0.4		
2032-65-7	METHIOCARB	ND	ug/L	1.0	0.3		

injound is detected > or = to the State Reporting Level, SRL, specified increased monitoring frequencies may occur per DOH.

MCL (Maximum Contaminant Level) maximum permissible level of a contaminant in water established by EPA; Federal Action Levels are 0.015 mg/L for Lead and 1.3 mg/L for Copper. Sodium has a recommended limit of 20 mg/L. A blank MCL value indicates a level is not currently established.

Drain more value for influences a rever is not collecting established.

Trigger Level: DOH Drinking Water Response level. Systems with compounds detected in excess of this level are required to take additional samples. Contact your regional DOH office.

ND (Not Detected): indicates that the parameter was not detected above the State Reporting Limit (SRL).



Burlington WA | 1620 S Walnut St - 98233

800.755.9295 • 360.757.1400 • 360.757.1402fax Bellingham WA 805 Orchard Dr Suite 4 - 98225 360.671.0688 • 360.671.1577fax

Page 1 of 2

SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

Client Name: Walla Walla Basin Watershe

810 S Main Street

Milton-Freewater, OR 97862

Project::

Field ID: OBS #1

Sample Description: Observation Well #1

Sampled By: Unknown Sample Date: 11/19/08

Source Type: Sampler Phone: Reference Number: 08-16537

Project: HBDIC Recharge Project

Lab Number: 046-34917 Report Date: 12/10/08 Date Analyzed: 12/01/08 Date Extracted: 525X_081125

Analyst: CO Peer Review: Analytical Method: 525.2

SOC for Walla Walla


CAS	COMPOUND	RESULTS	UNITS	PQL	MDL	MCL	COMMENT
2312-35-8	PROPARGITE	ND	ug/L	0.5	-		
-7	BISPHENOL-A	ND	ug/L	1	2		
60-51-5	DIMETHOATE	ND	ug/L	0.5	0.03		
57837-19-1	METALAXYL	ND	ug/L	0.1			
15299-99-7	NAPROPAMIDE	ND	ug/L	0.1	0.05		
122-34-9	SIMAZINE	ND	ug/L	0.1	0.030	4	
86-86-2	1-NAPHTHALENEACETAMIDE	ND	ug/L	0.5	-		
333-41-5	DIAZINON	ND	ug/L	0.1	0.035		
60168-88-9	FENARIMOL	ND	ug/L	0.1	0.03		
58-89-9	LINDANE (BHC - GAMMA)	ND	ug/L	0.1	0.028	0.2	
7786-34-7	MEVINPHOS	ND	ug/l	0.1	0.03		
36-50-0	AZINPHOS-METHYL	ND	ug/L	0.5	0.12		
921-88-2	CHLORPYRIFOS	ND	ug/L	0.1	0.04		
2-54-8	4,4-DDD	ND	ug/L	0.1	0.024		
2-55-9	4,4-DDE	ND	ug/L	0.1	0.024		
50-29-3	4,4-DDT	ND	ug/L	0.1	0.022		
115-32-2	DICOFOL	ND	ug/L	1			
121-75-5	MALATHION	ND	ug/L	0.1	0.015		
298-00-0	METHYL PARATHION	ND	ug/L	0.5	0.1		
56-38-2	PARATHION-ETHYL	ND	ug/L	0.1	0.022		
732-11-6	PHOSMET	ND	ug/L	0.5	-		
43121-43-3	TRIADIMEFON	ND	ug/L	0.1	0.07		
68694-11-1	TRIFLUMIZOLE	ND	ug/L	1.0	1.0		
950-37-8	METHIDATHINON	ND	ug/L	0.5	0.5		


I Jound is detected > or = to the State Reporting Level, SRL, specified increased monitoring frequencies may occur per DOH.


MCL. (Maximum Contaminant Level) maximum permissible level of a contaminant in water established by EPA; Federal Action Levels are 0.015 mg/L for Lead and 1.3 mg/L for Copper. Sodium has a recommended limit of 20 mg/L. A blank MCL value indicates a level is not currently established.

Trigger Level: DOH Drinking Water Response level. Systems with compounds detected in excess of this level are required to take additional samples. Contact your regional DOH office.

ND (Not Detected): indicates that the parameter was not detected above the State Reporting Limit (SRL).











SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

CAS	COMPOUND	RESULTS	UNITS	PQL	MDL	MCL	COMMENT
88671-89-0	MYCLOBUTANIL	ND	ug/L	0.5	0.5		
51235-04-2	HEXAZINONE	ND	ug/L	0.1	0.05		

If jound is detected > or = to the State Reporting Level, SRL, specified increased monitoring frequencies may occur per DOH.

MCL (Maximum Contaminant Level) maximum permissible level of a contaminant in water established by EPA; Federal Action Levels are 0.015 mg/L for Lead and 1.3 mg/L for Copper. Sodium has a recommended limit of 20 mg/L. A blank MCL value indicates a level is not currently established.

Trigger Level: DOH Drinking Water Response level. Systems with compounds detected in excess of this level are required to take additional samples. Contact your regional DOH office.

ND (Not Detected): indicates that the parameter was not detected above the State Reporting Limit (SRL).



Burlington WA | 1620 S Walnut St - 98233

800.755.9295 • 360.757.1400 • 360.757.1402fax Bellingham WA 805 Orchard Dr Suite 4 - 98225

360.671.0688 • 360.671.1577fax

Page 1 of 2

SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

Client Name: Walla Walla Basin Watershe

810 S Main Street

Milton-Freewater, OR 97862

Project::

Field ID: Intake

Sample Description: HBDIC Intake

Sampled By: Unknown Sample Date: 11/19/08

Source Type:

Sampler Phone:

Reference Number: 08-16537

Project: HBDIC Recharge Project

Lab Number: 046-34918

Report Date: 12/10/08 Date Analyzed: 12/01/08

Date Extracted: 525X_081125

Analyst: GO Peer Review:

Analytical Method: \$25.2

SOC for Walla Walla


CAS	COMPOUND	RESULTS	UNITS	PQL	MDL	MCL	COMMENT	
2312-35-8	PROPARGITE	ND	ug/L	0.5	-			
)-7	BISPHENOL-A	ND	ug/L	1				
60-51-5	DIMETHOATE	ND	ug/L	0.5	0.03			
7837-19-1	METALAXYL	ND	ug/L	0.1	_			
15299-99-7	NAPROPAMIDE	ND	ug/L	0.1	0.05			
122-34-9	SIMAZINE	ND	ug/L	0.1	0.030	4		
36-86-2	1-NAPHTHALENEACETAMIDE	ND	ug/L	0.5	-			
333-41-5	DIAZINON	ND	ug/L	0.1	0.035			
0168-88-9	FENARIMOL	ND	ug/L	0.1	0.03			
8-89-9	LINDANE (BHC - GAMMA)	ND	ug/L	0.1	0.028	0.2		
786-34-7	MEVINPHOS	ND	ug/l	0.1	0.03			
36-50-0	AZINPHOS-METHYL	ND	ug/L	0.5	0.12			
921-88-2	CHLORPYRIFOS	ND	ug/L	0.1	0.04			
2-54-8	4,4-DDD	ND	ug/L	0.1	0.024			
2-55-9	4,4-DDE	ND	ug/L	0.1	0.024			
50-29-3	4,4-DDT	ND	ug/L	0.1	0.022			
115-32-2	DICOFOL	ND	ug/L	1	-			
121-75-5	MALATHION	ND	ug/L	0.1	0.015			
298-00-0	METHYL PARATHION	ND	ug/L	0.5	0.1			
56-38-2	PARATHION-ETHYL	ND	ug/L	0.1	0.022			
732-11-6	PHOSMET	ND	ug/L	0.5	-			
43121-43-3	TRIADIMEFON	ND	ug/L	0.1	0.07			
68694-11-1	TRIFLUMIZOLE	ND	ug/L	1.0	1.0			
950-37-8	METHIDATHINON	ND	ug/L	0.5	0.5			


Journal is detected > or = to the State Reporting Level, SRL, specified increased monitoring frequencies may occur per DOH.

MCL (Maximum Contaminant Level) maximum permissible level of a contaminant in water established by EPA; Federal Action Levels are 0.015 mg/L for Lead and 1.3 mg/L for Copper. Sodium has a recommended limit of 20 mg/L. A blank MCL value indicates a level is not currently established.

Trigger Level: DOH Drinking Water Response level. Systems with compounds detected in excess of this level are required to take additional samples. Contact your regional DOH office.

ND (Not Detected); indicates that the parameter was not detected above the State Reporting Limit (SRL).





Lab Number: 046-34918 Report Date: 12/10/08 11:01 Page 2 of 2



SYNTHETIC ORGANIC COMPOUNDS (SOC) REPORT

CAS	COMPOUND	RESULTS	UNITS	PQL	MDL	MCL	COMMENT	
88671-89-0	MYCLOBUTANIL	ND	ug/L	0.5	0.5			
51235-04-2	HEXAZINONE	ND	ug/L	0.1	0.05			

L : jound is detected > or = to the State Reporting Level, SRL, specified increased monitoring frequencies may occur per DOH.

MCL (Maximum Contaminant Level) maximum permissible level of a contaminant in water established by EPA; Federal Action Levels are 0.015 mg/L for Lead and 1.3 mg/L for Copper. Sodium has a recommended limit of 20 mg/L. A blank MCL value indicates a level is not currently established.

Trigger Level: DOH Drinking Water Response level. Systems with compounds detected in excess of this level are required to take additional samples. Contact your regional DOH office.

ND (Not Detected): indicates that the parameter was not detected above the State Reporting Limit (SRL).



Burlington WA | 1620 S Walnut St - 98233

Corporate Office

800.755.9295 • 360.757.1400 • 360.757.1402fax

Microbiology

Bellingham WA 805 Orchard Dr Suite 4 - 98225 360.671.0688 • 360.671.1577fax Page 1 of 10



SAMPLE INDEPENDENT QUALITY CONTROL REPORT

Laboratory Fortified Blank

Reference Number: 08-16537

Report Date: 12/10/08

			True			%		QC
Batch	Analyte	Result	Value	Units	Method	Recovery	Limits	Qualifier Type* Comment
515_081201	2,4 - D	2.04	2	ug/L	515.1	102	70-130	LFB
	2,4 - DCAA (SURR)	102		%	515.1		70-130	
	2,4 DB	6.1	8	ug/L	515.1	76	70-130	
	2,4,5 - TP (SILVEX)	1.08	1	ug/L	515.1	108	70-130	,
	2,4,5 T	1.01	1	ug/L	515.1	101	70-130	
	ACIFLUORFEN	0.89	1	ug/L	515.1	89	70-130	
	BENTAZON	1.73	2	ug/L	515.1	87	70-130	
	CHLORAMBEN	0.88	1	ug/L	515.1	88	70-130	
	DALAPON	12.7	13	ug/L	515.1	98	70-130	
	DCPA (ACID METABOLITES)	1.39	1	ug/L	515.1	139	70-130	HQ
	DICAMBA	1.12	1	ug/L	515.1	112	70-130	
	DICHLORPROP	3.27	3	ug/L	515.1	109	70-130	
	DINOSEB	2.08	2	ug/L	515.1	104	70-130	
	PENTACHLOROPHENOL	1.09	1	ug/L	515.1	109	70-130	
	PICLORAM	1.02	1	ug/L	515.1	102	70-130	
	TOTAL (DCPA & Metabolites)	1.39	1	ug/L	515.1	139	70-130	HQ
-05 004405	4.0 DIMETLINI O NITROPENZENE (O)	00						
25_081125	1,3-DIMETHYL-2-NITROBENZENE (Surr)	96		%	525.2	444	70-130	LFB
	4,4-DDD	1.11	1	ug/L	525.2	111	70-130	
	4,4-DDE	1.13	1	ug/L	525.2	113	70-130	
	4,4-DDT	1.15	1	ug/L	525.2	115	70-130	
	BISPHENOL-A	4.3	5	ug/L	525.2	86	85-115	
	DIAZINON	1.91	2	ug/L	525.2	96	70-130	
	LINDANE (BHC - GAMMA)	0.81	1	ug/L	525.2	81	70-130	
	MALATHION	2.45	2	ug/L	525.2	123	70-130	
	PERYLENE-D12 (Surr)	95		%	525.2		70-130	
	PYRENE-D10 (Surr)	89		%	525.2		70-130	
	SIMAZINE	1.16	1	ug/L	525.2	116	70-130	
	TRIPHENYLPHOSPHATE (Surr)	112		%	525.2		70-130	
525X_081125	1-NAPHTHALENEACETAMIDE	1.95	2	ug/L	525.2	98	70-130	LFB
esterno lis usseniones siste	CHLORPYRIFOS	2.09	2	ug/L	525.2	105	70-130	
	DICOFOL	2.72	2	ug/L	525.2	136	70-130	
	DIMETHOATE	0.63	1	ug/L	525.2		70-130	

^{*}Notation:

Recovery = (Result of Analysis)/(True Value) * 100

^{-1 =} Indicates % Recovery could not be calculated.

QCS: Quality Control Sample, a solution containing known concentrations of method analytes which is used to fortify an aliquot of reagent matrix. The QCS is obtained from an external source and is used to check lab performance.

LFB: Laboratory Fortified Blank, an aliquot of reagent matrix to which known quantities of method analytes are added in the lab. The LFB is analyzed exactly like a sample, and its purpose is to determine whether method performance is within accepted control limits.

MB or LRB: Method Blank or Laboratory Reagent Blank, an aliquot of reagent matrix is analyzed exactly like a sample, and its purpose is to determine if there is background contamination.



Burlington WA | 1620 S Walnut St - 98233

800.755.9295 • 360.757.1400 • 360.757.1402fax Bellingham WA 805 Orchard Dr Suite 4 - 98225

360.671.0688 • 360.671.1577fax

Page 2 of 10



SAMPLE INDEPENDENT QUALITY CONTROL REPORT

Laboratory Fortified Blank

Reference Number: 08-16537

Report Date: 12/10/08

			True			%		QC
Batch	Analyte	Result	Value	Units	Method	Recovery	Limits	Qualifier Type* Comment
525X_081125	FENARIMOL	1.39	1	ug/L	525.2	139	70-130	HQ LFB
	HEXAZINONE	1.23	1	ug/L	525.2	123	70-130	
	MALATHION	2.94	3	ug/L	525.2	98	70-130	
	METALAXYL	2.06	2	ug/L	525.2	103	70-130	
	METHIDATHINON	3	2	ug/L	525.2	150	85-115	HR
	MEVINPHOS	1.07	1	ug/L	525.2	107	70-130	
	MYCLOBUTANIL	2.27	2	ug/L	525.2	114	85-115	
	NAPROPAMIDE	1.12	1	ug/L	525.2	112	70-130	
	PARATHION-ETHYL	2.16	2	ug/L	525.2	108	70-130	
	PHOSMET	2.64	2	ug/L	525.2	132	70-130	HR
	PROPARGITE	2.05	2	ug/L	525.2	103	85-115	
	TRIADIMEFON	1.14	1	ug/L	525.2	114	70-130	
	TRIFLUMIZOLE	1.91	2	ug/L	525.2	96	85-115	
531_081119	BDMC (SURR)	108		%	531.2		70-130	LFB
31_081119	3-HYDROXYCARBOFURAN	50	50	ug/L	531.2	100	70-130	LFB
	ALDICARB	50	50	ug/L	531.2	100	70-130	
	ALDICARB SULFONE	49.9	50	ug/L	531.2	100	70-130	
	ALDICARB SULFOXIDE	49.5	50	ug/L	531.2	99	70-130	
	BDMC (SURR)	100		%	531.2		70-130	
	CARBARYL	48.5	50	ug/L	531.2	97	70-130	
	CARBOFURAN	46.4	50	ug/L	531.2	93	70-130	
	METHIOCARB	46	50	ug/L	531.2		70-130	
	METHOMYL	50.3	50	ug/L	531.2		70-130	
	OXYMAL	50	50	ug/L	531.2	100	70-130	
	PROPOXUR (BAYGON)	50.2	50	ug/L	531.2	100	70-130	
31_081119	3-HYDROXYCARBOFURAN	10.5	10	ug/L	531.2	105	70-130	LFB
TA	ALDICARB	10.6	10	ug/L	531.2		70-130	
	ALDICARB SULFONE	10.9	10	ug/L	531.2		70-130	
	ALDICARB SULFOXIDE	10.7	10	ug/L	531.2		70-130	
	BDMC (SURR)	101	3598	%	531.2		70-130	
	CARBARYL	10.3	10	ug/L	531.2		70-130	
	CARBOFURAN	10.1	10	ug/L	531.2		70-130	
	METHIOCARB	10.2	10	ug/L	531.2		70-130	

^{*}Notation:

Recovery = (Result of Analysis)/(True Value) * 100

A = Indicates % Recovery could not be calculated.

QCS: Quality Control Sample, a solution containing known concentrations of method analytes which is used to fortify an aliquot of reagent matrix. The QCS is obtained from an external source and is used to check lab performance.

LFB: Laboratory Fortified Blank, an aliquot of reagent matrix to which known quantities of method analytes are added in the lab. The LFB is analyzed exactly like a sample, and its purpose is to determine whether method performance is within accepted control limits.

MB or LRB: Method Blank or Laboratory Reagent Blank, an aliquot of reagent matrix is analyzed exactly like a sample, and its purpose is to determine if there is background contamination.



Burlington WA | 1620 S Walnut St - 98233 800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225 Microbiology 360.671.0688 • 360.671.1577fax Page 3 of 10



SAMPLE INDEPENDENT QUALITY CONTROL REPORT

Laboratory Fortified Blank

Reference Number: 08-16537

Report Date: 12/10/08

			True			%		QC	
Batch	Analyte	Result	Value	Units	Method	Recovery	Limits	Qualifier Type*	Comment
531_081119	METHOMYL	11.2	10	ug/L	531.2	112	70-130	LFB	
	OXYMAL	10.6	10	ug/L	531.2	106	70-130		
	PROPOXUR (BAYGON)	10.5	10	ug/L	531.2	105	70-130		
COD_081126	CHEMICAL OXYGEN DEMAND	48	50	mg/L	SM5220 D	96	80-120	LFB	
OPHOS-081120	ORTHO-PHOSPHATE	1.02	1.00	mg/L	SM4500-P F	102	70-130	LFB	
tds_081125	TOTAL DISSOLVED SOLIDS	482	500	mg/L	SM2540 C	96	80-120	LFB	
*ds_081125	TOTAL DISSOLVED SOLIDS	482	500	mg/L	SM2540 C	96	80-120	LFB	
TKN-081121	TOTAL KJELDAHL NITROGEN	·4.20	4.00	mg/L	SM4500-Norg C	105	80-120	LFB	
TSS_081124	TOTAL SUSPENDED SOLIDS	480	500	mg/L	SM2540 D	96	80-120	LFB	
TSS_081124	TOTAL SUSPENDED SOLIDS	490	500	mg/L	SM2540 D	98	80-120	LFB	

*Notation:

Recovery = (Result of Analysis)/(True Value) * 100

⁼ Indicates % Recovery could not be calculated.

QCS: Quality Control Sample, a solution containing known concentrations of method analytes which is used to fortify an aliquot of reagent matrix. The QCS is obtained from an external source and is used to check lab performance.

LFB: Laboratory Fortified Blank, an aliquot of reagent matrix to which known quantities of method analytes are added in the lab. The LFB is analyzed exactly like a sample, and its purpose is to determine whether method performance is within accepted control limits.

MB or LRB: Method Blank or Laboratory Reagent Blank, an aliquot of reagent matrix is analyzed exactly like a sample, and its purpose is to determine if there is background contamination.



Burlington WA Corporate Office 1620 S Walnut St - 98233 800.755.9295 • 360.757.1

800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225 360.671.0688 • 360.671.1577fax Page 4 of 10



SAMPLE INDEPENDENT QUALITY CONTROL REPORT

Low Level Laboratory Fortified Blank

Reference Number: 08-16537

Report Date: 12/10/08

			True			%		QC	
Batch	Analyte	Result	Value	Units	Method	Recovery	Limits	Qualifier Type*	Comment
531_081119	3-HYDROXYCARBOFURAN	0.96	1	ug/L	531.2	96	50-150		
	ALDICARB	0.95	1	ug/L	531.2	95	50-150		
	ALDICARB SULFONE	1	1	ug/L	531.2	100	50-150		
	ALDICARB SULFOXIDE	0.99	1	ug/L	531.2	99	50-150		
	CARBARYL	1	1	ug/L	531.2	100	50-150		
	CARBOFURAN	1.2	1	ug/L	531.2	120	50-150		
	METHIOCARB	1.2	1	ug/L	531.2	922	50-150		
	METHOMYL	0.94	1	ug/L	531.2		50-150		
	OXYMAL	0.95	1	ug/L	531.2		50-150		
	PROPOXUR (BAYGON)	0.91	1	ug/L	531.2	4000	50-150		

*Notation:

Recovery = (Result of Analysis)/(True Value) * 100

MB or LRB: Method Blank or Laboratory Reagent Blank, an aliquot of reagent matrix is analyzed exactly like a sample, and its purpose is to determine if there is background contamination.

α = Indicates % Recovery could not be calculated.

QCS: Quality Control Sample, a solution containing known concentrations of method analytes which is used to fortify an aliquot of reagent matrix. The QCS is obtained from an external source and is used to check lab performance.

LFB: Laboratory Fortified Blank, an aliquot of reagent matrix to which known quantities of method analytes are added in the lab. The LFB is analyzed exactly like a sample, and its purpose is to determine whether method performance is within accepted control limits.



Burlington WA Corporate Office 1620 S Walnut St - 98233 800.755.9295 • 360.757.1 800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225 360.671.0688 • 360.671.1577fax

Page 5 of 10



SAMPLE INDEPENDENT QUALITY CONTROL REPORT

Laboratory Reagent Blank

Reference Number: 08-16537

Report Date: 12/10/08

			True			%	QC	
Batch	Analyte	Result	Value	Units	Method	Recovery Limits	Qualifier Type*	Comment
COD_081126	CHEMICAL OXYGEN DEMAND	ND		mg/L	SM5220 D	4.00000		
1081120A	CHLORIDE	ND		mg/L	300.0	0.10000	LRB	
	NITRATE-N	ND		mg/L	300.0	0.10000		
OPHOS-081120	ORTHO-PHOSPHATE	ND		mg/L	SM4500-P F	0.10000	LRB	
TKN-081121	TOTAL KJELDAHL NITROGEN	ND		mg/L	SM4500-Norg C	1.00000	LRB	

*Notation:

Recovery = (Result of Analysis)/(True Value) * 100

... = Indicates % Recovery could not be calculated.

QCS: Quality Control Sample, a solution containing known concentrations of method analytes which is used to fortify an aliquot of reagent matrix. The QCS is obtained from an external source and is used to check lab performance.

LFB: Laboratory Fortified Blank, an aliquot of reagent matrix to which known quantities of method analytes are added in the lab. The LFB is analyzed exactly like a sample, and its purpose is to determine whether method performance is within accepted control limits.

MB or LRB: Method Blank or Laboratory Reagent Blank, an aliquot of reagent matrix is analyzed exactly like a sample, and its purpose is to determine if there is background contamination.



Burlington WA | 1620 S Walnut St - 98233

800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225 Microbiology 360.671.0688 • 360.671.1577fax

Page 6 of 10



SAMPLE INDEPENDENT QUALITY CONTROL REPORT

Method Blank

Reference Number: 08-16537

Report Date: 12/10/08

2-4-6	100000		True			%	QC	
Batch	Analyte	Result	Value	Units	Method	Recovery Limits	Qualifier Type* Co	mment
15_081201	2,4 - D	ND		ug/L	515.1	0.05000	MB	
	2,4 - DCAA (SURR)	99		%	515.1			
	2,4 DB	ND		ug/L	515.1	0.25000		
	2,4,5 - TP (SILVEX)	ND		ug/L	515.1	0.10000		
	2,4,5 T	ND		ug/L	515.1	0.10000		
	ACIFLUORFEN	ND		ug/L	515.1	0.50000		
	BENTAZON	ND		ug/L	515.1	0.12000		
	CHLORAMBEN	ND		ug/L	515.1	0.20000		
	DALAPON	ND		ug/L	515.1	0.50000		
	DCPA (ACID METABOLITES)	ND		ug/L	515.1	0.10000		
	DICAMBA	ND		ug/L	515.1	0.05000		
	DICHLORPROP	ND		ug/L	515.1	0.12000		
	DINOSEB	ND		ug/L	515.1	0.10000		
	PENTACHLOROPHENOL	ND		ug/L	515.1	0.02000		
	PICLORAM	ND		ug/L	515.1	0.05000		
	TOTAL (DCPA & Metabolites)	ND		ug/L	515.1	0.02000		
25_081125	1,3-DIMETHYL-2-NITROBENZENE (Surr)	96		%	505.0			
-	4,4-DDD	ND			525.2		MB	
	4,4-DDE	ND		ug/L	525.2	0.05000		
	4,4-DDT	ND		ug/L	525.2	0.05000		
	BISPHENOL-A	ND		ug/L	525.2	0.05000		
	DIAZINON			ug/L	525.2	1.00000		
	LINDANE (BHC - GAMMA)	ND		ug/L	525.2	0.05000		
	MALATHION	ND		ug/L	525.2	0.02000		
	PERYLENE-D12 (Surr)	ND 07		ug/L	525.2	0.05000		
	PYRENE-D10 (Surr)	97		%	525.2			
	SIMAZINE	93 ND		%	525.2			
	TRIPHENYLPHOSPHATE (Surr)	ND 400		ug/L	525.2	0.02000		
	THE HEATER HOSE FIATE (SUIT)	109		%	525.2			
5X_081125	1-NAPHTHALENEACETAMIDE	ND		ug/L	525.2	0.10000	MB	
	AZINPHOS-METHYL	ND		ug/L	525.2	0.00000		
	CHLORPYRIFOS	ND		ug/L	525.2	0.00000		
	DICOFOL	ND		ug/L	525.2	0.00000		

*Notation:

Recovery = (Result of Analysis)/(True Value) * 100

^{, =} Indicates % Recovery could not be calculated.

QCS: Quality Control Sample, a solution containing known concentrations of method analytes which is used to fortify an aliquot of reagent matrix. The QCS is obtained from an external source and is used to check lab performance.

LFB: Laboratory Fortified Blank, an aliquot of reagent matrix to which known quantities of method analytes are added in the lab. The LFB is analyzed exactly like a sample, and its purpose is to determine whether method performance is within accepted control limits.

MB or LRB: Method Blank or Laboratory Reagent Blank, an aliquot of reagent matrix is analyzed exactly like a sample, and its purpose is to determine if there is background contamination.



Microbiology

Burlington WA | 1620 S Walnut St - 98233

800.755.9295 • 360.757.1400 • 360.757.1402fax Bellingham WA 805 Orchard Dr Suite 4 - 98225

360.671.0688 • 360.671.1577fax

Page 7 of 10



SAMPLE INDEPENDENT QUALITY CONTROL REPORT

Method Blank

Reference Number: 08-16537

Report Date: 12/10/08

Dotah	W 100		True			%	QC	
Batch 525X_081125	Analyte	Result	Value	Units	Method	Recovery Limits	Qualifier Type*	Comment
5257_061125	DIMETHOATE	ND		ug/L	525.2	0.00000	and the second s	Comment
	FENARIMOL	ND		ug/L	525.2	0.00000		
	HEXAZINONE	ND		ug/L	525.2	0.00000		
	MALATHION	ND		ug/L	525.2	0.05000		
	METALAXYL	ND		ug/L	525.2	0.10000		
	METHIDATHINON	ND		ug/L	525.2	0.50000		
	METHYL PARATHION	ND		ug/L	525.2	0.00000		
	MEVINPHOS	ND		ug/L	525.2	0.00000		
	MYCLOBUTANIL	ND		ug/L	525.2	0.50000		
	NAPROPAMIDE	ND		ug/L	525.2	0.00000		
	PARATHION-ETHYL	ND		ug/L	525.2	0.05000		
	PHOSMET	ND		ug/L	525.2	0.10000		
	PROPARGITE	ND		ug/L	525.2	0.00000		
	TRIADIMEFON	ND		ug/L	525.2	0.00000		
	TRIFLUMIZOLE	ND		ug/L	525.2	1.00000		
531_081119	3-HYDROXYCARBOFURAN	N/D						
	ALDICARB	ND		ug/L	531.2	0.50000	MB	
	ALDICARB SULFONE	ND		ug/L	531.2	0.25000		
	ALDICARB SULFOXIDE	ND		ug/L	531.2	0.40000		
		ND		ug/L	531.2	0.25000		
	BDMC (SURR)	98		%	531.2	0.00000		
	CARBARYL	ND		ug/L	531.2	0.50000		
	CARBOFURAN	ND		ug/L	531.2	0.45000		
	METHIOCARB	ND		ug/L	531.2	1.00000		
	METHOMYL	ND		ug/L	531.2	0.25000		
	OXYMAL	ND		ug/L	531.2	1.00000		
	PROPOXUR (BAYGON)	ND		ug/L	531.2	0.25000		
OPHOS-081120	ORTHO-PHOSPHATE	ND		mg/L	SM4500-P F	0.10000	MB	
	4							
ds_081125	TOTAL DISSOLVED SOLIDS	ND		mg/L	SM2540 C	2.50000	MB	
ds_081125	TOTAL DISSOLVED SOLIDS	ND		mg/L	SM2540 C	2.50000	MB	

^{*}Notation:

Recovery = (Result of Analysis)/(True Value) * 100

^{. =} Indicates % Recovery could not be calculated.

QCS: Quality Control Sample, a solution containing known concentrations of method analytes which is used to fortify an aliquot of reagent matrix. The QCS is obtained from an external source and is used to check lab performance.

LFB: Laboratory Fortified Blank, an aliquot of reagent matrix to which known quantities of method analytes are added in the lab. The LFB is analyzed exactly like a sample, and its purpose is to determine whether method performance is within accepted control limits.

MB or LRB: Method Blank or Laboratory Reagent Blank, an aliquot of reagent matrix is analyzed exactly like a sample, and its purpose is to determine if there is background contamination.



Burlington WA | 1620 S Walnut St - 98233

800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225 Microbiology 360.671.0688 • 360.671.1577fax Page 8 of 10



SAMPLE INDEPENDENT QUALITY CONTROL REPORT

Method Blank

Reference Number: 08-16537

Report Date: 12/10/08

			True			%	QC	
Batch	Analyte	Result	Value	Units	Method	Recovery Limits	Qualifier Type*	Comment
TKN-081121	TOTAL KJELDAHL NITROGEN	ND		mg/L	SM4500-Norg C	0.12000	МВ	
TSS_081124	TOTAL SUSPENDED SOLIDS	ND		mg/L	SM2540 D	1.00000	MB	
TSS_081124	TOTAL SUSPENDED SOLIDS	ND		mg/L	SM2540 D	1.00000	MB	

*Notation:

Recovery = (Result of Analysis)/(True Value) * 100

\(\) = Indicates % Recovery could not be calculated.

QCS: Quality Control Sample, a solution containing known concentrations of method analytes which is used to fortify an aliquot of reagent matrix. The QCS is obtained from an external source and is used to check lab performance.

LFB: Laboratory Fortified Blank, an aliquot of reagent matrix to which known quantities of method analytes are added in the lab. The LFB is analyzed exactly like a sample, and its purpose is to determine whether method performance is within accepted control limits.

MB or LRB: Method Blank or Laboratory Reagent Blank, an aliquot of reagent matrix is analyzed exactly like a sample, and its purpose is to determine if there is background contamination.



Microbiology

Burlington WA | 1620 S Walnut St - 98233

800.755.9295 • 360.757.1400 • 360.757.1402fax Bellingham WA 805 Orchard Dr Suite 4 - 98225

360.671.0688 • 360.671.1577fax

Page 9 of 10



SAMPLE INDEPENDENT QUALITY CONTROL REPORT

Quality Control Sample

Reference Number: 08-16537 Report Date: 12/10/08

			True			%		QC	
Batch	Analyte	Result	Value	Units	Method	Recovery	Limits	Qualifier Type*	Comment
531_081119	3-HYDROXYCARBOFURAN	26.9	26.9	ug/L	531.2	100	70-130	QCS	
	ALDICARB	25.6	27.9	ug/L	531.2	92	70-130		
	ALDICARB SULFONE	37	38.5	ug/L	531.2	96	70-130		
	ALDICARB SULFOXIDE	21	28.8	ug/L	531.2	73	70-130		
	BDMC (SURR)	122		%	531.2		70-130		
	CARBARYL	83.9	90.1	ug/L	531.2	93	70-130		
	CARBOFURAN	123	136	ug/L	531.2	90	70-130		
	METHIOCARB	33.9	34.7	ug/L	531.2	98	70-130		
	METHOMYL	81.3	78.3	ug/L	531.2	104	70-130		
	OXYMAL	33.4	32.5	ug/L	531.2	103	70-130		
	PROPOXUR (BAYGON)	31.2	30.1	ug/L	531.2	104	70-130		
531_081119	3-HYDROXYCARBOFURAN	46.8	50	ug/L	531.2	94	70-130	QCS	
	ALDICARB	50.4	50	ug/L	531.2	101	70-130		
	ALDICARB SULFONE	50.2	50	ug/L	531.2	100	70-130		
	ALDICARB SULFOXIDE	53.2	50	ug/L	531.2	106	70-130		
	BDMC (SURR)	112		%	531.2		70-130		
	CARBARYL	46.5	50	ug/L	531.2	93	70-130		
	CARBOFURAN	48.7	50	ug/L	531.2	97	70-130		
	METHIOCARB	48.9	50	ug/L	531.2	98	70-130		
	METHOMYL	51.7	50	ug/L	531.2	103	70-130		
	OXYMAL	50	50	ug/L	531.2	100	70-130		
	PROPOXUR (BAYGON)	51	50	ug/L	531.2	102	70-130		
COD_081126	CHEMICAL OXYGEN DEMAND	91	92	mg/L	SM5220 D	99	80-120	QCS	
1081120A	CHLORIDE	28.3	30.0	mg/L	300.0	94	80-120	QCS	
	NITRATE-N	2.42	2.50	mg/L	300.0	97	80-120		
OPHOS-081120	ORTHO-PHOSPHATE	0.49	0.49	mg/L	SM4500-P F	100	70-130	QCS	
TKN-081121	TOTAL KJELDAHL NITROGEN	5.02	4.77	mg/L	SM4500-Norg C	105	80-120	QCS	

*Notation:

Recovery = (Result of Analysis)/(True Value) * 100

^{. =} Indicates % Recovery could not be calculated.

QCS: Quality Control Sample, a solution containing known concentrations of method analytes which is used to fortify an aliquot of reagent matrix. The QCS is obtained from an external source and is used to check lab performance.

LFB: Laboratory Fortified Blank, an aliquot of reagent matrix to which known quantities of method analytes are added in the lab. The LFB is analyzed exactly like a sample, and its purpose is to determine whether method performance is within accepted control limits.

MB or LRB: Method Blank or Laboratory Reagent Blank, an aliquot of reagent matrix is analyzed exactly like a sample, and its purpose is to determine if there is background contamination.



Burlington WA | 1620 S Walnut St - 98233

800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225 360.671.0688 • 360.671.1577fax Page 10 of 10



SAMPLE INDEPENDENT QUALITY CONTROL REPORT

Quality Control Sample

Reference Number: 08-16537

Report Date: 12/10/08

True

Result

Value

Recovery Limits Qualifier Type*

Batch

Analyte

Units

Method

Comment

*Notation:

Recovery = (Result of Analysis)/(True Value) * 100

. = Indicates % Recovery could not be calculated.

QCS: Quality Control Sample, a solution containing known concentrations of method analytes which is used to fortify an aliquot of reagent matrix. The QCS is obtained from an external source and is used to check lab performance.

LFB: Laboratory Fortified Blank, an aliquot of reagent matrix to which known quantities of method analytes are added in the lab. The LFB is analyzed exactly like a sample, and its purpose is to determine whether method performance is within accepted control limits.

MB or LRB: Method Blank or Laboratory Reagent Blank, an aliquot of reagent matrix is analyzed exactly like a sample, and its purpose is to determine if there is background contamination.



Burlington WA 1620 S Walnut St - 98233 corporate Office 800.755.9295 • 360.757.1400 • 360.757.1402fax Bellingham WA 805 Orchard Dr Suite 4 - 98225 Microbiology 360.671.0688 • 360.671.1577fax



2 Page 1 of

QUALITY CONTROL REPORT

Duplicate and Matrix Spike/Matrix Spike Duplicate Report

Reference Number: 08-16537

Report Date: 12/10/2008

Duplicate	a								
3011			Duplicate				oc		
Batch	Sample Analyte	Result	Result	Units	%RPD	Limits	Qualifier	Comments	
515_081201	34917 2,4 - DCAA (SURR)	103	105	%	1.9	0-45	DUP		
525_081125	34807 13-DIMETHYL-2-NITROBENZENE (Surr	96	96	%	0.0	0-45	DUP		
			92	%	1.1	0-45	DUP		
		66	96	%	3.1	0-45	DUP		
		106	108	%	1.9	0-45	DUP		
531 081119						1	i		
	32550 OXYMAL	55.7	59.4	ng/L	6.4	0-45	and .		
	32550 CARBOFURAN	62.9	67.2	ng/L	9.9	0-45	DUP		
		42.2	44.6	ng/L	5.5	0-45	DUP	0	
		40.3	43.2	ug/L	6.9	0-45	DUP	0	
		61.7	65.8	ng/L	6.4	0-45	DUP	0	
		41.9	42.6	ng/L	1.7	0-45	DUP	0	
		37.7	40.2	ng/L	6.4	0-45	and	0	
		44.8	48.4	ng/L	7.7	0-45	DUP	0	
		101	107	ng/L	5.8	0-45	DUP	0.	
		123	131	ng/L	6.3	0-45	DUP	Ω.	
		92	103	Area	8.1	0-45	DUP	0.	
COD 081126							i		
1	35364 CHEMICAL OXYGEN DEMAND	8200	8550	mg/L	4.2	0-45	And	1	
1081120A							ō		
	34897 NITRATE-N	2.5	2.5	mg/L	0.0		ביים ו	L (
	34897 CHLORIDE	63	63	mg/L	0.0		70	1	
	34918 CHLORIDE	9.0	0.5	mg/L	18.2	0-45	DUP	۵.	
OPHOS-081120	20						i		
	34918 ORTHO-PHOSPHATE	0.11	0.11	mg/L	0.0	0-20	DUP	۵.	

%RPD = Relative Percent Difference

NA = Indicates %RPD could not be calculated

Matrix Spike (MS)/Matrix Spike Duplicate (MSD) analyses are used to determine the accuracy (MS) and precision (MSD) of a analytical method in a given sample matrix. Therefore, the usefulness of this report is limited to samples of similar matrices analyzed in the same analytical batch.



Report Date: 12/10/2008 Page 2 of 5 Reference Number: 08-16537

Duplicate	O		Duplicate				oc		
Batch	Sample Analyte	Result	Result	Units	%RPD	%RPD Limits	Qualifier	Comments	
TDS_081125	35236 TOTAL DISSOLVED SOLIDS	382	379	mg/L	9.0	0.8 0-45	DUP		
TKN-081121	34471 TOTAL KJELDAHL NITROGEN	11.4	11.4	mg/L	0.0	0-45	DUP		
TSS_081124	35097 TOTAL SUSPENDED SOLIDS	19	23	mg/L	19.0	0-45	DUP		

%RPD = Relative Percent Difference

NA = Indicates %RPD could not be calculated
Matrix Spike (MS)/Matrix Spike Duplicate (MSD) analyses are used to determine the accuracy (MS) and precision (MSD) of a analytical method in a given sample matrix. Therefore, the usefulness of this report is limited to samples of similar matrices analytical batch.



Page 3 of 5 Reference Number: 08-16537 Report Date: 12/10/2008

Matrix Spike	pike				Duplicate										
				Spike	Spike	Spike		Percen	Percent Recovery				oc		
Batch	Sample Analyte	alyte	Result	Result	Result	Conc	Units	MS	MSD	Limits	%RPD	Limits	Qualifier	Comments	
515 081201															
ľ	34807 2,4	2,4-D	QN	1.87		2	ng/L	94	NA	65-135	NA	09-0	LFM	V	
	34807 2,4	2,4,5 - TP (SILVEX)	QN	0.99			ng/L	66	NA	65-135	NA	09-0	LFM	V	
	34807 PE	PENTACHLOROPHENOL	Q	0.99		-	ng/L	66	NA	65-135	NA	09-0	LFM	V	
		DALAPON	Q	11.1		13	ng/L	85	NA	65-135	NA	09-0	LFM	V	
		DINOSEB	Q	1.99		2	ng/L	100	NA	65-135	NA	09-0	LFM	V	
	34807 PIC	PICLORAM	QN	0.91		-	ng/L	91	NA	65-135	NA	09-0	LFM	V	
	34807 DIC	DICAMBA	Q	-		-	ng/L	100	NA	65-135	NA	09-0	LFM	V	
		TOTAL (DCPA & Metabolites)	Q	1.28		-	ng/L	128	NA	65-135	NA	09-0	LFM	V	
		2,4 DB	N	6.29		8	ng/L	79	NA	65-135	NA	09-0	LFM	V	
	34807 2,4	2,4,5 T	Q	0.93		-	ng/L	93	NA	65-135	NA	09-0	LFM	_	
	34807 BE	BENTAZON	N	1.57		2	ng/L	62	NA	65-135	NA	09-0	LFM	V	
	34807 DIC	DICHLORPROP	N	3.06		8	ng/L	102	NA	65-135	AN	09-0	LFM	V	
	34807 AC	ACIFLUORFEN	Q	0.84		-	ng/L	84	NA	65-135	AN	09-0	LFM	5	
	34807 CH	CHLORAMBEN	N	0.85		-	ng/L	82	NA	65-135	NA	0-20	LFM	5	
	34807 2,4	2,4 - DCAA (SURR)	96	93			%		NA	70-130	NA	09-0	LFM	V	
525_081125															
	34405 BIS	BISPHENOL-A	ND	3.1		2	ng/L	62	A	70-130	NA	0-20	ME LFM	5	
	34405 SIN	SIMAZINE	Q	0.94		-	ng/L	94	NA	70-130	AN	09-0	LFM	5	
	34405 DI/	DIAZINON	R	1.93		-	ng/L	193	A	70-130	NA	09-0	LFM	5	
	34405 LIN	LINDANE (BHC - GAMMA)	Q	0.91		-	ng/L	91	NA	70-130	NA	09-0	LFM	5	
	34405 4,4	4,4-DDD	2	0.95		-	ng/L	92	NA	70-130	NA	09-0	LFM	>	
	34405 4,4	4,4-DDE	Q	0.87		-	ng/L	87	NA	70-130	NA	09-0	LFM	>	
	34405 4,4	4,4-DDT	R	0.93		-	ng/L	93	NA	70-130	NA	09-0	LFM	×	
	34405 M/	MALATHION	Q	5.09		2	ng/L	105	NA	70-130	Ϋ́	09-0	LFM	5	
	34405 PA	PARATHION-ETHYL	Q	1.96		2	ng/L	86	NA	70-130	AN	09-0	LFM	Σ.	
525X_081125	2														
	34405 PF	PROPARGITE	Q	2.18		2	ng/L	109	NA	70-130	AN	0-20		Σ.	
	34405 DII	DIMETHOATE	R	0.62		-	ng/L	62	NA	70-130	AN	0-20	N1 LFM		
	34405 ME	METALAXYL	Q	1.93		2	ng/L	26	NA	70-130	AN	0-20	LFM	Σ.	
	34405 NA	NAPROPAMIDE	N	1.04		-	ng/L	104	NA	70-130	AN	0-20	LFM	∑	
	34405 1-1	1-NAPHTHALENEACETAMIDE	Q	1.86		2	ng/L	93	NA	70-130	NA	0-20	LFM	≥	
	34405 FE	FENARIMOL	Q	1.16		-	ng/L	116	NA	70-130	Y Y	0-20	LFM	Σ	
	34405 ME	MEVINPHOS	N	0.99		-	ng/L	66	NA	70-130	NA	0-20	LFM	M	
	34405 CF	CHLORPYRIFOS	ND	1.91		2	ng/L	96	NA	70-130	NA NA	0-20		Σ	
	34405 DI	DICOFOL	N	2.62		2	ng/L	131	NA	70-130	NA	0-20	HR LFM	M	

%RPD = Relative Percent Difference

NA = Indicates %RPD could not be calculated

Matrix Spike (MS)/Matrix Spike Duplicate (MSD) analyses are used to determine the accuracy (MS) and precision (MSD) of a analytical method in a given sample matrix. Therefore, the usefulness of this report is limited to samples of similar matrices analyzed in the same analyzed.



Report Date: 12/10/2008 Reference Number: 08-16537 Page 4 of 5

Matrix Spike	oike				Duplicate										
				Spike	Spike	Spike		Percent F	Percent Recovery				00		
Batch	Sample Analyte	Analyte	Result	Result	Result	Conc	Units	MS	MSD	Limits	%RPD	Limits	Qualifier	Comments	ıts
	34405	34405 MALATHION	QN	2.52		3	ng/L	84	NA	70-130	NA	09-0	17	LFM	
	34405	PARATHION-ETHYL	QN	1.74		2	ng/L	87	NA	70-130	NA	09-0	5	LFM	
	34405	PHOSMET	QN	2.26		2	ng/L	113	NA	70-130	NA	0-20	5	LFM	
	34405	TRIADIMEFON	QN	96.0		_	ng/L	96	NA	70-130	NA	0-20	5	LFM	
	34405	TRIFLUMIZOLE	QN	1.62		2	ng/L	81	NA	70-130	NA	0-20	5	LFM	
	34405	METHIDATHINON	Q	2.62		2	ng/L	131	NA	70-130	NA	0-20	HR LF	LFM	
	34405	MYCLOBUTANIL	Q	2.02		2	ng/L	101	NA	70-130	NA	0-20		LFM	
	34405	HEXAZINONE	Q	1.09		-	ng/L	109	NA	70-130	NA	0-20	ב	LFM	
531_081119															
	33930	OXYMAL	QN	10.5	6.6	10	ng/L	105	66	70-130	5.9	0-20	_	LFM	
	33930	CARBOFURAN	Q	10.2	10.1	10	ng/L	102	101	70-130	1.0	0-20	_	LFM	54
	33930	ALDICARB SULFOXIDE	Q.	10.4	8.6	10	ng/L	104	86	70-130	5.9	0-20	_	LFM	
	33930	ALDICARB SULFONE	Q	10.8	9.8	10	ng/L	108	86	70-130	7.6	0-20	_	LFM	
	33930	METHOMYL	Q	1	10.1	10	ng/L	110	101	70-130	8.5	0-20	_	LFM	
	33930	3-HYDROXYCARBOFURAN	ND	10.9	10.3	10	ng/L	109	103	70-130	2.7	0-20	_	LFM	
	33930	ALDICARB	QN	10.7	10.3	10	ng/L	107	103	70-130	3.8	0-20	_	LFM	
	33930	CARBARYL	N	10.5	10.4	10	ng/L	105	104	70-130	1.0	0-20	_	LFM	
	33930	PROPOXUR (BAYGON)	QN	10.9	10.7	10	ng/L	109	107	70-130	1.9	0-20	_	LFM	
	33930	METHIOCARB	ND	10.5	9.3	10	ng/L	105	93	70-130	12.1	0-20	_	LFM	
	33930	BDMC (SURR)	130	100	100		%		NA	70-130	NA	0-20	_	LFM	
	34917	OXYMAL	ND	2	2.2	2	ng/L	100	110	70-130	9.5	0-20	_	LFM	
	34917	CARBOFURAN	ND	2	2.1	2	ng/L	100	105	70-130	4.9	0-20	_	LFM	
	34917	ALDICARB SULFOXIDE	Q	2.1	2	2	ng/L	105	100	70-130	4.9	0-20	_	LFM	
	34917	ALDICARB SULFONE	ND	2	2.3	2	ng/L	100	115	70-130	14.0	0-20	_	LFM	
	34917	METHOMYL	QN	2	2.2	2	ng/L	100	110	70-130	9.5	0-20		LFM	
	34917	3-HYDROXYCARBOFURAN	QN	2	2.05	2	ng/L	100	103	70-130	2.5	0-20		LFM	
	34917	ALDICARB	Q	2	2.1	2	ng/L	100	105	70-130	4.9	0-20		LFM	
	34917	CARBARYL	QN	2.05	2.2	2	ng/L	103	110	70-130	7.1	0-20		LFM	
	34917	PROPOXUR (BAYGON)	Q	2.1	2.2	2	ng/L	105	110	70-130	4.7	0-20		LFM	
	34917	METHIOCARB	Q	2	2.5	2	ng/L	100	125	70-130	22.2	0-20		LFM	
	34917	BDMC (SURR)	66	88	86		%		NA	70-130	NA	0-20		LFM	
COD_081126															
	35364	35364 CHEMICAL OXYGEN DEMAND	8200	10600	10550	2500	mg/L	96	94	80-120	2.1	09-0		LFM	
1081120A	34897	N-HFATE-N	25	3.51		1.00	ma/L	101	AN AN	80-120	N.	09-0		LFM	
	34897		63	64		1.00	mg/L	100	AN	80-120	N A	09-0	_	LFM	
			1000	2000			,								

%RPD = Relative Percent Difference

NA = Indicates %RPD could not be calculated

Matrix Spike (MS)/Matrix Spike Duplicate (MSD) analyses are used to determine the accuracy (MS) and precision (MSD) of a analytical method in a given sample matrix. Therefore, the usefulness of this report is limited to samples of similar matrices analyzed in the same analytical batch.



Page 5 of 5
Reference Number: 08-16537
Report Date: 12/10/2008

Matrix Spike	pike			Duplicate										
			Spike	Spike	Spike		Percent Recovery	Recovery				oc		
Batch	Sample Analyte	Result	Result	Result	Conc	Units	MS	MSD	Limits	%RPD Limits	Limits	Qualifier	Comments	
	34918 NITRATE-N	Q	19.6		20.00	mg/L	86	NA	80-120	NA	09-0	LFM		
	34918 CHLORIDE	9.0	21		20.00	mg/L	102	NA	80-120	NA	09-0	LFM		
OPHOS-081120	20 34918 ORTHO-PHOSPHATE	0.11	1.18	1.18	1.00	mg/L	107	107	70-130	0.0	0-20	LFM		
TKN-081121	34919 TOTAL KJELDAHL NITROGEN	45.2	87.2		40.0	mg/L	105		80-120	NA A	09-0	LFM		

%RPD = Relative Percent Difference

NA = Indicates %RPD could not be calculated

Matrix Spike (MS)/Matrix Spike Duplicate (MSD) analyses are used to determine the accuracy (MS) and precision (MSD) of a analytical method in a given sample matrix. Therefore, the usefulness of this report is limited to samples of similar matrices analyzed in the same analytical batch.





Qualifier Definitions

Reference Number: 08-16537 Report Date: 12/10/08

Qualifier	Definition
HQ	High QCS recovery due to increased detector response of the sample extract. The continuing calibration checks are within acceptance limits.
HR	High QCS recovery due to increased detector response No sample dectections, therefore, no further action taken for this analysis set.
ME	Matrix spike shows a possible matrix induced bias. The LFB was within acceptance limits, results for this compound are suspect.
N1	Acceptance limits have not been established, the limits listed are for guidance only.







QUALITY CONTROL REPORT SURROGATE REPORT

Reference Number: 08-16537

Report Date: 12/10/08

1,3-DIMETHYL-2-NITROBENZENE (Surr) PYRENE-D10 (Surr) PERYLENE-D12 (Surr) TRIPHENYLPHOSPHATE (Surr)	96 94 98 108	% % %	525.2	Acceptance Range is 70% to 130% Acceptance Range is 70% to 130% Acceptance Range is 70% to 130% Acceptance Range is 70% to 130%
PYRENE-D10 (Surr) PERYLENE-D12 (Surr)	94 98	% %	525.2	Acceptance Range is 70% to 130% Acceptance Range is 70% to 130%
PERYLENE-D12 (Surr)	98	%		Acceptance Range is 70% to 130%
		%		
TRIPHENYLPHOSPHATE (Surr)	108	%		Acceptance Range is 70% to 130%
2.4 - DCAA (SURR)	103	%	515.1	Acceptance Range is 70 - 130%
_,,,				
RDMC (SURR)	99	%	531.2	
BBMO (GOTAL)				
			505.0	Acceptance Range is 70% to 130%
			525.2	Acceptance Range is 70% to 130%
PYRENE-D10 (Surr)				
PERYLENE-D12 (Surr)	100	%		Acceptance Range is 70% to 130%
TRIPHENYLPHOSPHATE (Surr)	112	%		Acceptance Range is 70% to 130%
2.4 - DCAA (SURR)	100	%	515.1	Acceptance Range is 70 - 130%
-,				
BDMC (SUBD)	102	%	531.2	
		BDMC (SURR) 99 1,3-DIMETHYL-2-NITROBENZENE (Surr) 96 PYRENE-D10 (Surr) 91 PERYLENE-D12 (Surr) 100 TRIPHENYLPHOSPHATE (Surr) 112 2,4 - DCAA (SURR) 100	BDMC (SURR) 99 % 1,3-DIMETHYL-2-NITROBENZENE (Surr) 96 % PYRENE-D10 (Surr) 91 % PERYLENE-D12 (Surr) 100 % TRIPHENYLPHOSPHATE (Surr) 112 % 2,4 - DCAA (SURR) 100 %	BDMC (SURR) 99 % 531.2 1,3-DIMETHYL-2-NITROBENZENE (Surr) PYRENE-D10 (Surr) PERYLENE-D12 (Surr) TRIPHENYLPHOSPHATE (Surr) 2,4 - DCAA (SURR) 99 % 531.2 96 % 525.2 91 % 70 % 525.2 91 % 70 % 525.2 91 % 70 % 525.2

and treek Water Beatment Plant Lebourtory

581 Mill Creek Road

Walla Walla, WA 99362

Lab ID#:

143

Washington State ID:

M1873 WA 01177

EPA ID#: Telephone: (509) 522-3775

Fax: (509) 529-9681

Date: 11/20/08

System ID / Name:	Walla W	Valla Basin Wate	rshed Council	Amount Due:	\$75.00
Sampler:	Bob Bo	wer		Invoice Number:	8007
Address:	P.O. Box	x 68		Date Collected:	11/19/08
City:	Milton-F	reewater		Date Analyzed:	11/19/08
State:	OR	Zip Code:	97874	Lab Analyst:	Skifstad

Test Methods Are Selected From The Standard Methods For Examination Of Water and Wastewater ~ 20th Edition~

	Test Method 9222D		
Sample ID #1	Results	Units	Lab Number
Intake	19.0	CFU's / 100 mL	143-06246
Sample ID #2	Results	Units	Lab Number
OBS-1A	2.0	CFU's / 100 mL	143-06247
Sample ID #3	Results	Units	Lab Number
OBS-1B	1.0	CFU's / 100 mL	143-06248
		(Carena Artical Mesaninsean)	
and the second s			THE WORLD
		MINISTER OF THE PROPERTY.	
		1	

The City of Walla Walla's Mill Creek Water Treatment Laboratory will maintain records pertaining to reconstructing client's data for a minimum of five years from the date of issuance of the final report. Records may be destroyed after that .

Signature Lab Director:

11-20-08 (date)

City Of Walla Walla Water Plant Laboratory 581 Mill Creek Road Walla Walla, WA 99362



Microbiology

Burlington WA | 1620 S Walnut St - 98233
 Corporate Office
 800.755.9295 • 360.757.1400 • 360.757.1402fax

 Bellingham WA
 805 Orchard Dr Suite 4 - 98225
 360.671.0688 • 360.671.1577fax

Page 1 of 1

INVOICE

Client No:

Client:

WAL06

WALLA WALLA BASIN WATERSHED COUNCIL

810 SOUTH MAIN STREET

MILTON-FREEWATER, OR 97862

Attn: Dob Bower

Please include this number with payment

Reference: 09-03975

Date: March 24, 2009

Project: HBDIC Recharge Project

Date Received: March 23, 2009

Purchase Order:

	Lab Sample		Client Sample	Type of	Extended
Item	Number	Number	Description	Analysis	Cost
1	8072.00	LWW-Intake/Head	LWW-Intake/Head	Total Suspended Solids	\$19.00
2	8073.00	IG-Intake	IG-Intake 3-20-09	Total Suspended Solids	\$19.00
3	8074.00	LWW-Head	LWW-Head 3-16-09	Total Suspended Solids	\$19.00
4	8075.00	LWW-Head	LWW-Head 3-19-09	Total Suspended Solids	\$19.00
5	8076.00	IG-Intake	IG-Intake 3-18-09	Total Suspended Solids	\$19.00
6	8077.00	IG-Intake	IG-Intake 3-18-09 Dup	Total Suspended Solids	\$19.00
7	8078.00	IG-Intake	IG-Intake 3-16-09 1350	Total Suspended Solids	\$19.00
8	8079.00	LWW-Head	LWW-Head	Total Suspended Solids	\$19.00
9	8080.00	IG-Intake	IG-Intake 3-16-09 1355	Total Suspended Solids	\$19.00
		The second second	100 (100)	Crand Total:	\$171.00

Grand Total: \$171.00

Amount Paid:

\$0.00

Amount Due:

\$171.00



Burlington WA | 1620 S Walnut St - 98233 | 800.755.9295 • 360.757.1

800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225 360.671.0688 • 360.671.1577fax

March 23, 2009

Page 1 of 1

Mr. Bob Bower Walla Walla Basin Watershed Council 810 South Main Street Milton-Freewater, OR 97862

RE: 09-03975 - HBDIC Recharge Project

Dear Mr. Bob Bower,

Your project: HBDIC Recharge Project, was received on Monday March 23, 2009.

All samples were analyzed within the accepted holding times, were appropriately preserved and were analyzed according to approved analytical protocols. The quality control data was within laboratory acceptance limits, unless specified in the QA reports.

If you have questions phone me at 800 755-9295.

Respectfully Submitted,

Lawrence | Henderson, PhD Director of Laboratories

Enclosures Data Report

QC Reports

Chain of Custody



Burlington WA | 1620 S Walnut St - 98233 800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225

360.671.0688 • 360.671.1577fax

Page 1 of 2

Data Report

Client Name: Walla Walla Basin Watershed Council

810 South Main Street

Milton-Freewater, OR 97862

Reference Number: 09-03975

Project: HBDIC Recharge Project

Report Date: 3/23/09 Date Received: 3/23/09


Peer Review:

		-	_				Commis	Date: 2/40/00		
AND DESCRIPTION OF THE PARTY OF	ription: LWW-Intake/Head umber: 8072							Date: 3/19/09 ed By: Bower		
CAS ID#	Parameter	Result	PQL	MDL	Units	DF	Method /	Analyzed Analyst	Batch	Comment
E-10162	TOTAL SUSPENDED SOLIDS	8	4	1.68	mg/L	1	SM2540 D 3	/23/09 MAK	rss_090323	
	ription: IG-Intake - IG-Intake 3-20-0 umber: 8073	09						Date: 3/20/09 ed By: Bower		
CAS ID#	Parameter	Result	PQL	MDL	Units	DF	Method A	Analyzed Analyst	Batch	Comment
E-10162	TOTAL SUSPENDED SOLIDS	9	4	1.68	mg/L	1	SM2540 D 3/	/23/09 MAK 1	rss_090323	
	ription: LWW-Head - LWW-Head 3 umber: 8074	-16-09					510900001980000	Date: 3/16/09 ed By: Bower		
CAS ID#	Parameter	Result	PQL	MDL	Units	DF	Method A	Analyzed Analyst	Batch	Comment
E-10162	TOTAL SUSPENDED SOLIDS	37	4	1.68	mg/L	1	SM2540 D 3/	/23/09 MAK 1	SS_090323	
	ription: LWW-Head - LWW-Head 3 umber: 8075	-19-09						Date: 3/19/09 ed By: Bower		
CAS ID#	Parameter	Result	PQL	MDL	Units	DF	Method A	Analyzed Analyst	Batch	Comment
E-10162	TOTAL SUSPENDED SOLIDS	8	4	1.68	mg/L	1	SM2540 D 3/	/23/09 MAK 1	"SS_090323	
	ription: IG-Intake - IG-Intake 3-18-0 umber: 8076	09						Date: 3/18/09 ed By: Bower		
CAS ID#	Parameter	Result	PQL	MDL	Units	DF	Method A	Analyzed Analyst	Batch	Comment
E-10162	TOTAL SUSPENDED SOLIDS	8	4	1.68	mg/L	1	SM2540 D 3/	/23/09 MAK 1	SS_090323	
All and the second	ription: IG-Intake - IG-Intake 3-18-0 umber: 8077	9 Dup						Date: 3/18/09 ed By: Bower		
CAS ID#	Parameter	Result	PQL	MDL	Units	DF	Method A	Analyzed Analyst	Batch	Comment
E-10162	TOTAL SUSPENDED SOLIDS	8	4	1.68	mg/L	1	SM2540 D 3/	/23/09 MAK 1	SS_090323	

^{.) =} Not detected above the listed practical quantitation limit (PQL) or not above the Method Detection Limit (MDL), if requested

PQL = Practical Quantitation Limit is the lowest level that can be acheived within specified limits of precision and accuracy during routine laboratory operating conditions.

D.F. - Dilution Factor





Reference Number: 09-03975 Report Date:3/23/09

Data Report

	cription: IG-Intake - IG-Intake 3-16- lumber: 8078						Sample Date Collected By			
CAS ID#	Parameter	Result	PQL	MDL	Units	DF	Method Analyz	ed Analyst	Batch	Comment
E-10162	TOTAL SUSPENDED SOLIDS	27	4	1.68	mg/L	1	SM2540 D 3/23/09	MAK	TSS_090323	
Sample Des	cription: LWW-Head						Sample Date	3/20/09		
Lab N	lumber: 8079						Collected By	: Bower		
CAS ID#	Parameter	Result	PQL	MDL	Units	DF	Method Analyz	ed Analyst	Batch	Comment
E-10162	TOTAL SUSPENDED SOLIDS	7	4	1.68	mg/L	1	SM2540 D 3/23/09	MAK 1	TSS_090323	
of State of Section Committee of Section Secti	cription: IG-Intake - IG-Intake 3-16-	09 1355					Sample Date			
Labin	lumber: 8080						Collected By	Bower		
CAS ID#	Parameter	Result	PQL	MDL	Units	DF	Method Analyz	ed Analyst	Batch	Comment
E-10162	TOTAL SUSPENDED SOLIDS	15	4	1.68	mg/L	1	SM2540 D 3/23/09	MAK 1	SS 090323	

Not detected above the listed practical quantitation limit (PQL) or not above the Method Detection Limit (MDL), if requested.

PQL = Practical Quantitation Limit is the lowest level that can be acheived within specified limits of precision and accuracy during routine laboratory operating conditions.



Burlington WA | 1620 S Walnut St - 98233

800.755.9295 • 360.757.1400 • 360.757.1402fax Bellingham WA 805 Orchard Dr Suite 4 - 98225

360.671.0688 • 360.671.1577fax

Page 1 of 2



SAMPLE INDEPENDENT QUALITY CONTROL REPORT

Laboratory Fortified Blank

Reference Number: 09-03975

Report Date: 03/23/09

			True			%		QC		
Batch	Analyte	Result	Value	Units	Method	Recovery	Limits	Qualifier Type*	Comment	
TSS_090323	TOTAL SUSPENDED SOLIDS	480	500	mg/L	SM2540 D	96	80-120	LFB		
TSS_090323	TOTAL SUSPENDED SOLIDS	500	500	mg/L	SM2540 D	100	80-120	LFB		
TSS_090323	TOTAL SUSPENDED SOLIDS	500	500	mg/L	SM2540 D	100	80-120	LFB		

*Notation:

Recovery = (Result of Analysis)/(True Value) * 100

= Indicates % Recovery could not be calculated.

QCS: Quality Control Sample, a solution containing known concentrations of method analytes which is used to fortify an aliquot of reagent matrix. The QCS is obtained from an external source and is used to check lab performance.

LFB: Laboratory Fortified Blank, an aliquot of reagent matrix to which known quantities of method analytes are added in the lab. The LFB is analyzed exactly like a sample, and its purpose is to determine whether method performance is within accepted control limits.

MB or LRB: Method Blank or Laboratory Reagent Blank, an aliquot of reagent matrix is analyzed exactly like a sample, and its purpose is to determine if there is background contamination.



Burlington WA Corporate Office 1620 S Walnut St - 98233 800.755.9295 • 360.757.1

800.755.9295 • 360.757.1400 • 360.757.1402fax Bellingham WA 805 Orchard Dr Suite 4 - 98225 360.671.0688 • 360.671.1577fax

Page 2 of 2



SAMPLE INDEPENDENT QUALITY CONTROL REPORT

Method Blank

Reference Number: 09-03975

Report Date: 03/23/09

			True			%	QC		
Batch	Analyte	Result	Value	Units	Method	Recovery Limits	Qualifier Type*	Comment	
TSS_090323	TOTAL SUSPENDED SOLIDS	ND		mg/L	SM2540 D	1.00000) MB		
TSS_090323	TOTAL SUSPENDED SOLIDS	ND		mg/L	SM2540 D	1.00000	MB		
TSS_090323	TOTAL SUSPENDED SOLIDS	ND		mg/L	SM2540 D	1.00000	MB		

*Notation:

* Recovery = (Result of Analysis)/(True Value) * 100

\= Indicates % Recovery could not be calculated.

QCS: Quality Control Sample, a solution containing known concentrations of method analytes which is used to fortify an aliquot of reagent matrix. The QCS is obtained from an external source and is used to check lab performance.

LFB: Laboratory Fortified Blank, an aliquot of reagent matrix to which known quantities of method analytes are added in the lab. The LFB is analyzed exactly like a sample, and its purpose is to determine whether method performance is within accepted control limits.

MB or LRB: Method Blank or Laboratory Reagent Blank, an aliquot of reagent matrix is analyzed exactly like a sample, and its purpose is to determine if there is background contamination.



Burlington WA 1620 S Walnut St - 98233

Corporate Office 800.755.9295 • 360.757.1402fax
Bellingham WA 805 Orchard Dr Suite 4 - 98225

Microbiology 360.671.0688 • 360.671.1577fax



Page 1 of 1

QUALITY CONTROL REPORT

Duplicate and Matrix Spike/Matrix Spike Duplicate Report

75	
39	
9	
60	
1.	
pe	
Ę	
ž	
8	
en	
je.	
8	

Report Date: 3/23/2009

Duplicate	te								
			Duplicate				ac		
Batch	Sample Analyte	Result Result	Result	Units	%RPD	Limits	fier	Comments	
TSS_090323									
	8078 TOTAL SUSPENDED SOLIDS	27	30	mg/L	10.5	0-45	DUP		
	8080 TOTAL SUSPENDED SOLIDS	15	18	mg/L	18.2	0-45	DUP		

%RPD = Relative Percent Difference

NA = Indicates %RPD could not be calculated

Matrix Spike (MS)/Matrix Spike Duplicate (MSD) analyses are used to determine the accuracy (MS) and precision (MSD) of a analytical method in a given sample matrix. Therefore, the usefulness of this report is limited to samples of similar matrices analyzed in the same analytical batch.

Only Duplicate sample with detections are listed in this report

3/2=/9 TO EDGE LAB, 09-03975 This samples for Inflitation Galley test-of project. I don't need chan of costod, etc. (AII TSS samples) Samples are: Project HBDIC Recharge All examples for Site Date Sampler Time Bower 8:34 3/19/9 LWW-INTake/Head 3/20/9 11,50 IIG-ILITATE 3/16/9 - Lun - Head 13:34 Eww- Head 23/19/9 3:50 3/18/9 HA-GETTHANKEY 9:30 3/18/9 8:30 Duplicate Samples 11 are 3/14/5 13:50 rement Head 12:05 3/20/9 16-Intake 3-16-69 I will use abotter par for bothy To. The Bampes & De Borne N 64646 To EDGE LIMAT. Called & left message for Bob about 09-03975 extra bottle. 3-23-09@09316+44 3-23-09 UPS 3.



Burlington WA 1620 S Walnut St - 98233 Corporate Office

800.755.9295 • 360.757.1400 • 360.757.1402fax Bellingham WA 805 Orchard Dr Suite 4 - 98225

360.671.0688 • 360.671.1577fax

Page 1 of 1

INVOICE

Client No:

Client:

WAL06

WALLA WALLA BASIN WATERSHED COUNCIL

810 SOUTH MAIN STREET

MILTON-FREEWATER, OR 97862

Bob Bower

Please include this number with payment

Reference: 09-04307

Date: April 3, 2009

Project: Recharge Project Monitoring

Date Received: March 30, 2009

Purchase Order:

	Lab Sample		Client Sample	Type of	Extended
Item	Number	Number	Description	Analysis	Cost
1	8827.00	IG-INTAKE	3/26/09	Total Suspended Solids	\$19.00
2	8828.00	IG-INTAKE DUP	3/26/09	Total Suspended Solids	\$19.00
3	8829.00	IG-INTAKE	3/27/09 @ 1435	Total Suspended Solids	\$19.00
4	8830.00	IG-INTAKE	3/27/09 @ 1438	Total Suspended Solids	\$19.00
5	8831.00	IG-INTAKE	3/24/09	Total Suspended Solids	\$19.00
6	8832.00	LWW-HEAD	3/24/09	Total Suspended Solids	\$19.00
7	8833.00	LWW-HEAD	3/26/09	Total Suspended Solids	\$19.00
8	8834.00	LWW-HEAD DUP	3/26/09	Total Suspended Solids	\$19.00
9	8835.00	LWW-HEAD	3/27/09 @ 1400	Total Suspended Solids	\$19.00
10	8836.00	LWW-HEAD	3/27/09 @ 1433	Total Suspended Solids	\$19.00

Grand Total: \$190.00 Amount Paid: \$0.00

Amount Due: \$190.00



Corporate Office

Burlington WA | 1620 S Walnut St - 98233 800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225

360.671.0688 • 360.671.1577fax

April 2, 2009

Page 1 of 1

Mr. Bob Bower Walla Walla Basin Watershed Council 810 South Main Street Milton-Freewater, OR 97862

RE: 09-04307 - Recharge Project Monitoring

Dear Mr. Bob Bower,

Your project: Recharge Project Monitoring, was received on Monday March 30, 2009.

All samples were analyzed within the accepted holding times, were appropriately preserved and were analyzed according to approved analytical protocols. The quality control data was within laboratory acceptance limits, unless specified in the QA reports.

If you have questions phone me at 800 755-9295.

Respectfully Submitted,

Lawrence J Henderson, PhD Director of Laboratories

Enclosures Data Report

QC Reports

Chain of Custody



Burlington WA 1620 S Walnut St - 98233 800.755.9295 • 360.757.1

800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225 Microbiology 360.671.0688 • 360.671.1577fax

Page 1 of 2

Data Report

Client Name: Walla Walla Basin Watershed Council

810 South Main Street

Milton-Freewater, OR 97862

Reference Number: 09-04307

Project: Recharge Project Monitoring

Report Date: 4/2/09

Date Received: 3/30/09

Peer Review:


							1 0	or review. Quy		
	cription: IG-INTAKE - 3/26/09 lumber: 8827							nple Date: 3/26/09 lected By: Unknown	1	
CAS ID#	Parameter	Result	PQL	MDL	Units	DF	Method	Analyzed Analyst	Batch	Comment
E-10162	TOTAL SUSPENDED SOLIDS	ND	4	1.68	mg/L	1	SM2540 D	3/31/09 MAK T	SS_090331	
	cription: IG-INTAKE DUP - 3/26/09 lumber: 8828							nple Date: 3/26/09 lected By: Unknown	1	
CAS ID#	Parameter	Result	PQL	MDL	Units	DF	Method	Analyzed Analyst	Batch	Comment
E-10162	TOTAL SUSPENDED SOLIDS	7	4	1.68	mg/L	1	SM2540 D	3/31/09 MAK T	SS_090331	
The same and the s	cription: IG-INTAKE - 3/27/09 @ 143 lumber: 8829	35						nple Date: 3/27/09 lected By: Unknown	1	
CAS ID#	Parameter	Result	PQL	MDL	Units	DF	Method	Analyzed Analyst	Batch	Comment
E-10162	TOTAL SUSPENDED SOLIDS	6	4	1.68	mg/L	1	SM2540 D	3/31/09 MAK T	SS_090331	
The same of the sa	cription: IG-INTAKE - 3/27/09 @ 143 lumber: 8830	38						nple Date: 3/27/09 lected By: Unknown	1	
CAS ID#	Parameter	Result	PQL	MDL	Units	DF	Method	Analyzed Analyst	Batch	Comment
E-10162	TOTAL SUSPENDED SOLIDS	6	4	1.68	mg/L	1	SM2540 D	3/31/09 MAK T	SS_090331	
	cription: IG-INTAKE - 3/24/09 lumber: 8831							nple Date: 3/24/09 lected By: Unknown	1	
CAS ID#	Parameter	Result	PQL	MDL	Units	DF	Method	Analyzed Analyst	Batch	Comment
E-10162	TOTAL SUSPENDED SOLIDS	4	4	1.68	mg/L	1	SM2540 D	3/31/09 MAK T	SS_090331	
	cription: LWW-HEAD - 3/24/09 Number: 8832							nple Date: 3/24/09 lected By: Unknown	1	
CAS ID#	Parameter	Result	PQL	MDL	Units	DF	Method	Analyzed Analyst	Batch	Comment
E-10162	TOTAL SUSPENDED SOLIDS	24	4	1.68	mg/L	1	SM2540 D	3/31/09 MAK T	SS_090331	

otes:

^{.4}D = Not detected above the listed practical quantitation limit (PQL) or not above the Method Detection Limit (MDL), if requested.

PQL = Practical Quantitation Limit is the lowest level that can be acheived within specified limits of precision and accuracy during routine laboratory operating conditions.

D.F. - Dilution Factor





Data Report

Sample Description: LWW-HEAD - 3/26/09 Sample Date: 3/26/09

Lab Number: 8833 Collected By: Unknown

CAS ID# Parameter Result PQL MDL Units DF Method Analyzed Analyst Batch Comment

E-10162 TOTAL SUSPENDED SOLIDS 10 4 1.68 mg/L 1 SM2540 D 3/31/09 MAK TSS_090331

Sample Description: LWW-HEAD DUP - 3/26/09 Sample Date: 3/26/09

Lab Number: 8834 Collected By: Unknown

CAS ID# Parameter Result PQL MDL Units DF Method Analyzed Analyst Batch Comment

E-10162 TOTAL SUSPENDED SOLIDS 5 4 1.68 mg/L 1 SM2540 D 3/31/09 MAK TSS_090331

Sample Description: LWW-HEAD - 3/27/09 @ 1400 Sample Date: 3/27/09

Lab Number: 8835 Collected By: Unknown

CAS ID# Parameter Result PQL MDL Units DF Method Analyzed Analyst Batch Comment

E-10162 TOTAL SUSPENDED SOLIDS ND 4 1.68 mg/L 1 SM2540 D 3/31/09 MAK TSS_090331

Tample Description: LWW-HEAD - 3/27/09 @ 1433 Sample Date: 3/27/09

Lab Number: 8836 Collected By: Unknown

Analyzed Analyst Batch Comment Method Parameter Result MDL Units DF CAS ID# MAK TSS 090331 SM2540 D 3/31/09 E-10162 TOTAL SUSPENDED SOLIDS ND 1.68 mg/L



Burlington WA 1620 S Walnut St - 98233 800.755.9295 • 360.757.1

800.755.9295 • 360.757.1400 • 360.757.1402fax Bellingham WA 805 Orchard Dr Suite 4 - 98225

360.671.0688 • 360.671.1577fax

Page 1 of 2



SAMPLE INDEPENDENT QUALITY CONTROL REPORT

Laboratory Fortified Blank

Reference Number: 09-04307

Report Date: 04/02/09

			True			%		QC		
Batch	Analyte	Result	Value	Units	Method	Recovery	Limits	Qualifier Type*	Comment	
TSS_090331	TOTAL SUSPENDED SOLIDS	470	500	mg/L	SM2540 D	94	80-120	LFB		
TSS_090331	TOTAL SUSPENDED SOLIDS	490	500	mg/L	SM2540 D	98	80-120	LFB		

*Notation:

% Recovery = (Result of Analysis)/(True Value) * 100

\(\lambda = \) Indicates \(\%\) Recovery could not be calculated.

QCS: Quality Control Sample, a solution containing known concentrations of method analytes which is used to fortify an aliquot of reagent matrix. The QCS is obtained from an external source and is used to check lab performance.

LFB: Laboratory Fortified Blank, an aliquot of reagent matrix to which known quantities of method analytes are added in the lab. The LFB is analyzed exactly like a sample, and its purpose is to determine whether method performance is within accepted control limits.

MB or LRB: Method Blank or Laboratory Reagent Blank, an aliquot of reagent matrix is analyzed exactly like a sample, and its purpose is to determine if there is background contamination.



Corporate Office

Burlington WA | 1620 S Walnut St - 98233

800.755.9295 • 360.757.1400 • 360.757.1402fax Bellingham WA 805 Orchard Dr Suite 4 - 98225

360.671.0688 • 360.671.1577fax

Page 2 of 2



SAMPLE INDEPENDENT QUALITY CONTROL REPORT

Method Blank

Reference Number: 09-04307

Report Date: 04/02/09

			True			%	QC	
Batch	Analyte	Result	Value	Units	Method	Recovery Limits	Qualifier Type*	Comment
TSS_090331	TOTAL SUSPENDED SOLIDS	ND		mg/L	SM2540 D	1.00000	MB	
TSS_090331	TOTAL SUSPENDED SOLIDS	ND		mg/L	SM2540 D	1.00000	MB	

% Recovery = (Result of Analysis)/(True Value) * 100

A = Indicates % Recovery could not be calculated.

QCS: Quality Control Sample, a solution containing known concentrations of method analytes which is used to fortify an aliquot of reagent matrix. The QCS is obtained from an external source and is used to check lab performance.

LFB: Laboratory Fortified Blank, an aliquot of reagent matrix to which known quantities of method analytes are added in the lab. The LFB is analyzed exactly like a sample, and its purpose is to determine whether method performance is within accepted control limits.

MB or LRB: Method Blank or Laboratory Reagent Blank, an aliquot of reagent matrix is analyzed exactly like a sample, and its purpose is to determine if there is background contamination.



Burlington WA 1620 S Walnut St. - 98233

corporate Office 800.755.39295 • 360.757.1400 • 560.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225

Microbiology 360.671.0688 • 360.671.1577fax



Page 1 of 1

QUALITY CONTROL REPORT

Duplicate and Matrix Spike/Matrix Spike Duplicate Report

Reference Number: 09-04307

Report Date: 4/2/2009

Duplicate

Result Sample Analyte

Units

Duplicate Result

00 %RPD Limits

Qualifier

Comments

TSS_090331

Batch

%RPD = Relative Percent Difference

NA = Indicates %RPD could not be calculated

Matrix Spike (MS)/Matrix Spike Duplicate (MSD) analyses are used to determine the accuracy (MS) and precision (MSD) of a analytical method in a given sample matrix. Therefore, the usefulness of this report is limited to samples of similar matrices analyzed in the same analytical batch.

Only Duplicate sample with detections are listed in this report

To whom it may concern) Samply are \$ 16-Intake & LWW-Head, reclarge proper montiging. No draw of custory requied. St Barer 519-520-3134 09-04307 09-04307 0 93 9:45 3.36.09) • ups

NO COC Given 09-04307

Walla Walla

755

LWW- Head

3/04/09 2:35

3/26/09 11:00

Dup 3/26/09 11:00

3/27/09 14:00

3/27/09 14:33

IG lutake

3/26/09 10:41

Dus 3/26/09 10:41

3/27/09 14:35

3/27/09 14:38

3/24/09 14:45



Page 1 of 1

INVOICE

Client No:

WAL06

Please include this number with payment

Client:

WALLA WALLA BASIN WATERSHED COUNCIL

810 SOUTH MAIN STREET

MILTON-FREEWATER, OR 97862

Project: TSS

Reference: 09-01621

Date: February 6, 2009

Data Bassivadi. Es

Date Received: February 04, 2009

Purchase Order:

	6	2
Attn:	Doh	Dower

= 1	Lab Sample		Client Sample	Type of	Extended
Item	Number	Number	Description	Analysis	Cost
1	3362.00	IG P2-2	IG P2-2	Total Suspended Solids	\$19.00
2	3363.00	IG P2-5	IG P2-5	Total Suspended Solids	\$19.00
3	3364.00	IG P2-5	IG P2-5	Total Suspended Solids	\$19.00
4	3365.00	IG-INTAKE	IG-INTAKE	Total Suspended Solids	\$19.00
5	3366.00	IG-P2-H	IG-P2-H	Total Suspended Solids	\$19.00
6	3367.00	IG-P2-8	IG-P2-8	Total Suspended Solids	\$19.00
7	3368.00	IG-P2-6	IG-P2-6	Total Suspended Solids	\$19.00
8	3369.00	IG-P2-4	IG-P2-4	Total Suspended Solids	\$19.00
9	3370.00	IG-INTAKE	IG-INTAKE	Total Suspended Solids	\$19.00
10	3371.00	LWW-HEAD GATE	LWW-HEAD GATE	Total Suspended Solids	\$19.00
11	3372.00	IG-P2-6	IG-P2-6	Total Suspended Solids	\$19.00
12	3373.00	IG-INTAKE	IG-INTAKE	Total Suspended Solids	\$19.00
13	3374.00	IG-P2-4	IG-P2-4	Total Suspended Solids	\$19.00
14	3375.00	IG-INTAKE	IG-INTAKE	Total Suspended Solids	\$19.00
15	3376.00	IG-P2-5	IG-P2-5	Total Suspended Solids	\$19.00
16	3377.00	IG-INTAKE C	IG-INTAKE C	Total Suspended Solids	\$19.00
17	3378.00	IG-P2-6	IG-P2-6	Total Suspended Solids	\$19.00
18	3379.00	IG-INTAKE	IG-INTAKE	Total Suspended Solids	\$19.00
19	3380.00	IG-P2-3	IG-P2-3	Total Suspended Solids	\$19.00
20	3381.00	IG-P2-4	IG-P2-4	Total Suspended Solids	\$19.00
21	3382.00	IG-P2-5	IG-P2-5	Total Suspended Solids	\$19.00
22	3383.00	IG-P2-5	IG-P2-5	Total Suspended Solids	\$19.00
23	3384.00	IG-P2-4	IG-P2-4	Total Suspended Solids	\$19.00
24	3385.00	IG-P2-4	IG-P2-4	Total Suspended Solids	\$19.00

Grand Total: \$456.00 Amount Paid: \$0.00

Amount Due: \$456.00



February 6, 2009

Page 1 of 1

Bob Bower Walla Walla Basin Watershed Council 810 South Main Street Milton-Freewater, OR 97862

RE: 09-01621 - TSS

Dear Bob Bower,

Your project: TSS, was received on Wednesday February 04, 2009.

All samples were analyzed within the accepted holding times, were appropriately preserved and were analyzed according to approved analytical protocols. The quality control data was within laboratory acceptance limits, unless specified in the QA reports.

If you have questions phone me at 800 755-9295.

Respectfully Submitted,

Lawrence J Henderson, PhD Director of Laboratories

Enclosures Data Report

QC Reports

Chain of Custody



Burlington WA | 1620 S Walnut St - 98233

800.755.9295 • 360.757.1400 • 360.757.1402fax Bellingham WA 805 Orchard Dr Suite 4 - 98225

Microbiology 360.671.0688 • 360.671.1577fax

Page 1 of 4

Data Report

Client Name: Walla Walla Basin Watershed Council

810 South Main Street

Milton-Freewater, OR 97862

Reference Number: 09-01621

Project: TSS

Report Date: 2/6/09

Date Received: 2/4/09

Peer Review: WW

						Peer Review:
Sample Description: IG P2-2 Lab Number: 3362						Sample Date: 1/29/09 Collected By:
CAS ID# Parameter	Result	PQL	MDL	Units	DF	Method Analyzed Analyst Batch Commer
E-10162 TOTAL SUSPENDED SOLIDS	191	4	1.68	mg/L	1	SM2540 D 2/5/09 MAK TSS_090205
Sample Description: IG P2-5 Lab Number: 3363						Sample Date: 1/29/09 Collected By:
CAS ID# Parameter	Result	PQL	MDL	Units	DF	Method Analyzed Analyst Batch Commen
E-10162 TOTAL SUSPENDED SOLIDS	496	4	1.68	mg/L	1.	SM2540 D 2/5/09 MAK TSS_090205
Sample Description: IG P2-5 Lab Number: 3364						Sample Date: 1/29/09 Collected By:
CAS ID# Parameter	Result	PQL	MDL	Units	DF	Method Analyzed Analyst Batch Commen
E-10162 TOTAL SUSPENDED SOLIDS	1670	4	1.68	mg/L	1	SM2540 D 2/5/09 MAK TSS_090205
Sample Description: IG-INTAKE Lab Number: 3365						Sample Date: 1/29/09 Collected By:
CAS ID# Parameter	Result	PQL	MDL	Units	DF	Method Analyzed Analyst Batch Comment
E-10162 TOTAL SUSPENDED SOLIDS	9	4	1.68	mg/L	31	SM2540 D 2/5/09 MAK TSS_090205
Sample Description: IG-P2-H Lab Number: 3366						Sample Date: 1/29/09 Collected By:
CAS ID# Parameter	Result	PQL	MDL	Units	DF	Method Analyzed Analyst Batch Comment
E-10162 TOTAL SUSPENDED SOLIDS	747	4	1.68	mg/L	1	SM2540 D 2/5/09 MAK TSS_090205
Sample Description: IG-P2-8 Lab Number: 3367						Sample Date: 1/29/09 Collected By:
CAS ID# Parameter	Result	PQL	MDL	Units	DF	Method Analyzed Analyst Batch Comment
E-10162 TOTAL SUSPENDED SOLIDS	2202	4	1.68	mg/L	1	SM2540 D 2/5/09 MAK TSS_090205

ND = Not detected above the listed practical quantitation limit (PQL) or not above the Method Detection Limit (MDL), if requested.

PQL = Practical Quantitation Limit is the lowest level that can be acheived within specified limits of precision and accuracy during routine laboratory operating conditions.

D.F. - Dilution Factor





Reference Number: 09-01621 Report Date: 2/6/09

Data Report

Sample Description: IG-P2-6 Lab Number: 3368							mple Date: llected By:	1/29/09		
CAS ID# Parameter	Result	PQL	MDL	Units	DF	Method	Analyzed	i Analysi	Batch	Comment
E-10162 TOTAL SUSPENDED SOLIDS	954	4	1.68	mg/L	1	SM2540 D	2/5/09		rss_090205	200000000000000000000000000000000000000
Sample Description: IG-P2-4 Lab Number: 3369	()						mple Date:	1/29/09		
CAS ID# Parameter	Result	PQL	MDL	Units	DF	Method	Analyzed	Analyst	Batch	Comment
E-10162 TOTAL SUSPENDED SOLIDS	539	4	1.68	mg/L	1	SM2540 D	2/5/09	MAK 1	SS_090205	
Sample Description: IG-INTAKE Lab Number: 3370							mple Date: llected By:	1/29/09		
CAS ID# Parameter	Result	PQL	MDL	Units	DF	Method	Analyzed	Analyst	Batch	Comment
E-10162 TOTAL SUSPENDED SOLIDS	4	4	1.68	mg/L	1.	SM2540 D	2/5/09	MAK T	SS_090205	
ample Description: LWW-HEAD GATE Lab Number: 3371		1.3					mple Date:	2/2/09		
CAS ID# Parameter	Result	PQL	MDL	Units	DF	Method	Analyzed	Analyst	Batch	Comment
E-10162 TOTAL SUSPENDED SOLIDS	ND	4	1.68	mg/L	:1	SM2540 D	2/5/09	MAK T	SS_090205	
Sample Description: IG-P2-6 Lab Number: 3372							nple Date: lected By:	1/29/09		
CAS ID# Parameter	Result	PQL	MDL	Units	DF	Method	Analyzed	Analyst	Batch	Comment
E-10162 TOTAL SUSPENDED SOLIDS	732	4	1.68	mg/L	-1	SM2540 D	2/5/09	MAK T	SS_090205	
Sample Description: IG-INTAKE Lab Number: 3373	p						nple Date:	1/29/09		
CAS ID# Parameter	Result	PQL	MDL	Units	DF	Method	Analyzed	Analyst	Batch	Comment
E-10162 TOTAL SUSPENDED SOLIDS	7	4	1.68	mg/L	4	SM2540 D	2/5/09	MAK TS	S_090205	
Sample Description: IG-P2-4 Lab Number: 3374							nple Date:	1/29/09		
CAS ID# Parameter	Result	PQL	MDL	Units	DF	Method	Analyzed	Analyst	Batch	Comment
E-10162 TOTAL SUSPENDED SOLIDS	564	4	1.68	mg/L	1	SM2540 D	2/5/09	MAK TS	S_090205	

ND = Not detected above the listed practical quantitation limit (PQL) or not above the Method Detection Limit (MDL), if requested.

PQL = Practical Quantitation Limit is the lowest level that can be acheived within specified limits of precision and accuracy during routine laboratory operating conditions.





Reference Number: 09-01621 Report Date: 2/6/09

Data Report

	ber: 3375							mple Date: llected By:	1/29/09		
CAS ID#	Parameter	Result	PQL	MDL	Units	DF	Method	Analyzed	Analyst	Batch	Comment
E-10162	TOTAL SUSPENDED SOLIDS	8	4	1.68	mg/L	1	SM2540 D	2/5/09	E ONDE THE MESSAGE	rss_090205	
Sample Descript	ion: IG-P2-5 ber: 3376							mple Date:	1/29/09		
CAS ID#	Parameter	Result	PQL	MDL	Units	DF	Method	Analyzed	Analyst	Batch	Comment
E-10162	TOTAL SUSPENDED SOLIDS	1282	4	1.68	mg/L	1	SM2540 D	2/5/09		SS_090205	
	ion: IG-INTAKE C per: 3377			4				nple Date: lected By:	2/2/09		
CAS ID#	Parameter	Result	PQL	MDL	Units	DF	Method	Analyzed	Analyst	Batch	Comment
E-10162	TOTAL SUSPENDED SOLIDS	5	4	1.68	mg/L	1	SM2540 D	2/5/09	MAK T	SS_090205	
ample Description	on: IG-P2-6 per: 3378							nple Date: lected By:	1/29/09		
CAS ID#	Parameter	Result	PQL	MDL	Units	DF	Method	Analyzed	Analyst	Batch	Comment
E-10162	TOTAL SUSPENDED SOLIDS	773	4	1.68	mg/L	1	SM2540 D	2/5/09	MAK TS	SS_090205	
Sample Description	on: IG-INTAKE er: 3379							nple Date:	1/29/09		
CAS ID#	Parameter	Result	PQL	MDL	Units	DF	Method	Analyzed	Analyst	Batch	Comment
E-10162 1	FOTAL SUSPENDED SOLIDS	5	4	1.68	mg/L	1	SM2540 D	2/5/09	MAK TS	S_090205	
Sample Description Lab Numb								pple Date: 1	1/29/09		
CAS ID# F	Parameter	Result	PQL	MDL	Units	DF	Method	Analyzed	Analyst	Batch	Comment
E-10162 T	TOTAL SUSPENDED SOLIDS	4280	4	1.68	mg/L	É	SM2540 D	2/5/09	MAK TS	S_090205	
Sample Description								ple Date: 1	/29/09		
CAS ID# F	Parameter	Result	PQL	MDL	Units	DF	Method	Analyzed	Analyst	Batch	Comment
E-10162 T	OTAL SUSPENDED SOLIDS	880	4	1.68	mg/L	1	SM2540 D	2/5/09	MAK TS	S_090205	

ND = Not detected above the listed practical quantitation limit (PQL) or not above the Method Detection Limit (MDL), if requested.

PQL = Practical Quantitation Limit is the lowest level that can be acheived within specified limits of precision and accuracy during routine laboratory operating conditions.





Reference Number: 09-01621 Report Date: 2/6/09

Data Report

Sample Description: IG-P2-5 Lab Number: 3382						Sample Date: Collected By:	1/29/09		
CAS ID# Parameter	Result	PQL	MDL	Units	DF	Method Analyzed	Analyst	Batch	Comment
E-10162 TOTAL SUSPENDED	SOLIDS 8420	4	1.68	mg/L	1	SM2540 D 2/5/09	MAK T	SS_090205	
Sample Description: IG-P2-5 Lab Number: 3383						Sample Date: Collected By:	1/29/09		-
CAS ID# Parameter	Result	PQL	MDL	Units	DF	Method Analyzed	Analyst	Batch	Comment
E-10162 TOTAL SUSPENDED	SOLIDS 1346	4	1.68	mg/L	1	SM2540 D 2/5/09	MAK T	SS_090205	
Sample Description: IG-P2-4 Lab Number: 3384						Sample Date: Collected By:	1/29/09		
CAS ID# Parameter	Result	PQL	MDL	Units	DF	Method Analyzed	Analyst	Batch	Comment

ample Description:	IG-P2-4
Lab Number:	3385

E-10162

CAS ID#

Sample Date: 1/29/09

Collected By:

2/5/09

Analyzed Analyst Batch Comment

E-10162 **TOTAL SUSPENDED SOLIDS**

Parameter

TOTAL SUSPENDED SOLIDS

610

PQL

7110

Result

1.68

MDL

1.68

Units mg/L

mg/L

DF Method

SM2540 D

SM2540 D

2/5/09

MAK TSS_090205

MAK TSS_090205



Burlington WA | 1620 S Walnut St - 98233

800.755.9295 • 360.757.1400 • 360.757.1402fax Bellingham WA 805 Orchard Dr Suite 4 - 98225

Microbiology 360.671.0688 • 360.671.1577fax Page 1 of 2



SAMPLE INDEPENDENT QUALITY CONTROL REPORT

Laboratory Fortified Blank

Reference Number: 09-01621

Report Date: 02/06/09

			True			%		QC	
Batch	Analyte	Result	Value	Units	Method	Recove	ery Limits	Qualifier Type*	Comment
TSS_090205	TOTAL SUSPENDED SOLIDS	480	500	mg/L	SM2540 D	96	80-120	LFB	
TSS_090205	TOTAL SUSPENDED SOLIDS	500	500	mg/L	SM2540 D	100	80-120	LFB	
TSS_090205	TOTAL SUSPENDED SOLIDS	470	500	mg/L	SM2540 D	94	80-120	LFB	
TSS_090205	TOTAL SUSPENDED SOLIDS	480	500	mg/L	SM2540 D	96	80-120	LFB	

*Notation:

Recovery = (Result of Analysis)/(True Value) * 100

... = Indicates % Recovery could not be calculated.

QCS: Quality Control Sample, a solution containing known concentrations of method analytes which is used to fortify an aliquot of reagent matrix. The QCS is obtained from an external source and is used to check lab performance.

LFB: Laboratory Fortified Blank, an aliquot of reagent matrix to which known quantities of method analytes are added in the lab. The LFB is analyzed exactly like a sample, and its purpose is to determine whether method performance is within accepted control limits.

MB or LRB: Method Blank or Laboratory Reagent Blank, an aliquot of reagent matrix is analyzed exactly like a sample, and its purpose is to determine if there is background contamination.



Burlington WA | 1620 S Walnut St - 98233

800.755.9295 • 360.757.1400 • 360.757.1402fax Bellingham WA 805 Orchard Dr Suite 4 - 98225

Microbiology

360.671.0688 • 360.671.1577fax

Page 2 of 2



SAMPLE INDEPENDENT QUALITY CONTROL REPORT

Method Blank

Reference Number: 09-01621

Report Date: 02/06/09

			True			%	QC	
Batch	Analyte	Result	Value	Units	Method	Recovery Limits	Qualifier Type*	Comment
TSS_090205	TOTAL SUSPENDED SOLIDS	ND	-	mg/L	SM2540 D	1.00000	1-1-1 (C. 1986-1-1-1) 1-1-1-1-1-1	
TSS_090205	TOTAL SUSPENDED SOLIDS	ND		mg/L	SM2540 D	1.00000	MB	
TSS_090205	TOTAL SUSPENDED SOLIDS	ND		mg/L	SM2540 D	1,00000	MB	
TSS_090205	TOTAL SUSPENDED SOLIDS	ND		mg/L	SM2540 D	1.00000	MB	

*Notation:

?ecovery = (Result of Analysis)/(True Value) * 100

INA = Indicates % Recovery could not be calculated.

QCS: Quality Control Sample, a solution containing known concentrations of method analytes which is used to fortify an aliquot of reagent matrix. The QCS is obtained from an external source and is used to check lab performance.

LFB: Laboratory Fortified Blank, an aliquot of reagent matrix to which known quantities of method analytes are added in the lab. The LFB is analyzed exactly like a sample, and its purpose is to determine whether method performance is within accepted control limits.

MB or LRB: Method Blank or Laboratory Reagent Blank, an aliquot of reagent matrix is analyzed exactly like a sample, and its purpose is to determine if there is background contamination.



Burlington WA 1620 S Walnut St - 98233

Corporate Office 800.755.9295 • 360.757.1400 • 360.757.1402fax

Bellingham WA 805 Orchard Dr Suite 4 - 98225

Microbiology 360.671.0688 • 360.671.1577fax



Page 1 of 1

QUALITY CONTROL REPORT

Duplicate and Matrix Spike/Matrix Spike Duplicate Report

Reference Number: 09-01621

Report Date: 2/6/2009

Batch Sample Analyte	Re	Result	Duplicate Result	Units	%RPD	Limits	QC %RPD Limits Qualifier	Comments	nments
TSS_090205									
3370 TOTAL SUSPENDED SOLIDS	D SOLIDS 4		4	mg/L	00	0-45	OI IC		
SOUTH TOTAL SUSPENDED SOUTH			070	,	;	2	5		
SSS TOTAL SOST ENDE			3916	mg/L	8.9	0-45	DUP		
3385 TOTAL SUSPENDED SOLIDS		610	633	mg/L	3.7	0-45	DUP		

%RPD = Relative Percent Difference

NA = Indicates %RPD could not be calculated

Matrix Spike (MS)/Matrix Spike Duplicate (MSD) analyses are used to determine the accuracy (MS) and precision (MSD) of a analytical method in a given sample matrix. Therefore, the usefulness of this report is limited to samples of similar matrices analytical batch.

Only Duplicate sample with detections are listed in this report

N/A 13 take into off buttes + time I date - Cindy Ortook will tolk to elient Conditions on Receipt of 3 Samole 805 W. Orchard Dr. Suite 4 Bellingham, WA 98225 Special Instructions 2,680 Burlington, WA 98233 1.800.755.9295 CO002680 1620 S. Walnut St. Total Containers Page 603. Bour Quatacar C satisfactory Chain of custody & labels agree Number of Containers Custody seals intact Samples received intact Safe Drinking Water Act Check Regulatory Program Sample temp For Lab Use Only RCRA / CERCLA Clean Water Act Analyses Requested (Please complete all applicable shaded sections) Other Time Ref# 1 Set HCL Green caps only. Email: 97862 Date 2.4.0 NO3, 0-PO4, CI, TDS Walla Walla Basin Watershed Counc 0 Zip: тки, сор Expires 600 OH 20C backage 18:57 12:51 13:58 10:52 13:57 11:45 FAX Attn: AVE 11:15 Quickest (100% surcharge) Time St. 0 Half-time (50% surcharge) 810 S Main Street Milton-Freewa **Turn Around Time Required** 1.29 41-938-2420 1.39 1.39 otto 1.39 1.79 (19 3 Date 26 M/C Matrix Chain of Custody / Analysis Request Standard Other Address: Visa Grab/ Comp. Phone: Card#: P.O.# Bill to: City: Intitration Galley 2 Sample Receipt Request (Must include FAX or Email) 97862 Walla Walla Basin Watershed Cour 14.09 No Into on Occ - stay, to 200 Phone: Date Zip: Check off analyses to be performed for Location bob.bower@wwwbwc.org OR inh the Be specific in analysis requests. 541.938-2170 FAX: Ship Address: 810 S Main Street Enter number of containers. Milton-Freews St. Use one line per sample. 300 **Bob Bower** -Intake Laarding In-Pa-H 028 7-60 Ig-102-6 の井り each sample. Field ID Relingershed by Instructions Sampled by: 0 Report to: Project Phone: Email:

4

City: Attn:

N/A SPECIAL INSTRUCTIONS/ CONDITIONS ON RECEIPT 805 W. Orchard Dr. Suite 4 Bellingham, WA 98225 **▲TOTAL CONTAINERS** Burlington, WA 98233 1620 S Walnut St 1.800.755.9295 Microbiology YES OC SATISFACTORY CHAIN OF CUSTODY & LABELS AGREE CONTAINERS NUMBER OF SAMPLES RECEIVED INTACT CUSTODY SEALS INTACT SAFE DRINKING WATER ACT CHAIN OF CUSTODY / ANALYSIS REQUEST (PLEASE COMPLETE ALL APPLICABLE SHADED SECTIONS) CHECK REGULATORY PROGRAM SAMPLE TEMP **ANALYSIS REQUESTED** FOR LAB USE ONLY RCRA / CERCLA **CLEAN WATER ACT** OTHER TIME EMAIL: DATE EXPIRES ZIP: 15:00 9:43 00:00 13:59 14:55 P25.4 9:30 TIME QUICKEST (100% SURCHARGE) PHONE CALL REQ. ATTN: FAX: STATE: □ A/E EMERGENCY (PHONE CALL REQUIRED) DATE 1.29 HALF-TIME (50% SURCHARGE) RECEIVED BY □ M/C MATRIX TURN AROUND TIME REQUIRED ADDRESS: □ VISA GRAB/ COMP. BILL TO: PHONE: P.O.#: CARD# CITY: TIME STANDARD PHONE: SAMPLE RECEIPT REQUESTED (MUST INCLUDE FAX OR EMAIL) DATE ZIP: LOCATION CHECK OFF ANALYSIS TO BE PERFORMED USE ONE LINE PER SAMPLE LOCATION. ENTER NUMBER OF CONTAINERS. STATE: BE SPECIFIC IN TEST REQUESTS. FAX: Lww-Head gala FOR EACH SAMPLE LOCATION. - pa-10 ntake ntake 11 Iq- Intake -pg-4 SAMPLE ID RELINQUISHED BY FORM: COC 10-02-2007 INSTRUCTIONS PROJECT NAME: Q REPORT TO: ADDRESS: PHONE: EMAIL: ATTN: CITY: 4.

THE RESERVE THE PERSON NAMED IN COLUMN TWO IS NOT THE PERSON NAMED IN THE PERSON NAMED IN THE PERSON NAMED IN THE PERSON NAMED IN THE PERSON NAMED			
ВЕРОЯТ ТО:		BILL TO:	FOR LAB USE ONLY
Address:		ADDRESS:	REF#
Cirv:	STATE: ZIP:	CITY: STATE: ZIP:	CHECK REGULATORY PROGRAM
ATTN:		PHONE: FAX:	SAFE DRINKING WATER ACT
PHONE:	FAX:	P.O.#; ATTN:	CLEAN WATER ACT
EMAIL:		UVISA DIMIC DIAJE EXPIRES /	RCRA / CERCLA
PROJECT NAME:		CARD#	OTHER

CHAIN OF CUSTODY / ANALYSIS REQUEST	/ ANALY	SISH	EQU		(PLEASE COMPLETE ALL APPLICABLE SHADED SECTIONS)	MPLETE	ALL APP	LICABLE	HADED SE	CTIONS)		PAGE O OF	
ПЕРОЯТ ТО:	SIERICAMON CONTRACTOR	BILL TO:					13	FOR	FOR LAB USE ONLY	NLY			
Address:		ADDRESS:					ReF#	#=				ANALYTICAL	
CITY: STATE:	ZIP:	CITY:		STATE:	re: ZIP:	6.		CHECK RE	CHECK REGULATORY PROGRAM	PROGRAM		LABORATORIES	
ATTN:		PHONE:			FAX:] SAFE	SAFE DRINKING WATER ACT	/ATER ACT		1620 S Walnut St	
PHONE: FAX:		P.O.#:			ATTN:			CLEAR	CLEAN WATER ACT			Burlington, WA 98233	
EMAIL:		□ VISA	D M/C	□ A/E	EXPIRES	S] RCR/	RCRA / CERCLA	4		Microbiology	
PROJECT NAME:		CARD#						OTHER	Œ		80	805 W. Orchard Dr. Suite 4 Bellingham, WA 98225	
							¥	IALYSIS	ANALYSIS REQUESTED	旦	7		
INSTRUCTIONS	TUBN ABOLIND TIME BEOLIBED	TIME REDI	IIBED				The same						
USE ONE LINE PER SAMPLE LOCATION. BE SPECIFIC IN TEST REQUESTS. CHECK OFF ANALYSIS TO BE PERFORMED FOR EACH SAMPLE LOCATION. ENTER NUMBER OF CONTAINERS.	STANDARD HALF-TIME QUICKEST (STANDARD HALF-TIME (50% SURCHARGE) QUICKEST (100% SURCHARGE) PHONE CALL EMERGENCY (PHONE CALL REQUIRED)	URCHARGE URCHARGE NE CALL	E)) PHONE CALL REG. REQUIRED)	L REQ.								
SAMPLEID	MOLEVION	GRAB/	M	1								BET SPECIAL INSTRUCTIONS/	77
	NOUN	COMP.	MAIRIX	DAIE	IIME							00	10
19-D2-3				96.	10:54								
7 Ig-103-4				(.29	11:15								
27 19- p25				-3.	7:17								
sed the				.5%	12.51								
MTA - 103-4				.2.	27:11								
1-20- ptg				1.30	7.7								
٠ ا ا ا ا				1									
8			0.7										

							YES NO N/A	N 09	Ø
RELINQUISHED BY	DATE	TIME	RECEIVED BY	DATE	TIME	TIME CUSTODY SEALS INTACT			
						SAMPLE TEMP OC SATISFACTORY			
						SAMPLES RECEIVED INTACT			
						CHAIN OF CUSTODY & LABELS AGREE			
ORM: COC 10-02-7***									

▲TOTAL CONTAINERS

EMAIL:

FAX:

PHONE:

SAMPLE RECEIPT REQUESTED (MUST INCLUDE FAX OR EMAIL)

SAMPLED BY:

10



Date Sample Collected Time San Collecte Month Day Year	nple County			
Type of Water System (check only one box ☐ Group A Public ☐ Group B Public	Private Household ASR Other			
Group A and Group B Systems – Provide fr ID#	om Water Facilities Inventory (WFI):			
Contact Person: 636 G	NIFR			
	Cell Phone: (509) 530-3534			
Eve. Phone: ()	FAX: ()			
Send results to: (Print full name, address at				
INALLA WALLA BASIN I	NOT THE RESERVE OF THE PARTY OF			
810, SO, MAIN P.O				
MUTON-FREGUETE	2, OR. 97862			
SAMPLE IN	FORMATION			
Sample collected by (name):				
Specific location where sample collected (address or sample site, and type of faucet):				
Special instructions or comments:				
Type of Sample (must check only one box of #1 through #4 listed below)				
1.□ Routine Distribution Sample Provide information below. Chlorinated: Yes No Chlorine Residual: Total Free 1.□ Repeat Sample (follow-up to an unsatisfactory sample) Provide information below. Unsatisfactory routine lab number:				
3. ☐ Raw Water Source Sample Required for Surface Water, GWI, and some Spring Sources) ☐ Total Coliform ☐ ☐ ☐ ☐ Fecal Coliform Public Systems must provide Source Number from (WFI)	Unsatisfactory routine collect date: // / Chlorinated: Yes No Chlorine Residual: Total Free			
4. Sample Collected for Information Construction Repairs Priva	Only vate ResidenceOther			
The second secon				

LAB USE ONLY DRINKING WA	TER RESULTS LAB USE ONLY			
Unsatisfactory Total Coliform Present and □ E.coli present □ E.coli absent □ Fecal coliform present □ Fecal coliform	Satisfactory Total Coliform Absent			
☐ Replacement Sample Required	Sun Territoria Section Contraction			
Sample not tested because: Sample too old (>30 hours) Improper container Test unsuitable because: TNTC Turbid culture				
Bacterial Density Results: Plate Count_	/ml. E.coli/100m\.			
Total Coliform/100ml. Fed	al Coliform/100ml.			
MICR Method Code:	Date and Time Received:			
□ 1140 □ 1340 □ 2720	5/28/09 @ 10 Am			
Date Analyzed: 5/38/09	Date Reported: 5/29/09			
Lab/Sample Number	Lab Use:			
143- 06951				

DOH Form #331-319 (revised 5/06) SEE REVERSE OF GREEN COPY FOR EXPLANATION OF RESULTS

WATER SUPPLIER COPY



MILL CREEK WATER TREATMENT PLANT
581 MIII Creek Road • Walla Walla, WA 99362
Phone 509/522-3775 • Fax 509/529-9681

COLIFORM BACTERIA ANALYSIS
PLE COLLECTION: READ INSTRUCTIONS ON BACK OF GOLDEN ROD OF

	wed, sample will be rejected.				
Date Sample Collected Time Sa	ample County				
5 / 28 / 09 _ Collect	cted Walla Walla				
Month Day Year 5:30	2 PM VValla VValla				
Type of Water System (check only one bo	ox)				
☐ Group A Public	☐ Private Household				
☐ Group B Public	Other_				
Group A and Group B Systems – Provide	from Water Facilities Inventory (WFI):				
ID#					
System Name: WWBWC					
Contact Person: 608 6000					
Day Phone: (541) 938-2170	Cell Phone: (50A) 530 -353				
Eve. Phone: ()	FAX: ()				
Send results to: (Print full name, address					
WALLA WALLA BASIN	I WATERSHED COUNC				
810 SO. MAIN P.	Q BOX 68				
MILITON - FREEWATT	C) 02 03 01 0				
	7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7				
	NFORMATION				
Sample collected by (name):					
Confedential Boules	P. H.				
Specific location where sample collected					
HBD1C OP	S.V-mira Britania				
Special instructions or comments:					
Type of Sample (must check only one bo	ox of #1 through #4 listed below)				
1. ☐ Routine Distribution Sample	2. □ Repeat Sample (follow-up				
Provide information below.	to an unsatisfactory sample)				
Chlorinated: Yes No	Provide information below.				
Chlorine Residual: Total Free Unsatisfactory routine lab number:					
3. ☐ Raw Water Source Sample Required for Surface Water, GWI, and					
Required for Surface Water, GWI, and	Unsatisfactory routine collect date:				
Required for Surface Water, GWI, and some Spring Sources)	Unsatisfactory routine collect date:				
Required for Surface Water, GWI, and some Spring Sources) Total Coliform Fecal Coliform	/				
Required for Surface Water, GWI, and some Spring Sources)	Chlorinated Yes No				
Required for Surface Water, GWI, and some Spring Sources) Total Coliform Fecal Coliform	Chlorinated: Yes No Chlorine Residual: Total Free				
Required for Surface Water, GWI, and some Spring Sources) Total Coliform Fecal Coliform Public Systems must provide Source Number from (WFI) 4. Sample Collected for Information	Chlorinated: Yes No Chlorine Residual: Total Free				
Required for Surface Water, GWI, and some Spring Sources) Total Coliform Total Coliform	Chlorinated: Yes No Chlorine Residual: Total Free Only vate Residence Other				
Required for Surface Water, GWI, and some Spring Sources) Total Coliform Fecal Coliform Public Systems must provide Source Number from (WFI) 4. Sample Collected for Information Construction Repairs Pri LAB USE ONLY DRINKING W.	Chlorinated: Yes No Chlorine Residual: Total Free Only				
Required for Surface Water, GWI, and some Spring Sources) Total Coliform Fecal Coliform Public Systems must provide Source Number from (WFI) 4. Sample Collected for Information Construction Repairs Pri LAB USE ONLY DRINKING WA	Chlorinated: Yes No Chlorine Residual: Total Free Only vate Residence Other ATER RESULTS LAB USE ONL Satisfactory				
Required for Surface Water, GWI, and some Spring Sources) Total Coliform Fecal Coliform Public Systems must provide Source Number from (WFI) 4. Sample Collected for Information Construction Repairs Pri LAB USE ONLY Unsatisfactory Total Coliform Present and	Chlorinated: Yes No Chlorine Residual: Total Free Only vate Residence Other ATER RESULTS LAB USE ONL				
Required for Surface Water, GWI, and some Spring Sources) Total Coliform Fecal Coliform Public Systems must provide Source Number from (WFI) 4. Sample Collected for Information Construction Repairs Pri LAB USE ONLY DRINKING W. Unsatisfactory Total Coliform Present and E.coli present E.coli absent	Chlorinated: Yes NoChlorine Residual: Total Free Only vate Residence Other				
Required for Surface Water, GWI, and some Spring Sources)	Chlorinated: Yes NoChlorine Residual: Total Free Only vate Residence Other ATER RESULTS LAB USE ONL Satisfactory Total Coliform Absent				
Required for Surface Water, GWI, and some Spring Sources) Total Coliform Public Systems must provide Source Number from (WFI) 4. Sample Collected for Information Construction Repairs Pri LAB USE ONLY DRINKING W. Unsatisfactory Total Coliform Present and E.coli present Ecoli absent Fecal coliform present Fecal coliform Replacement Sample Required	Chlorinated: Yes NoChlorine Residual: Total Free Only vate Residence Other				
Required for Surface Water, GWI, and some Spring Sources) Total Coliform Public Systems must provide Source Number from (WFI) 4. Sample Collected for Information Construction Repairs Pri LAB USE ONLY DRINKING W. Unsatisfactory Total Coliform Present and E.coli present E.coli absent Fecal coliform present Fecal coliform Replacement Sample Required Sample not tested because:	Chlorinated: Yes NoChlorine Residual: Total Free Only vate Residence Other				
Required for Surface Water, GWI, and some Spring Sources) Total Coliform Public Systems must provide Source Number from (WFI) 4. Sample Collected for Information Construction Repairs Pri LAB USE ONLY DRINKING W. Unsatisfactory Total Coliform Present and E.coli present Ecoli absent Fecal coliform present Fecal coliform Replacement Sample Required	Chlorinated: Yes NoChlorine Residual: Total Free Only vate Residence Other				
Required for Surface Water, GWI, and some Spring Sources)	Chlorinated: Yes No Chlorine Residual: Total Free Only vate Residence Other ATER RESULTS LAB USE ONL Satisfactory Total Coliform Absent Test unsuitable because: TNTC Turbid culture				
Required for Surface Water, GWI, and some Spring Sources)	Chlorinated: Yes NoChlorinated: Yes NoChlorine Residual: Total Free Only vate Residence Other ATER RESULTS LAB USE ONL Satisfactory Total Coliform Absent Test unsuitable because: TNTC Turbid culture /ml. E.coli/100ml.				
Required for Surface Water, GWI, and some Spring Sources) Total Coliform Public Systems must provide Source Number from (WFI) 4. Sample Collected for Information Construction Repairs Pri LAB USE ONLY DRINKING W. Unsatisfactory Total Coliform Present and E.coli present E.coli absent Fecal coliform present Fecal coliform Replacement Sample Required Sample not tested because: Sample too old (>30 hours) Improper container Bacterial Density Results: Plate Count Total Coliform Fecal coliform	Chlorinated: Yes NoChlorinated: Yes NoChlorine Residual: Total Free				
Required for Surface Water, GWI, and some Spring Sources) Total Coliform Total Coliform Total Coliform Total Coliform Total Coliform Pri 4. Sample Collected for Information Graph Construction Repairs Pri LAB USE ONLY DRINKING W Total Coliform Present and E.coli absent Fecal coliform Present Fecal coliform Replacement Sample Required Sample not tested because: Sample too old (>30 hours) Improper container Bacterial Density Results: Plate Count Total Coliform /100ml. Fed MICR Method Code:	Chlorinated: Yes NoChlorinated: Yes NoChlorine Residual: Total Free Only vate Residence Other ATER RESULTS LAB USE ONL Satisfactory Total Coliform Absent Test unsuitable because: TNTC Turbid culture /ml. E.coli/100ml.				
Required for Surface Water, GWI, and some Spring Sources)	Chlorinated: Yes NoChlorinated: Yes NoChlorine Residual: Total Free				
Required for Surface Water, GWI, and some Spring Sources) Total Coliform Total Coliform Total Coliform Total Coliform Total Coliform Pri 4. Sample Collected for Information Graph Construction Repairs Pri LAB USE ONLY DRINKING W Total Coliform Present and E.coli absent Fecal coliform Present Fecal coliform Replacement Sample Required Sample not tested because: Sample too old (>30 hours) Improper container Bacterial Density Results: Plate Count Total Coliform /100ml. Fed MICR Method Code:	Chlorinated: Yes NoChlorinated: Yes NoChlorine Residual: Total Free				
Required for Surface Water, GWI, and some Spring Sources)	Chlorinated: Yes No_Chlorine Residual: Total Free Only vate Residence Other ATER RESULTS LAB USE ONL Satisfactory Total Coliform Absent Test unsuitable because: TNTC Turbid culture /ml. E.coli /100ml. cal Coliform / 100ml. Date and Time Received:				
Required for Surface Water, GWI, and some Spring Sources)	Chlorinated: Yes NoChlorinated: Yes NoChlorine Residual: Total Free				
Required for Surface Water, GWI, and some Spring Sources) Total Coliform	Chlorinated: Yes NoChlorinated: Yes NoChlorine Residual: Total Free				

WATER SUPPLIER COPY

Appendices II-A

OWRD Limited Testing License for HBDIC Recharge Site (#2) LL-1189

Permit to operate recharge: 2009-2014

Oregon Water Resources Department

Final Order Limited License Application LL-1189



Appeal Rights

This is a final order in other than a contested case. This order is subject to judicial review under ORS 183.484. Any petition for judicial review must be filed within the 60-day time period specified by ORS 183.484(2). Pursuant to ORS 536.075 and OAR 137-004-0080 you may either petition for judicial review or petition the Director for reconsideration of this order. A petition for reconsideration may be granted or denied by the Director, and if no action is taken within 60 days following the date, the petition was filed, the petition shall be deemed denied.

Requested Water Use

On January 30, 2009, the Water Resources Department received completed application **LL-1189** from Hudson Bay District Improvement Company for the use of 50 cubic feet per second from the Walla River, located in the SE ¼, NE ¼, Section 2, and the SW ¼, NE ¼, Section 12, Township 6 North, Range 35 East, W.M., for ground water recharge use, for the period of February 19, 2009, through February 18, 2014.

Authorities

The Department may approve a limited license pursuant to its authority under ORS 537.143, 537.144 and OAR 690-340-0030.

ORS 537.143(2) authorizes the Director to revoke the right to use water under a limited license if it causes injury to any water right or a minimum perennial streamflow.

A limited license will not be issued for more than five consecutive years for the same use, as directed by ORS 537.143(8).

Findings of Fact

- 1. The forms, fees, and map have been submitted, as required by OAR 690-340-0030(1).
- 2. The Department provided public notice of the application, on February 3, 2009, as required by OAR 690-340-0030(2).
- 3. This limited license request is limited to an area within a single drainage basin as required by OAR 690-340-0030(3).
- 4. The Department has determined that there is water available for the requested use.
- 5. The Department has determined that the proposed source has not been withdrawn from further appropriation.

- 6. Because this use is from surface water and has the potential to impact fish, the Department finds that fish screening is required to protect the public interest.
- 7. Because the use requested is longer than 120 days and because the use is in an area that has sensitive, threatened or endangered fish species, the use is subject to the Department's rules under OAR 690-33. These rules aid the Department in determining whether a proposed use will impair or be detrimental to the public interest with regard to sensitive, threatened, or endangered fish species.
- 8. The Department has received comments related to the possible issuance of the limited license from the Confederated Tribes of the Umatilla Indian Reservation (CTUIR) in support of the project and requesting measured and reported data and results from the previous 5 years and annual reporting of results to CTUIR and basin water managers. Oregon Department of Environmental Quality (ODEQ) notified the Department that it had no comments, since the water quality monitoring plan for the previous Limited License was acceptable, and did not change for this application. The comments did cause the Department to add additional conditions or limitations. The licensee shall work with CTUIR to provide data as requested. The authorization of limited license LL-1189, as conditioned below, will satisfactorily address the issues raised in those comments.
- 9. Pursuant to OAR 690-340-0030(4)(5), conditions have been added with regard to notice and water-use measurement.

Conclusions of Law

The proposed water use will not impair or be detrimental to the public interest pursuant to OAR 690-340-0030(2), as limited in the order below.

Order

Therefore, pursuant to ORS 537.143, ORS 537.144, and OAR 690-340-0030, application LL-1189 is approved as conditioned below.

- 1. The period and rate of use for **LL-1189** shall be from February 23, 2009, through February 18, 2014, for the use of 50 cfs of water from the Walla Walla River, for the purpose of groundwater recharge testing during the period November 1 through May 15 each year.
- 2. The licensee shall give notice to the Watermaster in the district where use is to occur not less than 15 days or more than 60 days in advance of using the water under the limited license. The notice shall include the location of the diversion, the quantity of water to be diverted and the intended use and place of use. In the case of this application, this order serves as the notice described above.

- 3. When water is diverted under this Limited License, the use is limited to times when the following minimum streamflows are met in the Tum A Lum reach of the Walla Walla River, between the Little Walla Walla River diversion and Nursery Bridge Dam and flowing past Nursery Bridge Dam: November 64 cfs, December and January 95 cfs, February to May 15 150 cfs. Nursery Bridge Dam is located just downstream of Nursery Bridge and is downstream of the Little Walla Walla diversion. The District 5 Watermaster, based on gage and/or streamflow measurements, shall make the determination that the above described streamflows are flowing past Nursery Bridge Dam. Diversion under this Limited License shall cease when said streamflows are unmet.
- 4. The Licensee shall follow the same operations, monitoring and reporting plan that was developed with ODEQ for the water quality plan followed in LL-758.
- 5. Based on a review of water quality information generated during the term of this Limited License, or from other sources, ODEQ may require the licensee to terminate the diversion of water into the recharge area. In addition, if monitoring data or other information result in identification of potential water quality concerns, ODEQ may require modifications to the existing Limited License and/or require a permit to address the water quality concerns prior to resumption of artificial groundwater recharge.
- 6. Before water use may begin under this license, the licensee shall install a totalizing flow meter at each point of diversion. The totalizing flow meter must be installed and maintained in good working order. In addition the licensee shall maintain a record of all water use, including the total number of hours of pumping, the total quantity pumped, and the categories of beneficial use to which the water is applied. During the period of the limited license, the record of use shall be submitted to the Department annually, and shall be submitted to the Watermaster upon request.
- 7. The Director may revoke the right to use water for any reason described in ORS 537.143(2), and OAR 690-340-0030(6). Such revocation may be prompted by field regulatory activities or by any other information.
- 8. Use of water under a limited license shall not have priority over any water right exercised according to a permit or certificate, and shall be subordinate to all other authorized uses, including Limited Licenses issued prior to this one, that rely upon the same source.
- 9. The licensee shall install, maintain and operate fish screening and by-pass devices as required by the Oregon Department of Fish and Wildlife to prevent fish from entering the proposed diversion. See copy of enclosed fish screening criteria for information.
- 10. The licensee shall provide the Confederated Tribes of the Umatilla Indian Reservation the data, results, and analysis that were sought by letter dated February 17, 2009.
- 11. A copy of this limited license shall be kept at the place of use, and be available for inspection by the Watermaster or other state authority.

NOTE: This water-use authorization is temporary. Applicants are advised that issuance of this final order does not guarantee that any permit for the authorized use will be issued in the future; any investments should be made with that in mind.

Issued March 5, 2009

E. Timothy Wallin, Water Rights Program Manager, for

Phillip C. Ward, Director

Water Resources Department

Enclosures - limited license, fish screen criteria

Twiothy Wall.

cc: Tony Justus, District 5 Watermaster Bill Duke, ODFW Phil Richerson, DEQ Eric Quaempts, CTUIR Hydrographics File

If you need further assistance, please contact the Water Rights Section at the address, phone number, or fax number below. When contacting the Department, be sure to reference your limited license number for fastest service.

Remember, this limited license does not provide a secure source of water. Water use can be revoked at any time. Such revocation may be prompted by field regulatory activities or many other reasons.


Water Rights Section Oregon Water Resources Department 725 Summer Street NE, Suite A Salem OR 97301-1271

Phone: (503) 986-0817 Fax: (503) 986-0901

Appendices II-B

WWBWC-HBDIC Application to OWRD Limited Testing License for HBDIC Recharge Site (#2) LL-1189

1/21/2009



Application for Limited Water Use License

A summary of review criteria and procedures that are generally applicable to these applications is available at www.wrd.state.or.us/OWRD/PUBS/forms.shtml.

License No. <u>LL-1</u>		
Applicant(s):	Hudson Bay District Improvem John Zerba-HBDIC (Bob)	ent Co. (HBDIC)
Contact Person:	John Zerba-HBDIC (Bob)	Buer-hwBWC)
Mailing Address:	144 Main str. Milton-Fre	ewater, OR 97862
Telephone No:	541-938-6105(20	ba) / 541-938-217\$ (Bower)
waters or groundy	ication for a Limited License to use or store the follow water-not otherwise exempt, or to use stored water of or <u>fixed duration</u> :	<u> </u>
1. SOURCE((S) OF WATER for the proposed use: Walla	Walla River a
2. TOTAL A 22. 440 ga quantity fr	MOUNT OF WATER to be diverted: cubic cubic llons per minute. If water is to be used from more the om each:	c feet per second, or an one source, give the
☐ Road o	construction or maintenance; al construction; land and rangeland management; or Aquifer Techarge	JAN 3 0 2009 WATER RESOURCES DEPT SALEM, OREGON
of use as s	TION OF PROPOSED PROJECT: Include a descript hown on the accompanying site map, the method of vent to be used (including pump horsepower, if applications and pipelines: See A Hacked (over lefter materials)	water diversion, the type able), length and dimensions
	<u>materials</u>	

5. PROJECT SCHEDULE: (List day, month, and year)
Date water use will begin
Date project will be completed
Feb. 19th 2014

Date water use will be completed Feb 18th 2014

PLEASE READ CAREFULLY

NOTE: A completed water availability statement from the local watermaster, Land Use Information Form completed by the local Planning Department, fees and site map meeting the requirements of OAR 690-340-030 must accompany this request. The fee for this request is \$150 for the first point of diversion plus \$15 for each additional point of diversion. Failure to provide any of the required information will result in return of your application. The license, if granted, will not be issued or replaced by a new license for a period of more than five consecutive years. The license, if granted, will be subordinate to all other authorized uses that rely upon the same source, or water affected by the source, and may be revoked at any time it is determined the use causes injury to any other water right or minimum perennial streamflow.

If water source is a well, well logs or adequate information for the Department to determine aquifer, well depth, well seal and open interval, etc. are required. The licensee shall indicate the intended aquifer. If for multiple wells, each map location shall be clearly tied to a well log.

If a limited license is approved, the licensee shall give notice to the Department (Watermaster) at least 15 days in advance of using the water under the Limited License and shall maintain a record of use. The record of use shall include, but need not be limited to, an estimate of the amount of water used, the period of use and the categories of beneficial use to which the water is applied. During the period of the Limited License, the record of use shall be available for review by the Department upon request.

REMARKS:	OWRO Water Master (Tony Justus) sending
hic	water availability report (separately) to Salem; for this application.
SIGNATURE o Title:	Applicant: DATE: 1-21-09

Mapping Requirements (OAR 690-340-0030):

(1) A request for a limited license shall be submitted on a form provided by the Water Resources Department, and shall be accompanied by the following:

RECEIVED

(c) A site map of reproducible quality, drawn to a standard, even scale of not less than 2 inches = 1 mile, showing:

JAN 3 0 2009

(A) The locations of all proposed points of diversion referenced by coordinates or by bearing and distance to the nearest established or projected public land survey corner;

WATER RESOURCES DEPT SALEM, OREGON

(B) The general course of the source for the proposed use, if applicable;

(C) Other topographical features such as roads, streams, railroads, etc., which may be helpful in locating the diversion points in the field.

This page to be completed by the local Watermaster.

WATER AVAILABILITY STATEMENT

Name of Applicant: Hudson Bay Im Number: <u>I.L-1189</u>	provement Company	Limited License
1. To your knowledge, has the stream regulated for prior rights?	m or basin that is the set \square No	ource for this application ever been
If yes, please explain:		
The Walla Walla River is typically s September and October.	short of water to serve	all water rights in July, August,
2. Based on your observations, would needed to supply the use proposed b		able in the quantity and at the times
3. Do you observe this stream system X Ye If yes, what are your observations for	es No	vork?
ii yes, what are your observations in	r the stream?	
Typically, there can be water available 33 may also dictate restrictions on p		e. OAR Division
interference with nearby surface wat	ter sources, would ther	at there is the potential for substantial e still be ground water and surface at requested without injury to existing
	s $\square_{ m No}$	⊠ _N /A
What would you recommend for corthis application?	nditions on a limited lie	cense that may be issued approving
• • •		fursury Bridge Dam. Restrict with by- - 64 cfs, December & January- 95 cfs
5. Any other recommendations you	would like to make?	
Subordinate to any other limited lice	nse from the same sou	arce issued prior to this one.
Signature	WM District	#: Date:

This page to be completed by the local Watermaster.

WATER AVAILABILITY STATEMENT

Name of Applicant: Hudson Bay In Number: <u> </u>	nprovem	ent Company	Lin	nited License	
1. To your knowledge, has the streamegulated for prior rights?	am or bas Yes	_	source for th	is application ever bee	en
If yes, please explain:					
The Walla Walla River is typically September and October.	short of	water to serve	all water ri	ghts in July, August,	
2. Based on your observations, wou			lable in the o	quantity and at the tim	es
needed to supply the use proposed X	oy uns ar Tes	·		RECEIVED	
3. Do you observe this stream syste	m during	regular field	work?	FEB 0 2 2009	
\boxtimes_{Y}	res	No	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	WATER RESOURCES DES	PT
If yes, what are your observations f					
Typically, there can be water availa 33 may also dictate restrictions on page 23.			ne. OAR Di	ivision	
4. If the source is a well and if WRI interference with nearby surface wawater available during the time requivater rights?	ater sourc	es, would the	re still be gr	ound water and surfac	e
\square_{Y}	es	\square_{No}	$\mathbf{X}_{N/A}$		
What would you recommend for co this application?	nditions	on a limited l	icense that n	nay be issued approving	ng
Allow diversion only when by-pass pass flows similar to the flows in Portion of the flows in Portion o					
5. Any other recommendations you	would li	ke to make?			
Subordinate to any other limited lic	ense from	n the same so	urce issued	prior to this one.	

ture Vory fusto WM District #: 5 Date: fanuary 30, 2009

Application for Limited Water Use License



Oregon Water Resources Department Land Use Information Form

THIS FORM IS NOT REQUIRED IF: 1) water is to be diverted, conveyed, and/or used only on federal lands; or 2) the application is for a water-right transfer, allocation of conserved water, exchange, permit amendment, or ground water registration modification, and all of the following apply: a) only the place of use is proposed for change, b) there are no structural changes, c) the use of water is for irrigation, and d) the use is located in an irrigation district or exclusive farm-use zone.

App	licant Nan	ne:	Hud] د، درا	Bay Dis	that Improv	ement (MOMY	
Applicant Name: Hudson Bay District Improvement Company Mailing Address: 144 Main Str.									
City: M, How- Freewater State: OR Zip: 97862 Day Phone: 541-938-6105									
City. 1700 2 Day Findic. 341-730 810 3									
A. Land and Location									
						x lots where water will			
						or irrigation uses within mation requested below		icts may subs	intuite existing and
	Township	Range	Section	1/4 1/4	Tax Lot#	Plan Designation (e.g. Rural Residential/RR-5)	Water	to be: N/A	Proposed Land Use:
	62	35E	3.3	NE	900	N/A	Diverted Conve	•	N/A
						<u>'</u>	Diverted Conve		
							Diverted Conve		
							Diversed Conve		
							44/		
List a	dl counties	and citie	s where	water is	proposed to	be diverted, conveyed,	or used.	†	
									
B D	escriptio	n of Pro	nosod	leo					
Type	of applica	tion to be	niea wi	th the v	vater Resou	rces Department:			
[☐ Permit	to Use o	r Store W	ater	□ Wa	ter-Right Transfer	☐ Exchange of	f Water	
	☐ Allocat				_	nited Water Use License	•		
[☐ Permit	Amendn	nent or G	round V	Water Regis	tration Modification			
Sour	ce of water	: Reserv	oir/Pond		Ground W	/ater Surface W	ater (name) $\sqrt{\mathcal{V}}$	alla Wall	a River
					50				
Estimated quantity of water needed:							cre-reer		
Intended use of water: Irrigation Commercial Industrial Domestic for household(s)									
] Munici	oal 🗀	Quasi-mur	nicipal Instream	Other	Pechara	<u></u>
								`	
Briefly describe: HBOIC Aquites Placharge site will recharge water to shallow aquiter for community and ecological benefits.									
the do challe so to the to see that									
water to swelling and the comment of the									
x cological benegits.									
Note to applicant: If the Land Use Information Form cannot be completed while you wait, please have a local government									
	representative sign the receipt below and include it with the application filed with the Water Resources Department.								

Receipt for Request for Land Use Information

State of Oregon Water Resources Department 725 Summer Street NE, Suite A Salem, OR 97301-1266 RECEIVED

JAN 3 0 2009

WATER RESOURCES DEPT SALEM, OREGON

For Local Government Use Only

The following section must be completed by a planning official from each county and city listed unless the project will be located entirely within the city limits. In that case, only the city planning agency must complete this form.

This deals only with the local land-use plan. Do not include approval for activities such as building or grading permits.

Please check the appropriate box below and provide the requested information

Land uses to be served by proposed water uses (including proposed construction) are allowed outright or are not regulated by your comprehensive plan. Cite applicable ordinance section(s): ______.

Land uses to be served by proposed water uses (including proposed construction) involve discretionary land-use approvals as listed in the table below. (Please attach documentation of applicable land-use approvals which have already been obtained. Record of Action/land-use decision and accompanying findings are sufficient.) If approvals have been obtained but all appeal periods have not ended, check "Being pursued".

Type of Land-Use Approval Needed (e.g. plan amendments, rezones, conditional-use permits, etc.)	Cite Most Significant, Applicable Plan Policies & Ordinance Section References	Land-Use Approval:	
1711	11/ 1	Obtained	Being pursued
NIA	I WA	Denied	Not being pursued
	, , , , , , , , , , , , , , , , , , , 	Obtained	Being pursued
		Denied	Not being pursued
		Obtained	Being pursued
	•	Denied	Not being pursued
		Obtained	Being pursued
·		Denied	Not being pursued
		Obtained	Being pursued
		Denied	Not being pursued

Local governments are invited to express special land-use concerns or make recommendations to the Water Resources

Department regarding this proposed use of water below, or on a separate sheet.

This project previously approached by flamming.

Unachilla County Planaine? In Superative of developing involve him. I must him. I must him. I must him. I must him. I must him. I must him. I must him. I must him. I must him. I must him. I must him. I must him. I have the form of the flamming.

Shorter receipt Lace believe are constant.

Name:

Signsture:

Phone 14. 178.645 | Date. 1 - 16 - 09

Rovernment Entities I must him and 30 days from the Water Resources Department's notice date to return the completed Land Use Information Form or WRD may presume the land use associated with the proposed use of water is compatible with local comprehensive plans.

Receipt for Request for Land Use Information

Applicant name:

City or County:

Staff contact:

Last updated 12/22/06 WR

RECEIVED

JAN **3 0** 2009



RECEIVED

JAN 30 2009

To: Water Rights Section

Oregon Water Resources Department

158 12th St NE Salem, OR 97310 WATER RESOURCES DEPT SALEM, OREGON

From: Walla Walla Basin Watershed Council (WWBWC)/Hudson Bay District

Improvement Company (HBDIC)

810 South Main Street

Milton-Freewater, Oregon 97862

RE: New Limited Testing License Application for HBDIC Recharge Site (Final Order 758).

To Whom It May Concern:

This letter and attached documents are being submitted in support of our application for a new limited testing license for aquifer recharge at the HBDIC Recharge project, in Umatilla County Oregon. The actual recharge site is located in the NE ½, of Section 33, Township 6 North, and Range 35 East. The project has been in operation for nearly 5 years and has shown to effectively recharge water to the aquifer, help restore baseflows to downgradient streams and recharge good quality surface water in to the shallow aquifer system. Through a series of Rules Advisory Committee (RAC) meetings last spring and early summer the OWRD worked to add aquifer recharge to the basin rules¹ along with surface storage. The RAC was decided that the decision to add aquifer recharge and surface storage for the Walla Walla basin would be delayed pending the US Army Corp of Engineers (CTUIR) Feasibility study project being completed in 2010. Therefore to continue to test aquifer recharge at the HBDIC recharge site we are submitting a new limited testing license for the site (see attached).

We are also submitting the support materials (study plan, etc) from the original application titled Hudson Bay Aquifer Recharge Project: An application for AR Testing Limited License to Oregon Water Resource Department (OWRD) (October, 20th 2003, Attachment A). In this new limited testing license application we request to follow the same operations, monitoring and reporting plan that was outlined in this original application. ODEQ (Phil Richerson, Pendleton-ODEQ) was contacted this week regarding this new application and gave a verbal permission to submit the same water quality plan that was developed with ODEQ (2003) and submitted with our original application.

We are also requesting that the new limited license has **the same** water-use conditions of Final Order #758 including:

- ☐ Water Use time period: November 1st through May 15th
- ☐ Maximum Water Use Allocation of **50 cfs**.
- ☐ Seasonal Minimum Instream flow requirements (Walla Walla River) as were determined by ODFW and CTUIR in original application which were:
 - November 1st through November 31st = 64 cfs

¹ Mike Ladd, Tony Justus at OWRD Pendleton office can be contacted regarding this process.



- December 1st through January 31st = 95 cfs
- o February 1st through May 15th = 150 cfs

Final Order #758 Final Requirements stated that "The licensee shall meter all water use and maintain a record of use, including the total number of hours of diversion and an estimate of the total quantity diverted. During the period of the limited license, the record of use shall be available for review by the Department upon request and shall be submitted to the Watermaster upon request. Upon project completion, the license shall submit the record of use to the Water Resources Department."

At the time of this letter, the project was still in operations (2008-9 recharge season), but a summary for the record of use (as outlined above) can be found in **Attachment B**. The attachment outlines both the water use from the Walla Walla River (POD) to the HBDIC Recharge Project (as estimated conveyance loss of 10 cfs) and the actual water use at the HBDIC recharge site. Following the completion of final order #758, a summary of all water use 2004-2009 will be provided to the department. All water use meter records are available to OWRD staff at any time, upon request. As the HBDIC site has gone through several expansions during this 2004-2008 period, **Attachment C** outlines some additional information that will help assess the changes in water use at the site over the period of record. The HBDIC recharge project managers intend to further develop this site for recharge testing upon approval of a new limited testing license.

You will find the following Attachments in support of this new application:

- ☐ Attachment A-C: Original Application Supporting document that includes:
 - o Maps of site as required by OWRD application
 - o ODEQ Water Quality Monitoring Plan (and supplementary changes)
- ☐ Attachment D: Copy of Current OWRD Limited Testing License (Final Order#758)
- ☐ Attachment E: Original Water availability report from OWRD water master (New one being sent to Salem from Pendleton Office)

Also attached you will find the application fee for \$165 dollars to cover new limited license application. As there are now two separate diversions at the recharge site, we added the additional \$15 for this application to ensure the proper fee was submitted.

Thank you for your continued support.

Robert J. Bower

Senior Flydrologist/HBDIC Project Co-manager

Walla Walla Basin Watershed Council

RECEIVED

00000

JAN 3 0 2009


WATER RESOURCES DEPT SALEM, OREGON

Cc: Tony Justus, OWRD Pendleton Rick George, CTUIR, Mission Phil Richerson, ODEQ, Pendleton Bill Duke, ODFW, Pendleton on application for ASE contain Line of the new resonance Department (INVIII)

Attachment A

Hudson Bay Aquifer Recharge Project

An application for ASR Testing Limited License to Oregon Water Resources Department (OWRD) (OAR 690-350-0020)



Prepared for the HBDIC by:

Walla Walla Basin Watershed Council Kennedy and Jenks Consultants, Inc.

October 20, 2003

RECEIVED

JAN 3 0 2009

Table of Contents

Table of Contents	2
Introduction	4
Overview of Watershed Conditions	4
Figure 1 Scaled Map of Project and Surrounding Area	7
Figure 2 WWBW Monitoring and Recharge Site Map	
Attachment 1. Project Layout, 690-350-0020(3)(a)(E) and (I) and 690-350-0020(3)(b)(B)	10
Engineering Attachments:	
Attachment 1A: Location Map	
Attachment 1B: Site Plan	
Attachment 1C: Structure Details.	
Attachment 1D: Structure Reinforcing Steel	
Attachment 1E: Signed and Stamped Copy of Project Engineering Report	
Attachment 2. Water Rights Statement, 690-350-0020(3)(a)(F) and (G)	
Water Right Applicant:	
Hudson Bay District Improvement Co	12
Source of Water:	
Purpose of Use:	
Proposed Period of Use:	
Point of Diversion Location:	
Minimum Instream Flow Information:	
Attachment 3. Land Use Approval, 690-350-0020(3)(a)(H)	
Land Use Attachments	14
Attachment 3A: Umatilla County Land Use Approval	
Attachment 3B: Lease Agreement with Landowner	
Attachment 4. Proposed Test Program, 690-350-0020(3)(b)(A)	
Introduction.	15
Preliminary Test Site-Specific Hydrogeologic Characterization	
Soil Characteristics	
Geology	
Hydrogeology	
Surface Water	
Water Quality	
Characterization Conclusions	
Preliminary Test Site Operation Plan	
Site Construction	
Test Operations	
Test Timing, Monitoring, and Water Quantities	
Outside Influences	
Responsible Parties and Access Permission	
Mitigation	
Reporting	
Attachment 5. Proposed Monitoring Program, 690-350-0020(3)(b)(A)	
Overview of Basin Wide Monitoring Plan	
Recharge Project Monitoring Plan	
Sampling and Analysis Program	
(1) Source Water at Test Site	
(2) Site Groundwater	
(3) Distal Groundwater	
(4) Surface Water (Springs)	
Sampling Parameters	
Damping 1 atameters	

RECEIVED

Sampling Procedure	27
Equipment	27
Water Level	
Decontamination	28
Purging and Field Parameters (On site wells only)	28
Water Sampling	
Resampling	
Chain of Custody and Sample Handling	29
Field Records and Data Validation	
Data Reporting and Statistical Analysis	30
Record Keeping	
Evaluation	30
Data evaluation will include:	30
Annual Review and Reporting	30
Final Recharge Test Project Report	31
Monitoring Plan Attachments	31
Attachment 5A. Methodology Water Quality Assessment and Evaluation	31
Attachment 5B. Figure 5A Map of On-site Recharge Well Locations	
Attachment 5C Chemicals of interest for Hudson Bay Recharge Project	
Attachment 6. Site Hydrogeology, 690-350-0020(3)(b)(C), (E), and (G) (attached)	
Attachment 7. Source Water Quality, 690-350-0020(3)(b)(D)	
Overview	
Attachment 7A Source Water Quality Information	
Resources and References:	
ATTACHMENTS	34
PAHachment SD History of chemical Use Recharge Site Specific	
Attachment SD History of chemical Use Recharge Site Specific Attachment 8A water Availability (water Master) 8B Application form - OWRD	
8B Application form-OWID	

RECEIVED

JAN 3 0 2009

Introduction

The Walla Walla Basin Watershed Council (WWBWC), in cooperation with the Hudson Bay District Improvement Company (HBDIC), has proposed to test shallow aquifer recharge at a site located adjacent to the HBDIC's White Ditch in section 33, T6N, R35E. At the test site a series of three infiltration pits will be built. Water will be supplied to these pits via a diversion from the canal. Recharge activities are proposed during the winter and spring months, when the Walla Walla River (the source of water for the canal) is running at higher flows. The proposed shallow aquifer recharge testing would be done under an ASR Testing Limited License granted by Oregon Water Resources Department (OWRD) (OAR 690-350-0020). By recharging shallow groundwater it is hoped that a portion of the recharge water will return to restore diminished spring-creek and Walla Walla River baseflows. Testing will not include removal of stored water by pumping or other artificial means.

0

0

CE

CE.

The Limited License Application requires several supporting documents be attached (690-350-0020 (3)(b)), including (but not limited to) those describing proposed testing, groundwater conditions (including hydrogeologic conditions and groundwater quality), and source water quality. Information not included in this assessment report, but still needed for the application, will be collected during proposed site-specific hydrogeologic characterization, monitoring, and testing process. This limited license application is to gain approval of the proposed shallow aquifer recharge testing. The complete list of Attachments as called for in include:

Attachment 1. Project Layout and Size, 690-350-0020(3)(a)(E) and (I) and 690-350-0020(3)(b)(B)

Attachment 2. Water Rights Statement, 690-350-0020(3)(a)(F) and (G)

Attachment 3. Land Use Approval, 690-350-0020(3)(a)(H)

Attachment 4. Proposed Test Program, 690-350-0020(3)(b)(A)

Attachment 5. Proposed Monitoring Program, 690-350-0020(3)(b)(A)

Attachment 6. Site Hydrogeology, 690-350-0020(3)(b)(C), (E), and (G)

Attachment 7. Source Water Quality, 690-350-0020(3)(b)(D)

Overview of Watershed Conditions

The quantity, storage, timing, and availability of water are several major challenges facing watershed managers in the Walla Walla River Basin. The relationship between the Walla Walla River and its distributaries with that of the shallow alluvium aquifer has been shown to be highly interdependent (Piper, 1933, Newcomb, 1965, Barker & McNish, 1975, Bower et. al., 2001). The Walla Walla Basin Watershed Council, Walla Walla Watershed Alliance, and Hudson Bay District Improvement Company (HBDIC), working with their partners in OWRD, ODEQ and ODFW, propose to explore the utility of artificially recharging the shallow alluvial aquifer as a way to help offset the loss of natural recharge opportunities throughout the basin.

Surface water and shallow groundwater in the Walla Walla Basin (the Basin) form an interconnected system. In some areas, especially upstream areas where streams leave the mountains and highlands surrounding the Basin to flow out onto the Basin floor, streams historically probably branched out onto the Basin floor and some of the water they carried seeped into the ground, recharging the shallow groundwater system. This shallow groundwater, recharged near the edge of the Basin, formed the main source of clean, cool groundwater found further down basin where it returned to the surface via springs and base flow to the Walla Walla River. Through the years, the issuance of hundreds of surface and groundwater rights has resulted in the allocation of nearly all of the naturally available water in the basin. These allocations have pressured water resources, compelling the

RECEIVED

Washington State Department of Ecology to close ground waters to further appropriations due to concerns about dropping water table levels. Other indicators of overstressed water resources include: (1) dry or dropping well levels, some wells in OWRD's inventory of state-observation-wells, (2) dry or dropping flow volumes in the spring branches, and (3) loss of natural and artificial groundwater recharge opportunities through irrigation efficiency and improved surface water management.

The state of Oregon has recognized use of artificial recharge as a tool "that can be an effective and efficient method for storing water for futures uses." (OWRD, Umatilla Basin Report, 1988). Artificial recharge has been shown to work in other areas of Umatilla County such as the County Line Water Improvement District Project, in operation since 1977. An OWRD review of this project states "It has been instrumental in arresting and reversing ground water level declines in a portion of the Ordnance Critical Ground Water Area." (OWRD, 1988). The USGS also noted the need for artificial recharge in the Walla Walla valley to offset increased water demands and loss of natural and artificial recharge mechanisms: "(Irrigation efficiency measures) can diminish the infiltration to recharge the ground water," wrote Newcomb in his important 1965 report. "Consequently, any such plans for changes in river regimen could well be required to provide for compensatory recharge or to sustain counter charges for their diminution of natural recharge and storage.

This project will comprise of three major components: Construction-Operation, Monitoring-Evaluation and Outreach-Education.

Construction-Operation: After receiving the appropriate permits and/or approval from OWRD, OWDF, ODEQ, USFWS, NOAA Fisheries and the Umatilla County Planning Department, a series of three pits specifically designed for passive artificial recharge will be constructed on land provided by the Hudson District Improvement Company (HBDIC). The land is being leased from one of the district's patrons by the HBDIC and a written agreement for the lease has been secured. The pits will be constructed in such a way to maximize recharge rates while minimizing the ground water quality impacts during the winter/spring recharge period. Project features include a concrete check structure in adjacent White Ditch, a concrete flow-measuring flume, an open connection ditch, three excavated pits, pipes connecting the pits and an outflow ditch from the down stream pit. These pits are designed to handle 50 cubic feet per second (cfs) of water anticipated to be available during the winter/spring Walla Walla River runoff. The actual volume of winter-spring water delivered will depend on the above-mentioned permitting and review process and the actual field verified constraints once in operation. Operation of this structure will be based on the instructions provided by OWRD in the operation permit and agreed to by the various project partners and agencies.

Monitoring-Evaluation: Monitoring of project will be conducted at several levels including: (1) onsite subsurface hydrologic and hydrogeologic monitoring, (2) off-site subsurface hydrologic and hydrogeologic monitoring, (3) off-site surface monitoring of springs through flow and photo-point measurements, (4) on/off-site water quality monitoring of key physical and chemical properties. The results of this intensive monitoring will be evaluated to identify impacts of the proposed project on groundwater levels and flow beneath and around the site, on surface water and spring discharges down gradient of the site, and on base flow to the Walla Walla River. Monitoring will also identify potential problems associated with the project

RECEIVED

JAN 3 0 2009

Outreach-Education: This project will also serve as an important outreach and education tool for the general public and water users of the Walla Walla valley. Particular focus and time will be spent on utilizing the site and the results for the recharge analysis to educate people on the role that ground water plays in the rivers and streams of the Walla Walla Watershed.

This project meets all of the habitat restoration actions from the Oregon Aquatic Habitat Restoration and Enhancement Guide including:


- 1. Change the trend of aquatic habitat function from one of a diminishing ability to support salmonids and other organisms to one that supports a complex, self-sustaining system. Such systems provide high quality habitat and ecological capacity for salmonids and other species; or
- 2. Correct or improve conditions caused by past management and/or disturbance events; or
- 3. Maximize beneficial habitat in the short term where watershed degradation has been extensive and natural processes will need substantial time to restore habitat; or
- 4. Create beneficial habitat and restore stream function to the fullest extent possible within developed areas where no reasonable expectation of returning to natural conditions exists.


RECEIVED

JAN 3 0 2009

HUDSON BAY AQUIFER RECHARGE PROJECT LOCATED IN THE NE 1_4 OF SEC33, T6 N, R35E W.M.

Figure 1 Scaled Map of Project and Surrounding Area





NOTE.

THE PURPOSE OF THIS MAP IS TO IDENTIFY THE APPROXIMATE LOCATION OF THE PROJECT. IF IS NOT IMPOUNDED FOR PROVIDE INFORMATION RELATIVE.

TO THE EXACT LICENTED OF PROPRETY OWNERSHIP DURINERY LINES OF ANY OTHER SCHOOL TICAT MAP SUBJECT!

LEGEND

POWELL PV CANAL

TAX LOT BOUNDERY LINES

QUARTER QUARTER LINES

SECTION CORNER



HUDSON W THE QUIFE NE 1/4 OF FIGURE N RECHAR SE ů, T6 H PROJECT R35E





Figure 2 WWBW Monitoring and Recharge Site Map

FIGURE 2. WWBWC Monitoring Network and Hudson Bay Recharge Project 2003



RECEIVED

Attachment 1. Project Layout, 690-350-0020(3)(a)(E) and (I) and 690-350-0020(3)(b)(B)

Prepared by Bernard Hewes, Licensed Engineer in the State of Oregon.

This project entails diverting water from an existing irrigation ditch to three pits to be excavated for the purpose of infiltrating the water into the shallow aquifer. Project features include a concrete check structure in the existing White Ditch, a concrete flow measuring flume, an open ditch, three excavated pits, pipes connecting the pits and an outflow ditch from the down stream pit.

These items were sized to handle 50 cubic feet per second (cfs) of water. This is the amount anticipated will be available from excess flow in the Walla Walla River and that the Hudson Bay District is able to deliver.

Data gathered to design the project consisted of a site topographic survey and installing two sites for testing the water infiltration capacity of the natural materials and determining the layers in the soil profile. In addition the Soil Survey of Umatilla County Area, Oregon was consulted. This is a US Dept. of Agriculture, Natural Resources Conservation Service publication giving general soils information.

The topographic survey data was used to prepare a topographic map with one foot contour intervals at a scale of 1" = 60'. This information was used to help determine the location of the project features.

Two test pits were excavated to a depth of 6'-7' each. A 24" diameter by 5' long section of corrugated metal pipe was set on end in the bottom of the pit and about one foot of fill placed around it to hold it in place. Water was pumped into the pipe at a rate that would sustain a water depth of one foot in the pipe. Both flow rate and total flow was measured. The test was run for 6.25 hours in the first pit and 3.5 hours for the second pit.

PIT #1

Soil profile:

0-12" sandy loam

12"-36" gravelly sandy loam, approximately 50% of the material volume is gravel size particles with an estimated D 50 size of about 0.75"

36"-48" sandy loam, in parts of the trench this layer does not exist

48"-?" gravelly sandy loam approximately 20% of the volume is gravel size particles

The inflow rate at the end of the test period was 4.0 gallons per minute (gpm). This resulted in an infiltration rate of 1.7 gpm/sq. ft./ foot of head.

PIT #2

Soil profile:

0"-13" gravelly sandy loam

13"-39" cobbly sandy loam, the D50 of the gravel is approximately 1"

39"-52" gravelly sandy loam

52"-? sand gravel mix D 50 estimated to be about 0.25"

JAN 3 0 2009
WATER RESOURCES DEPT SALEM, OREGON

In this pit the inflow rate of 11.9 gpm was maintained for 3.5 hours and at no time did water puddle in the bottom of the pipe. The infiltration rate is in excess of 3.8 gpm/sq. ft.

The area needed for infiltrating the water was determined assuming an infiltration rate for the entire area of 3.0 gpm/sq.ft./ per foot of head. For an inflow rate of 50 cfs the infiltration area needs to be

7480 square feet. The infiltration rate of 3.0 gpm/sq.ft. was chosen because the pits will be located in the area with soil surface texture similar to test pit #2.

Due to the possibility of fine soil particles plugging the infiltration area, unknowns concerning the long-term infiltration rate and that the amount of water available is not yet known extra infiltration area is being provided. Three separate pits with bottom dimensions of 50 feet X 100 feet are proposed. This will provide an infiltration area of 15,000 square feet.

The pits will be excavated to a depth of about 5 feet to get below the second sandy loam layer noted in both test pits. This will allow the water depth to be 2.5 feet - 3.5 feet. That will increase the rate of infiltration over the test values derived with one foot of water depth. The overall safety factor for the infiltration area is well over 2.

Inflow to the system will be measured with a ramp flume and continuously recorded. The ramp flume is sized to provide 5% flow rate accuracy over a flow range of 10 cfs-50 cfs

Any outflow from the last pit will be safely returned to the White Ditch through a 12-inch pipe. The pipe will be on a slope that will keep water from flowing out of White Ditch.

Engineering Attachments:

Attachment 1A: Location Map

Attachment 1B: Site Plan

Attachment 1C: Structure Details

Attachment 1D: Structure Reinforcing Steel

Attachment 1E: Signed and Stamped Copy of Project Engineering Report

RECEIVED

JAN 3 0 2009

Attachment 2. Water Rights Statement, 690-350-0020(3)(a)(F) and (G)

Water Right Applicant:

Hudson Bay District Improvement Co.

P.O. Box 110

Milton-Freewater, Oregon 97862

Project Contact: John Zerba, WBDIC Board Member

Telephone: (541)-938-6100

Operations Contact: Jon Brough, WBDIC District Manager

Telephone: (541)-520-2856

Recharge Project Manager (WWBWC), Bob Bower, Hydrologist

Telephone: (541)-938-2170

Source of Water:

Walla Walla River, a tributary of the Colombia River, within the Umatilla River Basin.

Purpose of Use:

Artificial Groundwater Recharge using water diverted during the fall, winter, and spring freshet flows on the Walla Walla River and utilizing the HBDIC recharge structure near Milton-Freewater, Oregon.

Proposed Period of Use:

November 1 through May 15 and as Further limited below

Point of Diversion Location:

NF ¼ NW ½, Section 1, SW ¼ NF ¼ Section 12, T5N, R35E, W.M.; <u>DPV.PT. 1</u>910 Feet South and 700 Feet West from North ¼ Corner Section 1; <u>DIV. PT. 2</u> – 1030 Feet North and 900 Feet East From the Center ¼ Corner Section 12.

Minimum Instream Flow Information:

When water is diverted under this permit, the use is further limited to times when there is, at a minimum, the following streamflows in the Tum-a-lum branch (mainstem) of the Walla Walla River, between the Little Walla Walla River diversion and Nursery Bridge Dam and flowing past Nursery Bridge Dam.

Utilizing the Minimum Perennial Streamflows information (table 1, page 31) in OWRD Umatilla Basin Report (OWRD, 1988) and HBDIC's current winter water diversion permit (Permit Number 53662) the following represent the minimum instream flows at Nursery Bridge Dam:

- November 64 cfs
- December through January 95 cfs
- February through May 15 132 cfs

RECEIVED

JAN 3 0 2009

Nursery Bridge is located just downstream of Nursery Bridge and is downstream of the Little Walla Walla Diversion, the East Side Canal and the District's Canal, also described as point of diversion 1 in this application.

In order for diversion to occur under this permit, the above described streamflows must be met in the Tum-a-lum branch of the Walla Walla River, between the Little Walla Walla River diversion and Nursery Bridge Dam and following past Nursery Bridge Dam (see OWRD permit (Permit Number 53662 for operating and maintenance requirements for this station). Said streamflows shall be measured at the gauging station described below. In the event the primary gage experiences mechanical difficulties, stream flows at Nursery Bridge Dam shall be calculated by subtracting from the streamflows at Little Walla Walla Diversion (Cemetery Bridge) from those streamflows recorded at either the WWBWC gauge at Grove School Bridge or a combination of streamflows at OWRD's North and South Fork stations (#s).

RECEIVED

JAN 9 0 2009

Attachment 3. Land Use Approval, 690-350-0020(3)(a)(H)

The HBDIC recharge project staff has consulted with both the Umatilla County Planning department and the current landowner (Hulette Johnson). Attached you will find two documents addressing the anticipated land use and zoning issues needed for construction and operation of this project. The first (Attachment 3A) a Land Use Form approved by the Umatilla County Planning Department. This was originally submitted as a requirement in the funding request to the Oregon Watershed Enhancement Board. The second Attachment (Attachment 3B) was is a lease agreement between the HBDIC and the current landowner and water right holder, Hulette Johnson.

Land Use Attachments

Attachment 3A: Umatilla County Land Use Approval Attachment 3B: Lease Agreement with Landowner

RECEIVED

JAN 3 0 2009

Attachment 4. Proposed Test Program, 690-350-0020(3)(b)(A)

Introduction

The Walla Walla Basin Watershed Council (WWBWC), in cooperation with the Hudson Bay Improvement District (HBID), has proposed to test shallow aquifer recharge at a site located adjacent to the Hudson Bay Canal in section 33, T6N, R35E. At the test site a series of three infiltration pits will be built. Water will be supplied to these pits via a diversion from the canal. Recharge activities are proposed for winter and spring months when the Walla Walla River (the source of water for the canal) is at peak annual flows. The proposed shallow aquifer recharge testing will be done under an ASR Testing Limited License granted by Oregon Water Resources Department (OWRD) (OAR 690-350-0020).

Preliminary Test Site-Specific Hydrogeologic Characterization

Site-specific hydrogeologic characterization is designed to identify and define local conditions to provide a technical basis for designing the monitoring which will be used to evaluate testing. For this project a number of characterization needs are outlined in the 3 July 2003 hydrogeologic assessment letter report (Attachment 6). These needs include determining the physical properties of the geologic units underlying the test site, investigating the presence of a possible semi-confined aquifer in the upper part of the suprabasalt aquifer system, identifying aquifer hydraulic properties, and establishing suprabasalt aquifer baseline conditions, including seasonal variation, for groundwater depth, flow direction, and quality. These, and other site characterization issues, will be addressed using test site-specific hydrogeologic characterization data collected predominantly using:

- Test pits, boreholes, and wells constructed for the direct observation of `subsurface conditions
- 2. Infiltration tests (constant and falling head) designed to evaluate spatial variability at a site both laterally and vertically (note, the water source for this activity may require a temporary permit)
- 3. Aquifer testing and water level measurements to evaluate baseline aquifer physical conditions before testing
- 4. Surface and ground water quality data collected to evaluate the affect (if any) of test site operation on area groundwater quality
- 5. Well and canal records describing water use in the project area
- 6. Water flow metering at the test site that indicates surface water in-flow and out-flow during testing

At this time, geophysical investigations are not being considered because of the lack of subsurface control and ground truth data that could be used to constrain geophysical interpretations. The following sections describe proposed soils, geologic, hydrogeologic, surface water, and water quality characterization for this project.

Soil Characteristics

The HBDIC recharge project will be constructed by excavating the top 5 feet (72 inches) of soil from each of the recharge pits (See Engineering Design Report, ATTACHMENT 1). Test Pits constructed and evaluated in the Engineering Design Report provide site-specific soil profile information. Additionally, the "Soil Survey of Umatilla County Area, Oregon, (USDA, 1988) provides some general information about soil in the upper 60 inches at the project site. The two soils

15

RECEIVED

JAN 3 0 2009

present at the site are: Freewater (29A) and Cowsly (22C). As the entire soil layer will be removed during construction, it was not found useful to further characterize the specific soil properties further.

Geology

Geologic features control the physical characteristics of aquifer hosting materials, and therefore the distribution and movement of groundwater through an aquifer. Understanding the nature and occurrence of these features, both regionally and locally, provide constraints on testing, data interpretation, monitoring, mitigation, and final design. The objective of geologic characterization is to develop a three dimensional physical framework that describes the materials hosting the vadose zone and groundwater at the test site. Within this framework, or conceptual model, the nature and distribution of those factors thought to control groundwater movement and distribution will be evaluated.

Site-specific geologic characterization will be accomplished largely through the analysis of data collected during the drilling of several proposed boreholes at the site and comparison of that data to information collected during the preparation of the hydrogeologic assessment report. A minimum of three boreholes are proposed for the immediate vicinity of the test site. One of these boreholes will be located on the inferred up-gradient side of the test site, two will be located on the inferred downgradient side (Attachment 5C). As testing progresses, additional boreholes may be drilled to collect additional characterization, testing, and/or monitoring data. Subsurface hydrogeologic conditions will be interpreted via drilling cuttings and spilt-spoon sample logging.

The project hydrogeologic assessment identified work needed to complete site-specific hydrogeologic characterization. Hydrogeologic characterization targets, and the rational for them, are described below.

It is likely that the uppermost, unconfined part of the shallow aquifer system, is hosted by predominantly uncemented alluvial gravel beneath the test site. However, it is not clear from the available data how deep the alluvial gravels extend and what their properties are beneath the test site. Identifying the three-dimensional extent of these strata is critical to the proposed testing because water probably will move more rapidly through these uncemented strata, both downwards and laterally, then in the deeper, more cemented Mio-Pliocene conglomerate that comprises the majority of the shallow aquifer system in the area.

Area data indicates that, if present, the unconfined part of the shallow aquifer system at the site may be relatively thin and underlain by a semi-confined zone at depths of less than 75 feet. Characterization will identify if this semi-confined zone is actually present, and if found, the nature of the confining layer separating it from the overlying unconfined zone and the basic hydrologic properties of the semi-confined zone. Knowing the nature and extent of the confined aquifer underlying the site is critical in evaluating if the proposed recharge will affect this deeper aquifer. If data collected indicates that the project could potentially affect this deeper aquifer, monitoring will need to be designed to not only assess shallower unconfined aquifer impacts but deeper confined aquifer impacts as well.

The nature and distribution of the confining layer atop the confined aquifer should be identified in order to support evaluation of the thickness and distribution of the unconfined aquifer (if present). If the unconfined aquifer is absent, or only present seasonally, we will still need to identify the nature and extent of the confining layer because, just as it inhibits upward movement of groundwater, it will restrict the downward movement of recharge water. Knowing where the confining layer is will provide information on where recharge water may potentially collect atop this layer and where it will potentially spread to.

RECEIVED

Mapping for the assessment identified a potential depression in the top of the older Mio-Pliocene conglomerate below the western end, and west of, the test site. The depth, shape, and orientation of this feature will need to be evaluated because it will effect how the aquifer(s) underlying the test site responds to the testing. If an unconfined aquifer indeed underlies the site, this depression may act as a "reservoir" for water introduced into this aquifer. Alternatively, it may serve as a recharge pathway, hydrologically connecting the upper, unconfined part of the suprabasalt aquifer system with deeper, confined parts of the aquifer system.

Hydrogeology

Piezometers and/or observation wells will be constructed in the borings drilled for geologic characterization. If additional geologic characterization boreholes are drilled (either close to or more distal from the test site) one or more of these also may be converted to observation wells. All but one of the boreholes converted to monitoring wells will be completed as 2-inch observation wells that fully penetrate the unconfined aquifer (if present) or above the confining layer (if unconfined aquifer not present). At least one of the geologic characterization boreholes should be of sufficient size to accommodate a 4-inch diameter well which will be used for aquifer testing.

Test site-specific hydrogeologic work would be done, in large part, concurrently with the site-specific geology work. The hydrogeologic assessment concluded that the following information must be collected for the uppermost part of the suprabasalt system at the test site:

- 1. Depth, thickness, and lateral and vertical extent of the vadose zone and the uppermost aquifer(s) underlying a site.
- 2. Nature and effect of perching layers (if any) in the vadose zone.
- 3. Aquifer and vadose zone physical and hydrologic properties including, grain size, matrix content, induration, hydraulic conductivity, transmissivity, and porosity
- 4. Groundwater flow direction and velocity, including both spatial and temporal variation
- 5. Anthropomorphic effects, primarily changes in groundwater pumping, surface water (including canals), and irrigation activities.

For characterization it is important to build monitoring (or observation) wells in such a way as to provide means for accurately measuring the target aquifer. Well construction considerations are listed below:

- 1. Most project observation wells will probably be 2 inch-diameter piezometer type installations. These should be built to ensure that they are monitoring the anticipated aquifer targets, and we recommend building to well construction standards and avoiding cost cutting measures designed to get more/cheaper wells (these commonly result in poorly built wells unsuitable for collection of the high quality data we feel is necessary to support the project).
- 2. For aquifer testing, a 4 inch-diameter observation well is the minimum recommended diameter and at least one such well should be built.
- 3. The minimum number of observation wells at the test site is 3, one up-gradient and 2 downgradient. If funding can be procured we recommend that more than 3 observation wells be installed. Most, if not all, of these additional observation wells could be built in geotechnical borings drilled for geologic characterization.

 RECEIVED

JAN 3 0 2009

In addition to the observation wells built near the test site, it seems likely that observation wells will eventually need to be built more distant from the site. The purpose of these observation wells would be to more accurately trace the down gradient migration of recharge water away from the test site. A minimum of 3 more distant observation wells, 1 up-gradient and 2 down-gradient is again recommended. These might include at least some previously built groundwater supply wells that would be available for use. However, these should only be used if construction details can be verified and if they are not being used as water supply wells. Access to offsite observation well drilling locations will need to be acquired from willing landowners. The WWBWC currently has a network of existing wells that could be used for the purpose of tracking the recharge water distally from the site.

Aquifer testing designed to collect aquifer hydraulic property data will be part of site characterization. During aquifer testing, the 2-inch observation wells will be monitored to observe the effects of testing on the surrounding aquifer. Aquifer testing would include an 8-hour step-drawdown test to establish probable sustainable yields in the suprabasalt aquifer, followed by a 24 to 72 hour constant discharge test. Water level data collected during aquifer testing will be analyzed using standard analysis techniques.

Combining the interpretations developed in the completed hydrogeologic assessment with the drilling and testing data collected during site-specific characterization, a conceptual model of test site hydrogeologic conditions will be prepared.

Surface Water

One of the main objectives of the project is to increase surface water quantity (base flow) and improve its quality (temperature). To document that, surface water bodies that the project may influence need to be identified and monitoring points on them established and characterized (includes collection of baseline data). These locations will be used as monitoring locations during subsequent testing.

The hydrogeologic assessment identified three, down gradient, spring-feed streams, Goodman Spring Branch, Johnson Creek, and Dugger Creek, which are most likely to be affected by recharging the shallow aquifer. During test-site specific characterization these streams will be examined and monitoring points identified. At these points stream conditions will be photographed and stream conditions documented prior to the initiation of testing that will include the following parameters:

Flow volume and discharge

Water temperature

Water quality (temperature)

Hydrophilic plants and habitat quality

RECEIVED

JAN 3 0 2009

WATER RESOURCES DEPT SALEM, OREGON

Sampling frequency will be designed to collect enough data to demonstrate the range of conditions likely at the monitoring points so that site background conditions can be documented enough to provide an adequate baseline to measure test results against.

Water Quality

Both surface and groundwater quality at the test site, and at likely down-gradient discharge points, needs to be documented. There are several reasons for this, including:

- We do not want to introduce contaminated water into the shallow aquifer via recharge
 activities and violate antidegradation rules. We need to establish background water quality
 parameter concentrations and monitor source-water quality periodically during testing and
 operations.
- 2. Certain source-water conditions (e.g., turbidity) have the potential to degrade or even "plug" the recharge system. From an operational standpoint, one would monitor for those conditions and halt test operations when the source-water exceeded those conditions.
- 3. Up-gradient groundwater quality needs to be monitored so that the effects of recharge on water quality can be differentiated from those water quality conditions caused by recharge activities, including leaching of vadose zone constituents by recharge water.

Sampling Quality Assurance and Quality Control (QA/QC) protocols will need to be established and followed for characterization and later monitoring. QA/QC for the project, which is described in Attachment 5, includes:

- Sampling equipment
- Measurement techniques for field parameters
- Decontamination procedures
- Well purging guidance for groundwater samples
- Sampling methods
- Chain of custody and sample handling procedures
- Record keeping
- QA/QC guidelines

RECEIVED

JAN 3 0 2009

WATER RESOURCES DEPT SALEM, OREGON

Characterization Conclusions

With the completion of site-specific characterization, updated monitoring and test plans will be prepared if necessary. These monitoring and test plans will be based on the results of the characterization effort which includes the generation of a site conceptual groundwater flow model that describes probable aquifer conditions, suprabasalt aquifer water level(s) and groundwater flow direction(s) (including seasonal variations), and discharge points for recharge water.

Preliminary Test Site Operation Plan

The objective of proposed artificial groundwater recharge testing to be done under the limited license is to evaluate the feasibility of restoring diminished shallow aquifer water levels and increasing decreased spring creek flows using infiltration pits and winter high flow water diverted from the Walla Walla River to these pits. Testing will be done over five years. If testing indicates shallow aquifer recharge and spring creek flow restoration is feasible using infiltration, test results will be used to design and implement larger scale artificial groundwater recharge at this, and potentially other sites in the area. Testing will not include removal of stored water by pumping or other artificial means.

This preliminary test plan describes how the test site will be operated during testing. Elements included in the preliminary test plan include: (1) site construction, (2) test operations, (3) mitigation activities, and (4) reporting. The preliminary test plan may be modified as testing proceeds.

Site Construction

The basic layout of the test site is shown on Figure 1. The site, located adjacent to the Hudson Bay Canal, will consist of three infiltration pits excavated approximately 3 feet into Quaternary alluvial gravel which immediately underlies the test site (Attachment 6). Water will be delivered to the pits via a diversion structure in the canal. Any water that does not infiltrate into the ground from these pits will be returned to the canal via a return ditch or pipe.

More detailed site construction information describing: (1) test site survey and layout (2) specifications for pits/basins/pits used for infiltration (3) water supply design (including diversion from canals if appropriate) (4) monitoring points (both on and off site) and (5) site access controls (fences, etc.) are described in detail in Attachment 1, (1A-1E), Engineering Design.

Test Operations

Test operations describe how the site will be used during testing and possible reasons for changing the test as new data and information is collected during the test. Test operations include:

- 1. Test timing, including timing of recharge and monitoring frequencies
- Quantities of water used
- 3. Outside influences that effect test, including weather (probably freezing), elevated river turbidity, river flooding, trip wires for identifying potential offsite impacts before they occur so they can be mitigated and or testing suspended to prevent worsening conditions
- Responsible parties for diversion and delivery of water, operation of test, monitoring, and data review

 RECEIVED
- 5. Permissions required to access offsite monitoring points

JAN 3 0 2009

These are discussed further in the following paragraphs.

WATER RESOURCES DEPT SALEM, OREGON

Test Timing, Monitoring, and Water Quantities

Testing is tentatively planned to begin in the winter of 2003/2004 and continue for 5 years. Test operation will generally be conducted in the winter when Walla Walla River flows are at their highest and irrigation activities are at their lowest. A maximum of approximately 50 cfs will be delivered to the test site during normal operation. However, in the event minimum Walla Walla River flows are not meet, water will not be diverted from the river for test site use. Depending on stream flows in any given year, recharge water may be delivered as early as December to as late as March/April. In addition, in the event of prolonged freezing weather, test site operation may be temporally suspended to avoid ice damage to the canal diversion on the Walla Walla River, the canal system itself, and/or the recharge pits and related structures.

Water quantities delivered to the test site will be monitored via a gauge at the diversion from the canal into the test site. The return canal from the test site back into the canal will also be monitored to determine the quantity of water that leaves the test site (if any) because it did not infiltrate into the ground. Based on this monitoring data, and estimated evaporation loses that could occur during operation; water quantities discharged to the ground will be calculated.

Groundwater levels in the immediate vicinity of the test site will be monitored before, during, and following recharge test events via three (at a minimum) observation wells constructed during characterization, potentially via existing water wells in the area if any can be found that can be used for shallow aquifer water level monitoring, and potentially with new observation wells built as the test progresses. During the recharge test event, tentatively scheduled for the winter/spring of 2003/2004 water levels will be measured as follows:

- 1. Throughout the calendar year water levels will be measured at least weekly, beginning with the granting of the limited license.
- 2. In the month prior to the anticipated start of recharge activity and in the month following the termination of recharge, water levels will be measured daily.
- 3. During recharge water levels will be measured daily, at a minimum.

Based on preliminary engineering design studies (Attachment 1) and the hydrogeologic assessment (Attachment 6) most, if not all, of the water delivered to the test site will probably infiltrate into the ground. However, because this project is a test project, the current plan is to initially operate the test site at approximately half capacity. The quantity of water discharged to the site will than be increased or decreased as experience and observations dictate. Final operating quantities will determined based on test results.

Water quality data will also be collected before, during, and following recharge events. Parameters to be collected, sampling timing, and other water quality monitoring information are presented in the Monitoring Plan (Attachment 5).

Outside Influences

The primary currently identified outside influences on testing are Walla Walla River flow levels, freezing conditions, source water turbidity levels, and increased groundwater water levels resulting from testing that impact surface activities and conditions. The likely effects of these on testing, and possible mitigation actions to be implemented during testing, are as follows:

Low flows in the Walla Walla River will impact testing because the use of Walla Walla River water for recharge will be conditional, based on river flows exceeding a certain threshold. When flows do not, water will not be delivered to the test site and testing will not occur.

High Walla River flows may also effect testing. In the event of high flow during a flood or rapid snow melt event, turbidity will generally increase. The repeated delivery of turbid water to the test site infiltration pits may eventually lead to plugging of pore space and reduced infiltration capacity. To mitigate against this, delivery of recharge water may be terminated or scaled back during high flow events. Alternatively, the pits may be periodically re-excavated to remove these fines. The preferred mitigation strategy for dealing with this will be based on monitoring and performance data collected during testing.

The effects of freezing on the test are outlined earlier in this Attachment and repeated here. In the event of prolonged freezing weather, test site operation may be temporally suspended to avoid ice damage to the canal diversion on the Walla Walla River, the canal system itself, and/or the recharge pits and related structures and to avoid the risk of ice jams forming in the canal, backing up water in the canal, and causing flooding adjacent to the canal.

It is possible that recharge testing could cause groundwater levels to reach the ground surface at locations where human activity and habitat is negatively impacted. One of the main purposes of

RECEIVED

10 N 2 0 2009

groundwater level monitoring is to identify increasing water levels in the test site area in order to: (1) directly observe the effects of recharge on water levels (2) use these observations (in conjunction with characterization data) to evaluate whether or not recharge is having an impact on groundwater levels that could lead to surface problems, and (3) identify when and where this type of problem may occur. If water level monitoring data suggest increased groundwater levels are approaching the ground surface and that flooding of low lying areas seems possible, the quantity of recharge test water being delivered to the infiltration pits will be reduced or, if necessary, terminated.

Responsible Parties and Access Permission

The test will be managed primarily by the Hudson Bay District Irrigation Company, lead by John Brough, Operations Manager, and the Walla Walla Basin Watershed Council (WWBWC) technical staff, lead by Mr. Bob Bower, Hydrologist. HBDIC and WWBWC staff (or a subcontractor working for the HBDIC and WWBWC) will compile monitoring and testing data, prepare reports as necessary to meet license requirements, and in consultation with Hudson Bay Irrigation District (HBDIC) staff make decisions regarding timing and quantity of water delivered to the site and when to suspend recharge activities. Submittal of all monitoring reports to OWRD will be the responsibility of HBDIC and WWBWC staff. The HBDIC and WWBWC may choose to subcontract report preparation and delivery to a subcontractor.

HBDIC staff will be responsible for operating all facilities associated with removing recharge test water from the Walla Walla River and delivering it to the test site, including operation of the diversion structure which routes water from the canal into the pits. HBDIC staff also will maintain all equipment associated with water delivery and pit operation, including reexcavation of the pits, if necessary.

Mitigation

As stated above, one of the objectives of monitoring is to identify likely unintended consequences of recharge testing before they occur. When the precursors to these consequences, such as changing water quality detrimental to aquatic habitat or groundwater levels rising to close to the surface in areas where shallow groundwater is not desired, can be detected soon enough via monitoring, recharge activities will be modified and/or terminated to mitigate against these effects.

Reporting

Data and observations collected during testing, including monitoring data, will be compiled into reports. The basic objective of these reports will be to describe what was done during the test, what was observed at the monitoring points, interpret the data collected, and recommend changes to testing, monitoring, and mitigation plans. These reports will be produced annually. Based on the proposed recharge schedule, annual reports will be submitted to OWRD in the summer following each winter recharge test.

More frequent reporting will be done when monitoring reveals the presence of an undesired effect from testing. If monitoring reveals that undesired consequences of testing are likely to occur, WWBWC staff (or designated representative) will report the monitoring information to OWRD staff.

At the conclusion of the 5-year recharge testing done under the limited license a final report will be prepared. The final reports will describes the project, data colleted during testing and monitoring, interpretations of how well the recharge project worked in achieving project goals, and recommendations for future operations. The final report will be submitted to OWRD in the summer following the fifth annual winter recharge event.

JAN 3 0 2009
WATER RESOURCES DEPT
SALEM, OREGON

Attachment 5, Proposed Monitoring Program, 690-350-0020(3)(b)(A)

Overview of Basin Wide Monitoring Plan

In 2003, the WWBWC expanded its watershed monitoring strategy to include collecting basin line information for the numerous spring-creeks and district ditches spread out across the Walla Walla River valley (Oregon). Starting in June 2003, many new flow stations (15-minute stage and temperature recorders) were installed at or near the sources of nearly all the springs in the Oregon portion of the system (Figure 2). The WWBWC monitoring program has a total of 28 continuous flow stations with additional 15 continuous static well recorders with many more manual measurement locations. The objectives of this monitoring (specifically for the spring-creek and shallow aquifer system) is to accomplish the following:

- 1. Be able to discern between Walla Walla River Water (coming from districts water rights and use) and spring waters (emerging strictly from the shallow aquifer). It is understood that the application of irrigation water will undoubtedly show up as spring returns, but this monitoring is intended as a beginning to understanding this complicated system.
- 2. Collect baseline information on spring flow as it relates to seasonal and yearly fluctuations.
- 3. Many of the spring-creek monitoring stations were sited based on the presence of historical data collected by Piper (USGS, 1933). Where Piper had collected spring-creek flow, we attempted to locate our gauges as near as possible to his historic data sites. The intention is to allow us the ability to compare and contrast historical and current spring-creek conditions based on a significant period of time. Most of these Piper's original sites were located upstream of any irrigation with draws, making them key locations for us in this type of comparison.
- 4. Monitor water table levels continuously for daily, seasonal and yearly fluctuations and timing. Some of the wells being recorded have periods of record dating back to the 1930s, allowing us some opportunity to understand any long-term changes in the aquifer system.

Recharge Project Monitoring Plan

The proposed ground water recharge project exists inside this larger monitoring network and it is expected that this will help provide useful information in testing of the proposed testing (see below). Some of the sites shown in this larger network were specifically located to provide proximal and distal pre-construction and operation information for this project (Figure 2). Site specific monitoring includes observation wells and surface monitoring stations (Attachment 5B).

Monitoring for the site-specific proposed testing is designed to meet four basic objectives. These are to identify: (1) changes in the natural system caused by factors other than those related to testing, (2) changes in the natural system caused by the testing (track the test performance), (3) potential problems caused by the testing that may require modification or termination of the test and/or mitigation actions, and (4) events that effect test operations, such as a freezing or a flooding. To meet these objectives, monitoring will track:

- 1. Source water quality and volume coming onto the test site
- 2. Up-gradient groundwater water quality
- 3. Up-gradient groundwater level changes to provide the information needed to differentiate recharge test effects from other, natural and artificial, effects on the groundwater levels beneath test site

RECEIVED

JAN 3 0 2009

- 4. Down-gradient groundwater quality and levels, both near and distal to the test site
- 5. Surface water discharge and quality changes

Four basic types of monitoring points are planned for this project:

- 1. Source water
- 2. Test site groundwater
- 3. Distal groundwater
- 4. Surface water (e.g., springs).

RECEIVED

JAN 3 0 2009

WATER RESOURCES DEPT SALEM, OREGON

Monitoring data collected at these points during testing will be evaluated against what is known about pre-test conditions to identify testing effects on the surrounding environment, differentiate those effects from others in the environment, and identify when changes in test operations appear necessary. Pre-test conditions will be determined during the planned site-specific characterization activities described in Attachment 4 and are partially described in the preliminary hydrogeologic assessment (Attachment 6).

This preliminary monitoring plan discusses monitoring activities to be undertaken at the four types of monitoring points and sampling and QA/QC protocols.

Sampling and Analysis Program

The groundwater-monitoring program proposed for the test project is outlined in the following sections. Annual reporting is proposed and a Water Quality Analysis Report will be prepared following five years of testing.

As stated in the introduction, four types of monitoring are proposed: (1) source water at the test site (2) site-specific groundwater (3) distal groundwater and (4) surface water (springs).

(1) Source Water at Test Site

Source water monitoring will be at the point of diversion onto the test site. Monitoring will include both water quantity and quality. The volume of water delivered to the test site will be monitored via a gauge at the diversion. Water quality samples will be collected at the gauge.

Proposed monitoring frequency is as follows:

Gauge data will be recorded 15-minute readings via a continuous recording data logger. Rating measurements and tables will be generated for each surface flow site and continuously checked for shifts.

Three source water quality-sampling events are proposed for each yearly seasonal recharge period. They are proposed for approximately: (1) one month prior to the projected beginning of the recharge period (2) during the mid part of the recharge period and (3) approximately one month following the end of the recharge period. The exact timing of these will be based on predicted Walla Walla River flows and may vary from year-to-year. OWRD and ODEQ staff will be notified by WWBWC staff of pending sampling events at least two weeks prior to each sampling event.

The results of source water quality monitoring will be used to determine if modifications to test operations are warranted. During testing different sampling frequencies may be tried to identify those that are most effective.

(2) Site Groundwater

Site groundwater monitoring, consisting of the collection of water quality and water level data, will be conducted at the three observations wells built during characterization. The purpose of site groundwater monitoring is to establish water quantity and quality impacts from testing to groundwater in the immediate vicinity of the site. In addition, up-gradient monitoring will be used to differentiate test impacts from those caused by other activities not controlled by the testing.

Proposed monitoring frequency is as follows:

Water levels will be measured weekly throughout the year when recharge testing is not underway.

In the month prior to, during, and the month following the yearly seasonal recharge period, water levels will be collected daily (at a minimum) for the first year of testing. Measurement frequency during subsequent years will be based on previous observations and proposed in annual reports.

Three groundwater quality sampling events are proposed for each yearly seasonal recharge period. They are proposed for approximately: (1) one month prior to the projected beginning of the recharge period (2) during the mid part of the recharge period and (3) approximately one month following the end of the recharge period. The exact timing of these will be based on predicted Walla Walla River flows and may vary from year-to-year. OWRD and ODEQ staff will be notified by WWBWC staff of pending sampling events at least two weeks prior to each sampling event.

The proposed locations of site-specific groundwater observation wells are shown on Figure 1. The results of groundwater quality and level monitoring will be used to determine if modifications to test operations are warranted. During testing different sampling frequencies may be tried to identify those that are most effective.

(3) Distal Groundwater

Distal groundwater monitoring, consisting of the collection of water quality and water level data, will be conducted at observation wells more distal from the test site than the site observation wells. Initially, during the first year of recharge testing, these wells will probably be previously constructed water supply wells that can be used by WWBWC staff and can be shown to be open to only the shallow aquifer. If funding for new wells can be procured for subsequent years, dedicated distal groundwater observations wells may be built to improve the monitoring coverage.

A minimum of 3 distal observation wells will be used, 1 up-gradient and 2 well down-gradient. The locations of these will be determined during site specific characterization currently planned for the winter of 2003. Monitoring frequency is the same as proposed for site-specific groundwater monitoring. Figure 5B shows the approximate site locations for the site-specific observation wells.

Distal monitoring will be used to identify longer term quantity impacts from testing. This includes the formation and migration of a groundwater mound and recharge water plume at, and away from, the test site, towards intended and unintended receptors. Up-gradient monitoring will be a part of this so that testing effects can be differentiated from offsite events. Sampling frequency will be determined from characterization data and modified as more is learned during testing.

RECEIVED

JAN 3 0 2009

(4) Surface Water (Springs)

The WWBWC is currently monitoring most of the surface springs, creeks and rivers of Oregon's lower Walla Walla River basin (See Figure 2.) While this project will specifically Surface water monitoring in Dugger, Johnson and Goodman Spring-Creeks will be done to identify the effects of recharge on flow. This monitoring will include the collection of both water quality (specifically temperature), flow and habitat improvements (photo-documentation). As with groundwater monitoring, surface water monitoring will need up-gradient and pre-project condition monitoring information so that effects unrelated to test site operations/testing can be differentiated from those due to testing. Pre-project surface flow monitoring was started during the 2003 summer irrigation season at Dugger and Johnson Spring-Creeks in the form of a continuous.

Sampling Parameters

Sampling methods are specified in the following sections. The chemical monitoring parameters are to be conducted on a two-tiered system. Level 1 monitoring will be conducted during all three water quality-monitoring events (each recharge period). Consistently elevated concentrations of nitrate will be initiate the level 2 chemical analysis. Samples will be tested for chemicals in the level 2 list. Operation of the recharge project will depend on the absence/presence of the chemical parameters on this list. ATTACHMENT 5B describes the specific method and documents used to determine the level 1 and 2 chemical parameters (pesticides, herbicides, insecticides, fungicides, etc.) listed below.

Monitoring is proposed for the following parameters:

Physical Parameters (all monitoring types)

Static water level (in observation and WWBWC network well)

Standard field parameters, including pH, turbidity, electrical conductance, and temperature

Flow (in cubic feet per second)

Chemical Parameters -Level 1 (On-site monitoring only)

Total nitrogen as nitrate (screening parameter for Level 2 Chemical screening)

TKN

Total dissolved solids

Chemical oxygen demand

Chloride

Orthophosphate

Fecal Coliforms (Presence/absence only)

Chemical Parameters -Level 2 (On-site monitoring only)

Rubigan (Fenarimol)

Ridomil (Metalxyl)

RECEIVED

JAN 3 0 2009

Systhane/Rally (Myclobutanil)

Devrinol (Napropamide)

DDD-DDE-DDT

Elgetol (DNOC sodium salt)

Alar/B-Nine (Daminozide)

Lindane (Lindane)

Sampling dates will be coordinated for all monitoring points used in the project.

This list of analytes was selected to optimize routine sampling to address constituents commonly of concern (nutrients and salt) and provide prompt indication of potential impacts by analyzing for anions (nitrate and chloride) that are known as groundwater tracers (DEQ, 1995). Additional parameters will be proposed for future sampling if the results of the initial proposed sampling indicate this is necessary.

Sampling Procedure

Equipment and sampling procedures proposed for recharge test monitoring are provided in the following sections.

Equipment

This section lists the equipment for groundwater monitoring. Submersible pump (Grundfos or similar) or dedicated bailers/sampling line

Temperature measuring instrument (Vemco data logger)

pH and conductivity meter(s) with calibration reagents

Water level and flow meters (Tru-traks, In-situ Mini-trolls, Stevens 420 loggers, 0.01 foot resolution required)

Shipping cooler with ice packs or ice

Five-gallon pail marked at the 5-gallon level, stopwatch

Laboratory supplied sample containers with appropriate preservatives

Tap water, deionized water, phosphate-free soap, cleaning brushes, field note book, log sheets

Water Level

An electronic water level meter will be used to measure the depth to groundwater in each observation well to the nearest 0.01 foot. Static water levels must be measured at the indicated reference point prior to purging any water from the well. The reference points will be on the top of the observation well casings. The static water levels in all wells should be measured on the same day for each site. Coordination with quarterly sampling of other wells in the vicinity should be attempted. Accumulation of sediment in the well should also be checked by lowering a weighted tape to the bottom of the well, reading the depth at the well casing's reference point, and comparing this value to the as-built well depth.

RECEIVED

JAN 3 0 2009

Decontamination

All non-disposable field equipment that may potentially come in contact with any soil or water sample shall be decontaminated in order to minimize the potential for cross-contamination between sampling locations. Thorough decontamination of all sampling equipment shall be conducted prior to each sampling event. In addition, the sampling technician shall decontaminate all equipment in the field as required to prevent cross-contamination of samples collected in the field. The procedures described in this section are specifically for field decontamination of sampling equipment. At a minimum, field-sampling equipment should be decontaminated following these procedures:

- 1. Wash the equipment in a solution of non-phosphate detergent (Liquinox® or equivalent) and distilled/deionized water. All surfaces that may come in direct contact with the samples shall be washed. Use a clean Nalgene and/or plastic tub to contain the wash solution and a scrub brush to mechanically remove loose particles. Wear clean latex or plastic gloves during all washing and rinsing operations.
- 2. Rinse twice with distilled/deionized water.

JAN 3 0 2009

3. Dry the equipment before use, to the extent practicable.

WATER RESOURCES DEPT SALEM, OREGON

Purging and Field Parameters (On site wells only)

Sufficient water will be purged to ensure that the sample collected represents water from the geological formation. Borehole volumes are calculated as the volume of water in the casing and the volume of water in the filter pack.

During purging, measure pH, temperature, and electrical conductivity of the water removed. At a minimum, these parameters are measured at the start of purging and after each successive borehole volume is removed. Temperature should be measured first because it changes most rapidly. Purging continues until at least three borehole volumes have been purged and the field parameters are established to within \pm 10 percent over three consecutive measurements. At this point, the observation well is considered adequately purged and can be sampled.

Occasionally, observation wells installed in low permeability formations may be purged nearly dry (within 6 inches of bottom of well) prior to stabilization of groundwater parameters and prior to purging at least three borehole volumes. If this happens at least one set (more if possible) of purge water groundwater parameters (pH, temperature, EC) need to be measured. Sample collection can be done after the water level has recovered at least 75 percent of the drawdown ensuring most of the well water is from the formation. Prior to groundwater sample collection several measurements are required as explained above. These include static water level and total depth, pH, temperature, and electrical conductivity.

All field instruments should be calibrated each day prior to sample collection. Instrument calibration and maintenance should precisely follow the manufacturers recommended procedures. Electrical conductivity and pH standards used to calibrate the instruments should be within the range encountered at the monitoring sites. Calibration records should be recorded on the sample collection forms.

Water Sampling

Samples will be collected after sufficient water has been purged according to the procedure described above. Samples will be collected from the discharge end of the pump hose after the flow rate has been reduced to less than approximately 0.2 gallons per minute. Discharge from a bailer should be controlled to minimize agitation and aeration. Sample containers should be sealed with tape, labeled, and immediately placed in a cooler with ice. Sample containers should be filled completely to eliminate head space. Sample containers should be provided by the analytical laboratory and should be requested at least one week in advance of the sampling. The containers should be appropriate for

the parameters analyzed and all shipping coolers should have chain-of-custody seals placed on them prior to shipping.

One additional sample should be collected from one of the sample points for quality control purposes. This sample should be evaluated as a "blind duplicate."

Sample Preservation and Holding Time. Samples should be stored immediately after collection in an ice chest containing sufficient ice to cool the samples to 4 degrees Celsius (°C). Use "blue ice" if possible. If water ice must be used, the ice should be sealed in plastic bags, as should the sample bottles. Samples should remain cooled at 4°C and delivered to the laboratory within 24 hours of collection. Sample receipt at the laboratory must be sooner if analysis includes parameters with a shorter holding time. Care should be taken to prevent excessive agitation of samples or breakage/leakage of containers. Samples should be analyzed within the specified holding time for each constituent.

Resampling

In accordance with OAR 340-40-030(5), resampling is done if monitoring indicates a significant increase (or decrease for pH) in the concentration of a monitored parameter at a sampling point. Determining if a significant increase in parameter concentration has occurred is customarily done either by assessing concentrations in relation to established concentration limits or by using a statistical analysis. Since background or baseline conditions have yet to be established for the test site a concentration limit has not been set and insufficient data exists upon which to base a statistical analysis. The criteria to guide resampling decisions will be reevaluated is subsequent test project annual reports.

Chain of Custody and Sample Handling

A chain-of-custody form should be completed and signed by the sampler on the day samples are collected. The chain-of-custody form must be signed by laboratory personnel upon receipt and any other individuals that maintain custody of the samples in the interim. Coolers should be sealed and shipped or driven to the lab as soon as possible. The method of shipping (bus, next day air, etc.) is usually determined by the parameter having the shortest holding time. In any case, shipping times of more than 24 hours should not be used as the cooler(s) may warm and compromise sample quality.

Field Records and Data Validation

All field notes, analytical results, and other pertinent data associated with the project should be maintained in a secure location and be archived for at least a five-year period. Data validation for both field and lab Quality Assurance and Quality Control (QA/QC) will be performed using a checklist. All pertinent information with respect to QA/QC will be checked. The following items are included on the QA/QC review checklist:

- 1. Field data sheets (or notebooks) and observations (observations are used to check for potentially erroneous data) will be reviewed to make sure they are completely filled out.
- 2. Chain-of-custody forms will be completed, being signed by all sample handlers.
- 3. Holding times for all constituents will be met.
- 4. Field blind duplicate results will be evaluated to make sure they are compatible.
- 5. Laboratory method blanks, matrix spike, matrix spike duplicates, and surrogate percent recovery data supplied by the analytical laboratory will be evaluated to make sure they are compatible.

RECEIVED

JAN 3 0 2009

Data Reporting and Statistical Analysis

The following procedures for reporting analysis are proposed for this project.

Record Keeping

All field notes, laboratory results, critical calculations, and published reports will be maintained at the WWBWC office for a period of five years following completion of the final testing and monitoring report. If possible, both paper and electronic copies will be maintained.

Evaluation

Monitoring data and observations should be evaluated when they are received from the sampler and laboratory.

Materials to be received include:

Field monitoring and sample collection records

Original laboratory reporting sheets

Data evaluation will include:

- 1. Verification of analytical methods and detection limits, along with the date the analysis was performed
- 2. Review of document handling, sampling and analytical problems, and actions taken to correct any problems
- 3. Summarizing water level data in tabular and/or graphical form
- 4. Summarizing water quality analytical results in tabular form and/or graphical form
- 5. Performing data validation checks, as appropriate to the data set
- 6. Identifying any significant increases in parameter concentrations (will be done later in project only after enough data has been collected to warrant)

Annual Review and Reporting

All monitoring activities performed during the previous monitoring year will be included in an annual report to be submitted to OWRD during the summer following the preceding seasonal recharge period. The annual report will present the following information:

Water quality data, including duplicate sample results in tabular form and time-series plots for specific parameters

Water level data, including hydrographs showing water level changes over time

Basic statistical parameters for each parameter of interest: mean, median, maximum, minimum, standard deviation, number of data points, and number of non-detects

Evaluation of all field and laboratory data, including observed changes and groundwater flow direction and gradient

Discussion and conclusions, including recommended changes to recharge testing

RECEIVED

JAN 3 0 2009

The methods needed to evaluate water quality and water level data will depend on the objectives of the evaluation. In general, the principal objective is to evaluate whether or not recharge tests have affected groundwater levels and quality. Evaluation methods include: a comparison of water quality data with a concentration limit or with background water quality; comparison of water quality over time; or comparison of water quality between up-gradient and down-gradient wells. For the test site, insufficient data are available for a statistical analysis to be performed because concentration limits have not yet been established. Until that time, evaluation of dataset trends will be solely qualitative, but revisited in each annual report until a database has been compiled that is sufficient for statistical analysis.

Final Recharge Test Project Report

At the conclusion of five years of recharge testing under the limited license a final report will be prepared. The report will contain the data collected for the test project; analysis and interpretation of that data (including statistical analysis as appropriate), and a recommendation for proposed future artificial groundwater recharge activities at the test site. The report will be complete enough to serve as supplemental material to a permanent artificial groundwater recharge permit under OAR 690-350-0110, if such a permit is sought following completion of the test project.

Monitoring Plan Attachments

Attachment 5A. Methodology Water Quality Assessment and Evaluation Attachment 5B. Figure 5A Map of On-site Recharge Well Locations Attachment 5C Chemicals of interest for Hudson Bay Recharge Project

RECEIVED

JAN 3 0 2009

Attachment 6. Site Hydrogeology, 690-350-0020(3)(b)(C), (E), and (G) (attached)

Attachment 7. Source Water Quality, 690-350-0020(3)(b)(D)

Overview

This project will utilize winter-spring flow from the Walla Walla River as the *source* water for recharge during the project operation. The time period that Walla Walla River water will be used is November 15th through May 15th. A review of existing reports and data was conducted to identify any areas of concern regarding source water quality for the recharge project. What little information that exists for source water quality conditions is discussed below.

In 2003, the WWBWC tracked turbidity levels through a winter storm event (1/27/3 through 2/3/3) and found turbidity levels to be a potential issue on the Walla Walla River (mainstem) during peak flow events (WWBWC, Unpublished data). Turbidity could be problematic for project operations, as it may act to decrease the rate of infiltration by plugging and layering the bottom of the recharge pits. Turbidity may also be a preliminary screen for fecal contamination issues, as bacteria may use the large particles as a vector for mobilization.

The other known source water quality information was obtained from the Environmental Protection Agencies STORET database. STORET provided some historical water quality data that showed several parameters (circa 1960s) that were accounted for in the recharge project's monitoring plan (ATTACHMENT 5). STORET data that was collected nearest to the source water POD at the Little Walla Diversion (NE ½ NW ¼, Section 1, SW ¼ NE ¼ Section 12, T5N, R35E, W.M.; DIV.PT. 1) is attached in table form as ATTACHMENT 7A.

From the review of all known source water information, the parameters that appeared to be of concern are:

- 1. Fecal Coliforms
- 2. Turbidity

There was no other relevant information found for source water quality conditions. The monitoring plan covers the establishment of source water quality conditions during operation of the recharge facility. This will insure safe water quality conditions for the recharge project.

Attachment 7A Source Water Quality Information

JAN 3 0 2009
WATER RESOURCES DEPT SALEM, OREGON

Limited License Supplemental Application Materials 10/16/03

Resources and References:


- Cooperative Extension Washington State University. 2002. 2002 Crop Protection Guide for Tree Fruits in Washington. Washington State University EB0419.
- Darnell, T., Topielec, R. 1996, October. Nitrates and Bacteria in Groundwater: A Second Look, Milton-Freewater Area, Umatilla County, Oregon. Oregon State University Extension Service Water Quality Program.
- Darnell, T. Hart, J. Vomocil, Jim. 1989. Nitrates and Bacteria in Groundwater: Milton-Freewater, Umatilla County Oregon. Oregon State University Extension Service.
- Darnell, T., Montgomery, M. L., Witt, J. M., 1989, July. Pesticides in Groundwater: Milton-Freewater, Umatilla County, Oregon. Oregon State University
- EPA STORET Water Quality Database information (http://www.epa.gov/storet/)
- Jenkins, J. J., Thomson P. A., 1999, January. OSU Extension Pesticide Properties Database. . Oregon State University Extension EM 8709
- Kerle, E.A., Vogue, P. A., Jenkins, J. J., 1996, October. Understanding pesticide persistence and mobility for groundwater and surface water protection. Oregon State University Extension EM 86561
- MacNish, R.D. and R.A. Barker. Digital model of the gravel aquifer, Walla Walla Basin. United States Geological Survey, 1976.
- MacNish, R.D. and R.A. Barker. Digital simulation of a basalt aquifer system, Walla Walla River. Water Supply Bulletin #44. Washington Department of Ecology, 1976.
- Newcomb, R.C. Geology and Groundwater Resources of the Walla Walla River Basin. Water Supply Bulletin #21. Washington Department of Conservation, Division of Water Resources, 1965.
- Oregon Water Resources Department. Umatilla Basin Report. 1988. Government Printing Office 774-398/20006 Region NO. 8
- Piper, A.M., T.W. Robinson, and H.E. Thomas. Groundwater in the Walla Walla Basin, OR-WA-Part I. Department of the Interior, United States Geological Survey, 1933.
- Piper, A.M., T.W. Robinson, and H.E. Thomas. *Groundwater in the Walla Walla Basin*, OR-WA-Part II. Department of the Interior, United States Geological Survey, 1933.v
- Richerson, P., Cole, D. 2000, June April 1999 Milton-Freewater Groundwater Quality Study: As part of the Statewide Groundwater Monitoring Program. State of Oregon Department of Environmental Quality
- U.S. Department of Agriculture (USDA), Soil Conservation Service. Nov, 1988. Soil Survey of Umatilla County Area, Oregon. WWBWC technical library
- U.S. Geological Survey 1996, July. Fact Sheet 171-96: <u>Article: The Nitrate Connection.</u> US

 Government Printing Office 774-398/20006 Region NO. 8


 RECEIVED


JAN 3 0 2009

Attachments



.







JAN 3 0 2009

WATER RESOURCES DEPT SALEM OREGON





APRON PLAN VIEW



REINFORCING STEEL SCHEDULE


BAR	NO.	SHAPE	Α	В	С
		CHEC	K		
Α	10	STRAIGHT	4'-7"	-	-
В	10	AL_B_	1'-7"	4'-1"	-
C	4	STRAIGHT	2'-6"	-	-
D	4	STRAIGHT	4'-6"	-	-
E	3	STRAIGHT	13'-8'	,	
F	5	STRAIGHT	7'-8"	-	-
		FLUM	E		
G	19	ALBUC	3'-1"	7′-6″	3'-1"
Н	20	AL B	1'-6"	8'-1"	-
I	4	STRAIGHT	7'-6'	, -	_
J	8	STRAIGHT	14'-6'	' -	-


NOTES ALL BARS TO BE NUMBER 4. BARS TO BE PLACED IN THE CENTER OF THE WALLS AND FLOOR. NEED 820 LINEAL FEET OF REINFORCING BARS WITHOUT ANY WASTE.



EXPIRES 6/30/2003

FLUME END WALL ELEVATION VIEW





SON BAY AQUIFER RECHARGE STRUCTURE REINFORCING ST HUD CADFILE whiteckst SHEET 4 DF 4

DATE

4/03

DESIGNED B. HEWES
PLOTTED
APPROVED

GE PROJECT STEEL

HUDSON BAY AQUIFER RECHARGE PROJECT

ENGINEERING REPORT

This project entails diverting water from an existing irrigation ditch to three pits to be excavated for the purpose of infiltrating the water into the shallow aquifer. Project features include a concrete check structure in the existing White Ditch, a concrete flow measuring flume, an open ditch, three excavated pits, pipes connecting the pits and an outflow ditch from the down stream pit.

These items were sized to handle 50 cubic feet per second (cfs) of water. This is the amount anticipated will be available from excess flow in the Walla Walla River and that the Hudson Bay District is able to deliver.

Data gathered to design the project consisted of a site topographic survey and installing two sites for testing the water infiltration capacity of the natural materials and determining the layers in the soil profile. In addition the Soil Survey of Umatilla County Area, Oregon was consulted. This is a US Dept. of Agriculture, Natural Resources Conservation Service publication giving general soils information.

The topographic survey data was used to prepare a topographic map with one foot contour intervals at a scale of 1'' = 60'. This information was used to help determine the location of the project features.

Two test pits were excavated to a depth of 6'-7' each. A 24" diameter by 5' long section of corrugated metal pipe was set on end in the bottom of the pit and about one foot of fill placed around it to hold it in place. Water was pumped into the pipe at a rate that would sustain a water depth of one foot in the pipe. Both flow rate and total flow was measured. The test was run for 6.25 hours in the first pit and 3.5 hours for the second pit.

PIT#1

Soil profile:

0-12" sandy loam

12"-36" gravelly sandy loam, approximately 50% of the material volume is gravel size particles with an estimated D $_{50}$ size of about 0.75"

36"-48" sandy loam, in parts of the trench this layer does not exist

48"-?" gravelly sandy loam approximately 20% of the volume is gravel size particles

The inflow rate at the end of the test period was 4.0 gallons per minute (gpm). This resulted in an infiltration rate of 1.7 gpm/sq. ft./ foot of head.

RECEIVED

JAN 3 0 2009

PIT #2

Soil profile:

0"-13" gravelly sandy loam

13"-39" cobbly sandy loam, the D₅₀ of the gravel is approximately 1"

39"-52" gravelly sandy loam

52"-? sand gravel mix D₅₀ estimated to be about 0.25"

In this pit the inflow rate of 11.9 gpm was maintained for 3.5 hours and at no time did water puddle in the bottom of the pipe. The infiltration rate is in excess of 3.8 gpm/sq. ft.

The area needed for infiltrating the water was determined assuming an infiltration rate for the entire area of 3.0 gpm/sq.ft./ per foot of head. For an inflow rate of 50 cfs the infiltration area needs to be 7480 square feet. The infiltration rate of 3.0 gpm/sq.ft. was chosen because the pits will be located in the area with soil surface texture similar to test pit #2.

Due to the possibility of fine soil particles plugging the infiltration area, unknowns concerning the long term infiltration rate and that the amount of water available is not yet known extra infiltration area is being provided. Three separate pits with bottom dimensions of 50 feet X 100 feet are proposed. This will provide an infiltration area of 15,000 square feet.

The pits will be excavated to a depth of about 5 feet to get below the second sandy loam layer noted in both test pits. This will allow the water depth to be 2.5 feet - 3.5 feet. That will increase the rate of infiltration over the test values derived with one foot of water depth. The overall safety factor for the infiltration area is well over 2.

Inflow to the system will be measured with a ramp flume and continuously recorded. The ramp flume is sized to provide 5% flow rate accuracy over a flow range of 10 cfs-50 cfs

Any outflow from the last pit will be safely returned to the White Ditch through a 12-inch pipe. The pipe will be on a slope that will keep water from flowing out of White Ditch.

Date: 8/21/03

RECEIVED

JAN 3 0 2009

LAND USE INFORMATION SHEET

This information is needed to determine if the proposed project complies with statewide planning goals and is compatible with local comprehensive plans (ORS 192.180)

	(/COUNTY LAND USE INFORMATION (to be completed by local planning official):					
Please	Recharge Hudson Bay project e check below the one that applies! Project					
	This project is not regulated by the local comprehensive plan and zoning ordinance.					
	This project has been reviewed and is compatible with the local comprehensive zoning ordinance. (Please cite appropriate plan policies, ordinance section, and case numbers.)					
	This project has been reviewed and is not compatible with the local comprehensive plan and zoning ordinance. (Cite appropriate plan policies, ordinance section, and case numbers).					
	Compatibility of this project with the local planning ordinance cannot be determined until the following local approvals are obtained:					
	Conditional Use Permit Plan Amendment Other Development Permit Zone Change					
An ap	plication has has not been made for the local approvals checked above.					
* Sign	nature of Local Official: Vally Perry e: Senier Planner Date: 5-27-03					
Muse	be authorized signature from your local City/County Planning Department					

RECEIVED

JAN 3 0 2009

ATTACHMENT 5A: Methodology to Determine Chemical Constituents for Water Quality Assessment and Evaluation

Introduction:

The Artificial Groundwater Recharge rules (OAR 690-350-120) require both up front water quality and a water quality-monitoring plan. Further, for any recharge project the rules (OAR 690-350-120 (3) (b) require an applicant to either obtain a water quality permit (typically a water pollution control facility (WPCF) permit) or show that a permit is not necessary. Also, rules OAR 690-350-120 (3)(g) require a "Project Description Report" (ATTACHMENT 5) that outlines the proposed groundwater quality-monitoring plan. This attachment is intended to specifically help clarify the method by which the list of chemical constituents was determined.

Project Area Sample Chemical Review Methodology

Working with Tom Darnell, OSU Extension agent in Milton-Freewater, a chemical constituents review was conducted in order to determine what types of chemicals should be examined in the surface and groundwater monitoring for the project. Several steps were followed to determine which chemicals were of interest.

Review Steps

- 1. Reviewed the ODEO Report: April 1999 Milton-Freewater Groundwater Quality Study: As part of the Statewide Groundwater Monitoring Program (Richardson, et. al., 2000). Particular attention was focused on the constituents tested, testing protocol and timing, and the results-conclusions.
- 2. Reviewed OSU Extension Pesticide Properties Database and determined which were used in the Milton-Freewater area and a list was comprised. (Table 4A1, 4A2)
- 3. Determined which were currently and/or historically used in the area utilizing past chemical studies in the basin (see references). This included interviewing the current landowner on the site-specific history of chemical use on that property (see signed written statement below).
- 4. Determined which chemicals were important to monitor for during the recharge period (winter-spring). Considered each chemical's typical seasonal application period, solubility in water, soil half-life, and soil movement ratings.
- 5. Considered project design (top soil removed), and finalized list of chemicals of interest.

Final List of Chemicals to Monitor for Recharge Project

Chemicals Currently Used:

Rubigan (Fenarimol) Ridomil (Metalxyl) Systhane/Rally (Myclobutanil) Devrinol (Napropamide)

Chemicals Historically Used:

DDD-DDF-DDT Elgetol (DNOC sodium salt) Alar/B-Nine (Daminozide) Lindane (Lindane) RECEIVED

JAN 3 0 2009

Laboratory Resources

Nitrate Analysis: Walla Walla County-City Health Department

310 W. Popular, P. O. Box 1753

Walla Walla, WA 99362 Telephone (509) 527-3290

Chemical Analysis: KUO Testing Labs, INC.


337 south 1st Avenue Othello, WA 99344

Telephone: (509)-488-0118

JAN 3 0 2009

WATER RESOURCES DEPT
SALEM, OREGON

Attachment 5B Map of On-Site Monitoring Well Locations



Attachment 50

History of Chemical Use: Recharge Site Specific

Landowner Statement of Past Use:

'Gentleman.

I have been the owner of a certain parcel of land in the ralley with an address known as 84140 Prunedale Rd., Milton-Freewater, Oregon, 97862.

I have owned this land since 1978 at which time we took over the existing orchard of apples and farmed it for two years at which time we began removing various blocks of tress and replanting with new varieties. In the past few years we raised Nursery Tree Stock and began leveling the land to its present condition, letting it lay in a dormant stage for a year and then planting cover crops to enrich the soil for a future cherry orchard.

The pesticides applications were the normal tree finit pesticides as allowed by regulations of the industry. The herbicide applications were Round-Up. Simizine and Paraquat. No other chemicals were used on this parcel of land during my ownership. If you should have other questions, please contact me at the following: (541)-278-6305, (509)-386-6175, or (541)-558-3752 or email at:

Date: 10-17-03

Hjohnson(W.o.umatillelor. Is

Landown

RECEIVED

JAN 3 0 2009

¹ Chemical is defined here to include insecticides, fertilizers, herbicides, rodenticides, fungicides, and all other non-natural chemicals.

1STORET RETRIEVAL DATE 99/06/23

402388 28AWALL03780

46 01 08.6 118 24 45.1 4

WALLA WALLA RIVER AT HWY 11 (MILTON-FREEWATER)

41059 OREGON UPACIFIC NORTHWEST

UMATILLA

131007

COLUMBIA RIVER BASIN BELOW YAKIMA RIVER

21400000

17070102007 00

0000 FEET DEPTH

Grey areas samples that correspond to Recharge Project

RECEIVED

JAN 3 0 2009

				~					
INITIAL DATE	67/04/24	67/08/21	67/12/11	68/04/02	68/08/05	68/12/16	69/03/04	69/12/10	70/04/28
INITIAL TIME	1235	1400	1440	1615	1750	1100	1510	1145	930
MEDIUM	WATER	WATER	WATER	WATER	WATER	WATER	WATER	WATER	WATER
00010 WATER TEMP CENT	8	25.5	7	8.5	25	5	8.6	5	6
00011 WATER TEMP FAHN	46.4\$	77.9\$	44.6\$	47.3\$	77.0\$	41.0\$	47.5\$	41.0\$	42.8\$
00027 COLLECT AGENCY CODE	10	10	10	10	10	10	10	10	10
00070 TURB JKSN: JTU	250	2		10	3	8		7	1
00080 COLOR PT-CO UNITS	20	4		3	5	3		1	3
00095 CNDUCTVY AT 25C MICROMHO	67	225	200	72	243	69	95		71
00300 DO MG/L	10.3	12.2	10.6	11.4	10.7	12.2	11.6	11.7	12.7
00301 DO SATUR PERCENT	89	150	89	99	131	95	99	94	105
00310 BOD 5 DAY MG/L	0.7	1.3	0.9	0.5	1.3	1.6	0.8	1.5	1.5
00400 PH SU	7.3	8.3	7.7	7.5	8.40L	7.2	7.6	7.5	7.5
00410 TALK CACO3 MG/L	30	108		33	105	30		54	31
00500 RESIDUE TOTAL MG/L	518			99	184	101		118	87
00530 RESIDUE TOT NFLT MG/L	368	11		10	10	21		18	12
00610 NH3+NH4- N TOTAL MG/L	0.13	0.34		0.38	0.32	0.17		80.0	0.12
00612 UN-IONZD NH3-N MG/L	.0004\$.036\$.002\$.040\$.0003\$.0003\$.0005\$
00619 UN-IONZD NH3-NH3 MG/L	.0005\$.043\$.002\$.049\$.0004\$.0004\$.0006\$
00620 NO3-N TOTAL MG/L	0.03	0.02		0.07	0.38	0.54		0.73	0.13
00660 ORTHOPO4 PO4 MG/L	0.06	0.16		0.1	0.18	0.56		0.16	0.03
00760 SWL PBI MG/L	1K	1K	29	1K					
00940 CHLORIDE TOTAL MG/L	2			1	8	2		2	1
00945 SULFATE SO4-TOT MG/L	8	33		4	14	4		6	3
22413 HARDNESS TOTLDISS WTR MG/L	28			37	99	35		49	24
31505 TOT COLI MPN CONF /100ML	620	2400	7000	60	230	2300	620	450K	620
31615 FEC COLI MPNECMED /100ML			230						60
31677 FECSTREP MPNADEVA /100ML				-				240	
							The state of the s		-

INITIAL DATE INITIAL TIME MEDIUM 00010 WATER TEMP CENT 00011 WATER TEMP FAHN 00027 COLLECT AGENCY CODE 00070 TURB JKSN JTU 00080 COLOR PT-CO UNITS 00094 CNDUCTVY FIELD MICROMHO (SAMPLE CONTINUED FROM PREVIOUS		E)	70/07/13 1400 WATER 24 75.2\$ 10	70/11/30 1645 WATER 5.5 41.9\$ 10 5	71/05/11 2000 WATER 15.5 59.9\$ 10 3	71/08/16 1620 WATER 26 78.8\$ 10 1	72/02/28 1610 WATER 9 48.2\$ 10 28 10	72/08/30 1130 WATER 20.5 68.9\$ 10 2 5	73/02/12 845 WATER 2.5 36.5\$ 10 15 5	73/06/13 1055 WATER 16.5 61.7\$ 10 3 5	73/09/24 1400 WATER 16 60.8\$ 10 2
INITIAL DATE			70/07/13	70/11/30	71/05/11	71/08/16	72/02/28	72/08/30	73/02/12	73/06/13	73/09/24
INITIAL TIME			1400	1645	2000	1620	1610	1130	845	1055	1400
MEDIUM			WATER	WATER	WATER	WATER	WATER	WATER	WATER	WATER	WATER
00095 CNDUCTVY AT 25C MICROMHO			236	66	51	200	67	221	87		
00300 DO MG/L			12.5	11.5	9.5	14.2	11	12.5	12.9	11.7	11.5
00301 DO SATUR PERCENT			151	95	99	172	97	137	97	117.0\$	115.0\$
00310 BOD 5 DAY MG/L			2	0.7	0.8	2.3	0.7	0.9	1.4		
00400 PH SU			8.6	7.5	7.3	8.9	7.1	8.4	7.3		
00410 T ALK CACO3 MG/L				29	21	96	23	92	29	82	95
00500 RESIDUE TOTAL MG/L				89	75	172	280	170	100	153	164
00530 RESIDUE TOT NFLT MG/L			L	12	12	4	106	8	32	10	3
00610 NH3+NH4- N TOTAL MG/L			DE	0.34	0.06	0.66	0.09	0.14	0.04	0.1	0.17
00612 UN-IONZD NH3-N MG/L	Ш	2009	SO	.001\$.0003\$.215\$.0002\$.013\$.00008\$		
00619 UN-IONZD NH3-NH3 MG/L	\geq	2	55	.002\$.0004\$.261\$.0002\$.016\$.00010\$		2.22
00620 NO3-N TOTAL MG/L	M	. 00	90	0.02	0.1	0.15	0.3	0.51	0.14	0.36	0.39
00625 TOT KJEL N MG/L 00650 T PO4 PO4 MG/L	RECEIVED	JAN 3 0	WATER RESOURCES DEPT SALEM, OREGON						0.2		
00660 ORTHOPO4 PO4 MG/L	œ	Y	A P	0.06	0.09	0.12	0.09	0.04	0.3	0.1	0.14
00930 SODIUM NA,DISS MG/L			S	0.06	0.09	0.13	2.4	0.04	2.8	0.1	0.14
00935 PTSSIUM K,DISS MG/L			*				2.4		1.5		
00940 CHLORIDE TOTAL MG/L				1	0.7	5	0.8	3	1.5	6	4
00945 SULFATE SO4-TOT MG/L				3	.1K	11	3	11	2	6	4
22413 HARDNESS TOTLDISS WTR MG/I	,			26	19	80	22	84	28	71	79
31505 TOT COLI MPN CONF /100ML			230	2400	2400	230	620	620	290	′`	17
31615 FEC COLI MPNECMED /100ML			230	45K	45K	45K	45K	020	60		
7 10000			200	1011	1011	1011	1011		00		

1STORET RETRIEVAL DATE 99/06/23

28AWALL04860 402389

45 54 13.6 118 22 02.9 4

WALLA WALLA RIVER U/S MILTON-FREEWATER

41059 OREGON

UMATILLA

PACIFIC NORTHWEST 131007

COLUMBIA RIVER BASIN BELOW YAKIMA RIVER

21400000

17070102011 00

0000 FEET DEPTH

RECEIVED

JAN 30 2009

INITIAL DATE	67/04/24	67/08/21	67/12/11	68/04/03	68/08/06	68/12/16	69/03/04	69/12/10
INITIAL TIME	1300	1520	1700	810	905	1030	1540	1055
MEDIUM	WATER	WATER	WATER	WATER	WATER	WATER	WATER	WATER
00010 WATER TEMP CENT	6	21	5	6.5	16	5	6.4	3
00011 WATER TEMP FAHN	42.8\$	69.8\$	41.0\$	43.7\$	60.8\$	41.0\$	43.5\$	37.4\$
00027 COLLECT AGENCY CODE	10	10	10	10	10	10	10	10
00070 TURB JKSN JTU	5	7	15	2	5	9	12	2
00080 COLOR PT-CO UNITS	6	2	4	4	4	3	2	0
00095 CNDUCTVY AT 25C MICROMHO	59	180	69	57	93	57	63	
00300 DO MG/L	11.2	8.7	11.9	11.6	9.7	11.1	11.6	12.9
00301 DO SATUR PERCENT	94	101	98	98	102	87	99	100
00310 BOD 5 DAY MG/L	0.6	0.8	1.1	0.6	0.4	0.2	0.7	1.2
00400 PH SU	7.4	7.5	7.5	7.3	7.3	7	7.5	7.7
00410 TALK CACO3 MG/L	26	32	32	26	40	16	27	33
00500 RESIDUE TOTAL MG/L	89	101	83	113	98	92	81	67
00530 RESIDUE TOT NFLT MG/L	2	8	6	7	22	26	7	6
00610 NH3+NH4- N TOTAL MG/L	0.14	0.17	0.32	0.12	0.18	0.11	0.06	0.03
00612 UN-IONZD NH3-N MG/L	.0005\$.002\$.001\$.0003\$.001\$.0001\$.0003\$.0002\$
00619 UN-IONZD NH3-NH3 MG/L	.0006\$.003\$.002\$.0004\$.001\$.0002\$.0003\$.0002\$
00620 NO3-N TOTAL MG/L	0.01	0.02	0.02	0.03	0.04	0.39	0.3	0.12
00660 ORTHOPO4 PO4 MG/L	0.02	0.1	0.1	0.07	.01K	0.01	0.11	0.1
00760 SWL PBI MG/L	8	1K	1					
00940 CHLORIDE TOTAL MG/L	1	5	1	1	6	2	2	0.8
00945 SULFATE SO4-TOT MG/L	3	0.6	4	2	15	3	1	3
22413 HARDNESS TOTLDISS WTR MG/L	23	36	29	24	32	25	26	31
31505 TOT COLI MPN CONF /100ML	230	620	210	230	620	210	60	60
31615 FEC COLI MPNECMED /100ML			210					
31677 FECSTREP MPNADEVA /100ML								5K

INITIAL DATE	74/05/06	74/07/30	74/11/11	75/05/27	75/07/08	75/11/10		
INITIAL TIME	1420	1745	1630	1930	1745	1745		
MEDIUM	WATER	WATER	WATER	WATER	WATER	WATER		
00010 WATER TEMP CENT	10.5	20.5		10.5	27	4.7		
00011 WATER TEMP FAHN	50.9\$	68.9\$		50.9\$	80.6\$	40.5\$		
00027 COLLECT AGENCY CODE	10	10	10	10	10	10		
00070 TURB JKSN JTU	7	2	1	1	2	1.0K		11
00080 COLOR PT-CO UNITS	5	5	1K	5	15	1K		ECEIVED
00094 CNDUCTVY FIELD MICROMHO	49	80		55	170	80		LL
00095 CNDUCTVY AT 25C MICROMHO	- 53	90		54	195	72		2
00300 DO MG/L	10.8	9		10.8	8.7	11.9		Ш
00301 DO SATUR PERCENT	101	103		102	106	95		00
00310 BOD 5 DAY MG/L	1	0.3		0.6	3	0.4		
00400 PH SU	7.5	8		7.3	8	7.7		
00410 T ALK CACO3 MG/L	17	34	33	20	65	34		
INITIAL DÂTE	74 /05 /06	74/07/30	74/11/11	75 /05 /27	75/07/98	75/11/10		
INITIAL TIME	1420	1745	1630	1930		1745		
MEDIUM	WATER				WATER			
00500 RESIDUE TOTAL MG/L	62	76	68	64	180	87		
00530 RESIDUE TOTNFLT MG/L	39	4	1K	5	38	3		
00610 NH3+NH4- N TOTAL MG/L	0.03	0.02	0.06	0.01	0.19	0.02		
00612 UN-IONZD NH3-N MG/L	.0002\$.0008\$	0.00	.00004\$.012\$.0001\$	•	
00619 UN-IONZD NH3-NH3 MG/L	.0002\$.0010:\$.00005\$.014\$.0001\$		
00620 1:03-N TOTAL MG/L	0.01	0.05	0.06	0.1	0.72	0.12		
00650 T PO4 PO4 MG/L	0.2	0.2		0.3	0.5	0.1		
00660 ORTHOPO4 PO4 MG/L	0.01	0.14	0.08	0.09	0.08	0.11	•	
00930 SODIUM NA,DISS MG/L	2.1	3		2.4	8.4	3		
00935 PTSSIUM K,DISS MG/L	1.6	2.4		1.3	3.5	2		
00940 CHLORIDE TOTAL MG/L	0.4	0.9	1	1	6	1		
00945 SULFATE SO4-TOT MG/L	2	1	2	2	8	2		
22413 HARDNESS TOTLDISS WTR MG/L	14	27	27	19	60	27		
31505 TOT COLI MF'N CONF /100ML	60	7000L		230	7000	2400		
31615 FEC COLI MPNECMED /100ML	45K	620		45	7000	230		

WATER RESOURCES DEPT SALEM, OREGON

RECEIVED

JAN 3 0 2009

WATER RESOURCES DEPT SALEM, OREGON

LAND LEASE

1. PARTIES

The parties to this Lease are HULETTE M. JOHNSON, SHIRLEY A. JOHNSON, and H. MARC JOHNSON, hereinafter referred to as Landlord, and HUDSON BAY DISTRICT IMPROVEMENT COMPANY, and Oregon Non-profit Improvement District, hereinafter referred to as Tenant.

2. DATE

This Lease will begin the first of the following month, after the Tenant has obtained a water right certificate for the purpose of ground water recharge for this site from the State of Oregon.

3. DESCRIPTION OF LEASED PREMISES

Landlord leases to Tenant and Tenant leases from Landlord, under the terms and conditions stated herein, the real property in Umatilla County, State of Oregon, described in Exhibit "A" attached hereto and by such reference incorporated herein.

4. TERM OF LEASE

The term of this Lease will be from the date of this lease for a period of five(5) years. Tenant shall have the option to renew this lease with notice to Landlord of not less than 90 days prior to the end of the initial term and any renewal terms for future additional five year terms upon the mutual agreement of renegotiated rental terms for each renewal period.

5. POSSESSION

The Tenant shall be granted possession of the property upon execution of this document by all parties, together with the receipt of the initial lease payment as prescribed in RENT.

6. RENT

Tenant shall pay advance annual rent payments in the amount of three thousand six hundred dollars(\$3,600) plus annual assessment for irrigation water for surface water rights delivered by Tenant to 84140 Prunedale Road, beginning with INV # 1276C for 2003. Landlord shall pay same assessment to Tenant upon receipt of said annual assessment payment from Tenant. Tenant shall make each annual payment for the term of this lease to Landlords address, 52833 Sunquist Road, Milton-Freewater, Oregon, 97862, or otherwise as notified. The initial payment shall be due on the date this agreement is executed by Tenant and Landlord, and Tenant it therefore granted possession to said real property.

7. INSURANCE

Tenant shall maintain liability insurance on the leased property in an amount acceptable to the Landlord and shall provide proof of such insurance naming Landlords as additional insureds. Tenant shall also be responsible for necessary insurance on laborers. Tenant shall also be responsible for insurance coverage on personal property kept or installed upon this leased premises.

8. USE OF PREMISES

Tenant agrees that they will use the property for ground water recharge/storage, ponding.

9. LANDLORDS OBLIGATIONS

Landlord shall install electricity, pump, collection pond and mainline with the assistance of Tenant necessary to connect the source of irrigation water provided by Tenant to the existing delivery systems of Landlord's.

If there is a mortgage or other encumbrance on said premises, Landlord covenants to keep same in good standing, at all times, to make payments when due and not to suffer or permit default in said encumbrance.

Landlord shall pay all property taxes upon the real property subject to this lease in a timely manner.

RECEIVED

JAN 3 0 2009

RECEIVED

JAN 3 0 2009

WATER RESOURCES DEPT SALEM, OREGON

10. TENANT'S OBLIGATIONS

Tenant shall provide all labor and materials for the construction of the ground water recharge pond, Landlord's irrigation collection pond and pumping station or other improvements required by Tenant, including maintenance of bridges and culverts.

Tenant shall pay all taxes of any kind and necessary insurance for labor to maintain to maintain improvements including any increase in property taxes as a result of said improvements as made by Tenant.

Tenant shall pay for all maintenance and operation of improvements constructed on said premises.

Tenant agrees that earth material excavated from the recharge pond shall be placed along the edges of the recharge area to produce a basin-like pond. Excess material shall be placed in other areas of Landlords property as directed by Landlord and spread evenly where located so that agricultural activities may continue.

Tenant upon termination of lease, shall replace all soil to a level topography using stored material from the sides of said 'recharge' pond, together with other off site soil as approved by Landlord, necessary to return the recharge pond to a level premise for agricultural growing activities.

Tenant shall pay for all costs incurred for control of noxious weeds and vegetation around perimeter of ponding areas, and shall spray the perimeter of said pond including the banks of the Hudson Bay Canal and the Pleasantview Canal including bridges and culverts to maintain a clean ground cover as directed by Landlord

Tenant shall provide signage for trespass prevention and notice of manmade hazard upon premises at the commencement of work efforts at the recharge area.

Tenant shall install any and all fences and gates necessary as may be required by an insurance company or others around the recharge pond.

16

JAN 3 0 2009

WATER RESOURCES DEPT SALEM, OREGON

11. LIENS

Tenant shall pay, as due, all claims for work done on and for services rendered or materials furnished to the leased premises incurred and owing by Tenant and shall keep the premises free of any liens resulting from acts of the Tenant.

12. COVENANTS OF TITLE

Landlord covenants that he is the owner of the above described property free of any encumbrance that would impair or interfere with Tenant's rights under this Lease, and that Landlord has full right and authority to lease the premises described herein.

13. WASTE

Tenant shall not committed or permit to be committed any waste, strip, damage to or misuse of the premises.

14. INDEMNIFICATION

Tenant shall indemnify, hold harmless and defend Landlords from all claims, loss or liability arising out of or related to any activity of Tenant on the leased premises or any condition of the leased premises in the possession or under the control of the Tenant.

15. ASSIGNMENT

No part of the leased property may be assigned, mortgaged, or subleased, nor may a right of use of any portion of the property be conferred on any third person by any other means without the prior written consent of Landlord. This provision shall apply to all transfers to and by trustees in bankruptcy, receivers, administrators, executors, and legatees. No consent in one instance shall prevent the provision from applying to a subsequent instance.

16. DEFAULT

The following shall be events of default:

Failure to pay rent when due.

Failure of either Landlord or Tenant to comply with any other term or condition or fulfill any other obligation of this Lease within twenty(20) days after written notice by Landlord or Tenant specifying the nature of the default with reasonable particularity.

Abandonment by the Tenant of the property

If the default is of such a nature that it cannot be completely remedied within the twenty-day period and the defaulting party thereafter proceeds with reasonable diligence and in good faith to effect the remedy as soon as practicable, default shall not be declared unless the defaulting party ceases to effect the remedy.

17. TAXES

The Landlord shall pay all real property taxes for real property for the term of this Lease. Tenant shall be liable to pay any taxes, personal or real, incurred as a result of improvements placed upon the leased premises.

18. NONWAIVER

Waiver by either party of strict performance of any provision of this Lease shall not be a waiver of or prejudice the party's right to require strict performance of the same provision in the future or of any other provision of this Lease.

ATTORNEY FEES

If suit or action is instituted in connection with any controversy arising out of the Lease, the prevailing party shall be entitled to recover, in addition to costs, such sums as the Court may adjudge reasonable as attorney fees.

RECEIVED

JAN 3 0 2009

20. SUCCESSION

Subject to the above-stated limitations on transfer of Tenant's interest, this Lease shall be binding upon and inure to the benefit of the parties, their respective successors and assigns.

21. INSPECTION OF PREMISES

The Landlord reserves the right to themselves and their agents to go upon the premises at reasonable and proper times to inspect the same for the purpose of determining that the Lease is being properly observed and that all of the terms of this lease are being performed by the Tenant.

22. IMPROVEMENTS

Any improvements to the real property by Tenant shall remain the property of the Landlord upon termination of this Lease, unless the Tenant obtains the written consent of Landlord to remove said improvements prior to the time the improvements are placed on the property. However, Tenant shall be responsible for refilling the recharge "pond" as set forth in paragraph 10 above.

23. TERMINATION

The Tenant agrees to deliver the property to the Landlord at the end of the term of this Lease and in as good a condition as when accepted, and pursuant to paragraph 10 above.

24. TIME IS OF THE ESSENCE

The parties acknowledge and agree that time is of the essence with respect to all of the terms, conditions, and provisions of this Lease.

25. NOTICES

Any notice required or permitted under this Lease shall be given when actually delivered or when deposited in the United States Mail as certified mail, addressed as follows:

RECEIVED

JAN 3 0 2009 WATER RESOURCES DEPT SALEM, OREGON LANDLORD: HULETTE M. JOHNSON, et., al.

52833 Sunquist Road

Milton-Freewater, Oregon 97862

TENANT: HUDSON BAY DISTRICT IMPROVEMENT

COMPANY P.O. Box 110

Milton-Freewater, Oregon 97862

26. WATER DUES

The annual irrigation water dues as billed to Landlord by Tenant shall be paid by Landlord to Tenant as billed. As part of the rent agreement in paragraph 6 above, Tenant shall pay Landlord an equal amount of said water dues within thirty(30) days of receipt of said water dues from Landlord, during the term of this Lease and any renewals thereof.

27. CAPTIONS AND HEADINGS

The captions and headings throughout this Lease are for convenience and reference only and the words contained therein shall in no way be held or deemed to define, limit, describe, explain or modify the meaning of any provisions of or the scope or intent of this Lease.

28. ENTIRE AGREEMENT

This document is the entire, final, and complete agreement of the parties pertaining to the Lease of the premises described herein, and supersedes and replaces all written and oral agreements theretofore made or existing by and between the parties or their representatives in so far as the premises are concerned.

RECEIVED

JAN 3 0 2009

IN WITNESS WHEREOF, the parties have executed by the parties have executed	shirtey Mighnson day of
TENANT:	
HUDSON BAY IMPROVEMENT CO.	
BY: Seh a Tele	RECEIVED
it's Secretary /Treasurer	JAN 3 0 2009
STATE OF OREGON))ss. County of Umatilla)	WATER RESOURCES DEPT SALEM, OREGON
	ppeared before me the above named . MARC JOHNSON and acknowledged
OFFICIAL SEAL KATHLEEN F. YENNEY NOTARY PUBLIC-OREGON COMMISSION NO. 337142 MY COMMISSION EXPIRES SEPT. 24, 2004 My commission My commission	DELIC FOR PREGON Jon expires: 9-24-2004
STATE OF OREGON)	
County of Umatilla) ss.	
On this 15th day of Oct 2003, personally John C-Zerba in his capacity as Sec BAY IMPROVEMENT CO. and acknowledged the forego	appeared before me the above named whary / Treasurer of HUDSON ong to be a voluntary act
· Vn	Att. A. Dance

OFFICIAL SEAL

KATHLEEN F. YENNIEY


NOTARY PUBLIC-OREGON

COMMISSION NO. 337142

MY COMMISSION EXPIRES SEPT. 24, 2004

NOTARY PUBLIC FOX OREGON
My Commission expires: 9-24-2004

STATE OF OREGO	N)
)ss
County of Umatilla)



On this <u>33</u> day of <u>october</u> 2003, personally appeared before me the above named <u>it. marc Johnson</u>, and acknowledged the foregoing to be a voluntary act and deed.

NOTARY PUBLIC FOR OREGON

My commission expires may 15, 2007.

RECEIVED

JAN 3 0 2009

TRACT I:

Township 6 North, Range 35, East of the Williamette Meridian: Section 33: A tract of land located in the South Half of the Northeast Quarter, and being a portion of that tract of land conveyed to William J. Jackson, by Deed recorded in Book 369, Page 267, Deed Records, and being described as follows, to-wit:

Commencing at the quarter section corner on the line between Sections 33 & 34; running thence North 20 chains: thence West 33-16/100 chains; thence Southeasterly 32-16/100 chains, more or less, to a point on the center line; running East and West through said Section 33, said point being 7 chains West of the point of beginning; thence East 7 chains to the point of beginning. Excepting Therefrom, beginning at the Northeast corner of the Southeast Quarter of the Northeast Quarter of said Section 33: and running thence South 45 rods: then Nest 35-5/9 rods; thence North 45 rods; thence East 33-5/9 rods to the place of beginning. ATI being East of the Willamette Meridian, Umatilla County, Oregon. Subject to any and all water rights of way and roads.


TRACT !!!:

Beginning at the Northeast corner of the Southeast Quarter of the Northeast Quarter of Section 33, Township 6 North. Range 35; running thence South 45 rods; thence West 35 and 5/9 rods; thence North 45 rods; thence East 35 and 5/9 rods to the place of beginning. Excepting therefrom that tract of land conveyed to the State of Oregon, by and through its State Highway Commission by deed recorded in Book 130, Page 573 of the Deed Records of Umatilla County, Oregon, Also, excepting any portion of said premises lying within that strip of land conveyed to Walla Walla and Columbia River Railroad Company, by deed recorded in Book "D", Page 834 of the said Deed Records. All being East of the Willamette Meridian, in the County of Umatilla and State of Oregon;

Excepting any and all water rights of way.

RECEIVED

JAN 3.0 2009



Altachment	- 8	B
------------	-----	---

RECEIVED

JAN 3 0 2009

License	No.	
---------	-----	--

WATER RESOURCES DEPT SALEM, OREGON

STATE OF OREGON

WATER RESOURCES DEPARTMENT

APPLICATION FOR LIMITED WATER USE LICENSE

Applican	ıt(s):	Hudson	Bay	District	Irrigat	tion (ompany	
Contact 1	Person:	Jon B10	ugh /-	John Zerbo				
Mailing A	Address: _	8.0. Bix	110					_
Telephon	ie No:	541 438	4-6105					_
waters or use of a <u>s</u>	groundwa hort-term	ation for a Lim ter-not otherw or <u>fixed duration</u>	ise exem _l o <u>n</u> :	ot, or to use st	ored water	of the Sta	te of Oreg	on for a
1. Se	OURCE(S)	OF WATER 1	or the pr	oposed use: _	Walla L	Jalla T	Zluer	_ a
ga		OUNT OF WA					The state of the s	
3. II	TENDED	General con Forestland a	uction or struction; nd range	maintenance	nent; or	(ge.		

4. DESCRIPTION OF PROPOSED PROJECT: Include a description of the intended place of use as shown on the accompanying site map, the method of water diversion, the type of equipment to be used (including pump horsepower, if applicable), length and dimensions of supply ditches and pipelines: See attached Application document

RECEIVED

JAN 3 0 2009

5. PROJECT SCHEDULE: (List day, month, and yea	ar)
Date water use will begin	
Date project will be completed	
Date need for water will be completed//- 09	<u></u>
NOTE: A completed water availability statement from the map meeting the requirements of OAR 690-340-030 must act this request is \$100 for the first point of diversion plus \$10 for the license, if granted, will not be issued or replaced by a nefive consecutive years. The right granted will be subordinately upon the same source, or water affected by the source, determined the use causes injury to any other water right or any other water right o	ccompany this request. The fee for for each additional point of diversion. ew license for a period of more than te to all other authorized uses that and may be revoked at any time it is
REMARKS:	
SIGNATURE of Applicant: Soc - From	DATE: 10-23.63
I certify that I have examined the foregoing applicat hereby grant a Limited License to use said water as describe water rights of record, and subject to any valid public interesting.	ed in the application, subject to all
This license shall be in effect beginning, 20	, 20, and shall expire
WITNESS my hand this,	, 20
	Paul R. Cleary Water Resources Department Director
The licensee shall give notice to the Department (Watermast using the water under the Limited License and shall maintain shall include, but need not be limited to, an estimate of the ause and the categories of beneficial use to which the water is Limited License, the record of use shall be available for revi	in a record of use. The record of use mount of water used, the period of applied. During the period of the
The application was first received at the Water Resources D day of, 20, at o	

2/5/04

To: Department of Environmental Quality

Eastern Region Pendleton Office 700 SE Emigrant, Suite 330 Pendleton, OR 97801 RECEIVED

JAN 3 0 2009

WATER RESOURCES DEPT SALEM, OREGON

ATTENTION: Phil Richardson, (OWRD File # LL-758)

From: Hudson Bay District Irrigation Company (HBDIC)

P.O. Box 110

Milton-Freewater, Oregon 97862

RE: Request for additional information; Artifical Ground Water Recharge Testing Project (OWRD File # LL-758)

To Whom It May Concern:

The purpose of this letter is to provide the additional information requested by ODEQ for the Artifical Ground Water Testing Project (Attachment 5A: Methodology to Determine Chemical Constituents For Water Quality Assessment and Evaluation and Attachment 5C: Chemicals of Interest for Hudson Bay Recharge Project). The following addresses each of the items requested in the 2/3/4 letter.

- Simazine has been included in Attachment 5C (see attached) along with the chemical properties needed to screen the chemical. If deemed appropriate, the chemical could be added to the final screening list. Also, ODEQ had sampled for this analyte during the 1999 study, and was found not to be a risk. (ODEQ, 1999).
- We concur that the four sampling events (once before, once shortly after, once during and once shortly before the end of the project) would be a more comprehensive way to screen for chemicals during the project. The final chemical list and their cost to process may pose some limitations as to the amount of samples we can collect. After we receive the final list, we can assess costs and notify ODEQ as to our financial constraints of adding a fourth sample.
- Nitrate has been used as a surrogate for solubility in other pesticides studies. However, we concur that
 unless it was possible to also know how it was applied and which chemicals most resembled its
 physical properties, that it may have less application for this project. We will still intend however to
 collect nitrate samples during recharge event(s) as a parameter of general water quality concern.

The additional information requested on the physical properties of the chemicals of concern is provided below.

Objective: In order to assess the parameters of use for each of the chemicals of concern (yellowed in Attachment 5C) in the project area. An assessment was conducted to better quantify the definition of "project area" and the types of crops/chemicals used over that area. The additional information requested on the chemicals of interest were:

- Application Method (see below)
- Time of year chemical applied (see below)
- Volume of chemical used per acre (see below)
- Concentration of chemical in application (see below)
- Percentage of project area receiving chemical (see below)
- Recharge site irrigation method (see below)
- Onsite use or offsite use (see below)
- Current or historic use (see Attachment 5C)

Collaborators: Bob Bower (Hydrologist/Artifical Recharge Testing Project Manager), WWBWC and Tom Darnell (Oregon State University Extension Agent).

Project Area: The project area was quantitatively defined to include the recharge testing site and the areas along that the ditch providing the surface recharge water. Total ditch length and land use was determined using a combination of recent aerial photographs (map wheel) and GIS mapping software. In order to calculate total project area, a 20-yard streamside buffer! was applied to both sides of the ditch for total area calculations.

- Total Length of Recharge Project area: 3.7 Miles
 - o 2 miles in ag area (54% of total length)
 - o 1.7 miles (46%) in Milton-Freewater city limits (no buffer value available).
- Total Ag chemical interest area: 14.6 acres
 - O Apples: 5 acres
 - O Cherries: 1.8 acres
 - O Pasture/open ground: 7.7 acres (no chemicals of interest used)
 - O Grapes: < 0.1 acre (minute use of chemicals of interest)
- Total of Project area with potential to receive chemicals: 47.3 % (city not included).

Specific area and use information:

APPLE ACRES

PRODUCT	SEASON	RATE/ACRE (MATERIAL)	%ACTIVE INGREDENT	AI/ACRE	TOTAL AMOUNT ² 5 ACRES
Amid-Thin	May	.25 lb	8.4	.021 lb	.105 lb
Rally	April-May	5.0 oz	40.0	2.0 oz	10.0 oz
Rubigan	April-May	12.0 oz	12.0	1.44 oz	7.2 oz
Ridomil ³	Oct	1.5 fl oz/1000sqft	49.0	32.0 oz	32.0 oz
Procure	April-May	12.0 oz	50.0	6.0 oz	30.0 oz
Intrepid	May	16.0 fl oz	22.6	3.6 oz	18.0 oz
Success	April	8.0 fl oz	22.8	1.8 oz	9.0 oz
Bayleton	April-May	6.0 oz	50.0	3.0 oz	15.0 oz
Provado	May	8.0 oz	17.4	1.4 oz	7.0 oz
Elgetol ⁴	April	1.0 gal	N/A	N/A	N/A

RECEIVED

JAN 3 0 2009

¹ A recent United States District Court decision (Case No. CO1-0132C) stated: "The Court further finds that 20-yard buffer zones for ground use... will substantially contribute to the prevention of jeopardy." (http://agr.wa.gov/PestFert/EnvResources/docs/FinalOrder01-22-04.pdf)

² Total amount on five acres is the probable maximum amount of material (active ingredient). Actual use depends on variety, weather conditions and disease pressure. Rally, Rubigan. Procure and Bayleton are fungicides used to control apple scab and/or mildew. Apple orchards do not receive an application of each fungicide each season. The fungicides and insecticides are applied by air blast sprayer.

³ Ridomil is soil applied, either by hand gun or herbicide sprayer, at the base of the tree. Total amount used is figured on 20 percent of the soil surface treated.

⁴ Elgetol use was discontinued in 1986.

CHERRY ACRES

PRODUC	Γ SEASON	RATE/ACRE (MATERIAL)	%ACTIVE INGREDENT	AI/ACRE	TOTAL AMOUNT ⁵ 1.8 ACRES
Success	March-April	7.0 fl oz	22.8	1.6 fl oz	2.88 fl oz
Rally	March-April	5.0 oz	40.0	2.0 oz	3.6 oz
Rubigan	March-April	9.0 oz	12.0	1.08 oz	1.9 oz
Procure	March-April	13.0 oz	50.0	6.5 oz	11.7 oz

OTHER PROJECT AREA ACRES

The other project areas were estimated not to have any of the chemicals of interested (yellowed, Attachment 5C). The portion of the ditch passing through the city of Milton-Freewater was not considered for the agricultural chemicals of interest. This portion of the ditch would predominantly be surrounded by lawns and gardens. The types of chemicals used in these areas would include three from our original list: Dacamine (2,4 D), Round Up and Diazinon. These chemicals not typically applied during the recharge project time period and were thus determined to pose little risk. No chemicals were estimated to be used on the pasture/open acreage areas.

Project site irrigation method: Landowner has informed us that sprinkler irrigation has been used at the recharge site.

Project area irrigation method: All of the project Ag areas are in sprinkler irrigation. The small parcel with grapes are on a drip irrigation system.

Onsite use or offsite use: A letter from the landowner described the onsite use in which Simazine was listed. This chemical has been added to the comprehensive list.

Current or historic use: The original Attachment 5A and 5C included an assessment and categorization of chemicals based on historic and current use.

Thank you for your time and attention.

John Brough, HBDIC Director

CC: Don Miller – OWRD Tim Bailey – ODFW RECEIVED

JAN 3 0 2009

⁵ Total amount on 1.8 acres is the probable maximum amount of material (active ingredient). Actual use depends on pest populations and pressure and weather conditions. All pesticides are applied on ground by air blast sprayer.

ATTACHMENT 5A: Methodology to Determine Chemical Constituents for Water Quality Assessment and Evaluation

Introduction:

This attachment is intended to specifically help clarify the process by which the proposed list of chemical constituents were determined and to show that a ODEQ water quality permit will not be needed for this limited license groundwater recharge project.

Chemical Constituents Review Methodology

It should be **clearly reiterated** that during construction of the recharge pits/ponds, the top 60 inches (5 feet) of topsoil would be **removed**. This construction criteria assists the project in two ways: (1) it minimizes the chance of site specific chemicals being leached into the ground water during the recharge process, (2) it increases the rate at which recharge water can be applied by exposing the more transmissive substrate below this top soil layer.

Working with our local pesticides expert, (Tom Darnell, OSU Extension Agent in Milton-Freewater) a review was conducted to determine the types of chemicals to consider for during this project's water quality monitoring plan. A description of this review processed is presented below.

Chemical Review Process

- 1. Using the proposed water diversion time period (Nov 1st through May 15th), a comprehensive list of chemicals was compiled for the project area. This included interviewing the current landowner on the site-specific history of chemical use on that property (see attached signed, written statement).
- 2. Chemicals were broken down into two classes: current chemicals were determined to be those that have been used in the past several years in the project area, and historical chemicals are not currently in use, but have were used at some point in the past. This "project area" is defined as the area starting at the Little Walla Walla diversion (on the Walla Walla River) through the lands adjacent to the ditch network to the project site. Attachment 5C lists this comprehensive list of chemicals in table form.
- 3. Reviewed the ODEO Report: April 1999 Milton-Freewater Groundwater Quality Study: As part of the Statewide Groundwater Monitoring Program (Richardson, et. al., 2000). ODEQ's well # UMA298 is located proximal to the proposed recharge site which provides excellent preexisting information for this project. Attached is a copy of the results and conclusions from that study.
- 4. Using information from OSU Pesticides database (and several other websites), the complete list of chemicals was further screened based on a set of sequential screening steps. Chemicals were selected for the final monitoring list if they appeared to meet all of the criteria listed below.

RECEIVED

JAN 3 0 2009

WATER RESOURCES DEPT SALEM, OREGON a. Currently and Historically used chemicals were choosen if:

- i. Soil ½ life = > period when last used, and if
- ii. Pesticide Movement Rating² > or = moderate, and if
- iii. ODEQ did not sample for it in 1999 study (UMA 298 well)
- 5. Exception to above selection process
 - a. ODEQ sampled and found a "positive" detection of **Dathal & Metabolites** as a part of the Phenoxyherbicide screen tests (ODEQ, 1999). The results noted:

"Dathal and its metabolites were detected in six samples as part of the Phenoxyherbicide screen. The maximum concentration detected (24.6 micrograms per liter) was much less than the 4,000 micrograms per liter healthy advisory level. Therefore, the concentration of dathal and metabolites is not believed to represent problems to human health or the environment." (ODEQ, 1999)

¹ Chemicals defined to include fungicides, herbicides, miticides, pesticides, and growth regulators.

² The Pesticide Movement Rating as reported in OSU report, (OSU, 1999)

The plan is to test for this group of chemicals during the water quality monitoring portion of this project.

6. The final step in the review process was to evaluate **if** the final list of chemicals were "testable". Two private water quality-testing laboratories (Kuo and Edge Analytical) were contacted and asked if they were able to test for these chemicals in water samples. The results are noted in attachment 5C.

Screening process conclusions:

The final list of chemicals for testing is shown below. Screening and/or testing information for the chemicals Myclobutanil (Systhane, Rally), Triflumizole (Procure), Triadimefon (Bayleton), Imidacloprid (Provado), Methoxyfenozide (Intrepid), and Spinosad (Success) was not available at the time this document was completed. If this information becomes available in the future, and shows evidence that they should not or cannot be screened for, they would be dropped from the final testing list. Chemicals can also be added or deleted from the final list per request by ODEQ review staff.

Proposed List of Chemicals to Monitor for Recharge Project

Fenarimol (Rubigan)
DNOC sodium salt (Elgetol)
Metalxyl (Ridomil)
DCPA, (Dacthal @ Metabolites)
1-Naphthaleneacetamide (Amid-thin)
Myclobutanil (Systhane, Rally)
Triflumizole (Procure)
Triadimefon (Bayleton)
Imidacloprid (Provado)
Methoxyfenozide (Intrepid)
Spinosad (Success)

RECEIVED

JAN 3 0 2009

WATER RESOURCES DEPT SALEM, OREGON

Pre-conditions: Using Nitrate as the Indicator

Agricultural fertilizers are the primary source of nitrate in groundwater. Nitrate concentrations greater than 2-3 mg/L in well water indicate that chemicals applied to the land surface are reaching the gorund water system, so detection of pesticides in these wells may be more likely. This relationship between nitrate concentration and pesticide detection may help identify wells at risk for contamination by pesticides. Laboratory analysis for nitrate is simpler and less costly than analysis of pesticides. Consequently, many more Central Columbia Plateau wells have been sampled for nitrate. See attached report and Rkyer, S.J. and Jones, J.L., 1995, Nitrate concentrations in ground water of the Central Columbia Plateau: U.S. Geological Survey Open-File Report 95-445, 4 p.)

After the monitoring wells and recharge facility has been constructed and before operation of the project, a preconditions water quality test will be conducted of all chemical constituents (Levels 1 and 2 from Attachment 5 Monitoring Plan). Samples will be collected from the (1) source water entering project site, (2) upgradient on-site observation well, and (3) one of the two down gradient on-site observation wells.

Working in consultation with ODEQ staff, nitrate concentrations collected from this preconditions water quality test will used along with other published information in order to determine a Warning Concentration Level (WCL). This warning concentration level will be used to screen water quality during and after operation of the recharge project. If concentrations exceed this level, operation of the recharge facility will be stopped and a Level II water quality sampling will be done on both surface and groundwater location to determine if chemicals are present. Working with ODEQ, results will be reviewed and any operation changes will implemented to avoid chemical contamination of the groundwater.

Laboratory Resources

Nitrate Analysis:

Walla Walla County-City Health Department

310 W. Popular, P. O. Box 1753

Walla Walla, WA 99362 Telephone (509) 527-3290

Chemical Analysis:

KUO Testing Labs, INC. 337 south 1st Avenue Othello, WA 99344 Telephone: (509)-488-0118

JAN 3 0 2009

Edge Analytical 1151 Knudson

Burlington, WA 98233

(360) 757-1400 (800) 755-9295 WATER RESOURCES DEPT SALEM, OREGON

RECEIVED

References and additional chemical resources used for the screening process:

Darnell, T., Topielec, R. 1996, October. Nitrates and Bacteria in Groundwater: A Second Look, Milton-Freewater Area, Umatilla County, Oregon. Oregon State University Extension Service Water Quality Program.

Darnell, T. Hart, J. Vomocil, Jim. 1989. Nitrates and Bacteria in Groundwater: Milton-Freewater, Umatilla County Oregon. Oregon State University Extension Service.

Darnell, T., Montgomery, M. L., Witt, J. M., 1989, July. Pesticides in Groundwater: Milton-Freewater, Umatilla County, Oregon. Oregon State University

U.S. Geological Survey 1996, July. Fact Sheet 171-96: <u>Article:</u> The Nitrate Connection. US Government Printing Office 774-398/20006 Region NO. 8

Kerle, E.A., Vogue, P. A., Jenkins, J. J., 1996, October. *Understanding pesticide persistence and mobility for groundwater* and surface water protection. Oregon State University Extension EM 86561

Jenkins, J. J., Thomson P. A., 1999, January. OSU Extension Pesticide Properties Database. Oregon State University Extension EM 8709

Cooperative Extension Washington State University. 2002. 2002 Crop Protection Guide for Tree Fruits in Washington. Washington State University EB0419.

Richerson, P., Cole, D. 2000, June April 1999 Milton-Freewater Groundwater Quality Study: As part of the Statewide Groundwater Monitoring Program. State of Oregon Department of Environmental Quality

http://www.cdpr.ca.gov/docs/publicreports/5698.pdf http://www.fruit.wsu.edu/labels/insecucides.htm#S http://ace.orst.edu/info/extoxnet/ http://www.pesticideinfo.org/Index.html

Attachment B

ATTACHMENT B: RECORD OF USE (2004-2008)

Recharge Seasons	Period of Operation	Hours of Diversion (actual)	Total Water Use ON HBDIC Recharge Site (acre-feet)	Water Use: Little Walla Walla Diversion to HBDIC Recharge (Conveyance Loss) (acre-feet)
Spring 2004	4/8/4 to 5/14/4	888	409	714
2004-2005	12/1/4 to 2/3/5	672	388	540
2004-2005	3/27/5 to 4/30/5	720	650	579
2005-2006	11/1/5 to 5/15/6	2544	2,813	2,046
2006-2007	11/1/6 to 5/15/7	3072	3,278	2,470
2007-2008	11/14/7 to 3/25/7	2400	1,939	1,930
2007-2008	4/10/8 to 5/15/8	840	820	676
	Total	11,136	10,297	8,955
	_		Sum of Recharge Project and Conveyance	19,252

RECEIVED

Attachment C

Attachment C: HBDIC Recharge On-Site Operations and Expansions (2004-2008)

Infiltration Area

Recharge Seasons	Period of Operation	Days of Operation (actual)	Peak Recharge Rate (cfs)	Site Expansion Phase	(feet ²)	(acres)	Total Recharge Volume (acre- feet)	Total Recharge Volume (Gallons x 1,000)	Total Rechage (acre-feet (season))
Spring 2004	4/8/4 to 5/14/4	37	8.0	I	15,000	0.3	409	133,273	409 (2004)
2004-2005	12/1/4 to 2/3/5	28	6.8	I	15,000	0.3	388	126,398	1010/2004 5
2004-2005	3/27/5 to 4/30/5	30	12.1	II	47,420	1.1	650	211,803	1038(2004-5)
2005-2006	11/1/5 to 5/15/6	106	13.2	II	47,420	1.1	2,813	916,619	2813 (2005-6)
2006-2007	11/1/6 to 5/15/7	128	12.8	II	47,420	1.1	3,278	1,068,140	3278 (2006-7)
2007-2008	11/14/7 to 3/25/7	100	18.4	II	61,987	1.4	1,939	631,962	2759 (2007-8)
2007-2008	4/10/8 to 5/15/8	35	16.8	III	61,987	1.4	820	267,125	
	Total	464				•	10,297	3,355,320	

RECEIVED

Attachment D

RECEIVED


Oregon Water Resources Department

JAN 3 0 2009

WATER RESOURCES DEPT SALEM, OREGON

Final Order Regarding Limited License Request 758

Requested Water Use



Department Review

The Department, in consultation with Oregon Department of Fish and Wildlife (ODFW), Oregon Department of Environmental Quality (ODEQ), and Confederated Tribes of the Umatilla Indian Reservation (CTUIR), has determined that the requested use may be approved as conditioned and limited below.

The use of water for artificial ground water recharge testing, as requested in limited license application 758, is a use allowed under ORS 537.143.

Sufficient water is available, as required under 690-340-0030(1)(b), for this short-term, fixed duration use. The Director may revoke the right to use water for any reason described in ORS 537.143(2).

The Department provided public notice of the application in the Department's weekly public notice as required by OAR 690-340-0030(2). The Department has received comments related to the issuance of the limited license. The authorization of limited license 758, as conditioned below, will satisfactorily address the issues raised in those comments.

Conditions and Limitations

The use of water from the Walla Walla River shall be limited to 50.0 cfs for the purpose of testing artificial ground water recharge during a testing season of November 1 through May 15. Water may only be diverted when there is adequate flow in the Walla Walla River to honor all existing water rights. When water is diverted under this limited license, the use is further limited to times when there is, at a minimum, the following streamflows in the Tum A Lum reach of the Walla Walla River, between the Little Walla Walla River diversion and Nursery Bridge Dam and flowing past

This is a final order in other than contested case. Pursuant to ORS 536.075 and OAR 137-004-080 and OAR 690-01-005 you may either petition the Director for reconsideration of this order or petition for judicial review of this order. As provided in ORS 536.075, this order is subject to judicial review under ORS 183.484. Any petition for judicial review of the order must be filed within the 60 day time period specified by ORS 183.484(2).



Nursery Bridge Dam: November - 64 cfs, December and January - 95 cfs, February to May 15 - 150 cfs. Nursery Bridge Dam is located just downstream of Nursery Bridge and is downstream of the Little Walla Walla diversion. The District 5 Watermaster, based on gage and/or streamflow measurements, shall make the determination that the above described streamflows are flowing past Nursery Bridge Dam. Diversion under this limited license shall cease when said streamflows are not being met.

Based on a review of water quality information generated during the term of this limited license or from other sources, ODEQ can require the licensee to terminate the diversion of water into the recharge area. If monitoring data or other information results in identification of potential water quality concerns ODEQ may require modifications to the existing limited license and/or require a permit to address the water quality concerns prior to reinitiating artificial ground water recharge.

The licensee shall install, maintain and operate fish screening and by-pass devices as required by the Oregon Department of Fish and Wildlife to prevent fish from entering the proposed diversion. See copy of enclosed fish screening criterial for information.

The use of water under a limited license shall not have priority over any water right exercised according to a permit or certificate, and shall be subordinate to all other authorized uses that rely upon the same source. The Director may be prompted by field regulatory activities or by any other reason to revoke the right to use water (ORS 537.143 (2) and OAR 690-340-0030 (6)).

The licensee shall give notice to the Watermaster at least 15 days, but no more than 60 days, in advance of using water. The notice shall include the location of the diversion, place of recharge, the quantity of water to be diverted and the intended use.

ORS 537.143(8) provides that a limited license cannot be issued for the same use for more than five consecutive years. This limited license provides for the maximum allowable time.

The licensee shall meter all water use and maintain a record of use, including the total number of hours of diversion and an estimate of the total quantity diverted. During the period of the limited license, the record of use shall be available for review by the Department upon request and shall be submitted to the Watermaster upon request.

Upon project completion, the licensee shall submit the record of use to the Water Resources Department.

The licensee shall conduct artificial ground water recharge testing in a manner consistent with the license application proposal. This includes monitoring the amount of water diverted from the Walla Walla River and the amount delivered to the recharge pits from the ditch.

Figs is a final order in other than contested case. Pursuant to ORS 536.075 and OAR 237-004-080 and OAR 690-01-005 you may either petition the Director for reconsideration of order or petition for judicial review of this order. As provided in ORS 536.075, this order is provided in ORS 183.484. Any petition for judicial review of the order must filed within the 60 day time period specified by ORS 183.484(2).

Order

Therefore, pursuant to ORS 537.143 and ORS 537.144, limited license 758 is issued as conditioned and limited above.

Issued February <u>15</u>, 2004

Paul R. Cleary, Director

Water Resources Department

Enclosures - limited license and fish screen criteria

cc:

Tony Justus, Watermaster, District 5

Tim Bailey, ODFW Phil Richerson, ODEQ Rick George, CTUIR RECEIVED

JAN 3 0 2009

File

WATER RESOURCES DEPT SALEM, OREGON

If you need further assistance, please contact the Water Rights Section at the address, phone number, or fax number below. When contacting the Department, be sure to reference your limited license number for better service.

Remember, the use of water under the terms of this limited license is not a secure source of water. Water use can be revoked at any time. Such revocation may be prompted by field regulatory activities or by any other reason.

Water Rights Section
Oregon Water Resources Department
158 12th ST NE
SALEM, OR 97310

Phone: (503)378-8455 Fax: (503)378-6203

FISH SCREENING CRITERIA FOR WATER DIVERSIONS

This summary describes ODFW fish screening criteria for all fish species.

Screen material openings for ditch (gravity) and pump screens must provide a minimum of 27% open area:

Perforated plate: Openings shall not exceed 3/32 or 0.0938 inches (2.38 mm).

Mesh/Woven wire screen: Square openings shall not exceed 3/32 or 0.0938 inches (2.38 mm) in the narrow direction, e.g., 3/32 inch x 3/32 inch open mesh.

Profile bar screen/Wedge wire: Openings shall not exceed 0.0689 inches (1.75 mm) in the narrow direction.

Screen area must be large enough not to cause fish impact. Wetted screen area depends on the water flow rate and the approach velocity.

Approach velocity: The water velocity perpendicular to and approximately three inches in front of the screen face.

Sweeping velocity: The water velocity parallel to the screen face.

Bypass system: Any pipe, flume, open channel or other means of conveyance that transports fish back to the body of water from which the fish were diverted.

Active pump screen: Self cleaning screen that has a proven cleaning system.

Passive pump screen: Screen that has no cleaning system other than periodic manual cleaning.

Screen approach velocity for ditch and active pump screens shall not exceed 0.4 fps (feet per second) or 0.12 mps (meters per second). The wetted screen area in square feet is calculated by dividing the maximum water flow rate in cubic feet per second (1 cfs = 449 gpm) by 0.4 fps.

Screen sweeping velocity for ditch screens shall exceed the approach velocity. Screens greater than 4 feet in length must be angled at 45 degrees or less relative to flow. An adequate bypass system must be provided for ditch screens to safely and rapidly collect and transport fish back to the stream.

Screen approach velocity for passive pump screens shall not exceed 0.2 fps or 0.06 mps. The wetted screen area in square feet is calculated by dividing the maximum water flow rate by 0.2 fps. Pump rate should be less than 1 cfs.

For further information please contact:

Bernie Kepshire
Oregon Department of Fish and Wildlife
7118 NE Vandenberg Avenue
Corvallis, OR 97330-9446
(541)757-4186 x255
bernard.m.kepshire@state.or.us

RECEIVED

JAN 3 0 2009

WATER RESOURCES DEPT SALEM, OREGON

Attachment E

This page to be completed by the local Watermaster.

WATER AVAILABILITY STATEMENT

Na	lame of Applicant: Hudson Bay District Irrigation Co. Application Number:	
1.	. To your knowledge, has the stream or basin that is the source for this applicate for prior rights?	ion ever been regulated
	✓ Yes No	
	If yes, please explain:	
	The Walla Walla River is typically short of water to serve all rights in Ju September and October.	ıly, August,
2.	. Has the stream or basin that is the source for this application ever been regular flows?	ed for minimum stream
	Yes V No	
	If yes, please explain:	
3.	Do you observe this stream system during regular fieldwork?	
		RECEIVED
	Yes No If yes, what are your observations for the stream?	JAN 3 0 2009
		JAN 3 0 2003
	Typically there is extra water from November to June.	WATER RESOURCES DEPT SALEM, OREGON
4.	Based on your observations, would there be water available in the quantity and supply the development proposed by this application? Yes No What would you recommend for conditions on a permit that may be issued application similarly to Hudson Bays permit #53662. Allow diversion	proving this application?
	excess of 64cfs in November, 95cfs in December and January, and 13 May 15 each year.	
5.	Any other recommendations you would like to make?	
Sig	gnature WM District #: 5 Da	ate: 10/31/03

Oregon Water Resources Department

Final Order Regarding Limited License Request 758

Requested Water Use



On November 11, 2003 the Water Resources Department received completed LL request 758 from Hudson Bay District Irrigation Company for the use of 50.0 cfs from the Walla Walla River, located in the SW1/4, NE1/4, Section 12, Township 5 North, Range 35 East, W.M., for the purpose of artificial ground water recharge testing, for a period of five years, pursuant to ORS 537.143 and 537.144.

Department Review

The Department, in consultation with Oregon Department of Fish and Wildlife (ODFW), Oregon Department of Environmental Quality (ODEQ), and Confederated Tribes of the Umatilla Indian Reservation (CTUIR), has determined that the requested use may be approved as conditioned and limited below.

The use of water for artificial ground water recharge testing, as requested in limited license application 758, is a use allowed under ORS 537.143.

Sufficient water is available, as required under 690-340-0030(1)(b), for this short-term, fixed duration use. The Director may revoke the right to use water for any reason described in ORS 537.143(2).

The Department provided public notice of the application in the Department's weekly public notice as required by OAR 690-340-0030(2). The Department has received comments related to the issuance of the limited license. The authorization of limited license 758, as conditioned below, will satisfactorily address the issues raised in those comments.

Conditions and Limitations

The use of water from the Walla Walla River shall be limited to 50.0 cfs for the purpose of testing artificial ground water recharge during a testing season of November 1 through May 15. Water may only be diverted when there is adequate flow in the Walla Walla River to honor all existing water rights. When water is diverted under this limited license, the use is further limited to times when there is, at a minimum, the following streamflows in the Tum A Lum reach of the Walla Walla River, between the Little Walla Walla River diversion and Nursery Bridge Dam and flowing past

This is a final order in other than contested case. Pursuant to ORS 536.075 and OAR 137-004-080 and OAR 690-01-005 you may either petition the Director for reconsideration of this order or petition for judicial review of this order. As provided in ORS 536.075, this order is subject to judicial review under ORS 183.484. Any petition for judicial review of the order must be filed within the 60 day time period specified by ORS 183.484(2).

Nursery Bridge Dam: November - 64 cfs, December and January - 95 cfs, February to May 15 - 150 cfs. Nursery Bridge Dam is located just downstream of Nursery Bridge and is downstream of the Little Walla Walla diversion. The District 5 Watermaster, based on gage and/or streamflow measurements, shall make the determination that the above described streamflows are flowing past Nursery Bridge Dam. Diversion under this limited license shall cease when said streamflows are not being met.

Based on a review of water quality information generated during the term of this limited license or from other sources, ODEQ can require the licensee to terminate the diversion of water into the recharge area. If monitoring data or other information results in identification of potential water quality concerns ODEQ may require modifications to the existing limited license and/or require a permit to address the water quality concerns prior to reinitiating artificial ground water recharge.

The licensee shall install, maintain and operate fish screening and by-pass devices as required by the Oregon Department of Fish and Wildlife to prevent fish from entering the proposed diversion. See copy of enclosed fish screening criterial for information.

The use of water under a limited license shall not have priority over any water right exercised according to a permit or certificate, and shall be subordinate to all other authorized uses that rely upon the same source. The Director may be prompted by field regulatory activities or by any other reason to revoke the right to use water (ORS 537.143 (2) and OAR 690-340-0030 (6)).

The licensee shall give notice to the Watermaster at least 15 days, but no more than 60 days, in advance of using water. The notice shall include the location of the diversion, place of recharge, the quantity of water to be diverted and the intended use.

ORS 537.143(8) provides that a limited license cannot be issued for the same use for more than five consecutive years. This limited license provides for the maximum allowable time.

The licensee shall meter all water use and maintain a record of use, including the total number of hours of diversion and an estimate of the total quantity diverted. During the period of the limited license, the record of use shall be available for review by the Department upon request and shall be submitted to the Watermaster upon request.

Upon project completion, the licensee shall submit the record of use to the Water Resources Department.

The licensee shall conduct artificial ground water recharge testing in a manner consistent with the license application proposal. This includes monitoring the amount of water diverted from the Walla Walla River and the amount delivered to the recharge pits from the ditch.

This is a final order in other than contested case. Pursuant to ORS 536.075 and OAR 137-004-080 and OAR 690-01-005 you may either petition the Director for reconsideration of this order or petition for judicial review of this order. As provided in ORS 536.075, this order is subject to judicial review under ORS 183.484. Any petition for judicial review of the order must be filed within the 60 day time period specified by ORS 183.484(2).

Order

Therefore, pursuant to ORS 537.143 and ORS 537.144, limited license 758 is issued as conditioned and limited above.

Issued February 1, 2004

Paul R. Cleary, Director

Water Resources Department

Enclosures - limited license and fish screen criteria

cc:

Tony Justus, Watermaster, District 5

Tim Bailey, ODFW Phil Richerson, ODEQ Rick George, CTUIR

File

If you need further assistance, please contact the Water Rights Section at the address, phone number, or fax number below. When contacting the Department, be sure to reference your limited license number for better service.

Remember, the use of water under the terms of this limited license is not a secure source of water. Water use can be revoked at any time. Such revocation may be prompted by field regulatory activities or by any other reason.

Water Rights Section
Oregon Water Resources Department
158 12th ST NE
SALEM, OR 97310

Phone: (503)378-8455 Fax: (503)378-6203

FISH SCREENING CRITERIA FOR WATER DIVERSIONS

This summary describes ODFW fish screening criteria for all fish species.

Screen material openings for ditch (gravity) and pump screens must provide a minimum of 27% open area:

Perforated plate: Openings shall not exceed 3/32 or 0.0938 inches (2.38 mm).

Mesh/Woven wire screen: Square openings shall not exceed 3/32 or 0.0938 inches (2.38 mm) in the narrow direction, e.g., 3/32 inch x 3/32 inch open mesh.

Profile bar screen/Wedge wire: Openings shall not exceed 0.0689 inches (1.75 mm) in the narrow direction.

Screen area must be large enough not to cause fish impact. Wetted screen area depends on the water flow rate and the approach velocity.

Approach velocity: The water velocity perpendicular to and approximately three inches in front of the screen face.

Sweeping velocity: The water velocity parallel to the screen face.

Bypass system: Any pipe, flume, open channel or other means of conveyance that transports fish back to the body of water from which the fish were diverted.

Active pump screen: Self cleaning screen that has a proven cleaning system.

Passive pump screen: Screen that has no cleaning system other than periodic manual cleaning.

Screen approach velocity for ditch and active pump screens shall not exceed 0.4 fps (feet per second) or 0.12 mps (meters per second). The wetted screen area in square feet is calculated by dividing the maximum water flow rate in cubic feet per second (1 cfs = 449 gpm) by 0.4 fps.

Screen sweeping velocity for ditch screens shall exceed the approach velocity. Screens greater than 4 feet in length must be angled at 45 degrees or less relative to flow. An adequate bypass system must be provided for ditch screens to safely and rapidly collect and transport fish back to the stream.


Screen approach velocity for passive pump screens shall not exceed 0.2 fps or 0.06 mps. The wetted screen area in square feet is calculated by dividing the maximum water flow rate by 0.2 fps. Pump rate should be less than 1 cfs.

For further information please contact:

Bernie Kepshire
Oregon Department of Fish and Wildlife
7118 NE Vandenberg Avenue
Corvallis, OR 97330-9446
(541)757-4186 x255
bernard.m.kepshire@state.or.us

Hudson Bay Aquifer Recharge Project

An application for ASR Testing Limited License to Oregon Water Resources Department (OWRD) (OAR 690-350-0020)



Prepared for the HBDIC by:

Walla Walla Basin Watershed Council Kennedy and Jenks Consultants, Inc.

October 20, 2003

Table of Contents

Table of Contents	2
Introduction	
Overview of Watershed Conditions	4
Figure 1 Scaled Map of Project and Surrounding Area	7
Figure 2 WWBW Monitoring and Recharge Site Map	
Attachment 1. Project Layout, 690-350-0020(3)(a)(E) and (I) and 690-350-0020(3)(b)(B)	10
Engineering Attachments:	11
Attachment 1A: Location Map	11
Attachment 1B: Site Plan	
Attachment 1C: Structure Details	11
Attachment 1D: Structure Reinforcing Steel	11
Attachment 1E: Signed and Stamped Copy of Project Engineering Report	11
Attachment 2. Water Rights Statement, 690-350-0020(3)(a)(F) and (G)	12
Water Right Applicant:	12
Hudson Bay District Improvement Co	12
Source of Water:	12
Purpose of Use:	12
Proposed Period of Use:	12
Point of Diversion Location:	12
Minimum Instream Flow Information:	
Attachment 3. Land Use Approval, 690-350-0020(3)(a)(H)	14
Land Use Attachments	14
Attachment 3A: Umatilla County Land Use Approval	14
Attachment 3B: Lease Agreement with Landowner	14
Attachment 4. Proposed Test Program, 690-350-0020(3)(b)(A)	15
Introduction	15
Preliminary Test Site-Specific Hydrogeologic Characterization	15
Soil Characteristics	
Geology	
Hydrogeology	
Surface Water	
Water Quality	
Characterization Conclusions	
Preliminary Test Site Operation Plan	
Site Construction	
Test Operations	
Test Timing, Monitoring, and Water Quantities	
Outside Influences	
Responsible Parties and Access Permission	
Mitigation	
Reporting	
Attachment 5. Proposed Monitoring Program, 690-350-0020(3)(b)(A)	
Overview of Basin Wide Monitoring Plan	23
Recharge Project Monitoring Plan	23
Sampling and Analysis Program	24
(1) Source Water at Test Site	24
(2) Site Groundwater	
(3) Distal Groundwater	
(4) Surface Water (Springs)	26
Sampling Parameters	

Sampling Procedure	27		
Equipment			
Water Level	27		
Decontamination	28		
Purging and Field Parameters (On site wells only)			
Water Sampling	28		
Resampling	29		
Chain of Custody and Sample Handling	29		
Field Records and Data Validation	29		
Data Reporting and Statistical Analysis			
Record Keeping	30		
Evaluation			
Data evaluation will include:			
Annual Review and Reporting			
Final Recharge Test Project Report			
Monitoring Plan Attachments	31		
Attachment 5A. Methodology Water Quality Assessment and Evaluation	31		
Attachment 5B. Figure 5A Map of On-site Recharge Well Locations	31		
Attachment 5C Chemicals of interest for Hudson Bay Recharge Project			
Attachment 6. Site Hydrogeology, 690-350-0020(3)(b)(C), (E), and (G) (attached)			
Attachment 7. Source Water Quality, 690-350-0020(3)(b)(D)	32		
Overview	32		
Attachment 7A Source Water Quality Information	32		
Resources and References:	33		
ATTACHMENTS	34		
ATTACHMENTS			
Attachment 8A Water Availability (Water Waster)			
8B Applicator form - OWILD			

Introduction

The Walla Walla Basin Watershed Council (WWBWC), in cooperation with the Hudson Bay District Improvement Company (HBDIC), has proposed to test shallow aquifer recharge at a site located adjacent to the HBDIC's White Ditch in section 33, T6N, R35E. At the test site a series of three infiltration pits will be built. Water will be supplied to these pits via a diversion from the canal. Recharge activities are proposed during the winter and spring months, when the Walla Walla River (the source of water for the canal) is running at higher flows. The proposed shallow aquifer recharge testing would be done under an ASR Testing Limited License granted by Oregon Water Resources Department (OWRD) (OAR 690-350-0020). By recharging shallow groundwater it is hoped that a portion of the recharge water will return to restore diminished spring-creek and Walla Walla River baseflows. Testing will not include removal of stored water by pumping or other artificial means.

The Limited License Application requires several supporting documents be attached (690-350-0020 (3)(b)), including (but not limited to) those describing proposed testing, groundwater conditions (including hydrogeologic conditions and groundwater quality), and source water quality. Information not included in this assessment report, but still needed for the application, will be collected during proposed site-specific hydrogeologic characterization, monitoring, and testing process. This limited license application is to gain approval of the proposed shallow aquifer recharge testing. The complete list of Attachments as called for in include:

Attachment 1. Project Layout and Size, 690-350-0020(3)(a)(E) and (I) and 690-350-0020(3)(b)(B)

Attachment 2. Water Rights Statement, 690-350-0020(3)(a)(F) and (G)

Attachment 3. Land Use Approval, 690-350-0020(3)(a)(H)

Attachment 4. Proposed Test Program, 690-350-0020(3)(b)(A)

Attachment 5. Proposed Monitoring Program, 690-350-0020(3)(b)(A)

Attachment 6. Site Hydrogeology, 690-350-0020(3)(b)(C), (E), and (G)

Attachment 7. Source Water Quality, 690-350-0020(3)(b)(D)

Overview of Watershed Conditions

The quantity, storage, timing, and availability of water are several major challenges facing watershed managers in the Walla Walla River Basin. The relationship between the Walla Walla River and its distributaries with that of the shallow alluvium aquifer has been shown to be highly interdependent (Piper, 1933, Newcomb, 1965, Barker & McNish, 1975, Bower et. al., 2001). The Walla Walla Basin Watershed Council, Walla Walla Watershed Alliance, and Hudson Bay District Improvement Company (HBDIC), working with their partners in OWRD, ODEQ and ODFW, propose to explore the utility of artificially recharging the shallow alluvial aquifer as a way to help offset the loss of natural recharge opportunities throughout the basin.

Surface water and shallow groundwater in the Walla Walla Basin (the Basin) form an interconnected system. In some areas, especially upstream areas where streams leave the mountains and highlands surrounding the Basin to flow out onto the Basin floor, streams historically probably branched out onto the Basin floor and some of the water they carried seeped into the ground, recharging the shallow groundwater system. This shallow groundwater, recharged near the edge of the Basin, formed the main source of clean, cool groundwater found further down basin where it returned to the surface via springs and base flow to the Walla Walla River. Through the years, the issuance of hundreds of surface and groundwater rights has resulted in the allocation of nearly all of the naturally available water in the basin. These allocations have pressured water resources, compelling the

Washington State Department of Ecology to close ground waters to further appropriations due to concerns about dropping water table levels. Other indicators of overstressed water resources include: (1) dry or dropping well levels, some wells in OWRD's inventory of state-observation-wells, (2) dry or dropping flow volumes in the spring branches, and (3) loss of natural and artificial groundwater recharge opportunities through irrigation efficiency and improved surface water management.

The state of Oregon has recognized use of artificial recharge as a tool "that can be an effective and efficient method for storing water for futures uses." (OWRD, Umatilla Basin Report, 1988). Artificial recharge has been shown to work in other areas of Umatilla County such as the County Line Water Improvement District Project, in operation since 1977. An OWRD review of this project states "It has been instrumental in arresting and reversing ground water level declines in a portion of the Ordnance Critical Ground Water Area." (OWRD, 1988). The USGS also noted the need for artificial recharge in the Walla Walla valley to offset increased water demands and loss of natural and artificial recharge mechanisms: "(Irrigation efficiency measures) can diminish the infiltration to recharge the ground water," wrote Newcomb in his important 1965 report. "Consequently, any such plans for changes in river regimen could well be required to provide for compensatory recharge or to sustain counter charges for their diminution of natural recharge and storage.

This project will comprise of three major components: Construction-Operation, Monitoring-Evaluation and Outreach-Education.

Construction-Operation: After receiving the appropriate permits and/or approval from OWRD, OWDF, ODEQ, USFWS, NOAA Fisheries and the Umatilla County Planning Department, a series of three pits specifically designed for passive artificial recharge will be constructed on land provided by the Hudson District Improvement Company (HBDIC). The land is being leased from one of the district's patrons by the HBDIC and a written agreement for the lease has been secured. The pits will be constructed in such a way to maximize recharge rates while minimizing the ground water quality impacts during the winter/spring recharge period. Project features include a concrete check structure in adjacent White Ditch, a concrete flow-measuring flume, an open connection ditch, three excavated pits, pipes connecting the pits and an outflow ditch from the down stream pit. These pits are designed to handle 50 cubic feet per second (cfs) of water anticipated to be available during the winter/spring Walla Walla River runoff. The actual volume of winter-spring water delivered will depend on the above-mentioned permitting and review process and the actual field verified constraints once in operation. Operation of this structure will be based on the instructions provided by OWRD in the operation permit and agreed to by the various project partners and agencies.

Monitoring-Evaluation: Monitoring of project will be conducted at several levels including: (1) onsite subsurface hydrologic and hydrogeologic monitoring, (2) off-site subsurface hydrologic and hydrogeologic monitoring, (3) off-site surface monitoring of springs through flow and photo-point measurements, (4) on/off-site water quality monitoring of key physical and chemical properties. The results of this intensive monitoring will be evaluated to identify impacts of the proposed project on groundwater levels and flow beneath and around the site, on surface water and spring discharges down gradient of the site, and on base flow to the Walla Walla River. Monitoring will also identify potential problems associated with the project


Outreach-Education: This project will also serve as an important outreach and education tool for the general public and water users of the Walla Walla valley. Particular focus and time will be spent on utilizing the site and the results for the recharge analysis to educate people on the role that ground water plays in the rivers and streams of the Walla Walla Watershed.


This project meets all of the habitat restoration actions from the Oregon Aquatic Habitat Restoration and Enhancement Guide including:


- 1. Change the trend of aquatic habitat function from one of a diminishing ability to support salmonids and other organisms to one that supports a complex, self-sustaining system. Such systems provide high quality habitat and ecological capacity for salmonids and other species; or
- 2. Correct or improve conditions caused by past management and/or disturbance events; or
- 3. Maximize beneficial habitat in the short term where watershed degradation has been extensive and natural processes will need substantial time to restore habitat; or
- 4. Create beneficial habitat and restore stream function to the fullest extent possible within developed areas where no reasonable expectation of returning to natural conditions exists.

HUDSON BAY AQUIFER RECHARGE PROJECT LOCATED IN THE NE_4^1 OF SEC33, T6 N, R35E W.M.

Figure 1 Scaled Map of Project and Surrounding Area








HUDSON BAY AQUIFER RECHARGE PROJECT LOCATED IN THE NE 1/4 OF SEC33, T6 N, R35E W.M. FIGURE 1A

Figure 2 WWBW Monitoring and Recharge Site Map



Attachment 1. Project Layout, 690-350-0020(3)(a)(E) and (I) and 690-350-0020(3)(b)(B)

Prepared by Bernard Hewes, Licensed Engineer in the State of Oregon.

This project entails diverting water from an existing irrigation ditch to three pits to be excavated for the purpose of infiltrating the water into the shallow aquifer. Project features include a concrete check structure in the existing White Ditch, a concrete flow measuring flume, an open ditch, three excavated pits, pipes connecting the pits and an outflow ditch from the down stream pit.

These items were sized to handle 50 cubic feet per second (cfs) of water. This is the amount anticipated will be available from excess flow in the Walla Walla River and that the Hudson Bay District is able to deliver.

Data gathered to design the project consisted of a site topographic survey and installing two sites for testing the water infiltration capacity of the natural materials and determining the layers in the soil profile. In addition the Soil Survey of Umatilla County Area, Oregon was consulted. This is a US Dept. of Agriculture, Natural Resources Conservation Service publication giving general soils information.

The topographic survey data was used to prepare a topographic map with one foot contour intervals at a scale of 1" = 60'. This information was used to help determine the location of the project features.

Two test pits were excavated to a depth of 6'-7' each. A 24" diameter by 5' long section of corrugated metal pipe was set on end in the bottom of the pit and about one foot of fill placed around it to hold it in place. Water was pumped into the pipe at a rate that would sustain a water depth of one foot in the pipe. Both flow rate and total flow was measured. The test was run for 6.25 hours in the first pit and 3.5 hours for the second pit.

PIT #1

Soil profile:

0-12" sandy loam

12"-36" gravelly sandy loam, approximately 50% of the material volume is gravel size particles with an estimated D 50 size of about 0.75"

36"-48" sandy loam, in parts of the trench this layer does not exist

48"-?" gravelly sandy loam approximately 20% of the volume is gravel size particles

The inflow rate at the end of the test period was 4.0 gallons per minute (gpm). This resulted in an infiltration rate of 1.7 gpm/sq. ft./ foot of head.

PIT #2

Soil profile:

0"-13" gravelly sandy loam

13"-39" cobbly sandy loam, the D50 of the gravel is approximately 1"

39"-52" gravelly sandy loam

52"-? sand gravel mix D 50 estimated to be about 0.25"

In this pit the inflow rate of 11.9 gpm was maintained for 3.5 hours and at no time did water puddle in the bottom of the pipe. The infiltration rate is in excess of 3.8 gpm/sq. ft.

The area needed for infiltrating the water was determined assuming an infiltration rate for the entire area of 3.0 gpm/sq.ft./ per foot of head. For an inflow rate of 50 cfs the infiltration area needs to be

7480 square feet. The infiltration rate of 3.0 gpm/sq.ft. was chosen because the pits will be located in the area with soil surface texture similar to test pit #2.

Due to the possibility of fine soil particles plugging the infiltration area, unknowns concerning the long-term infiltration rate and that the amount of water available is not yet known extra infiltration area is being provided. Three separate pits with bottom dimensions of 50 feet X 100 feet are proposed. This will provide an infiltration area of 15,000 square feet.

The pits will be excavated to a depth of about 5 feet to get below the second sandy loam layer noted in both test pits. This will allow the water depth to be 2.5 feet - 3.5 feet. That will increase the rate of infiltration over the test values derived with one foot of water depth. The overall safety factor for the infiltration area is well over 2.

Inflow to the system will be measured with a ramp flume and continuously recorded. The ramp flume is sized to provide 5% flow rate accuracy over a flow range of 10 cfs-50 cfs

Any outflow from the last pit will be safely returned to the White Ditch through a 12-inch pipe. The pipe will be on a slope that will keep water from flowing out of White Ditch.

Engineering Attachments:

Attachment 1A: Location Map

Attachment 1B: Site Plan

Attachment 1C: Structure Details

Attachment 1D: Structure Reinforcing Steel

Attachment 1E: Signed and Stamped Copy of Project Engineering Report

Attachment 2. Water Rights Statement, 690-350-0020(3)(a)(F) and (G)

Water Right Applicant:

Hudson Bay District Improvement Co.

P.O. Box 110

Milton-Freewater, Oregon 97862

Project Contact: John Zerba, WBDIC Board Member

Telephone: (541)-938-6100

Operations Contact: Jon Brough, WBDIC District Manager

Telephone: (541)-520-2856

Recharge Project Manager (WWBWC), Bob Bower, Hydrologist

Telephone: (541)-938-2170

Source of Water:

Walla Walla River, a tributary of the Colombia River, within the Umatilla River Basin.

Purpose of Use:

Artificial Groundwater Recharge using water diverted during the fall, winter, and spring freshet flows on the Walla Walla River and utilizing the HBDIC recharge structure near Milton-Freewater, Oregon.

Proposed Period of Use:

November 1 through May 15 and as Further limited below

Point of Diversion Location:

NE ½ NW ½, Section 1, SW ½ NE ¼ Section 12, T5N, R35E, W.M.; <u>DFV.PT. 1</u> 910 Feet South and 700 Feet West from North ¼ Corner Section 1; <u>DIV. PT. 2</u> – 1030 Feet North and 900 Feet East From the Center ¼ Corner Section 12.

Minimum Instream Flow Information:

When water is diverted under this permit, the use is further limited to times when there is, at a minimum, the following streamflows in the Tum-a-lum branch (mainstem) of the Walla Walla River, between the Little Walla Walla River diversion and Nursery Bridge Dam and flowing past Nursery Bridge Dam.

Utilizing the Minimum Perennial Streamflows information (table 1, page 31) in OWRD Umatilla Basin Report (OWRD, 1988) and HBDIC's current winter water diversion permit (Permit Number 53662) the following represent the minimum instream flows at Nursery Bridge Dam:

- November 64 cfs
- December through January 95 cfs
- February through May 15 132 cfs

Nursery Bridge is located just downstream of Nursery Bridge and is downstream of the Little Walla Walla Diversion, the East Side Canal and the District's Canal, also described as point of diversion 1 in this application.

In order for diversion to occur under this permit, the above described streamflows must be met in the Tum-a-lum branch of the Walla Walla River, between the Little Walla Walla River diversion and Nursery Bridge Dam and following past Nursery Bridge Dam (see OWRD permit (Permit Number 53662 for operating and maintenance requirements for this station). Said streamflows shall be measured at the gauging station described below. In the event the primary gage experiences mechanical difficulties, stream flows at Nursery Bridge Dam shall be calculated by subtracting from the streamflows at Little Walla Walla Diversion (Cemetery Bridge) from those streamflows recorded at either the WWBWC gauge at Grove School Bridge or a combination of streamflows at OWRD's North and South Fork stations (#s).

Attachment 3. Land Use Approval, 690-350-0020(3)(a)(H)

The HBDIC recharge project staff has consulted with both the Umatilla County Planning department and the current landowner (Hulette Johnson). Attached you will find two documents addressing the anticipated land use and zoning issues needed for construction and operation of this project. The first (Attachment 3A) a Land Use Form approved by the Umatilla County Planning Department. This was originally submitted as a requirement in the funding request to the Oregon Watershed Enhancement Board. The second Attachment (Attachment 3B) was is a lease agreement between the HBDIC and the current landowner and water right holder, Hulette Johnson.

Land Use Attachments

Attachment 3A: Umatilla County Land Use Approval Attachment 3B: Lease Agreement with Landowner

Attachment 4. Proposed Test Program, 690-350-0020(3)(b)(A)

Introduction

The Walla Walla Basin Watershed Council (WWBWC), in cooperation with the Hudson Bay Improvement District (HBID), has proposed to test shallow aquifer recharge at a site located adjacent to the Hudson Bay Canal in section 33, T6N, R35E. At the test site a series of three infiltration pits will be built. Water will be supplied to these pits via a diversion from the canal. Recharge activities are proposed for winter and spring months when the Walla River (the source of water for the canal) is at peak annual flows. The proposed shallow aquifer recharge testing will be done under an ASR Testing Limited License granted by Oregon Water Resources Department (OWRD) (OAR 690-350-0020).

Preliminary Test Site-Specific Hydrogeologic Characterization

Site-specific hydrogeologic characterization is designed to identify and define local conditions to provide a technical basis for designing the monitoring which will be used to evaluate testing. For this project a number of characterization needs are outlined in the 3 July 2003 hydrogeologic assessment letter report (Attachment 6). These needs include determining the physical properties of the geologic units underlying the test site, investigating the presence of a possible semi-confined aquifer in the upper part of the suprabasalt aquifer system, identifying aquifer hydraulic properties, and establishing suprabasalt aquifer baseline conditions, including seasonal variation, for groundwater depth, flow direction, and quality. These, and other site characterization issues, will be addressed using test site-specific hydrogeologic characterization data collected predominantly using:

- 1. Test pits, boreholes, and wells constructed for the direct observation of `subsurface conditions
- 2. Infiltration tests (constant and falling head) designed to evaluate spatial variability at a site both laterally and vertically (note, the water source for this activity may require a temporary permit)
- Aquifer testing and water level measurements to evaluate baseline aquifer physical conditions before testing
- 4. Surface and ground water quality data collected to evaluate the affect (if any) of test site operation on area groundwater quality
- 5. Well and canal records describing water use in the project area
- Water flow metering at the test site that indicates surface water in-flow and out-flow during testing

At this time, geophysical investigations are not being considered because of the lack of subsurface control and ground truth data that could be used to constrain geophysical interpretations. The following sections describe proposed soils, geologic, hydrogeologic, surface water, and water quality characterization for this project.

Soil Characteristics

The HBDIC recharge project will be constructed by excavating the top 5 feet (72 inches) of soil from each of the recharge pits (See Engineering Design Report, ATTACHMENT 1). Test Pits constructed and evaluated in the Engineering Design Report provide site-specific soil profile information. Additionally, the "Soil Survey of Umatilla County Area, Oregon, (USDA, 1988) provides some general information about soil in the upper 60 inches at the project site. The two soils

present at the site are: Freewater (29A) and Cowsly (22C). As the entire soil layer will be removed during construction, it was not found useful to further characterize the specific soil properties further.

Geology

Geologic features control the physical characteristics of aquifer hosting materials, and therefore the distribution and movement of groundwater through an aquifer. Understanding the nature and occurrence of these features, both regionally and locally, provide constraints on testing, data interpretation, monitoring, mitigation, and final design. The objective of geologic characterization is to develop a three dimensional physical framework that describes the materials hosting the vadose zone and groundwater at the test site. Within this framework, or conceptual model, the nature and distribution of those factors thought to control groundwater movement and distribution will be evaluated.

Site-specific geologic characterization will be accomplished largely through the analysis of data collected during the drilling of several proposed boreholes at the site and comparison of that data to information collected during the preparation of the hydrogeologic assessment report. A minimum of three boreholes are proposed for the immediate vicinity of the test site. One of these boreholes will be located on the inferred up-gradient side of the test site, two will be located on the inferred downgradient side (Attachment 5C). As testing progresses, additional boreholes may be drilled to collect additional characterization, testing, and/or monitoring data. Subsurface hydrogeologic conditions will be interpreted via drilling cuttings and spilt-spoon sample logging.

The project hydrogeologic assessment identified work needed to complete site-specific hydrogeologic characterization. Hydrogeologic characterization targets, and the rational for them, are described below.

It is likely that the uppermost, unconfined part of the shallow aquifer system, is hosted by predominantly uncemented alluvial gravel beneath the test site. However, it is not clear from the available data how deep the alluvial gravels extend and what their properties are beneath the test site. Identifying the three-dimensional extent of these strata is critical to the proposed testing because water probably will move more rapidly through these uncemented strata, both downwards and laterally, then in the deeper, more cemented Mio-Pliocene conglomerate that comprises the majority of the shallow aquifer system in the area.

Area data indicates that, if present, the unconfined part of the shallow aquifer system at the site may be relatively thin and underlain by a semi-confined zone at depths of less than 75 feet. Characterization will identify if this semi-confined zone is actually present, and if found, the nature of the confining layer separating it from the overlying unconfined zone and the basic hydrologic properties of the semi-confined zone. Knowing the nature and extent of the confined aquifer underlying the site is critical in evaluating if the proposed recharge will affect this deeper aquifer. If data collected indicates that the project could potentially affect this deeper aquifer, monitoring will need to be designed to not only assess shallower unconfined aquifer impacts but deeper confined aquifer impacts as well.

The nature and distribution of the confining layer atop the confined aquifer should be identified in order to support evaluation of the thickness and distribution of the unconfined aquifer (if present). If the unconfined aquifer is absent, or only present seasonally, we will still need to identify the nature and extent of the confining layer because, just as it inhibits upward movement of groundwater, it will restrict the downward movement of recharge water. Knowing where the confining layer is will provide information on where recharge water may potentially collect atop this layer and where it will potentially spread to.

Mapping for the assessment identified a potential depression in the top of the older Mio-Pliocene conglomerate below the western end, and west of, the test site. The depth, shape, and orientation of this feature will need to be evaluated because it will effect how the aquifer(s) underlying the test site responds to the testing. If an unconfined aquifer indeed underlies the site, this depression may act as a "reservoir" for water introduced into this aquifer. Alternatively, it may serve as a recharge pathway, hydrologically connecting the upper, unconfined part of the suprabasalt aquifer system with deeper, confined parts of the aquifer system.

Hydrogeology

Piezometers and/or observation wells will be constructed in the borings drilled for geologic characterization. If additional geologic characterization boreholes are drilled (either close to or more distal from the test site) one or more of these also may be converted to observation wells. All but one of the boreholes converted to monitoring wells will be completed as 2-inch observation wells that fully penetrate the unconfined aquifer (if present) or above the confining layer (if unconfined aquifer not present). At least one of the geologic characterization boreholes should be of sufficient size to accommodate a 4-inch diameter well which will be used for aquifer testing.

Test site-specific hydrogeologic work would be done, in large part, concurrently with the site-specific geology work. The hydrogeologic assessment concluded that the following information must be collected for the uppermost part of the suprabasalt system at the test site:

- 1. Depth, thickness, and lateral and vertical extent of the vadose zone and the uppermost aquifer(s) underlying a site.
- 2. Nature and effect of perching layers (if any) in the vadose zone.
- 3. Aquifer and vadose zone physical and hydrologic properties including, grain size, matrix content, induration, hydraulic conductivity, transmissivity, and porosity
- 4. Groundwater flow direction and velocity, including both spatial and temporal variation
- Anthropomorphic effects, primarily changes in groundwater pumping, surface water (including canals), and irrigation activities.

For characterization it is important to build monitoring (or observation) wells in such a way as to provide means for accurately measuring the target aquifer. Well construction considerations are listed below:

- 1. Most project observation wells will probably be 2 inch-diameter piezometer type installations. These should be built to ensure that they are monitoring the anticipated aquifer targets, and we recommend building to well construction standards and avoiding cost cutting measures designed to get more/cheaper wells (these commonly result in poorly built wells unsuitable for collection of the high quality data we feel is necessary to support the project).
- 2. For aquifer testing, a 4 inch-diameter observation well is the minimum recommended diameter and at least one such well should be built.
- 3. The minimum number of observation wells at the test site is 3, one up-gradient and 2 down-gradient. If funding can be procured we recommend that more than 3 observation wells be installed. Most, if not all, of these additional observation wells could be built in geotechnical borings drilled for geologic characterization.

In addition to the observation wells built near the test site, it seems likely that observation wells will eventually need to be built more distant from the site. The purpose of these observation wells would be to more accurately trace the down gradient migration of recharge water away from the test site. A minimum of 3 more distant observation wells, 1 up-gradient and 2 down-gradient is again recommended. These might include at least some previously built groundwater supply wells that would be available for use. However, these should only be used if construction details can be verified and if they are not being used as water supply wells. Access to offsite observation well drilling locations will need to be acquired from willing landowners. The WWBWC currently has a network of existing wells that could be used for the purpose of tracking the recharge water distally from the site.

Aquifer testing designed to collect aquifer hydraulic property data will be part of site characterization. During aquifer testing, the 2-inch observation wells will be monitored to observe the effects of testing on the surrounding aquifer. Aquifer testing would include an 8-hour step-drawdown test to establish probable sustainable yields in the suprabasalt aquifer, followed by a 24 to 72 hour constant discharge test. Water level data collected during aquifer testing will be analyzed using standard analysis techniques.

Combining the interpretations developed in the completed hydrogeologic assessment with the drilling and testing data collected during site-specific characterization, a conceptual model of test site hydrogeologic conditions will be prepared.

Surface Water

One of the main objectives of the project is to increase surface water quantity (base flow) and improve its quality (temperature). To document that, surface water bodies that the project may influence need to be identified and monitoring points on them established and characterized (includes collection of baseline data). These locations will be used as monitoring locations during subsequent testing.

The hydrogeologic assessment identified three, down gradient, spring-feed streams, Goodman Spring Branch, Johnson Creek, and Dugger Creek, which are most likely to be affected by recharging the shallow aquifer. During test-site specific characterization these streams will be examined and monitoring points identified. At these points stream conditions will be photographed and stream conditions documented prior to the initiation of testing that will include the following parameters:

Flow volume and discharge

Water temperature

Water quality (temperature)

Hydrophilic plants and habitat quality

Sampling frequency will be designed to collect enough data to demonstrate the range of conditions likely at the monitoring points so that site background conditions can be documented enough to provide an adequate baseline to measure test results against.

Water Quality

Both surface and groundwater quality at the test site, and at likely down-gradient discharge points, needs to be documented. There are several reasons for this, including:

- We do not want to introduce contaminated water into the shallow aquifer via recharge
 activities and violate antidegradation rules. We need to establish background water quality
 parameter concentrations and monitor source-water quality periodically during testing and
 operations.
- 2. Certain source-water conditions (e.g., turbidity) have the potential to degrade or even "plug" the recharge system. From an operational standpoint, one would monitor for those conditions and halt test operations when the source-water exceeded those conditions.
- Up-gradient groundwater quality needs to be monitored so that the effects of recharge on
 water quality can be differentiated from those water quality conditions caused by recharge
 activities, including leaching of vadose zone constituents by recharge water.

Sampling Quality Assurance and Quality Control (QA/QC) protocols will need to be established and followed for characterization and later monitoring. QA/QC for the project, which is described in Attachment 5, includes:

- Sampling equipment
- Measurement techniques for field parameters
- Decontamination procedures
- Well purging guidance for groundwater samples
- Sampling methods
- Chain of custody and sample handling procedures
- Record keeping
- QA/QC guidelines

Characterization Conclusions

With the completion of site-specific characterization, updated monitoring and test plans will be prepared if necessary. These monitoring and test plans will be based on the results of the characterization effort which includes the generation of a site conceptual groundwater flow model that describes probable aquifer conditions, suprabasalt aquifer water level(s) and groundwater flow direction(s) (including seasonal variations), and discharge points for recharge water.

Preliminary Test Site Operation Plan

The objective of proposed artificial groundwater recharge testing to be done under the limited license is to evaluate the feasibility of restoring diminished shallow aquifer water levels and increasing decreased spring creek flows using infiltration pits and winter high flow water diverted from the Walla Walla River to these pits. Testing will be done over five years. If testing indicates shallow aquifer recharge and spring creek flow restoration is feasible using infiltration, test results will be used to design and implement larger scale artificial groundwater recharge at this, and potentially other sites in the area. Testing will not include removal of stored water by pumping or other artificial means.

This preliminary test plan describes how the test site will be operated during testing. Elements included in the preliminary test plan include: (1) site construction, (2) test operations, (3) mitigation activities, and (4) reporting. The preliminary test plan may be modified as testing proceeds.

Site Construction

The basic layout of the test site is shown on Figure 1. The site, located adjacent to the Hudson Bay Canal, will consist of three infiltration pits excavated approximately 3 feet into Quaternary alluvial gravel which immediately underlies the test site (Attachment 6). Water will be delivered to the pits via a diversion structure in the canal. Any water that does not infiltrate into the ground from these pits will be returned to the canal via a return ditch or pipe.

More detailed site construction information describing: (1) test site survey and layout (2) specifications for pits/basins/pits used for infiltration (3) water supply design (including diversion from canals if appropriate) (4) monitoring points (both on and off site) and (5) site access controls (fences, etc.) are described in detail in Attachment 1, (1A-1E), Engineering Design.

Test Operations

Test operations describe how the site will be used during testing and possible reasons for changing the test as new data and information is collected during the test. Test operations include:

- 1. Test timing, including timing of recharge and monitoring frequencies
- 2. Quantities of water used
- Outside influences that effect test, including weather (probably freezing), elevated river turbidity, river flooding, trip wires for identifying potential offsite impacts before they occur so they can be mitigated and or testing suspended to prevent worsening conditions
- 4. Responsible parties for diversion and delivery of water, operation of test, monitoring, and data review
- 5. Permissions required to access offsite monitoring points

These are discussed further in the following paragraphs.

Test Timing, Monitoring, and Water Quantities

Testing is tentatively planned to begin in the winter of 2003/2004 and continue for 5 years. Test operation will generally be conducted in the winter when Walla Walla River flows are at their highest and irrigation activities are at their lowest. A maximum of approximately 50 cfs will be delivered to the test site during normal operation. However, in the event minimum Walla Walla River flows are not meet, water will not be diverted from the river for test site use. Depending on stream flows in any given year, recharge water may be delivered as early as December to as late as March/April. In addition, in the event of prolonged freezing weather, test site operation may be temporally suspended to avoid ice damage to the canal diversion on the Walla Walla River, the canal system itself, and/or the recharge pits and related structures.

Water quantities delivered to the test site will be monitored via a gauge at the diversion from the canal into the test site. The return canal from the test site back into the canal will also be monitored to determine the quantity of water that leaves the test site (if any) because it did not infiltrate into the ground. Based on this monitoring data, and estimated evaporation loses that could occur during operation; water quantities discharged to the ground will be calculated.

Groundwater levels in the immediate vicinity of the test site will be monitored before, during, and following recharge test events via three (at a minimum) observation wells constructed during characterization, potentially via existing water wells in the area if any can be found that can be used for shallow aquifer water level monitoring, and potentially with new observation wells built as the test progresses. During the recharge test event, tentatively scheduled for the winter/spring of 2003/2004 water levels will be measured as follows:

- 1. Throughout the calendar year water levels will be measured at least weekly, beginning with the granting of the limited license.
- 2. In the month prior to the anticipated start of recharge activity and in the month following the termination of recharge, water levels will be measured daily.
- 3. During recharge water levels will be measured daily, at a minimum.

Based on preliminary engineering design studies (Attachment 1) and the hydrogeologic assessment (Attachment 6) most, if not all, of the water delivered to the test site will probably infiltrate into the ground. However, because this project is a test project, the current plan is to initially operate the test site at approximately half capacity. The quantity of water discharged to the site will than be increased or decreased as experience and observations dictate. Final operating quantities will determined based on test results.

Water quality data will also be collected before, during, and following recharge events. Parameters to be collected, sampling timing, and other water quality monitoring information are presented in the Monitoring Plan (Attachment 5).

Outside Influences

The primary currently identified outside influences on testing are Walla Walla River flow levels, freezing conditions, source water turbidity levels, and increased groundwater water levels resulting from testing that impact surface activities and conditions. The likely effects of these on testing, and possible mitigation actions to be implemented during testing, are as follows:

Low flows in the Walla Walla River will impact testing because the use of Walla Walla River water for recharge will be conditional, based on river flows exceeding a certain threshold. When flows do not, water will not be delivered to the test site and testing will not occur.

High Walla River flows may also effect testing. In the event of high flow during a flood or rapid snow melt event, turbidity will generally increase. The repeated delivery of turbid water to the test site infiltration pits may eventually lead to plugging of pore space and reduced infiltration capacity. To mitigate against this, delivery of recharge water may be terminated or scaled back during high flow events. Alternatively, the pits may be periodically re-excavated to remove these fines. The preferred mitigation strategy for dealing with this will be based on monitoring and performance data collected during testing.

The effects of freezing on the test are outlined earlier in this Attachment and repeated here. In the event of prolonged freezing weather, test site operation may be temporally suspended to avoid ice damage to the canal diversion on the Walla Walla River, the canal system itself, and/or the recharge pits and related structures and to avoid the risk of ice jams forming in the canal, backing up water in the canal, and causing flooding adjacent to the canal.

It is possible that recharge testing could cause groundwater levels to reach the ground surface at locations where human activity and habitat is negatively impacted. One of the main purposes of

groundwater level monitoring is to identify increasing water levels in the test site area in order to: (1) directly observe the effects of recharge on water levels (2) use these observations (in conjunction with characterization data) to evaluate whether or not recharge is having an impact on groundwater levels that could lead to surface problems, and (3) identify when and where this type of problem may occur. If water level monitoring data suggest increased groundwater levels are approaching the ground surface and that flooding of low lying areas seems possible, the quantity of recharge test water being delivered to the infiltration pits will be reduced or, if necessary, terminated.

Responsible Parties and Access Permission

The test will be managed primarily by the Hudson Bay District Irrigation Company, lead by John Brough, Operations Manager, and the Walla Walla Basin Watershed Council (WWBWC) technical staff, lead by Mr. Bob Bower, Hydrologist. HBDIC and WWBWC staff (or a subcontractor working for the HBDIC and WWBWC) will compile monitoring and testing data, prepare reports as necessary to meet license requirements, and in consultation with Hudson Bay Irrigation District (HBDIC) staff make decisions regarding timing and quantity of water delivered to the site and when to suspend recharge activities. Submittal of all monitoring reports to OWRD will be the responsibility of HBDIC and WWBWC staff. The HBDIC and WWBWC may choose to subcontract report preparation and delivery to a subcontractor.

HBDIC staff will be responsible for operating all facilities associated with removing recharge test water from the Walla River and delivering it to the test site, including operation of the diversion structure which routes water from the canal into the pits. HBDIC staff also will maintain all equipment associated with water delivery and pit operation, including reexcavation of the pits, if necessary.

Mitigation

As stated above, one of the objectives of monitoring is to identify likely unintended consequences of recharge testing before they occur. When the precursors to these consequences, such as changing water quality detrimental to aquatic habitat or groundwater levels rising to close to the surface in areas where shallow groundwater is not desired, can be detected soon enough via monitoring, recharge activities will be modified and/or terminated to mitigate against these effects.

Reporting

Data and observations collected during testing, including monitoring data, will be compiled into reports. The basic objective of these reports will be to describe what was done during the test, what was observed at the monitoring points, interpret the data collected, and recommend changes to testing, monitoring, and mitigation plans. These reports will be produced annually. Based on the proposed recharge schedule, annual reports will be submitted to OWRD in the summer following each winter recharge test.

More frequent reporting will be done when monitoring reveals the presence of an undesired effect from testing. If monitoring reveals that undesired consequences of testing are likely to occur, WWBWC staff (or designated representative) will report the monitoring information to OWRD staff.

At the conclusion of the 5-year recharge testing done under the limited license a final report will be prepared. The final reports will describes the project, data colleted during testing and monitoring, interpretations of how well the recharge project worked in achieving project goals, and recommendations for future operations. The final report will be submitted to OWRD in the summer following the fifth annual winter recharge event.

Attachment 5. Proposed Monitoring Program, 690-350-0020(3)(b)(A)

Overview of Basin Wide Monitoring Plan

In 2003, the WWBWC expanded its watershed monitoring strategy to include collecting basin line information for the numerous spring-creeks and district ditches spread out across the Walla Walla River valley (Oregon). Starting in June 2003, many new flow stations (15-minute stage and temperature recorders) were installed at or near the sources of nearly all the springs in the Oregon portion of the system (Figure 2). The WWBWC monitoring program has a total of 28 continuous flow stations with additional 15 continuous static well recorders with many more manual measurement locations. The objectives of this monitoring (specifically for the spring-creek and shallow aquifer system) is to accomplish the following:

- 1. Be able to discern between Walla Walla River Water (coming from districts water rights and use) and spring waters (emerging strictly from the shallow aquifer). It is understood that the application of irrigation water will undoubtedly show up as spring returns, but this monitoring is intended as a beginning to understanding this complicated system.
- 2. Collect baseline information on spring flow as it relates to seasonal and yearly fluctuations.
- 3. Many of the spring-creek monitoring stations were sited based on the presence of historical data collected by Piper (USGS, 1933). Where Piper had collected spring-creek flow, we attempted to locate our gauges as near as possible to his historic data sites. The intention is to allow us the ability to compare and contrast historical and current spring-creek conditions based on a significant period of time. Most of these Piper's original sites were located upstream of any irrigation with draws, making them key locations for us in this type of comparison.
- 4. Monitor water table levels continuously for daily, seasonal and yearly fluctuations and timing. Some of the wells being recorded have periods of record dating back to the 1930s, allowing us some opportunity to understand any long-term changes in the aquifer system.

Recharge Project Monitoring Plan

The proposed ground water recharge project exists inside this larger monitoring network and it is expected that this will help provide useful information in testing of the proposed testing (see below). Some of the sites shown in this larger network were specifically located to provide proximal and distal pre-construction and operation information for this project (Figure 2). Site specific monitoring includes observation wells and surface monitoring stations (Attachment 5B).

Monitoring for the site-specific proposed testing is designed to meet four basic objectives. These are to identify: (1) changes in the natural system caused by factors other than those related to testing, (2) changes in the natural system caused by the testing (track the test performance), (3) potential problems caused by the testing that may require modification or termination of the test and/or mitigation actions, and (4) events that effect test operations, such as a freezing or a flooding. To meet these objectives, monitoring will track:

- 1. Source water quality and volume coming onto the test site
- 2. Up-gradient groundwater water quality
- Up-gradient groundwater level changes to provide the information needed to differentiate
 recharge test effects from other, natural and artificial, effects on the groundwater levels
 beneath test site

- 4. Down-gradient groundwater quality and levels, both near and distal to the test site
- 5. Surface water discharge and quality changes

Four basic types of monitoring points are planned for this project:

- 1. Source water
- 2. Test site groundwater
- 3. Distal groundwater
- 4. Surface water (e.g., springs).

Monitoring data collected at these points during testing will be evaluated against what is known about pre-test conditions to identify testing effects on the surrounding environment, differentiate those effects from others in the environment, and identify when changes in test operations appear necessary. Pre-test conditions will be determined during the planned site-specific characterization activities described in Attachment 4 and are partially described in the preliminary hydrogeologic assessment (Attachment 6).

This preliminary monitoring plan discusses monitoring activities to be undertaken at the four types of monitoring points and sampling and QA/QC protocols.

Sampling and Analysis Program

The groundwater-monitoring program proposed for the test project is outlined in the following sections. Annual reporting is proposed and a Water Quality Analysis Report will be prepared following five years of testing.

As stated in the introduction, four types of monitoring are proposed: (1) source water at the test site (2) site-specific groundwater (3) distal groundwater and (4) surface water (springs).

(1) Source Water at Test Site

Source water monitoring will be at the point of diversion onto the test site. Monitoring will include both water quantity and quality. The volume of water delivered to the test site will be monitored via a gauge at the diversion. Water quality samples will be collected at the gauge.

Proposed monitoring frequency is as follows:

Gauge data will be recorded 15-minute readings via a continuous recording data logger. Rating measurements and tables will be generated for each surface flow site and continuously checked for shifts.

Three source water quality-sampling events are proposed for each yearly seasonal recharge period. They are proposed for approximately: (1) one month prior to the projected beginning of the recharge period (2) during the mid part of the recharge period and (3) approximately one month following the end of the recharge period. The exact timing of these will be based on predicted Walla Walla River flows and may vary from year-to-year. OWRD and ODEQ staff will be notified by WWBWC staff of pending sampling events at least two weeks prior to each sampling event.

The results of source water quality monitoring will be used to determine if modifications to test operations are warranted. During testing different sampling frequencies may be tried to identify those that are most effective.

(2) Site Groundwater

Site groundwater monitoring, consisting of the collection of water quality and water level data, will be conducted at the three observations wells built during characterization. The purpose of site groundwater monitoring is to establish water quantity and quality impacts from testing to groundwater in the immediate vicinity of the site. In addition, up-gradient monitoring will be used to differentiate test impacts from those caused by other activities not controlled by the testing.

Proposed monitoring frequency is as follows:

Water levels will be measured weekly throughout the year when recharge testing is not underway.

In the month prior to, during, and the month following the yearly seasonal recharge period, water levels will be collected daily (at a minimum) for the first year of testing. Measurement frequency during subsequent years will be based on previous observations and proposed in annual reports.

Three groundwater quality sampling events are proposed for each yearly seasonal recharge period. They are proposed for approximately: (1) one month prior to the projected beginning of the recharge period (2) during the mid part of the recharge period and (3) approximately one month following the end of the recharge period. The exact timing of these will be based on predicted Walla Walla River flows and may vary from year-to-year. OWRD and ODEQ staff will be notified by WWBWC staff of pending sampling events at least two weeks prior to each sampling event.

The proposed locations of site-specific groundwater observation wells are shown on Figure 1. The results of groundwater quality and level monitoring will be used to determine if modifications to test operations are warranted. During testing different sampling frequencies may be tried to identify those that are most effective.

(3) Distal Groundwater

Distal groundwater monitoring, consisting of the collection of water quality and water level data, will be conducted at observation wells more distal from the test site than the site observation wells. Initially, during the first year of recharge testing, these wells will probably be previously constructed water supply wells that can be used by WWBWC staff and can be shown to be open to only the shallow aquifer. If funding for new wells can be procured for subsequent years, dedicated distal groundwater observations wells may be built to improve the monitoring coverage.

A minimum of 3 distal observation wells will be used, 1 up-gradient and 2 well down-gradient. The locations of these will be determined during site specific characterization currently planned for the winter of 2003. Monitoring frequency is the same as proposed for site-specific groundwater monitoring. Figure 5B shows the approximate site locations for the site-specific observation wells.

Distal monitoring will be used to identify longer term quantity impacts from testing. This includes the formation and migration of a groundwater mound and recharge water plume at, and away from, the test site, towards intended and unintended receptors. Up-gradient monitoring will be a part of this so that testing effects can be differentiated from offsite events. Sampling frequency will be determined from characterization data and modified as more is learned during testing.

(4) Surface Water (Springs)

The WWBWC is currently monitoring most of the surface springs, creeks and rivers of Oregon's lower Walla Walla River basin (See Figure 2.) While this project will specifically Surface water monitoring in Dugger, Johnson and Goodman Spring-Creeks will be done to identify the effects of recharge on flow. This monitoring will include the collection of both water quality (specifically temperature), flow and habitat improvements (photo-documentation). As with groundwater monitoring, surface water monitoring will need up-gradient and pre-project condition monitoring information so that effects unrelated to test site operations/testing can be differentiated from those due to testing. Pre-project surface flow monitoring was started during the 2003 summer irrigation season at Dugger and Johnson Spring-Creeks in the form of a continuous.

Sampling Parameters

Sampling methods are specified in the following sections. The chemical monitoring parameters are to be conducted on a two-tiered system. Level 1 monitoring will be conducted during all three water quality-monitoring events (each recharge period). Consistently elevated concentrations of nitrate will be initiate the level 2 chemical analysis. Samples will be tested for chemicals in the level 2 list. Operation of the recharge project will depend on the absence/presence of the chemical parameters on this list. ATTACHMENT 5B describes the specific method and documents used to determine the level 1 and 2 chemical parameters (pesticides, herbicides, insecticides, fungicides, etc.) listed below.

Monitoring is proposed for the following parameters:

Physical Parameters (all monitoring types)

Static water level (in observation and WWBWC network well)

Standard field parameters, including pH, turbidity, electrical conductance, and temperature

Flow (in cubic feet per second)

Chemical Parameters -Level 1 (On-site monitoring only)

Total nitrogen as nitrate (screening parameter for Level 2 Chemical screening)

TKN

Total dissolved solids

Chemical oxygen demand

Chloride

Orthophosphate

Fecal Coliforms (Presence/absence only)

Chemical Parameters -Level 2 (On-site monitoring only)

Rubigan (Fenarimol)

Ridomil (Metalxyl)

Systhane/Rally (Myclobutanil)

Devrinol (Napropamide)

DDD-DDE-DDT

Elgetol (DNOC sodium salt)

Alar/B-Nine (Daminozide)

Lindane (Lindane)

Sampling dates will be coordinated for all monitoring points used in the project.

This list of analytes was selected to optimize routine sampling to address constituents commonly of concern (nutrients and salt) and provide prompt indication of potential impacts by analyzing for anions (nitrate and chloride) that are known as groundwater tracers (DEQ, 1995). Additional parameters will be proposed for future sampling if the results of the initial proposed sampling indicate this is necessary.

Sampling Procedure

Equipment and sampling procedures proposed for recharge test monitoring are provided in the following sections.

Equipment

This section lists the equipment for groundwater monitoring.

Submersible pump (*Grundfos* or similar) or dedicated bailers/sampling line

Temperature measuring instrument (Vemco data logger)

pH and conductivity meter(s) with calibration reagents

Water level and flow meters (Tru-traks, In-situ Mini-trolls, Stevens 420 loggers, 0.01 foot resolution required)

Shipping cooler with ice packs or ice

Five-gallon pail marked at the 5-gallon level, stopwatch

Laboratory supplied sample containers with appropriate preservatives

Tap water, deionized water, phosphate-free soap, cleaning brushes, field note book, log sheets

Water Level

An electronic water level meter will be used to measure the depth to groundwater in each observation well to the nearest 0.01 foot. Static water levels must be measured at the indicated reference point prior to purging any water from the well. The reference points will be on the top of the observation well casings. The static water levels in all wells should be measured on the same day for each site. Coordination with quarterly sampling of other wells in the vicinity should be attempted. Accumulation of sediment in the well should also be checked by lowering a weighted tape to the bottom of the well, reading the depth at the well casing's reference point, and comparing this value to the as-built well depth.

Decontamination

All non-disposable field equipment that may potentially come in contact with any soil or water sample shall be decontaminated in order to minimize the potential for cross-contamination between sampling locations. Thorough decontamination of all sampling equipment shall be conducted prior to each sampling event. In addition, the sampling technician shall decontaminate all equipment in the field as required to prevent cross-contamination of samples collected in the field. The procedures described in this section are specifically for field decontamination of sampling equipment. At a minimum, field-sampling equipment should be decontaminated following these procedures:

- 1. Wash the equipment in a solution of non-phosphate detergent (Liquinox® or equivalent) and distilled/deionized water. All surfaces that may come in direct contact with the samples shall be washed. Use a clean Nalgene and/or plastic tub to contain the wash solution and a scrub brush to mechanically remove loose particles. Wear clean latex or plastic gloves during all washing and rinsing operations.
- 2. Rinse twice with distilled/deionized water.
- 3. Dry the equipment before use, to the extent practicable.

Purging and Field Parameters (On site wells only)

Sufficient water will be purged to ensure that the sample collected represents water from the geological formation. Borehole volumes are calculated as the volume of water in the casing and the volume of water in the filter pack.

During purging, measure pH, temperature, and electrical conductivity of the water removed. At a minimum, these parameters are measured at the start of purging and after each successive borehole volume is removed. Temperature should be measured first because it changes most rapidly. Purging continues until at least three borehole volumes have been purged and the field parameters are established to within \pm 10 percent over three consecutive measurements. At this point, the observation well is considered adequately purged and can be sampled.

Occasionally, observation wells installed in low permeability formations may be purged nearly dry (within 6 inches of bottom of well) prior to stabilization of groundwater parameters and prior to purging at least three borehole volumes. If this happens at least one set (more if possible) of purge water groundwater parameters (pH, temperature, EC) need to be measured. Sample collection can be done after the water level has recovered at least 75 percent of the drawdown ensuring most of the well water is from the formation. Prior to groundwater sample collection several measurements are required as explained above. These include static water level and total depth, pH, temperature, and electrical conductivity.

All field instruments should be calibrated each day prior to sample collection. Instrument calibration and maintenance should precisely follow the manufacturers recommended procedures. Electrical conductivity and pH standards used to calibrate the instruments should be within the range encountered at the monitoring sites. Calibration records should be recorded on the sample collection forms.

Water Sampling

Samples will be collected after sufficient water has been purged according to the procedure described above. Samples will be collected from the discharge end of the pump hose after the flow rate has been reduced to less than approximately 0.2 gallons per minute. Discharge from a bailer should be controlled to minimize agitation and aeration. Sample containers should be sealed with tape, labeled, and immediately placed in a cooler with ice. Sample containers should be filled completely to eliminate head space. Sample containers should be provided by the analytical laboratory and should be requested at least one week in advance of the sampling. The containers should be appropriate for

the parameters analyzed and all shipping coolers should have chain-of-custody seals placed on them prior to shipping.

One additional sample should be collected from one of the sample points for quality control purposes. This sample should be evaluated as a "blind duplicate."

Sample Preservation and Holding Time. Samples should be stored immediately after collection in an ice chest containing sufficient ice to cool the samples to 4 degrees Celsius (°C). Use "blue ice" if possible. If water ice must be used, the ice should be sealed in plastic bags, as should the sample bottles. Samples should remain cooled at 4°C and delivered to the laboratory within 24 hours of collection. Sample receipt at the laboratory must be sooner if analysis includes parameters with a shorter holding time. Care should be taken to prevent excessive agitation of samples or breakage/leakage of containers. Samples should be analyzed within the specified holding time for each constituent.

Resampling

In accordance with OAR 340-40-030(5), resampling is done if monitoring indicates a significant increase (or decrease for pH) in the concentration of a monitored parameter at a sampling point. Determining if a significant increase in parameter concentration has occurred is customarily done either by assessing concentrations in relation to established concentration limits or by using a statistical analysis. Since background or baseline conditions have yet to be established for the test site a concentration limit has not been set and insufficient data exists upon which to base a statistical analysis. The criteria to guide resampling decisions will be reevaluated is subsequent test project annual reports.

Chain of Custody and Sample Handling

A chain-of-custody form should be completed and signed by the sampler on the day samples are collected. The chain-of-custody form must be signed by laboratory personnel upon receipt and any other individuals that maintain custody of the samples in the interim. Coolers should be sealed and shipped or driven to the lab as soon as possible. The method of shipping (bus, next day air, etc.) is usually determined by the parameter having the shortest holding time. In any case, shipping times of more than 24 hours should not be used as the cooler(s) may warm and compromise sample quality.

Field Records and Data Validation

All field notes, analytical results, and other pertinent data associated with the project should be maintained in a secure location and be archived for at least a five-year period. Data validation for both field and lab Quality Assurance and Quality Control (QA/QC) will be performed using a checklist. All pertinent information with respect to QA/QC will be checked. The following items are included on the QA/QC review checklist:

- Field data sheets (or notebooks) and observations (observations are used to check for
 potentially erroneous data) will be reviewed to make sure they are completely filled out.
- 2. Chain-of-custody forms will be completed, being signed by all sample handlers.
- 3. Holding times for all constituents will be met.
- 4. Field blind duplicate results will be evaluated to make sure they are compatible.
- Laboratory method blanks, matrix spike, matrix spike duplicates, and surrogate percent recovery data supplied by the analytical laboratory will be evaluated to make sure they are compatible.

Data Reporting and Statistical Analysis

The following procedures for reporting analysis are proposed for this project.

Record Keeping

All field notes, laboratory results, critical calculations, and published reports will be maintained at the WWBWC office for a period of five years following completion of the final testing and monitoring report. If possible, both paper and electronic copies will be maintained.

Evaluation

Monitoring data and observations should be evaluated when they are received from the sampler and laboratory.

Materials to be received include:

Field monitoring and sample collection records

Original laboratory reporting sheets

Data evaluation will include:

- Verification of analytical methods and detection limits, along with the date the analysis was performed
- 2. Review of document handling, sampling and analytical problems, and actions taken to correct any problems
- 3. Summarizing water level data in tabular and/or graphical form
- 4. Summarizing water quality analytical results in tabular form and/or graphical form
- 5. Performing data validation checks, as appropriate to the data set
- 6. Identifying any significant increases in parameter concentrations (will be done later in project only after enough data has been collected to warrant)

Annual Review and Reporting

All monitoring activities performed during the previous monitoring year will be included in an annual report to be submitted to OWRD during the summer following the preceding seasonal recharge period. The annual report will present the following information:

Water quality data, including duplicate sample results in tabular form and time-series plots for specific parameters

Water level data, including hydrographs showing water level changes over time

Basic statistical parameters for each parameter of interest: mean, median, maximum, minimum, standard deviation, number of data points, and number of non-detects

Evaluation of all field and laboratory data, including observed changes and groundwater flow direction and gradient

Discussion and conclusions, including recommended changes to recharge testing

The methods needed to evaluate water quality and water level data will depend on the objectives of the evaluation. In general, the principal objective is to evaluate whether or not recharge tests have affected groundwater levels and quality. Evaluation methods include: a comparison of water quality data with a concentration limit or with background water quality; comparison of water quality over time; or comparison of water quality between up-gradient and down-gradient wells. For the test site, insufficient data are available for a statistical analysis to be performed because concentration limits have not yet been established. Until that time, evaluation of dataset trends will be solely qualitative, but revisited in each annual report until a database has been compiled that is sufficient for statistical analysis.

Final Recharge Test Project Report

At the conclusion of five years of recharge testing under the limited license a final report will be prepared. The report will contain the data collected for the test project; analysis and interpretation of that data (including statistical analysis as appropriate), and a recommendation for proposed future artificial groundwater recharge activities at the test site. The report will be complete enough to serve as supplemental material to a permanent artificial groundwater recharge permit under OAR 690-350-0110, if such a permit is sought following completion of the test project.

Monitoring Plan Attachments

Attachment 5A. Methodology Water Quality Assessment and Evaluation Attachment 5B. Figure 5A Map of On-site Recharge Well Locations Attachment 5C Chemicals of interest for Hudson Bay Recharge Project

Attachment 6. Site Hydrogeology, 690-350-0020(3)(b)(C), (E), and (G) (attached)

Attachment 7. Source Water Quality, 690-350-0020(3)(b)(D)

Overview

This project will utilize winter-spring flow from the Walla Walla River as the *source* water for recharge during the project operation. The time period that Walla Walla River water will be used is November 15th through May 15th. A review of existing reports and data was conducted to identify any areas of concern regarding source water quality for the recharge project. What little information that exists for source water quality conditions is discussed below.

In 2003, the WWBWC tracked turbidity levels through a winter storm event (1/27/3 through 2/3/3) and found turbidity levels to be a potential issue on the Walla Walla River (mainstem) during peak flow events (WWBWC, Unpublished data). Turbidity could be problematic for project operations, as it may act to decrease the rate of infiltration by plugging and layering the bottom of the recharge pits. Turbidity may also be a preliminary screen for fecal contamination issues, as bacteria may use the large particles as a vector for mobilization.

The other known source water quality information was obtained from the Environmental Protection Agencies STORET database. STORET provided some historical water quality data that showed several parameters (circa 1960s) that were accounted for in the recharge project's monitoring plan (ATTACHMENT 5). STORET data that was collected nearest to the source water POD at the Little Walla Walla Diversion (NE ½ NW ¼, Section 1, SW ¼ NE ¼ Section 12, T5N, R35E, W.M.; DIV.PT. 1) is attached in table form as ATTACHMENT 7A.

From the review of all known source water information, the parameters that appeared to be of concern are:

- 1. Fecal Coliforms
- 2. Turbidity

There was no other relevant information found for source water quality conditions. The monitoring plan covers the establishment of source water quality conditions during operation of the recharge facility. This will insure safe water quality conditions for the recharge project.


Attachment 7A Source Water Quality Information


Resources and References:

- Cooperative Extension Washington State University. 2002. 2002 Crop Protection Guide for Tree Fruits in Washington. Washington State University EB0419.
- Darnell, T., Topielec, R. 1996, October. Nitrates and Bacteria in Groundwater: A Second Look, Milton-Freewater Area, Umatilla County, Oregon. Oregon State University Extension Service Water Quality Program.
- Darnell, T. Hart, J. Vomocil, Jim. 1989. Nitrates and Bacteria in Groundwater: Milton-Freewater, Umatilla County Oregon. Oregon State University Extension Service.
- Darnell, T., Montgomery, M. L., Witt, J. M., 1989, July. Pesticides in Groundwater: Milton-Freewater, Umatilla County, Oregon. Oregon State University
- EPA STORET Water Quality Database information (http://www.epa.gov/storet/)
- Jenkins, J. J., Thomson P. A., 1999, January. OSU Extension Pesticide Properties Database. . Oregon State University Extension EM 8709
- Kerle, E.A., Vogue, P. A., Jenkins, J. J., 1996, October. Understanding pesticide persistence and mobility for groundwater and surface water protection. Oregon State University Extension EM 86561
- MacNish, R.D. and R.A. Barker. Digital model of the gravel aquifer, Walla Walla Basin. United States Geological Survey, 1976.
- MacNish, R.D. and R.A. Barker. Digital simulation of a basalt aquifer system, Walla Walla River. Water Supply Bulletin #44. Washington Department of Ecology, 1976.
- Newcomb, R.C. Geology and Groundwater Resources of the Walla Walla River Basin. Water Supply Bulletin #21. Washington Department of Conservation, Division of Water Resources, 1965.
- Oregon Water Resources Department. Umatilla Basin Report. 1988. Government Printing Office 774-398/20006 Region NO. 8
- Piper, A.M., T.W. Robinson, and H.E. Thomas. Groundwater in the Walla Walla Basin, OR-WA-Part I. Department of the Interior, United States Geological Survey, 1933.
- Piper, A.M., T.W. Robinson, and H.E. Thomas. Groundwater in the Walla Walla Basin, OR-WA-Part II.


 Department of the Interior, United States Geological Survey, 1933.v
- Richerson, P., Cole, D. 2000, June April 1999 Milton-Freewater Groundwater Quality Study: As part of the Statewide Groundwater Monitoring Program. State of Oregon Department of Environmental Quality
- U.S. Department of Agriculture (USDA), Soil Conservation Service. Nov, 1988. Soil Survey of Umatilla County Area, Oregon. WWBWC technical library
- U.S. Geological Survey 1996, July. Fact Sheet 171-96: <u>Article: The Nitrate Connection</u>. US Government Printing Office 774-398/20006 Region NO. 8

Attachments





Shand Mishard Charles All Charles



HUDSON BAY AQUIFER RECHARGE PROJECT

ENGINEERING REPORT

This project entails diverting water from an existing irrigation ditch to three pits to be excavated for the purpose of infiltrating the water into the shallow aquifer. Project features include a concrete check structure in the existing White Ditch, a concrete flow measuring flume, an open ditch, three excavated pits, pipes connecting the pits and an outflow ditch from the down stream pit.

These items were sized to handle 50 cubic feet per second (cfs) of water. This is the amount anticipated will be available from excess flow in the Walla Walla River and that the Hudson Bay District is able to deliver.

Data gathered to design the project consisted of a site topographic survey and installing two sites for testing the water infiltration capacity of the natural materials and determining the layers in the soil profile. In addition the Soil Survey of Umatilla County Area, Oregon was consulted. This is a US Dept. of Agriculture, Natural Resources Conservation Service publication giving general soils information.

The topographic survey data was used to prepare a topographic map with one foot contour intervals at a scale of 1'' = 60'. This information was used to help determine the location of the project features.

Two test pits were excavated to a depth of 6'-7' each. A 24" diameter by 5' long section of corrugated metal pipe was set on end in the bottom of the pit and about one foot of fill placed around it to hold it in place. Water was pumped into the pipe at a rate that would sustain a water depth of one foot in the pipe. Both flow rate and total flow was measured. The test was run for 6.25 hours in the first pit and 3.5 hours for the second pit.

PIT#1

Soil profile:

0-12" sandy loam

12"-36" gravelly sandy loam, approximately 50% of the material volume is gravel size particles with an estimated D $_{50}$ size of about 0.75"

36"-48" sandy loam, in parts of the trench this layer does not exist

48"-?" gravelly sandy loam approximately 20% of the volume is gravel size particles

The inflow rate at the end of the test period was 4.0 gallons per minute (gpm). This resulted in an infiltration rate of 1.7 gpm/sq. ft./ foot of head.

PIT #2

Soil profile:

0"-13" gravelly sandy loam

13"-39" cobbly sandy loam, the D₅₀ of the gravel is approximately 1"

39"-52" gravelly sandy loam

52"-? sand gravel mix D 50 estimated to be about 0.25"

In this pit the inflow rate of 11.9 gpm was maintained for 3.5 hours and at no time did water puddle in the bottom of the pipe. The infiltration rate is in excess of 3.8 gpm/sq. ft.

The area needed for infiltrating the water was determined assuming an infiltration rate for the entire area of 3.0 gpm/sq.ft./ per foot of head. For an inflow rate of 50 cfs the infiltration area needs to be 7480 square feet. The infiltration rate of 3.0 gpm/sq.ft. was chosen because the pits will be located in the area with soil surface texture similar to test pit #2.

Due to the possibility of fine soil particles plugging the infiltration area, unknowns concerning the long term infiltration rate and that the amount of water available is not yet known extra infiltration area is being provided. Three separate pits with bottom dimensions of 50 feet X 100 feet are proposed. This will provide an infiltration area of 15,000 square feet.

The pits will be excavated to a depth of about 5 feet to get below the second sandy loam layer noted in both test pits. This will allow the water depth to be 2.5 feet - 3.5 feet. That will increase the rate of infiltration over the test values derived with one foot of water depth. The overall safety factor for the infiltration area is well over 2.

Inflow to the system will be measured with a ramp flume and continuously recorded. The ramp flume is sized to provide 5% flow rate accuracy over a flow range of 10 cfs-50 cfs

Any outflow from the last pit will be safely returned to the White Ditch through a 12-inch pipe. The pipe will be on a slope that will keep water from flowing out of White Ditch.

Bernard J. Hewes

Date: 8/21/03

LAND USE INFORMATION SHEET

This information is needed to determine if the proposed project complies with statewide planning goals and is compatible with local comprehensive plans (ORS 192.180)

Please check below the one that applies!
Please check below the one that applies!
This project is not regulated by the local comprehensive plan and zoning ordinance.
This project has been reviewed and is compatible with the local comprehensive zoning ordinance. (Please cite appropriate plan policies, ordinance section, and case numbers.)
This project has been reviewed and is not compatible with the local comprehensive plan and zoning ordinance. (Cite appropriate plan policies, ordinance section, and case numbers).
Compatibility of this project with the local planning ordinance cannot be determined unti the following local approvals are obtained:
Conditional Use Permit Plan Amendment Other Development Permit Zone Change
An application has has not been made for the local approvals checked above.
* Signature of Local Official: Party Perry Title: Senier Planner Date: 5-27-03
Title: Senier Planner Date: 5-27-03 Must be authorized signature from your local City/County Planning Department

ATTACHMENT 5A: Methodology to Determine Chemical Constituents for Water Quality Assessment and Evaluation

Introduction:

The Artificial Groundwater Recharge rules (OAR 690-350-120) require both up front water quality and a water quality-monitoring plan. Further, for any recharge project the rules (OAR 690-350-120 (3) (b) require an applicant to either obtain a water quality permit (typically a water pollution control facility (WPCF) permit) or show that a permit is not necessary. Also, rules OAR 690-350-120 (3)(g) require a "Project Description Report" (ATTACHMENT 5) that outlines the proposed groundwater quality-monitoring plan. This attachment is intended to specifically help clarify the method by which the list of chemical constituents was determined.

Project Area Sample Chemical Review Methodology

Working with Tom Darnell, OSU Extension agent in Milton-Freewater, a chemical constituents review was conducted in order to determine what types of chemicals should be examined in the surface and groundwater monitoring for the project. Several steps were followed to determine which chemicals were of interest.

Review Steps

- 1. Reviewed the ODEO Report: April 1999 Milton-Freewater Groundwater Quality Study: As part of the Statewide Groundwater Monitoring Program (Richardson, et. al., 2000). Particular attention was focused on the constituents tested, testing protocol and timing, and the results-conclusions.
- 2. Reviewed OSU Extension Pesticide Properties Database and determined which were used in the Milton-Freewater area and a list was comprised. (Table 4A1, 4A2)
- 3. Determined which were currently and/or historically used in the area utilizing past chemical studies in the basin (see references). This included interviewing the current landowner on the site-specific history of chemical use on that property (see signed written statement below).
- 4. Determined which chemicals were important to monitor for during the recharge period (winter-spring). Considered each chemical's typical seasonal application period, solubility in water, soil half-life, and soil movement ratings.
- 5. Considered project design (top soil removed), and finalized list of chemicals of interest.

Final List of Chemicals to Monitor for Recharge Project

Chemicals Currently Used:

Rubigan (Fenarimol) Ridomil (Metalxyl) Systhane/Rally (Myclobutanil) Devrinol (Napropamide)

Chemicals Historically Used:

DDD-DDE-DDT Elgetol (DNOC sodium salt) Alar/B-Nine (Daminozide) Lindane (Lindane)

Laboratory Resources

Nitrate Analysis: Walla Walla County-City Health Department

310 W. Popular, P. O. Box 1753

Walla Walla, WA 99362 Telephone (509) 527-3290

Chemical Analysis: KUO Testing Labs, INC.

337 south 1st Avenue Othello, WA 99344

Telephone: (509)-488-0118

CADFILE whiteplan SHEET 2 OF 4 CENCENTA CENCENTA 60° CULVERT CHECK & FLUME
STRUCTURES INFLOW 60° CULVERT 2" Observation 2" Observation Well CONNECTING Well INFLOW DITCH POTEL DE 4" Observation Well -INLET 60" CULVERT

Attachment 5B Map of On-Site Monitoring Well Locations

Attachment 50

History of Chemical Use: Recharge Site Specific

Landowner Statement of Past Use:

"Gentleman.

I have been the owner of a certain parcel of land in the valley with an address known as 84140 Prunedale Rd., Milton-Freewater. Oregon, 97862.

I have owned this land since 1978 at which time we took over the existing orchard of apples and farmed it for two years at which time we began removing various blocks of tress and replanting with new varieties. In the past few years we raised Nursery Tree Stock and began leveling the land to its present condition, letting it lay in a dormant stage for a year and then planting cover crops to enrich the soil for a future cherry orchard.

The pesticides applications were the normal tree fruit pesticides as allowed by regulations of the industry. The herbicide applications were Round-Up. Simizine and Paraquat. No other chemicals were used on this parcel of land during my ownership. If you should hard other questions, please contact me at the following: (5+1)-278-6305. (509)-386-6175, or (5+1)-558-3752 or email at:

Hjohnson(Wco.umatillofor.fis'

Landowner

Chemical is defined here to include insecticides, fertilizers, herbicides, rodenticides, fungicides, and all other non-natural chemicals.

Grey areas samples that correspond to Recharge Project

1STORET RETRIEVAL DATE 99/06/23 28AWALL03780

46 01 08.6 118 24 45.1 4
WALLA WALLA RIVER AT HWY 11 (MILTON-FREEWATER)
41059 OREGON UMATILLA

PACIFIC NORTHWEST 131007

COLUMBIA RIVER BASIN BELOW YAKIMA RIVER 17070102007 00

0000 FEET DEPTH

00945 SULFATE SO4-TOT MG/L 22413 HARDNESS TOTLDISS WTR MG/L 31505 TOT COLI MPN CONF /100ML 31615 FEC COLI MPNECMED /100ML 31677 FECSTREP MPNADEVA /100ML	00612 UN-IONZD NH3-N MG/L 00619 UN-IONZD NH3-NH3 MG/L 00620 NO3-N TOTAL MG/L 00660 ORTHOPO4 PO4 MG/L 00760 SWL PBI MG/L 00940 CHLORIDE TOTAL MG/L	00301 DO SATUK PERCENT 00310 BOD 5 DAY MG/L 00400 PH SU 00410 T ALK CACO3 MG/L 00500 RESIDUE TOTAL MG/L 00610 NH3+NH4 N TOTAL MG/L	WATER COLLEC TURB COLOR CNDUCT	INITIAL DATE INITIAL TIME MEDIUM 00010 WATER TEMP CENT
	(4)			

					(a)																						
		620	28	00	2	1K	0.06	0.03	.0005\$.0004\$	0.13	368	518	30	7.3	0.7	89	10.3	67	20	250	10	46.4\$	8	WATER	1235	67/04/24
		2400		သ																	2	10	77.9\$	25.5	WATER	1400	67/08/21
	230	7000				29			*			1 I I I			7.7	0.9	89	10.6	200			10	44.6\$	7	WATER	1440	67/12/11
,		60	37	4	<u></u>	1K	0.1	0.07	.002\$.002\$	0.38	10	99	33	7.5	0.5	99	11.4	72	ယ		_				1615	XPEC.
		230	99	14	00		0.18	0.38	.049\$.040\$	0.32	10	184	105	8.40L	1.3	131	10.7	243	51	ω	10	77.0\$	25	WATER	1750	68/08/05
		2300	35	4	2			0.54							100		MATERIAL STREET	-	_		8	10	41.0\$	5	WATER	1100	68/12/16
		620													7.6	0.8	99	11.6	95			10	47.5\$	8.6	WATER	1510	69/03/04
240		450K	49	6	2		0.16	0.73	.0004\$.0003\$	0.08	18	118	54	7.5	1.5	94	11.7		-						1145	_
	60	620	24	(J)	↦		0.03	0.13	.0006\$.0005\$	0.12	12	87	31	7.5	1.5	105	12.7	71	ယ		10	42.8\$	6	WATER	930	70/04/28

SOURCE: STORET DATABASE

PAGE:1

10/16/03

PTSSIUM K,DISS I CHLORIDE TOTAL SULFATE SO4-TOT HARDNESS TOTLDIS TOT COLI MPN CON FEC COLI MPNECME	OTAL MG MG/D4 MG/I	00500 RESIDUE TOTAL MG/L 00530 RESIDUE TOT NFLT MG/L 00610 NH3+NH4 N TOTAL MG/L 00612 UN-IONZD NH3-N MG/L 00619 UN-IONZD NH3-NH3 MG/L	MG/L MG/L ATUR PER 5 DAY MC SU CACO3 M		00011 WATER TEMP FAHN 00027 COLLECT AGENCY CODE 00070 TURB JKSN JTU 00080 COLOR PT-CO UNITS 00094 CNDUCTVY FIELD MICROMHO (SAMPLE CONTINUED FROM PREVIOUS PAGE)	INITIAL DATE INITIAL TIME MEDIUM 00010 WATER TEMP CENT
230 230	*	14	236 12.5 151 2 8.6	70/07/13 1400 WATER	75.2\$ 10	70/07/13 1400 WATER 24
1 3 26 2400 45K	0.02	89 12 0.34 .001\$	66 11.5 95 0.7 7.5 29	70/11/30 1645 WATER	41.9\$ 10 5 0	70/07/13 70/11/30 71/05/11 1400 1645 2000 WATER WATER WATER 24 5.5 15.5
0.7 .1K 19 2400 45K	0.1	75 12 0.06 .0003\$	51 9.5 0.8 7.3	71/05/11 2000 WATER	59.9\$ 10 3 1	
5 11 80 230 45K	0.15	172 4 0.66 .215\$.261\$	200 14.2 172 2.3 8.9 96	71/08/16 1620 WATER	78.8\$ 10 1 2	71/08/16 1620 WATER 26
2 0.8 3 22 620 45K	0.3	280 106 0.09 .0002\$	67 11 97 0.7 7.1 23	72/02/28 1610 WATER	48.2\$ 10 28 10	72/02/28 1610 WATER 9
3 11 84 620	0.51	170 8 0.14 .013\$.016\$	2221 12.5 137 0.9 8.4 92	72/02/28 72/08/30 1610 1130 WATER WATER	68.9\$ 10 2 5	72/08/30 1130 WATER 20.5
1.5 1 2 2 28 290 60	0.14 0.2 0.3 0.09	100 32 0.04 .00008\$	12.9 97 1.4 7.3 29	73/02/12 845 WATER	36.5\$ 10 15 . 5 90	73/02/12 845 WATER 2.5
6 6 71	0.36	153 10 0.1	11.7 117.0\$	73/02/12 73/06/13 845 1055 WATER WATER	61.7 \$ 10 3 5	72/08/30 73/02/12 73/06/13 1130 845 1055 WATER WATER WATER 20.5 2.5 16.5
79	0.39	164 3 0.17	11.5 115.0\$ 95	73/09/24 1400 WATER	60.8\$ 10 2 0	73/09/24 1400 WATER 16

I MG/L 205 12 22 . L MG/L .010K 0.02 0.06	ZD NH3-N MG/L .00007\$.003\$ ZD NH3-NH3 MG/L .00009\$.004\$	00620 NO3-N TOTAL MG/L 0.11 0.29 0.3	NOT NOT	IG/L MG/L	IG/L 0.5 0.2 MG/L 0.04 0.13 MG/L 2.2 8	IG/L 0.5 0.2 MG/L 0.04 0.13 MG/L 2.2 8 MG/L 1.6 4	PO4 MG/L 0.5 0.2 PO4 PO4 MG/L 0.04 0.13 M NA,DISS MG/L 2.2 8 M K,DISS MG/L 1.6 4 DE TOTAL MG/L 0.4 3	0.5 0.2 0.04 0.13 2.2 8 1.6 4 0.4 3 1 6	0.5 0.2 0.04 0.13 2.2 8 1.6 4 1.6 4 0.4 3 MG/L 16 69	0.5 0.2 0.04 0.13 2.2 8 1.6 4 1.6 4 0.4 3 1 6 MG/L 16 69 AL 230 620
R	1945 WATER 70 7 .010K	1945 WATER 70 7 .010K .00004\$.00005\$	1945 WATER 70 7 .010K .00004\$.00005\$	1945 WATER 70 7 .010K .00004\$.00005\$ 0.14 0.3 0.11	1945 WATER 70 7 .010K .00004\$.00005\$ 0.14 0.3 0.11 2.7	1945 WATER 70 7 .010K .00004\$.00005\$ 0.14 0.3 0.11 2.7	1945 WATER 70 7 .010K .00004\$.00005\$ 0.14 0.3 0.11 2.7 1.6	1945 WATER 70 7 .010K .00004\$.00005\$ 0.14 0.3 0.11 2.7 1.6 2 2	1945 WATER 70 7 .010K .00004\$.00005\$ 0.14 0.3 0.11 2.7 1.6 2 20	1945 WATER 70 7 .010K .00004\$.00005\$ 0.14 0.3 0.11 2.7 1.6 2 2 20 620
1640 WATER	1640 WATER 180 44 0.09	1640 WATER 180 44 0.09 .013\$	15/01/08 1640 WATER 180 44 0.09 .013\$.016\$	1640 WATER 180 44 0.09 .013\$.016\$ 0.69 0.1	15/01/08 1640 WATER 180 44 0.09 .013\$.016\$ 0.69 0.5 0.5	15/01/08 1640 WATER 180 44 0.09 .013\$.016\$ 0.69 0.5 0.5	1640 WATER 180 44 0.09 .013\$.016\$ 0.69 0.5 0.1 8.9 3.1 4	1640 WATER 180 44 0.09 .013\$.016\$ 0.69 0.5 0.1 8.9 3.1 4	15/01/08 1640 WATER 180 44 0.09 .013\$.016\$ 0.69 0.5 0.1 8.9 3.1 4	1640 WATER 180 44 0.09 .013\$.016\$ 0.69 0.5 0.1 8.9 3.1 4 8 63
										75/11/10 1715 WATER 114 5 0.02 .0003\$.0004\$ 0.1 0.12 4.6 2.8 2 40 230

1STORET RETRIEVAL DATE 99/06/23
402389 28AWALL04860
45 54 13.6 118 22 02.9 4
WALLA WALLA RIVER U/S MILTON-FREEWATER
41059 OREGON UMATILLA
PACIFIC NORTHWEST 131007
COLUMBIA RIVER BASIN BELOW YAKIMA RIVER
21400000 17070102011 00

31615 FEC COLI MPNECMED /100ML 31677 FECSTREP MPNADEVA /100ML	31505 TOT COLI MPN CONF /100ML	22413 HARDNESS TOTLDISS WTR MG/L	00945 SULFATE SO4-TOT MG/L	00940 CHLORIDE TOTAL MG/L	00760 SWL PBI MG/L	00660 ORTHOPO4 PO4 MG/L	00620 NO3-N TOTAL MG/L	00619 UN-IONZD NH3-NH3 MG/L	00612 UN-IONZD NH3-N MG/L	00610 NH3+NH4- N TOTAL MG/L	00530 RESIDUE TOT NFLT MG/L	00500 RESIDUE TOTAL MG/L	00410 T ALK CACO3 MG/L	00400 PH SU	00310 BOD 5 DAY MG/L	00301 DO SATUR PERCENT	00300 DO MG/L	00095 CNDUCTVY AT 25C MICROMHO	00080 COLOR PT-CO UNITS	00027 COLLECT AGENCY CODE	00011 WATER TEMP FAHN	00010 WATER TEMP CENT	MEDIUM	INITIAL TIME	INITIAL DATE
Ă Á	F	1G/L																OHIM							

		230	23	(J)	H	∞	0.02	0.01	.0006\$.0005\$	0.14	2	89	26	7.4	0.6	94	11.2	59	6	5	10	42.8\$	6	WATER	1300	67/04/24	**********
		620	36	0.6	O1	1K	0.1	0.02	.003\$.002\$	0.17	00	101	32	7.5	0.8	101	8.7	180	2	7	10	69.8\$	21	WATER	1520	67/08/21	
	210	210	29	4	1	1	0.1	0.02	.002\$.001\$	0.32	6	83	32	7.5	1.1	98	11.9	69	4	15	10	41.0\$	C)	WATER	1700	67/12/11	
		230	24	2	1		0.07	0.03	.0004\$.0003\$	0.12	7	113	26	7.3	0.6	98	11.6	57	4	2	10	43.7\$	6.5	WATER	810	68/04/03	
		620	32	15	6		.01K	0.04	.001\$.001\$	0.18	22	98	40	7.3	0.4	102	9.7	93	4	S	10	60.8\$	16	WATER	905	68/08/06	
	N. The state of th	210	25	w	2		0.01	0.39	.0002\$.0001\$	0.11	26	92	16	7	0.2	87	11.1	57	U)	9	10	41.0\$	51	WATER	1030	68/12/16	
		60	26		2		0.11	0.3	.0003\$.0003\$	0.06	7	81	27	7.5	0.7	99	11.6	63	2	12	10	43.5\$	6.4	WATER	1540	69/03/04	-
5K		60	31	ယ	0.8		0.1	0.12	.0002\$.0002\$	0.03	6	67	33	7.7	1.2	100	12.9		0	2	10	37.4\$	w	WATER	1055	69/12/10	

INITIAL TIME	1420	1745	1630	1930	1745	174
MEDIUM	WATER	WATER	WATER	WATER	WATER	WAT
00010 WATER TEMP CENT	10.5	20.5		10.5	27	4.7
00011 WATER TEMP FAHN	50.9\$	68.9\$		50.9\$	80.6\$	40.
CT AGENCY	10	10	10	10	10	10
00070 TURB JKSN JTU	7	2	1	1	2	1.0
COLOR PT-CO	5	υ	1K	S	15	11
\Box	49	80		55	170	80
00095 CNDUCTVY AT 25C MICROMHO	. 53	90		54	195	7:
00300 DO MG/L	10.8	9		10.8	8.7	1
00301 DO SATUR PERCENT	101	103		102	106	9,
00310 BOD 5 DAY MG/L	₽	0.3		0.6	رى د	0.
00400 PH SU	7.5	00		7.3	00	7.
00410 TALK CACO3 MG/L	17	34	33	20	65	34
INITIAL DATE	74/05/06	74/07/30	74/11/11	75/05/27	75/07/08	75/11
INITIAL TIME	1420	1745	1630	1930	1745	17,
MEDIUM	WATER	WATER	WATER	WATER	WATER	WAT
00500 RESIDUE TOTAL MG/L	62	76	68	64	180	00
00530 RESIDUE TOT NFLT MG/L	39	4	1K	(J)	38	ပ
00610 NH3+NH4- N TOTAL MG/L	0.03	0.02	0.06	0.01	0.19	0.0
00612 UN-IONZD NH3-N MG/L	.0002\$.0008\$.00004\$.012\$.000
00619 UN-IONZD NH3-NH3 · MG/L	.0002\$.0010\$.00005\$.014\$.000
	0.01	0.05	0.06	0.1	0.72	0.1
00650 TPO4 PO4 MG/L	0.2	0.2		0.3	0.5	0.
00660 ORTHOPO4 PO4 MG/L	0.01	0.14	0.08	0.09	0.08	0.1
00930 SODIUM NA,DISS MG/L	2.1	(J)		2.4	8.4	ري د
00935 PTSSIUM K,DISS MG/L	1.6	2.4		1.3	3.5	2
00940 CHLORIDE TOTAL MG/L	0.4	0.9	1	-	6	-
00945 SULFATE SO4-TOT MG/L	2	↦	2	2	00	2
22413 HARDNESS TOTLDISS WTR MG/L	14	27	27	19	60	2
31505 TOT COLI MPN CONF /100ML	60	7000L		230	7000	241
31615 FEC COLL MPNECMED /100ML	45K	620		45	7000	23

LAND LEASE

1. PARTIES

The parties to this Lease are HULETTE M. JOHNSON, SHIRLEY A. JOHNSON, and H. MARC JOHNSON, hereinafter referred to as Landlord, and HUDSON BAY DISTRICT IMPROVEMENT COMPANY, and Oregon Non-profit Improvement District, hereinafter referred to as Tenant.

2. DATE

This Lease will begin the first of the following month, after the Tenant has obtained a water right certificate for the purpose of ground water recharge for this site from the State of Oregon.

3. DESCRIPTION OF LEASED PREMISES

Landlord leases to Tenant and Tenant leases from Landlord, under the terms and conditions stated herein, the real property in Umatilla County, State of Oregon, described in Exhibit "A" attached hereto and by such reference incorporated herein.

4. TERM OF LEASE

The term of this Lease will be from the date of this lease for a period of five(5) years. Tenant shall have the option to renew this lease with notice to Landlord of not less than 90 days prior to the end of the initial term and any renewal terms for future additional five year terms upon the mutual agreement of renegotiated rental terms for each renewal period.

5. POSSESSION

The Tenant shall be granted possession of the property upon execution of this document by all parties, together with the receipt of the initial lease payment as prescribed in RENT.

THAT DEAL

ESTRACT 1

The content of the co

STAG 3

ord Armide Content of American processing and the profession of the same of each of each of the same of each of the same of th

A DESCRIPTION OF LEASING PROPERTY.

The Continue of the Continue o

REASEL TO BESET A

The form of the based with the stan of past of the past of the past of the form of the for

s Polymonia

periodical descriptive of the property of the conference of the co

6. RENT

Tenant shall pay advance annual rent payments in the amount of three thousand six hundred dollars(\$3,600) plus annual assessment for irrigation water for surface water rights delivered by Tenant to 84140 Prunedale Road, beginning with INV # 1276C for 2003. Landlord shall pay same assessment to Tenant upon receipt of said annual assessment payment from Tenant. Tenant shall make each annual payment for the term of this lease to Landlords address, 52833 Sunquist Road, Milton-Freewater, Oregon, 97862, or otherwise as notified. The initial payment shall be due on the date this agreement is executed by Tenant and Landlord, and Tenant it therefore granted possession to said real property.

7. INSURANCE

Tenant shall maintain liability insurance on the leased property in an amount acceptable to the Landlord and shall provide proof of such insurance naming Landlords as additional insureds. Tenant shall also be responsible for necessary insurance on laborers. Tenant shall also be responsible for insurance coverage on personal property kept or installed upon this leased premises.

8. USE OF PREMISES

Tenant agrees that they will use the property for ground water recharge/storage, ponding.

9. LANDLORDS OBLIGATIONS

Landlord shall install electricity, pump, collection pond and mainline with the assistance of Tenant necessary to connect the source of irrigation water provided by Tenant to the existing delivery systems of Landlord's.

If there is a mortgage or other encumbrance on said premises, Landlord covenants to keep same in good standing, at all times, to make payments when due and not to suffer or permit default in said encumbrance.

Landlord shall pay all property taxes upon the real property subject to this lease in a timely manner.

TODIS A

Tennet state of the product of the property of the payment of the product of the product of the product of the payment of the

Management of

Tomore the property of the pro

BURNESS TO MEDIA

Tender equals that they fell use the property for ground enten

Production of the second

I ambient dealt begind electrica, programme per de describint problème. I Un restricte et l'emplement de source et tre source et tre product de l'origination tentre. Procedured tre l'account de discrimination dell'interpretation et l'emplement de

The last and an experience of a control of the cont

whill get in which have been provided and the state of th

10. TENANT'S OBLIGATIONS

Tenant shall provide all labor and materials for the construction of the ground water recharge pond, Landlord's irrigation collection pond and pumping station or other improvements required by Tenant, including maintenance of bridges and culverts.

Tenant shall pay all taxes of any kind and necessary insurance for labor to maintain to maintain improvements including any increase in property taxes as a result of said improvements as made by Tenant.

Tenant shall pay for all maintenance and operation of improvements constructed on said premises.

Tenant agrees that earth material excavated from the recharge pond shall be placed along the edges of the recharge area to produce a basin-like pond. Excess material shall be placed in other areas of Landlords property as directed by Landlord and spread evenly where located so that agricultural activities may continue.

Tenant upon termination of lease, shall replace all soil to a level topography using stored material from the sides of said 'recharge' pond, together with other off site soil as approved by Landlord, necessary to return the recharge pond to a level premise for agricultural growing activities.

Tenant shall pay for all costs incurred for control of noxious weeds and vegetation around perimeter of ponding areas, and shall spray the perimeter of said pond including the banks of the Hudson Bay Canal and the Pleasantview Canal including bridges and culverts to maintain a clean ground cover as directed by Landlord

Tenant shall provide signage for trespass prevention and notice of manmade hazard upon premises at the commencement of work efforts at the recharge area.

Tenant shall install any and all fences and gates necessary as may be required by an insurance company or others around the recharge pond.

SHOUMALING STRANGE OF

I dell'amplication de sit soft interestation independ i liquigning it a la many i garden et de la company partie i l'est de l'est de l'est de l'est des grands de l'est de l'e

The find of the first the transmission have been been to be a second for any there are not the control of the c

all meroromy at the enterty tree accommunity and heat was their tage of

Affinite As any amplified, will strong be constituted between the profession of profession profession and profession and profession are and distributed by the profession and the profession are and distributed by the profession are and distributed by the profession are and a second are also between the profession and the profession are an appropriate to the profession and the profession are an appropriate to the profession and the profession are an appropriate to the profession and the profession are a second are an appropriate to the profession and the profession are an appropriate to the profession and the profession are a second are

The state of the Ten resident their consideration posterior of the page to be the state of the s

The state of the s

Columnia provided from Goldine rising arresporat and colorage and investigation in a material lighter and policy and allower for improvement and as the last arresporate and allower and a

(and the restaut limb as fail, there are used the limb resignation of the limbs become I a should digitalize to the hope as well to be qualquinated to have a see the largery

11. LIENS

Tenant shall pay, as due, all claims for work done on and for services rendered or materials furnished to the leased premises incurred and owing by Tenant and shall keep the premises free of any liens resulting from acts of the Tenant.

6.8

12. COVENANTS OF TITLE

Landlord covenants that he is the owner of the above described property free of any encumbrance that would impair or interfere with Tenant's rights under this Lease, and that Landlord has full right and authority to lease the premises described herein.

13. WASTE

Tenant shall not commit or permit to be committed any waste, strip, damage to or misuse of the premises.

14. INDEMNIFICATION

Tenant shall indemnify, hold harmless and defend Landlords from all claims, loss or liability arising out of or related to any activity of Tenant on the leased premises or any condition of the leased premises in the possession or under the control of the Tenant.

15. ASSIGNMENT

No part of the leased property may be assigned, mortgaged, or subleased, nor may a right of use of any portion of the property be conferred on any third person by any other means without the prior written consent of Landlord. This provision shall apply to all transfers to and by trustees in bankruptcy, receivers, administrators, executors, and legatees. No consent in one instance shall prevent the provision from applying to a subsequent instance.

3400 LE 711

And the first bette me words drown with resistant for perbote a free fraction.

And finding bett becaused readones; bested out of distribution to be becomes on the expense of the finding of the period of the finding

52. COVERNORS OF CHILD

Lagrand of britished bounds with his manual state of the

THE WASTE

Exhibition with faithment of of throught of thought the flate recently and agrands

Tenary should the chart of terminal for early and black (dependent that exacts).

Let be be be been proportionally and the control of the control of the policy of the control of the chart of the chart of the best of the chart

THE PROPERTY AND

The control of the political product of the control

16. DEFAULT

The following shall be events of default:

Failure to pay rent when due.

Failure of either Landlord or Tenant to comply with any other term or condition or fulfill any other obligation of this Lease within twenty(20) days after written notice by Landlord or Tenant specifying the nature of the default with reasonable particularity.

Abandonment by the Tenant of the property

If the default is of such a nature that it cannot be completely remedied within the twenty-day period and the defaulting party thereafter proceeds with reasonable diligence and in good faith to effect the remedy as soon as practicable, default shall not be declared unless the defaulting party ceases to effect the remedy.

17. TAXES

The Landlord shall pay all real property taxes for real property for the term of this Lease. Tenant shall be liable to pay any taxes, personal or real, incurred as a result of improvements placed upon the leased premises.

18. NONWAIVER

Waiver by either party of strict performance of any provision of this Lease shall not be a waiver of or prejudice the party's right to require strict performance of the same provision in the future or of any other provision of this Lease.

ATTORNEY FEES

If suit or action is instituted in connection with any controversy arising out of the Lease, the prevailing party shall be entitled to recover, in addition to costs, such sums as the Court may adjudge reasonable as attorney fees.

20. SUCCESSION

Subject to the above-stated limitations on transfer of Tenant's interest, this Lease shall be binding upon and inure to the benefit of the parties, their respective successors and assigns.

21. INSPECTION OF PREMISES

The Landlord reserves the right to themselves and their agents to go upon the premises at reasonable and proper times to inspect the same for the purpose of determining that the Lease is being properly observed and that all of the terms of this lease are being performed by the Tenant.

22. IMPROVEMENTS

Any improvements to the real property by Tenant shall remain the property of the Landlord upon termination of this Lease, unless the Tenant obtains the written consent of Landlord to remove said improvements prior to the time the improvements are placed on the property. However, Tenant shall be responsible for refilling the recharge "pond" as set forth in paragraph 10 above.

23. TERMINATION

The Tenant agrees to deliver the property to the Landlord at the end of the term of this Lease and in as good a condition as when accepted, and pursuant to paragraph 10 above.

24. TIME IS OF THE ESSENCE

The parties acknowledge and agree that time is of the essence with respect to all of the terms, conditions, and provisions of this Lease.

25. NOTICES

Any notice required or permitted under this Lease shall be given when actually delivered or when deposited in the United States Mail as certified mail, addressed as follows:

PERMITTED IN THE

the part of the test of the selection of

STATE OF STREET STATE OF STREET

August des autobies, at plant form en des en est en en plant de proposer la contence d'ent l'en de contence de La contence de la contence de

imitation vincinal re-

And improvement to the expert of visage of the act of the money and but the money and the second of

POSTAVILOUS ES

The Count is feeling to the first project of the project of the first part to the first of the f

INVESTIGATION OF THE PARTY OF THE PARTY.

per a the contract of the all state to transport the audit broadless extract out to the wi-

MINISTER AT

a distribute de la fresionale de la vielt militar de la fresionale de distribute de la fresionale de la fres

LANDLORD: HULETTE M. JOHNSON, et., al.

52833 Sunquist Road

Milton-Freewater, Oregon 97862

TENANT: HUDSON BAY DISTRICT IMPROVEMENT

COMPANY P.O. Box 110

Milton-Freewater, Oregon 97862

WATER DUES

The annual irrigation water dues as billed to Landlord by Tenant shall be paid by Landlord to Tenant as billed. As part of the rent agreement in paragraph 6 above, Tenant shall pay Landlord an equal amount of said water dues within thirty(30) days of receipt of said water dues from Landlord, during the term of this Lease and any renewals thereof.

27. CAPTIONS AND HEADINGS

The captions and headings throughout this Lease are for convenience and reference only and the words contained therein shall in no way be held or deemed to define, limit, describe, explain or modify the meaning of any provisions of or the scope or intent of this Lease.

28. ENTIRE AGREEMENT

This document is the entire, final, and complete agreement of the parties pertaining to the Lease of the premises described herein, and supersedes and replaces all written and oral agreements theretofore made or existing by and between the parties or their representatives in so far as the premises are concerned.

Alices According to an extension contraction of the contract o

Prepinds - Idillison for Distribut Billion Shelest Cupitably P. D. Bos 110 Billion Suppose Distribution

- National Property

The account formation of the list of the l

PERSONAL PROPERTY OF THE PROPERTY OF

Interpretation (the polymer account with hereigneed), to principally become force and the consense of the contract of the cont

THE ENGINE ACCESSION

This document is becoming a limit of the control of the provided of the provid

	IN WITNESS WHEREOF, the parties have executed this Lease on the 15 day of October, 2003.
	LANDLORD: Shilley O. Show
	HULETTEM. JOHNSON, SHIRLEY MJOHNSON H. MARC JOHNSON
9	TENANT:
	HUDSON BAY IMPROVEMENT CO.
	BY: Joh c Joh
į	si's Secretary Treasurer
,	STATE OF OREGON)
	County of Umatilla)ss.
and a	On this 15 day of Oct 2003 personally appeared before me the above named HULETTEM. JOHNSON, SHIRLEY M. JOHNSON and H. MARC JOHNSON and acknowledged the foregoing to be a voluntary act and deed.
4.	OFFICIAL SEAL KATHLEEN F. YENNEY NOTARY PUBLIC FOR OREGON COMMISSION NO. 337142 MY COMMISSION EXPIRES SEPT. 24, 2004 My commission expires: 9-24-2004
5. **:	STATE OF OREGON) County of Umatilla)
	On this 15th day of Oct 2003, personally appeared before me the above named John C. Zerbainhis capacity as Sechtary / Treasurer of HUDSON BAY IMPROVEMENT CO. and acknowledged the foregoing to be a voluntary act.
	OFFICIAL SEAL NOTARY PUBLIC FOR OREGON NOTARY PUBLIC-OREGON COMMISSION NO. 337142 MY COMMISSION EXPIRES SEPT. 24, 2004 MY COMMISSION EXPIRES SEPT. 24, 2004

TRACT I:

美国经历公司

Terrible - Terrib

175 July

Township 6 North, Range 35, East of the Hillamette Meridian: Section 33: A tract of land located in the South Half of the Northeast Quarter, and being a portion of that tract of land conveyed to Hilliam J. Jackson, by Deed recorded in Book 369, Page 267, Deed Records, and being described as follows, to-wit:


Commencing at the quarter section corner on the line between Sections 33 & 34; running thence North 20 chains: thence Hest 33-16/100 chains; thence Southeasterly 32-16/100 chains, more or less, to a point on the center line; running East and Hest through said Section 33, said point being 7 chains West of the point of beginning; thence East 7 chains to the point of beginning. Excepting Therefrom, beginning at the Northeast corner of the Southeast Quarter of the Northeast Quarter of said Section 33: and running thence South 45 rods: then Nest 35-5/9 rods; thence North 45 rods; thence East 33-5/9 rods to the place of beginning. All being East of the Willamette Meridian, Umatilla County, Oregon. Subject to any and all water rights of way and roads.

-

TRACT !!!:

Beginning at the Northeast corner of the Southeast Quarter of the Northeast Quarter of Section 33, Township 6 North. Range 35; running thence South 45 rods; thence West 35 and 5/9 rods; thence North 45 rods; thence East 35 and 5/9 rods to the place of beginning. Excepting therefrom that tract of land conveyed to the State of Oregon, by and through its State Highway Commission by deed recorded in Book 130. Page 573 of the Deed Records of Umatilla County, Oregon, Also, excepting any portion of said premises lying within that strip of land conveyed to Walla Walla and Columbia River Railroad Company, by deed recorded in Book "D". Page 834 of the said Deed Records. All being East of the Willamette Meridian, in the County of Umatilla and State of Oregon;

Excepting any and all water rights of way.



Affachment &B:

License	No.	
THEFTING	7 100	

STATE OF OREGON

WATER RESOURCES DEPARTMENT

APPLICATION FOR LIMITED WATER USE LICENSE

Applic	ant(s):	Hudson Bay District Irrigation Company
	ct Person:	Jon Brough / John Zerba
Mailin	g Address:	B. O. Box 110
Telephone No:		541 438-6105
waters	or groundw	cation for a Limited License to use or store the following described surface vater-not otherwise exempt, or to use stored water of the State of Oregon for a or fixed duration:
1.	SOURCE(S	6) OF WATER for the proposed use: Walla Walla River a f Colombia River.
2.	TOTAL All	MOUNT OF WATER to be diverted: 50 cubic feet per second, or 50 minute. If water is to be used from more than one source, give the quantity
3.		D USE(S) OF WATER: (check all that apply) Road construction or maintenance; General construction; Forestland and rangeland management; or Other: Artifical Sional water Recharge.
4.	DESCRIPT	TION OF PROPOSED PROJECT: Include a description of the intended place

4. DESCRIPTION OF PROPOSED PROJECT: Include a description of the intended place of use as shown on the accompanying site map, the method of water diversion, the type of equipment to be used (including pump horsepower, if applicable), length and dimensions of supply ditches and pipelines:

See attacked polication document

5.	PROJECT SCHEDULE: (List day, month,	and year)
	Date water use will begin // 04	
	Date project will be completed//- Date need for water will be completed//-	
map this The five rely deter	TE: A completed water availability statement from meeting the requirements of OAR 690-340-030 request is \$100 for the first point of diversion plusicense, if granted, will not be issued or replaced consecutive years. The right granted will be subupon the same source, or water affected by the semined the use causes injury to any other water affected by the semined the use causes injury to any other water affected by the semined the use causes injury to any other water affected by the semined the use causes injury to any other water affected by the semined the use causes injury to any other water affected by the semined the use causes injury to any other water affected by the semined the use causes injury to any other water affected by the semined the use causes injury to any other water affected by the semined the use causes injury to any other water affected by the semined the use causes injury to any other water affected by the semined the use causes injury to any other water affected by the semined the use causes injury to any other water affected by the semined the use causes injury to any other water affected by the semined the use causes injury to any other water affected by the semined the use causes injury to any other water affected by the semined the use causes injury to any other water affected by the semined the use causes injury to any other water affected by the semined the use causes injury to any other water affected by the semined the use causes injury to any other water affected by the semined the use causes and the use causes are affected by the semined the use causes are affected by the semined the use causes are affected by the semined the use causes are affected by the semined the use causes are affected by the semined the use causes are affected by the semined the use causes are affected by the semined the use affected by the semined the use affected by the semined the use affected by the semined the use affected by the semined the use affected by the semined the use affected by the semine	must accompany this request. The fee for us \$10 for each additional point of diversion by a new license for a period of more than ordinate to all other authorized uses that ource, and may be revoked at any time it is
SIGN	NATURE of Applicant: Soc - Pron	DATE: //٥->3.03
	I certify that I have examined the foregoing apply grant a Limited License to use said water as derights of record, and subject to any valid publicant. This license shall be in effect beginning	escribed in the application, subject to all c interest concerns which may become
	WITNESS my hand this	
		Paul R. Cleary Water Resources Department Director
using shall i use ar	icensee shall give notice to the Department (Wate the water under the Limited License and shall n include, but need not be limited to, an estimate o nd the categories of beneficial use to which the w ed License, the record of use shall be available for	naintain a record of use. The record of use f the amount of water used, the period of ater is applied. During the period of the
The a	pplication was first received at the Water Resou day of, 20, at	rces Department at Salem, Oregon, on the o'clock,M.
(Fall, 200 M:\group	00) os/wr/forms/limited license appl	



Kennedy/Jenks Consultants

Engineers & Scientists

1020 North Center Parkway Suite F Kennewick, Washington 99336 509-734-9763 FAX 509-734-9764

3 July 2003

Mr. Bob Bower Hydrologist Walla Walla Basin Watershed Council PO Box 68 Milton-Freewater, Oregon 97862

Subject:

Test Site Hydrogeologic Assessment

Sediment Aquifer Study

K/J 026046.10

Dear Bob:

Kennedy/Jenks Consultants is pleased to present this letter report to the Walla Walla Basin Watershed Council (WWBWC). This letter report presents the results of a hydrogeologic assessment of the proposed shallow aquifer recharge test site (the test site) adjacent to the Hudson Bay Canal southeast of the WWBWC Office. This letter report was prepared as part of our letter contract with the WWBWC dated 13 February 2003 and amended 1 April 2003.

Introduction

The WWBWC is planning to sponsor a shallow aquifer recharge field test in the Walla Walla Basin (the Basin) just west of Milton-Freewater, Oregon. This letter report presents a preliminary hydrogeologic assessment of the proposed test site and the surrounding area. The area covered by this letter report includes an approximately 30 square mile area bounded on the north by the Washington/Oregon border, on the south by the base of the Horse Heaven Hills and Blue Mountains, to the east by a north-south line approximately 1 mile east of the Walla Walla River, and to the west by a north-south line through Umapine, Oregon (Attachment 1).

The proposed test site is located on approximately 9 acres adjacent to the south side of the Hudson Bay Canal (the Canal) in the east half of section 33, T6N, R35E (Attachment 1). This site is approximately 2 miles west of Milton-Freewater, Oregon, in Umatilla County. The test site was chosen because of its proximity to the Canal which will supply water for the test and the willingness of the land owner (Mr. H. Johnson) to allow construction of test infiltration ponds on the property.

The proposed test will be done with a facility consisting of three individual infiltration ponds lined up, one after the other, adjacent to the Canal. Approximately 50 cubic feet/second (cfs) of water will be available for diversion from the Canal into the upstream (easternmost) pond via a diversion structure. Water will then cascade from one pond to the next (from east to west) until it infiltrates out of the bottom of the pond(s). Any water escaping the final pond will be directed back into the Canal via a return pipe. In-flow from, and out-flow to, the Canal will be metered.

Testing is proposed for winter and early spring months when Walla Walla River flows (ultimate source of recharge water) are at their peak.

It is anticipated that recharge testing will be conducted under an ASR Limited License granted to the WWBWC by Oregon Department of Water Resources (OWRD) under OAR 690-350-0020. One of the requirements of the Limited License Application is to provide a supplemental preliminary hydrogeologic report describing groundwater conditions at the test site (OAR 690-350-0020 (3)(a)(b)(C)). This letter report, which is based predominantly on previously written reports and publicly available information, was written to meet this requirement.

This letter report focuses on suprabasalt sediments, the target for shallow aquifer recharge, and is subdivided into sections describing regional geology and hydrogeology, test site hydrogeology, surface water in the test site area (including springs), and groundwater and surface water quality. The assessment was done under the supervision of Mr. Terry Tolan, RG. The assessment is based largely on previously prepared and readily available reports and information. Attachments to this report include:

- Location map for the project area (Attachment 1)
- Structure contour and isopach maps for selected geologic units comprising the upper part of the shallow aquifer system (Attachments 2, 3, 4, and 5)
- A table summarizing geologic interpretations, well construction information, and water pumping data taken from water supply well logs used to assess area hydrogeology (Attachment 6)
- Draft test and monitoring plan (Attachment 7)

In addition, a number of reports and papers were reviewed for information relevant to this assessment. These reports are listed below.

Barker, R.A., and Mac Nish, R.D., 1976, Digital model of the gravel aquifer, Walla Walla River Basin, Washington and Oregon: Washington Department of Ecology Water-Supply Bulletin 45, 49 p.

Bauer, H.H., and Vaccaro, J.J., 1990, Estimates of ground water recharge to the Columbia Plateau regional aquifer system, Washington, Oregon, and Idaho, for predevelopment and current land-use conditions: U.S. Geological Survey Water Resources Investigations Report 88-4108, 37 p.

Bjornstad, B.N., 1980, Sedimentology and depositional environment of the Touchet Beds, Walla Walla River basin, Washington: Richland, Washington, Rockwell Hanford Operations RHO-BWI-SA-44, 116 p.

Busacca, A.J., and MacDonald, E.V., 1994, Regional sedimentation of Late Quaternary loess on the Columbia Plateau - sediment source areas and loess distribution pattern, *in*, Lasmanis, R., and Cheney, E.S., eds., Regional geology of Washington State: Washington Department of Natural Resources, Division of Geology and Earth Resources Bulletin 80, p. 181-190.

Busacca, A.J., Gaylord, D.R., and Sweeney, M.R., 2002, Paired eolian deposits and megaflood features, Columbia Plateau, Washington: Friends of the Pleistocene 10th annual Pacific Northwest Cell Field Trip, 16-18 August 2002 Field Trip Guide, 80 p.

Bush, J.H., Jr., Morton, J.A., Anderson, J.V., Crosby, J.W., III, and Siems, B.A., 1973, Test-observation well near Walla Walla, Washington - description, stratigraphic relationships, and preliminary results: Washington State University, College of Engineering Research Report 73/15-66, 38 p.

Campbell, N.P., Lillie, J.T., and Webster, G.D., 1979, Surficial geologic map of the Walla Walla quadrangle, Washington: Washington Department of Natural Resources, Division of Geology and Earth Resources Open-File Report 79-13, 1 plate, scale 1:250,000.

Carson, R.J., and Pogue, K.R., 1996, Flood basalts and glacier floods - roadside geology of parts of Walla Walla, Franklin, and Columbia Counties, Washington: Washington Department of Natural Resources, Division of Geology and Earth Resources Information Circular 90, 47 p.

Carson, R.J., McKhann, C.F., and Pizey, M.H., 1978, The Touchet Beds of the Walla Walla Valley, *in*, Baker, V.R., and Nummedal, eds., The Channeled Scabland - a guide to the geomorphology of the Columbia Basin, Washington: U.S. National Aeronautics and Space Administration, p. 173-177.

Fecht, K.R., Lindsey, K.A., Bjornstad, B.N., Horton, D.G., Last, G.V., and Reidel, S.P., 1999, Clastic Injection Dikes Of The Pasco Basin And Vicinity, BHI-01103, Bechtel Hanford, Inc., Richland, Washington.

Hewes, B, 2003, Hudson Bay Aquifer Recharge Project, consulting engineer report, 2 p.

Kienle, C.F., 1980, Geologic reconnaissance of parts of the Walla Walla and Pullman, Washington, and Pendleton, Oregon 1° x 2° AMS quadrangles: Seattle, Washington, Consultant report to U.S. Army Corps of Engineers, Seattle District, 76 p., 3 plates, scale 1:125,000.

Lindsey, K.A., 1996, The Miocene to Pliocene Ringold Formation and associated deposits of the ancestral Columbia River system, south-central Washington and north-central Oregon: Washington Department of Natural Resources, Division of Geology and Earth Resources Open-File Report 96-8.

Mac Nish, R.D., and Barker, R.A., 1976, Digital simulation of a basalt aquifer system, Walla Walla River Basin, Washington and Oregon: Washington Department of Ecology Water-Supply Bulletin 44, 51 p.

Mann, G.M., and Meyer, C.E., 1993, Late Cenozoic structure and correlations to seismicity along the Olympic-Wallowa Lineament, northwest United States: Geological Society of America Bulletin, v. 105, no. 7, p. 853-871.

Newcomb, R.C., 1965, Geology and ground-water resources of the Walla Walla River Basin, Washington and Oregon: Washington Department of Conservation, Division of Water Resources Water-Supply Bulletin 21, 151 p, 3 plates.

Pacific Groundwater Group, 1995, Initial watershed assessment water resources inventory area 32 Walla Walla River watershed: Washington Department of Ecology Open-File Technical Report 95-11, 47 p.

Piper, A.M., Robinson, T.W., and Thomas, H.E., 1935, Ground water in the Walla Walla Basin, Oregon-Washington: Transcript of Record, The State of Washington, Complainant vs. the State of Oregon; Supreme Court of the United States, October term, p. 72-142.

Price, C.E., 1960, Artificial recharge of a well tapping basalt aquifers, Walla Walla area, Washington Division of Water Resources, Water-Supply Bulletin 7, 50 p.

Reidel, S.P., and Tolan, T.L., 1994, Late Cenozoic structure and correlation to seismicity along the Olympic-Wallowa Lineament, northwestern United States (Discussion and Reply) - Discussion: Geological Society of America Bulletin, v. 106, no. 12, p. 1634-1638.

Reidel, S.P., Fecht, K.R., Hagood, M.C., and Tolan, T.L., 1989, The geologic evolution of the central Columbia Plateau, *in*, Reidel, S.P., and Hooper, P.R., eds., Volcanism and tectonism in the Columbia River flood-basalt province: Geological Society of America Special Paper 239, p. 247-264.

Rigby, J.G., Othberg, K.L., Campbell, N.P., Hanson, L.G., Kiver, E.P., Stradling, D.F., and Webster, G.D., 1979, Reconnaissance surficial geologic mapping of the late Cenozoic sediments of the Columbia Basin, Washington: Washington Department of Natural Resources, Division of Geology and Earth Resources Open-File Report 79-3, 94 p., 7 plates, scale 1:250,000.

Richerson, P., and Cole, D., 2000, April 1999 Milton-Freewater groundwater quality study: Oregon Department of Environmental Quality, State-Wide Groundwater Monitoring Program, 17 p.

Schuster, J.E., 1994, Geologic map of the Walla Walla 1:100,000 quadrangle, Washington: Washington Department of Natural Resources, Division of Geology and Earth Resources Open-File Report 94-3, 18 p., 1 plate.

Shannon & Wilson, Inc., 1973, Geologic studies of Columbia River basalt structures and age of deformation - The Dalles-Umatilla region, Washington and Oregon, Boardman nuclear project: Portland, Oregon, consultant report to Portland General Electric Company, 1 vol., 2 plates.

Smith, G.A., 1993, Missoula flood dynamics and magnitudes inferred from sedimentology of slack-water deposits on the Columbia Plateau, Washington: Geological Society of America Bulletin, v. 105, no. 1, p. 77-100.

Smith, G.A., Bjornstad, B.N., and Fecht, K.R., 1989, Neogene terrestrial sedimentation on and adjacent to the Columbia Plateau; Washington, Oregon, and Idaho, *in* Reidel, S.P. and Hooper, P.R., eds., Volcanism and Tectonism in the Columbia River Flood-Basalt Province: Geological Society of America Special Paper 239, p. 187-198.

Swanson, D.A., Wright, T.L., Camp, V.E., Gardner, J.N., Helz, R.T., Price, S.M., Reidel, S.P., and Ross, M.E., 1980, Reconnaissance geologic map of the Columbia River Basalt Group, Pullman and Walla Walla quadrangles, southeast Washington and adjacent Idaho: U.S. Geological Survey Miscellaneous Investigations Series Map I-1139, scale 1:250,000.

Swanson, D.A., Anderson, J.L., Camp, V.E., Hooper, P.R., Taubeneck, W.H., and Wright, T.L., 1981, Reconnaissance geologic map of the Columbia River Basalt Group, northern Oregon and western Idaho: U.S. Geological Survey Open-File Report 81-797, scale 1:250,000.

Tolan, T.L. and Reidel, S.P., 1989, Structure map of a portion of the Columbia River flood-basalt province, *in* Reidel, S.P. and Hooper, P.R., eds., Volcanism and Tectonism in the Columbia River Flood-Basalt Province: Geological Society of America Special Paper 239, Plate 1, scale 1:576,000.

USDOE (U.S. Department of Energy), 1988, Site characterization plan, Reference Repository Location, Hanford Site, Washington - consultation draft: Washington, D.C., Office of Civilian Radioactive Waste Management, DOE/RW-0164, v. 1 - 9.

Waitt, R.B., Jr., O' Connor, J.E., and Benito, G., 1994, Scores of gigantic, successively smaller Lake Missoula floods through Channeled Scabland and Columbia valley, *in*, Swanson, D.A., and Haugerud, R.A., eds., Geologic field trips in the Pacific Northwest: Seattle, Washington, University of Washington Department of Geological Sciences, v. 1, p. 1k.1 - 1k.88.

WWC (Woodward-Clyde Consultants, Inc.), 1980, Seismological review of the July 16, 1936, Milton-Freewater earthquake source region: Consultant report prepared for Washington Public Power Supply System, Richland, Washington, 44 p.

Wozniak, K.C., 1995, Chapter 2 - Hydrogeology, *in*, Hydrogeology, groundwater chemistry, and land uses in the lower Umatilla Basin Groundwater Management Area, northern Morrow and Umatilla Counties, Oregon - Final Review Draft: Salem, Oregon, Oregon Department of Environmental Quality Report, p. 2.1-2.80.

WPPSS (Washington Public Power Supply System), 1981, Nuclear project No. 2 - final safety analysis report: Richland, Washington, v. 2, amendment 18.

Other data sources used for the project include: (1) OWRD Water Well Reports (driller's logs) for water wells drilled in the project area, (2) interviews and conversations with people who have knowledge and/or experience with area groundwater, including OWRD staff, and (3) reconnaissance visits to the test site area. For this assessment it was assumed that well locations recorded on driller's logs are correct and the locations of wells were not independently field-verified.

Overview of the Test Site Area Geologic Setting

The most recent comprehensive geologic investigation of the suprabasalt sediments in the Basin, the strata which are the focus of this assessment, is Newcomb (1965). Our review of area geology is based on Newcomb (1965), more recent insights into area geology taken from reports describing regional suprabasalt sediment geology (Smith and others, 1989; Lindsey, 1996), and our ongoing work in the area on other projects. Since the emphasis of this hydrogeologic assessment is on the suprabasalt aquifer system, this section will focus primarily on the sedimentary strata and only briefly introduces the underlying Columbia River basalt.

Generally, suprabasalt sediments found in the Walla Walla Basin include (Figure 1):

- Holocene to Pliocene (?) alluvial gravel
- Pleistocene Cataclysmic Flood deposited sand and silt (Touchet Beds)
- Pleistocene loess (Palouse Formation)
- Miocene to Pliocene (?) conglomerate, sand, silt, and clay

Newcomb (1965) also described several terrace sequences within the Basin. These are not described in this letter report because they typically do not host aquifers. The basic physical characteristics and distribution of the uppermost 200 feet of the suprabasalt sediment sequence across the study area are briefly summarized in the following sections. We focus on the uppermost 200 feet of the suprabasalt sediment sequence because this is the stratigraphic interval that hosts the upper part of the shallow aquifer system, the primary target for proposed shallow aquifer recharge projects.

Holocene to Pliocene (?) Alluvial gravel

Basaltic, uncemented and nonindurated gravelly strata immediately underlies the groundsurface across much of the study area north of the base of the Horse heaven Hills. Based on the few outcrops of this unit described in reports (e.g., Newcomb, 1965), these strata are probably moderately to well bedded, have a silty to sandy matrix, and are generally uncemented. Our interpretation of borehole logs in the study area suggests the top of these strata appear to form a gently south-to-north dipping surface (Attachment 2). The alluvial gravel varies from absent to almost 120 feet-thick beneath the study area (Attachment 3). Many of the thicker accumulations of uncemented gravel appear to form elongate, linear tracts. Thickness variation in these strata

are inferred to be the result of paleodeposition in stream channels, syndeposition folding and faulting, and post-deposition erosion and deformation.

These uncemented gravels are generally equivalent to Newcomb's (1965) younger alluvial sand and gravel and referred to in the remainder of this letter report as alluvial gravel. The alluvial gravel is interpreted to record deposition of sand and gravel in the Walla Walla Basin by streams draining off the adjacent Blue Mountains and Horse Heaven Hills. These streams were probably the recent ancestors of many of the modern streams in the Basin, including the Walla Walla River, Mill Creek, Cottonwood Creek, Dry Creek, and Pine Creek. The distribution of the alluvial gravel, in large part, probably reflects the orientation of the streams in which these strata were deposited.

The age of the alluvial gravel is not well constrained. Depending on where one is at in the Basin, the alluvial gravel unit appears to predate, be contemporaneous with, and younger than the Palouse Formation and Touchet Beds. If this is the case, the alluvial gravel may be late Pliocene to Holocene in age (e.g., greater than 2 million years to less than a few thousand or even hundreds of years old).

Pleistocene Cataclysmic Flood Deposits (Touchet Beds)

During the Pleistocene, Cataclysmic Floods (e.g., Missoula or Bretz Floods) periodically inundated the Walla Walla valley between approximately 1,000,000 and 12,000 years ago (Waitt and others, 1994). Sand and silt deposited in the Walla Walla Basin by these flood waters consist of well stratified, normally graded, interbedded felsic silt and felsic to basaltic fine to medium sand (Figure 2). Finer grained layers tend to be brown to tan colored, coarser layers brown to gray-brown colored. Individual beds (or layers) range from a few inches to less than 3 feet-thick. These strata do not commonly display significant cementing, although some pedogenic calcium carbonate (caliche or hardpan) is commonly observed in the upper parts of these deposits where they are exposed at the Earth's surface. A range of soft-sediment deformation features and cross-cutting clastic dikes are commonly found in this unit (Fecht and others, 1999).

These Cataclysmic Flood deposits, also known as Touchet Beds, form most of the small hills located across the Walla Walla valley floor and along the base of the Blue Mountains (Attachment 4) to an elevation of approximately 1100 feet above mean sea level (msl).

Pleistocene loess (Palouse Formation)

Massive to poorly stratified silt and very fine sand deposits that display evidence of pedogenic (soil forming) modification is found on the hills surrounding the Basin (Figure 3). Pedogenic calcium carbonate may also be found in these deposits which are thought to be eolian (wind-deposited) loess, also referred to as the Palouse Formation (Busacca and others, 2002). These loess deposits are thought to range from greater than 1 million years old to less than 10,000 year old, making it older than, and age-equivalent to, the Touchet Beds (Busacca and others, 2002).

The Palouse Formation may be present in the western to central parts of the study area and intercalated within Touchet Beds. However, we suspect loess is rare to absent in this area because of a lack of loess outcrops. The Palouse Formation does crop out on the highlands bordering the southern and eastern edge of the Basin. Some of the strata mapped on Attachment 4 may be part of the Palouse Formation, but it was not differentiated from the Touchet Beds because of a lack of borehole log information.

Mio-Pliocene strata

Variably indurated conglomerate, sand, silt, and clay is found in the subsurface beneath the Walla Walla Basin. Based on limited outcrop descriptions, field reconnaissance, and borehole log descriptions these indurated gravel and sand, may locally have a caliche cap, and is they predominantly are basaltic in composition (Figure 4). Based on drill cuttings collected from wells recently drilled near Milton-Freewater, Oregon, these strata may also contain some mica and quartz. These indurated gravelly strata (conglomerate) are continuous beneath the entire study area (Attachment 5), range between approximately 75 and 250 feet-thick, and are referred to as the Mio-Pliocene conglomerate. It is differentiated from younger alluvial gravel unit by its physical characteristics, including a greater degree of induration, cement, and weathering.

The Mio-Pliocene conglomerate, sand, silt, and clay are generally equivalent to Newcomb's (1965) old gravel unit and old clay units. Newcomb (1965) placed the old gravel unit stratigraphically above the old clay unit. However, review of driller's logs across the study area reveal: (1) the presence of interstratified silt and gravel lithologies throughout entire thickness of the Mio-Pliocene strata, (2) areas where strata correlative to one of the two units, old gravel and old clay, are absent, and/or (3) areas where the inferred contact between the old gravel and clay units varies greatly in depth over distances of less than one mile. Given this, it is likely that the top of the old clay unit and bottom of the old gravel unit is not a single, continuous surface as suggested by Newcomb (1965). It is more likely that these strata interfinger and that a distinctive old gravel unit and old clay unit can not always be differentiated.

The mixed conglomerate, sand, silt, and clay forming the Mio-Pliocene unit are assigned a Miocene to Pliocene age (approximately 10 to 2 million years old) based on degree of induration, evidence of greater weathering, and stratigraphic position. To our knowledge no absolute age dates are available for this unit. Mio-Pliocene deposits of the Walla Walla Basin probably record deposition by the ancestral Salmon/Clearwater/Snake and Walla Walla River systems and include river channel deposits, overbank and flood plain deposits, and lake deposits. The distribution of coarse channel deposits in this unit should reflect the orientation of the ancient streams in which these materials were deposited.

Columbia River Basalt Group

The basalt flows that crop out on the highland bordering the Basin and that underlie the sediment sequence in the Basin belong to the Miocene Columbia River Basalt Group. The top of the Columbia River basalt surface is generally found to lie at lower elevations from the south (where it crops out on the steep hillsides south and west of Milton Freewater at elevations of

850 feet and above) to the north beneath the suprabasalt sediment filling the Basin. Abrupt elevation changes in the top of basalt near the Basin edge are interpreted to reflect the presence of faults offsetting this surface. Because of the depth at which this unit is generally found within the study area, it is assumed for the purposes of this assessment that it is likely that the Columbia River basalt does not exert a significant influence over the hydrogeologic behavior of the shallow suprabasalt sediment aquifer system in the immediate area of the test site.

Structural Geology

The Walla Walla Basin is a structural basin that began to develop during Miocene time (approximately 16 million years ago) and has continued to develop to the present day (Kienle, 1980; USDOE, 1988). The Basin is bounded on the south by the Horse Heaven Hills, the east by the Blue Mountains, and to the north by the Palouse Slope. The southern and eastern edges of the Basin are fault controlled. The uppermost basalt which crops out around the edge of the Basin on the Horse Heaven Hills and Blue Mountains is down dropped at these bounding faults. The faults, and associated folds, found on the southern and eastern edge of the Basin probably extends into the subsurface beneath the Basin (Kienle, 1980; Swanson and others, 1981). The presence of these faults beneath the Basin are inferred to, in part, explain discontinuities seen in the distribution of suprabasalt sediments, especially Mio-Pliocene sedimentary strata, and the top of basalt.

Overview of the Study Area Hydrogeologic Setting

Groundwater in the Walla Walla Basin is found in two primary aquifer systems: (1) the suprabasalt sediment aquifer system which is primarily hosted by Mio-Pliocene conglomerate and to a lesser extent, the overlying alluvial gravel (2) the underlying Columbia River basalt aquifer system. The suprabasalt aquifer, which is the target for shallow aquifer recharge, is the focus of this section.

Physical properties

The majority of the suprabasalt aquifer is hosted by Mio-Pliocene conglomerate unit while the uppermost part of the aquifer is found, at least locally, in the younger alluvial gravel unit. The suprabasalt aquifer is generally characterized as unconfined, but it does, at least locally, display confined conditions. Variation between confined and unconfined conditions within the aquifer system is probably controlled by sediment lithology (e.g., facies – coarse versus fine) and induration (e.g., cementation, compaction). Groundwater movement into, and through, the suprabasalt aquifer also is inferred to be controlled by sediment lithology (e.g., facies – coarse versus fine) and induration (e.g., cementation, compaction).

Given the physical properties of the alluvial gravel (non-indurated sand and gravel) versus those of the Mio-Pliocene conglomerate (e.g., finer matrix and the presence of naturally occurring cement), Mio-Pliocene conglomerate probably has generally lower permeability and porosity than the alluvial gravel. Consequently, suprabasalt aquifer groundwater flow velocities are inferred to be less where the water table lies within the Mio-Pliocene conglomerate than where it

lies within the younger, more permeable alluvial gravel. In addition, where the alluvial gravel is saturated, this uncemented, high permeability gravel and sand could form preferred pathways for groundwater movement and areas of increased infiltration capacity in the shallow parts of the suprabasalt aquifer system.

Very little hydraulic property information is available for the suprabasalt aquifer. Newcomb (1965) reports average effective porosity of 5 percent in the old gravel (e.g., the Mio-Pliocene conglomerate and sand). Given the physical characteristics of the overlying alluvial gravel, we suspect average effective porosity in it is higher. Modeling work by Barker and MacNish (1976) report estimated hydraulic conductivity and transmissivity of 1.5×10^{-4} feet/second to 7.6×10^{-3} feet/second and 10,000 feet²/day to 60,000 feet²/day, respectively, for the entire shallow aquifer. As with Newcomb's (1965) effective porosity estimate, we suspect hydraulic conductivity and transmissivity would be higher in saturated alluvial gravel than in saturated Mio-Pliocene conglomerate.

Groundwater level and flow direction

In the study, groundwater flow in the suprabasalt aquifer area is generally thought to be from south to north and northwest. There probably also is a component of groundwater movement towards the Walla Walla River where the suprabasalt water table near it is higher than the river. Where this occurs, the Walla Walla River is, in part, feed by groundwater discharge. However, along the course of the Walla Walla River through the study area, the suprabasalt water table may at least locally be below the bed of the river during much of the year. This is thought to be common between Milton-Freewater and the Stateline. When and where this occurs, such reaches of the river probably lose water to the suprabasalt aquifer.

WWBWC staff are collecting suprabasalt aquifer water level data from water supply wells located within the Basin between the Walla Walla River and Umapine. Water level data reported on well logs, and the few reports written for the Basin, suggest groundwater levels near the Walla Walla River (and many of the spring creeks) historically were relatively shallow, commonly less than 5 feet deep. With increased groundwater use over the past 20 years these water levels have generally declined, at least locally. This groundwater level decline is thought to account for, at least in part, the reduction in spring creek flow reported by many land owners in the Basin. Based on WWBWC water level data, the depth to suprabasalt aquifer groundwater ranges from 30 to 40 feet near Milton-Freewater, 3 to 10 feet along the Walla Walla River north of Milton-Freewater, 1 to 10 feet along the East and West Prongs of the Little Walla Walla, and 30 to 50 feet in the Umapine Area.

Aquifer recharge

Natural recharge to the suprabasalt aquifer is described by Newcomb (1965) to be from infiltration of surface water into the ground near the edge of the Basin where streams leave the adjacent basalt highlands and flow out onto the basin floor. The majority of this recharge probably occurs in the spring when streams flowing into the Basin reach peak discharges. Precipitation on parts of the Basin floor where the alluvial gravel and older, Mio-Pliocene strata lie at, or near, the surface also provides some natural recharge. With flood control and

channelization of the Walla Walla River and smaller streams, natural recharge via infiltration from surface waters has probably decreased with continued development.

Artificial recharge of the suprabasalt aquifer has become an important component of the hydrologic system since the 1920's and 1930's. This recharge is thought to have historically contributed water to at least some shallow water wells and springs (Newcomb, 1965). Artificial recharge probably occurs through irrigation ditch leakage and infiltration past the root zone in irrigated fields. With the advent of ditch/channel lining and reduction in the practice of flood irrigation, this type of recharge has probably decreased.

Reduced natural and artificial recharge will, and probably does, at least in part account for decreased suprabasalt water table levels. These reduced levels probably account for reduced spring flows and base level discharge to the Walla Walla River. The objective of the proposed SASR project is to attempt to locally replenish groundwater in the suprabasalt aquifer and restore some spring flows and Walla Walla River baseflow.

Water Quality

The most up-to-date groundwater quality data for the study area is found in Richerson and Cole (2000), an Oregon Department of Environmental Quality (ODEQ) report prepared for the northern portion of Umatilla County between Milton-Freewater and the Stateline. Two water quality parameters presented in the ODEQ report suggest groundwater quality in the uppermost suprabasalt aquifer in the area is relatively good with regard to ODEQ standards. These parameters, total dissolved solids (TDS) and nitrate-N, range from 150 to 250 mg/l and 0.5 to 4.5 mg/l, respectively on the Oregon side of the Stateline. Concentrations of these parameters generally decrease from north to south toward where the Walla Walla River enters the valley. This trend suggests the introduction of low nitrate-N and TDS surface water into the groundwater system and supports Newcomb's (1965) conclusion that a significant amount of surface water recharge of shallow groundwater occurs where the Walla Walla River enters the Basin. The increase in TDS and nitrate-N concentrations as suprabasalt groundwater moves north into the Basin is inferred to be, at least in part, the result of the relative increase in recharge from irrigation water reaching the suprabasalt aquifer.

Test Site Hydrogeology

Geologic features control the physical characteristics of aquifer hosting materials, and therefore the distribution and movement of groundwater through an aquifer. Understanding the nature and occurrence of these features both regionally and locally provide constraints on testing, data interpretation, monitoring, mitigation, and final design. This section describes the basic hydrogeology in the immediate vicinity of the test site.

Information reviewed for this assessment report is interpreted to indicate that the uppermost 200 feet of the suprabasalt sediment sequence underlying the test site consists predominantly of gravelly strata assigned to the Mio-Pliocene conglomerate (Figure 5). Specific unit thicknesses and distribution in the immediate vicinity of the test site are as follows:

- Touchet Beds are thin to non-existent, being absent at, north, and east of the test site. A
 thin veneer of Touchet Beds are found northwest and south of the test site where the
 unit is 6 to 18 feet thick and less than 5 feet-thick, respectively. Given this distribution,
 the unit has no role in effecting recharge at the test site.
- The top of the alluvial gravel unit beneath the test site is essentially the ground surface.
 Beneath the test site these uncemented strata are interpreted to range from
 approximately 30 feet-thick at the east end to over 60 feet-thick at the west end
 (Figure 5). Based on our interpretations of well logs in the vicinity, this east to west
 thickening is inferred to be the result of these strata filling a depression in the top of the
 underlying, indurated Mio-Pliocene conglomerate.
- The origin of the low inferred to be in the top of the Mio-Pliocene conglomerate is not known. The location of the test site near the fault zone that bounds the base of the Horse Heaven Hills suggests this low could be a faulted depression formed in the top of the conglomerate. Alternatively, given the variable quality of driller's geologic descriptions we can not completely discount the possibility that this low is not present, it being the result of poor or inaccurate driller's descriptions. One of the objectives of site-specific characterization work will be to verify the presence of this feature. Mio-Pliocene conglomerate underlying the test site appears to be at least 100 feet-thick (Figure 5).

In the immediate vicinity of the test site the suprabasalt aquifer water table appears to be between 30 and 55 feet bgs. Based on our reconstruction of site-specific geology summarized in the preceding bullets and in Figure 5, this places the water table predominantly within the Mio-Pliocene conglomerate beneath the easternmost portion of the tests site. To the west, where the alluvial gravel thickens, the suprabasalt aquifer water table is interpreted to be within the alluvial gravel. In the test site area, suprabasalt aquifer groundwater flow is inferred to be from generally east to west-northwest. The degree of seasonal variability is not known

Review of first water and final water depth's reported on well logs in the immediate vicinity of the test site suggests the suprabasalt aquifer here consists of an unconfined zone overlying a deeper, semi-confined zone. The transition between these zones may lie approximately 75 feet bgs (Figure 5). The nature of the "confining" horizon(s) that causes this apparent change in aquifer character is not known, but inferred to be well cemented and/or fine grained layers within the upper 20 to 50 feet of the Mio-Pliocene conglomerate. Where the top of the Mio-Pliocene conglomerate drops into the low inferred to underlie and be situated west of the test site, this confining zone would be displaced to depths greater than 95 ft bgs and the overlying unconfined zone would be correspondingly thicker (Figure 5).

The assessment did not find any site-specific hydraulic properties data for any of the aquifers or the vadose zone underlying the Test Site. The only hydraulic properties data found are the general estimates provided in the regional discussions. These suggest porosity, hydraulic conductivity, and transmissivity of gravelly strata in the Basin of 5%, 1.5x10⁻⁴ to 7.0x10⁻³ ft/s, and 10,000 to 60,000 ft²/d, respectively. A preliminary engineering report for the materials immediately below the test site (Hewes, 2003) indicates infiltration capacity in the alluvial gravel

of 1.7 to 3.0 gpm/ft²/foot of head. If these values persist across the entire thickness of the alluvial gravel, porosity, hydraulic conductivity, and transmissivity in the alluvial gravel beneath the test site is probably considerably higher than the regional estimates. If that is the case, the regional estimates are probably more indicative of Mio-Pliocene conglomerate hydraulic properties.

Well Assessment

The OWRD GRID database lists 176 wells in sections 33 and 34, T6N, R35E. Of these, 53 are listed in section 33. Most of these wells are less than 100 feet deep and appear to be open to the shallow aquifer groundwater system which is the target of shallow aquifer recharge. Less than 30 of the wells found in section 33 are in the inferred down gradient direction from the test site.

Surface Water

Surface water found in the vicinity of the test site includes: (1) the Canal, (2) Dugger Creek, (3) Johnson Creek, and (4) Goodman Spring Branch (Attachment 1). The basic characteristics of these four water bodies are discussed below:

- The Canal is an artificial stream operated to deliver irrigation water to users west of Milton-Freewater. The Canal has a capacity of up to approximately 100 cfs and many reaches of it are suspected to leak.
- Dugger Creek appears to be a natural creek that is currently feed by water leaking from, and/or discharged from, the Canal. The head of Dugger Creek is approximately ³/₄ to 1 mile west of the test site.
- Johnson Creek is a natural spring creek that flows from a spring located in the SE $\frac{1}{4}$, SE $\frac{1}{4}$, section 29, T6N, R35E, approximately $\frac{3}{4}$ to 1 mile west-northwest of the test site.
- Goodman Spring Branch is a natural creek that has been modified by channelization. It
 passes within less than ½ mile north of the test site, paralleling Sunnyside Road.

All three of the natural creeks are reported to have seen reduced flow in the past few years.

Water Quality

As described in the regional hydrogeologic setting, there is little water quality data for the area except what is reported in Richerson and Cole (2000). That report shows TDS and nitrate-N concentrations in groundwater beneath the test site of approximately 125 to 150 mg/l and 2 to 2.5 mg/l, respectively. These parameter concentrations compare to those of approximately 55 mg/l and <0.25 mg/l at Milton-Freewater, where the Walla Walla River enters the Basin. If, as Newcomb (1965) surmises and others suspect, groundwater chemistry near Milton-Freewater is affected by direct recharge from the Walla Walla River, this groundwater chemistry is probably

reflective of surface water chemistry. Therefore, although not a direct measurement of surface water quality, this data is very suggestive of surface water quality and it suggests that recharge water delivered to the test site will be comparable to the water quality data reported in Richerson and Cole (2000).

Preliminary Conceptual Hydrogeologic Model and Possible Effects of Shallow Aquifer Recharge

The objective of this section is to briefly summarize a preliminary conceptual hydrogeologic model for the test site and speculate on possible effects of shallow aquifer recharge on the area surrounding the test site. One of the purpose of this is to identify data gaps to be filled by future site-specific work, including analysis of pilot test monitoring data. We anticipate that this conceptual model, and our assessment of recharge effects, will change as data is collected during subsequent characterization and monitoring activities.

Our conceptual model of how the test will work is summarized below:

- Relatively good quality Walla Walla River water will be delivered to the test site during peak flow periods in the winter and early spring. This water will rapidly infiltrate from the ponds into the ground, moving downwards through the alluvial gravel.
- 2. If the alluvial gravel and Mio-Pliocene conglomerate contact is located below the water table at the site:
 - a. There may be some lateral spreading of recharge water on the top of the Mio-Pliocene conglomerate,
 - Spreading will probably be predominantly to the west, into the low spot inferred to be present in the top of the Mio-Pliocene conglomerate, and
 - c. If this low turns out to be present, it may act to slow the movement of recharge water away from the test site and provide recharge pathways deeper into the Mio-Pliocene conglomerate than would be the case if the contact was flat.
- If the water table is above the alluvial gravel and Mio-Pliocene contact, movement of groundwater offsite will be relatively rapid through a saturated alluvial gravel interval. If this is the case, the actual direction of movement can not be determined at this time.
- 4. Given the groundwater quality trends seen in Richerson and Cole (2000), we infer that recharge will generally improve groundwater quality in the test site area.
- 5. At this time we do not know what effect, if any, recharge will have on the spring creeks potentially down gradient of the test site. This is in large part due to the lack of site-specific data and information, including water levels, aquifer hydraulic properties, storage data, and ground water velocity and flow direction. These are specific targets of site characterization and pilot test monitoring data collection.

Conclusions and Recommendations

The test site is underlain by uncemented alluvial gravel which overlies indurated Mio-Pliocene conglomerate. Unfortunately, little test site-specific data is available upon which to build a detailed understanding of test site hydrogeology. For example:

- The depth of the suprabasalt aquifer water table at the test site is not well constrained, it
 could lie either above or below the alluvial gravel/Mio-Pliocene conglomerate contact.
- Although suprabasalt groundwater probably flows from the east to the west-northwest, suprabasalt groundwater flow direction, velocity, and seasonally variability are essentially unknown at the test site.
- A significant portion of the suprabasalt aquifer in the test site area displays at least some evidence of semi-confined conditions.
- The low in the top of the Mio-Pliocene conglomerate currently inferred to be present just
 west of the test site, based on very limited subsurface data. If present, it could serve to
 facilitate recharge to deeper parts of the suprabasalt aquifer. If it seems likely that it will,
 testing and monitoring will need to be designed to not only assess shallower aquifer
 impacts but also deeper semi-confined suprabasalt aquifer impacts.
- Suprabasalt aquifer and Walla Walla River (Hudson Bay Canal) water quality is generally good, although up-to-date water quality data, including most importantly up gradient and down gradient variations at the test site is unknown.

In addition to addressing the bullet listed above, we recommend that site-specific characterization and monitoring address the following issues:

- Identify the three-dimensional extent of the alluvial gravel and Mio-Pliocene conglomerate beneath the test site. This is important to understanding how recharge water will probably move as the uncemented strata may provide for more rapid water movement, both downwards and laterally towards springs, then likely in the more cemented Mio-Pliocene conglomerate.
- Evaluate the inferred low in the top of the Mio-Pliocene conglomerate just west of the
 test site. If this feature is present, it could affect the amount of recharge that may reach
 deeper portions of the suprabasalt aquifer.
- The nature and distribution of a possible confining layer within the upper portion of the Mio-Pliocene conglomerate should be investigated in order to better define the thickness and distribution of the unconfined aquifer. If the unconfined aquifer is absent, or only present seasonally, identifying the nature and extent of the confining layer is important since it will inhibit both downward or upward movement of groundwater. Knowing the

extent of this confining layer will provide information on where recharge water may tend to collect and spread atop this layer.

If you have any questions concerning the results of this report please do not hesitate to contact Terry Tolan in our Tri-Cities office at (509) 734-9763. It has been a pleasure working with you on this and we look forward to continuing to work with you on this project.

Very truly yours,

KENNEDY/JENKS CONSULTANTS

Terry Tolan, R.G. Hydrogeologist

Kevin Lindsey, Ph.D. Project Manager

Luy a Lur

OREGON TERRY L. TOLAN 1285

Enclosure

cc: file

026046.10 9.08 test site hydro assess




Figure 1. Stratigraphic chart for the suprabasalt sediments in the Walla Walla Basin.




Figure 2. Photograph of interbedded sand and silt typical of the Touchet Beds. Darker layers are sandy, lighter colored layers are silty.




Figure 3. Photograph of massive bedded loess typical of the Palouse Formation.



Figure 4. Photograph of indurated basaltic gravel interpreted to be the Mio-Pliocene conglomerate. Note the caliche horizon at the top of the outcrop.




Figure 5. Schematic hydrogeologic cross-section of test site area.

Kennedy/Jenks Consultants

Attachment 6

Well Data Table

static																		17	29		40		24	7.5	34		60	70	47	2	38	13	30	000	2 2	50	38	46	31	
u.st water																		14	39				92	23	24		C	70			A6	48	04 00	07	_		80	21		
Mio-Pliocene conglomerate isopach	0	175	157	157	40	22	43	157	40	120		0	132	0	42	27	41	>141	>162		>85	5	>68	>114	>74			>104	>190	117/	200	20.	8-10-7	JRA	88<	>120	>64	>103	>104	108
Mio-Pliocene conglomerate top	₽N	992	997	266	931	006	1000	266	893	946	908		932	NP	1038	1047	1115	799	776	740	781	٤	768	811	738	758	744	/54	726.5	000	171	044	1/9	638	698	625	720	748	755	750
alluvial gravel isopach	19	16	0	က	24	48	0	3	55	10	34	0	0	0	28	21	0	0	0	36	0	خ	32	0	33	10	4	0	0 ;	12	0		0 !	2/	0	62	21	22	0	0
alluvial gravel top	066	1008	NP NP	1000	955	948		1000	948	926	939	NP	NP	NP	1066	1068	NP	NP	NP	692	NP	ċ	800	811	771	292	748	NP P	NP.	00/	d S	Z :	A !	695	NP	687	741	770	NP	NP
Fouchet	-	12	3	0	9	0	0	0	0	2	0	10	20	ω	0	0	0	6	34	44	37	٥	0	6	18	0	14	46	3.5	25	o 3	.71	46	3	12	18	20	0	9	17
Touchet	d dN	1020	1000	NP.	961	NP	NP.	NP	NP	958	NP	606	952	873	NP	dN	dN.	808	810	813	818	2	NP	820	789	Ν	762	800	730	725	730	999	723	869	710	705	761	NP.	761	767
Surf	000	1020	1000	1000	961	948	1000	1000	948	958	939	606	952	873	1066	1068	1115	808	810	813	818	817	800	820	789	768		800			730		723		_	-	_		-	767
year	na lien																	1987			1961		1985	1983	1975			1967	1960	1959	1954	1972	1984	1977	1957	1958	1988	1987		
	4 E 2 E 2 4 E 2 4 D	1536240.43310	153/619 09445	1534010.03440	1535068 43975	1536234 30863	1533404 64769	1533404.04103	1534740.33312	1535384 19590	1535882 11907		1535177 73996	1535869 97461	1520031 32008	1520557.32330	1523334.03143	1553631 25840	1554922 84501	1555870 11348	1553875 56988	1553133 33523	1553441 21997	1553161 89721	1554582.79992	1555266.71729	1554187.46077	1552921.13313	1552906.74304	1553223.32495	1554316.97155	1553352.83573	1547568.02081	1550330.91749	1548632.88724	1549510.68254	1547683 14151	1550489 20845	15/0194 10063	_
	-	1850613.13455 1				-				-	184307 1.42021		1024746 02653	-						The second		1953310 32674	1844678 98787	1947508 64881	1844934 02169	1841686 37895	1836304.48646	1837283,01236	1830490.89136	1828677.74041	1831857.94961	1821842.44915	1826461.66703	1	_				1033370.33202	
	0				\top	T	T	T	N			T	\neg	T		28 B		21-00/0	200		0/33-13	0/33-13	6/35-13	0/33-14	6/35-14	6/35-17	6/35-16	6/35-16	6/35-17	6/35-17	6/35-17	6/35-18	6/35-19	6/35-19	6/35-19	6/35/10	6/36/30	0/30-40	0/33-7	
		03885	03888	03909	03814	03918	03922	03930	U3934	03937	U3940	19861	03820	10820	03820	U3967	U3963	03800	114405	04180	04202	04504	04200	04211	04218	114240	114256	114258	U4273	U4275	U4279	U4282	U4289	114293	114304	114305	04000	04317	04318	114320

Page 1

Oit ct	water	32.5		22	44	26	54				20	30		NR		29	16	10		32	27	29		27	NR	9	NR	34	28	33	49	54	NR		16	34	32	20	50		
	water				40	21	47?				75	12		NR.		65	2	15		39	28	43		65	NR	NR	NR	65	38	45	61	NR	NR		20	49	44	45	80		
Mio-Pliocene	isopach	>98	354	>169	>153	330	>82	37	240		>80	>87	226	144		>111	>100	>82			>25			06	63	>26	>155	>98	>67	>81	>103	>130	>68		>78	>138	>113	>125	>159	330	
Mio-Pliocene	top	715	783	765	764	807	774	793	802	790	775	795	817	842	781	805	838	833	779		760		794	790	832	988	850	910	830	881	968	875	838	853	803	853	788	800	852	832	820
alluvial	isopach	43	2	0	15	0	6	0	31	15	36	36	25	0	0	17	7	18	0	>61	52	>80	0	100	27	0	0	7	35	24	12	20	24	0	42	12	31	18	41	0	0
leivulle	gravel top	758	788	NP	779	NP	783	NP	833	805	811	831	842	NP	NP	822	845	851	NP	908	812	814	NP	890	859	NP	NP	917	865	902	808	895	862	NP	845	865	819	818	893	NP	NP
Toholichet	isopach	22	6	20	3	12	27	47	7	35	4	6	8	8	65	18	2	2	34	39	28	25	49	0	0	9	20	0	0	0	0	0	8	10	0	0	11	12	0	20	30
Tollohot	top	780	797	785	782	819	810	840	840	840	815	840	850	850	846	840	850	928	813	845	840	839	843	NP	NP	892	870	NP	NP	NP	NP	NP	870	863	NP	MP	830	830	NP	882	850
ţ	elev	780	797	785	782	819	810	840	840	840	815	840	850	850	846	840	850	856	813	845	840	839	843		~~2	1000				172.0	808			863			-			882	850
200	drilled	1965		1951	1943	1974	1969				1979	1975		1946		1987	1985	1982		1977	1977	1977		1979	1934	1926	pre-1917	1981	1977	1977	1974	1968	1925		1988	1982	1981	1981	1977		
	northing	1552244.79904	1547467.29020	1547668.75142	1550618.71923	1549021.41958	1552546.99087	1549194.10063	1549597.02306	1549077.08306	1552125.34442	1548154.10353	1548105.52566	1547692.61376	1550728.73065	1549660.01751	1548700.60457	1548239.11480	1552526.11185	1549380.69475	1551117.35361	1552441.10058	1552726.49556	1544535.05220	1547291.84634	1543818.52862	1546490.31148	1542482.63719	1545324.44259	1542919.83802	1542519.07059	1542931.98249	1545579.47641	1546332.43340	1545304.42671	1544041.40209	1545231.55991	1547028.94110		1542183.29855	1546518.87347
	easting	1837527.64384	1835081.32907	1833210.61778	1837412.52314	1839168.11374	1842636.12468	1840952.48451	1841038.82504	1843360.86335	1847210.65956	1843482.30802	1845206.82242	1847635.71593	1850683.97728	1848631.56226	1848340.09504	1849748.85328	1852663.52549	1850356.07666	1851291.20066	1851145.46705	1848908.86094	1852420.63614	1851764.83489	1852967.13718	_	1848157.92803	1843652.33057	1845000.36647	1845886.91260	1844077.38693	1844878.92179	1845291.83369	1839687.61171	1840999.21421	1838133.11986	1839204.86913	1842760.16200	1841242.10356	1842663.00626
	T/R-sec	6/35-21	6/35-21	6/35-21	6/35-21	6/35-22	6/35-22	6/35-22	6/35-22	6/35-23	6/35-23	6/35-23	6/35-23	6/35-23	6/35-24	6/35-24	6/35-24	6/35-24	6/35-24	6/35-24	6/35-24	6/35-24	6/35-24	6/35-25	6/35-25	6/35-25	6/35-25	6/35-26	6/35-26	6/35-26	6/35-26	6/35-26	6/35-26	6/35-26	6/35-27	6/35-27	6/35-27	6/35-27	6/35-27	6/35-27	6/35-27
	Well ID	U4332	U4345	U4347	U4348	U4367	U4369	U4370	U4381	U4404	U4406	U4412	U4416	U4452	U4461	U4462	U4464	U4469	U4471	U4478	U4479	U4482	U4506	U4538	U4590	U4599	U4610	U4642	U4643	U4644	U4648	U4653	U4690	U4691	U4707	U4712	U4714	U4715	U4718	U4730	U4731

Page 2

Test Site Assessment Report Final Geology Table

	static	water	14	93	23	12	23		20	29	62	31	20		39	26	32	40	14	30		16		20	19		29	42	70	16	32	09	24	52	35		9	20		20	32	111
	_	_	NR	180	35	24	34?		NR	70	06	43	NR		09	31	NR	NR	35(?)	NR		16		29	303		110	NR	125	65	09	173	24		0							20
Mio-Pliocene	conglomerate	isopach	>79	>301	>118	>51	06<	130	>98	>330	>67	>110	>109		>83	>28	>90	>101	>205	09<	0	>87	0	>146	>132	193	>171	>56	265	>112	>95	>150	>97	>118	28<		24<		>137	09<	>21	72
Min-Plincene	conglomerate	top	864	786	830	750	818	834	928	740	959	750	745	674	693	615	672	649	299	716	NP	729	NP	805?	809	801	842	859	827	786	776	807	807	838	831		816		832	852	740	875
leiville	gravel	isopach	46	0	0	43	0	0	0	10	83	0	0	46	11	77	15	36	30	30	0	17	4	23(?)	0	0	31	44	80	0	38	35	2	29	0	>65	0	>30	3	28	92	18
	alluvial	gravel top	910	NP	NP	793	NP	NP	NP	750	739	NP	NP	720	704	692	687	685	269	746	NP	746	825	828	NP	NP	873	903	835	NP	814	842	809	867	NP	824	NP	811	835	880	835	893
		isopach (0	14	5	12	14	12	2	0	11	0	0	11	9	0	3	0	2	15	12	16	.8	12	9	32	3	0	2	18	3	0	9	3	3	10	3	10	0	2	0	0
	Touchet	top	NP	800	830	805	832	846	930	NP	750	NP	NP	731	710	NP	069	NP	702	761	856	762	833	840	815	833	876	NP	837	804	817	NP	815	870	834	834	819	821	NP	882	NP	NP
	Surf	elev	910	800	830	805	832	846	930	750	750	750	745	731	710	692	069	685	702	761	856	762	833	840	815	833	928	903	837	804	817	842	815	870	834	834	819	821	835	882	835	893
	year	drilled	1981	1978	1978	1977	1971		1908	1988	1978	1976	1954		1985	1977	1971	1955	1955	1966		1981		1979	1970		3/82	1908	3/80	12/79	10/79	8/79	12/71	4/53	-/16	-/26	-/22	<-/20	1916	-/15	1910	1988
		northing	1543941.71892		1544344.64135		1545006.58535	1542358.80936	1538335.30152	1545193.65648	1542258.07875	1544934.63491	1545222.43665	1546301.69317	1543941.71892	1543812.20814	1545064.14569	1545121.70604	1546431.20395	1541236.38259	1537181.57710	1541610.52485	1539853.35996	1538845.36916	1538918.23596		1537655.21134	1540314.84973	1538602.47981	1541912.71667	1539270.42552	1541092.48172	1540991.75111	1538578.19087	1538371.73492	1540630.60589	1539270.42552	1540991.75111	1538031.68983	1537400.17752	23	1539233.99212
		easting	1834534.50577		1836563.50802		1837498.86367		1843119.99808	1829138.22319	1827598.48390	1828893.59172	1828461.88911	1827497.75329	1823900.23157	1821971.95993	1822418.05262	1821871.22932	1823813.89105	1825166.55922	1830635.48544	1827656.04425	1829190.29380	1830963.38606	1832445.01110		1837314.94259	1841771.96218	1834594.58186	1832462.33326	1832566.45578	1835815.22350	1833138.66734	1837266.36472	1833793.04700	1835153.22736	1832894.35640	1833800.61134	1833793.04700	Jan Street		1839585.95802
		T/R-sec	6/35-28	6/35-28	Torres.	6/35-28	6/35-28	6/35-28	6/35-34	6/35-29	T	6/35-29	6/35-29	6/35-29	6/35-30	6/35-30	6/35-30	6/35-30	6/35-30	6/35-31	6/35-32	6/35-32	6/35-32	6/35-32	6/35-32	6/35-32	6/35-33	6/35-34	6/35-33	6/35-33	6/35-33	6/35-33	6/35-33	6/35-33	6/35-33	6/35-33	6/35-33	6/35-33	6/35-33	6/35-33	6/35-33	6/35-34
		Well ID	U4759	U4762	U4763	U4764	U4774	U4775	U4785	U4797	U4799	U4801	U4806	U4808	U4819	U4824	U4828	U4839	U4840	U4848	U4853	U4856	U4857	U4858	U4859	U4864	U4873	U4876	U4879	U4880	U4881	U4882	U4888	U4897	U4898	U4903	U4906	U4907	U4912	U4914	U4917	U4924

Page 3

Test Site Assessment Report Final Geology Table

	^				0	-			alluvial	Mio-Pliocene	Mio-Pliocene		-
Well ID	T/R-sec	easting	northina	year	elev	top	isopach	gravel top	graver	congiomerate	congromerate	water	static
U4929		319	539	1982	925	NP	0	925	38	887	>214	148	110
U4936	6/35-34	1842743.51958	1538906.09149	1978	924	NP	0	924	120	804	>42	45	15
U4938	6/35-34	1843083.56467		1977	932	NP	0	932	41	891	>101	35	36
U4939	6/35-34	1841152.59433	_	1977	922	NP	0	922	20	852	>50	80	47
N4946	6/35-34		_	1973	891	NP	0	NP	0	891	>125	117	45
U4948	6/35-34		_	1971	895	NP	0	895	40(3)	855?	>88	(3)	41
U4954	6/35-34	1840011.01438			912	NP	0	912	20	892	169		
U4970	6/35-34	1842294.17428	1538311.01258	1960	923	NP	0	923	22	901	141	NR	40
U4971	6/35-34	1839646.68036	1537339.45518	1959	902	NP	0	902	20	885	>92	40	35
U4973	6/35-34	1842901.39766	1540144.82718	1959	915	NP	0	NP	0	915	>121	NR	23
U4975	6/35-34	1839525.23568	1536938.68775	1956	902	NP	0	902	26	879	>84	10	19
US	6/35-30	1821986.35002	1546632.66516	1987	681	681	4	677	9	671	>111	40	39
U50011	6/35-13	1848856.68471	1553599.09805	1995	810	810	44	NP	0	992	>146	181	
U50016	6/35-33	1833222.25702	1537278.73284	11/95	865	865	29	836	10	826	>202	41	100
U50068	6/35-31	1822668.71473	1539671.19295	1996	738	738	42	969	>126?			90	09
U50069	5/35-12	1853357.78422	1531534.39969		1163	1163	11	NP	0	1152	115		
U5021	6/35-34	1838626.54508	1537436.61092	<1900	890	NP	0	890	1.5	888	>91		20
U5025	6/35-34	1838165.05532	1539404.01466	خ	875	NP	0	875	3	872	>42		30
U50250	6/36-18		1555865.84042		835	835	63	NP	0	772	144		
U5027	6/35-35	1843397.29675	1541183.17916		606	606	18	891	9		0		
U5039	6/35-35		1537582.34453	1983	952	NP	0	952	98	854	>92	103	86
U5042	6/35-35		1540132.68272	1982	933	NP	0	M	0	933	226	80	70
U5043	6/35-35		1537618.77793	1982	970	NP	0	970	34	936	>119	46	34
U5044	6/35-35		1541462.50191	1982	918	NP	0	918	17	901	>85	75	09
U50473	6/35-36	_	1539707.62635	1997	952	AN	0	952	18	934	>87	NR	38
U50478	6/35-34		1539112.54744		875	MP	0	875	27	848	216		
U5048	6/35-35		1536975.12115		947	NP NP	0	NP	0	947			
U5049	6/35-35		1538869.65809	1981	947	A _P	0	947	152 ?			114	20
U5050	6/35-35		1541243.90150		922	NP NP	0	922	12	910			
U50516	5/35-4		1536550.06479		921	921	55	NP NP	0	998	71		
U5052	6/35-35		1541644.66893	1981	920	N N	0	920	30	890	>247	20	34
U5053	6/35-35			1979	808	AN	0	806	80	828	>20	80	45
U5057	6/35-35	1845158.24455		1977	915	AP	0	915	30	885	>132	46	36
U50577	6/35-32	1831194.13094	1539100.40297		820	820	12	808	17	791	385		
U5058	6/35-35	1845706.76966	1537618.77793		928	NP	0	958	26	932	119		
U5059	6/35-35	1846629.74920	1540557.73908	1977	935	NP	0	935	27	908	>98	45	34
U50804	6/35-34			1997	930	A N	0	930	86(?)	844?	>965	46	43
U5091	6/35-35			1960	944	NP	0	944	>167?			NR	09
U50953	6/35-34	_			902	MP	0	902	30	875	220		
U51035	6/35-13	1851655.53468	1554359.92645	1998	802	802	13	789	25	764	>120	14	5.5

Page 4

Test Site Assessment Report Final Geology Table

static	water		20	34	36		30			,69	28					30	26	43		33	43	35	34	19	49		47	34					47				30		42		
	water		35	22	78		NR			52	85					24	98	09		41	55	80	46	45	NR		75	40					NR.				35		NR		
Mio-Pliocene	isopach		>80	>41	>47		>115	15		>110	118	145	233	467	180	>91	>77	>149		>122?	>123	>65	>55	09<	>182		>101	09<			∞	260	>71	349	202	295	>77	387	>146	06	
Mio-Pliocene	top	761	904	870	869	971	096	869	815	772	853	883	944	974	948	746	767	894	781	834	699	942	855	206	822	853	099	805	962	783	1037	875	914	861	881	813	856	811	831	902	740
alluvial	isopach	0	40	09	55	10	20	83	0	0	47	0	0	0	0	19	34	36	0	71(?)	18	38	09	89	99	0	25(?)	65	0	99	26	0	21	2	37	0	95	0	34	0	36
luixin	gravel top	NP	944	931	924	981	086	952		NP	006	NP	NP	NP	NP	765	801	930	NP	902	687	980	915	975	888		685	870	NP	849	1063	NP	965	863	918	NP	951	М	865	NP	9//
Courbet	_	_	0	0	0	0	0	2	28	48	0	9	26	0	20	5.	o	0	0	0	8	0	2	2	2	9	0	0	2	10	0	4	0	0	0	6	0	o	0	18	2
Tollohot	top	NP	NP	NP	NP	NP	NP	954	843	820	NP	889	970		896	770	810	NP	NP	NP	695	NP	920	980	890	859	NP	NP	964	859	NP	879	NP	NP	NP	822	NP	820	NP	920	781
	elev	761	944	931	924	981	980	954	843	820	006	889	970	974	968	770	810	930	781	905	695	086	920	980	890	859	685	870	964	859	1063	879	965	863	918	822	951	820	865	920	781
100	drilled		1987	1985	1985		1961			1998	1978					1998	1989	1989		1999	1999	1990	1999	2000	2000		2000	2000					2001				1990		7/90		
	northina	418			L	1537460.89986	1537485.18879		1550813.74192				1539792.63762	1537983.11196	1539780.49316	1555827.93068	1546963.63716	1540569.88355	1553424.78617		1555108.42633	1537898.10069	1541875.41381	1537788.80048	1539962.66017	1547814.05844	1546647.05525	1544405.73611	1537995.25643	1547255.41293	1529907.04104	1545713.06555	1538553.90193	1541337.11320	1539999.09357	1542056.61754		1544272 69092	1541135 65198	1534813,40593	1554145.59909
	easting	829				-	11000	-	1855505 33090 1			4	4					11		-	1828720.91067			-	0.83				1848487.85273	1	1851779.00344	1847149.93722	1849046.49824	1838506.16975	1843277.87615	1834361 82473	1000	1835685 71272		1839391.64654	
	T/R-spc	_	1	_	T	_	_		Id			S 543	1		1	1			T	_	1	T.			_	6/36-19	6/35-30	6/35-27	6/35-36	6/35-26	5/35-12	6/35-26	6/35-36	6/35-34	6/35-35	6/35-28	6/35-35	6/35-28	6/35-34	5/35-3	6/35-14
	T CHINAM	1.	+			-		+		-			+	1		1_		115316	1153413	U53462	U53471	115358	1153647	1153762	1153769	U53863	1153932	U53996	U54050	U54063	U5408	U54134	U54145	1154341	1154464	115464	115477	115/06	115517	115530	U5625

Page 5

	static	water	34		52	36		34			13	89	42	29	20	40	30		32	55	36	36	43	18	54	9	2						
-		-	55		22	42		NR.			16		89	20	89	55			55	25	65	09	47	09	NR.		NK.						
Mio-Pliocene	conglomerate	isopach	>289	187	>148	>147		>82		260	324	>208	>79	>80	>186	>94	29<	243	>52	>59?	>85	>140	>116	96<	>67		69	141	62		+6		
Mio-Pliocene	conglomerate	top	837	901	989	269	875	915	769	870	712	678	724	727	800	862	730	886	795	704?	863	835	738	629	663	806	951	916	971				
alluvial	gravel	isopach	11	80	25	65	24	23	0	6	10	0	0	63	16	16	35	0	28	54(?)	15	30	27	24	33	27	0	0	33				
	alluvial	gravel top	848	606	711	762	899	938	NP	879	722	NP	NP	790	816	878	765	NP	823	758	878	865	765	703	969	935	NP	NP	1004				
	Touchet	isopach g	4	0	12	8	0	0	44	0	16	29	46	7	0	0	0	0	12	10	0	0	0	0	2	3	0	23	0	100			
	Touchet	top	852	NP	723	765	NP	NP	813	NP	738	745	770	979	dN	NP	NP	NP	835	768	NP	N N	NP	NP	869	938	NP	939	NP				
	Surf	elev	852	606	723	765	899	938	813	879	738	745	770	797	816	878	765	886	835	768	878	865	765	703	869	938	951	939	1004				
	year	drilled	1992		1992	1995		1993			1978	1955	1976	1978	8/94	1994	1995		6/95	1995	1981	1981	1981	1982	1986		1966						
		northing			1546287 30308	1550618.71923	1544280 01838	1540812 77290	1554444 93772	1538881 80256	1552417.48009	1551913.82705	1549942 38514	1548733 61785	1539853 35996	1543964 26223	1554504 04268	1538651 05768	1541293 94293	1546272 91299	1545275 86472	1542183 29855	1545193 65648	1544949.02500	1546186.57247	1537120.85476	1537643.06687	1540399.86100					
		easting	1841035 64761 1545365 14905		6/35 30 1826101 91486			100					1831095 27501	1837513 25375	1832001 51214											$\overline{}$	11000	$\overline{}$					
		T/R-sec			6/25/24	6/35-21	T					6/35-20	6/35-20	6/35/34	6/35-21	6/25 26	C/35 45	6/35-13	6/25 22	6/35,20	6/25/20	07-00/0	6/35,20	6/35-30	6/35-30	6/35-35	6/35-35	6/35-36	5/35-1				
		Mell ID		115670	115743	115841	115058	115065	116017	116053	116192	116194	116106	06100	00200	116201	10201	100342	00000	116405	100400	116442	116445	116447	116449	116466	116468	116475	116509				

Kennedy/Jenks Consultants

Attachment 7

Test and Monitoring Plan

PRELIMINARY CHARACTERIZATION, MONITORING, AND TESTING PLAN, HUDSON BAY DITCH SHALLOW AQUIFER RECHARGE PROJECT

Introduction

Surface water and shallow groundwater in the Walla Walla Basin (the Basin) form an interconnected system. In some areas, especially upstream areas where streams leave the mountains and highlands surrounding the Basin to flow out onto the Basin floor, streams historically probably branched out onto the Basin floor and some of the water they carried seeped into the ground, recharging the shallow groundwater system. This shallow groundwater, recharged near the edge of the Basin, formed the main source of clean, cool groundwater found further down basin where it returned to the surface via springs and base flow to the Walla Walla River. Over the past 100 or more years this system has been modified both as a result of efforts to increase water supply for human use and to control flooding.

Shallow aquifer recharge is being explored in the Basin in large part to restore some fraction of the natural historical shallow aquifer recharge that has been lost, in part, because of modifications to surface water drainages in the Basin. These modifications have benefited the economic and social values of the Basin, but at some cost to natural habitat. It is hoped that shallow aquifer recharge projects, by mimicking natural historical shallow aquifer recharge that occurred in the Basin, will directly benefit habitat in streams that were in part maintained by natural spring and groundwater discharge.

The Walla Walla Basin Watershed Council (WWBWC), in cooperation with the Hudson Bay Improvement District (HBID), has proposed to test shallow aquifer recharge at a site located adjacent to the Hudson Bay Canal in section 33, T6N, R35E. At the test site a series of three infiltration ponds will be built. Water will be supplied to these ponds via a diversion from the canal. Recharge activities are proposed for winter and spring months when the Walla Walla River (the source of water for the canal) displays peak annual flows. The proposed shallow aquifer recharge testing will be done under an ASR Testing Limited License granted by Oregon Water Resources Department (OWRD) (OAR 690-350-0020).

The Limited License Application requires several supporting documents be attached (690-350-0020 (3)(b)), including (but not limited to) those describing proposed testing, groundwater conditions (including hydrogeologic conditions and groundwater quality), and source water quality. Some of this information is reported in the 3 July 2003 hydrogeologic assessment report. Information not included in the assessment report, but still needed for the Application, will be collected during proposed site-specific hydrogeologic characterization, monitoring, and testing. Preliminary characterization, monitoring, and testing plans are described here. These, especially the monitoring and testing plans, will be modified as information is collected.

Preliminary Test Site Specific Hydrogeologic Characterization

Site-specific hydrogeologic characterization is designed to identify and define local conditions which provide a technical basis for designing the monitoring which will be used to evaluate testing. For this project a number of characterization needs are outlined in the 3 July 2003 hydrogeologic assessment letter report. These needs include determining the physical properties of the geologic units underlying the test site, investigating the presence of a possible semi-confined aquifer in the upper part of the suprabasalt aquifer system, identifying aquifer

hydraulic properties, and establishing suprabasalt aquifer baseline conditions, including seasonal variation, for groundwater depth, flow direction, and quality. These, and other site characterization issues, will be addressed using test site-specific hydrogeologic characterization data collected predominantly using:

- Test pits, boreholes, and wells constructed for the direct observation of subsurface conditions,
- 2. Infiltration tests (constant and falling head) designed to evaluate spatial variability at a site both laterally and vertically (note, the water source for this activity may require a temporary permit),
- 3. Aquifer testing and water level measurements to evaluate baseline aquifer physical conditions before testing,
- 4. Surface and ground water quality data collected to evaluate the affect (if any) of test site operation on area groundwater quality,
- 5. Well and canal records describing water use in the project area, and
- Water flow metering at the test site that indicates surface water in-flow and out-flow during testing.

At this time, geophysical investigations are not being considered because of the lack of subsurface control and ground truth data that could be used to constrain geophysical interpretations. The following sections describe proposed soils, geologic, hydrogeologic, surface water, and water quality characterization for this project.

Soils

The nature and extent of surface soils effect how fast water can infiltrate into the ground. However, the infiltration ponds proposed at the test site will be excavated through the surface soil layer. Therefore, surface soil conditions and properties are largely irrelevant to the project except in as far as the amount of soil at the site controls the amount of excavation needed for the infiltration ponds. The proposed characterization work will simply look at surface soils to the extent necessary to determine how much soil will probably need to be removed for infiltration pond construction.

Geology

Geologic features control the physical characteristics of aquifer hosting materials, and therefore the distribution and movement of groundwater through an aquifer. Understanding the nature and occurrence of these features, both regionally and locally, provide constraints on testing, data interpretation, monitoring, mitigation, and final design. The objective of geologic characterization is to develop a three dimensional physical framework that describes the materials hosting the vadose zone and groundwater at the test site. Within this framework, or conceptual model, the nature and distribution of those factors thought to control groundwater movement and distribution will be evaluated.

Site-specific geologic characterization will be accomplished largely through the analysis of data collected during the drilling of several proposed boreholes at the site and comparison of that

data to information collected during the preparation of the hydrogeologic assessment report. A minimum of three boreholes are proposed for the immediate vicinity of the test site. One of these boreholes will be located on the inferred up-gradient side of the test site, two will be located on the inferred down-gradient side. In the assessment report we also recommend that at least one more down gradient well be placed near the test site. In addition, we recommend the placement of several additional boreholes located more distally from the test site in both the inferred up- and down-gradient directions. Subsurface hydrogeologic conditions will be interpreted via drilling cuttings and spilt-spoon sample logging.

The project hydrogeologic assessment identified work needed to complete site-specific hydrogeologic characterization. Hydrogeologic characterization targets, and the rational for them, are described below.

- It is likely that the uppermost, unconfined part of the shallow aquifer system, is hosted by predominantly uncemented alluvial gravel beneath the test site. However, it is not clear from the available data how deep the alluvial gravels extend and what their properties are beneath the test site. Identifying the three-dimensional extent of these strata is critical to the proposed testing because water probably will move more rapidly through these uncemented strata, both downwards and laterally, then in the deeper, more cemented Mio-Pliocene conglomerate that comprises the majority of the shallow aquifer system in the area.
- Area data indicates that, if present, the unconfined part of the shallow aquifer system at the site may be relatively thin and underlain by a semi-confined zone at depths of less than 75 feet bgs. Characterization will identify if this semi-confined zone is actually present, and if found, the nature of the confining layer separating it from the overlying unconfined zone and the basic hydrologic properties of the semi-confined zone. Knowing the nature and extent of the confined aquifer underlying the site is critical in evaluating if the proposed recharge will affect this deeper aquifer. If data collected indicates that the project could potentially affect this deeper aquifer, monitoring will need to be designed to not only assess shallower unconfined aquifer impacts but deeper confined aquifer impacts as well.
- The nature and distribution of the confining layer atop the confined aquifer should be identified in order to support evaluation of the thickness and distribution of the unconfined aquifer (if present). If the unconfined aquifer is absent, or only present seasonally, we will still need to identify the nature and extent of the confining layer because, just as it inhibits upward movement of groundwater, it will restrict the downward movement of recharge water. Knowing where the confining layer is will provide information on where recharge water collecting on top of it will spread to.
- Mapping for the assessment identified a potential depression in the top of the older Mio-Pliocene conglomerate below the western end, and west of, the test site. The depth, shape, and orientation of this feature will need to be evaluated because it will effect how the aquifer(s) underlying the test site respond to the testing. If an unconfined aquifer indeed underlies the site, this depression may act as a "reservoir" for water introduced into this aquifer. Alternatively, it may serve as a recharge pathway, hydrologically connecting the upper, unconfined part of the suprabasalt aquifer system with deeper, confined parts of the aquifer system.

The assessment did not provide any site-specific geologic properties data for any of the geologic units hosting the vadose zone and upper part of the suprabasalt aquifer underlying the test site.

Hydrogeology

Piezometers (observation wells) will be constructed in at least three of the borings drilled for geologic characterization. If additional geologic characterization boreholes are drilled (either close to or more distal from the test site) we also recommend that at least three of these be converted to observation wells. All but one of the boreholes converted to monitoring wells should be completed as 2-inch observation wells that fully penetrate the unconfined aquifer (if present) or above the confining layer (if unconfined aquifer not present). At least one of the geologic characterization boreholes should be of sufficient size to accommodate a 4-inch diameter well which will be used for aquifer testing.

Test site-specific hydrogeologic work would be done, in large part, concurrently with the site-specific geology work. The hydrogeologic assessment concluded that the following information must be collected for the uppermost part of the suprabasalt system at the test site:

- Depth, thickness, and lateral and vertical extent of the vadose zone and the uppermost aquifer(s) underlying a site.
- Nature and effect of perching layers (if any) in the vadose zone.
- Aquifer and vadose zone physical and hydrologic properties including, grain size, matrix content, induration, hydraulic conductivity, transmissivity, porosity
- Groundwater flow direction and velocity, including both spatial and temporal variation
- Anthropomorphic effects, primarily changes in groundwater pumping, surface water (including canals), and irrigation activities.

Ideally, several months to several years of baseline hydrogeologic data should be collected prior to testing so that an adequate site background condition can be established against which test data can be compared to evaluate test success. Water level data will be collected periodically, with the sampling frequency initially being small, later decreasing as testing progresses and more is learned about water level variation in the target aquifer.

For characterization it is important to build monitoring wells in such a way as to provide means for accurately measuring the target aquifer. Well construction considerations are listed below:

- Most project wells will probably be 2 inch-diameter piezometer type installations. These should be built to ensure that they are monitoring the anticipated aquifer targets, and we recommend building to well construction standards and avoiding cost cutting measures designed to get more/cheaper wells (these commonly result in poorly built wells unsuitable for collection of the high quality data we feel is necessary to support the project).
- For aquifer testing, a 4 inch-diameter well is the minimum recommended diameter and at least one should be built.

- The minimum number of wells at the test site is 3, one up gradient and 2 down gradient.
 We do not recommend this. At a minimum we recommend 4 wells, one up and three
 down gradient, with more eventually being built as the test progresses and potentially
 unanticipated changes in the groundwater system are identified. Most, if not all, of these
 wells would be built in geotechnical borings drilled for geologic characterization.
- In addition to the wells built near the test site, it seems likely that wells will eventually need to be built more distant from the site. The purpose of these wells would be to more accurately trace the down gradient migration of recharge water away from the test site. A minimum of 4 wells, 1 well up gradient and 3 wells down gradient is again recommended. These might include at least some previously built groundwater supply wells that would be available for use. However, these should only be used if construction details can be verified and if they are not being used as water supply wells. Access to offsite well drilling locations will need to be acquired from willing land owners. Many offsite wells used in characterization may be unused water supply wells from which data is collected upon which to base decisions for building new monitoring wells.
- Aquifer testing designed to collect aquifer hydraulic property data will be part of site characterization. During aquifer testing, the 2-inch observation wells will be monitored to observe the effects of testing on the surrounding aquifer. Aquifer testing would include an 8 hour step drawdown test to establish probable sustainable yields in the suprabasalt aquifer, followed by a 24 to 72 hour constant discharge test. Water level data collected during aquifer testing will be analyzed using standard analysis techniques.

Combining the interpretations developed in the completed hydrogeologic assessment with the drilling and testing data collected during site specific characterization, a conceptual model of Test Site hydrogeologic conditions will be prepared.

Surface Water

One of the main objectives of the project is to increase surface water quantity and improve its quality. To document that, surface water bodies that the project might influence need to be identified and monitoring points on them established and characterized (includes collection of baseline data). These locations will be used as monitoring locations during subsequent testing.

The hydrogeologic assessment identified three spring-feed streams that are those most likely to be effected by shallow aquifer recharge, Goodman Spring Branch, Johnson Creek, and Dugger Creek. During test-site specific characterization these streams will be examined and monitoring points identified. At these points stream conditions will be photographed and stream conditions documented prior to the initiation of testing. Documentation of pre-test background conditions will include the following parameters:

- Flow volume and discharge
- Water temperature
- Water quality
- Hydrophilic plants and habitat quality

Sampling frequency will be designed to collect enough data to demonstrate the range of conditions likely at the monitoring points so that site background conditions can be documented enough to provide an adequate baseline to measure test results against.

Water Quality

Both surface and groundwater quality at the test site, and at likely down-gradient discharge points, needs to be documented. There are several reasons for this, including:

- We do not want to introduce contaminated water into the shallow aquifer via recharge activities and violate antidegradation rules. We need to establish background water quality parameter concentrations and monitor source-water quality periodically during testing and operations.
- Certain source-water conditions (e.g., turbidity) have the potential to degrade or even "plug" the recharge system. From an operational standpoint, one would monitor for those conditions and halt test operations when the source-water exceeded those conditions.
- Up-gradient groundwater quality needs to be monitored so that the effects of recharge on water quality can be differentiated from those water quality conditions caused by recharge activities, including leaching of vadose zone constituents by recharge water.

Sampling Quality Assurance and Quality Control (QA/QC) protocols will need to be established and followed for characterization and later monitoring. The sampling QA/QC protocol will need to describe:

- Sampling equipment
- Measurement techniques for field parameters
- Decontamination procedures
- Well purging guidance for groundwater samples
- Sampling methods
- Chain of custody and sample handling procedures
- Record keeping
- QA/QC guidelines

Parameters to be tested for include TDS, pH, temp, nitrate-N, chloride, TKN,

Conclusion to Characterization

With the completion of site-specific characterization, final monitoring and test plans will be prepared. This monitoring and test plans will be based on the results of the characterization effort which includes the generation of a site conceptual groundwater flow model that describes

probable aquifer conditions, suprabasalt aquifer water level(s) and groundwater flow direction(s) (including seasonal variations), and discharge points for recharge water.

Preliminary Site-Specific Surface Water and Groundwater Monitoring Plan

Monitoring for the proposed testing is designed to meet four basic objectives. These are to identify: (1) changes in the natural system caused by factors other than those related to testing, (2) changes in the natural system caused by the testing (track the test performance), (3) potential problems caused by the testing that may require termination of the test and/or mitigation actions, and (4) events that effect test operations, such as a freezing event. To meet these objectives, the results of site-specific characterization will be used to identify monitoring locations to track:

- · Source water quality and volume coming onto the test site
- Up-gradient groundwater water quality
- Groundwater level changes migrating into the test area in order to provide the information needed to differentiate the effects of testing from other effects on the site.
- Down-gradient groundwater quality and levels, both near and distal to the test site
- Surface water discharge and quality changes

Monitoring data collected at these points during testing will be evaluated against the established baseline to identify testing effects on the surrounding environment, differentiate those effects from others in the environment, and identify when changes in test operations appear necessary.

Four basic types of monitoring points are currently proposed, source water, test site groundwater, distal groundwater, and surface water (e.g., springs). Considerations for each are summarized below:

- Source water monitoring will be at the point of diversion onto the site. Sampling frequency will be periodic. For water quality, sampling frequency will be based on an analysis of characterization data that identifies when contaminants (if any) are likely to be present in the source water. The results of source water quality monitoring will be used to determine if modifications to test operations are warranted. The volume of water delivered to the test site and leaving the test site (via a return line to the Canal) also will be monitored to keep track of the volume of water that infiltrated into the ground via the ponds. During testing different sampling frequencies may be tried to identify those that are most effective.
- Site groundwater monitoring, consisting of water quality and level data, will be at
 monitoring wells established immediately adjacent to the test site to identify immediate
 quantity and quality impacts from testing. Up-gradient monitoring will be a part of this so
 that site impacts can be differentiated from offsite events. Sampling frequency will be
 determined from characterization data and modified as more is learned during testing.

- Distal groundwater monitoring, consisting of water quality and level data, will be at
 monitoring wells more distal from the test site. This monitoring will be used to identify
 longer term quantity and quality impacts from testing. This includes the formation and
 migration of a groundwater mound and recharge water plume at, and away from, the test
 site, towards intended and unintended receptors. Up-gradient monitoring will be a part
 of this so that testing effects can be differentiated from offsite events. Sampling
 frequency will be determined from characterization data and modified as more is learned
 during testing.
- Surface water monitoring, most likely in spring creeks, will be done to identify the effects of recharge on spring flow. This monitoring will include the collection of both water quality and flow parameters. As with groundwater monitoring, surface water monitoring will need up-gradient monitoring information so that effects unrelated to test site operations/testing can be differentiated from those due to testing. This monitoring will likely include a combination of flow volume and water quality.

Four basic elements are needed for the monitoring plan. These are summarized below and will be developed in greater detail following the collection of site-specific characterization data. The four basic monitoring plan elements are:

- 1. Identification of monitoring points and sampling frequency
- 2. Description of sampling procedures, including:
 - a. Equipment to be used
 - b. Water level measuring techniques
 - c. Stream gauging techniques
 - d. Sampling equipment decontamination
 - e. Well Purging
 - f. Field parameters to be collected at both surface and groundwater sites
 - g. Sample collection methods at both surface and groundwater sites
 - h. Chain of custody tracking
 - i. Sample handling protocols
 - j. Field record keeping
 - k. QA/QC
- 3. Sampling point maintenance
- 4. Data Reporting and Analysis, including:
 - a. Record keeping

b. Annual reporting, including review of previously collected data, reporting of unusual events, and guidelines for recommending changes to test operations as a result of data analysis

This monitoring plan outline will be expanded upon following the collection of site-specific hydrogeologic characterization data.

Preliminary Test Site Operation Plan

In addition to the monitoring plan, a test plan will need to be developed. The test plan should describe how the test site will be operated during testing. Elements included in the test plan will include: (1) site construction, (2) test operations, (3) mitigation activities, and (4) reporting. The test plan will be developed prior to the start of actual testing. However, completion of the plan is contingent on funding. Assuming funding for the project can be procured, construction planning elements would be completed in the Autumn of 2003.

The contents of each test plan element are outlined below:

- 1. Site construction information describes the site layout. Site construction planning will include:
 - a. Test Site survey and layout
 - b. Specifications for pits/basins/ponds used for infiltration
 - c. Water supply design (including diversion from canals if appropriate)
 - d. Monitoring points (both on and off site)
 - e. Site access controls (fences, etc.)
- 2. Test Operations will describe how the site will be used during the test. The operations plan will also describe provisions for changing the test operation plan as new data and information is collected during the test. The test operation plan will include:
 - a. Test timing, including timing of recharge and monitoring frequencies
 - b. Quantities of water used
 - c. Outside influences that effect test, including weather (probably freezing), river flooding, trip wires for identifying potential offsite impacts before they occur so they can be mitigated and or testing suspended to prevent worsening conditions
 - d. Responsible parties for diversion and delivery of water, operation of test, monitoring, and data review
 - e. Permissions required to access offsite monitoring points
- 3. Mitigation As stated above, one of the objectives of monitoring is to identify likely unintended consequences of recharge before they occur. If the precursors to these

- consequences, such as changing water quality detrimental to aquatic habitat or groundwater levels rising to close to the surface in areas where shallow groundwater is not desired, can be detected soon enough via monitoring, recharge activities will be modified and/or terminated to mitigate against these effects. The mitigation plan will describe what the undesirable consequences of the test are, how they will be detected, and how the testing will have to modified to mitigate against these undesirable effects.
- 4. Reporting Data and observations collected during testing, including monitoring data, will be compiled into reports. The basic objective of these reports will be to describe what was done during the test, what was observed at the monitoring points, interpret the data collected, and recommend changes to testing, monitoring, and mitigation plans. We anticipate that these reports will be produced annually. However, in cases where monitoring reveals the presence of an undesired effect from testing, the operator will need to immediately report the monitoring information to WRD and implement any required mitigation actions. At the conclusion of testing a final report will be prepared that describes the project, data colleted during operation and monitoring, interpretations of who well the recharge project worked in achieving project goals, and recommendations for future operations.



Department of Environmental Quality

Northwest Region Portland Office 2020 SW 4th Avenue, Suite 400 Portland, OR 97201-4987

> (503) 229-5263 Fax: (503) 229-6945

TTY: (503) 229-5471

October 30, 2008

Mr. Robert Bower 810 S. Main Street Milton-Freewater, Oregon 97862

UIC Registration for: Infiltration recharge galleries at 84140 Prunedale Road, in Milton-Freewater.

Dear Mr. Bower:

Thank you for submitting a registration form for the Underground Injection Control (UIC) systems at your site. The following table shows your UIC identification number, combined with the injection system information you submitted. Generally, each facility is issued one UIC number; the various injection systems for that facility are then identified sequentially -1, -2, -3, etc. Please reference this number in future correspondence, and retain this letter, or a copy of it, on site, should your UIC systems be inspected.

UIC#	Type Code	Status	Location
13233-1	5R21	New infiltration gallery, natural backfill	southern
13233-2	5R21	New infiltration gallery, clean gravel backfill	south-central
13233-3	5R21	New infiltration gallery, Atlantis Rain Tank	north-central
13233-4	5R21	New infiltration gallery, Stormtech chambers	northern

Please note that you are required to do the following:

- Update registration information whenever a change of ownership, change of land use, modification, abandonment or closure of your injection system takes place. If ownership for your UIC systems changes, notify the next owner and DEQ about the registered injection system.
- Maintain and operate each injection system to protect groundwater resources.
- This authorization is for Walla Walla River recharge water only. It does not include runoff or leakage from a dumpster, loading dock, waste or material storage areas or from construction activities, wash water, process water, fueling areas or waste water discharges.
- Rule authorization will be revoked and a permit required if this site is found to be inside the delineated 2-year time of travel for a municipal well.

In the event a substance is spilled which may contaminate groundwater, contact the DEQ Eastern Region office (541) 388-6146, and call Oregon Emergency Management at (503) 378-6377 or (800) 452-0311.

Based on the information you have sent to DEQ, your injection system has qualified as rule authorized under OAR 340-44. Please check with your local government to see if they have additional requirements.

If you have any questions about this letter, please contact me at (503) 229-6371, or toll free inside Oregon at 1-800-452-4011.

Sincerely,

David Cole, UIC Hydrogeologist

Water Quality Division

David Call

Cc: Eric Nigg, DEQ-ER

Phil Richerson, DEQ-ER



WWBWC-HBDIC's Infiltration Gallery Testing Project

In support of

UIC Permit Application to ODEQ

9/9/2008

Bob Bower Hydrologist MS-Eng.

Table of Contents

Гable of Contents	2
Introduction	3
Overview of HBDIC Recharge Project: Five years of Operations	5
HBDIC Recharge Site Water Quality Monitoring (2004-2008)	
2004-2008 HBDIC Recharge Water Quality Results	
Infiltration Gallery Study Plan	
Research Objectives	
Operations and Additional Monitoring	
Summary	



Introduction

The Walla Walla Basin Watershed Council (WWBWC) along with its project partners the Hudson Bay District Improvement Company (HBDIC) currently operate a shallow aquifer recharge site in the Walla Walla basin located in Umatilla County, Oregon (Figure 1). The site has been in operations since 2004 utilizing an Oregon Water Resources Department (OWRD) limited testing license¹ (Final Order #758). The site currently utilizes a series of spreading basins to recharge non-irrigation season water from the Walla Walla River into the shallow aquifer system (Figure 2). This project has been shown to effectively recharge the shallow aquifer to offset declining storage as well as help restore springs that feed streams in the Little Walla Walla River system. During the first five seasons of operation, water quality for this site has been tested by way of a monitoring program approved by ODEQ² during the original limited license application process (WWBWC, 2003). Results from this program has shown that source water quality recharged-at the sites has been of acceptable quality; meeting the standards established for this project by ODEQ staff.



Figure 1. Walla Walla basin locater map, HBDIC Recharge site in Umatilla County.

¹ OAR 690-350-0020

² Phil Richerson, ODEQ, Pendleton Office. Phil.Richerson@state.or.us, 541-278-4604





Figure 2. Spring 2008 Photo of HBDIC Recharge Project spreading basins.

While spreading or infiltration basins are well established recharge method, they are not always the best solution for varying field and conservation project conditions. One such example of their limitations would be in the steeply rising land costs associated with the Walla Walla wine industry. The cost of fallow-agriculture ground that could be purchased and transformed into a spreading basin site for recharge has skyrocketed in recent years, making sites like the HBDIC location difficult to secure. Walla Walla basin water managers are therefore looking to develop aquifer recharge capabilities that can be used in and along right-of-way of ditch easements or small corner locations that are often owned by the district or its irrigator patrons.

Ideally, infiltration galleries coupled with a lined/piped deliver system could provide conservation during the times of scarcity (irrigation season) and aquifer recharge and storage during the times of water abundance (fall-winter-spring) without requiring large open tracks of land for infiltration basins. With careful water quality monitoring in place, the WWBWC-HBDIC recharge team would like to test various infiltration gallery designs in order to further develop this tool for our basin. The following study plan outlines the objectives and research outline for the testing of an infiltration gallery system at the HBDIC site. It is intended as supporting information to the WWBWC-HBDIC Underground Injection Control (UIC) permit application.



Overview of HBDIC Recharge Project: Five years of Operations

The Hudson Bay Aquifer Recharge project was designed to test aquifer recharge as a tool to stabilize and restore declining aquifer levels and spring-creek flows in the Walla Walla River valley. Funding, technical-support and permitting has been provided by the Oregon Watershed Enhancement Board (OWEB), Walla Walla Watershed Alliance (NRCS funds), Oregon Water Resources Department (OWRD), Oregon Department of Environmental Quality (ODEQ), Oregon State University Extension, HBDIC and the WWBWC.

The Hudson Bay Aquifer Recharge Project has been operated successfully for five consecutive recharge seasons starting in 2004 through 2008. The current test project is operated under a Limited License Request (#758) from Oregon Water Resources Department. The conditions and limitation of the permit state:

"The use of water from the Walla Walla River shall be limited to 50 cfs for the purpose of testing artificial ground water recharge during a testing season of November 1 through May 15. Water may only be diverted when there is adequate flow in the Walla Walla River to honor all existing water rights. When water is diverted under this limited license, the use is further limited to times when there is, at a minimum, the following stream flows in the Tum a lum reach of the Walla Walla River, between the Little Walla Walla River diversion and Nursery Bridge Dam and flowing past Nursery Bridge Dam: November – 64 cfs, December and January – 95 cfs, February to May 15 – 150 cfs."

The project currently consists of a series of four spreading basins (Figure 1) that utilize water delivered from the Walla Walla River via the HBDIC's ditch system to operate the site. The current total infiltration area of the basins is 1.25 acres with an estimated on-site infiltration rate of between 13-18 cfs. In the 2006-2007 recharge seasons, the best to date, the project recharged approximately 3,300 acre-feet in 132 days of operation.

The project also has an extensive surface and groundwater monitoring system associated with in that measure onsite conditions (Figure 3) as well as more distal downgradient and surrounding locations (Figure 4). Water level monitoring, geology, surface flow and spring discharge and a battery of water quality samples are taken to monitor and assess the HBDIC recharge project. There are four on-site dedicated observation wells where water quality and groundwater levels are monitored (OBS 1, 2, 3 and 4). Well logs for observation well #3 (closest to new infiltration gallery) and Observation well #1 (water quality monitoring well, 4" casing) can be found in Attachment 2. Water levels in these wells range seasonally depending on local groundwater use and when the HBDIC site is in operations. Well OBS #3 ranges from 25 feet below ground surface (bgs) during recharge operations to 60 feet bgs (WWBWC data).

Several reports review the monitoring system at the HBDIC project including:



- ☐ Hudson Bay Aquifer Recharge Project: An application for ASR Testing Limited License to Oregon Water Resources Department (OWRD) (OAR 690-350-0020), and attachments. October, 2003. Bower, ET. al. WWBWC
- ☐ Hudson Bay Aquifer Recharge Testing Project: 2004 Annual Report. November 2004. Bower. WWBWC
- ☐ Hudson Bay Aquifer Recharge Testing Project: 2004-5 Annual Report. November 2005. Bower. WWBWC
- ☐ Hudson Bay Aquifer Recharge Testing Project: 2004-2008 Review Report, November 2008. Bower, et. al., WWBWC.

As the compilation report is still being completed (due November 2008) a review of all the project data and analysis is not available at this time. However, in support of this application for a HBDIC infiltration gallery UIC permit, the next section will review what is the most relevant to support the WWBWC UIC permit application: the water quality monitoring we have done during the first five recharge seasons. This will provide the ODEQ UIC review staff with the pertinent information by which to assess the attached application.

HBDIC Recharge Site Water Quality Monitoring (2004-2008)

As the HBDIC Recharge Project represented the first of its kind in the State of Oregon, water quality sampling has been a priority monitoring focus since the conception. DEQ and WWBWC staff developed the parameters and testing protocols for this project during the original application process in 2003-4 (Hudson Bay Aquifer Recharge Project: An application for ASR Testing Limited License to Oregon Water Resources Department (OWRD) (OAR 690-350-0020), and attachments).

To summarize the program and the results from the past water quality monitoring it is best to separated sampling into two categories and list of constituents.

□ Baseline:

- o nitrate
- o total kjeldahl nitrogen (TKN)
- o total dissolved solids (TDS)
- o chemical oxygen demand (COD)
- o chloride
- o orthophosphate
- o fecal coliform bacteria

☐ Soluble Organic Compounds – Pesticides

(Common/Trade names, EPA Drinking Water Method)

- o 2,4 D acid, Dacamine, 515.1
- o Dimethoate, Cygon, 525.2

- o Metalaxyl, Ridomil, 525.2
- o Napropamide, Devrinol, 525.2
- o Simazine, Princep, Aquazine, 525.2
- o 1-Naphthaleneacetamide, Amid-thin 525.2
- o Diazinon, Diazinon, 525.2
- o Fenarimol, Rubigan, 525.2
- o Lindane, Lindane, 525.2
- o Methidathinon, Supracide, 525.2
- o Mevinphos, Phosdrin, 525.2
- o Myclobutanil, Systhane, Rally 525.2
- o Triflumizole, Procure, 525.2
- o Azinphos-methyl, Guthion, 525.2
- o Carbaryl, Sevin, 531.1
- o Chlorpyrifos, Dursban, Lorsban, 525.2
- o DDD (TDE) Rhotane, DDD, 525.2
- o DDE degradation product, 525.2
- o DDT Anofex, Gesarol, 525.2
- o Dicofol, Kelthane, 525.2
- o Malathion, Cythion, 525.2
- o Methyl Parathion, Penncap, 525.2
- o Phosmet, Imidan, 525.2
- o Propargite, Omite, Comit, 525.2
- o Triadimefon Dimethoate, Bayleton, 525.2
- o Oxamyl, Vydate, 531.1
- o Hexazinone DPX 3674, Pronone, and Velpar, 525.2
- o Parathion-Ethyl, Niran, Phoskil (56), 525.2

These Soluble Organic Compounds (SOCs) were determined through a collaborative assessment process that involved the WWBWC, Oregon State Extension and the ODEQ to be the focus of the HBDIC recharge monitoring project. In additional to the SOC analytes listed above, there were additional compounds tested as reported by the standard EPA drinking water standard testing 508.1, 515.1, 525.2, and 531.1, a list of these compounds can be found in Attachment 1.

2004-2008 HBDIC Recharge Water Quality Results

The HBDIC Recharge project monitoring team and ODEQ have developed the monitoring program as an iterative process. More than 85 different SOC analytes have been tested at the site's source (surface) and groundwater monitoring locations during the five years of operations. The baseline chemistry results for site groundwater and source water are summarized in Table 1.



Table 1. HBDIC Baseline Chemistry Results (2004-2008) Water Sample Sites:

Ground/Surface	Analyte	Minimum	Maximum	Average	Units
Groundwater	Chloride	ND	0.8	0.6	mg/L
Groundwater	Chemical Oxygen Demand	ND	55.0	24.1	mg/L
	Nitrate as Nitrate as Nitrogen				
Groundwater		0.1	0.6	0.2	mg/L
Groundwater	Orthophosphate as P	ND	0.5	0.3	mg/L
Groundwater	TKN as Nitrogen	ND	1.6	ND	mg/L
Groundwater	Total Dissolved Solids	ND	84.0	61.2	mg/L
Surface	Chloride	ND	1.0	0.8	mg/L
Surface	Chemical Oxygen Demand	ND	21.0	ND	mg/L
	Nitrate as Nitrogen				
Surface	_	ND	0.5	0.2	mg/L
Surface	Orthophosphate as P	0.1	0.6	0.3	mg/L
Surface	TKN as Nitrogen	ND	ND	ND	mg/L
Surface	Total Dissolved Solids	ND	76.0	57.4	mg/L

ND - No Detection

*Data source: WWBWC, 2008.

Fecal Coliforms were detected in both the source and groundwater monitoring sites. Additional monitoring was conducted at the HBDIC site as well as in other, more distal locations. The results indicated that low level fecal coliform detections were prevalent in many area surface and groundwater locations leading the monitoring team to determine fecal contamination to be a prevalent background condition (Table 2.)

Table 2. Surface and Groundwater Monitoring Fecal Coliform Results

		Surface			Groundwater		
Recharge Sampling Year	Minimum	Maximum	Average	Minimum	Maximum	Average	Units
2004	1.0	130.0	39.8	0.0	14.8	3.8	MPN/100 ML
2004-5	0.0	62.0	9.4	0.0	12.0	2.0	MPN/100 ML
2005-6	14.0	20.0	17.0	0.0	3.0	1.0	MPN/100 ML
2006-7	7.0	23.0	15.3	0.0	3.0	1.0	MPN/100 ML
2007-8	11.0	14.0	12.5	0.0	1.0	0.5	MPN/100 ML

*Data source: WWBWC, 2008.

Pesticide or Soluble Organic Compounds sampling resulted in only <u>a single detection</u> in the 5 years of monitoring. On April 13, 2004 at the HBDIC Observation well #1, Di(ethylhexyl)-phthalate was detected at 2.2 ug/L. The Maximum Contaminant Level MCL for this compound is 6.0 ug/L according to EPA standards (2004). ODEQ staff concluded that this was likely a low-level detection arising from the newly installed PVC observation-well casing. The compound was not detected in subsequent monitoring of the recharge project's surface or observation sites.

Infiltration Gallery Study Plan

The WWBWC has been collaborating with other national and international recharge programs that are also seeking to improve designs for infiltration galleries for aquifer recharge purposes. After reviewing the available literature and discussing the main issues with our collaborative partners, we put together an infiltration gallery testing project for the



HBDIC site. The project will include four infiltration galleries each with different types of gallery materials. Each of these galleries will also include flow meters (to determine flow rate into each), and inspection ports where each can be checked for sediment accumulation and cleaned and maintained. The project will generally be run the same as the rest of the HBDIC recharge site between November 1sth and May 15th. A turbidity meter will also be installed and operated during the testing of the galleries to provide background information as to better understanding any clogging that may occur. The objectives of the study are as follows:

Research Objectives

Determine most effective infiltration gallery design and materials in recharging water
subsurface in the Walla Walla basin.
Determine rates of infiltration and any potential clogging of each of the four test
infiltration gallery designs.
Test varies methods to clean infiltration galleries if clogging to decreases performance.
Monitor surface and groundwater for quality and quantity changes related to operation
of infiltration galleries.

Project Designs

Site designs for the infiltration galleries testing project (Upper Recharge Project) and site plans are included in Attachment 2 (Plates 1 through 7).

	Plate 1 covers the original survey of the HBDIC recharge site before any of the spreading basins were build and the basic geologic information provided by the test pits
_	(2003).
Ч	Plate 2 provides an overview of the entire HBDIC recharge site with four existing
	spreading basins and the new infiltration gallery testing project.
	Plate 3 provides miscellaneous details as to the White Ditch inlet structure as well as
	inspection port and flow meter placements.
	Plate 4 provides information for two of the four infiltration gallery designs. The designs
	outline the piping and the location of inspection ports and flow meters.
	Plate 5 provides the layout and design information for the Atlantis Rain Tank (style of
	piping) and the Stormtech Chamber designs.
	Plate 6 provides the design information for the check and screen structure that will
	divert the water from the ditch into the project.
	Plate 7 provides general construction details for the check structure construction.

Operations and Additional Monitoring

The HBDIC Infiltration Gallery Testing Project will be operated by the instructions outlined in our OWRD/ODEQ-approved Limited Testing License. Water will be diverted to the infiltration galleries at the volumes and dates outlined in our current permit. The project has been designed to operate at approximately four cfs: one cfs for each of the four infiltration



gallery designs. All water quality monitoring will be conducted as instructed in our current license. However the WWBWC will conduct the following additional testing in order to gather information relative to our four project objectives:

	YSI Continuous Turbidity Meter Model # 6920 V2 ³ will be installed in the check structure piping that delivers the water to the four infiltration galleries.					
	Water Quality Samples: Total Suspended Solids (TSS) will be collected weekly					
	during recharge operations and sent to Edge Analytical ⁴ in order to establish a TSS-					
	Turbidity regression relationship. This will be used with flow information to determine					
	any correlation between source water turbidity with infiltration gallery performance					
	(clogging).					
	Water Quality Samples: Total Organic Carbons (TOC). Studies at the Orange					
	County Aquifer Recharge Program ⁵ have shown biological clogging decrease infiltration					
	gallery performance. While the fall-winter-spring water temperatures at HBDIC make					
	this issue unlikely, we will collect TOC and TSS to confirm biological clogging will not					
	have an effect.					
	1.5 Meter PVC piezometers will be installed at each of the infiltration galleries at the					
	midpoint at horizontal spacing of 0.5 and 1.5 meters. These capped piezometers will					
	provide us with water-level mounding information in the close vicinity of the galleries.					
	Water level measurements will be collected using an etape.					
	Aqua Master Model 900R (Jennings Inc.) or McCrometer Model EO3000					
	Propeller Style flow meters will be installed to measure flow capacity of each of the					
	four infiltration gallery designs. Four of the same type of recorder will be purchased.					

Summary

intake structures.

The HBDIC Infiltration Gallery Testing Project will be subject to the site's current water quality monitoring program with additional monitoring of the four different recharge gallery designs. Monitoring over the first five years has shown that the source water at the HBDIC recharge project is acceptable for a UIC permit for operations. The testing of the project will cover at a minimum of two full recharge seasons, November 1st 2008 through May 15th, 2009 and November 1st 2009 through May 15th, 2010 in order to establish enough data to address the main research objectives for the project. Any further monitoring and/or design ideas that ODEQ or OWRD considers essential for the safe operations and testing of these galleries can be incorporated into this application.

at the HBDIC Observation wells #1, #2, #3 and #4 at the White Ditch check and

³ https://www.ysi.com/ysi/Products/Product Family/Product?productID=EMS SEN02 6136

⁴ http://www.edgeanalytical.com/

⁵ Verbal communications with Adam Hutchinson, director of Orange County (CA) Aquifer Recharge Program. http://www.ocwd.com/Groundwater-Recharge/ca-34.aspx



Attachment 1: Additional SOC compounds tested 2004-2008

DOH#	Compounds	Results	Units	SRL	Trigger	MCL	Comments
	Carbamates in drinking water						
146	Carbofuran		ug/L	1.8	1.8	40.0	EPA Regulated
148	Oxymal		ug/L	4.0	4.0	200.0	EPA Regulated
141	3-Hydroxycarbofuran		ug/L	2.0	2.0		EPA Unregulated
142	Aldicarb		ug/L	1.0	1.0		EPA Unregulated
143	Aldicarb Sulfone		ug/L	1.6	1.6		EPA Unregulated
144	Aldicarb Sulfoxide		ug/L	1.0	1.0		EPA Unregulated
145	Carbaryl		ug/L	2.0	2.0		EPA Unregulated
147	Methomyl		ug/L	1.0	4.0		EPA Unregulated
326	Propoxur(Baygon)		ug/L	1.0			State Unregulated
327	Methiocarb		ug/L	4.0			State Unregulated
	Synthetic Organic Compounds						<u> </u>
33	Endrin		ug/L	0.02	0.02	2.0	EPA Regulated
34	Lindane (BHC-Gamma)		ug/L	0.04	0.04	0.2	EPA Regulated
35	Methoxychlor		ug/L	0.20	0.20	40.0	EPA Regulated
117	Alachlor		ug/L	0.40	0.40	2.0	EPA Regulated
119	Atrazine		ug/L	0.20	0.20	3.0	EPA Regulated
120	Benzo(a)pyrene		ug/L	0.04	0.04	0.2	EPA Regulated
122	Chlordane Technical		ug/L	0.40	0.40	2.0	EPA Regulated
124	Di(ethylhexyl)-Adipate		ug/L	1.30	1.30	400.0	EPA Regulated
125	Di(ethylhexyl)-phthalate		ug/L	1.30	1.30	6.0	EPA Regulated
126	Heptachlor		ug/L	0.08	0.08	0.4	EPA Regulated
127	Heptachlor epoxide (A & B)		ug/L	0.04	0.04	0.2	EPA Regulated
128	Hexachlorobenzene		ug/L	0.20	0.20	1.0	EPA Regulated
129	Hexachlorocyclo-Pentadiene		ug/L	0.20	0.20	50.0	EPA Regulated
133	Simazine		ug/L	0.15	0.15	4.0	EPA Regulated
118	Aldrin		ug/L	0.20	0.20		EPA Unregulated
121	Butachlor		ug/L	0.40	0.40		EPA Unregulated
123	Dieldrin		ug/L	0.20	0.20		EPA Unregulated
130	Metolachlor		ug/L	1.00	1.00		EPA Unregulated
131	Metribuzin		ug/L	0.20	0.20		EPA Unregulated
132	Propachlor		ug/L	0.20	0.20		EPA Unregulated
179	Bromacil		ug/L	0.20	0.20		State Unregulated
183	Prometon		ug/L	0.20	0.20		State Unregulated
190	Terbacil		ug/L	0.20	0.20		State Unregulated
202	Diazinon		ug/L	0.20	0.20		State Unregulated
208	EPTC		ug/L	0.30	0.30		State Unregulated
232	4,4-DDD		ug/L	0.20	0.20		State Unregulated
233	4,4-DDE		ug/L	0.20	0.20		State Unregulated
234	4,4_DDT		ug/L	0.20	0.20		State Unregulated
236	Cyanazine		ug/L	0.20	0.20		State Unregulated



Attachment 1: Additional SOC compounds tested 2004-2008 (Continued)

DOH#	Compounds	Results	Units	SRL	Trigger	MCL	Comments
	Synthetic Organic Compounds						
239	Malathion		ug/L	0.20	0.20		State Unregulated
240	Parathion		ug/L	0.20	0.20		State Unregulated
243	Trifluralin		ug/L	0.20	0.20		State Unregulated
96	Napthalene		ug/L	0.10	0.10		PAHs
154	Fluorene		ug/L	0.20	0.20		PAHs
244	Acenaphthylene		ug/L	0.20	0.20		PAHs
245	Acenaphthene		ug/L	0.20	0.20		PAHs
246	Anthracene		ug/L	0.20	0.20		PAHs
247	Benz(a)anthracene		ug/L	0.10	0.10		PAHs
248	Benzo(b)fluoranthene		ug/L	0.20	0.20		PAHs
249	Benzo(g,h,i)perylene		ug/L	0.20	0.20		PAHs
250	Benzo(k)fluoranthene		ug/L	0.20	0.20		PAHs
251	Chrysene		ug/L	0.20	0.20		PAHs
252	Dibenzo(A,H)anthracene		ug/L	0.20	0.20		PAHs
253	Fluoranthene		ug/L	0.20	0.20		PAHs
255	Indeno(1,2,3-CD)Pyrene		ug/L	0.20	0.20		PAHs
256	Phenanthrene		ug/L	0.20	0.20		PAHs
257	Pyrene		ug/L	0.20	0.20		PAHs
258	Benzyl Butyl Phthalate		ug/L	0.60	0.60		Phthalates
259	Di-N-Butyl Phthalate		ug/L	0.60	0.60		Phthalates
260	Diethyl Phthalate		ug/L	0.60	0.60		Phthalates
261	Dimethyl Phthalate		ug/L	0.60	0.60		Phthalates
36	Toxaphene		ug/L	2.0	2.0	3.0	PCBs/Toxaphene
173	Aroclor 1221		ug/L	20.0	20.0		PCBs/Toxaphene
174	Aroclor 1232		ug/L	0.5	0.5		PCBs/Toxaphene
175	Aroclor 1242		ug/L	0.5	0.3		PCBs/Toxaphene
176	Aroclor 1248		ug/L	0.1	0.1		PCBs/Toxaphene
177	Aroclor 1254		ug/L	0.1	0.1		PCBs/Toxaphene
178	Aroclor 1260		ug/L	0.2	0.2		PCBs/Toxaphene
180	Aroclor 1016		ug/L	0.1	0.1		PCBs/Toxaphene
	Herbicides in Drinking Water						
37	2,4-D		ug/L	0.2	0.2	70.0	EPA Regulated
38	2,4,5-TP (Silvex)		ug/L	0.4	0.4	50.0	EPA Regulated
134	Pentachlorophenol		ug/L	0.1	0.1	1.0	EPA Regulated
137	Dalapon		ug/L	2.0	2.0	200.0	EPA Regulated
139	Dinoseb		ug/L	0.4	0.4	7.0	EPA Regulated
140	Picloram		ug/L	0.2	0.2	500.0	EPA Regulated
138	Dicamba		ug/L	0.2	0.2		EPA Unregulated
135	2,4 DB		ug/L	1.0	1.0		State Unregulated
136	2,4,5 T		ug/L	0.4	0.4		State Unregulated



Attachment 1: Additional SOC compounds tested 2004-2008 (Continued)

DOH#	Compounds	Results	Units	SRL	Trigger	MCL	Comments
	Herbicides in Drinking Water						
220	Bentazon		ug/L	0.5	0.5		State Unregulated
221	Dichloroprop		ug/L	0.5	0.5		State Unregulated
223	Actiflorfin		ug/L	2.0	2.0		State Unregulated
225	Dacthal (DCPA)		ug/L	0.1	0.1		State Unregulated
226	3,5-Dichlorobenzoic Acid		ug/L	0.5	0.5		State Unregulated








Figure 4. Map showing surface and groundwater monitoring locations relative to HBDIC Recharge Site.





TBM IS AT THE TOP OF THE RIGHT SIDE WALL, DOWNSTREAM END

OF THE FLUME. ELEVATION 88.7 FEET.

OF 7 EXPIRES 6/30/2009

DESIGNED B. HEWES
PLOTTED
APPROVED

 \angle


-

(1)

CADFILE

whitextpln2

SHEET 2




NOTES


CUT THE HOLE IN THE INLET STRUCTURE TO CLOSELY FIT AROUND THE SUPPLY PIPE. FILL THE SPACE BETWEEN THE STRUCTURE AND PIPES WITH CAULKING ON BOTH SIDES. THE BOTTOM LIP OF THE 45° ELBOW CAN BE NO LESS THAN 0.2′ BELOW THE TOP OF THE 21″ PIPE.

LID FOR THE CMP MANHOLE TO BE GALVANIZED 1/8″ THICK STEEL.


SLIDE GATE TO BE A WATERMAN C-8-4 OR EQUIVALENT. INSTALL A CATWALK FOR ACCESS TO THE SLIDE GATE.




INLET STRUCTURE TRASH RACK DETAIL PERSPECTIVE VIEW



FRAME IS & X 3" STEEL, INSIDE DIAMETER 32". COVER TO BE FLATTENED EXPANDED METAL APPROXIMATELY 0.120" THICK; OPENINGS APPROXIMATELY 1/2" X 1 5/8 ".
CLEAN AND PAINT WITH 2 COATS OF HIGH ZINC COLD GALVANIZING PAINT.







CAD FILE whitemisc

B.

PRUJE

CHARG

APPROVED

CHECKED

LS

TAIL

Z

Q

WWBWC/HBDIC MISCEL UMATILL

0

<


N


FR


1


0

SHEET 3 OF 7










ASSEMBLE AND INSTALL RAIN TANKS AND INSPECTION PORT AS
DESCRIBED IN THE MANUFACTURERS LITERATURE. TANKS ARE 16" WIDE,
27" LONG AND 17% HIGH, NEED 336 TANKS FOR H-10 LOADING. USE 4"
PVC PIPE FOR THE PORT, EXTEND 1' ABOVE GROUND AND PROTECT WITH
A FENCE POST AND END CAP.
FILTER FABRIC TO BE ADS 4000 OR EQUIVALENT, NEED 160 SQ. YD.
FOLD AND TAPE THE CORNERS AS SHOWN IN THE LITERATURE.
GRAVEL TO BE ANGULAR CRUSHED ROCK WITH THE MAJORITY OF
PARTICLES BETWEEN %-2", NEED ABOUT 25 CU. YD.



ASSEMBLE AND INSTALL CHAMBERS AND INSPECTION PORT AS SHOWN IN THE MANUFACTURERS LITERATURE. TANKS ARE 34" WIDE, 7'-2" LONG AND 16" HIGH, NEED 50 CHAMBERS. IN LIEU OF THE SUBSURFACE PORT SHOWN IN THE LITERATURE EXTEND THE PORT 1' ABOVE GROUND AND PROTECT WITH A FENCE POST AND END CAP. FILTER FABRIC TO BE ADS 4000 OR EQUIVALENT, NEED 190 SQ. YD. GRAVEL TO BE ANGULAR CRUSHED ROCK WITH THE MAJORITY OF PARTICLES BETWEEN 3"-2", NEED ABOUT 115 CU. YD.

EXPIRES 6/30/2009

CAD FILI whiteatlar

V

ANTI

JECT

图日

Шα

ECHARGE CHAMBER IY, OREG

LA C


GBN


2


UPI


WBWC/HBDI


SHEET 5




















TBM IS AT THE TOP OF THE RIGHT SIDE WALL, DOWNSTREAM END

OF THE FLUME. ELEVATION 88.7 FEET.

OF 7 EXPIRES 6/30/2009

DESIGNED B. HEWES
PLOTTED
APPROVED

 \angle


-

(1)

CADFILE

whitextpln2

SHEET 2




NOTES


CUT THE HOLE IN THE INLET STRUCTURE TO CLOSELY FIT AROUND THE SUPPLY PIPE. FILL THE SPACE BETWEEN THE STRUCTURE AND PIPES WITH CAULKING ON BOTH SIDES. THE BOTTOM LIP OF THE 45° ELBOW CAN BE NO LESS THAN 0.2′ BELOW THE TOP OF THE 21″ PIPE.

LID FOR THE CMP MANHOLE TO BE GALVANIZED 1/8″ THICK STEEL.


SLIDE GATE TO BE A WATERMAN C-8-4 OR EQUIVALENT. INSTALL A CATWALK FOR ACCESS TO THE SLIDE GATE.




INLET STRUCTURE TRASH RACK DETAIL PERSPECTIVE VIEW



FRAME IS & X 3" STEEL, INSIDE DIAMETER 32". COVER TO BE FLATTENED EXPANDED METAL APPROXIMATELY 0.120" THICK; OPENINGS APPROXIMATELY 1/2" X 1 5/8 ".
CLEAN AND PAINT WITH 2 COATS OF HIGH ZINC COLD GALVANIZING PAINT.







CAD FILE whitemisc

B.

PRUJE

CHARG

APPROVED

CHECKED

LS

TAIL

Z

Q

WWBWC/HBDIC MISCEL UMATILL

0

<


N


FR


1


0

SHEET 3 OF 7










NOTES ASSEMBLE AND INSTALL RAIN TANKS AND INSPECTION PORT AS DESCRIBED IN THE MANUFACTURERS LITERATURE. TANKS ARE 16" WIDE, 27" LONG AND 17%" HIGH, NEED 336 TANKS FOR H-10 LOADING. USE 4" PVC PIPE FOR THE PORT, EXTEND 1' ABOVE GROUND AND PROTECT WITH A FENCE POST AND END CAP. FILTER FABRIC TO BE ADS 4000 OR EQUIVALENT, NEED 160 SQ. YD. FOLD AND TAPE THE CORNERS AS SHOWN IN THE LITERATURE. GRAVEL TO BE ANGULAR CRUSHED ROCK WITH THE MAJORITY OF PARTICLES BETWEEN 3"-2", NEED ABOUT 25 CU. YD.



THE MANUFACTURERS LITERATURE. TANKS ARE 34" WIDE, 7'-2" LONG AND 16" HIGH, NEED 50 CHAMBERS. IN LIEU OF THE SUBSURFACE PORT SHOWN IN THE LITERATURE EXTEND THE PORT 1' ABOVE GROUND AND PROTECT WITH A FENCE POST AND END CAP. FILTER FABRIC TO BE ADS 4000 OR EQUIVALENT, NEED 190 SQ. YD.

GRAVEL TO BE ANGULAR CRUSHED ROCK WITH THE MAJORITY OF PARTICLES BETWEEN 3"-2", NEED ABOUT 115 CU. YD.

EXPIRES 6/30/2009

CAD FIL whiteatlar

V

ANTI

JECT

图日

Шα

ECHARGE CHAMBER IY, OREG

LA C


GBN


2


UPI


WBWC/HBDI


SHEET 5 DF 7


















HBDIC Recharge Project Site





HBDIC Infiltration Gallery Testing Site Map




During the 2008-2009 Recharge Season, infiltration galleries are being tested at the HBDIC Recharge site, near Milton-Freewater Oregon. Preliminary testing results indicate infiltration galleries are viable recharge mechanism for areas where spreading basins are not feasible. A combination of all methods will be assessed during the design and siting phase of this program.



Infiltration Gallery Instrumentation





Infiltration Galleries: Atlantis® D-Raintank® Tank Module





Raintanks being deployed





Backfill: native materials











ADS Slotted Pipe





StormTech Drain Pipe



Figure 16



Infiltration Gallery: Stormtech SC-740™ Chamber



Figure 13



HBDIC Infiltration Gallery Testing Site: Profile of Galleries and Piezometers

2008-2009 Preliminary Testing Results

