

	SHEET INDEX			
1	G-01	TITLE SHEET / LOCATION MAP / SHEET INDEX		
2	G-02	LEGEND / ABBREVIATIONS / GENERAL PROJECT NOTES		
3G-03HIP GENERAL CONSERVATION MEASURES - 14G-04HIP GENERAL CONSERVATION MEASURES - 2		HIP GENERAL CONSERVATION MEASURES - 1		
		HIP GENERAL CONSERVATION MEASURES - 2		
5	G-05	HIP GENERAL CONSERVATION MEASURES - 3		
6	C-01	OVERALL EXISTING CONDITIONS SITE PLAN AND PLAN INDEX		
7	C-02	OVERALL PROPOSED TREATMENT SITE PLAN AND PLAN INDEX		
8	C-03	CONSTRUCTION ACCESS / STAGING / SITE PREPARATION		
9	C-04	RESTORATION/REVEGETATION PLAN 1		
10	C-05	RESTORATION/REVEGETATION PLAN 2		
11	C-06	RESTORATION/REVEGETATION PLAN 3		
12	C-07	RESTORATION/REVEGETATION PLAN 4		
13	C-08	ORDINARY HIGH WATER AT THALWEG PROFILE		
14	C-09	INLET GRADING - ALIGNMENTS A, B, AND C		
15	C-10	INLET GRADING - ALIGNMENT D AND ALL TYPICAL CROSS SECTIONS		
16	C-11	SIDE CHANNEL GRADING - ALIGNMENT E		
17	CD-01	LARGE WOOD SMALL LOG JAM		
18	CD-02	LARGE WOOD LARGE LOG JAM		
19	CD-03	APEX JAM		
20	CD-04	FLOODPLAIN ROUGHNESS WILLOW TRENCHING AND FLOODPLAIN PINNED LOGS		
21	CD-05	SITE RESTORATION AND PLANTING DETAILS		
22	CD-06	TEMPORARY FLOW ISOLATION AND TEMPORARY WATER CROSSING DETAILS		

# **GENERAL NOTES:**


1.	WORK SHOWN ON THESE PLANS WILL BE PERFORMED FOR THE WALLA WALLA BASIN WATERSHED COUNCIL (WWBW HEREIN REFERRED TO AS "CONTRACTING AGENCY." CONTACT INFORMATION FOR CONTRACTING AGENCY'S REPRESENTATIVE IS INCLUDED ON G-01. CONTRACTING AGENCY'S REPRESENTATIVE (OR OTHER PERSONS ASSIGN CONTRACTING AGENCY TO ACT AS CONTRACTING AGENCY'S REPRESENTATIVE) ARE HEREIN REFERRED TO AS THE "CONTRACTING OFFICER."
2.	ANY ITEM NOT SPECIFICALLY DISCUSSED IN THE CONTRACT DOCUMENTS FOR THIS PROJECT OR IN NOTES ON SHE THE DRAWINGS SHALL BE AS DESCRIBED IN THE PROJECT SPECIFICATIONS. CONTRACTOR IS RESPONSIBLE FOR BI FAMILIAR WITH PROJECT SPECIFICATIONS AND FOR HAVING ACCESS TO THE PROJECT SPECIFICATIONS AT THE PRO SITE TO ENSURE THAT CONSTRUCTION OF THE PROJECT IS IN CONFORMANCE WITH THE PROJECT SPECIFICATIONS
3.	CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING, AT CONTRACTOR'S EXPENSE, ALL CONSTRUCTION PERMIT REQUIRED BY LOCAL, STATE, AND FEDERAL AGENCIES. CONTRACTOR SHALL PROVIDE ALL MATERIAL, LABOR, AND EQUIPMENT REQUIRED TO COMPLY WITH ALL APPLICABLE PERMIT CONDITIONS AND REQUIREMENTS.
4.	CONTRACTOR SHALL BE SOLELY AND COMPLETELY RESPONSIBLE FOR THE CONDITIONS OF THE PROJECT SITE, INC SAFETY OF ALL PERSONS AND PROPERTY DURING PERFORMANCE OF THE WORK (SEE GENERAL CONDITIONS).
5.	REQUIRED CONSTRUCTION MATERIALS ARE SHOWN ON THE DRAWINGS AND DESCRIBED IN PROJECT SPECIFICATION
6.	INFORMATION SHOWN ON THE DRAWINGS SUPERSEDES ANY CONTRADICTORY INFORMATION IN THE PROJECT SPECIFICATIONS.
7.	DRAWINGS DO NOT SHOW ALL EXISTING VEGETATION.
8.	EXISTING TOPOGRAPHY, STRUCTURES, SITE FEATURES AND PHASED WORK ARE SHOWN SCREENED AND/OR LIGHT NEW FINAL GRADE, STRUCTURES AND SITE FEATURES ARE SHOWN HEAVY-LINED.
9.	FOR THOSE PORTIONS OF FULL-SIZE DRAWINGS (22X34 INCHES) SHOWING SCALE BARS, THE MAJOR SCALE UNIT EQUALS 1/2 INCH. ON COMPARABLE PORTIONS OF HALF-SIZE DRAWINGS (11X17 INCHES), THE MAJOR SCALE UNIT EQUALS 1/2 INC
10.	ELEVATIONS AND DISTANCES SHOWN ARE IN FEET AND DECIMALS WITH CONTOUR INTERVALS AT 5-FOOT INCREME
11.	ELEVATIONS GIVEN ARE TO FINAL GRADE UNLESS OTHERWISE SHOWN. UNLESS OTHERWISE NOTED, DEPTHS OF FI FINAL COMPACTED DEPTHS.
12.	FINAL GRADING SHALL PROVIDE DRAINAGE AS SHOWN ON DRAWINGS.
13.	DIGITAL TERRAIN DATA ARE BASED ON LIDAR COLLECTED ON JUNE 13 2021 BY EAGLE MAPPING INC. THE HORIZONT DATUM IS NAD 83 (2011), AND THE VERTICAL DATUM IS NAVD88 (GEOID18). THE PROJECTION FOR THE ORIGINAL LIDADATASET WAS UTM 11N, AND THE DATA WAS REPROJECTED TO STATE PLANE OREGON NORTH (LAMBERT CONFORCONIC, EXPRESSED IN INTERNATIONAL FEET) FOR USE ON THIS PROJECT. LIDAR WAS COLLECTED WITH A RIEGL VOW WHICH OPERATES IN THE NEAR IR WAVELENGTH. SUPPLEMENTAL SURVEY WAS COLLECTED BY CRAMER FISH SCIE JULY 2023 USING A SURVEY-GRADE REAL-TIME KINEMATIC (RTK) GLOBAL POSITIONING SYSTEM (GPS) UNIT AND/OR SURVEY-GRADE TOTAL STATION. THESE DATA WERE MERGED WITH EXISTING LIDAR (2021 EAGLE MAPPING) DATA B JACOBS TO DEFINE THE TOPOGRAPHIC AND BATHYMETRIC SURFACES WITHIN THE PROJECT AREA AT THE TIMES O RESPECTIVE SURVEYS.
14.	THE WATERS OF THE UNITED STATES (WOTUS) AND THEIR ASSOCIATED WETLANDS WERE LOCATED WITHIN THE PROJECT AREA BY ECOSYSTEM SCIENCES, LLC IN NOVEMBER 2022 IN ACCORDANCE WITH USACE GUIDELINES ON IDENTIFICATION OF THE ORDINARY HIGH WATER MARK (OHWM) AND IN CONJUNCTION WITH AGENCY CONSULTATION
15.	EXISTING CONDITIONS AT THE TIME OF CONSTRUCTION MAY VARY FROM THOSE SHOWN ON THE DRAWINGS. CONT SHALL VERIFY EXISTING CONDITIONS AND ADJUST WORK PLAN ACCORDINGLY PRIOR TO BEGINNING CONSTRUCTIO
16.	CONTRACTOR SHALL MAINTAIN, RELOCATE OR REPLACE EXISTING SURVEY MONUMENTS, CONTROL POINTS AND S <sup>-</sup> WHICH ARE DISTURBED OR DESTROYED. CONTRACTOR SHALL PERFORM THE WORK TO PRODUCE THE SAME LEVE ACCURACY AS THE ORIGINAL MONUMENT(S) IN A TIMELY MANNER AND AT THE CONTRACTOR'S EXPENSE.
17.	CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION STAKING AND LAYOUT.
18.	CONTRACTOR SHALL PURSUE WORK IN A CONTINUOUS AND DILIGENT MANNER TO ENSURE TIMELY COMPLETION O PROJECT. ANY WORK WITHIN THE FLOWING CHANNEL OF THE NORTH FORK WALLA WALLA RIVER MUST BE CONDUC BETWEEN JULY 1 AND SEPTEMBER 30.
19.	CONTRACTOR IS RESPONSIBLE FOR LOCATING ALL UTILITIES THAT MAY BE IMPACTED AND PROTECTING UTILITIES I CONSTRUCTION. PRIOR TO DIGGING, CONTRACTOR SHALL CALL "DIG SAFELY OREGON" 1-800-332-2344. LOCATING A PROTECTION OF ALL UTILITIES (PUBLIC AND PRIVATE) IS THE RESPONSIBILITY OF THE CONTRACTOR.
20.	CONTRACTOR SHALL PROTECT ALL EXISTING POWER POLES AND OVERHEAD UTILITIES. ALL EQUIPMENT SHALL MAI MINIMUM OF 10 FEET OF CLEARANCE HORIZONTALLY AND VERTICALLY FROM POWER LINES, OR MORE AS REQUIRE SAFETY.
21.	CONTRACTOR SHALL CONFIRM THE ACCESS POINT, ROUTE(S), AND LOCATION OF STORAGE OF MATERIALS AND EQ WITH CONTRACTING OFFICER PRIOR TO TRANSPORTING MATERIALS AND EQUIPMENT TO THE PROJECT SITE.
22.	STORING OF ALL EQUIPMENT WILL BE AT THE CONTRACTOR'S RISK AND AT A LOCATION APPROVED BY A RISK AND AT A
23.	WATER FOR FIRE PREVENTION AND SUPPRESSION AS WELL AS FOR USE WITH CONSTRUCTION ACTIVITIES SHALL B SUPPLIED BY THE CONTRACTOR FROM OFF-SITE SOURCE.
24.	CONTRACTOR SHALL COORDINATE WITH CONTRACTING OFFICER TO ENSURE FISH SALVAGE WITHIN THE PROJECT BEEN ACCOMPLISHED PRIOR TO CONSTRUCTION ACTIVITIES. FISH SALVAGE WILL BE THE RESPONSIBILITY OF THE CONTRACTING AGENCY.
25.	CONTRACTOR SHALL AVOID, PRESERVE, AND PROTECT EXISTING SENSITIVE AREAS SHOWN ON THE DRAWINGS AS BE DISTURBED" OR BEYOND HIGH-VISIBILITY FENCE, OR AS SUBSEQUENTLY MARKED IN THE FIELD BY CONTRACTIN OFFICER.
26.	CONTRACTOR SHALL BE RESPONSIBLE FOR IMPLEMENTING AND MAINTAINING EROSION CONTROL DEVICES DURING CONSTRUCTION. EROSION AND SEDIMENT CONTROL AND STREAM MANAGEMENT MEASURES SHALL CONFORM WIT APPROVED EROSION/SEDIMENT CONTROL PLAN (ESCP) AS SPECIFIED.
27.	ENGINEER RESPONSIBLE FOR THE PREPARATION OF THESE DRAWINGS AND SPECIFICATIONS WILL NOT BE RESPON FOR, OR LIABLE FOR, UNAUTHORIZED CHANGES TO, OR USE OF, THESE DRAWINGS. ALL CHANGES TO THE DRAWING SPECIFICATIONS MUST BE IN WRITING AND APPROVED BY THE ENGINEER RESPONSIBLE FOR THE PREPARATION OF DRAWINGS AND SPECIFICATIONS.
28.	CONTRACTOR SHALL BE RESPONSIBLE FOR ANY WORK NECESSARY TO MAINTAIN A PASSABLE CONDITION ON THE FORK WALLA WALLA RIVER ACCESS ROUTE TO ALL CONSTRUCTION VEHICLES AT THE TIME OF CONSTRUCTION AND PLANTING.
29.	AT THE END OF THE WORK, CONTRACTOR SHALL RESTORE EXISTING LANDOWNER ACCESS ROUTE TO PRE-PROJECT CONDITIONS OR BETTER WITH PLACED AND COMPACTED FILL, COMPARABLE TO ONSITE MATERIAL, TO ESTABLISH O AND DRIVING SURFACE EASILY PASSABLE TO RESIDENT VEHICLES.

2

# **ABBREVIATIONS**

L (WWBWC),	AASHTO AC	AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS ACRE	LARGE LOG JAM			
ASSIGNED BY DAS THE	APPROX ASTM AWPA	APPROXIMATELY AMERICAN SOCIETY FOR TESTING AND MATERIALS AMERICAN WOOD PROTECTION ASSOCIATION			[7	
ON SHEETS IN E FOR BEING THE PROJECT	CF CFS	CUBIC FEET CUBIC FEET PER SECOND	SMALL LOG JAM			
PERMITS AS	۹ CP CY	CENTERLINE CONTROL POINT CUBIC YARD	APEX JAM			
DR, AND	DIA DBH	DIAMETER DIAMETER BREAST HEIGHT	FLOODPLAIN PINNED LOGS			
SITE, INCLUDING NS).	E EA	EAST, EASTING EACH		<i>•</i>		
EIFICATIONS.	EG EX, EXST ELEC	EXISTING GRADE EXISTING ELECTRIC	BOULDER			
OR LIGHT-LINED.	EL, ELEV EOP EXT	ELEVATION EDGE OF PAVEMENT EXTERIOR	ACCESS ROUTE			
EUNIT EQUALS 1 LS ½ INCH.	FG FT	FINAL GRADE FEET	STAGING AND STOCKPILE AF	REA		
NCREMENTS. HS OF FILL ARE	HIP HORIZ HPI	HABITAT IMPROVEMENT PLAN HORIZONTAL HORIZONTAL POINT OF INTERSECTION	LOW FLOW (EXISTING COND	ITIONS)		
	IE INV	INVERT ELEVATION INVERT	WETLANDS			
DRIZONTAL NAL LIDAR ONFORMAL	LF LIDAR	LINEAL FOOT LIGHT DETECTION AND RANGING	WILLOW TRENCHING	-		
RIEGL VQ-1560II ISH SCIENCES IN AND/OR A	LS MAX	LUMP SUM MAXIMUM	ORDINARY HIGH WATER MODELED 100YR FLOW EXT			
) DATA BY TIMES OF THE	MIN	MINIMUM NORTH, NORTHING	(EXISTING CONDITIONS)		100	YR
N THE PROPOSED	N/A	NOT APPLICABLE	ANTICIPATED RIVER CHANNI			
IES ON	NAD NAVD	NORTH AMERICAN DATUM NORTH AMERICAN VERTICAL DATUM	TEMPORARY WATER CROSS	SING		
JLTATION.	NMFS NO	NATIONAL MARINE FISHERIES SERVICE NUMBER	TEMPORARY ACCESS PATH			
S. CONTRACTOR TRUCTION.	NTS	NOT TO SCALE	EXISTING CONTOUR		X	
S AND STAKES ME LEVEL OF	OHWM/OHW OPUS OSC OSHA	ORDINARY HIGH WATER MARK ONLINE POSITIONING USER SERVICE OFFICE OF SPECIES CONSERVATION OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION	TEMPORARY COFFER DAM			
ETION OF THE	PALS	POST-ASSISTED LOG STRUCTURES	QUA	ANTITY SUMMARY	,	
CONDUCTED	PI POB	POINT OF INTERSECTION POINT OF BEGINNING	MATERIAL	SIZE	ROOT	QUANTITY
ILITIES DURING	POE PVC	POINT OF ENDING POLYVINYL CHLORIDE			WAD	
CATING AND	PVI	POINT OF VERTICAL INTERSECTION	(F	NGTH X DIAM. T) /ROCK SIZE	YES/NO NO	# 546
IALL MAINTAIN A	R RM	RADIUS, RANGE RIVER MILE		< 10 X < 0.5	OPTIONAL	882
	SCH	SCHEDULE	LOG TYPE B	25 X 2	YES	10
AND EQUIPMENT	SEC	SECTON	LOG TYPE C	30 X 2	YES	10
E.	SF SIM	SQUARE FOOT SIMILAR	LOG TYPE D	35 X 2	YES	32
CONTRACTING	STA	STATION	LOG TYPE E	40 X 2	YES	120
	SWPPP SY	STORM WATER POLLUTION PREVENTION PLAN SQUARE YARD	LOG TYPE F	25 X 2	NO	5
SHALL BE			LOG TYPE G	30 X 2	NO	5
ROJECT SITE HAS	T TEMP	TOWNSHIP TEMPORARY		0-25 X 1.0 -1.5	NO	250
OF THE	TYP	TYPICAL	BOULDERS LIVE CUTTING	4 MAN	N/A N/A	320 2994
	UG	UNDERGROUND	WILLOW TRENCHING (LF)	N/A N/A	N/A N/A	900
INGS AS "NOT TO FRACTING	UON US UV	UNLESS OTHERWISE NOTED UNITED STATES ULTRAVIOLET	SIDE CHANNEL INLET EXCAVATION (CY)	N/A N/A	N/A N/A	391
S DURING ORM WITH THE	VPI VERT	VERTICAL POINT OF INTERSECTION VERTICAL	SIDE CHANNEL EXCAVATION (CY)	N/A	N/A	832
RESPONSIBLE DRAWINGS AND ATION OF THE	W/ WL WSE	WITH WATER LINE, WETLAND WATER SURFACE ELEVATION		PEC: 32.23.23 SECTION 2.06	N/A	550
	WTR	WATER		PEC: 32.23.23 SECTION 2.01	N/A	75
ON THE NORTH TON AND	WWBWC W/O	WALLA WALLA BASIN WATERSHED COUNCIL WITHOUT INCH, INCHES OR SECOND	SIDE CHANNEL S STREAMBED MIX S	PEC: 32.23.23 SECTION 2.07	N/A	300
-PROJECT ABLISH GRADES	r 0	FOOT, FEET OR MINUTE DEGREE	(CY) RESEEDING/SITE RESTORATION (ACRE)	N/A	N/A	3.53

# LEGEND:



PLOT TIME: 8:25:50 AM

	HIP GENERAL CONSERVATION MEASURES APPLICABLE TO ALL ACTIONS	<u>5. T</u>	Ē
AN FO	E ACTIVITIES COVERED UNDER THE HIP ARE INTENDED TO PROTECT AND RESTORE FISH D WILDLIFE HABITAT WITH LONG-TERM BENEFITS TO ESA-LISTED SPECIES. THE LLOWING GENERAL CONSERVATION MEASURES (DEVELOPED IN COORDINATION WITH FWS AND NMFS) WILL BE APPLIED TO ALL ACTIONS OF THIS PROJECT.	Α.	
00	PROJECT DESIGN AND SITE PREPARATION.	В.	
1	STATE AND FEDERAL PERMITS.	C.	
	ALL APPLICABLE REGULATORY PERMITS AND OFFICIAL PROJECT AUTHORIZATIONS WILL BE OBTAINED BEFORE PROJECT IMPLEMENTATION.		
B.	THESE PERMITS AND AUTHORIZATIONS INCLUDE, BUT ARE NOT LIMITED TO, NATIONAL ENVIRONMENTAL POLICY ACT, NATIONAL HISTORIC PRESERVATION ACT, THE APPROPRIATE STATE AGENCY REMOVAL AND FILL PERMIT, USACE CLEAN WATER ACT (CWA) 404 PERMITS, CWA SECTION 401 WATER QUALITY CERTIFICATIONS, AND FEMA NO-RISE ANALYSES.	D. E.	
2.	TIMING OF IN-WATER WORK.		
	APPROPRIATE STATE (OREGON DEPARTMENT OF FISH AND WILDLIFE (ODFW),		
7 (.	WASHINGTON DEPARTMENT OF FISH AND WILDLIFE (WDFW), IDAHO DEPARTMENT OF FISH AND GAME (IDFG), AND MONTANA FISH WILDLIFE AND PARKS (MFWP)) GUIDELINES FOR TIMING OF IN-WATER WORK WINDOWS (IWW) WILL BE FOLLOWED.	F.	
B.	CHANGES TO ESTABLISHED WORK WINDOWS WILL BE APPROVED BY REGIONAL STATE BIOLOGISTS AND BPA'S EC LEAD.		
C	BULL TROUT. FOR AREAS WITH DESIGNATED IN-WATER WORK WINDOWS FOR BULL	<u>6. T</u>	Ē
0.	TROUT OR AREAS KNOWN TO HAVE BULL TROUT, PROJECT PROPONENTS WILL CONTACT THE APPROPRIATE USFWS FIELD OFFICE TO INSURE THAT ALL REASONABLE IMPLEMENTATION MEASURES ARE CONSIDERED AND AN APPROPRIATE IN-WATER WORK	Α.	•
	WINDOW IS BEING USED TO MINIMIZE PROJECT EFFECTS.	В.	
D.	LAMPREY. WORKING IN STREAM OR RIVER CHANNELS THAT CONTAIN PACIFIC LAMPREY WILL BE AVOIDED FROM MARCH 1 TO JULY 1 FOR REACHES <5,000 FEET IN ELEVATION		
	AND FROM MARCH 1 TO AUGUST 1 FOR REACHES >5,000 FEET. IF EITHER TIMEFRAME IS INCOMPATIBLE WITH OTHER OBJECTIVES, THE AREA WILL BE SURVEYED FOR NESTS AND	C.	
	LAMPREY PRESENCE, AND AVOIDED IF POSSIBLE. IF LAMPREYS ARE KNOWN TO EXIST, THE PROJECT SPONSOR WILL UTILIZE DEWATERING AND SALVAGE PROCEDURES (SEE FISH SALVAGE AND ELECTROFISHING SECTIONS) TO MINIMIZE ADVERSE EFFECTS.	0.	
E.	THE IN-WATER WORK WINDOW WILL BE PROVIDED IN THE CONSTRUCTION PLANS.		
<u>3.</u>	CONTAMINANTS.		
A.	EXCAVATION OF MORE THAN 20 CUBIC YARDS WILL REQUIRE A SITE VISIT AND DOCUMENTED ASSESSMENT FOR POTENTIAL CONTAMINANT SOURCES. THE SITE ASSESSMENT WILL BE STORED WITH PROJECT FILES OR AS AN APPENDIX TO THE BASIS OF DESIGN REPORT.		
В.	THE SITE ASSESSMENT WILL SUMMARIZE:	7. S	_
	1. THE SITE VISIT, CONDITION OF THE PROPERTY, AND IDENTIFICATION OF ANY AREAS	<u>7.0</u>	
	USED FOR VARIOUS INDUSTRIAL PROCESSES;	Α.	•
	<ol> <li>AVAILABLE RECORDS, SUCH AS FORMER SITE USE, BUILDING PLANS, AND RECORDS OF ANY PRIOR CONTAMINATION EVENTS;</li> </ol>		
	3. INTERVIEWS WITH KNOWLEDGEABLE PEOPLE, SUCH AS SITE OWNERS, OPERATORS, OCCUPANTS, NEIGHBORS, OR LOCAL GOVERNMENT OFFICIALS; AND	В.	
	4. THE TYPE, QUANTITY, AND EXTENT OF ANY POTENTIAL CONTAMINATION SOURCES.	C.	•
<u>4. S</u>	SITE LAYOUT AND FLAGGING.		
Α.	CONSTRUCTION AREAS TO BE CLEARLY FLAGGED PRIOR TO CONSTRUCTION.	D.	
Β.	AREAS TO BE FLAGGED WILL INCLUDE:		
	<ol> <li>SENSITIVE RESOURCE AREAS, SUCH AS AREAS BELOW ORDINARY HIGH WATER, SPAWNING AREAS, SPRINGS, AND WETLANDS;</li> </ol>	<u>8. E</u>	
	2. EQUIPMENT ENTRY AND EXIT POINTS;	Α.	•
	3. ROAD AND STREAM CROSSING ALIGNMENTS;		
	4. STAGING, STORAGE, AND STOCKPILE AREAS; AND	-	
	5. NO-SPRAY AREAS AND BUFFERS.	В.	

## ORARY ACCESS ROADS AND PATHS.

ISTING ACCESS ROADS AND PATHS WILL BE PREFERENTIALLY USED WHENEVER ASONABLE, AND THE NUMBER AND LENGTH OF TEMPORARY ACCESS ROADS AND THS THROUGH RIPARIAN AREAS AND FLOODPLAINS WILL BE MINIMIZED.

EHICLE USE AND HUMAN ACTIVITIES, INCLUDING WALKING, IN AREAS OCCUPIED BY RRESTRIAL ESA-LISTED SPECIES WILL BE MINIMIZED.

MPORARY ACCESS ROADS AND PATHS WILL NOT BE BUILT ON SLOPES WHERE RADE, SOIL, OR OTHER FEATURES SUGGEST A LIKELIHOOD OF EXCESSIVE EROSION R FAILURE. IF SLOPES ARE STEEPER THAN 30%, THEN THE ROAD WILL BE DESIGNED ' A CIVIL ENGINEER WITH EXPERIENCE IN STEEP ROAD DESIGN.

IE REMOVAL OF RIPARIAN VEGETATION DURING CONSTRUCTION OF TEMPORARY CESS ROADS WILL BE MINIMIZED. WHEN TEMPORARY VEGETATION REMOVAL IS EQUIRED, VEGETATION WILL BE CUT AT GROUND LEVEL (NOT GRUBBED).

PROJECT COMPLETION, ALL TEMPORARY ACCESS ROADS AND PATHS WILL BE BLITERATED, AND THE SOIL WILL BE STABILIZED AND REVEGETATED, ROAD AND PATH BLITERATION REFERS TO THE MOST COMPREHENSIVE DEGREE OF ECOMMISSIONING AND INVOLVES DECOMPACTING THE SURFACE AND DITCH, PULLING IE FILL MATERIAL ONTO THE RUNNING SURFACE, AND RESHAPING TO MATCH THE RIGINAL CONTOUR.

ELICOPTER FLIGHT PATTERNS WILL BE ESTABLISHED IN ADVANCE AND LOCATED TO OID TERRESTRIAL ESA-LISTED SPECIES AND THEIR OCCUPIED HABITAT DURING ENSITIVE LIFE STAGES.

### ORARY STREAM CROSSINGS.

(ISTING STREAM CROSSINGS OR BEDROCK WILL BE PREFERENTIALLY USED HENEVER REASONABLE, AND THE NUMBER OF TEMPORARY STREAM CROSSINGS ILL BE MINIMIZED.

MPORARY BRIDGES AND CULVERTS WILL BE INSTALLED TO ALLOW FOR EQUIPMENT ID VEHICLE CROSSING OVER PERENNIAL STREAMS DURING CONSTRUCTION. REATED WOOD SHALL NOT BE USED ON TEMPORARY BRIDGE CROSSINGS OR IN CATIONS IN CONTACT WITH OR DIRECTLY OVER WATER.

IR PROJECTS THAT REQUIRE EQUIPMENT AND VEHICLES TO CROSS IN THE WET:

- THE LOCATION AND NUMBER OF ALL WET CROSSINGS SHALL BE APPROVED BY THE BPA EC LEAD AND DOCUMENTED IN THE CONSTRUCTION PLANS:
- VEHICLES AND MACHINERY SHALL CROSS STREAMS AT RIGHT ANGLES TO THE MAIN CHANNEL WHENEVER POSSIBLE:
- NO STREAM CROSSINGS WILL OCCUR 300 FEET UPSTREAM OR 100 FEET DOWNSTREAM OF AN EXISTING REDD OR SPAWNING FISH: AND
- AFTER PROJECT COMPLETION. TEMPORARY STREAM CROSSINGS WILL BE OBLITERATED AND BANKS RESTORED.

### NG, STORAGE, AND STOCKPILE AREAS.

AGING AREAS (USED FOR CONSTRUCTION EQUIPMENT STORAGE, VEHICLE STORAGE, IELING, SERVICING, AND HAZARDOUS MATERIAL STORAGE) WILL BE 150 FEET OR DRE FROM ANY NATURAL WATER BODY OR WETLAND. STAGING AREAS CLOSER THAN 0 FEET WILL BE APPROVED BY THE ENVIRONMENTAL COMPLIANCE (EC) LEAD.

TURAL MATERIALS USED FOR IMPLEMENTATION OF AQUATIC RESTORATION, SUCH S LARGE WOOD, GRAVEL, AND BOULDERS, MAY BE STAGED WITHIN 150 FEET IF EARLY INDICATED IN THE PLANS THAT AREA IS FOR NATURAL MATERIALS ONLY.

IY LARGE WOOD, TOPSOIL, AND NATIVE CHANNEL MATERIAL DISPLACED BY DNSTRUCTION WILL BE STOCKPILED FOR USE DURING SITE RESTORATION AT A PECIFICALLY IDENTIFIED AND FLAGGED AREA.

IY MATERIAL NOT USED IN RESTORATION, AND NOT NATIVE TO THE FLOODPLAIN, ILL BE DISPOSED OF OUTSIDE THE 100-YEAR FLOODPLAIN.

### MENT.

ECHANIZED EQUIPMENT AND VEHICLES WILL BE SELECTED, OPERATED, AND AINTAINED IN A MANNER THAT MINIMIZES ADVERSE EFFECTS ON THE ENVIRONMENT .G., MINIMALLY-SIZED, LOW PRESSURE TIRES; MINIMAL HARD-TURN PATHS FOR RACKED VEHICLES: TEMPORARY MATS OR PLATES WITHIN WET AREAS OR ON ENSITIVE SOILS).

UIPMENT WILL BE STORED, FUELED, AND MAINTAINED IN AN CLEARLY IDENTIFIED AGING AREA THAT MEETS STAGING AREA CONSERVATION MEASURES.

- GALLONS).
- AND ADJACENT TO THE STREAM CHANNEL AND LIVE WATER.
- BODY OR WETLAND.
- FREE.


### 9. EROSION CONTROL

- A. TEMPORARY EROSION CONTROL MEASURES INCLUDE:
  - REHABILITATION IS COMPLETE;
  - **PROJECT IMPLEMENTATION:**
  - GEOTEXTILES AND GEOSYNTHETIC FABRIC:

  - 1/3 OF THE EXPOSED HEIGHT OF THE CONTROL; AND
  - CONTROL MEASURES WILL BE REMOVED.
- EROSION CONTROL WILL BE AVAILABLE AT THE WORK SITE:
- 1. A SUPPLY OF SEDIMENT CONTROL MATERIALS; AND

### 10. DUST ABATEMENT.

- MEASURES.
- SUBJECT TO WIND EROSION.
- OR SLOPES ARE STEEP)
- ABATEMENT CHEMICALS.



PLOT DATE: 3/14/2024

PLOT TIME: 12:10:04 PM

	PROJECT DESIGN AND SITE PREPARATION (CONTINUED).		5.
<u>11.</u>	SPILL PREVENTION, CONTROL, AND COUNTER MEASURES.		
A	. A DESCRIPTION OF HAZARDOUS MATERIALS THAT WILL BE USED, INCLUDING INVENTORY, STORAGE, AND HANDLING PROCEDURES WILL BE AVAILABLE ON-SITE.		6.
E	. WRITTEN PROCEDURES FOR NOTIFYING ENVIRONMENTAL RESPONSE AGENCIES WILL BE POSTED AT THE WORK SITE.		7.
C	. SPILL CONTAINMENT KITS (INCLUDING INSTRUCTIONS FOR CLEANUP AND DISPOSAL) ADEQUATE FOR THE TYPES AND QUANTITY OF HAZARDOUS MATERIALS USED AT THE SITE WILL BE AVAILABLE AT THE WORK SITE.		8.
C	. WORKERS WILL BE TRAINED IN SPILL CONTAINMENT PROCEDURES AND WILL BE INFORMED OF THE LOCATION OF SPILL CONTAINMENT KITS.		9.
E	. ANY WASTE LIQUIDS GENERATED AT THE STAGING AREAS WILL BE TEMPORARILY STORED UNDER AN IMPERVIOUS COVER, SUCH AS A TARPAULIN, UNTIL THEY CAN BE PROPERLY TRANSPORTED TO AND DISPOSED OF AT A FACILITY THAT IS		10. 11.
	APPROVED FOR RECEIPT OF HAZARDOUS MATERIALS.		12.
F	PUMPS USED ADJACENT TO WATER SHALL USE SPILL CONTAINMENT SYSTEMS.		
<u>12.</u>	INVASIVE SPECIES CONTROL.		13.
A	. PRIOR TO ENTERING THE SITE, ALL VEHICLES AND EQUIPMENT WILL BE POWER WASHED, ALLOWED TO FULLY DRY, AND INSPECTED TO MAKE SURE NO PLANTS, SOIL, OR OTHER ORGANIC MATERIAL ADHERES TO THE SURFACE.		14. 15.
E	. WATERCRAFT, WADERS, BOOTS, AND ANY OTHER GEAR TO BE USED IN OR NEAR WATER WILL BE INSPECTED FOR AQUATIC INVASIVE SPECIES.		16.
C	. WADING BOOTS WITH FELT SOLES ARE NOT TO BE USED DUE TO THEIR PROPENSITY FOR AIDING IN THE TRANSFER OF INVASIVE SPECIES UNLESS DECONTAMINATION PROCEDURES HAVE BEEN APPROVED BY THE EC LEAD.	D.	17. SA
	WORK AREA ISOLATION AND FISH SALVAGE.		1.
<u>1.</u> V	/ORK AREA ISOLATION.		2.
A	. ANY WORK AREA WITHIN THE WETTED CHANNEL WILL BE ISOLATED FROM THE ACTIVE STREAM WHENEVER ESA-LISTED FISH ARE REASONABLY CERTAIN TO BE PRESENT, OR IF THE WORK AREA IS LESS THAN 300-FEET UPSTREAM FROM KNOWN SPAWNING HABITATS.		3. 4.
E	. WORK AREA ISOLATION AND FISH SALVAGE ACTIVITIES WILL COMPLY WITH THE IN-WATER WORK WINDOW.		-
C	. DESIGN PLANS WILL INCLUDE ALL ISOLATION ELEMENTS AND AREAS (COFFER DAMS, PUMPS, DISCHARGE AREAS, FISH SCREENS, FISH RELEASE AREAS, ETC.).		5. 6.
C	. WORK AREA ISOLATION AND FISH CAPTURE ACTIVITIES WILL OCCUR DURING PERIODS OF THE COOLEST AIR AND WATER TEMPERATURES POSSIBLE, NORMALLY EARLY IN THE MORNING VERSUS LATE IN THE DAY, AND DURING CONDITIONS APPROPRIATE TO MINIMIZE STRESS AND DEATH OF SPECIES PRESENT.		7.
2. F	ISH SALVAGE.		8.
	. MONITORING AND RECORDING WILL TAKE PLACE FOR DURATION OF SALVAGE. THE		9.
	SALVAGE REPORT WILL BE COMMUNICATED TO AGENCIES VIA THE PROJECT COMPLETION FORM (PCF).		10.
E	. SALVAGE ACTIVITIES SHOULD TAKE PLACE DURING CONDITIONS TO MINIMIZE STRESS TO FISH SPECIES, TYPICALLY PERIODS OF THE COOLEST AIR AND WATER TEMPERATURES WHICH OCCUR IN THE MORNING VERSUS LATE IN THE DAY.	<u>3. EL</u>	<u>ECT.</u>
C	. SALVAGE OPERATIONS WILL FOLLOW THE ORDERING, METHODS, AND CONSERVATION MEASURES SPECIFIED BELOW:	Α.	1.
	1. SLOWLY REDUCE WATER FROM THE WORK AREA TO ALLOW SOME FISH TO LEAVE VOLITIONALLY.		2.
	<ol> <li>BLOCK NETS WILL BE INSTALLED AT UPSTREAM AND DOWNSTREAM LOCATIONS AND MAINTAINED IN A SECURED POSITION TO EXCLUDE FISH FROM ENTERING THE PROJECT AREA.</li> </ol>		3.
	3. BLOCK NETS WILL BE SECURED TO THE STREAM CHANNEL BED AND BANKS UNTIL FISH CAPTURE AND TRANSPORT ACTIVITIES ARE COMPLETE. BLOCK		4.
	NETS MAY BE LEFT IN PLACE FOR THE DURATION OF THE PROJECT TO EXCLUDE FISH AS LONG AS PASSAGE REQUIREMENTS ARE MET.		5.
	4. NETS WILL BE MONITORED HOURLY DURING IN-STREAM DISTURBANCE.		

1

IF BLOCK NETS REMAIN IN PLACE MORE THAN ONE DAY, THE NETS WILL BE MONITORED AT LEAST DAILY TO ENSURE THEY ARE SECURED AND FREE OF ORGANIC ACCUMULATION. IF BULL TROUT ARE PRESENT. NETS ARE TO BE CHECKED EVERY 4 HOURS FOR FISH IMPINGEMENT.

CAPTURE FISH THROUGH SEINING AND RELOCATE TO STREAMS.

- WHILE DEWATERING, ANY REMAINING FISH WILL BE COLLECTED BY HAND OR DIP NETS.
- SEINES WITH A MESH SIZE TO ENSURE CAPTURE OF THE RESIDING ESA-LISTED FISH WILL BE USED.
- MINNOW TRAPS WILL BE LEFT IN PLACE OVERNIGHT AND USED IN CONJUNCTION WITH SEINING.
- ELECTROFISH TO CAPTURE AND RELOCATED FISH NOT CAUGHT DURING SEINING PER ELECTROFISH CONSERVATION MEASURES.
- CONTINUE TO SLOWLY DEWATER STREAM REACH.
- COLLECT ANY REMAINING FISH IN COLD-WATER BUCKETS AND RELOCATED TO THE STREAM.
- LIMIT THE TIME FISH ARE IN A TRANSPORT BUCKET
- MINIMIZE PREDATION BY TRANSPORTING COMPARABLE SIZES IN BUCKETS.
- BUCKET WATER TO BE CHANGED EVERY 15 MINUTES OR AERATED.
- BUCKETS WILL BE KEPT IN SHADED AREAS OR COVERED.
- DEAD FISH WILL NOT BE STORED IN TRANSPORT BUCKETS. BUT WILL BE LEFT ON THE STREAM BANK TO AVOID MORTALITY COUNTING ERRORS.
- VAGE GUIDELINES FOR BULL TROUT, LAMPREY, MUSSELS, AND NATIVE FISH.
- CONDUCT SITE SURVEY TO ESTIMATE SALVAGE NUMBERS.
- PRE-SELECT SITE(S) FOR RELEASE AND/OR MUSSEL BED RELOCATION.
- SALVAGE OF BULL TROUT WILL NOT TAKE PLACE WHEN WATER **TEMPERATURES EXCEED 15 DEGREES CELSIUS.**
- IF DRAWDOWN LESS THAN 48 HOURS, SALVAGE OF LAMPREY AND MUSSELS MAY NOT BE NECESSARY IF TEMPERATURES SUPPORT SURVIVAL IN SEDIMENTS.
- SALVAGE MUSSELS BY HAND. LOCATING BY SNORKELING OR WADING.
- SALVAGE LAMPREY BY ELECTROFISHING (SEE ELECTROFISHING FOR LARVAL LAMPREY SETTINGS AND LARVAL LAMPREY DRY SHOCKING SETTINGS).
- SALVAGE BONY FISH AFTER LAMPREY WITH NETS OR ELECTROFISHING (SEE ELECTROFISHING FOR APPROPRIATE SETTINGS).
- REGULARLY INSPECT DEWATERED SITE SINCE LAMPREY LIKELY TO EMERGE AFTER DEWATERING AND MUSSELS MAY BECOME VISIBLE.
- MUSSELS MAY BE TRANSFERRED IN COOLERS.
- MUSSELS WILL BE PLACED INDIVIDUALLY TO ENSURE ABILITY TO BURROW INTO NEW HABITAT.
- ROFISHING.
- IAL SITE SURVEY AND INITIAL SETTINGS.
- IDENTIFY SPAWNING ADULTS AND ACTIVE REDDS TO AVOID.
- RECORD WATER TEMPERATURE. ELECTROFISHING WILL NOT OCCUR WHEN WATER TEMPERATURES ARE ABOVE 18 DEGREES CELSIUS.
- IF POSSIBLE, A BLOCK NET WILL BE PLACED DOWNSTREAM AND CHECKED REGULARLY TO CAPTURE STUNNED FISH THAT DRIFT DOWNSTREAM.
- INITIAL SETTINGS WILL BE 100 VOLTS, PULSE WIDTH OF 500 MICRO SECONDS, AND PULSE RATE OF 30 HERTZ.
- RECORDS FOR CONDUCTIVITY, WATER TEMPERATURE, AIR TEMPERATURE, ELECTROFISHING SETTINGS, ELECTROFISHER MODEL, ELECTROFISHER CALIBRATION, FISH CONDITIONS, FISH MORTALITIES, AND TOTAL CAPTURE RATES WILL BE INCLUDED IN THE SALVAGE LOG BOOK.

- B. ELECTROFISHING TECHNIQUE.
  - VOLTAGE WHILE REMAINING BELOW MAXIMUM LEVELS.

  - 3. IF FISH CAPTURE IS NOT SUCCESSFUL USING STRAIGHT DC, THE MAXIMUM VALUES UNTIL CAPTURE IS SUCCESSFUL


  - GRADIENTS LIKELY TO INCREASE.
  - POOR (I.E. UNABLE TO SEE THE BED OF THE STREAM).
- C. SAMPLE PROCESSING.

  - CONTAINERS, AIR PUMPS, WATER TRANSFERS, ETC.
- D. BULL TROUT ELECTROFISHING.

  - **TEMPERATURES EXCEED 15 DEGREES CELSIUS.**
- E. LARVAL LAMPREY ELECTROFISHING.

  - AND "STUN".
  - RECOMMENDED TO INCREASE EMERGENCE.

  - MAY BE USED IN POOR VISIBILITY.
- UPSTREAM AND WORKING DOWNSTREAM.



PLOT TIME: 12:10:04 PM

4 of 22

SHEET

		WORK AREA ISOLATION AND FISH SALVAGE (CONTINUED).	В.	A MIX
	<u>4. DE</u>	EWATERING.		REDI PRE-
	A.	DEWATERING WILL OCCUR AT A RATE SLOW ENOUGH TO ALLOW SPECIES TO NATURALLY MIGRATE OUT OF THE WORK AREA.	C.	VEGE FROM
A	В.	WHERE A GRAVITY FEED DIVERSION IS NOT POSSIBLE, A PUMP MAY BE USED. PUMPS WILL BE INSTALLED TO AVOID REPETITIVE DEWATERING AND REWATERING.	D.	SHOI STEF
	C.	WHEN FISH ARE PRESENT, PUMPS WILL BE SCREENED IN ACCORDANCE WITH NMFS FISH SCREEN CRITERIA. NMFS ENGINEERING REVIEW AND APPROVAL WILL BE OBTAINED FOR PUMPS EXCEEDING 3 CUBIC FEET PER SECOND.	E.	OR C
	D.	DISSIPATION OF FLOW ENERGY AT THE BYPASS OUTFLOW WILL BE PROVIDED TO PREVENT DAMAGE TO THE STREAM CHANNEL AND RIPARIAN VEGETATION.	F.	
_	E.	SEEPAGE WATER WILL BE PUMPED TO A TEMPORARY STORAGE AND TREATMENT SITE OF INTO UPLAND AREAS TO ALLOW WATER TO PERCOLATE THROUGH SOIL AND VEGETATION PRIOR TO REENTERING THE STREAM CHANNEL.	G.	REVE
		CONSTRUCTION AND POST CONSTRUCTION CONSERVATION MEASURES.	7. SI	POST TE AC
	<u>1. FIS</u>	SH PASSAGE.		THE
	A.	FISH PASSAGE WILL BE PROVIDED FOR ADULT AND JUVENILE FISH LIKELY TO BE PRESENT DURING CONSTRUCTION UNLESS PASSAGE DID NOT EXIST BEFORE CONSTRUCTION, THE STREAM IS NATURALLY IMPASSABLE, OR PASSAGE WILL NEGATIVELY IMPACT ESA-LISTED SPECIES OR THEIR HABITAT.		IMPL FOLL AND
В	В.	FISH PASSAGE ALTERNATIVES WILL BE APPROVED BY THE BPA EC LEAD UNDER ADVISEMENT BY THE NMFS HABITAT BIOLOGIST.		PRO
	2. CC	INSTRUCTION AND DISCHARGE WATER.	<u>8. CV</u>	VA SE
		SURFACE WATER MAY BE DIVERTED TO MEET CONSTRUCTION NEEDS ONLY IF DEVELOPED SOURCES ARE UNAVAILABLE OR INADEQUATE.	A.	THE RECO ENSU
	В.	DIVERSIONS WILL NOT EXCEED 10% OF THE AVAILABLE FLOW.	В.	DURI
_	C.	CONSTRUCTION DISCHARGE WATER WILL BE COLLECTED AND TREATED TO REMOVE DEBRIS, NUTRIENTS, SEDIMENT, PETROLEUM HYDROCARBONS, METALS, AND OTHER POLLUTANTS.		DEPA ECOL
	<u>3. TIN</u>	ME AND EXTENT OF DISTURBANCE.	A.	WHE CHAI
	A.	EARTHWORK REQUIRING IN-STREAM MECHANIZED EQUIPMENT (INCLUDING DRILLING, EXCAVATION, DREDGING, FILLING, AND COMPACTING) WILL BE COMPLETED AS QUICKLY AS POSSIBLE.	В.	THE REW
С	В.	MECHANIZED EQUIPMENT WILL WORK FROM TOP OF BANK UNLESS WORK FROM ANOTHER LOCATION WILL RESULT IN LESS HABITAT DISTURBANCE (TURBIDITY, VEGETATION DISTURBANCE, ETC.).		1. T
	<u>4. CE</u>	SSATION OF WORK.		2. F
	A.	PROJECT OPERATIONS WILL CEASE WHEN HIGH FLOW CONDITIONS MAY RESULT IN INUNDATION OF THE PROJECT AREA (FLOOD EFFORTS TO DECREASE DAMAGES TO NATURAL RESOURCES PERMITTED).		3. I
	В.	WATER QUALITY LEVELS EXCEEDED. SEE CWA SECTION 401 WATER QUALITY CERTIFICATION AND TURBIDITY MEASURES.		4. S
_	<u>5. SI</u>	TE RESTORATION.		F
	A.	DISTURBED AREAS, STREAM BANKS, SOILS, AND VEGETATION WILL BE CLEANED UP AND RESTORED TO IMPROVED OR PRE-PROJECT CONDITIONS.		5. I F
	В.	PROJECT-RELATED WASTE WILL BE REMOVED.		6. F
	C.	TEMPORARY ACCESS ROADS AND STAGING WILL BE DECOMPACTED AND RESTORED. SOILS WILL BE LOOSENED IF NEEDED FOR REVEGETATION OR WATER INFILTRATION.		( 7.   (
D	D.	THE PROJECT SPONSOR WILL RETAIN THE RIGHT OF REASONABLE ACCESS TO THE SITE TO MONITOR AND MAINTAIN THE SITE OVER THE LIFE OF THE PROJECT.		8. I
	<u>6. RE</u>	VEGETATION.		F
	A.	PLANTING AND SEEDING WILL OCCUR PRIOR TO OR AT THE BEGINNING OF THE FIRST GROWING SEASON AFTER CONSTRUCTION.		9. I N

1

IX OF NATIVE SPECIES (INVASIVE SPECIES NOT ALLOWED) APPROPRIATE TO E SITE WILL BE USED TO REESTABLISH VEGETATION, PROVIDE SHADE, AND DUCE EROSION. REESTABLISHED VEGETATION SHOULD BE AT LEAST 70% OF E-PROJECT CONDITIONS WITHIN THREE YEARS.

GETATION SUCH AS WILLOWS, SEDGES, OR RUSH MATS WILL BE SALVAGED OM DISTURBED OR ABANDONED AREAS TO BE REPLANTED.

ORT-TERM STABILIZATION MEASURE MAY INCLUDE THE USE OF NON-NATIVE ERILE SEED MIX (WHEN NATIVE NOT AVAILABLE), WEED-FREE CERTIFIED STRAW, OTHER SIMILAR TECHNIQUES.

RFACE FERTILIZER WILL NOT BE APPLIED WITHIN 50 FEET OF ANY STREAM, WATE DY, OR WETLAND.

ICING WILL BE INSTALLED AS NECESSARY TO PREVENT ACCESS TO /EGETATED SITES BY LIVESTOCK OR UNAUTHORIZED PERSONS.

ASIVE PLANTS WILL BE REMOVED OR CONTROLLED UNTIL NATIVE PLANT ECIES ARE WELL ESTABLISHED (TYPICALLY THREE YEARS ST-CONSTRUCTION).

CCESS AND IMPLEMENTATION MONITORING.

E PROJECT SPONSOR WILL PROVIDE CONSTRUCTION MONITORING DURING PLEMENTATION TO ENSURE ALL CONSERVATION MEASURES ARE ADEQUATELY LOWED, EFFECTS TO LISTED SPECIES ARE NOT GREATER THAN PREDICTED, D INCIDENTAL TAKE LIMITATIONS ARE NOT EXCEEDED.

E PROJECT SPONSOR OR DESIGNATED REPRESENTATIVE WILL SUBMIT THE OJECT COMPLETION FORM (PCF) WITHIN 30 DAYS OF PROJECT COMPLETION.

# ECTION 401 WATER QUALITY CERTIFICATION.

E PROJECT SPONSOR OR DESIGNATED REPRESENTATIVE WILL COMPLETE AND CORD WATER QUALITY OBSERVATIONS (SEE TURBIDITY MONITORING) TO SURE IN-WATER WORK IS NOT DEGRADING WATER QUALITY.

RING CONSTRUCTION, WATER QUALITY PROVISIONS PROVIDED BY THE OREGON PARTMENT OF ENVIRONMENTAL QUALITY, WASHINGTON DEPARTMENT OF OLOGY, IDAHO DEPARTMENT OF ENVIRONMENTAL QUALITY WILL BE FOLLOWED.

### STAGED REWATERING PLAN.

EN REINTRODUCING WATER TO DEWATERED AREAS AND NEWLY CONSTRUCTED ANNELS, A STAGED REWATERING PLAN WILL BE APPLIED.

E FOLLOWING WILL BE APPLIED TO ALL REWATERING EFFORTS. COMPLEX WATERING EFFORTS MAY REQUIRE ADDITIONAL NOTES OR A DEDICATED SHEET THE CONSTRUCTION DETAILS.


- TURBIDITY MONITORING PROTOCOL WILL BE APPLIED TO REWATERING EFFORTS.
- PRE-WASH THE AREA BEFORE REWATERING. TURBID WASH WATER WILL BE DETAINED AND PUMPED TO THE FLOODPLAIN OR SEDIMENT CAPTURE AREAS RATHER THAN DISCHARGING TO FISH-BEARING STREAMS.
- INSTALL SEINE NETS AT UPSTREAM END TO PREVENT FISH FROM MOVING DOWNSTREAM UNTIL 2/3 OF TOTAL FLOW IS RESTORED TO THE CHANNEL.
- STARTING IN EARLY MORNING INTRODUCE 1/3 OF NEW CHANNEL FLOW OVER PERIOD OF 1-2 HOURS.
- INTRODUCE SECOND THIRD OF FLOW OVER NEXT 1 TO 2 HOURS AND BEGIN FISH SALVAGE OF BYPASS CHANNEL IF FISH ARE PRESENT.
- REMOVE UPSTREAM SEINE NETS ONCE 2/3 FLOW IN REWATERED CHANNEL AND DOWNSTREAM TURBIDITY IS WITHIN ACCEPTABLE RANGE (LESS THAN 40 NTU OR LESS THAN 10% BACKGROUND).
- INTRODUCE FINAL THIRD OF FLOW ONCE FISH SALVAGE EFFORTS ARE COMPLETE AND DOWNSTREAM TURBIDITY VERIFIED TO BE WITHIN ACCEPTABLE RANGE.


INSTALL PLUG TO BLOCK FLOW INTO OLD CHANNEL OR BYPASS. REMOVE ANY REMAINING SEINE NETS.

IN LAMPREY SYSTEMS, LAMPREY SALVAGE AND DRY SHOCKING MAY BE NECESSARY.


# TURBIDITY MONITORING.

- A. RECORD THE READING, LOCATION, AND TIME FOR THE BACKGROUND READING APPROXIMATELY 100 FEET UPSTREAM OF THE PROJECT AREA USING A RECENTLY CALIBRATED TURBIDIMETER OR VIA VISUAL OBSERVATION (SEE THE HIP HANDBOOK TURBIDITY MONITORING SECTION FOR A VISUAL OBSERVATION KEY).
- B. RECORD THE TURBIDITY READING, LOCATION, AND TIME AT THE MEASUREMENT COMPLIANCE LOCATION POINT.
  - 1. 50 FEET DOWNSTREAM FOR STREAMS LESS THAN 30 FEET WIDE.
  - 2. 100 FEET DOWNSTREAM FOR STREAMS BETWEEN 30 AND 100 FEET WIDE.
  - 3. 200 FEET DOWNSTREAM FOR STREAMS GREATER THAN 100 FEET WIDE.
  - 4. 300 FEET FROM THE DISCHARGE POINT OR NONPOINT SOURCE FOR LOCATIONS SUBJECT TO TIDAL OR COASTAL SCOUR.
- C. TURBIDITY SHALL BE MEASURED (BACKGROUND LOCATION AND COMPLIANCE POINTS) EVERY 4 HOURS WHILE WORK IS BEING IMPLEMENTED.
- D. IF THERE IS A VISIBLE DIFFERENCE BETWEEN A COMPLIANCE POINT AND THE BACKGROUND, THE EXCEEDANCE WILL BE NOTED IN THE PROJECT COMPLETION FORM (PCF). ADJUSTMENTS OR CORRECTIVE MEASURES WILL BE TAKEN IN ORDER TO REDUCE TURBIDITY.
- E. IF EXCEEDANCES OCCUR FOR MORE THAN TWO CONSECUTIVE MONITORING INTERVALS (AFTER 8 HOURS), THE ACTIVITY WILL STOP UNTIL THE TURBIDITY LEVEL RETURNS TO BACKGROUND. THE BPA EC LEAD WILL BE NOTIFIED OF ALL EXCEEDANCES AND CORRECTIVE ACTIONS AT PROJECT COMPLETION.
- F. IF TURBIDITY CONTROLS (COFFER DAMS, WADDLES, FENCING, ETC.) ARE DETERMINED INEFFECTIVE, CREWS WILL BE MOBILIZED TO MODIFY AS NECESSARY. OCCURRENCES WILL BE DOCUMENTED IN THE PROJECT COMPLETION FORM (PCF).
- G. FINAL TURBIDITY READINGS, EXCEEDANCES, AND CONTROL FAILURES WILL BE SUBMITTED TO THE BPA EC LEAD USING THE PROJECT COMPLETION FORM (PCF).








PLOT TIME: 10:22:40 AM




- BOUNDARY LINES ARE DUE TO DIFFERENT DATA
- MIX, AND STREAMBED MIX WHEREVER POSSIBLE. DISPERSED EVENLY IN THE UPLAND AREAS AT









LARGE LOG JAM
SMALL LOG JAM
APEX JAM
FLOODPLAIN PINNED LOGS
EXISTING ACCESS ROUTE
LOW FLOW (EXISTING CONDITIONS)
WILLOW TRENCHING
EXISTING CONTOURS
EXISTING WETLANDS
SIDE CHANNEL EXCAVATION AREA
ANTICIPATED FUTURE FLOWPATH
ORDINARY HIGH WATER
EXISTING THALWEG ALIGNMENT
TEMPORARY COFFERDAM




PLOT DATE: 3/18/2024






LEGEND



\_\_\_\_\_


SMALL LOG JAM
APEX JAM
FLOODPLAIN PINNED LOGS
EXISTING ACCESS ROUTE
LOW FLOW (EXISTING CONDITIONS)
WILLOW TRENCHING
EXISTING CONTOURS
EXISTING WETLANDS
SIDE CHANNEL EXCAVATION AREA
ANTICIPATED FUTURE FLOWPATH
ORDINARY HIGH WATER
EXISTING THALWEG ALIGNMENT
TEMPORARY COFFERDAM

PLOT TIME: 4:04:27 PM





PLOT DATE: 3/14/2024

PLOT TIME: 4:04:33 PM



- BETWEEN RM 4.3 AND 4.4. THEREFORE, THE DRAWING
- RESPONSIBLE FOR WATER MANAGEMENT DURING CONSTRUCTION TO MEET PERMIT REQUIREMENTS. COFFERDAMS SHOWN ON DRAWINGS ARE EXAMPLES
- CHANNEL AND THE OHW INUNDATION BOUNDARY LINES ARE DUE TO DIFFERENT DATA SOURCES AND COLLECTION DATES. SEE GENERAL NOTES 13 AND 14 ON DWG G-02.





FLOODPLAIN PINNED LOGS EXISTING ACCESS ROUTE

SMALL LOG JAM

APEX JAM

LOW FLOW (EXISTING CONDITIONS)

WILLOW TRENCHING

—×— EXISTING CONTOURS

EXISTING WETLANDS

SIDE CHANNEL EXCAVATION AREA

ANTICIPATED FUTURE FLOWPATH


- ORDINARY HIGH WATER
- EXISTING THALWEG ALIGNMENT
- ---- TEMPORARY COFFERDAM

PLOT TIME: 4:04:38 PM

LEGEND LARGE LOG JAM




AF.







/




FILENAME: W3Y00606-C-08 - NFWW PH2 Profiles.dwg



PLOT TIME: 12:28:03 PM





PLOT TIME: 3:27:20 PM



FILENAME: W3Y00606-C-09 - C-11 RESTORATION GRADING PLAN AND PROFILES.dwg









# SECTION NOTES:

- ELEVATIONS.







SMALL LOG JAM				
NUMBER OF STRUCTURES: 4				
MATERIAL	SIZE	ROOT WAD	QUANTITY PER STRUCTURE	TOTAL
TYPE	LENGTH X DIAM / ROCK SIZE DIAM	YES/NO	EA/ CY	EA/CY
LOG TYPE E (EA)	40 X 1.75	YES	3	12
RACKING WOOD (EA)	6-10 X 0.66-0.83	OPTIONAL	15	60
SLASH (CY)	< 10 X < 0.5	NO	8	32
HABITAT BOULDER (EA)	36" - 48"	N/A	6	24
LIVE CUTTING (EA)	N/A	N/A	5	20

1 TYPICAL DETAILS

– MIN EMBEDMENT DEPTH 6 FT MEASURED FROM TOP OF

3






TYPICAL DETAILS

NUME	SER OF STRUCTURES:	14		
MATERIAL	SIZE	ROOT WAD	QUANTITY PER STRUCTURE	TOTAL
ТҮРЕ	LENGTH X DIAM / ROCK SIZE DIAM	YES/NO	EA/CY	EA/CY
LOG TYPE E (EA)	40 X 1.75	YES	6	84
LOG PILE (EA)	20-25 X 1.0 -1.5	NO	9	126
RACKING WOOD (EA)	6-10 X 0.66-0.83	OPTIONAL	30	420
SLASH (CY)	< 10 X < 0.5	NO	16	224
HABITAT BOULDER (EA)	36" - 48"	N/A	12	168
LIVE CUTTING (EA)	N/A	N/A	10	140


LARGE LOG JAM TYPE 2						
NUMB	ER OF STRUCTURES:	4				
MATERIAL	SIZE	ROOT WAD	QUANTITY PER STRUCTURE	TOTAL		
ТҮРЕ	LENGTH X DIAM / ROCK SIZE DIAM	YES/NO	EA/CY	EA/CY		
LOG TYPE E (EA)	40 X 2	YES	6	24		
RACKING WOOD (EA)	6-10 X 0.66-0.83	OPTIONAL	30	120		
SLASH (CY)	< 10 X < 0.5	NO	16	64		
HABITAT BOULDER (EA)	36" - 48"	N/A	12	48		
LIVE CUTTING (EA)	N/A	N/A	10	40		
2 LARGE LOG JAM - TYPE 2 SCHEDULE TABLE						



NOT FOR TH' 2 WALLA RI ED OR ËR ALLA B/ THIS DO Δm NORTH FO 3 Ę RES<sup>-</sup> WAL ៊ី**()** CRAMER FISH SCIENCE LARGE WOOD ARGE LOG JAM AS SHOWN VERIFY SCALE BAR IS ONE INCH ON ORIGINAL DRAWING. MARCH 2024 DATE PROJ W3Y0060 DWG CD-02

18 of 22

SHEET



1


WOOD	


3

APEX JAM						
NUMBER OF STRUCTURES:		5				
MATERIAL	SIZE	ROOT WAD	QUANTITY PER STRUCTURE	TOTAL		
ТҮРЕ	LENGTH X DIAM / ROCK SIZE DIAM	YES/NO	EA/CY	EA/CY		
LOG TYPE F (EA)	25 X 2	NO	1	5		
LOG TYPE B (EA)	25 X 1.75	YES	2	10		
LOG TYPE G (EA)	30 X 2	NO	1	5		
LOG TYPE C (EA)	30 X 1.75	YES	2	10		
LOG TYPE D (EA)	40 X 1.75	YES	2	10		
RACKING WOOD (EA)	6-10 X 0.66-0.83	OPTIONAL	30	150		
SLASH (CY)	< 10 X < 0.5	NO	32	160		
LOG PILE (EA)	20-25 X 1.0 -1.5	NO	16	80		
HABITAT BOULDER (EA)	36" - 48"	N/A	16	80		
LIVE CUTTING (EA)	N/A	N/A	10	50		
APEX JAM SCHEDULE						

TABLE

FLOW






FLOODPLAIN ROUGHNESS - FLOODPLAIN PINNED LOGS 2 NOT TO SCALE

(EA)

2

TYPICAL DETAILS


ERIAL	SIZE	ROOT WAD	QUANTITY PER STRUCTURE	TOTAL QUANTITY		
PE	LENGTH X DIAM / ROCK SIZE DIAM	YES/NO	EA	EA/CY		
E D (EA)	35 X 1.75	YES	1	22		
LE (EA)	15 X 1.0	NO	2	44		
+ (CY)	< 10 X < 0.5	NO	3	66		
TING (EA)	N/A	N/A	2	44		
G WOOD A)	6-10 X 0.66-0.83	OPTIONAL	6	132		
FLOODPLAIN PINNED LOGS SCHEDULE						



NOTFOR


# SITE RESTORATION NOTES:

- 1. UPON COMPLETION OF EARTHWORK AND PLACEMENT OF STRUCTURES, SITE RESTORATION WILL BE COMPLETED IN COMPLIANCE WITH HABITAT IMPROVEMENT PROGRAM (HIP) MEASURES, REFER TO DWGS G-03 THRU G-05. SITE RESTORATION WILL REQUIRE COORDINATION BETWEEN THE CONTRACTOR AND CONTRACTING OFFICER.
- 2. GROUND SURFACES (WITH SOILS) IMPACTED BY PROJECT-RELATED ACTIVITIES WILL BE GRADED TO PROVIDE STABILITY FOR APPROVAL BY CONTRACTION OFFICER. CONTRACTING OFFICER WILL BE RESPONSIBLE FOR SEEDING.
- 3. WHERE ONLY COARSE RIVER COBBLE (LACKING SOILS) IS PRESENT, INSTEAD. CONTRACTOR WILL GRADE TO PRE-PROJECT CONDITIONS.
- 4. TOTAL APPROXIMATE RESTORATION AREA: 3.53 ACRES.



# FOR FLOODPLAIN ROUGHNESS STRUCTURES OR TYPICAL REVEGETATION:

- TIME OF CONSTRUCTION.
- A STINGER IS RECOMMENDED AS SHOWN.
- APART EMBEDDING UP TO 5 FEET OR 6" BELOW WATER TABLE ENCOUNTERED AT TIME OF CONSTRUCTION.
- 4. BACKFILL FLOODPLAIN ROUGHNESS OR BLEND DISTURBED ALLUVIUM.





# FLOODPLAIN ROUGHNESS PLANTING WITH STINGER TARGET EMBEDMENT DEPTH SHOULD ACHIEVE ONE-THIRD LENGTH OF THE LIVE CUTTING CONTACTING GROUND WATER AND NO MORE THAN TWO-THIRDS OF OVERALL LENGTH BURIED - LIVE CUTTING SHALL BE SOAKED IN WATER FOR 24 TO 48 PRIOR TO PLANTING 1. FLOODPLAIN ROUGHNESS WILLOW CUTTING INSTALLATIONS ARE CONTINGENT UPON TEST PIT RESULTS, PER SPECIFICATIONS. THESE RESULTS WILL INFORM WWBWC WHERE THE WATER TABLE IS LOCATED IN RELATION TO FLOODPLAIN ROUGHNESS FEATURES NEAR THE 2. THIS DETAIL PERTAINS TO THE FOLLOWING FLOODPLAIN ROUGHNESS FEATURES- INCLUDING: ROUGHENED GROUND, PINNED LOGS, AND WILLOW TRENCHING. WHERE EXCAVATION AND BACKFILL IS NOT POSSIBLE TO GET CUTTINGS DOWN TO DESIRED DEPTHS, PLANTING WITH 3. FOLLOWING COMPLETION OF THE FLOODPLAIN ROUGHNESS FEATURE, USE STINGER TO PLANT SPECIFIED LIVE CUTTING SPECIES. 1'-3' HABITAT STRUCTURE PLANTING - BACKFILLED GRADE \_\_\_\_\_ \_\_\_\_\_ - KEY PIECE SHOWN FOR REFERENCE (TYP) TEMPORARY EXCAVATED GRADE TO CONSTRUCT HABITAT STRUCTURES TARGET EMBEDMENT DEPTH SHOULD ACHIEVE ONE-THIRD LENGTH OF THE LIVE CUTTING ື ທີ CONTACTING GROUND WATER AND NO MORE THAN TWO-THIRDS OF OVERALL LENGTH BURIED – LIVE CUTTING SHALL BE SOAKED IN WATER FOR 24 TO 48 PRIOR TO PLANTING


PLANTING METHODS


TYPICAL DETAILS

NOT TO SCALE









# NOTES:

PLOT TIME: 2:37:00 PM