Application Name: Couse Creek Confluence Fish Passage Construction

Application Number: 000-0000-16709

By: Walla Walla Basin Watershed Foundation

Offering Type: Open Solicitation

Application Type: Restoration

OWEB Region: No Location Has Been Entered

County: Umatilla

Coordinates: 45.910346,-118.371062

Applicant:

Brian Wolcott 810 S. Main Street Milton Freewater OR 97862-1530 (541) 938-2170 brian.wolcott@wwbwc.org

Payee:

Chris Sheets 810 S. Main Street Milton-Freewater OR 97862 (541) 938-2170 chris.sheets@wwbwc.org

Project Manager:

Brian Wolcott 810 S. Main Street Milton Freewater OR 97862 5419382170 brian.wolcott@wwbwc.org

Budget Summary:

OWEB Amount Requested: \$117,992 Total Project Amount: \$337,066

Administrative Information

Abstract

Provide an abstract statement for the project. Include the following information: 1) Identify the project location; 2) Briefly state the project need; 3) Describe the proposed work; 4) Identify project partners.

Couse Creek is a tributary of the Walla Walla River located 1.5 miles upstream from the town of Milton-Freewater, in Umatilla County. This stream is used by ESA listed summer steelhead and redband trout, and occasionally ESA listed bull trout and reintroduced chinook salmon. There is a fish passage barrier near the confluence of Couse Creek and the Walla Walla River when steelhead are returning to 8 miles of spawning/rearing areas. Couse Creek transitions from a natural bedrock-controlled channel, past an old concrete and riprap pipe protection structure, and then onto the gravel bed of the Walla Walla River. A 3-4 foot, slanted drop exists at this transition point. Steelhead cannot navigate this drop in late winter and early spring when discharges from the Creek are high, and also at low flows in late spring and early summer.

An engineering assessment, survey, and 60% designs have been completed. BPA funds have funded design work with technical support provided by fisheries co-managers. Following a site assessment and an alternatives analysis, a preferred approach was selected. Final designs will be completed this winter. BPA funds have been secured to cover much of the construction project costs; however, OWEB funds are needed to cover the total cost of the project construction. Construction is scheduled for summer of 2019.

The work consists of removal of old concrete structures and riprap from Couse Creek, construction of a new 400-foot- long lower gradient Couse Creek channel that includes roughened riffles and step pools; placement of habitat boulders, and revegetation of one acre with native trees, shrubs, and grasses. Couse Creek was described in the Walla Subbasin Plan, 2004, as a Priority Protection Area, and fish passage barriers are a priority limiting factor. Recent restoration investments in Couse Creek have included fish passage and habitat work. A Couse Creek watershed habitat assessment is underway. Partners include BPA, ODFW and CTUIR.

Location Information

What is the ownership of the project site(s)?

✓ Public land (any lands owned by the Federal government, the State of Oregon, a city, county, district or municipal or public corporation in Oregon)

What agency(ies) are involved?

City of Milton-Freewater

✓ Private (land owned by non-governmental entities)

Please select one of the following Landowner Contact Certification statements:

- I certify that I have informed all participating private landowners involved in the project of the existence of the application, and I have advised all of them that all monitoring information obtained on their property is public record.
- O I certify that contact with all participating private landowners was not possible at the time of application for the following reasons: Furthermore, I understand that should this project be awarded, I will be required by the terms of the OWEB grant agreement to secure cooperative landowner agreements with all participating private landowners prior to expending Board funds on a property.

Please include a complete list of participating private landowners
Vivian Jorgensen

☐This grant will take place in more than one county.
Permits
Other than the land-use form, do you need a permit, license or other regulatory approval of any of the proposed project activities? Yes No For Details Go to Permit Page
Racial and Ethnic Impact Statement
Racial and Ethnic Impact Statement The proposed grant project policies or programs could have a disproportionate or unique POSITIVE impact on the following minority persons. (indicate all that apply) The proposed grant project policies or programs could have a disproportionate or unique NEGATIVE impact on the following minority persons. (indicate all that apply) The proposed grant project policies or programs WILL HAVE NO disproportionate or unique impact on minority persons.
Insurance Information
□ Working with hazardous materials (not including materials used in the normal operation of equipment such as hydraulic fluid) □ Earth moving work around the footprint of a well □ Aerial application of chemicals □ Removal or alteration of structures that hold back water on land or instream including dams, levees, dikes, tidegates and other water control devices (this does not include temporary diversion dams used solely to divert water for irrigation) □ Applicant's staff or volunteers are working with kids related to this project (DAS Risk assessment tool not required, additional insurance is required) □ Applicant's staff are applying herbicides or pesticides (DAS Risk assessment tool not required, additional insurance is required)

Additional Information

☐ This project affects Sage-Grouse.

Problem Statement

Describe the watershed problem(s) that this restoration project seeks to address.

This project addresses fish passage and habitat issues near the mouth of Couse Creek, a tributary to the Walla Walla River. Fish passage barriers and limited connection to floodplain habitat are primary limiting factors in the Walla Walla Basin for ESA listed steelhead and bull trout, and reintroduced spring chinook salmon.

The Walla River at the Couse Creek Confluence is highly constrained, incised, and simplified by the Milton-Freewater levee system and the remnants of an abandoned irrigation ditch. At the northern end of the project site, immediately to the left of the Couse Creek confluence, the Walla Walla River is constrained by an elevated terrace to the west that was built as the old Milton Ditch access road, the remnants of the six-foot-wide Milton Ditch and a six to eight foot tall flood protection berm built out of boulders and river cobbles to protect the Milton Ditch from being washed out by the river in high water events. The design proposes to use a portion of this area for the realigned routing of the Couse Creek and restore the rest to a more naturalized floodplain. Across the Walla Walla River, and also immediately upstream from the Couse Creek confluence are robust flood reduction levees built by the US Army Corps of Engineers in the late 1940s. Channel degradation in the Walla Walla River is an issue and the channel has degraded in areas of the levee system, exposing and undermining the levee toes and requiring levee repairs, and severely limiting channel habitat complexity. By removing the old berm that protected the abandoned Milton Ditch, the River will be able to access the floodplain on its left bank, reducing the degradation to the Walla Walla River bed and proving some opportunity for habitat boulders, pocket water, spawning gravel recruitment, and additional riparian vegetation.

There have been numerous fish habitat and passage restoration projects in the Walla Walla River within the Milton-Freewater Levee system, including at Marie Dorian Park, Zell Diversion, Smith Sill, and Nursery Bridge. Nearby work completed by the Milton-Freewater Water Control District included repairing approximately 500 feet of the levee toe near the Couse Creek Road bridge.

The lower few miles of the Couse Creek channel are straightened and steep. At approximately 150 feet upstream from the mouth the creek is confined to a ten-foot-wide channel up against a bedrock cliff on the left and an historic concrete wall and riprap boulders on the right and a horizontal concrete berm across the creek bed (all built to protect a city water pipe that has since been buried 4 feet below the creek bed). This project will remove the concrete wall, riprap, and concrete berm and install a roughened riffle to maintain a slope and channel much more conducive to fish passage. Below this point the Creek currently pushes through the narrow confines of the abandoned Milton Ditch and the remnants of its riprap push up dam, and then enters the Walla Walla River. The project will route the creek for 200 feet across the restored floodplain where the Milton Ditch and its flood protection berm are removed. The right bank of the abandoned Milton-Freewater ditch will be regraded to remove the push-up berm material used for the ditch and add additional floodplain material near the left bank of the existing Couse Creek near the water line crossing. The newly gained floodplain area will be revegetated with native trees, shrubs, and grasses. Other fish passage and habitat projects in Couse Creek have occurred upstream at the Konen, Shumway/Banks, and Hasso sites. There is an additional partial fish passage barrier located approximately 2.5 miles upstream of this project in Couse Creek. WWBWC staff are working with ODFW and the property owner to develop a solution so this barrier can be fixed in the next year or two.

How have past or current land management practices contributed to the problem?

The Walla Walla Subbasin Plan, completed for the Northwest Power and Conservation Council in 2004, estimates that, under current conditions, roughly 70 percent of the existing riparian corridor is in poor condition for the portion of the Walla Walla River that flows through Oregon. Anthropogenic effects that started prior to 1900 have severely affected the Walla Walla Subbasin, including livestock grazing, timber harvest, intensive agricultural practices, road construction, and stream channelization.

The Milton-Freewater Levee system was constructed in the 1940s and rebuilt between 1966 and 1968 by the USACE, and was recently brought back into USACE and FEMA compliance by the Milton-Freewater Water Control

District. The Milton-Freewater Levee system has been effective at protecting the Milton-Freewater community from flood impacts. However, the levee system and associated infrastructure have also reduced channel complexity, impaired fish passage, reduced floodplain access, and limited riparian vegetation. Lateral connectivity to the historical floodplain is severely limited in the project area. The historical (pre-levee) floodplain of the Walla Walla River is approximately 1,250 feet wide at the confluence and the floodplain of Couse Creek was approximately 400 feet wide above the confluence/alluvial fan. Current floodplain conditions are extremely limited upstream of the Couse Creek Confluence due to the flood levee on both sides of the river. Immediately downstream of the Couse Creek Confluence for approximately 1200 feet, there is only a flood levee on the opposite (right) bank of the river, limiting the floodplain to less than 100 feet.

Much of lower mile and a half of Couse Creek is entrenched about 5-6 feet.

Around 150 feet upstream of the confluence with the Walla Walla River, there is an old concrete berm poured across the creek bed of Couse Creek and a concrete wall and boulder riprap placement installed decades ago alongside Couse Creek on the right bank to protect a municipal water pipe that at the time crossed Couse Creek. These man made structures are a significant contributing factor for the fish passage issue. The pipe has more recently been buried under the creek.

For the last century, the Milton Ditch irrigation water diversion was rebuilt each year across the mouth of Couse creek at the confluence of Couse Creek and the Walla Walla River. This ditch and its push up dam has been abandoned and the irrigators receive their water now from the Little Walla Walla Diversion a mile downstream on the Walla Walla River. However the remnants of a ditch protection berm of imported boulders and piled up river cobbles, and remnants of the boulder push up dam that diverted river flows in to the Milton Ditch contribute to the loss of floodplain habitat and the fish passage problems at this site. The ditch's narrow flood protection berm that runs along the river bank is made of imported boulders and river cobbles and is as tall as eight feet above the creek and ditch and rises abruptly from the river's edge and is as much as 10 feet in height above the river surface. Most of this berm will be removed and the ditch filled in to allow room for a more natural Couse Creek confluence and to re establish the river's floodplain. The levee restriction has resulted in degrading of the Walla Walla River bed and has also impacted the ability of Steelhead to access Couse Creek at lower flows in the latter portion of the adult steelhead migration. Historic clearing of the river channel, construction of the levee, and installing the ditch's flood protection berm limited the establishment of riparian vegetation.

Stream flows in Couse Creek are limited in the summer. The WWBWC habitat assessment includes working with landowners to see if there are water management project opportunities that can lead to protected instream flows at times that are beneficial to steelhead spawning and rearing. Land management and poorly maintained roads in the uplands and floodplains of Couse Creek has contributed to faster runoff, and in some cases erosion gullies, during rain events and snow melts, and higher sediment transport rates in a channelized and entrenched creek channel. The WWBWC habitat assessment project is pursuing opportunities for improvements with willing land and road managers.

The Walla Walla River is 303(d) listed for Temperature. An EPA approved TMDL and WQMP has been completed and identifies the need for additional riparian shade along the leveed reach.

Does this project address one or both of the following:	
✓ Habitat needs for one or more Endangered Species Act-listed species and/or species of the species of the species and the species are species are species and the species are species and the species are species are species and the species are species are species are species are species are species and the species are sp	concern
✓ Concerns identified on 303(d) listed streams	
□No	

Resubmit - Have you submitted, but were not awarded an OWEB application for this project before?

Continuation - Are you requesting funds to continue work on a project previously funded by OWEB where that

Phased - Is proposed work in this application a phase of a comprehensive watershed restoration plan or project?

Project History

O Yes ● No

O Yes

No

O Yes ● No

work did not result in a completed project?

Plans and Salmon
Is the proposed restoration activity(ies) identified in a local assessment or other plan? ● Yes ○ No
Provide name of local plan, Watershed assessment or other locally relevant document. This project is explicitly described in the: Alternatives Analysis and Conceptual Design, Milton-Freewater Levee and Habitat, Walla Walla River, GeoEngineers, 2012.
Couse Creek is described as a Priority Protection area in the Walla Walla Subbasin Plan, Northwest Power and Conservation Council 2004.
Fish passage is described as a priority in the Walla Walla Subbasin Plan, the Middle-Columbia River Steelhead ESA DPS Recovery Plan, NOAA Fisheries 2009, and in the Middle Columbia River Bull Trout Recovery Plan, USFWS 2015.
The Walla Walla Subbasin Stream Temperature TMDL and Water Quality Management Plan, EPA 2005, identifies establishment of healthy riparian areas to provide shade for the Walla Walla River and its tributaries.
The WWBWC Strategic Action Plan identifies Couse Creek Fish Passage.
The WWBWC Annual Work Plan describes the design and implementation of Couse Creek Confluence Fish Passage.
Will this project benefit salmon or steelhead? ● Yes ○ No
How will the resulting restoration project benefit salmon or steelhead or their habitat? This project will provide fish passage for ESA listed steelhead to reach 8 miles of spawning and rearing habitat. This project will provide fish passage for re-introduced spring chinook salmon to reach 8 miles of potential spawning and rearing habitat. There are historical accounts of chinook salmon use in Couse Creek, however it is debatable whether current stream flow conditions would support salmon. This project will provide floodplain

connection, improved riparian shading, and instream habitat improvements in and along the Walla Walla River in a spawning and rearing reach for ESA listed steelhead and for re-introduced spring chinook salmon.

Does the project address a restoration action identified in a regional assessment or recovery plan?



Regional Assessments or Recovery Plans

Middle Columbia River Steelhead Distinct Population Segment ESA Recovery Plan

For each plan chosen above, describe how your project is consistent with specific recovery/restoration actions cited in that plan.

2009 Mid-Columbia Steelhead Recovery Plan, Umatilla/Walla Walla MPG (Major Population Group)

"Restore passage and connectivity to habitats blocked or impaired by artificial barriers." Couse Creek barrier will be removed.

"Restore floodplain connectivity and function." This project will restore just under one acre of floodplain.

"Restore channel structure and complexity." This project will install habitat boulders in the Walla Walla River and step pool structures in Couse Creek.

"Restore riparian condition and LWD recruitment." This project will restore riparian vegetation on just under one acre of floodplain.

Proposed Solution

Goal, Objectives, and Activities

State your project goal. A goal statement should articulate desired outcomes (the vision for desired future conditions) and the watershed benefit.

Restore and enhance fish passage at the Couse Creek Confluence by removing a fish barrier to allow Steelhead adults to move into Couse Creek when seeking 8 miles of spawning and rearing areas. Improve one acre of floodplain connection and riparian vegetation shading along 600 feet of the Walla Walla River immediately downstream of the current Couse Creek confluence. Improve habitat complexity in Couse Creek by installing 8 step pool structures. Improve instream habitat complexity in the Walla Walla River with the placement of 10 habitat boulders. These actions will address primary limiting factors in the Walla Walla Basin.

List specific and measurable objectives. Objectives support and refine the goal by breaking it down into steps for achieving the goal. (NOTE: If you quantify your objectives, ensure all numbers match the metrics listed in your selected habitat types.) Provide up to 7 objectives.

Objective #1

Objective

1. Improve fish passage including by removing the existing cement structures (approximately 150 feet upstream of the mouth) to reduce channel velocities and improve fish passage

Describe the project activities. Activities explain how the objective will be implemented.

An existing concrete wall jutting out from the right bank of Couse Creek and a foot-thick concrete apron poured across about 30 linear feet from bank to bank of the bed of Couse creek will be removed, along with boulder riprap along the right bank. Contractor will remove and dispose of concrete rubble. Boulders will be salvaged for utilization in the construction of the roughened riffle. After the removal of these fish passage barriers, the right bank of Couse Creek will be sloped back creating a more natural channel. A roughened riffle will be installed in Couse Creek to reduce scour potential in the area over the existing buried city water pipe. See Objective 4 for roughened riffle.

Objective #2

Objective

2. Improve habitat in Couse Creek and the Walla Walla River

Describe the project activities. Activities explain how the objective will be implemented.

Eight engineered step pool boulder structures will be installed in the realigned Couse Creek channel providing some needed pool habitat in Couse Creek and opportunities for spawning gravel sorting in pool tail outs. The contractor will build each of the step pool boulder structures out of a total of 237 three foot boulders. Each of the step pool rib structure boulders will be supported by underlying footer boulders. The step pool structure will be u-shaped in plan view, arcing upstream, and there are varying widths, depending on Couse Creek channel width. There will be 4 step boulder ribs comprised of 7 surface boulders, 1 step pool boulder rib comprised of 9 surface boulders, and 3 step pool boulder rib comprised of 10 surface boulders. Each of the step pool ribs will be supported by direct contact with buried footer boulders immediately downstream of each surface boulder. The gradient will strictly follow the designed gradient drop along this 400 foot long section of Couse Creek. The contractor will follow the designed pool depth criteria of 1.5 feet, and drop of 0.5 feet to downstream elevations. Each step pool rib will be trenched 8 foot into banks with additional boulders necessary to key structures into proposed channel banks. See attached Plans.

Ten habitat boulders sized 3-5 foot diameter will be placed in the Walla Walla River to create pocket water in what is currently a long riffle constrained by the municipal flood levee on its right bank and with limited habitat features. The habitat boulders will distributed across the 75 foot wide river channel along a 100 foot length centered on the new Couse Creek Confluence. See attached Plans.

Objective #3

Objective

3. Reroute Couse Creek to increase stream length and reduce channel gradient

Describe the project activities. Activities explain how the objective will be implemented.

Couse Creek will be slightly rerouted to the west through the existing floodplain above the Walla Walla River, which will increase the stream length and channel complexity and reduce the channel slope. Channel gradient will be maintained with the utilization of a 100 foot roughened riffle structure and a series of step pools.

If necessary, fish salvage and water isolation will occur prior to construction following the BPA USFWS and NOAA Fisheries Habitat Improvement Project (HIPIII) Biological Opinion protocols which are spelled out on the design sheets.

Water rerouting and sediment control BMPS will be utilized as necessary to eliminate, or greatly reduce, turbidity in Couse Creek and the Walla Walla River.

After regrading the Milton ditch and ditch flood protection berm, contractor will establish the new Couse Creek alignment and new grades following the design plans and pre construction staking laid out by the TetraTech engineers. This activity will be followed by the placement of the roughened riffle and step pool structures (objectives 2 and 4).

Objective #4

Objective

4. Install roughened riffle to maintain the desired slope and stability of the realigned Couse Creek channel.

Describe the project activities. Activities explain how the objective will be implemented.

Due to the steepness of the confluence and consistent with morphology observed upstream, a step pool morphology with slopes between 2.19 percent and 1 percent is proposed for the channel profile. This designed slope is less than the existing 2.5 percent channel slope upstream and the design will provide fill over the exposed bedrock and clearance above a buried city water pipe. The channel will then transition to lower slopes through the floodplain and will be consistent with the 1 percent to 2.5 percent slopes typically seen for alluvial fan channels. The existing Couse Creek channel will be plugged with an engineered rock placement to simulate a jam-forced avulsion, and the new Couse Creek alignment will utilize a short section of the old abandoned Milton Ditch then will enter the Walla Walla River. Low flows will be maintained within the new channel and overbank flows will be allowed to flow over the top of the added rock and native fill that will be placed at the current mouth of Couse Creek. Boulders will be placed in the roughened riffle to maintain the grade of the riffle and provide hydraulic resting areas and habitat for the fish passage. A roughened riffle is chosen along with the horizontal boulder sills since the roughened riffle can scour and transport bed material while the maintaining the grade via the boulder sills. While Couse Creek within the Project area is a less entrenched system than upstream reaches of the Project, the reach will transport the existing bed material. Therefore, oversized boulder sills are necessary to maintain the grade of the channel through the Project to resist channel bed degradation.

Contractor will utilize 86 3-foot boulders to build the roughened riffle ribs every 20 feet between each step pool rib. Additional smaller sediment comprised of 12 inch cobbles, and smaller riverbed sediment mix of cobbles, gravel, and finer sediments that adhere to engineer specifications will fill the area between the ribs and fill all interstitial spaces. The riffle will be to a two foot depth. Material to be placed and compacted in maximum 10-12 inch lifts and surface washed in with fines until ponding of water is observed. See section 35 49 50 in the specifications For material size and gradation.

Objective #5

Objective

5. Remove remnants of the old Milton Ditch flood protection berm and push up dam to increase floodplain connectivity.

Describe the project activities. Activities explain how the objective will be implemented.

Four hundred feet of the old Milton Ditch flood protection berm will be removed. Much of this boulder and cobble berm rises abruptly from the Walla Walla River as much ten feet in height. Portions of the boulder push up dam will also be removed. Both of these actions will create a more natural floodplain to be graded and planted with native riparian vegetation. Any of the quarry rock encountered will be salvaged and used in the construction of the roughened riffle and habitat structures if the rock meets the proper engineered specifications. This 0.96 acre area will then be regraded into a more natural floodplain following the designs and staking provided by the TetraTech engineers.

Objective #6

Objective

Control and manage invasive species with revegetation of disturbed area using native species.

Describe the project activities. Activities explain how the objective will be implemented.

Nonnative Himalayan blackberries, reed canary grass, and hounds tongue will be mechanically removed. The reestablished floodplain area will be revegetated with native trees, shrubs, and grasses following the attached Planting plan. Any additional disturbed areas will be regraded and revegetated with native plantings. Plantings will include the following native tree, shrub, and grass species: alder, black cottonwood, ponderosa pine, douglas fir, coyote willow, red osier dogwood, black hawthorn, lewis mock orange, pacificninebark, chokecherry, snowberry, rocky mountain maple, nootka rose, wildrye, idaho fescue, tufted hairgrass, blue wildrye, bluebunch wheatgrass, mountain brome.

Plantings will occur in October through December following construction.

List the major project activities and time schedule for each, including post project implementation.

Designs will be finalized from their current 60% status A comment and review meeting to review of the	Element	Description	Start Date	End Date
current 60% status or current 60% status. There will be a commetted are deview meeting to review of 50% comments received. These 90% designs will be created informed by comments and discussion with review agencies (ODEW, CTUR, NOAR, USFWS, CORP). There will be a comment and review meeting to review of 50% comments and concerned and review meeting to review of 50% comments received. Designs will be finalized with potential final adjustments based on agencies input. Permitting Permitting and authorizations for construction staking of the secured. Permitting and authorizations for construction staking of the secured. Permitting and authorizations for construction staking of the secured. Mobilize to site and conduct site preparation. Addition of the secured controls. Select Construction contractor Controls. Select Construction contractor Select Construction contractor Select Construction contractor Select Construction contractor Select Construction contractor will be selected using a competitive bid process that will not controls. Select Construction contractor will be selected using a competitive bid process that will not controls. Select Construction contractor will be selected using a competitive bid process that will not controls. Install and monitor temporary erasion and seldment controls. Install and monitor temporary erasion and seldment controls. Install work area isolation and dewater work areas Construct channel and floodplain below Ordinary High Were Install work area isolation and floodplain below Ordinary High Were Install troughened riffle and wash in fines Perwarb work areas and pump turbid water to an approved location and monitor for no turbid returns to the stream. Slowly reintroduce flow to the work areas, amontoning for turbidity and work areas and pump turbid water to an approved location and monitor for no turbid returns to the s		-		
comments and review meeting to review of 60% comments are review. The 90% designs will be created informed by comments and discussion with review agencies (ODPW, CTUIR, NOAA, USFWS, CORP). There will be a comment and review meeting to review agencies (ODPW, CTUIR, NOAA, USFWS, CORP). There will be a comment and review meeting to review agencies reput. Permitting of white the properties of the properties	ŭ .		10/2010	2/2013
designs will be created informed by comments and discussion with review agencies (OFW, CTUIR, NOAA, USFWS, Corps). There will be occurred to the comment and review meeting to review controls. Permitting P	Current 00 /0 Status			
designs will be created informed by comments and discussion with review agencies (OPFW, CTUIR, NOAA, USFWS, Corps). There will be a comment and review meeting to review 90% comments are received. Designs will be comment and review meeting to review 90% comments are received. Designs will be a comment and review meeting to review 90% comments received. Designs will be sourced. Permitting Permitting administrations of the first potential final administrations of construction staking of sensitive areas, contractor submittals etc. Mobilizes to site and conduct site proparation. Install emporary arosion and sediment controls. Select Construction confractor Construction confractor Construction confractor Construction confractor Construction confractor Submittals etc. Construction confractor William and the controls. Select Construction confractor Construction controls. Construction confractor Submittals etc. Construct channel and floodplain below Ordinary High Water Install block nets and salvage fish following HIP III Bloological Opinion protocols that are described in the design. Install and monitor temporary etc. Install and monitor temporary etc. Install and monitor temporary etc. Confidency				
agencies (ODP, CTUIR, NOA, A USFWS, Corps). There will be a comment and releview meeling for review 90% comments are received. Designs will be a comment and review meeling for review 90% comments and review meeling for review 90% comments and review meeling for review 90% comments are received. Designs will be form to struction attaking of the permitting and authorizations for construction staking. Regigning of sensitive areas, contractor submittable at the construction staking. The permitting of sensitive areas, contractor submittable at the properties of the pro				
Second Construction contractor Construction Construction Construction Construction Construction Construction Construction Construction Construction Cons				
Description of received and section and section and section control or section and secti				
Comment and review meeting to review Section Complete as built survey. Complete as default survey. Complete as built survey.		,		
Permitting Permitting Permitting and authorizations for constructions taked on agencies input. Permitting adjustments based on agencies input. 10/2018 5/2019 5/		1		
be finalized with potential final adjustments based on agendeic input. Permitting Permitting and authorizations for construction will be secured. Construction staking Perform construction will be secured. Mobilize to site and conduct site preparation. Install temporary erosion and sediment controls. Select Construction contractor Construction contractor Select Construction contractor Select Construction contractor Select Construction contractor Select Construction contractor Construction contractor Construction contractor Select Construct select sele		· ·		
Permitting Permitting and authorizations for construction staking Permitting and authorizations for construction staking Perform construction staking, flagging of sensitive areas, contractor submittals etc. Perform construction staking Perform construction staking, flagging of sensitive areas, contractor submittals etc. Perform construction staking of sensitive areas, contractor submittals etc. Perparation. Perform construction staking of sensitive areas, contractor submittals etc. Perparation. Perform contractor Perparation. Perform contractor will be selected using a competitive bid process that will include an RFP, site four, and review of bids with project partners. Perform contractor will be selected to bids with project partners. Perform contractor will be selected to bids with project partners. Perform contractor will be selected to bids with project partners. Perform contractor will be selected to bids with project partners. Perform contractor will be selected to bids with project partners. Perform contractor will be selected to bids with project partners. Perform contractor will be selected to bids with project partners. Perform contractor will be selected to bids with project partners. Perform contractor will be selected to bids with project partners. Perform contractor will be selected to bids with project partners. Perform contractor will be selected to bids with project partners. Perform contractor will be selected to bids with project partners. Perform contractor will be selected to bids with project partners. Perform contractor will be selected to bids with project partners. Perform contractor will be selected to bids with project partners. Perform contractor will be selected to bids with project partners. Perform contractor will be selected to				
Permitting and authorizations for construction staking construction staking and authorizations for construction staking and authorizations for construction staking and secured. Perform construction staking, flagging of sensitive areas, contractor submittals etc Mobilize to site and conduct site preparation. Install temporary erosion and sediment controls. Install temporary erosion and sediment controls. Select Construction contractor Construction contractor Construction contractor will be selected using a competitive bid process that will include an RPR, site tour, and review of bids with project partners. Site grading Excavate channel and floodplain above Cordinary High Water Install block nets and salvage fish following High III Biological Opinion protocols that are described in the design. Install and monitor temporary erosion and sediment controls. Install and monitor temporary erosion and sediment controls. Install roughened riffle Install roughened riffle Install roughened riffle and wash in fines Prewash work areas and pump turbid water to an approved location and monitor for no turbid returns to the stream Slowly reinroduce flow to the work areas, monitoring for turbidity areas, monitoring for turbidity areas, monitoring for turbidity areas, monitoring or for turbidity areas, monitoring or Remove work area isolation. Premovab work areas and temporary erosion and sediment controls Install work areas and pump turbid water to an approved location and monitor for no turbid returns to the stream Slowly reinroduce flow to the work areas, monitoring for turbidity Remove block nets, 71/2019 to 930/2019 Remove block nets, 71/2019 to 930/2019 Remove block nets, 71/2019 to 930/2019 Remove temporary erosion and sediment problem and demobilization on the prob		· ·		
Construction staking Perform construction staking, flagging of sensitive areas, contractor submittate etc Wolfilze to site and conduct site preparation. Mobilize to site and conduct site preparation. Install temporary erosion and sediment controls. Selient Construction contractor Selient Construction contractor Construction contractor will be selected using a competitive bid process that will include an RFP, site tour, and review of bids with project partners. Site grading Excavate channel and floodplain above containly likely water controls. Install block nets and salvage fish floodwight likely likely water controls. Install and monitor temporary erosion and sediment controls Install and monitor temporary erosion and sediment controls. Install work area isolation and dewater work areas Construct channel and floodplain below Condiany High Water Containy High Water Containy High Water Construct channel and floodplain below Condiany High Water Construct channel and floodplain below Construct channel and floodplain below Condiany High Water Construct channel and floodplain below Construct channel and floodplain below Condiany High Water Construct channel and floodplain below Condiany High Water Construct channel and floodplain below Construct channel and floodplain below Condiany High Water Construct channel and floodplain below Construct channel and floodplain below Condiany High Water Construct channel and floodplain below Construct channel and floodplain below Condiany High Water Cons	Describing.		40/0040	5/0040
construction staking of sensitive areas, contractor submittals etc of sensitive areas, monitoring for turbidity reintoduce flow to the work areas and pump turbid water submit and sediment controls. Select Construct channel and floodplain below of submitted teams and selected provided and sediment controls. Install and monitor temporary erosion and sediment controls. Install work area solation and dewater work areas and pump turbid water to an approved location and monitor for no turbid returns to the stream Slowly reintroduce flow to the work areas, monitoring for furbidity erosion controls. Remove block nets and temporary erosion and sediment controls. Remove block nets and temporary erosion and sending for turbidity areas, monitoring for furbidity erosion controls. Remove block nets and temporary erosion and sediment controls. Slowly reintroduce flow to the work areas, monitoring for furbidity erosion controls. Remove block nets and temporary erosion and sediment controls. Remove block nets and temporary erosion and sediment controls. Remove block nets and temporary erosion and sediment controls. Remove block nets and temporary erosion and sediment controls. Remove block nets and temporary erosion and sediment controls. Remove block nets and temporary erosion and sediment controls. Remove block nets and temporary erosion and sediment controls. Remove block nets and temporary erosion and sediment controls. Remove block nets and temporary erosion and sediment controls. Remove block nets and temporary erosion and sediment controls. Remove blo	Permitting		10/2018	5/2019
Second			0/0040	0/0040
Mobilize to site and conduct site preparation. Install temporary erosion and sediment controls. Select Construction contractor List grading Excavate channel and floodplain below of Continuation work area is lolation and sediment controls. Install block nets and salvage fish following reforescent and sediment controls work areas and pump turbid water to an approved location and monitor for no turbid returns to the stream List grading Excavate channel and floodplain ablow of Cordinary High Water Install block nets and salvage fish following high Water Install work area is collation and dewater work areas and pump turbid water to an approved location and monitor for no turbid returns to the stream Excavate work areas and monitor for no turbid returns to the stream Remove block nets and temporary erosion and sediment controls Remove block nets and emporary erosion and sediment for ontrols Remove block nets and temporary erosion and sediment controls Remove block nets and emporary erosion and sediment controls Remove block nets and temporary erosion and sediment controls Select and monitor temporary erosion and sediment controls Remove block nets and temporary Remove temporary erosion and sediment controls Select and monitor temporary erosion and sediment controls Remove block nets and temporary Remove temporary erosion and sediment controls Select and much all disturbed areas	construction staking		6/2019	6/2019
Mobilize to site and conduct site preparation. Install temporary erosion and sediment controls. Select Construction contractor Construction contractor will be selected suing a competitive bid process that will include an RFP, site tour, and review of bids with project patheres. Site grading Excavate channel and floodplain above Ordinary High Water Install block nets and salvage fish Install and monitor temporary erosion and sediment controls. Install and monitor temporary erosion and sediment controls. Install work area isolation and dewater work areas and pump turbid water to an approved location and monitor for no turbid returns to the stream Slowly reintroduce flow to the work areas, monitoring for turbidity and sediment controls Remove block nets and selment controls Site of an an approved to cation and dewater work areas, monitoring for furbidity areas, monitoring for turbidity areas, monitoring for		·		
Install temporary erosion and sediment controls. Construction contractor will be selected using a competitive bid process that will include an RFP, site tour, and review of bids with project partners.			0.0010	0/0040
Install temporary erosion and sediment controls. Select Construction contractor Construct channel and floodplain above obesign. Install and monitor temporary erosion and sediment controls Install and monitor temporary erosion and sediment controls Install and monitor temporary erosion and sediment controls Install work area isolation and devater work areas Construct channel and floodplain below Ordinary High Water Install roughened riffle Install roughened riffle and wash in fines Prewash work areas and pump turbid water to an approved location and monitor for no turbid returns to the stream Slowly reintroduce flow to the work areas, monitoring for turbidity Remove block nets and temporary erosion and sediment controls Complete as built survey. Compl			6/2019	6/2019
controls. Select Construction contractor Select Construct Construct Controls Select Controls Select Construct Controls Select Control Select Control Select Select Control Select S	' '			
Select Construction contractor Construction contractor will be selected using a competitive bid process that will include an RFP, site toru, and review of bids with project partners. Site grading Excavate channel and floodplain above Ordinary High Water Install block nets and salvage fish following HIP III Biological Opinion protocols that are described in the design. Install and monitor temporary erosion and sediment controls Install and monitor temporary erosion and sediment controls. Install work area isolation and dewater work areas Ordinary High Water Install roughened riffle Install roughened riffle Install roughened riffle Slowly reintroduce flow to the work areas, monitoring for turbidity Remove block nets and temporary erosion and sediment controls Prewash mork areas and pump turbid water to an approved location and monitor for no turbid returns to the stream Slowly reintroduce flow to the work areas, monitoring for turbidity Remove block nets and temporary erosion and sediment controls Complete as built survey. Complete as built survey. Complete as built survey. Complete as built survey. Seed and mulch all disturbed areas Site of grading and monitor temporary erosion and demobilization Did you provided or survival and provided mand monitor for no turbid returns are an expension and sediment controls Seed and mulch all disturbed areas Site clean-up and demobilization Construct channel and floodplain below ord and monitor for no turbid returns to the stream Slowly reintroduce flow to the work areas and pump turbid water to an approved location and monitor for no turbid returns to the stream Slowly reintroduce flow to the work areas isolation. 7/1/2019 to 9/30/2019 Remove work areas isolation. 7/1/2019 to 9/30/2019 Remove block nets. 7/1/2019 to 9/30/2019 Remove block			6/2019	6/2019
using a competitive bid process that will include an RFP, site tour, and review of bids with project partners. site grading Excavate channel and floodplain above Ordinary High Water Install block nets and salvage fish following HIP III Biological Opinion protocols that are described in the design. Install and monitor temporary erosion and sediment controls Install and monitor temporary erosion and sediment controls Install work area isolation and dewater work areas Construct channel and floodplain below Ordinary High Water Install roughened riffle Install roughened riffle Install roughened riffle in the design. Prewash work areas and pump turbid water to an approved location and monitor for no turbid returns to the stream Stowly reintroduce flow to the work areas, monitoring for turbidity Remove block nets and temporary erosion and sediment controls Remove block nets and temporary erosion and monitor for no turbid and sediment controls Prewash work areas and pump turbid y areas, monitoring for turbidity Remove block nets and temporary erosion and sediment controls Stowly reintroduce flow to the work areas isolation. 7/1/2019 to 9/30/2019 Remove work areas isolation. 7/1/2019 to 9/30/2019 Remove block nets. 7/1/2019 to 9/30/2019 Remove temporary erosion and sediment controls Complete as built survey. C				
Include an RFP, site tour, and review of bids with project partners. Site grading Excavate channel and floodplain above Ordinary High Water Install block nets and salvage fish following HIP III Bidological Opinion protocols that are described in the design. Install and monitor temporary erosion and sediment controls Install work area isolation and dewater work areas work areas Construct channel and floodplain below Ordinary High Water Install roughened riffle Install roughened riffle and wash in fines Prewash work areas and pump turbid water to an approved location and monitor for no turbid returns to the stream Slowly reintroduce flow to the work areas, monitoring for turbidity Remove block nets and temporary erosion and sediment controls Complete as built survey. Complete as built survey. Install cough and representation and demobilization File and the project partners. 6/2019 7/2019 7/2019 7/2019 7/2019 7/2019 7/2019 7/2019 7/2019 7/2019 7/2019 7/2019 7/2019 7/2019 7/2019 7/2019 7/2019 7/2019 8/	Select Construction contractor		5/2019	5/2019
Site grading Excavate channel and floodplain above ordinary High Water Install block nets and salvage fish following HIP III Biological Opinion protocols that are described in the design. T/2019 T/201		1 -		
Site grading Excavate channel and floodplain above Ordinary High Water Install block nets and salvage fish following HIP III Biological Opinion protocols that are described in the design. T/2019 T/201		' '		
Install block nets and salvage fish following HIP III Biological Opinion protocols that are described in the design. Install and monitor temporary erosion and sediment controls Install and monitor temporary erosion and sediment controls Install work area isolation and dewater work areas Ordinary High Water Install roughened riffle Install roughened riffle Install roughened riffle and wash in fines Prewash work areas and pump turbid water to an approved location and monitor for no turbid returns to the stream Slowly reintroduce flow to the work areas, monitoring for turbidity erosion controls Premove block nets and temporary erosion controls Complete as built survey. Ordinary High Water Complete as built survey. Ordinary High Water Install roughened riffle and wash in fines Prewash work areas and pump turbid water to an approved location and monitor for no turbid returns to the stream Slowly reintroduce flow to the work areas, monitoring for turbidity erosion controls Complete as built survey. Ordinary High Water Install work area isolation and dewater work area isolation and monitor for no turbid returns to the stream Complete as built survey. Ordinary High Water Install work areas and pump turbid water to an approved location and monitor for no turbid returns to the stream Slowly reintroduce flow to the work areas, monitoring for turbidity Remove block nets. 7/1/2019 to 9/30/2019 Remove temporary erosion and sediment controls Complete as built survey. Ordinary High Water Install work area isolation ond dewater work area isolation and monitor for surbidity areas. Install work area isolation and water work area isolation. 7/1/2019 to 9/30/2019 Remove temporary erosion and sediment controls Ordinary High Water Install work area isolation and dewater work area isolation. 7/1/2019 to 9/30/2019 Remove temporary erosion and sediment controls Install work area isolation and water work area isolation. 7/1/2019 to 9/30/2019 Install work areas and pump turbid water to an approved locatio		1 1 1		
Install block nets and salvage fish following HIP III Biological Opinion protocols that are described in the design. Install and monitor temporary erosion and sediment controls Install work area isolation and dewater work areas Construct channel and floodplain below Ordinary High Water Install roughened riffle and wash in fines Install roughened riffle and was	site grading	· ·	6/2019	7/2019
following HIP III Biological Opinion protocols that are described in the design. Install and monitor temporary erosion and sediment controls Install work area isolation and dewater work areas and pump turbid water to an approved location and monitor for no turbid returns to the stream Slowly reintroduce flow to the work areas, monitoring for turbidity Remove block nets and temporary erosion and ese diment controls Formplete as built survey. Complete as built survey. Formplete as built survey. Formplete as built survey. Formplete as built survey. Final monitor temporary erosion and sediment controls. Install roughened riffle and wash in fines Frewash work areas and pump turbid water to an approved location and monitor for no turbid returns to the stream Slowly reintroduce flow to the work areas, monitoring for turbidity Remove block nets and temporary erosion and sediment controls Site clean-up and demobilization Following HIP III Biological Opinion protocols that are described in the design and sediment controls water to sologist and monitor temporary erosion and sediment controls Formplete as built survey. Formplete		, ,		
protocols that are described in the design. Install and monitor temporary erosion and sediment controls and sediment controls and sediment controls and sediment controls and sediment controls. Install work area isolation and dewater work areas as old the protocol of t	Install block nets and salvage fish	<u> </u>	7/2019	7/2019
Install and monitor temporary erosion and sediment controls Install work area isolation and dewater work areas and pump turbid water to an approved location and monitor for no turbid returns to the stream Slowly reintroduce flow to the work areas, monitoring for turbidity erosion controls Remove block nets and temporary erosion and sediment controls Remove block nets and temporary erosion and sediment controls Seed and mulch all disturbed areas Siec clean-up and demobilization Install and monitor temporary erosion and sediment controls Install and monitor temporary erosion and sediment controls Install and monitor temporary erosion and sediment controls Install work area isolation and dewater V7/2019 V7		following HIP III Biological Opinion		
Install and monitor temporary erosion and sediment controls Install work area isolation and dewater work areas Construct channel and floodplain below Ordinary High Water Install roughened riffle Install roughened riffle and wash in fines Prewash work areas and pump turbid water to an approved location and monitor for no turbid returns to the stream Slowly reintroduce flow to the work areas, monitoring for turbidity Remove block nets and temporary erosion and sediment controls Complete as built survey. Complete as built survey. Install and monitor temporary erosion and dewater work area isolation. The properties of the survey. Install monitor temporary erosion and dewater work area isolation and dewater work area. 7/2019 7/2019 8/2019 8/2019 7/2019 8/2019		'		
and sediment controls Install work area isolation and dewater work areas Install roughened and floodplain below Ordinary High Water Install roughened riffle Install roughened riffle Install roughened riffle and wash in fines Install roughened riffle and wash i		-		
Install work area isolation and dewater work areas Construct channel and floodplain below Ordinary High Water Install roughened riffle and wash in fines Install roughened riffle Install roughened riffle and wash in fines Install roughened riffle Install roughened riffle and wash in fines Install roughened riffle Install roughened riffle and wash in fines Install roughened riffle Install roug	Install and monitor temporary erosion	Install and monitor temporary erosion	7/2019	7/2019
work areas work areas 8/2019 Construct channel and floodplain below Ordinary High Water Construct channel and floodplain below Ordinary High Water 8/2019 8/2019 Install roughened riffle Install roughened riffle and wash in fines 8/2019 8/2019 Prewash work areas and pump turbid water to an approved location and monitor for no turbid returns to the stream Prewash work areas and pump turbid water to an approved location and monitor for no turbid returns to the stream 8/2019 8/2019 Slowly reintroduce flow to the work areas, monitoring for turbidity areas, monitoring for turbidity 8/2019 8/2019 Remove block nets and temporary erosion controls Remove work area isolation. 7/1/2019 to 9/30/2019 8/2019 8/2019 Remove temporary erosion and sediment controls Remove temporary erosion and sediment controls 9/2019 9/2019 Complete as built survey. Complete as built survey. 9/2019 9/2019 Seed and mulch all disturbed areas Seed and mulch all disturbed areas 10/2019 10/2019	and sediment controls	and sediment controls.		
Construct channel and floodplain below Ordinary High Water Install roughened riffle and wash in fines Prewash work areas and pump turbid water to an approved location and monitor for no turbid returns to the stream Slowly reintroduce flow to the work areas, monitoring for turbidity Remove block nets and temporary erosion controls Pemove block nets. 7/1/2019 to 9/30/2019 Remove temporary erosion and sediment controls Complete as built survey. Complete as built survey. Complete as built survey. Complete as built survey. Site clean-up and demobilization Construct channel and floodplain below Ordinary High Water Install roughened riffle and wash in fines 8/2019	Install work area isolation and dewater	Install work area isolation and dewater	7/2019	7/2019
Ordinary High Water Ordinary High Water Macked Install roughened riffle Install roughened riffle Install roughened riffle and wash in fines 8/2019 Prewash work areas and pump turbid water to an approved location and monitor for no turbid returns to the stream Prewash work areas and pump turbid water to an approved location and monitor for no turbid returns to the stream 7/2019 8/2019 Slowly reintroduce flow to the work areas, monitoring for turbidity Slowly reintroduce flow to the work area, monitoring for turbidity 8/2019 8/2019 Remove block nets and temporary erosion controls Remove block nets. 7/1/2019 to 9/30/2019 Remove block nets. 7/1/2019 to 9/30/2019 Remove become temporary erosion and sediment controls 8/2019 8/2019 Complete as built survey. Complete as built survey. 9/2019 9/2019 Seed and mulch all disturbed areas Seed and mulch all disturbed areas 10/2019 10/2019 Site clean-up and demobilization Site clean-up and demobilization 10/2019 10/2019	work areas	work areas		
Install roughened riffle Install roughened riffle and wash in fines Prewash work areas and pump turbid water to an approved location and monitor for no turbid returns to the stream Slowly reintroduce flow to the work areas, monitoring for turbidity Remove block nets and temporary erosion controls Pemove temporary erosion and sediment controls Complete as built survey. Install roughened riffle and wash in fines 8/2019	Construct channel and floodplain below	Construct channel and floodplain below	8/2019	8/2019
Fines Prewash work areas and pump turbid water to an approved location and monitor for no turbid returns to the stream Slowly reintroduce flow to the work areas, monitoring for turbidity Remove block nets and temporary erosion controls Prewash work areas and pump turbid water to an approved location and monitor for no turbid returns to the stream Slowly reintroduce flow to the work areas, monitoring for turbidity Remove block nets and temporary erosion and sediment controls Complete as built survey. Seed and mulch all disturbed areas Frewash work areas and pump turbid water to an approved location and monitor for no turbid returns to the stream 8/2019	Ordinary High Water	Ordinary High Water		
Prewash work areas and pump turbid water to an approved location and monitor for no turbid returns to the stream Slowly reintroduce flow to the work areas, monitoring for turbidity Remove block nets and temporary erosion controls Complete as built survey. Complete as built survey. Prewash work areas and pump turbid water to an approved location and monitor for no turbid returns to the stream Slowly reintroduce flow to the work area, monitoring for turbidity Remove work area isolation. 7/1/2019 to 9/30/2019 Remove block nets. 7/1/2019 to 9/30/2019 Remove temporary erosion and sediment controls Complete as built survey. Complete as built survey. Seed and mulch all disturbed areas Site clean-up and demobilization Prewash work areas and pump turbid water to an approved location and monitor for no turbid returns to the stream 7/2019 8/2019	Install roughened riffle	Install roughened riffle and wash in	8/2019	8/2019
water to an approved location and monitor for no turbid returns to the stream Slowly reintroduce flow to the work areas, monitoring for turbidity Remove block nets and temporary erosion controls Complete as built survey. Complete as built survey. Seed and mulch all disturbed areas Water to an approved location and monitor for no turbid returns to the stream water to an approved location and monitor for no turbid returns to the stream Slowly reintroduce flow to the work area isolation to the work areas, monitoring for turbidity Remove work area isolation. 7/1/2019 to 9/30/2019 Remove block nets. 7/1/2019 to 9/30/2019 Remove temporary erosion and sediment controls Complete as built survey. Seed and mulch all disturbed areas Seed and mulch all disturbed areas Site clean-up and demobilization Water to an approved location and monitor for no turbid returns to the stream 8/2019 8/2019 8/2019 8/2019 8/2019 8/2019 8/2019 8/2019 8/2019 9/2019 9/2019 Site clean-up and demobilization Site clean-up and demobilization Water to an approved location and monitor for no turbid returns to the stream 8/2019		fines		
monitor for no turbid returns to the stream Slowly reintroduce flow to the work areas, monitoring for turbidity Remove block nets and temporary erosion controls Complete as built survey. Seed and mulch all disturbed areas Slowly reintroduce flow to the work atea isolation. 7/1/2019 to 9/30/2019 Site clean-up and demobilization Slowly reintroduce flow to the work atea isolation to turbidity 8/2019	Prewash work areas and pump turbid	Prewash work areas and pump turbid	7/2019	8/2019
streamstreamSlowly reintroduce flow to the work areas, monitoring for turbiditySlowly reintroduce flow to the work areas, monitoring for turbidity8/20198/2019Remove block nets and temporary erosion controlsRemove work area isolation. 7/1/2019 to 9/30/2019 Remove block nets. 7/1/2019 to 9/30/2019 Remove temporary erosion and sediment controls8/20198/2019Complete as built survey.Complete as built survey.9/20199/2019Seed and mulch all disturbed areasSeed and mulch all disturbed areas10/201910/2019Site clean-up and demobilizationSite clean-up and demobilization10/201910/2019	1			
Slowly reintroduce flow to the work areas, monitoring for turbidity Remove block nets and temporary erosion controls Complete as built survey. Slowly reintroduce flow to the work area isolation. 7/1/2019 to 9/30/2019 Remove work area isolation. 7/1/2019 to 9/30/2019 Remove block nets. 7/1/2019 to 9/30/2019 Remove temporary erosion and sediment controls Complete as built survey. Seed and mulch all disturbed areas Seed and mulch all disturbed areas Site clean-up and demobilization Site clean-up and demobilization Siowly reintroduce flow to the work area isolation to the work area isolation. 7/1/2019 8/2019	monitor for no turbid returns to the	monitor for no turbid returns to the		
areas, monitoring for turbidity Remove block nets and temporary erosion controls Complete as built survey. Seed and mulch all disturbed areas Site clean-up and demobilization Remove work area isolation. 7/1/2019 8/2019	stream	stream		
Remove block nets and temporary erosion controls Remove block nets. 7/1/2019 to 9/30/2019 Remove block nets. 7/1/2019 to 9/30/2019 Remove temporary erosion and sediment controls Complete as built survey. Complete as built survey. Seed and mulch all disturbed areas Seed and mulch all disturbed areas Site clean-up and demobilization Remove work area isolation. 7/1/2019 8/2019 8/2019 8/2019 8/2019 8/2019 10/2019 10/2019	Slowly reintroduce flow to the work	Slowly reintroduce flow to the work	8/2019	8/2019
erosion controls to 9/30/2019 Remove block nets. 7/1/2019 to 9/30/2019 Remove temporary erosion and sediment controls Complete as built survey. Complete as built survey. Seed and mulch all disturbed areas Seed and mulch all disturbed areas Site clean-up and demobilization to 9/30/2019 to 9/30/2019 9/2019 9/2019 10/2019 10/2019	areas, monitoring for turbidity			
Remove block nets. 7/1/2019 to 9/30/2019 Remove temporary erosion and sediment controls Complete as built survey. Complete as built survey. Seed and mulch all disturbed areas Seed and mulch all disturbed areas Site clean-up and demobilization Remove block nets. 7/1/2019 to 9/3019 Site clean-up and demobilization Site clean-up and demobilization Site clean-up and demobilization Remove block nets. 7/1/2019 to 9/3019 Site clean-up and demobilization	Remove block nets and temporary	Remove work area isolation. 7/1/2019	8/2019	8/2019
9/30/2019 Remove temporary erosion and sediment controls Complete as built survey. Complete as built survey. Seed and mulch all disturbed areas Seed and mulch all disturbed areas Site clean-up and demobilization Site clean-up and demobilization 9/2019 9/2019 10/2019 10/2019	erosion controls	to 9/30/2019		
Remove temporary erosion and sediment controls Complete as built survey. Complete as built survey. Seed and mulch all disturbed areas Seed and mulch all disturbed areas Site clean-up and demobilization Remove temporary erosion and sediment controls 9/2019 9/2019 10/2019 10/2019		Remove block nets. 7/1/2019 to		
sediment controlsSediment controlsComplete as built survey.Complete as built survey.9/20199/2019Seed and mulch all disturbed areasSeed and mulch all disturbed areas10/201910/2019Site clean-up and demobilizationSite clean-up and demobilization10/201910/2019		9/30/2019		
Complete as built survey.Complete as built survey.9/20199/2019Seed and mulch all disturbed areasSeed and mulch all disturbed areas10/201910/2019Site clean-up and demobilizationSite clean-up and demobilization10/201910/2019		Remove temporary erosion and		
Seed and mulch all disturbed areas Seed and mulch all disturbed areas 10/2019 10/2019 Site clean-up and demobilization Site clean-up and demobilization 10/2019 10/2019		sediment controls		
Site clean-up and demobilization Site clean-up and demobilization 10/2019 10/2019	Complete as built survey.	Complete as built survey.	9/2019	9/2019
	Seed and mulch all disturbed areas	Seed and mulch all disturbed areas	10/2019	10/2019
Plant trees and shrubs in the fall.	Site clean-up and demobilization	Site clean-up and demobilization	10/2019	10/2019
	Plant trees and shrubs in the fall.	Plant trees and shrubs in the fall.	11/2019	12/2019

Element	Q4 2018	Q1 2019	Q2 2019	Q3 2019	Q4 2019
Designs will be finalized from their					
current 60% status					
Permitting					
construction staking					

reparation. Install temporary erosion and sediment controls. Install temporary erosion and sediment controls. It is grading Install block nets and salvage fish Install and monitor temporary erosion Ind sediment controls Install work area isolation and dewater Install work area isolation and dewater Install repart of the sediment controls Install repart of the sediment controls Install work area isolation and dewater Install repart of the sediment controls Install repart of the s				
Install temporary erosion and sediment ontrols. Install temporary erosion and sediment ontrols. Install for grading file	Mobilize to site and conduct site			
ontrols. idelect Construction contractor its grading install block nets and salvage fish install and monitor temporary erosion and sediment controls install work area isolation and dewater work areas construct channel and floodplain below prolinary High Water install roughened riffle rewash work areas and pump turbid water to an approved location and inonitor for no turbid returns to the tream liowly reintroduce flow to the work reas, monitoring for turbidity temove block nets and temporary rosion controls complete as built survey. ieed and mulch all disturbed areas ifite clean-up and demobilization	preparation.			
ite grading stall block nets and salvage fish stall and monitor temporary erosion not sediment controls stall work area isolation and dewater work areas construct channel and floodplain below ordinary High Water stall roughened riffle rewash work areas and pump turbid varietr to an approved location and nonitor for no turbid returns to the tream slowly reintroduce flow to the work reas, monitoring for turbidity temove block nets and temporary rosion controls complete as built survey. seed and mulch all disturbed areas side clean-up and demobilization	Install temporary erosion and sediment			
ite grading stall block nets and salvage fish stall and monitor temporary erosion and sediment controls stall work area isolation and dewater work areas construct channel and floodplain below bridinary High Water stall roughened riffle rewash work areas and pump turbid vater to an approved location and nonitor for no turbid returns to the tream slowly reintroduce flow to the work reas, monitoring for turbidity temporary rosion controls complete as built survey.	controls.			
Install block nets and salvage fish Install and monitor temporary erosion and sediment controls Install work area isolation and dewater work areas Isolation and dewater work areas Isolation and floodplain below ordinary High Water Install roughened riffle Installation ro	Select Construction contractor			
Install and monitor temporary erosion and sediment controls anstall work area isolation and dewater vork areas and pump turbid vater to an approved location and and anonitor for no turbid returns to the stream slowly reintroduce flow to the work areas, monitoring for turbidity erosion controls and temporary rosion controls complete as built survey.	site grading			
Indicated in the sediment controls Install work area isolation and dewater Vork areas Install work areas Install roughened riffle Install roughene	Install block nets and salvage fish			
Install work area isolation and dewater work areas Construct channel and floodplain below ordinary High Water Install roughened riffle Prewash work areas and pump turbid water to an approved location and monitor for no turbid returns to the tream Clowly reintroduce flow to the work reas, monitoring for turbidity Remove block nets and temporary rosion controls Complete as built survey. Seed and mulch all disturbed areas Site clean-up and demobilization	Install and monitor temporary erosion			
construct channel and floodplain below ordinary High Water stall roughened riffle rewash work areas and pump turbid vater to an approved location and conitor for no turbid returns to the stream slowly reintroduce flow to the work reas, monitoring for turbidity stemove block nets and temporary rosion controls complete as built survey.	and sediment controls			
Construct channel and floodplain below ordinary High Water shatall roughened riffle streams work areas and pump turbid vater to an approved location and shonitor for no turbid returns to the stream slowly reintroduce flow to the work reas, monitoring for turbidity stemove block nets and temporary rosion controls complete as built survey.	Install work area isolation and dewater			
Ordinary High Water Install roughened riffle Prewash work areas and pump turbid returns to the Prewash work areas and returns to the Prewash work areas and pump turbid returns to the Prewash work areas and pump turbid returns to the Prewash work areas and pump turbid returns to the Prewash work areas and pump turbid Prewash work	work areas			
Install roughened riffle Prewash work areas and pump turbid Prewash work areas and returns to the Prewash work areas and pump turbid Prew	Construct channel and floodplain below			
Prewash work areas and pump turbid vater to an approved location and honoritor for no turbid returns to the stream slowly reintroduce flow to the work reas, monitoring for turbidity stemove block nets and temporary rosion controls complete as built survey.	Ordinary High Water			
vater to an approved location and nonitor for no turbid returns to the tream slowly reintroduce flow to the work reas, monitoring for turbidity temove block nets and temporary rosion controls complete as built survey.	Install roughened riffle			
nonitor for no turbid returns to the tream Island reintroduce flow to the work reas, monitoring for turbidity Remove block nets and temporary rosion controls Complete as built survey. Seed and mulch all disturbed areas iite clean-up and demobilization	Prewash work areas and pump turbid			
tream clowly reintroduce flow to the work reas, monitoring for turbidity temove block nets and temporary rosion controls complete as built survey. eed and mulch all disturbed areas iite clean-up and demobilization	water to an approved location and			
Islamity reintroduce flow to the work reas, monitoring for turbidity Remove block nets and temporary rosion controls Complete as built survey. Reed and mulch all disturbed areas Rite clean-up and demobilization	monitor for no turbid returns to the			
reas, monitoring for turbidity Remove block nets and temporary rosion controls Complete as built survey. Seed and mulch all disturbed areas Site clean-up and demobilization	stream			
Remove block nets and temporary rosion controls Complete as built survey. Seed and mulch all disturbed areas Site clean-up and demobilization	Slowly reintroduce flow to the work			
rosion controls Complete as built survey. Seed and mulch all disturbed areas Site clean-up and demobilization	areas, monitoring for turbidity			
Complete as built survey. Seed and mulch all disturbed areas Site clean-up and demobilization	Remove block nets and temporary			
seed and mulch all disturbed areas lite clean-up and demobilization	erosion controls			
ite clean-up and demobilization	Complete as built survey.			
·	Seed and mulch all disturbed areas			
	Site clean-up and demobilization			
Plant trees and shrubs in the fall.	Plant trees and shrubs in the fall.			
Plant trees and shrubs in the fall.				

Habitat Types

In which habitat type(s) are you proposing to work?

✓	Instream Habitat:	below the ordi	inary high	water mark	(includes	in-channel	habitat	restoration,	bank	stabilization,	flow,	fish
scree	ening, and fish pas	ssage) Detai	ils will follo	W.								

✓ Riparian Habitat: above the ordinary high-water mark of the stream and within the stream's floodplain. -- Details will follow.

- □ Upland Habitat: above the floodplain and improves native habitat and watershed function.
- ☐ Wetland Habitat: land or areas covered, often intermittently, with shallow water or have soil saturated with moisture.
- ☐ Estuarine Habitat: tidally influenced areas.

Instream Habitat

Select all applicable Instream categories.

□Bank stabilization

√Fish passage improvement

Select all the actions you propose to implement to address the problem. □Barriers at Road Crossings: Improve fish passage at road crossings. ✓ Non-road Crossing Barriers: Improves fish passage not located at road crossings.
Types of non-road crossing barriers to be improved or removed for the benefit of fish passage
(select all that apply).
□ Diversion dam
□Push-up Dam
□Non-Diversion Dam ✓ Weirs
□Natural debris jam barriers □Tidegates
☐ Natural Boulder/Rock barrier
□ Landslide
Number of non-road crossings to be treated/removed
1
☐Fish ladders or engineered bypasses not associated with road crossings
Total stream miles with improved access
8.0
Total number of barriers removed or modified
1
Are you coordinating or do you plan to coordinate with ODFW's fish passage program on this project?
● Yes
O No
If you have an ODFW project number(s), please enter them below. ODFW fish passage project numbers
will be in the form P-XX-XXXX.
ODFW staff are partnering on this project. I do not know if it has been assigned an ODFW Fish Passage
Project number yet.
□Fish screening project
□Instream Flow

✓Instream habitat restoration

Select all the actions you propose to implement to address the problem. ✓ Placement of materials in channel
Does the proposed project follow: ✓ ODFW Guidelines ✓ NOAA Guidelines
□ Other
What types of instream habitat materials are you proposing to install? (select all that apply)
✓ Boulders Number of structures.
19
Average number of boulders per structure. 17
Average size of boulders per structure (feet) 3
Combination log/boulder
✓ Other materials: Materials that stabilize the streambed Specify structure type(s):
☐ Beaver dam alternative
✓ Constructed riffle
☐ Weirs installed
Number of structures 1
✓ Channel reconfiguration and connectivity, including alcoves and side channel reconnection What type(s) of change are you proposing to the channel configuration and connectivity?
The Couse Creek channel will be realigned to a longer, more meandering route with a more gradual
slope. Slope will be establishing using a 100-foot-long roughened riffle structure and a series of 8 step pool structures.
Acres off-channel or floodplain habitat connected 1
Number of pools created/added 8
☐Spawning gravel placement
Beaver reintroduction
☐Non-native plant control ☐Nutrient enrichment
☐Animal species removal

Is the primary purpose of the instream habitat restoration treatment(s) to address water quality limiting factors?
O Yes
● No
Total miles of stream to be treated with all instream habitat restoration treatments 0.094
□Stockpiling logs
Riparian Habitat Select all applicable Riparian categories. □Riparian road activities □Fencing and other materials for habitat protection
✓Vegetation establishment or management
Select all the actions you propose to implement to address the problem. ✓ Planting For Details Go to Plant Page
✓ Non-native plant control Specify species himalayan blackberry, hounds tongue, reed canary grass
Treatment(s) to be applied ✓ Mechanical (cutting, mowing, girdling, etc.) □ Chemical (pesticides, fungicides, etc.) □ Biological (predators, herbivores, pathogens, etc.)
Acres to be treated 1
☐Prescribed burnings, stand thinning, stand conversions, silviculture☐Juniper treatment
□Livestock management □Debris and Structure Removal
Is an objective of the riparian treatment(s) to address water quality limiting factors? ▼ Yes ○ No
✓ Sediment ✓ High Temperature Total linear stream miles to be treated.

0.15

Total riparian acres to be treated.

1

Left streambank miles to be treated.

0.15

Right streambank miles to be treated.

0.075

Wrap-Up

Public Awareness

Does this proposed project include public awareness activities?

Yes
 No

Describe these activities, as well as any related products, and explain how the proposed activities relate to the project's objectives.

The WWBWC frequently conducts tours which showcase examples of collaboration, community involvement, and ecological restoration such as this Couse Creek Confluence Fish Passage Project. Tour audiences have and will include, local, state, federal, and tribal officials, school groups, landowners, and media organizations. This project will offer excellent opportunities to showcase projects of this nature in future and how project partners have worked together to complete this project. The WWBWC also provides presentations at WWBWC Board meetings, to local civic groups, County Commissioners, and restoration workshop audiences and this project will be featured. This project will also be posted on the WWBWC website, and described in our quarterly newsletter.

Design

Were design alternatives considered?

Yes

O No

Describe the design alternatives that were considered and why the preferred alternative was selected.

Design alternatives were developed based on the topographic and geomorphic site surveys conducted by Tetra Tech on September 25 to 28, 2017; evaluation of existing light detection and ranging (LiDAR) data (AeroMetric 2011; Quantum Spatial 2016); evaluation of available background documents (USACE 2010; WWBWC 2014 and 2017); review of the Alternatives Analysis and Conceptual Design: Milton-Freewater Levee and Habitat (GeoEngineers 2012); and discussion with the WWBWC.

The three alternatives that were developed include:

- ? Full Floodplain, Fish Passage, and Habitat Restoration
- ? Partial Floodplain, Fish Passage, and Habitat Restoration
- ? Fish Passage Restoration and Habitat Enhancement

Full Floodplain, Fish Passage, and Habitat Restoration Alternative

This is the most expansive alternative, with the potential to create extensive improvements to aquatic habitats. This is anticipated to be the most expensive option and would require the most extensive land owner cooperation and agency review. This alternative would involve activation of the area downstream of the confluence on river left through diversion of the full flow of Couse Creek and portions of the Walla Walla River seasonal high flows into the abandoned Milton Ditch. The new channel would connect to the Walla Walla River in two locations, adding approximately 1,300 feet of channel length. In the old Milton Ditch, abandoned irrigation diversion, fish screen, and headgate infrastructure would be removed, a culvert and road crossing removed, and a second culvert replaced with a fish passable structure. A large LWD revetment would be added at the downstream end of the new channel for landowner protection and fish habitat.

This alternative would also involve reshaping the "nose" of the confluence to provide additional floodplain access. The passage barrier in Couse Creek would be addressed through removal of the concrete structure, regrading the Couse Creek channel bed, and diverting the flow into the old Milton Ditch. Habitat and floodplain access would be

restored along Couse Creek through floodplain excavation and installation of LWD and boulder clusters upstream of the passage barrier. Boulder clusters and small pools would be added for habitat in the Walla Walla River. The existing municipal water line would be protected, including the resetting of the water valve cover and concrete pad. If this alternative is selected, potential relocation of the municipal water line should be considered to provide additional infrastructure protection.

A potential option includes the consideration of setback of the east bank levee based on landowner cooperation and agency approval. Setting back 2,200 linear feet of the east bank levee by 200 feet would create approximately 10 acres of channel migration, floodwater storage, and/or side channel development area in a reach of the Walla Walla River that is currently highly constrained and simplified.

Partial Floodplain, Fish Passage, and Habitat Restoration Alternative

This alternative would partially reconnect the downstream floodplain, address fish passage, and provide habitat restoration and enhancement in both Couse Creek and the Walla Walla River. This alternative would involve activation of the downstream area on river left through diversion of the full flow of Couse Creek into the upper portion of the abandoned Milton Ditch. The new channel would connect to the Walla Walla River in one location, adding approximately 450 feet of channel length. In the old Milton Ditch, the abandoned fishscreen would be removed to prevent stranding. A large LWD revetment would be added at the downstream end of the new channel for landowner protection and fish habitat.

The passage barrier in Couse Creek would be addressed through removal of the concrete structure, regrading the Couse Creek channel bed, and diverting the flow into the old Milton Ditch. Habitat and floodplain access would be restored along Couse Creek through installation of LWD and boulder clusters upstream of the passage barrier. Boulder clusters and small pools would be added for habitat in the Walla Walla River. The existing municipal water line would be protected, including the resetting of the water valve cover and concrete pad.

Fish Passage Restoration and Habitat Enhancement Alternative

This alternative would restore fish passage in Couse Creek and would provide fish habitat enhancements in Couse Creek and the Walla Walla River. This alternative would involve construction of an alcove and connection of the abandoned Milton Ditch for high flow relief. The new channel would connect to the Walla Walla River in one location, adding approximately 450 feet of high flow channel length. In the old Milton Ditch, the abandoned fish screen would be removed. A large LWD revetment would be added at the downstream end of the new channel for landowner protection and fish habitat.

The passage barrier in Couse Creek would be addressed through removal of the concrete structure, regrading the Couse Creek channel bed, and installing roughened riffles in the mainstem Walla Walla River. Habitat complexity would be enhanced along Couse Creek through installation of LWD and boulder clusters upstream of the passage barrier. Boulder clusters and small pools would be added for habitat in the Walla Walla River. The existing municipal water line would be protected.

Based on the comments received from BPA engineering staff, the fishery co-managers, and the US Army Corps of Engineers on the 15 Percent Design Alternatives submittal (Tetra Tech 2017a), site survey data collected, and the analyses discussed in Section 2, Section 3, and Appendix B of the 15 Percent Design Report, Tetra Tech advanced the design to the 30 percent conceptual design stage (Tetra Tech 2017b). The review team determined that levee setbacks on the east bank increased Project complexity and risk, and should not be part of the Project. Therefore, Alternative 2, the Partial Floodplain, Fish Passage, and Habitat Restoration Alternative was selected, with significant modifications that included realigning the lower portion of Couse Creek and measures to restore gradient and fish passage, as well as adding habitat boulders in the mainstem Walla Walla River (Tetra Tech 2017b).

Select the appropriate level of design for your project.

- O No design is required.
- O 10-30%: Conceptual design (evaluation of alternatives, concept-level plans, design criteria for project elements, rough cost estimates).
 - O 30-85%: Preliminary design (selection of the preferred alternative, draft plans, draft design report, preliminary

cost estimates).

• 85-100%: Final design (final design report, plans, and specifications, contracting and bidding documents, monitoring plan, final cost estimate).

If work remains on the project's design, describe the work that remains to be done and when you expect to have it completed. If no design is required put "N/A"

The 60% Basis of Design report and 60% designs have been completed. The 60% design comments from BPA's engineer, NOAA fisheries fish passage and hydraulic engineer, ODFW, and CTUIR fish biologists are currently being reviewed, discussed, and responded to. Anticipated next steps will be additional hydraulic and hydrologic modeling, slight adjustments to design drawings based on comments, development of an adaptive management plan, completion of 90% designs, 90% design review comments and discussion, final adjustments to the design, finalization of the Basis of Design report and final stamped design drawings.

Comments on the 60% designs have been received from BPA engineering and environmental Compliance staff, ODFW, CTUIR, NOAA Fisheries Hydraulics Engineering, and the Corps of Engineers. Based on the comments there are no significant changes to the design anticipated.

Describe the steps you will take to minimize adverse impacts to the site and adjacent lands during and after project implementation.

Adverse effects to fish and wildlife, existing vegetation, and water quality will be minimized using The Environmental Compliance BMPs spelled out in the BPA Habitat Improvement Project (HIP III) guidelines which are the result of consultation between Bonneville Power Administration's Habitat Program and USFWS and NOAA Fisheries.

The BMPs include:

- -temporary erosion and sediment controls
- -block nets and salvage fish
- -and monitor temporary erosion and sediment controls
- -work area isolation and dewater work areas
- -Prewash work areas and pump turbid water to an approved location and -monitor for no turbid returns to the stream
- -removal of nonnative vegetation
- -Seed and mulch all disturbed areas
- planting of shrubs and trees

Project Management

List the key individuals, their roles, and qualifications relevant to project and post project implementation. At a minimum include the following: project management, project design, project implementation, and project inspection.

Role	Name	Affiliation	Qualifications	Email	Phone
Project Manager	Brian Wolcott	Walla Walla Basin	Brian has been the	brian.wolcott@wwbwc.org	(541) 938-2170 Ext.106
		Watershed Council,	director for WWBWC for		
		Executive Director	over 20 years and has		
			overseen the installation		
			of 4 fish passage projects,		
			2 habitat projects, and		
			dozens of irrigation		
			efficiency projects. Brian		
			has attended Federal and		
			State trainings on		
			restoration.		
Engineer	Chad Bailey	TetraTech, Inc.	Civil Engineer, 12 years	Chad.Bailey@tetratech.c	(425) 482-7771
			experience with river and	om	
			water projects		
Construction oversight	Jonathan Thompson	TetraTech, Inc.	11 years of experience	Jonathan.Thompson@tetr	(425) 482-7678
and permitting lead			with river projects with	atech.com	
			TetraTech, private		
			construction, and CTUIR		
			Habitat program.		

Optional Monitoring

OPTIONAL: Restoration Project Monitoring

☐ Salmonid Monitoring
☐Non-salmonid biological monitoring
☐Water (quantity) flow monitoring
√ Water quality monitoring
☐Rangeland monitoring
✓ Onsite
✓ Downstream
✓ Upstream
□Upslope
Will effectiveness monitoring will be conducted for this project?
● Yes
○ No

<u>Please describe the monitoring activities and any additional sources of funding (amount and source) to support</u> this effort.

Turbidity monitoring will occur for the duration of construction activities following HIP III protocols. BPA funds will cover this work. The WWBWC has a turbidimeter and staff will check upstream and downstream of the project area to ensure standards are met.

WWBWC staff will monitor block nets to ensure that fish do not reenter the work area during construction.

Budget

Item	Unit Type	Unit Number	Unit Cost	OWEB Funds	External Cash	External In-Kind	Total Costs
Salaries, Wages and I	Benefits		•		•	•	
EXECUTIVE DIRECTOR	Hours	300	\$69.00	\$6,900	\$13,800	\$0	\$20,700
OPERATIONS MANAGER	Hours	100	\$46.00	\$2,300	\$2,300	\$0	\$4,600
		Categor	y Sub-total	\$9,200	\$16,100	\$0	\$25,300
Contracted Services			•				
ENGINEER PERMITTING	Each	1	\$24.655.00	\$24,655	\$0	\$0	\$24,655
ASSISTANCE & CONSTRUCTION OVERSIGHT	Lacii		ψ24,000.00	Ψ24,000	Ψ	ΨΟ	Ψ24,000
SITE PREP (MOBILIZATION, DEOMOBILIZATION, CLEARING AND GRUBBING	Each	1	\$27,820.00	\$5,460	\$22,360	\$0	\$27,820
GRADING - NEW COUSE CHANNEL AND FLOODPLAIN	Hours	2074	\$26.00	\$12,663	\$41,261	\$0	\$53,924
GRADING - ROUGHENED RIFFLE	Each	1	\$8,800.00	\$7,989	\$811	\$0	\$8,800
CONCRETE RUBBLE DISPOSAL	Hours	25	\$35.12	\$0	\$878	\$0	\$878
STEP BOULDER RIBS W/ FOOTERS (7 BOULDERS)	Each	4	\$3,380.00	\$3,520	\$10,000	\$0	\$13,520
STEP BOULDER RIBS W/ FOOTERS (7 BOULDERS)	Each	1	\$4,030.00	\$370	\$3,660	\$0	\$4,030
STEP BOULDER RIBS W/ FOOTERS (10 BOULDERS)	Each	3	\$4,420.00	\$3,260	\$10,000	\$0	\$13,260
RIFFLE BOULDERS W/ FOOTERS	Each	43	\$260.00	\$5,720	\$5,460	\$0	\$11,180
RIFFLE 12" COBBLE	Each	328	\$26.00	\$4,038	\$4,490	\$0	\$8,528
WALLA WALLA RIVER HABITAT BOULDERS	Each	10	\$260.00	\$0	\$2,600	\$0	\$2,600
CONSTRUCTION AREA BMPS	Each	1	\$15,600.00	\$0	\$15,600	\$0	\$15,600
TEMPORARY EROSION AND SEDIMENTATION CONTROL	Each	1	\$13,000.00	\$0	\$13,000	\$0	\$13,000
SITE STABILIZATION	Each	1	\$6,500.00	\$2,080	\$4,420	\$0	\$6,500
FLOODPLAIN/RIPARIAN PLANTING	Each	1	\$9,100.00	\$2,600	\$6,500	\$0	\$9,100
STREAM COFFERDAMS	Each	1	\$13,000.00	\$0	\$13,000	\$0	\$13,000
EQUIPMENT RENTAL HOURLY AND OPERATION	Hours	24	\$208.00	\$0	\$4,992	\$0	\$4,992
BYPASS PIPE (INSTALL, OPERATE, REMOVE)	Each	1	\$22,880.00	\$0	\$22,880	\$0	\$22,880
FISH SALVAGE	Each	1	\$3,380.00	\$0	\$3,380	\$0	\$3,380
REMOVAL AND HAUL OF	Each	1	\$2,730.00	\$2,730	\$0	\$0	\$2,730
OLD WATER SUPPLY							
REMOVAL AND HAUL OF FISH SCREEN	Each	1	\$4,160.00	\$832	\$3,328	\$0	\$4,160
TEMPORARY BRIDGE	Each	1	\$7,800.00	\$0	\$7,800	\$0	\$7,800
PROJECT CLEANUP & REPAIRS	Each	1	\$13,000.00	\$6,500	\$6,500	\$0	\$13,000
CONSTRUCTION STAKING	Each	1	\$7,526.00	\$7,526	\$0	\$0	\$7,526
AS-BUILT SURVEY	Each	1	\$8,067.00	\$8,067	\$0	\$0	\$8,067
		Categor	y Sub-total	\$98,010	\$202,920	\$0	\$300,930

Travel							
MILEAGE	Miles	200	\$0.55	\$55	\$54	\$0	\$109
		Cate	gory Sub-to	tal \$55	\$54	\$0	\$109
Materials and S	Supplies						•
			\$0	\$0	\$0	\$0	\$0
	·	Cate	gory Sub-to	tal \$0	\$0	\$0	\$0
Equipment and	l Software			•	•		
			\$0	\$0	\$0	\$0	\$0
		Cate	gory Sub-to	tal \$0	\$0	\$0	\$0
Other					•	•	
			\$0	\$0	\$0	\$0	\$0
		Cate	gory Sub-to	tal \$0	\$0	\$0	\$0
Mo	odified Total D	irect Cost	Amounts \$10	07,265	\$219,074	\$0	\$326,339
Indirect Costs			'				
Federally Accepted 'de	e minimis' Indirect Co	ost 10%			Indirect C	Cost Total: \$10,7	'27
Rate (up to 10%)							
			Total \$1	17,992	\$219,074	\$0	\$337,066

If the budget includes unusually high costs and/or rates, provide justification for those costs and/or rates.

If the budget identifies a contingency amount for specific line item(s) within the Contracted Services and Materials and Supplies budget categories, explain the specific reasons a contingency is needed for each line item. Contingencies are line-item specific and cannot be used for other costs.

Funding and Match

Fund Sources and Amounts

Organization Type	Name	Source Note	Contribution	туре	Amount	Description	Status
Federal	Bonneville Power	BPA Habitat Program	Cash		\$219,074	BPA funds will cost	Secured
	Administration	contract with				share materials,	
		WWBWC				construction, and	
						project management,	
						and admin.	
Fund So	ource Cash		\$219,074	Fun	d Source In-K	ind	\$0
	Total				T	otal	

Match

Contribution Source-Type: Description	Amount
Bonneville Power Administration-Cash: BPA funds will cost share materials,	\$219,074
construction, and project management, and admin.	
Match Total	\$219,074

Do match funding sources have any restrictions on how funds are used, timelines or other limitations that would impact the portion of the project proposed for OWEB funding?

Yes

No

Do you need state OWEB dollars (not Federal) to match the requirements of any other federal funding you will be using to complete this project?

O Yes

No

Does the non-OWEB funding include NOAA/PCSRF funds?

O Yes

No

Uploads

Map: Couse Creek site map.pdf -

Planting Details: Couse Ck Planting plan.pdf Photos: Couse Creek Fish passage barrier.pdf Secured Match Forms: BPA cost share contract.pdf -

Support Letters: CTUIR support for the WWBWC Couse Creek project_10.26.18.pdf -

Reports: Couse Ck Confluence Design 60 Percent summary.pdf_

Figures and Tables: Couse Creek 60% - HIP Comment Tracking 10 23 18.pdf -

Project Design: Couse Ck Confluence Design Sheets 60 Percent.pdf -

Plant Page

Planting Questions

Relationship to other conservation programs

This project will use OWEB funds to increase the planting density on CREP acres.

Planting Activities

Describe the current condition of the site(s) to be planted.

Riparian vegetation along the mainstem Walla Walla River near the project consists of a narrow band of continuous vegetation on both banks, punctuated by the occasional gap in canopy coverage. The upper canopy consists of alders (Alnus sp.) and black cottonwood (Populus balsamifera ssp. trichocarpa), with some of the larger alders extending well into the mainstem channel. The middle canopy is primarily black locust (Robinia pseudoacacia) and willows (Salix sp.) with some alders and black cottonwood present. Ground cover is typically sparse along the leveed banks, and along the west bank is highly infested with invasive non-native plant species, such as Himalayan blackberry (Rubus armeniacus), reed canarygrass (Phalaris arundinacea), and hounds tongue (Cynoglossum officinale). Very little of the soil surface has herbaceous plants because the Himalayan blackberry blocks most light from hitting the forest floor. Vegetation is also limited along the old flood protection rock berm that was built to protect the Milton Ditch from washing out in high water events.

The riparian vegetation community along Couse Creek is very similar to the riparian vegetation along the Walla Walla River. The primary difference is that Couse Creek is primarily shaded by vegetation that occupies the middle canopy, with very few mature trees. Additionally, there is a bedrock wall on river left just above the decaying cement infrastructure, which is mostly barren with only sparse grass growing in a few outcroppings. Along this section, Couse Creek is shaded by riparian vegetation on the right (east) bank, and shaded by the steep slope on the left bank.

Describe how you will prepare the site(s) prior to planting and how those activities are appropriate considering the site conditions described in the previous question.

Site will first be graded to engineered design grades. Planting shall not occur until after rolled erosion control fabric has been placed per Section 01 35 43 ENVIRONMENTAL PROTECTION. Planting zone boundaries 1-2 shall be staked on the Project site by the Contractor at the locations shown on the Drawings before any excavation for planting is made. Planting zone boundaries shall be reviewed to confirm agreement with the staked planting zone boundaries. Existing trees, shrubs, and other plants that are to be preserved shall be fenced off or otherwise barricaded along the dripline to protect them during planting. When obstructions below ground affect the work, adjustments to plant material location, type of plant and planting method shall be done with review by WWBWC staff and engineering firm representative.

Use of any Rolled Erosion Control Product to control erosion or protect young plants shall conform to Section 01 35 43 ENVIRONMENTAL PROTECTION. Grade areas to be seeded to achieve the finished grades and grading drainage patterns indicated on the Drawings. Grading shall be accomplished in accordance with the requirements of Section 35 01 60 STREAM RESTORATION and Section 01 52 00 TEMPORARY CONSTRUCTION FACILITIES. Blend new surfaces to existing areas. C. The ground to be seeded shall be free of large clods or rocks, roots and other material that may interfere with the work and subsequent maintenance operations. Hand picking may be

required. The Rolled Erosion Control Product shall be installed in accordance with the requirements of Section 01 35 43 ENVIRONMENTAL PROTECTION. Seeding shall not commence until Owner's Representative or Engineer has accepted the condition of the prepared areas.

Criteria for planting plan

- 1. Local stock of native species should be used to the extent possible because these stocks would be best suited to and adapted to local conditions.
- 2. Final planting plans will be based on the final construction design. Factors such as topography distance to stream channel and side channel shall be taken into account. The final planting plan will be intended to facilitate plant survival and to facilitate project goal of improving aquatic and riparian habitat.
- 3. To augment survival of riparian plantings:
- A. Final placement of plants shall be chosen based on microsite conditions, because soil properties and water table depth can vary over short distances, such that species are best matched to their site conditions.
- B. Site preparation, such as removal of weeds or other species that will compete with seedlings and tilling of the soil shall occur prior to planting.
- C. If necessary, soil amendment, such as fertilizer, shall be incorporated prior to or during planting.
- D. If necessary, measures such as tubing, or other animal control techniques, can be utilized to protect woody plants from grazing/herbivory.
- E. If possible, plants shall be installed in the late fall through early spring to minimize the need for supplemental water and to allow for the option of using bare root plant stock if available.

General planting notes

- 1. If applicable, supplemental fertilizer may be added to the bottom of each tree and shrub planting hole prior to planting and backfilling. If used, fertilizers shall be slow release products that will not result in nutrient runoff into aquatic systems.
- 2. If applicable, addition of mulch three inches deep may be placed in an 18 inch diameter ring around each tree and shrub to prevent competition with invasive species.

Riparian planting zone example sequence:

- 1. Seed bare soil at approximately 30 lbs/acre in selected areas as needed/desired for erosion control.
- 2. Install plants based on microsite variations within riparian planting zone.
- 3. Depending on desired density: trees should be planted 10 to 18 feet on center, shrubs should be planted at approximately 4 to 8 feet on center. However, final plant spacing will depend on specific site conditions and desired outcomes and should be designed during final plan design.

Seed mix description:

Seed mix, composed of native species, shall be used on bare soil in selected areas of the riparian planting zones as needed/desired for erosion control.

Live stakes description:

If used, live stakes should be installed along banks of stream and side channel, where applicable. The width of the zone for planting live stakes will depend on site conditions and design characteristics including final grade of bank and moisture availability.

Example sequence:

- 1. Seed bare soil at approximately 30 lbs/acre in selected areas as needed/desired for erosion control.
- 2. Install stakes based on microsite variations within riparian planting zone.
- 3. Depending on desired density, stakes may be planted at approximately 1 to 10 feet on center.

Selection and installation notes:

- 1. Live stakes should be between 18-48 inches long and at least 1/2" in diameter.
- 2. Stakes should be cut straight at the tip of the branch and at an angle at the base of

Cutting to ensure the correct end is driven into the ground.

3. Keep stakes moist and in a dark place until installed; do not let stakes dry out.

- 4. Soaking stakes before installation increases survival and growth weight.
- 5. Drive stakes into the soil so at least 2/3 of its length is underground; leave at least 12 lnches above ground.
- 6. Use thicker diameter stakes when planting in riprap; thicker diameter stakes will Resist heat and drying better than smaller cuttings.
- 7. Plant stakes during the dormant season.

Notes:

- 1. Seed at approximately 30 lbs/acre; final quantity of seed mix per acre will depend on species composition and site conditions.
- 2. Species to be used for seed mix(es) and final composition should be chosen based on site specific design and conditions (e.g. slope, width of planting zone, moisture availability)
- 3. All seed mixes should be certified weed-free.

Fill out the table below. Identify the vegetation communities you plan on planting in, the acres each vegetation community encompasses, and the density of your planting.

Vegetation Community	Acres	Density
Wetland	1	77-203 depending on species.

Fill out the table below for each vegetation community listed in the table above, provide the common and scientific names of up to five plants that will be planted, the form(tree, shrub, grass), type of plant (bare root, cutting, etc) and the planting timing.

Vegetation	Plants: Common	Plants: Scientific	Form	Туре	Year	Month
Community	Name	Name				
Wetland	WHITE ALDER	ALNUS	Tree	Rooted	2019	OCTOBER
		RHOMBIFOLIA				THROUGH
						DECEMBER
Wetland	BLACK	POPULUS	Tree	Rooted	2019	OCTOBER
	COTTONWOOD	BALSAMFIERA,				THROUGH
		SUBSPECIES				DECEMBER
		TRICHOCARPA				
WETLAND	PONDEROSA PINE	PINUS PONDEROSA	Tree	Rooted	2019	OCTOBER
						THROUGH
						DECEMBER
WETLAND	DOUGLAS FIR	PSEUDOTSUGA	Tree	Rooted	2019	OCTOBER
		MENZIESII				THROUGH
						DECEMBER
WETLAND	COYOTE WILLOW	SALIX EXIGUA	Shrub	Rooted	2019	OCTOBER
						THROUGH
						DECEMBER
WETLAND	BLACK HAWTHORN	CRATAEGUS	Shrub	Rooted	2019	OCTOBER
		DOUGLASII				THROUGH
						DECEMBER
WETLAND	LEWIS' MOCK	PHILADELPHUS	Shrub	Rooted	2019	OCTOBER
	ORANGE	LEWISII				THROUGH
						DECEMBER
WETLAND	PACIFIC NINEBARK	PHYSOCARPUS	Shrub	Rooted	2019	OCTOBER
		CAPITATUS				THROUGH
						DECEMBER
WETLAND	CHOKECHERRY	PRUNUS	Shrub	Rooted	2019	OCTOBER
		VIRGINIANA				THROUGH
						DECEMBER
WETLAND	SNOWBERRY	SYMPHORICARPOS	Shrub	Rooted	2019	OCTOBER
		ALBUS				THROUGH
						DECEMBER

WETLAND	ROCKY MOUNTAIN	ACER GLABRUM	Shrub	Rooted	2019	OCTOBER
	MAPLE					THROUGH
						DECEMBER
WETLAND	NOOTKA ROSE	ROSA NUTKANA	Shrub	Rooted	2019	OCTOBER
						THROUGH
						DECEMBER
WETLAND	GREAT BASIN	LEYMUS CINEREUS	Grass	Seeds	2019	OCTOBER
	WILDRYE					
WETLAND	IDAHO FESCUE	FESTUCA	Grass	Seeds	2019	OCTOBER
		IDAHOENSIS				
WETLAND	TUFTED	DESCHAMPSIA	Grass	Seeds	2019	OCTOBER
	HAIRGRASS	CESPITOSA				
WETLAND	BLUE WILDRYE	ELYMUS GLAUCUS	Grass	Seeds	2019	OCTOBER
WETLAND	BLUEBUNCH	PSEUDOROEGNERI	Grass	Seeds	2019	OCTOBER
	WHEATGRASS	A SPICATA				
WETLAND	MOUNTAIN BROME	BROMUSCARINATU	Grass	Seeds	2019	OCTOBER
		S VAR.				
		MARGINATUS				

Plant Stewardship

Afte	r the plantings are installed, will you conduct plant stewardship ("free to grow")?
	Yes
0	No

Are you requesting OWEB funds for plant stewardship activities?

O Yes

No

Explain how you plan to carry out activities to help the plantings survive and grow over time. Plants will be watered and any weeds removed.

Measures of Planting Success

Use the table below to explain how you will document and determine success for the plantings.


Vegetation Community	Parameter	Percentages
Wetland	Percent Survival	50%

If, in the course of the 3-5 years following planting, the success rate falls below your standard, what is your plan?

The Walla Walla Basin Watershed Council will organize volunteer tree planting days with local community members, agency staff, and college, and high school students. We will use willow cuttings and rooted cottonwoods that WWBWC staff will gather. This has been a successful activity at previous fish passage and habitat restoration projects that we have completed that needed some supplemental vegetation.

Permit Page

Project Activity Requiring a Permit or	Name of Permit or License	Entity Issuing Permit or License	Status
License			
Removal/Fill	Oregon Department of State Lands	Oregon Department of State Lands	Application will be submitted with final
	Removal/Fill		design.
Removal/Fill	US Army Corps of Engineers	US Army Corps of Engineers	Application will be submitted with final
	Removal/Fill 404permit		design
US Army Corps of Engineers 408	US Army Corps of Engineers 408	US Army Corps of Engineers	Initial review completed
Levee Alterations	Levee Alterations		
Fish passage project	ODFW Fish Passage review	Oregon Department of Fish and Wildlife	ODFW has been providing input on
			designs
in river habitat and fish passage	BPA Habitat Improvement Project III	USFWS and NOAA Fisheries	USFWS has been reviewing designs
	Biop review		
construction in floodplain	Umatilla County floodplain permit	Umatilla County	application will be submitted with final
			design



Shrub

RATAEGUS DOUGLASII HILADELPHUS LEWISII ORNUS SERICEA

BLACK HAWTHORN LEWIS' MOCK ORANGE

10 10 20 20 10 10

REDOSIER DOGWOOD COYOTE WILLOW DOUGLAS FIR PONDEROSA PINE WHITE ALDER

LIVE STAKE OR CONTAINER

CONTAINER CONTAINER CONTAINER CONTAINER

15 15 15 15

4 41

203 19 19 7

LIVE STAKE

CONTAINER

CONTAINER

CONTAINER CONTAINER

203 102 102 102 102 51

427 427 427 213 213 213 213 213 107

CONTAINER

SYMPHORICARPOS ALBUS PRUNUS VIRGINIANA PHYSOCARPUS CAPITATUS

ACER GLABRUM

ROCKY MOUNTAIN MAPLE SNOWBERRY CHOKECHERRY PACIFIC NINEBARK

- CRITERIA FOR PLANTING PLAN

 CRITERIA FOR PLANTING PLAN

 LOCAL STOCK OF NATIVE SPECIES SHOULD BE USED TO THE EXTENT POSSIBLE BECAUSE THESE STOCKS

 WOULD BE BEST SUITED TO AND ADAPTED TO LOCAL CONDITIONS.

 PROLE PLANTING PLANS WILL BE BASED ON THE FINAL CONSTRUCTION DESIGN, FACTORS SUCH AS TOPOGRAPHY DISTANCE TO STREAM CHANNEL AND SIDE CHANNEL SHALL BE TAKEN INTO ACCOUNT. THE FINAL PLANTING PLAN WILL BE INTENDED TO FACILITATE PLANT SURVIVAL AND TO FACILITATE PROJECT GOAL OF IMPROVING ACUATIC AND RIPARIAN HABITAT.

 TO AUGMENT SURVIVAL OF RIPARIAN PLANTINGS.

 B. FINAL PLACEMENT OF PLANTS SHALL BE CHOSEN BASED ON MICROSITE CONDITIONS, BECAUSE SOIL PROPERTIES AND WATER TABLE DEPTH CAN VARY OVER SHORT DISTANCES, SUCH THAT SPECIES ARE
- ი ō. BEST MATCHED TO THEIR SITE CONDITIONS.
 SHEDT REPEARATION, SUCH AS REMOVAL OF WEEDS OR OTHER SPECIES THAT WILL COMPETE WITH SEEDLINGS AND TILLING OF THE SOIL SHALL OCCUR PRIOR TO PLANTING. IF NECESSARY, SOIL AMENDMENT, SUCH AS FERTILIZER, SHALL BE INCORPORATED PRIOR TO OR DURING
- ٩ IF NECESSARY, MEASURES SUCH AS TUBING, OR OTHER ANIMAL CONTROL TECHNIQUES, CAN BE PLANTING.
- Φ. UTILIZED TO PROTECT WOODY PLANTS FROM GRAZING/HERBIVORY.
 IF POSSIBLE, PLANTS SHALL BE INSTALLED IN THE LATE FALL THROUGH EARLY SPRING TO MINIMIZE THE
 NEED FOR SUPPLEMENTAL WATER AND TO ALLOW FOR THE OPTION OF USING BARE ROOT PLANT STOCK

- GENERAL PLANTING NOTES

 1. IF APPLICABLE, SUPPLEMENTAL FERTILIZER MAY BE ADDED TO THE BOTTOM OF EACH TREE AN SHRUB
 1. PLANTING HOLE PRIOR TO PLANTING AND BACKFILLING. IF USED, FERTILIZERS SHALL BE SLOW RELEASE
 1. PRODUCTS THAT WILL NOT RESULT IN NUTRIENT RUNOFF INTO ADUATIC SYSTEMS.
 2. IF APPLICABLE, ADDITION OF MUICH THREE INCHES DEEP MAY BE PLACED IN AN 18 INCH DIAMETER RING
 2. AROUND EACH TREE AND SHRUB TO PREVENT COMPETITION WITH INVASIVE SPECIES.

ωΝ

DURING FINAL PLAN DESIGN.

INSTALL PLANTS BASED ON MICROSITE VARIATIONS WITHIN RIPARIAN PLANTING ZONE.
DEPENDING ON DESIRED DENSITY: TREES SHOULD BE PLANTED 10 10 18 FEET ON CENTER, SHRUBS
SHOULD BE PLANTED AT APPROXIMATELY 4 TO 8 FEET ON CENTER, HOWEVER, FINAL PLANT SPACING
WILL DEPEND ON SPECIFIC SITE CONDITIONS AND DESIRED OUTCOMES AND SHOULD BE DESIGNED

Growth Habit

Tree

POPULUS BALSAMIFERA SUBSP. TRICHOCARPA BLACK COTTONWOOD

PSEUDOTSUGA MENZIESII

INUS PONDEROSA

LNUS RHOMBIFOLIA

RIPARIAN PLANTING ZONE EXAMPLE SEQUENCE:

SEED BARE SOIL AT APPROXIMATELY 30 LBS/ACRE IN SELECTED AREAS AS NEEDED/DESIRED FOR

EROSION CONTROL

BANK AND MOISTURE AVAILABILITY

- EXAMPLE SEQUENCE: SEED BARE SOIL AT APPROXIMATELY 30 LBS/ACRE IN SELECTED AREAS AS NEEDED/DESIRED FOR **EROSION CONTROL**
- INSTALL STAKES BASED ON MICROSITE
- VARIATIONS WITHIN RIPARIAN PLANTING ZONE.
 DEPENDING ON DESIRED DENSITY, STAKES MAY BE
 PLANTED AT APPROXIMATELY 1 TO 10 FEET ON CENTER

ω Ņ

- SELECTION AND INSTALLATION NOTES:
 1. LIVE STAKES SHOULD BE BETWEEN 18-48 INCHES
- LONG AND AT LEAST \S'' IN DIAMETER. STAKES SHOULD BE CUT STRAIGHT AT THE TIP OF THE BRANCH AND AT AN ANGLE AT THE BASE OF CUTTING TO ENSURE THE CORRECT END IS DRIVEN INTO THE GROUND.
- KEEP STAKES MOIST AND IN A DARK PLACE UNTIL INSTALLED; DO NOT LET STAKES DRY OUT.

ω

- SOAKING STAKES BEFORE INSTALLATION INCREASES SURVIVAL AND GROWTH WEIGHT.
- DRIVE STAKES INTO THE SOIL SO AT LEAST ½ OF ITS LENGTH IS UNDERGROUND; LEAVE AT LEAST 12 INCHES ABOVE GROUND.
- IN RIPRAP; THICKER DIAMETER STAKES WILL USE THICKER DIAMETER STAKES WHEN PLANTING RESIST HEAT AND DRYING BETTER THAN SMALLER

6 Ģ

PLANT STAKES DURING THE DORMANT SEASON

POTENTIAL SPECIES FOR RIPARIAN REVEGETATION

Acres: 0.961

Common Name

Composition² 40

Propagation Method

(feet o.c.) Spacing

Quantity 163 163

Density per Acre 77

LIVE STAKES DESCRIPTION:

IF USED, LIVE STAKES SHOULD BE INSTALLED ALONG
IF USED, LIVE STAKES SHOULD BE INSTALLED ALONG
BANKS OF STREAM AND SIDE CHANNEL, WHERE
APPLICABLE. THE WIDTH OF THE ZONE FOR PLANTING
APPLICABLE. THE WIDTH OF STAKES WILL EDERNO ON STIE CONDITIONS AND
DESIGN CHARACTERISTICS INCLUDING FINAL GRADE OF
DESIGN CHARACTERISTICS INCLUDING FINAL GRADE OF

NOTES:


SEED MIX DESCRIPTION:
SEED MIX COMPOSED OF NATIVE SPECIES, SHALL BE USED ON BARE
SOIL IN SELECTED AREAS OF THE RIPARIAN PLANTING ZONES AS
NEEDED/DES/RED FOR EROSION CONTROL.


SEED AT APPROXIMATELY 30 LBS/ACRE; FINAL QUANTITY OF SEED MIX PER ACRE WILL

- DEPEND ON SPECIES COMPOSITION AND SITE CONDITIONS.

 SPECIES TO BE USED FOR SEED MIX(ES) AND FINAL COMPOSITION SHOULD BE CHOSEN BASED ON SITE SPECIFIC DESIGN AND CONDITIONS (E.G. SLOPE, WIDTH OF PLANTING ZONE, MOISTURE AVAILABILITY)
- ALL SEED MIXES SHOULD BE CERTIFIED WEED-FREE.

	ased on 60% design.	Acres and seed mix required are estimates based on 60% design.
100	TOTAL	
5	MOUNTAIN BROME	BROMUS CARINATUS VAR. MARGINATUS
15	BLUEBUNCH WHEATGRASS	PSEUDOROEGNERIA SPICATA
15	BLUE WILDRYE	ELYMUS GLAUCUS
15	TUFTED HAIRGRASS	DESCHAMPSIA CESPITOSA
20	IDAHO FESCUE	FESTUCA IDAHOENSIS
30	GREAT BASIN WILDRYE	LEYMUS CINEREUS
Percent Composition	Common Name	Scientific Name ²
	Total Seed Mix: 63 pounds (at seeding rate of 30 lbs/acre).	Total Seed Mix: 63 po
	Acres: 1.01	





LIVE STAKE PLANTING DETAIL COUSE CREEK CONFLUENCE FISH PASSAGE 60 PERCENT DESIGN DWG, NO. L-101

ASL JSA JSA 월 왜 왜 PLANTING PLAN CREATED: SHEET 7/2/18

1/8/18 7/2/18

Percent composition adds to 100 for each strata (i.e., tree, shrub) Acres, density per acre, and quantities are estimates based on 60% design, the final species list and quantities will be decided when construction plans are finalized This species should be placed near the bank of the side channel

TETRA TECH

CONSTRUCTION **NOT FOR**



Couse Creek Fish passage barrier



Couse Creek Fish passage barrier

UNITED STATES GOVERNMENT

COOPERATIVE AGREEMENT



Mail Invoice To:

fwinvoices@bpa.gov

F & W Invoices - KEWB-4

P. O. Box 3621

Portland OR 97208-3621

Contract

: 00080649

Release

Page

: 1

Vendor:

WALLA WALLA BASIN WATERSHED FOUNDATION

810 S MAIN STREET

MILTON-FREEWATER OR 97862

Please Direct Inquiries to:

JAY CHONG

Title: CONTRACT SPECIALIST

Phone: 503-230-4007

Fax:

Attn:

CHRIS SHEETS

Contract Title:

2007-396-00 EXP WALLA WALLA BASINWIDE TRIB PASSAGE

Total Value:

\$666,032.00

Pricing Method:

COST, NO FEE

Performance Period:

11/01/18

10/31/19

** NOT TO EXCEED **

Payment Terms:

Days Net 15

Contractor Signature

PEXECUTIVE DIRECTOR BRIAN R. WOLCOTT

Printed Name/Title 10/22/2018


Date Signed

RACHEL KULAK Digitally signed by RACHEL KULAK Date: 2018.10.18 10:49:17 -07'00'

BPA Contracting Officer

10/18/2018

Date Signed





Hannah Dondy- Kaplan	COTR	Bonneville Power Administration	(503) 230-4071 / (503) 230-5699	hadondy- kaplan@bpa.gov	P.O. Box 3621 Mailstop - KEC-4 Portland OR 97208- 3621
Claire McClory	Env. Compliance Lead	Bonneville Power Administration	(503) 230-5922 / NA	cdmcclory@bpa.gov	P.O. Box 3621 Mail Stop ECT-4 Portland OR 97208- 3621
Elham Zolmajd- Haghighi	CO Assistant	Bonneville Power Administration	(503) 230-7414 / NA	ezolmajd- haghighi@bpa.gov	P.O. Box 3621 Mailstop - NSSP-4 Portland OR 97208- 3621
Douglas Knapp	Interested Party	Bonneville Power Administration	(503) 230-3285 / NA	ddknapp@bpa.gov	AB
Tybee Sheidler	CO Assistant	Bonneville Power Administration	(503) 230-3820 / NA	tasheidler@bpa.gov	P.O. Box 3621 Mail Stop NSSP-4 Portland OR 97208- 3621 AB
Christopher Roper	CO Assistant	Bonneville Power Administration	(503) 230-3514 / NA	cproper@bpa.gov	P.O. Box 3621 Mail Stop NSSP-4 Portland OR 97208- 3621 AB
Jay Chong	Contracting Officer	Bonneville Power Administration	(503) 230-4007 / NA	jxchong@bpa.gov	

Work Element Budget Summary:

Work	Element - Work Element Title	EC Needed*	Estimate	(%)
A :	185. Produce Pisces Status Report - Periodic Status Reports for BPA		\$2,000	(0.30 %)
В:	119. Manage and Administer Projects - Admin oversight for Exp Activities		\$5,000	(0.75 %)
C:	165. Produce Environmental Compliance Documentation - Environmental Compliance Documentation for all Exp actions		\$30,000	(4.50 %)
D:	132. Produce (Annual) Progress Report - Annual Progress Report (11-1-17 to 10-31-18)		\$4,600	(0.69 %)
E:	99. Outreach and Education - Youth and adult presentations		\$7,000	(1.05 %)
F:	175. Produce Design and/or Specifications - Lampson Side Channel Entrance Final Design and Permitting	*	\$123,000	(18.47 %)
G:	175. Produce Design and/or Specifications - North Fork WW Push Up Dams Alternatives Assessment/Initial Design - NF8	*	\$62,500	(9.38 %)
H:	175. Produce Design and/or Specifications - North Fork WW Push Up Dams Alternatives Assessment/Initial Design - NF7	*	\$66,500	(9.98 %)
1:	184. Install Fish Passage Structure - Couse Creek Fish Passage Construction	*	\$253,000	(37.99 %)
J:	148. Install Flow Measuring Device - Walla Walla River	*	\$40,000	(6.01 %)



DIVISION OF FISH AND WILDLIFE

Deliverable Specification: The Couse Creek Fish Passage Construction will be completed according to approved designs.

Work Element Budget: \$253000 (37.99 %)

Planned Metrics: * # of miles of habitat accessed to the next upstream barrier(s) or likely limit of habitable range: 9.00

* # of natural stream crossings installed in the freshwater non-tidal zone: 1

Locations:

Primary Focal Species: Chinook (O. tshawytscha) - Mid-Columbia River Spring ESU | Steelhead (O. mykiss) - Middle Columbia River DPS |

Trout, Bull (S. confluentus)

Country: US NPCC Subbasin: Walla Walla

State: OR HUC5 Watershed: Upper Walla Walla River

County: Umatilla HUC6 Name: Couse Creek

Salmonid ESUs Present: Middle Columbia River Steelhead DPS (Accessible)

Milestone Title	Start Date	End Date	Status	Milestone Description
A. Environmental compliance requirements complete	11/1/2018	5/31/2019	Inactive	On-the-ground work associated with this work element cannot proceed until this milestone is complete. Milestone is complete when final documentation is received from BPA environmental compliance staff.
B. Discuss HIP3 ESA coverage with BPA EC lead; obtain HIP3 risk determination	11/1/2018	5/31/2019	Inactive	The EC Lead will determine if work under this work element may be able to have full ESA-coverage (NOAA & USFWS) under the 2013 Habitat Improvement Program Biological Opinion (HIP3). The HIP3 has expanded coverage for projects that may pose a moderate to high risk of impacting an ESA-listed species or critical habitat that would normally require a Biological Assessment. For work that qualifies, projects will undergo a review by the BPA-internal Restoration Review Team (RRT). Before conceptual design commences, contact the EC lead for HIP3 consideration, instruction, and information needs and requirements for coverage eligibility. The HIP3 activity categories and risk criteria are located in the "Note" section of
				the work element background page here:https://www.cbfish.org/WorkElement.mvc/Summary/165
C. Choose contractor for fish passage construction	11/1/2018	5/31/2019	Inactive	A RFP for the fish passage construction will be developed with input from basin fish managers. Proposals will be solicited and a contractor will be chosen through a criteria developed by WWBWC and the basin fish managers. While WWBWC always strives to award contracts to the lowest bidder, qualifications will be a major part of the selection process for this in-stream project.
D. Obtain necessary permits to complete this project	11/1/2018	5/31/2019	Inactive	WWBWC will obtain the necessary permits that are required to complete this project.
E. Clearing and prepping project site	7/1/2019	7/31/2019	Inactive	The Couse Creek Fish Passage project site will be cleared and prepped for construction.
F. Excavation for roughened riffles	7/1/2019	9/30/2019	Inactive	Project site will be excavated for placement of roughened riffles.
G. Install roughened riffles	7/1/2019	9/30/2019	Inactive	Boulders will be placed to create a roughened riffle to repair fish passage issue.
H. Bank protection structures installed	7/1/2019	9/30/2019	Inactive	Logs will be used for bank stabilization.
I. Riparian planting	7/1/2019	9/30/2019	Inactive	Riparian planting will be done to restore river bank stabilization.
J. Site Clean-up	7/1/2019	10/31/2019	Inactive	WWBWC will work with contractor to ensure project site is returned to a reasonable condition.
Deliverable: K. Couse Creek Fish Passage Construction Complete		10/31/2019	Inactive	See the Deliverable Specification above

J: 148. Install Flow Measuring Device

Title: Walla Walla River Flow Gauge at Tumulum Bridge

Description: A flow gauge is necessary at this location to ensure the 20.05 cfs that has been conserved in OR and protected

instream through WA as instream water rights actually remains instream. This location is at the downstream end of the worst losing (riverbed seepage) reach of the Walla Walla River in the Oregon half of the watershed. This gauge

location will show the conserved water that is passing on to

Washington from Oregon instream water rights to assist Washington with protecting that same amount from



DIVISION OF FISH AND WILDLIFE

Milestone Title	Start Date	End Date	Status	Milestone Description
D. Obtain HIP risk determination	11/1/2018	2/28/2019	Inactive	FOR HABITAT ACTIONS ONLY: The EC Lead will determine if work under this work element may be able to have full ESA-coverage (NMFS & USFWS) under the Habitat Improvement Program Biological Opinion (HIP). The HIP has expanded coverage for projects that may pose a moderate to high risk of impacting an ESA-listed species or critical habitat that would normally require a Biological Assessment. For work that qualifies, projects will undergo a review by the EC Lead and Engineering Technical Services (ETS) team. Before conceptual design commences, contact the EC lead for HIP consideration, instruction, and information needs and requirements for coverage eligibility.
E. Bid out design of instream habitat actions to comply with HIP	11/1/2018	2/28/2019	Inactive	Create design bid package that follows design constraints in HIP guidance. The intent of this milestone is to determine early if proposed habitat actions comply with HIP requirements. If the contractor feels they cannot design within the constraints of the HIP, discuss the proposed action with BPA COR/EC. BPA Engineering Technical Services (ETS) is also available for early review of project designs.
F. Submit designs for BPA engineering review	2/1/2019	4/30/2019	Inactive	Submit designs consistent with development stage for BPA engineering review. Designs may be reviewed at conceptual stage (requiring a brief functional review), or 15% and higher (requiring a complete Basis of Design Report). Submit designs to ECL, COR, and other relevant reviewers.
G. Provide project concepts: 15% preliminary design to the EC and COTR.	11/1/2018	4/30/2019	Inactive	Provide conceptual strategy, restoration approach, or preliminary design (even if at the very earliest stages of development) to the EC-lead and COTR to inform the HIP III risk characterization; and before developing any additional significant technical detail or engineering specifications.
H. Obtain cultural resource clearance for ground-disturbing survey and monitoring actions	11/1/2018	6/30/2019	Inactive	If planning or design work requires ground disturbance including but not limited to geotechnical surveys, ground water monitoring, or well exploration, obtain appropriate cultural resources consultation prior to any ground disturbance. Notify EC lead well in advance of ground disturbing work. On-the-ground work associated with this work element may not proceed until this milestone is complete. Milestone is complete when BPA environmental compliance staff provides final documentation.
I. Provide project concepts: 30% preliminary design to the EC and COTR.	5/1/2019	9/1/2019	Inactive	Design review by EC required, which may include HIP RTT review, before proceeding to the next design phase.
J. Meet with landowners, BPA, and basin partners to review alternatives	9/1/2019	9/30/2019	Inactive	WWBWC will meet with landowners, BPA, basin partners, and fish managers to determine which alternatives best meet goals.
Deliverable: K. North Fork WW Push Up Dam NF8 Alternatives Designed		10/31/2019	Inactive	See the Deliverable Specification above

1: 184. Install Fish Passage Structure

Title:

Couse Creek Fish Passage Construction

Description:

Couse Creek is a tributary of the Walla Walla River just upstream from Milton-Freewater, and is currently used by steelhead, spring Chinook salmon, redband trout, and occasionally by bull trout. Currently, there is a fish passage issue near the confluence of Couse Creek and the Walla Walla River during lower flows when there are still returning steelhead adults and Chinook salmon adults seeking their spawning areas. Where Couse Creek discharges into the river, Couse Creek transitions from a bedrock-controlled bed onto the gravel bed of the Walla Walla River. A three to four foot, slanted, bedrock drop exists at this transition point. From this point, the Creek continues upstream as a steep, shallow, bedrock controlled bed before gravels and cobbles dominate the bed. Steelhead cannot navigate this drop in late winter and early spring when discharges from the Creek are relatively high.

An engineering assessment, survey, and 30% designs to improve fish passage at this location have been completed.

An engineering assessment, survey, and 30% designs to improve fish passage at this location have been completed. BPA funds have covered the costs of initial project design work with technical support provided by ODFW and CTUIR fisheries staff and the WWBWC. Three alternatives have been developed, and final designs are scheduled to be completed by November 2018. With the assistance of BPA EC staff, permitting work has been initiated. Under this contact, construction will be scheduled for summer of 2019.

Couse Creek was described in the Walla Walla Subbasin Plan EDT analysis as a Priority Protection Area. The Walla Walla Subbasin Plan identifies addressing fish passage barriers as a priority action. Recent restoration investments in Couse Creek have included fish passage work at the Konen rock quarry culvert replacement bridge project. Also, fish habitat investments have occurred along the Shumway-Banks property.

As previously stated, with the assistance of BPA EC staff, EC work has been initiated for this project.

From: <u>Gary James</u>
To: <u>GREER Sue * OWEB</u>

Cc: <u>Eric Hoverson</u>; <u>Mike Lambert</u>; <u>Brian Wolcott (brian.wolcott@wwbwc.org)</u>; <u>DUKE William B</u>

Subject: CTUIR support for the WWBWC Couse Creek project

Date: Friday, October 26, 2018 12:32:32 PM

Attachments: <u>image001.png</u>

Sue,

Just a quick note to relay CTUIR support of the Couse Creek Confluence Fish Passage project proposal being submitted by the Walla Walla Basin Watershed Council. We have been in close coordination with the WWBWC for the planning of this beneficial project. Thanks, GJames

Gary James

Conf. Tribes of the Umatilla Indian Re... Fisheries Program Manager

(541) 429-7285 Work (541) 969-3153 Mobile garyjames@ctuir.org 46411 Ti'Mine Way Pendleton, Oregon 97801

Couse Creek Confluence Fish Passage Design Project

60 Percent Preliminary Design

Prepared for:



Walla Walla Basin Watershed Council 810 South Main Street Milton-Freewater, OR 97862

Prepared by:



19803 North Creek Parkway Bothell, WA 98011 Tel 425-482-7600 Fax 425-482-7652

July 2018

Contents

Con	tents.		i
Figu	res		iii
Tabl	les		iii
1.	Pref	ace	1
	1.1	Name and titles of sponsor, firms, and individuals responsible for design	2
	1.2	List of project elements that have been designed by a licensed Professional	
		Engineer	3
	1.3	Identification and description of risk to infrastructure or existing resources	3
	1.4	Explanation and background on fisheries use (by life stage - period) and limiting	
		factors addressed by project	4
	1.5	List of primary project features including constructed or natural elements	6
		1.5.1 Project Goal	
		1.5.2 Past Designs	6
		1.5.3 15 Percent Design Alternatives	7
		1.5.4 30 Percent Conceptual Design	8
		1.5.5 60 Percent Preliminary Design	9
	1.6	Description of performance / sustainability criteria for project elements and	
		assessment of risk of failure to perform, potential consequences and	
		compensating analysis to reduce uncertainty	9
	1.7	Description of disturbance including timing and areal extent and potential	
		impacts associated with implementation of each element	14
2.	Resc	ource Inventory and Evaluation	15
	2.1	Description of past and present impacts on channel, riparian and floodplain	
		conditions	15
	2.2	Instream flow management and constraints in the project reach	16
	2.3	Description of existing geomorphic conditions and constraints on physical	
		processes	16
	2.4	Description of existing riparian condition and historical riparian impacts	18
	2.5	Description of lateral connectivity to floodplain and historical floodplain impacts	19
	2.6	Tidal influence in project reach and influence of structural controls (dikes or	
		gates)	20
3.	Tech	nnical Data	21
	3.1	Incorporation of HIP III specific Activity Conservation Measures for all included	
		project elements	21
	3.2	Summary of site information and measurements (survey, bed material, etc.) used	
		to support assessment and design	21
	3.3	Summary of hydrologic analyses conducted, including data sources and period	
		of record including a list of design discharge (Q) and return interval (RI) for each	
		design element	26
	3.4	Summary of sediment supply and transport analyses conducted, including data	
		sources including sediment size gradation used in streambed design	29
	3.5	Summary of hydraulic modeling or analyses conducted and outcomes –	
		implications relative to proposed design	31

		3.5.1 1D model updated for the 60 Percent Design and 2D model created	32
	3.6	Stability analyses and computations for project elements, and comprehensive	
		project plan	34
		3.6.1 Streambed aggregate and boulder sizing for the roughened riffle	34
		3.6.2 Evaluation of sediment transport at the proposed confluence	
		3.6.3 Jump heights at boulder sills	
	3.7	Description of how preceding technical analysis has been incorporated into and	
		integrated with the construction – contract documentation	39
	3.8	For projects that address profile discontinuities (grade stabilization, small dam	
		and structure removals): A longitudinal profile of the stream channel thalweg for	
		20 channel widths upstream and downstream of the structure shall be used to	
		determine the potential for channel degradation	39
	3.9	For projects that address profile discontinuities (grade stabilization, small dam	
		and structure removals): A minimum of three cross-sections – one downstream	
		of the structure, one through the reservoir area upstream of the structure, and	
		one upstream of the reservoir area outside of the influence of the structure) to	
		characterize the channel morphology and quantify the stored sediment	39
4.	Con	struction – Contract Documentation	39
	4.1	Incorporation of HIP III General and Construction Conservation Measures	39
	4.2	Design – construction plan set including but not limited to plan, profile, section	
		and detail sheets that identify all project elements and construction activities of	
		sufficient detail to govern competent execution of project bidding and	
		implementation	
	4.3	List of all proposed project materials and quantities	40
	4.4	Description of best management practices that will be implemented and	
		implementation resource plans including:	
		4.4.1 Site Access Staging and Sequencing Plan	
		4.4.2 Work Area Isolation and Dewatering Plan	
		4.4.3 Erosion and Pollution Control Plan	
		4.4.4 Site Reclamation and Restoration Plan	
		4.4.5 List proposed equipment and fuels management plan	
	4.5	Calendar schedule for construction/implementation procedures	40
	4.6	Site or project specific monitoring to support pollution prevention and/or	
_		abatement.	
5.		nitoring and Adaptive Management Plan.	
6.	Ref	erences	42

APPENDIX A-PROJECT PLAN SHEETS AND CONCEPT PLANTING PLAN

APPENDIX B-OTHER SUPPORTING REPORTS

APPENDIX C-ENGINEER'S COST ESTIMATE

APPENDIX D-PROJECT TECHNICAL SPECIFICATIONS

APPENDIX E-RRT DESIGN REVIEW COMMENTS

Figures

Figure 1-1.	National Wetland Inventory Polygons, indicating Potential Forested	
	(PFOA) and Riverine (R3UBH) Wetlands	
Figure 2-1.	Fish Passage Barrier	17
Figure 2-2.	Representative Riparian Conditions at the Project Site, Between the Mouth of Couse Creek and the Bedrock Barrier	19
Figure 2-3.	Couse Creek-Walla Walla River Confluence Floodplain	20
Figure 3-1.	Longitudinal Profile of the Walla Walla River	22
Figure 3-2.	Longitudinal Profile of Couse Creek	22
Figure 3-3.	Substrate Grain Size Distribution for Site 1 on the Walla Walla River	24
Figure 3-4.	Substrate Grain Size Distribution for Site 2 on the Walla Walla River	25
Figure 3-5.	Substrate Grain Size Distribution for Couse Creek	25
Figure 3-6.	Couse Creek Existing Condition Incipient Motion Analysis	31
Figure 3-7.	Couse Creek Proposed Condition 2D Hydraulic Model Data	33
Figure 3-8.	2-Year Shear Stress at the Proposed Couse Creek and Walla Walla River Confluence	36
Figure 3-9.	2-Year Velocities at the Proposed Couse Creek and Walla Walla River Confluence	
Figure 3-10.	Jump Height for the High Fish Passage Design Flow in Couse Creek	38
	Tables	
Table 1-1.	EDT Assessed Limiting Factors for Anadromous Species in the Walla Walla River Subbasin	5
Table 1-2.	Fish Passage Criteria	
Table 1-3.	Project Actions and Performance Criteria	
Table 3-1.	Geomorphic and Habitat Existing Conditions for Walla Walla River	
Table 3-2.	Substrate Size Characteristics Based on Pebble Counts	
Table 3-3.	Walla Walla River Flood Discharges	
Table 3-4.	Walla Walla River 100-Year Flood Discharges	
Table 3-5.	Couse Creek Flood Discharges	
Table 3-6.	Walla Walla River Downstream of Confluence Flood Discharges	
Table 3-7.	Couse Creek 5th and 95th Annual Percent Exceedance Flows	
Table 3-8.	Walla Walla River 5th and 95th Annual Percent Exceedance Flows	

1. Preface

This report for the Couse Creek Confluence Fish Passage Design (Project) is based on the General Project Data Summary Requirements (GPDSR) Basis of Design Report template for Bonneville Power Administration (BPA) Habitat Improvement Program (HIP III) projects (BPA 2017a). Some formatting changes have been made to the template but the sections and requested information follow the template structure. The GPDSR requirements below are as presented in the GPDSR template. However, the BPA Restoration Review Team (RRT) review stages for the Project will differ slightly from the review junctures suggested by the template. As described below, the Project review will include the 60 percent and 90 percent Design Submittal reviews by the RRT in place of an 80 percent design review.

General Project Data Summary Requirements (GPDSR)

Planning and design documentation of conservation practices should effectively communicate that appropriate planning, analysis, design, and resulting construction documentation are met. The project documentation should provide other persons the means of quickly following the rationale used in determining all features of a design including the design objective(s), data, criteria, assumptions, procedures, and decisions used in design and resulting construction plans, specifications and details. The GPDSR serves as the design submittal framework that is needed to assess and evaluate the adequacy of the proposed project.

The GPDSR criteria were developed using the River Restoration Analysis Tool (RiverRAT) and address the 16 overarching questions proposed within the RiverRAT Framework.

The BPA RRT will review submitted GPDSR documents to determine if the technical deliverables provided are adequate for *functionality* (*adherence to HIP 3 Conservation Measures*) and technical quality (competent execution of design and project plans – contract documents).

For the Channel Reconstruction activity category, a project-specific Monitoring and Adaptive Management Plan must be included.

Project Review Junctures

15 Percent RRT Review: The Project Sponsor will notify BPA at the 15 percent project concept completion stage and coordinate a site visit to review project concepts, goals, and objectives and confirm the direction and planning for subsequent phases of project design. The site visit will include the review of limiting factors and any pertinent studies or reports

that document restoration targets for implementation and draft project concepts. Additional data that may be presented and reviewed include other data sources, e.g., high resolution aerial photography, topographic maps, Geographic Information System (GIS) – computeraided drafting (CAD) data layers, or other resource data. BPA will clarify technical documentation requirements with the Sponsor at this stage. BPA will provide functional and technical comments after the site review to be addressed as the Project advances to 30 percent completion.

Submit 30 Percent Design for RRT Review: Sponsor will notify BPA at the 30 percent preliminary design completion stage of the Project. The 30 percent project drawings and preferred project alternatives will be submitted for RRT functional and technical review. The 30 percent design shall demonstrate incorporation of technical comments and recommendations provided at the 15 percent project review. The 30 percent design submittals should include conceptual drawings and specifications including overall site locations, site plans, profiles, cross sections, details, preliminary quantities and provisional technical analyses as summarized in a draft Basis of Design Report using the GPDSR outline. BPA will perform functional and technical review of the 30 percent submittal and provide comments back to the Sponsor to be addressed as the project advances to 60 percent completion.

Submit 60 Percent and 90 Percent Designs for RRT Review: As noted previously, the suggested 80 percent design review will be replaced by 60 percent and 90 percent design reviews. The 60 percent project drawings will be submitted for RRT functional and technical review. Following BPA's functional and technical review of the 60 percent submittal, BPA's comments back to the Sponsor will be addressed as the Project advances to the 90 percent level and the 90 percent project drawings will be submitted for RRT functional and technical review. The 90 percent design submittals should include near final drawings and specifications including specific site locations, site plans, profiles, cross sections, details, construction quantities, implementation resource plans and design technical analyses as summarized in a Basis of Design Report addressing the GPDSR requirements. BPA will perform functional and technical review of the 90 percent submittal and provide comments back to the Sponsor to be addressed as the Project advances to completion, after which the Sponsor will submit the final design for BPA's records.

1.1 NAME AND TITLES OF SPONSOR, FIRMS, AND INDIVIDUALS RESPONSIBLE FOR DESIGN

Project Name: Couse Creek Confluence Fish Passage Design (Project)

Project Location: Couse Creek Confluence, Milton-Freewater, Oregon

Sponsor: Walla Walla Basin Watershed Council (WWBWC), 810 South Main Street, Milton-

Freewater, OR 97862

Walla Walla Basin Watershed Council Executive Director: Brian Wolcott

Engineering firm: Tetra Tech, Inc. (Tetra Tech), 19803 North Creek Parkway, Bothell, WA

98011

Project Manager: Chris James

Lead Design Engineer: Chad Bailey, PE, CFM

Water Resources Engineer: Jeremy Andrews, PE

1.2 LIST OF PROJECT ELEMENTS THAT HAVE BEEN DESIGNED BY A LICENSED PROFESSIONAL ENGINEER

Project Design Drawings (see Appendix A)

Other Supporting Reports (see Appendix B)

Engineer's Cost Estimate (see Appendix C)

Construction Specifications (see Appendix D)

1.3 IDENTIFICATION AND DESCRIPTION OF RISK TO INFRASTRUCTURE OR EXISTING RESOURCES

The Project is located on both private property and property held by the City of Milton-Freewater. The adjoining land uses are a mix of rural residential and agriculture, and the land use downstream of the Project remains rural residential for 0.5 river miles (RM), before entering the outskirts of Milton-Freewater. The Project is located within the Milton-Freewater Levee system, which was constructed in the 1940s and rebuilt between 1966 and 1968 by the U.S. Army Corps of Engineers (USACE), and recently repaired by the Milton-Freewater Water Control District to bring the system back into USACE and Federal Emergency Management Agency (FEMA) compliance. The Milton-Freewater Water Control District holds the easement for the Milton-Freewater Levee system, which is almost entirely on private land.

Infrastructure within the Project includes the Milton-Freewater Levee system, a water line for the city of Milton-Freewater that crosses underneath the channel bed of Couse Creek, and a pair of associated valves present on the elevated terrain to the east. One of these is the

original valve, and the second is a modern valve protected by a cement pad. The Couse Creek Road Bridge is a short distance upstream of the Project, and there are three paved vehicle bridges located 0.8, 1.3, and 2.6 miles downstream from the Project, respectively. No utilities other than the municipal water line were reported during a utility locate.

Couse Creek has incised down to bedrock near the mouth, and there is an existing cement structure approximately 150 feet upstream of the mouth that constricts the channel. The bedrock drop and the velocities at the cement structure each present a partial fish passage barrier at various flows. Project actions to address fish passage and improve local habitat conditions are anticipated to include channel, streambank, and floodplain modifications in Couse Creek and in the floodplain downstream from the current mouth of Couse Creek.

1.4 EXPLANATION AND BACKGROUND ON FISHERIES USE (BY LIFE STAGE - PERIOD) AND LIMITING FACTORS ADDRESSED BY PROJECT

Couse Creek is a tributary to the Walla Walla River, flowing 16.2 miles from north to south and joining with the Walla Walla River at approximately RM 47.2 based on United States Geological Survey (USGS) river mile locations. Use of the USGS river mile locations will be used hereafter, and is consistent with river mile locations reported by the USACE (2010). The Project is intended to improve fish passage for all life stages of resident and anadromous salmonids from the confluence with the Walla Walla River up into the spawning and rearing habitats of Couse Creek. The focal species for the Project are summer steelhead (*Oncorhynchus mykiss*) and spring Chinook salmon (*O. tshawytscha*). Other fish species that are expected to benefit from the Project include resident redband trout (*O. mykiss*) and, to a lesser extent, bull trout (*Salvelinus confluentus*).

Steelhead in the Walla Walla River and tributaries belong to the Umatilla-Walla Walla major population group, part of the federally threatened Middle Columbia River (MCR) steelhead distinct population segment (DPS). The MCR DPS of steelhead was listed as threatened on March 25, 1999, and the threatened status was reaffirmed on August 15, 2011 (76 Federal Register 50448). Accessible habitat for steelhead in Couse Creek has been estimated at 14.2 miles (NPCC 2005). Spring Chinook salmon in the Walla Walla River were originally part of the Middle Columbia Spring Chinook Species Management Unit until they were effectively extirpated from the Walla Walla River Subbasin in the 1920s (SRSRB 2011). Recently, spring Chinook salmon were reintroduced into the subbasin by the Confederated Tribes of the Umatilla Indian Reservation Department of Natural Resources in 2000. Bull trout are currently listed under the Endangered Species Act (ESA) as Threatened, and are considered a Candidate species by the State of Washington. The Walla Walla system is one of the

currently occupied bull trout core areas in the Middle Columbia Recovery Unit (USFWS 2015).

The Walla Walla Subbasin Plan (NPCC 2005) assessed summer steelhead and spring Chinook salmon populations in the Walla Walla Subbasin by using the Ecosystem Diagnosis and Treatment (EDT) method. The typical 16 limiting factors that are assessed in the EDT modeling are listed in Table 1-1. The results of the general subbasin-wide analysis indicate that the key limiting factors for summer steelhead were sediment load, habitat diversity, key habitat quantity, and obstructions. The primary limiting factors for spring Chinook salmon below the Mill Creek confluence were sediment load, key habitat quantity, habitat diversity, and water temperature, with flow and predation as secondary limiting factors. In the mainstem Walla Walla reaches between the Mill Creek confluence and Nursery Bridge (Milton-Freewater, OR), channel stability and obstructions also became secondary limiting factors (NPCC 2005).

Table 1-1. EDT Assessed Limiting Factors for Anadromous Species in the Walla Walla River Subbasin

Lim	niting Factors				
Flow	Water Temperature				
Channel Stability	Habitat diversity				
Key Habitat Quantity	Obstructions				
Withdrawals	Sediment Load				
Oxygen	Chemicals				
Food	Hatchery Competition				
Resident Competition	Predation				
Pathogens	Harassment/poaching				

Source: NPCC 2005

More thorough coverage of Walla Walla River via the EDT process is provided in Appendix 1 of the Subbasin Plan (NPCC 2005). The Project is located at the mouth of Couse Creek, which is identified in the EDT analysis as the Couse 1 reach of the Couse Creek Drainage geographical area. Limiting factors identified for Couse 1 include water temperature and flows (NPCC 2005). Additionally, Couse Creek is listed by the Oregon Department of Environmental Quality (ODEQ) under Section 303(d) as being potentially limited (category 3, insufficient data) for numerous pollutants/adverse water quality conditions (alkalinity, ammonia, chlorophyll a, dissolved oxygen, e. coli, flow modification, habitat modification, pH, phosphate/phosphorus, sedimentation, and water temperature) (ODEQ 2012).

The 2008 Fish Accords (Three Treaty Tribes-Action Agencies 2008) lists three primary limiting factors for Walla Walla River Summer Steelhead in the Walla Walla River below the

North and South Forks of the Walla Walla River. These limiting factors are identified as inchannel characteristics, passage/entrainment, and riparian/floodplain.

1.5 LIST OF PRIMARY PROJECT FEATURES INCLUDING CONSTRUCTED OR NATURAL ELEMENTS

1.5.1 Project Goal

The overall goal of the Project is to restore and enhance fish passage and habitat within Couse Creek and potentially improve habitat conditions of the Walla Walla River in the near vicinity. These actions will address the primary limiting factors identified in the 2008 Fish Accords (Three Treaty Tribes-Action Agencies 2008).

To address the overall Project goal, the following potential Project objectives were identified:

- Improve fish passage at the site, including by removing the existing cement structure (approximately 150 feet upstream of the mouth) to reduce channel velocities and improve fish passage;
- Improve quality and quantity of habitat in Couse Creek and the Walla Walla River;
- Reroute Couse Creek to increase stream length and reduce channel gradient;
- Assess the need to install roughened riffles to raise the bed elevation of the Walla
 Walla River (based on available levee freeboard) and increase channel stability;
- Assess the feasibility of a levee setback on the east bank of the Walla Walla River, to increase floodplain connectivity;
- Control and manage invasive species;
- Protect private property from erosion and channel evulsion; and
- Work closely with the WWBWC at each stage of design and obtain consensus on the design before proceeding to the next design stage.

1.5.2 **Past Designs**

The Alternatives Analysis and Conceptual Design: Milton-Freewater Levee and Habitat report (GeoEngineers 2012) was developed to improve habitat conditions for ESA-listed steelhead and bull trout, while also reducing flood risk to the city of Milton-Freewater and outlying residential areas. Fish passage at the mouth of Couse Creek was specifically addressed in the analysis and conceptual designs, including a discussion of an alternative that focused on providing fish passage and stabilizing the creek bed. The primary recommendation was to improve fish passage by stabilizing the Couse Creek stream bed and the Walla Walla River around the confluence. A secondary recommendation was to stop

degradation and head cutting. The suggested action was to place cobbles and boulders at the mouth of the creek and within the river as part of a channel roughening effort, rather than using rock vanes or weirs. The design plan sheets also indicate establishing off channel alcove habitat, approximately at the start of the old Milton Ditch Line. Other actions considered were variations of smaller roughened stream bed arrangements, and potential modification of the bedrock channel to facilitate passage.

The Couse Creek fish passage alternative ended up being ranked third out of eight proposed project alternatives within the assessment area. Following the completion of the two highest ranked alternatives (Smith and Zell Diversions), the WWBWC selected Tetra Tech to develop the design for this Project.

1.5.3 15 Percent Design Alternatives

Design alternatives were developed based on the topographic and geomorphic site surveys conducted by Tetra Tech on September 25 to 28, 2017; evaluation of existing light detection and ranging (LiDAR) data (AeroMetric 2011; Quantum Spatial 2016); evaluation of available background documents (USACE 2010; WWBWC 2014 and 2017); review of the Alternatives Analysis and Conceptual Design: Milton-Freewater Levee and Habitat (GeoEngineers 2012); and discussion with the WWBWC.

The three alternatives that were developed included:

- Full Floodplain, Fish Passage, and Habitat Restoration This alternative would create a new channel, remove old irrigation ditch infrastructure, remove a culvert and road crossing, replace a second culvert, and add a large woody debris (LWD) revetment to the channel. The existing municipal line would be protected or moved.
- Partial Floodplain, Fish Passage, and Habitat Restoration This alternative would re-route Couse Creek through an irrigation ditch, remove a fish screen in an old ditch, add an LWD revetment, remove a concrete structure in Couse Creek, regrade the Couse Creek channel bed, and add boulder clusters and small pools to the Walla Walla River. The existing municipal line would be protected.
- Fish Passage Restoration and Habitat Enhancement This alternative would partially reconnect the irrigation ditch to the main Couse Creek flow, remove the fish screen, add an LWD revetment, remove a concrete structure, regrade the Couse Creek channel bed, install roughened riffles in the mainstem Walla Walla River, and add boulder clusters and small pools. The existing municipal line would be protected.

1.5.4 30 Percent Conceptual Design

Based on the comments received on the 15 Percent Design Alternatives submittal (Tetra Tech 2017a), site survey data collected, and the analyses discussed in Section 2, Section 3, and Appendix B of the 15 Percent Design Report, Tetra Tech advanced the design to the 30 percent conceptual design stage (Tetra Tech 2017b). The review team determined that levee setbacks on the east bank increased Project complexity and risk, and should not be part of the Project. Therefore, the Partial Floodplain, Fish Passage, and Habitat Restoration Alternative was selected, with significant modifications that included realigning the lower portion of Couse Creek and measures to restore gradient and fish passage, as well as adding habitat boulders in the mainstem Walla Walla River (Tetra Tech 2017b).

It was proposed that the right bank of the abandoned Milton-Freewater ditch would be regraded to remove the push-up berm material used for the ditch and add additional floodplain material near the left bank of the existing Couse Creek near the water line crossing. The floodplain fill would have then be placed outside of the mapped floodway for the Walla Walla River as shown on the FEMA National Flood Hazard Layer for Umatilla County. Couse Creek was proposed to be rerouted to the west through the existing floodplain above the Walla Walla River, which would have increased the stream length and channel complexity. Due to the steepness of the confluence and consistent with morphology observed upstream, a step pool morphology with slopes between 2.5 percent and 1.1 percent was proposed for the channel profile. The 2.5 percent slope matched the existing channel slope upstream and would have provided fill over the exposed bedrock and clearance above the existing water line. The existing concrete wall and apron would have been removed and the right bank would be sloped back. A roughened riffle would be installed in Couse Creek to reduce scour potential in the area of the existing water line. The channel then would have transitioned to lower slopes through the floodplain and would have been consistent with the 1 percent to 4 percent slopes typically seen for alluvial fan channels (Paustian 2010). The existing Couse Creek channel would have been plugged with a log jam to simulate a jamforced avulsion. Low flows would have been maintained within the new channel and overbank flows would have been allowed to flow over the top of the log jam.

The need to install roughened riffles to raise the bed elevation of the Walla Walla River and increase channel stability was assessed, and it was determined that the riffle element would not be added to the design.

1.5.5 60 Percent Preliminary Design

Based on the comments received on the 30 Percent Conceptual Design submittal (Tetra Tech 2017b), site survey data collected, and the analyses discussed in Section 2 and Section 3, of this report, Tetra Tech advanced the design to the 60 percent preliminary design level (this submittal). The 60 Percent Preliminary Design includes the following changes to the 30 Percent Design:

Removal of Proposed LWD Structure

Based on the comments received on the 30 Percent Conceptual Design submittal (Tetra Tech 2017b), no LWD structures will be installed as a part of the 60 Percent Preliminary Design. Additional fill was added to the former Couse Creek channel where the LWD plug was proposed in the 30 percent conceptual design plans.

Addition of Floodplain Bench

A 10-foot-wide floodplain bench has been added to the roughened riffle in Couse Creek to help spread out the flow and reduce velocities.

1.6 DESCRIPTION OF PERFORMANCE / SUSTAINABILITY CRITERIA FOR PROJECT ELEMENTS AND ASSESSMENT OF RISK OF FAILURE TO PERFORM, POTENTIAL CONSEQUENCES AND COMPENSATING ANALYSIS TO REDUCE UNCERTAINTY

Performance criteria for Project elements are provided in this section. Fish passage criteria (e.g., velocities, jump height, flows) including National Marine Fisheries Service (NMFS) fish passage criteria provided in the Anadromous Salmonid Passage Facility Design (NMFS 2011) and Oregon Department of Fish and Wildlife (ODFW) fish passage criteria provided in Oregon Administrative Rules (OAR) Division 412 are presented in Table 1-2. Performance criteria for Project elements, associated risks to infrastructure or failure to perform, and compensating analyses are summarized in Table 1-3.

Fish Passage Criteria **Table 1-2**.

Fish Passage Criteria							
Criteria	NMFS ^{1/}	ODFW ^{2/}					
Category	4 - Roughened Channels	635-412-0035 (1) – Roughened Channel Fishway					
	Salmonid						
Method	Streambed Simulation Design	Stream Simulation Option					
Channel Width	Entrenched – bankfull or greater	Equal or greater than active channel width, taken from stream crossing requirements					
Channel Slope	Less than 6%	Slope of long-channel bed profile, taken from stream crossing requirements					
Max Length	150 feet	NA					
Fill Materials	An appropriate mix of bed materials (from fines to boulder sized material) are used such that flow depths of at least 1 foot can be maintained for upstream adult salmonid passage.	Natural bed material with bed retention and hydraulic shadow					
Water Depth	Resemble existing stream	At all flows, fall into a receiving pool of sufficient depth, depending on impact velocity and quantity of flow, to ensure that fish and flow shall not impact the stream bottom or other solid features					
Water Velocity	Resemble existing stream	Water velocity is greater than 2 feet per second during all flows					

NA – not applicable

^{1/} Anadromous Salmonid Passage Facility Design (National Marine Fisheries Service 2011) 2/ Oregon Department of Fish and Wildlife, Oregon Administrative Rules Division 412

 Table 1-3.
 Project Actions and Performance Criteria

Project Actions		Pertormance Criteria	KISK ASSESSMENT		compensating Analyses or Measures
Overall	•	Maintenance of a "no-rise" condition in	Changes to the baseflood elevations may require certification by the USACE and remapping of the	•	No work aside from habitat boulders is proposed within the Walla Walla River, so the proposed design is
		baseflood elevations as determined by LOMR 12-	 LEMA floodway and associated floodplain. Increases in baseflood elevations could 	•	expected to maintain a "no-rise" condition. Floodplain fill will be placed outside of the mapped
		10-1210P, effective September 20, 2013.	compromise levee freeboard or present risks to infrastructure.		floodway for the Walla Walla River as shown on the FEMA National Flood Hazard Layer for Umatilla County.
				•	Proposed conditions hydraulic modeling will be
					completed at a later design stage, and will be used to demonstrate baseflood elevations at the FEMA approved
					100-year recurrence interval flow.
Roughened Riffle	•	Riffle boulders stable to	 Potential for head cutting or avulsions in Couse 	•	Streambed aggregate will be placed and compacted in
		proposed 100-year flood	Creek channel where current water line is buried.		lifts and fines washed in until surface flow or ponding is
		hydraulic conditions.			apparent.
	•	Maintenance of surface		•	Bed stability analyses will be provided at the next design
		flow.			phase.
Habitat Boulders	•	Stable to proposed 100-	 Undersized boulders could move or become buried, 	•	Boulder sizing was based on observations of the largest,
		year flood hydraulic	but are generally a low risk.		immobile boulders present under existing conditions and
		conditions.	 Addition of large quantities of boulders can 		on sizing calculations detailed in Section 3.6.1.
			increase roughness and raise flood stage.	•	The proposed habitat boulders will be partially buried to
					the point of being completely overtopped by the 1.5-year
					flow and spaced out in a density that will not appreciable
					impact the flood flow areas thereby not increasing the
					flood stage.
Revegetation	•	Revegetation of all	 Potential for low survival. 	•	Use site appropriate native vegetation.
		disturbed areas	 Noxious weed infestations. 	•	Technical specifications for plant handling, care,
	•	12-month plant survival			installation, and survival.
		of greater than 75		•	Noxious weeds shall be monitored and removed.
		percent.			
				 -	

FEMA - Federal Emergency Management Agency, LOMR - Letter of Map Revision; USACE - United States Army Corp of Engineers

Walla Walla Basin Watershed Council

1.7 DESCRIPTION OF DISTURBANCE INCLUDING TIMING AND AREAL EXTENT AND POTENTIAL IMPACTS ASSOCIATED WITH IMPLEMENTATION OF EACH ELEMENT

Construction is anticipated to occur during the 2019 in-water work window. According to the ODFW (2008) guidelines, the in-water work window is July 1 to September 30 for the Walla Walla River and July 1 to October 31 for Couse Creek. A detailed construction schedule will be developed as a component of the implementation plan. The specific areal extent of disturbance of 1.0 acre was developed based on the results of refined construction plan designs (see Appendix A) and hydraulic modeling (see Section 3.5 and Appendix B). The developed channel slope for the regraded confluence for Couse Creek will be stable and passable for the focal fish species.

Project construction may result in temporary turbidity releases to the stream, minor impacts to resident fish populations from de-fishing activities, possible spills from construction equipment, dust transport, colonization of disturbed ground by invasive vegetation, damage to existing vegetation along designated access routes, and short-term disturbance issues for landowners.

The National Wetlands Inventory (NWI) shows two types of wetlands in the Project reach, identified as PFOA (Freshwater Forested/Shrub Wetland) and R3UBH (Riverine) along Couse Creek and along river left of the Walla Walla River (Figure 1-1) (NWI 2018). Using methods prescribed by the United States Army Corp of Engineers Wetland Delineation Manual (USACE 1987) and the Arid West Region Supplement (USACE 2008), no wetlands were discovered in the Project study area or adjacent floodplain areas.



Project Information:
Project Name:

Couse Creek Confluence Fish Passage

BPA Project #: 2007-396-00 **Contract #**: 77247

Sponsor: Walla Walla Basin Watershed Council

Designer: Tetra Tech

PM/COTR: Hannah Dondy-Kaplan

Manager: John T. Skidmore, Oregon Implementation Manager, EWL

HIP Reviewers:

Activity Categories:

HIP Program Lead: Daniel A. Gambetta, ECF EC Lead: Claire McClory, ECF

Technical Lead: Douglas D. Knapp, P.E., EWL

Risk Level:

1c - Headcut and Grade StabilizationMedium2a - Improve Secondary Channel and WetlandsMedium2c - Protect Streambanks Using Bioeng. MethodsMedium2d - Install Habitat-Forming Natural StructuresMedium

2f - Channel Reconstruction Medium

Overall Project Risk Medium

Review Information:

Date: July 27, 2018

Review Iteration (%): 60% Design Iteration

Status of Review: Compiling comments

Review Schedule: - EC Lead to perform functional review and compile comments.

- EC Lead to send comments to Sponsor.

- Sponsor to respond to comments and proceed to next design

iteration.

Agency Team Members:

NMFS Branch Chief: Dale Bambrick, NMFS, Columbia Basin Branch Chief

NMFS Reviewer: Rebecca Viray

USFWS Field Office: Gary Miller, USFWS La Grande Field Office

USFWS Reviewer: John Stephenson

Documents Reviewed:

Couse Creek Confluence Fish Passage 60% Design Document, July 2018

Couse Creek Confluence Fish Passage 60% Plans, July 2018

#	Reviewer	Date	Document	Page/	Comment	Response by	Date	Comment	Status
	(Org.)			Section		(Org.)			(BPA to Update)
1	BPA	2/15/18	General	NA	The BDR and plans are in excellent condition for 30%. Tables 1-4 and 1-5 were very helpful. Responses to the comments below are requested, but BPA approval is not required before proceeding to the next design iteration. The next design iteration of 60% to 80% is recommended (stability	(615.7)			Open (Requirement)
					calcs to be reviewed at that time). Update 7/27/18: Please provide responses to the remaining open comments.				



#	Reviewer	Date	Document	Page/	Comment	Response by	Date	Comment	Status
	(Org.)			Section		(Org.)			(BPA to Update)
2	BPA	2/15/18	BDR	Section	Recommend adding a simple	Tetra Tech	June 2018	A monitoring and adaptive	Open
				5	monitoring and adaptive management			management plan for grade control	(Requirement)
					plan due to grade control and channel			and channel alignment will be	
					alignment features that could impact			prepared and managed by the Walla	
					fish passage. If a passage barrier did			Walla Basin Watershed Council.	
					develop, an adaptive management				
					plan would provide the opportunity to				
					efficiently address the problem w/o a				
					new project and consultation.				
					Update 7/27/18: Due to the				
					importance of the grade control				
					features for the success of the project				
					and recommendations from NMFS as				
					well, please provide a monitoring and				
					adaptive management plan for the				
					grade control structures. It is				
					recommended that the structures be				
					monitored seasonally and after high				
					flow events for five years.				
3	BPA	2/15/18	BDR	Section	It is recommended that Walla Walla	Tetra Tech	June 2018	The Hydraulic Analysis Technical	Closed
				3.4	River backwater effects be analyzed			Memorandum (located in Appendix B	
					for Couse Creek channel forming			 Other Supporting Reports) details 	
					flows. The most common failure for			the sediment transport and possible	
					channel alignment designs at			shear stress in the 60% design	
					confluences is sediment transport.			iteration. The memo details the	
					Tributary channels are often designed			estimated shear stress at the new	
					to adequately handle incoming			confluence of Couse Creek and the	
					sediment. However, backwater effects			Walla Walla River and indicates that	
					from the mainstem are often ignored.			barrier issues are not anticipated.	
					During high Couse Creek flows capable			Details are also included in the design	
					of moving sediment, it is likely that			report in Section 3.6.	
					flows and stages in the Walla Walla				
					will be high as well. If the Couse Creek				
					channel is backwatered, velocity				
					decrease, sediment drops out, and the				
					stream takes a new alignment. A self-				
					sustaining sediment delta design at				
					the confluence is dynamic, but may				
					provide consistent fish passage.				



#	Reviewer (Org.)	Date	Document	Page/ Section	Comment	Response by (Org.)	Date	Comment	Status (BPA to Update)
4	BPA	2/15/18	Plans	Sheet C-201	Show water line in stream alignment profile view.	Tetra Tech	June 2018	The water line has been added to the design drawings in Appendix A on sheet C-101.	Closed
5	ВРА	2/15/18	Plans	Sheet C-305	Consider small pipe to bypass flow at existing passage barrier and concrete wall. It is unclear how the 10'+ diversion channel will fit in the narrow gap between the rock wall (left bank) and concrete wall (right bank).	Tetra Tech	June 2018	The 60% Design Iteration includes a 24" temporary bypass pipe for the construction of the roughened riffle on Sheet C-106 in Appendix A.	Closed
6	ВРА	2/15/18	Plans	C-301	All details including cut – fill, excavations and areal disturbance boundaries should prescribe material, compaction and finished surface requirements. Specifically how are exposed construction surfaces to be treated for erosion control, vegetation salvage and revegetation. These locations should reference the applicable project specifications.	Tetra Tech	June 2018	The 60% design drawings include instructions for the erosion and sedimentation control measures. See Appendix A, Sheets C-101 and C-105 for location of best management practices (BMPS) and temporary erosion and sediment control (TESC). In addition, specifications for TESC can be found in Appendix D – Technical Specifications. Channel and floodplain grading compaction specifications can be found in Section 31 23 00 of Appendix D – Technical Specifications. The planting plan in Appendix A, Sheets L-100 & L-101 contains instructions on vegetation salvage and revegetation.	Closed
7	ВРА	2/15/18	Plans	NA	Please provide a planting plan, erosion and sedimentation control plan, and stormwater treatment plan in a future design iteration Update 7/27/18: Concur that stormwater plan not needed.	Tetra Tech	June 2018	The planting plan is found in the 60% design drawings (Appendix A) on Sheets L-100 & L-101, and the erosion and sedimentation control plan is found in the design drawings (Appendix A) on Sheets C-101 and C-105.	Closed



#	Reviewer (Org.)	Date	Document	Page/ Section	Comment	Response by (Org.)	Date	Comment	Status (BPA to Update)
8	ВРА	2/15/18	Plans	NA	Please provide a dewatering, rewatering and fish salvage plan in the plan sheets in later design iteration.	Tetra Tech	June 2018	The instructions for dewatering and rewatering can be found in the design drawings (Appendix A) on Sheet C-106. Fish salvage plans design drawings on Sheets C-106. Fish salvage instructions are located on Sheets G-004 and G-005.	Closed
9	ВРА	2/15/18	Plans	C-203	What shall the resultant jump height of the boulder weirs be during flow flow conditions? < 6 inches is required for juvenile fish passage.	Tetra Tech	June 2018	A Hydraulic Analysis Technical Memorandum detailing the water surface elevation at boulder sills is included in the 60% Design Iteration (Appendix B – Other Supporting Reports). Jump heights at high fish flows are at or less than 0.5 feet. Further details are also located in the design report in Section 3.6.3.	Closed
10	ВРА	2/15/18	Plans	C-301	The plans need to include a compaction and material specification to be applied to all locations where fill is to be placed including LWD ballast and excavation locations should prescribe post material removal surface treatments.	Tetra Tech	June 2018	LWD has been removed from designs. Channel and floodplain grading compaction specifications can be found in Section 31 23 00 of Appendix D – Technical Specifications.	Closed
11	ВРА	2/15/18	Plans	NA	Staging areas shall be located 150 feet from streams and wetlands. Update 7/27/18: Note that natural materials (bed material, wood, etc.) can be stored within 150 feet if clearly identified in the plans. Equipment, machinery, fuel, etc. must all be staged greater than 150 feet.	Tetra Tech	June 2018	The access and staging areas are proposed to be sited along the south side of Jorgenson Lane, an established road that is in a location more than 150 feet from the Walla Walla River. This location precludes erosion and contamination of either the Walla Walla River or Couse Creek. The location is provided in Appendix A, Sheet C-100.	Closed



#	Reviewer (Org.)	Date	Document	Page/ Section	Comment	Response by (Org.)	Date	Comment	Status (BPA to Update)
12	BPA	2/15/18	Plans	C-203	Boulder weirs should be placed diagonally across the channel or in upstream pointing "V" or "U" configurations (with the apex oriented upstream). The apex should be lower in elevation than the structure wings to support low flow consolidation.	Tetra Tech	June 2018	The designs for the roughened riffle show a V shape with a lowered apex elevation. They are located in Appendix A on sheet C-103.	Closed
13	ВРА	2/15/18	Plans	C-203	Please show 1.5-year event in profile to demonstrate that boulders will be topped by 1.5- year event.	Tetra Tech	June 2018	2-year water surface elevation added to the riffle rock detail in Appendix A, Sheet C-104.	Closed
14	ВРА	7/27/18	Plans	C-103	What are the large boulders parallel to flow in the roughened riffle plan view on the east side of the channel? Are these needed to protect the pipe? Information needed to determine necessity.	Tetra Tech	October 2018	The design for the roughened riffle includes boulders in the fill material in the existing Couse Creek channel to provide stability and erosion protection during high flows to maintain fish passage as well as protecting the existing infrastructure (i.e., the pipe). In the 90% design the layout of the boulders will be changed to function as both habitat boulders and help the backfilled channel to resist erosion and protect the existing infrastructure. Hydraulic modeling and stability calculations were reevaluated during this 90 percent design phase. The roughened riffle boulders will remain at 3 ft diameter. The step boulders will be increased to 4 ft diameter to resist the additional shear stresses generated at the toe of the steps as compared to the roughened riffle over the existing pipeline.	Request Additional Information
15	NMFS	2/21/18	BDR	NA	NMFS agrees there are great benefits for a Adaptive Management plan related to the grade control and alignment.	Tetra Tech	June 2018	A monitoring and adaptive management plan for grade control and channel alignment will be prepared and managed by the Walla Walla Basin Watershed Council.	Open (Recommendation)





#	Reviewer (Org.)	Date	Document	Page/ Section	Comment	Response by (Org.)	Date	Comment	Status (BPA to Update)
16	NMFS	2/21/18	BDR	NA	NMFS wants to emphasis the importance of the sediment transport and hydrological modeling of the Walla Walla River and impacts to Crouse Creek . Several past projects resulted in unplanned additional work needed when dynamic flows of the Walla Walla created scours or barrier issues not anticipated.	Tetra Tech	June 2018	The Hydraulic Analysis Technical Memorandum (Appendix B – Other Supporting Reports) details the sediment transport and possible shear stress in the 60% design iteration. The memo details the estimated shear stress at the new confluence of Couse Creek and the Walla Walla River and indicates that barrier issues are not anticipated. Details are also included in the design report in Section 3.6.2.	For Information Only
17	NMFS – Hydro	10/17/18		NA	I was not able to find any info (I may have missed it somewhere in the document) which details the particle size distribution of the material used in the grade control structures. This data is a key conversation point I would like to address. I think in general I'm comfortable with the approach being used so conceptually I don't have any concerns. I do want to dig deeper into the size and amount of rock being used in the design and how it will be installed.	Tetra Tech	October 2018	Section 35 49 50 in the Project Specifications specifies the gradations for Boulders, Streambed Cobble, Streambed Sediment, and Scour Protection Material. As described in Section 35 49 50 in the Project Specifications and will be included in the 90 percent design Implementation Plan, streambed cobble and streambed sediment shall be placed and compacted in lifts. Fines shall be washed in for each lift until voids within the placed matrix are minimized such that ponding occurs with little to no percolation losses to keep the introduced water on the surface and avoid the creek going subsurface. The 60% Basis of Design report included discussion on the roughened riffle boulder sizing and Attachment B included the calculations. For the 90% design, the step boulders were evaluated separately and sized to be 4 ft min. A revised calculation for the roughened riffle and step boulders is	Open (Requirement)





#	Reviewer (Org.)	Date	Document	Page/ Section	Comment	Response by (Org.)	Date	Comment	Status (BPA to Update)
								being provided with this comment tracking using the two methods described in the 60% Basis of Design report.	

COUSE CREEK CONFLUENCE FISH PASSAGE WALLA WALLA BASIN WATERSHED COUNCIL 60 PERCENT DESIGN











www.tetratech.com 19803 North Creek Parkway Bothell, Washington 98011 e: 425-482-7600 Fax: 425-482-7652 **TETRA TECH**

(00-5		CREATED:		SHEET:
60 PERCENT DESIGN				COVER SHEET	
APP			CEB	괴	3
ENG			JSA	CEB	JSA
DRW			JSA	VSC	JSA
REVISION DESCRIPTION			60 PERCENT DESIGN	30 PERCENT DESIGN	15 PERCENT CONCEPTUAL DESIGN
DATE			7/2/18	1/8/18	10/31/17
REV.		_	o	8	⋖



H • 0	ALLA RIVER AND JULY 1 TO OCTOBER 31 FOR TROST. R WORK AREAS. PRIFILES. AND BOULDERS. ALS SUBJECT TO APPROVAL BY LANDOWNER. ALS SUBJECT TO APPROVAL BY LANDOWNER. MENTS IN ACCORDANCE WITH THE PLANS STAMPED E CONTRACTOR BY THE CONTRACTION AGENCY URRENT SET OF APPROVED CONSTRUCTION OF CONTRACTOR BY THE CONTRACTOR BY THE CONTRACTOR OF AMAN AND AND AND AND AND AND AND AND AND A
*	BEFORE IN-WATER WORK WINDOW (PRIOR TO JULY 1): • MOBILIZE TO SITE AND SITE PREPARATION. • INSTALL TESC. • EXCANATE CHANNEL AND FLOODPLAIN ABOVE OHW. INSTALL TESC. • EXCANATE WORK WINDOW (JULY 1 TO SEPTEMBER 30 FOR THE WALLA WOUGUSE CREEK): • SALVAGE FISH (WORK TO BE COMPLETED BY OUTSIDE PARTY/OTHE • INSTALL AND MONITOR TESC, WORK AREA ISOLATION AND DEWATE • INSTALL AND MONITOR TESC, WORK AREA ISOLATION AND DEWATE • CONS TRUCT CHANNEL AND FLOODPLAIN BELOW OHW, ROUGHENER • COMPLETE ANY EXCAVATION REMAINING ABOVE OHW. • REVEGETATE ALL DISTURBED AREAS. • SITE CLEAN-UP AND DEMOBILIZATION. • REVEGETATE ALL DISTURBED AREAS. • SITE CLEAN-UP AND DEMOBILIZATION. • REVEGETATE ALL DISTURBED AREAS. • SITE CLEAN-UP AND DEMOBILIZATION. • REVEGETATE ALL DISTURBED AREAS. • SITE CLEAN-UP AND DEMOBILIZATION. • REVEGETATE ALL DISTURBED AREAS. • SITE CLEAN-UP AND DEMOBILIZATION. • REVEGETATE ALL DISTURBED AREAS. • SITE CLEAN-UP AND DEMOBILIZATION. • REVEGETATE ALL DISTURBED AREAS. • SITE CLEAN-UP AND DEMOBILIZATION. • THE CONTRACTOR SHALL CONSTRUCTION ACTIVITIES, AND MATERIA PROPOSED PROJECT DESIGN, CONSTRUCTION WORK SHALL CONTRACTOR SHALL CONTRACTOR SHALL CONTRACT THE RESTORATION DESIGN ELENS. • THE CONTRACTOR SHALL CONTRACT THE RESTORATION USE SERVING THE CONTRACTOR SHALL CONTRACT THE ORDER SHALL OF SHALL CONTRACT THE CONTRACTOR SHALL CONTRACT THE CHANNEL SHALL OCCURE WITHIN THE ACTIVITIES SHALL MINIMIZE DISTURBANCE TO AND CHOSEN SHALL PROJECT. • SEPTEMBER 30) AND COUSE CREEK (JULY 1 - OCTOBER 31). • ALL CONSTRUCTION ACTIVITIES SHALL MINIMIZE DISTURBANCE TO AND THE CONTRACTOR SHALL PROVIDE AND SCIENK (JULY 1 - OCTOBER 31). • ALL CONTRACTOR SHALL PROVIDE AN ERCOSION AND SEDIMENT CONTRACTOR SHALL PROVIDE OF OCCURE SHALL
√ 0	MAXIMUM MILE MINIMUM MAJOR MINIMUM MAJOR MINIMUM MAJOR MINIMUM MINIMUM MINIMUM MINIMUM MINIMUM MINIMUM MATIONAL HAREICAN VERTICAL DATUM OF 1988 NATIONAL HAREICAN OF RESENVICE NOT TO SCALE PULSED DIRECT CURRENT OREGON DEPARTMENT OF FISH AND WILDLIFE OREGON WATER RESOURCES DEPARTMENT PROPOSED TEMPORARY TEMPORARY TEMPORARY TEMPORARY TEMPORARY TOTICS UNITED STATES FORES FISH AND WILDLIFE SERVICE VOLTS VOLTS VOLTS VOLTS WITH WASHINGTON DEPARTMENT OF FISH AND WATH WASHINGTON DEPARTMENT OF FISH AND WATH WASHINGTON DEPARTMENT TEMPORARY TO THE STATES FISH AND WITH WASHINGTON DEPARTMENT TO THE STATES FISH AND WITH WASHINGTON TO T
B B	ABBREVATIONS MINEROSONIAL TOVERTICAL EXAGGERATION MINERO SECONDS PER CENTIMETER MINERO SECONDS MINEROS INSTITUTE MINERO SECONDS MINEROS INSTITUTE MINEROS COLUMENT MINE

DOCUMENTATION: TO BE POSTED ONSITE BY THE CONTRACTOR IN A LOCATION VISIBLE TO THE PUBLIC:

- A) NAME(S), PHONE NUMBER(S), AND ADDRESS(ES) OF PERSON(S) RESPONSIBLE FOR OVERSIGHT.

 B) A DESCRIPTION OF HAZARDOUS MATERIALS THAT WILL BE USED, INCLUDING INVENTORY, STORAGE, AND HANDLING PROCEDURES.
- C) PROCEDURES TO CONTAIN AND CONTROL A SPILL OF ANY HAZARDOUS MATERIAL GENERATED, USED OR STORED ON-SITE, INCLUDING NOTIFICATION OF PROPER AUTHORITIES.
- A STANDING ORDER TO CEASE WORK IN THE EVENT OF HIGH FLOWS EXCEPT AS NECESSARY TO MINIMIZE RESOURCE DAMAGE (ABOVE THOSE ADDRESSED IN THE DESIGN AND IMPLEMENTATION PLANS) OR EXCEEDANCE OF TAKE OR WATER QUALITY LIMITATIONS.

NSPECTIONS AND MONITORING: PROJECT SPONSOR STAFF OR THEIR DESIGNATED REPRESENTATIVE WILL PROVIDE IMPLEMENTATION MONITORING TO ENSURE COMPLIANCE WITH THIS BIOLOGICAL OPINION, INCLUDING:
A) GENERAL CONSERVATION MEASURES AND PROJECT DESIGN CRITERIA ARE ADEQUATELY FOLLOWED; AND

EFFECTS TO ESA-LISTED SPECIES ARE NOT GREATER THAN PREDICTED AND TAKE LIMITATIONS ARE NOT EXCEEDED

€ B

HIP III GENERAL AQUATIC CONSERVATION MEASURES APPLICABLE TO ALL ACTIONS:
THE ACTIVITIES COVERED UNDER THE HIP III ARE INTENDED TO PROTECT AND RESTORE FISH AND WILDLIFE HABITAT WITH LONG-TERM
BENEFITS TO ESA-LISTED SPECIES, HOWEVER, CONSTRUCTION ACTIVITIES MAY HARE SHORT-TERM ADVERSE EFFECTS ON ESA-LISTED
SPECIES AND ASSOCIATED CRITICAL HABITAT. TO AVOID AND MINIMEST THESE WHOTH TERM ADVERSE EFFECTS, BPA HAS DEVELOPED THE
FOLLOWING GENERAL CONSERVATION MEASURES IN COORDINATION WITH USFWS AND NIMES. THESE MEASURES WILL BE IMPLEMENTED ON ALL PROJECTS COVERED UNDER THE HIP III.

CLIMATE CHANGE: BEST AVAILABLE SCIENCE REGARDING THE FUTURE EFFECTS WITHIN THE PROJECT AREA OF CLIMATE CHANGE, SUCH AS CHANGES INSTREAM FLOWS AND WATER TEMPERATURES, WILL BE CONSIDERED DURING PROJECT DESIGN

STATE AND FEDERAL PERMITS: ALL APPLICABLE REGULATORY PERMITS AND AUTHORIZATIONS WILL BE OBTAINED PRIOR TO PROJECT IMPLEMENTATION, THES PERMITS AND AUTHORIZATIONS INCLUDE, BUT ARE NOTLIMITED TO, THE NATIONAL ENVIRONMENTAL POLICY ACT (NEPA), NATIONAL HISTORIC PRESERVATION ACT (NHPA), STATE AND FEDERAL SECTION 404 OF THE CLEAN WATER ACT (CWA) PERMITS, AND SECTION 401 WATER QUALITY CERTIFICATIONS.

TIMING OF IN-WATER WORK: FORMAL RECOMMENDATIONS PUBLISHED BY STATE AGENCIES SUCH AS THE OREGON DEPARTMENT OF FISH AND WILDLIFE (ODPO), WASHINGTON DEPARTMENT OF FISH AND WILDLIFE (OMPO), DAHO DEPARTMENT OF FISH AND GAME (IDFG), AND MONTAM, FISH WILDLIFE AND PARKS (MFWP) OR INFORMAL RECOMMENDATIONS FROM THE APPROPRIATE STATE FISHERY BIOLOGIST IN REGARD TO THE TIMING OF IN-WATER WORK WILL BE FOLLOWED.

- A) BULL TROUT UTILIZING STATE-RECOMMENDED IN-WATER WORK WINDOWS WILL DECREASE POTENTIAL EFFECTS TO BULL TROUT, BUT THIS ALOUR MAY NOT BE SUFFICIALT TO PROTECT LOCAL BULL TROUT POULATIONS. THIS IS SEPECIALLY TRUE IF WORK WILL COCUR IN SPAWMING AAD REARING AREAS BECAUSE EGGS, ALEVIN, AND FRY ARE PRESENT INEXLY YEAR ROUND. SOME PROJECT LOCATIONS MAY NOT HAVE DESIGNATED IN-WATER WORK WINDOWS FOR BULL TROUT, OR IF THE YOODS DEVING IS TO COCUR WITHIN BULL TROUT SPAWMING AND SEAMMON AND STEELEMEAD. IF THIS IS THE THE ROPOSED WORK IS TO COCUR WITHIN BULL TROUT SPAWMING AND REARING HABITATS. THE PROJECT SPONSOR WILL CONTACT THE APPROPRIATE USFAYS FIELD OFFICE TO ENSIRE THAT ALL REASONABLE IMPLEMENTATION MEASURES ARE CONSIDERED AND AN APPROPRIATE IN-WATER WORK WINDOW IS
 - B) LAMPREY THE PROJECT SPONSOR AND/OR THEIR CONTRACTORS WILL AVOID WORKING INSTREAM OR RIVER CHANNELS THAT CONTAIN PACIFIC LAMPREY FROM MARCH 10 JULY 1 IN LOW-10 MID-ELEVATION REACHES (-5,000 FEET). IN HIGHELEVATION REACHES (-5,000 FEET). IN HIGHELEVATION REACHES (-5,000 FEET). THE PROJECT SPONSOR WILL AVOID WORKING INSTREAM OR RIVER CHANNELS FROM MARCH 1 TO AUGUST 1. FEITHER TIMEFRAME IS INCOMPATIBLE WITH OTHER OBJECTIVES. THE AREA WILL BE SURVEYED FOR NESTS AND LAMPREY PRESENCE, AND AVOIDED IF POSSIBLE. IF LAMPREYS ARE KNOWN TO EXIST, THE PROJECT SPONSOR WILL UTILIZE DEWATERING AND SALVAGE BEST MANAGEMENT PRACTICES (BMPS) OUTLINED IN USFWS 2010. BEING USED TO MINIMIZE PROJECT EFFECTS.
 - C) EXCEPTIONS TO ODFW, WDPW, MFWP, OR IDFG IN-WATER WORK WINDOWS WILL BE REQUESTED THROUGH THE VARBANCE PROCESS (PAGE 22 OF THE MOST RECENT HIPII HANDBOOK), WORK AREA ISOLATION AND FISH SALVAGE ACTIVITIES ARE CONSIDERED INCIDENTAL TO CONSTRUCTION-RELATED ACTIVITIES AND SALLALL OCCUR DURING STATE-RECOMMENDED IN-WATER WORK WINDOWS.

CONTAMINANTS: THE PROJECT SPONSOR WILL COMPLETE A SITE ASSESSMENT WITH THE FOLLOWING ELEMENTS TO IDENTIFY THE TYPE, QUANTITY, AND EXTENT OF ANY POTENTIAL CONTAMINATION FOR ANY ACTION THAT INVOLVES EXCAVATION OF MORE THAN 20 CUBIC YARDS OF MATERIAL:

- A) A REVIEW OF AVAILABLE RECORDS, SUCH AS FORMER SITE USE, BUILDING PLANS, AND RECORDS OF ANY PRIOR CONTAMINATION
- C) INTERVIEWS WITH KNOWLEDGEABLE PEOPLE, SUCH AS SITE OWNERS, OPERATORS, AND OCCUPANTS, NEIGHBORS, OR LOCAL GOVERNMENT OFFICIALS, AND B) A SITE VISIT TO INSPECT THE AREAS USED FOR VARIOUS INDUSTRIAL PROCESSES AND THE CONDITION OF THE PROPERTY;
- A SUMMARY, STORED WITH THE PROJECT FILE THAT INCLUDES AN ASSESSMENT OF THE LIKELIHOOD THAT CONTAMINANTS ARE PRESENT AT THE SITE, BASED ON ITEMS 4(A) THROUGH 4(C). â

SITE LAYOUT AND FLAGGING: PRIOR TO CONSTRUCTION, THE PROJECT AREA WILL BE CLEARLY FLAGGED TO IDENTIFY THE FOLLOWING:



CONSTRUCTION NOT FOR

TETRA TECH 19803 North Creek Parkway Bothell, Washington 98011 425-482-7600 Fax: 425-482-7652

A) SENSITIVE RESOURCE AREAS, SUCH AS AREAS BELOW ORDINARY HIGH WATER (OHW), SPAWNING AREAS, SPRINGS, AND WETLANDS;
B) EQUIPMENT ENTRY AND EXIT POINTS;
C) ROAD AND STREAM CROSSING ALIGNMENTS;

TEMPORARY ACCESS ROADS AND PATHS

- A) EXISTING ACCESS ROADS AND PATHS WILL BE PREFERENTALLY USED WHENEVER POSSIBLE, AND THE NUMBER AND LENGTH OF TEMPORARY ACCESS ROADS AND PATHS THROUGH RIPARIAN AREAS AND FLOODPLAINS WILL BE MINIMIZED TO LESSEN SOIL DISTURBANCE, SOIL COMPACTION, AND IMPACTS TO VEGETATION.
- B) TEMPORARY ACCESS ROADS AND PATHS WILL NOT BE BUILT ON SLOPES WHERE GRADE, SOIL, OR OTHER FEATURES SUGGEST A LIKELIHOOD OF EXCESSIVE EROSION OR FAILURE. IF SLOPES ARE STEEPER THAN 30%, THE ROAD WILL BE DESIGNED BY A CIVIL ENGINEER WITH EXPERIENCE IN STEEP ROAD DESIGN.
 - C) THE REMOVAL OF RIPARIAN VEGETATION DURING CONSTRUCTION OF TEMPORARY ACCESS ROADS WILL BE MINIMIZED. WHEN TEMPORARY VEGETATION REMOVAL IS REQUIRED, VEGETATION WILL BE CUT AT GROUND LEVEL (NOT GRUBBED).
- D) AT PROJECT COMPLETION, ALL TEMPORARY ACCESS ROADS AND PATHS WILL BE OBLITERATED, AND THE SOIL WILL BE STABILIZED AND REVEGETATED. ROAD AND ANTH OBLITERATION REFERS TO THE MOST COMPREHENSIVE DEGREE OF DECOMMISSIONING AND INVOLVES DECOMPACTING THE ROAD SURFACE AND ASSOCIATED DITCHES, PULLING THE FILL MATERIAL ONTO THE RUNNING SURFACE, AND RESHAPING TO MATCH THE ORIGINAL CONTOUR.

 E) TEMPORARY ROADS AND PATHS IN WET AREAS OR AREAS PRONE TO FLOODING WILL BE OBLITERATED BY THE END OF THE IN-WATER

TEMPORARY STREAM CROSSINGS:

- A) EXISTING STREAM CROSSINGS WILL BE PREFERENTIALLY USED WHENEVER REASONABLE, AND THE NUMBER OF TEMPORARY STREAM CROSSINGS WILL BE MINIMIZED.

 B) TEMPORARY BRIDGES AND CULVERTS WILL BE INSTALLED TO ALLOW FOR EQUIPMENT AND VEHICLE CROSSING OVER PERENNIAL
 - STREAMS DURING CONSTRUCTION. TREATED WOOD SHALL NOT BE USED ON TEMPORARY BRIDGE CROSSINGS OR IN LOCATIONS IN CONTACT WITH OR OVER WATER.
- C) EQUIPMENT AND VEHICLES WILL CROSS STREAMS IN THE WET ONLY WHERE
 - I. THE STREAMBED IS BEDROCK: OR
- II. MATS OR OFF-SITE LOGS ARE PLACED IN THE STREAM AND USED AS A CROSSING.
- D) VEHICLES AND MACHINERY WILL CROSS STREAMS AT RIGHT ANGLES TO THE MAIN CHANNEL WHEREVER POSSIBLE. E) THE LOCATION OF THE TEMPORARY CROSSING WILL AVOID AREAS THAT MAY INCREASE THE RISK OF CHANNEL RE-ROUTING OR
- F) IMPACTS TO POTENTIAL SPAWNING HABITAT (I.E., POOL TAILOUTS) AND POOLS WILL BE AVOIDED TO THE MAXIMUM EXTENT POSSIBLE. G) NO STREAM CROSSINGS WILL COCUR AT ACTIVE PRAYMINING SITES, WHEN HOLDING ADULT LISTED FISH ARE PRESENT. OR WHEN EGGS OR ALEVINS ARE IN THE GRAVIEL. THE APPROPRIATE STATE FISH AND WILDIER AGENCY WILL BE CONTACTED FOR SPECIFIC TIMING
- H) AFTER PROJECT COMPLETION, TEMPORARY STREAM CROSSINGS WILL BE OBLITERATED, AND THE STREAM CHANNEL AND BANKS

STAGING, STORAGE, AND STOCKPILE AREAS:

INFORMATION.

- A) STAGING AREAS (USED FOR CONSTRUCTION EQUIPMENT STORAGE, VEHICLE STORAGE, FUELING, SERVICING, AND HAZARDOUS MATERIAL STORAGE) WILL BE 150 FEET OR MORE FROM ANY NATURAL WATER BOLV OR WETTAND, OR ON AN ADJACENT, ESTABLISHED ROAD AREA IN A LOCATION AND MAINER THAT WILL PRECUDE REOSION INTO OR CONTAMINATION OF THE STREAM OF FLOODPLAN.
 - NATURAL MATERIALS USED FOR IMPLEMENTATION OF AQUATIC RESTORATION, SUCH AS LARGE WOOD, GRAVEL, AND BOULDERS, MAY BE STAGED WITHIN THE 100-YEAR FLOODPLAIN.
- C) ANY LARGE WOOD, TOPSOIL, AND NATIVE CHANNEL MATERIAL DISPLACED BY CONSTRUCTION WILL BE STOCKPILED FOR USE DURING SITE RESTORATION AT A SPECIFICALLY IDENTIFIED AND FLAGGED AREA.
 - D) ANY MATERIAL NOT USED IN RESTORATION, AND NOT NATIVE TO THE FLOODPLAIN, WILL BE REMOVED TO A LOCATION OUTSIDE OF THE 100-YEAR FLOODPLAIN FOR DISPOSAL.

101100	COOSE		ď	<u></u>
	АРР		CEB	징
	DRW ENG		JSA	CEB
	DRW		JSA	1SA
LEGILLED AND THE ALL ALL ALL ALL SEE AND DIEZ AD A	REVISION DESCRIPTION		60 PERCENT DESIGN	30 PERCENT DESIGN
	DATE		772/18	1/8/18
	REV.		O	В

G-003

CREATED: SHEET:

HIP III GENERAL CONSERVATION MEASURES APPLICABLE TO ALL ACTIONS (CONTINUED);

EQUIPMENT: MECHANIZED EQUIPMENT AND VEHICLES WILL BE SELECTED, OPERATED, AND MAINTAINED IN A MANNER THAT MINIMIZES ADVERSE EFFECTS ON THE ENVIRONMENT (F.G. MINIMALLY-SIZED, LOW PRESSURE TIRES, MINIMAL, HARD-TURN PATHS FOR TRACKED VEHICLES: TEMPORARY MATS OR PLATES WITHIN WET AREAS OR ON SENSITIVE SOILS), ALL VEHICLES AND OTHER MECHANIZED EQUIPMENT WILL BE:

SPILL CONTAINMENT KITS (INCLUDING INSTRUCTIONS FOR CLEANUP AND DISPOSAL) ADEQUATE FOR THE TYPES AND QUANTITY OF

WRITTEN PROCEDURES FOR NOTIFYING ENVIRONMENTAL RESPONSE AGENCIES WILL BE POSTED AT THE WORK SITE.

E) ANY WASTE LIQUIDS GENERATED AT THE STAGING AREAS WILL BE TEMPORARILY STORED UNDER AN IMPERVIOUS COVER, SUCH AS A TARPAULIN, UNTIL THEY CAN BE PROPERLY TRANSPORTED TO AND DISPOSED OF AT A FACILITY THAT IS APPROVED FOR

RECEIPT OF HAZARDOUS MATERIALS.

U) WORKERS WILL BE TRAINED IN SPILL CONTAINMENT PROCEDURES AND WILL BE INFORMED OF THE LOCATION OF SPILL
CONTAINMENT KITS.

HAZARDOUS MATERIAL USED AT THE SITE WILL BE AVAILABLE AT THE WORK SITE

A) PRIOR TO ENTERING THE SITE, ALL VEHICLES AND EQUIPMENT WILL BE POWER-WASHED, ALLOWED TO FULLY DRY, AND INSPECTED TO MAKE SURE NO PLANTS, SOIL, OR OTHER ORGANIC MATERIAL ADHERES TO THE SURFACE.

B) WATERCRAFT, WADERS, BOOTS, AND ANY OTHER GEAR TO BE USED IN OR NEAR WATER WILL BE INSPECTED FOR AQUATIC INVASIVE SPECIES. WADING BOOTS WITH FELT SOLES ARE NOT TO BE USED DUE TO THEIR PROPENSITY FOR AIDING IN THE TRANSFER OF INVASIVE SPECIES.

INVASIVE SPECIES CONTROL: THE FOLLOWING MEASURES WILL BE FOLLOWED TO AVOID INTRODUCTION OF INVASIVE PLANTS AND NOXIOUS WEEDS INTO PROJECT AREAS.

- A) STORED, FUELED, AND MAINTAINED IN A VEHICLE STAGING AREA PLACED 150 FEET OR MORE FROM ANY NATURAL WATERBODY OR WETLAND, OR ON AN ADJACENT, ESTABLISHED ROAD AREA
 - ISOLATED HARD ZONE, SUCH AS A PAVED PARKING LOT OR ADJACENT, ESTABLISHED ROAD (THIS MEASURE APPLIES TO ONLY GAS-POWERED EQUIPMENT WITH TANKS LARGER THAN 5 GALLONS); OR IN AN B) REFUELED IN A VEHICLE STAGING AREA PLACED 150 FEET OR MORE FROM A NATURAL WATERBODY OR WETLAND,
- C) BIODEGRADABLE LUBRICANTS AND FLUIDS SHOULD BE USED, IF POSSIBLE, ON EQUIPMENT OPERATING IN AND ADJACENT TO THE INSPECTED DAILY FOR FLUID LEAKS BEFORE LEAVING THE VEHICLE STAGING AREA FOR OPERATION WITHIN 150 FEET OF ANY STREAM CHANNEL AND LIVE WATER;

ш

THOROUGHLY CLEANED BEFORE OPERATION BELOW ORDINARY HIGH WATER, AND AS OFTEN AS NECESSARY DURING OPERATION, TO REMAIN GREASE FREE. NATURAL WATER BODY OR WETLAND; AND

EROSION CONTROL: EROSION CONTROL BEST MANAGEMENT PRACTICES (BMPS) WILL BE PREPARED AND CARRIED OUT, COMMENSURATE IN SCOPE WITH THE ACTION, THAT MAY INCLUDE THE FOLLOWING:

A) TEMPORARY EROSION CONTROL BMPS

- TEMPORARY EROSION CONTROL BMPS WILL BE IN PLACE BEFORE ANY SIGNIFICANT ALTERATION OF THE ACTION SITE AND APPROPRIATELY INSTALLED DOWNSLOPE OF PROJECT ACTIVITY WITHIN THE RIPARIAN BUFFER AREA UNTIL SITE REHABILITATION
- THERE IS A POTENTIAL FOR ERODED SEDIMENT TO ENTER THE STREAM, SEDIMENT BARRIERS WILL BE INSTALLED AND MAINTAINED FOR THE DURATION OF PROJECT IMPLEMENTATION. =

WHEN WORK AREA ISOLATION IS REQUIRED, DESIGN PLANS WILL INCLUDE ALL ISOLATION ELEMENTS, FISH RELEASE AREAS, AND, WHEN A PUMP IS USED TO DEWATER THE ISOLATION AREA AND FISH ARE PRESENT. A FISH SCREEN THAT MEETS MMFSS FISH SCREEN CRITERA (MMFS 2011, OR MOST CURRENT), WORK AREA SOLATION AND FISH CAPTURE ACTIVITIES WILL OCCUR DURING PERIODS OF THE COOLEST ARE AND WATER TEMPERATURES POSSIBLE. NORMALL YEARLY IN THE MORNING VERSUS LATE IN THE DAY, AND DURING CONDITIONS APPROPRIATE TO MINIMIZE STRESS AND DEATH OF SPECIES PRESENT.

FOR SALVAGE OPERATIONS IN KNOWN BULL TROUT SPAWNING AND REARING HABITAT, ELECTROFISHING SHALL ONLY OCCUR FROM MAY 1 TO JULY 31. NO ELECTROFISHING WILL OCCUR IN ANY BULL TROUT OCCUPIED HABITAT AFTER AUGUST 15. BULL TROUT ARE VERY TEMPERATURES ENDER SENSITIVE AND GENERALLY SHOULD NOT BE ELECTROFISHED OR OTHERWISE HANDLED WHEN TEMPERATURES EXCEED 15 DEGREES CELSIUS. SALVAGE ACTIVITIES SHOULD TAKE PLACE DURING PERIODS OF THE COOLEST AR AND WATER TEMPERATURES SHOULD TAKE PLACE DURING PERIODS OF THE COOLEST AR AND WATER TEMPERATURES DURING SHOULD THE DAY, AND DURING CONDITIONS APPROPRIATE TO

MINIMIZE STRESS TO FISH SPECIES PRESENT

ANY WORK AREA WITHIN THE WETTED CHANNEL WILL BE ISOLATED FROM THE ACTIVE STREAM WHENEVER ESA-LISTED FISH ARE REASONABLY CERTAIN TO BE PRESENT, OR I THE WORK AREA IS LESS THAN 300 FEET UNSTREAM FROM MINOWN SPANING HABITATS. WORK AREA ISOLATION & FISH SALVAGE ACTIVITIES ARE CONSIDERED INCIDENTAL TO CONSTRUCTION-RELATED ACTIVITIES AND SHALL

OCCUR DURING THE STATE-RECOMMENDED IN-WATER WORK WINDOWS

WORK AREA ISOLATION & FISH SALVAGE:

- TEMPORARY EROSION CONTROL MEASURES MAY INCLUDE FIBER WATTLES, SILT FENCES, JUTE MATTING, WOOD FIBER MULCH AND SOIL BINDER, OR GEOTEXTILES AND GEOSYNTHETIC FABRIC. \equiv
 - SOIL STABILIZATION UTILIZING WOOD FIBER MULCH AND TACKIFIER (HYDRO-APPLIED) MAY BE USED TO REDUCE EROSION OF BARE SOIL IF THE MATERIALS ARE NOXIOUS WEED-FREE AND NONTOXIC TO AQUATIC AND TERRESTRIAL ANIMALS, SOIL MICROORGANISMS, AND VEGETATION. ≥
- SEDIMENT WILL BE REMOVED FROM EROSION CONTROL BMP ONCE IT HAS REACHED 1/3 OF THE EXPOSED HEIGHT OF THE BMP. ONCE THE SITE IS STABILIZED FOLLOWING CONSTRUCTION, TEMPORARY EROSION CONTROL BMPS WILL BE REMOVED $\geq_{i} \geq_{i}$
- B) EMERGENCY EROSION CONTROL BMPS. THE FOLLOWING MATERIALS FOR EMERGENCY EROSION CONTROL WILL BE AVAILABLE AT
- A SUPPLY OF SEDIMENT CONTROL MATERIALS; AND
- AN OIL-ABSORBING FLOATING BOOM WHENEVER SURFACE WATER IS PRESENT.

DUST ABATEMENT: THE PROJECT SPONSOR WILL DETTERMINE THE APPROPRATE DUST CONTROL MEASURES (IF NECESSARY) BY CONSIDERING SOIL TYPE, EQUIPMENT USAGE, PREVALING WIND DIECTION, AND THE EFFECTS CAUSED BY OTHER EROSION AND SEDIMENT CONTROL MEASURES. IN ADDITION, THE FOLLOWING CRITERA WILL BE FOLLOWED:

WORK WILL BE SEQUENCED AND SCHEDULED TO REDUCE EXPOSED BARE SOIL SUBJECT TO WIND EROSION.

€

- LIGNINSULFONATE) WILL NOT BE APPLIED WITHIN 25 FEET OF WATER OR STREAM CHANNELS AND WILL BE APPLIED SO AS TO MINIMIZE THE LIKELIHOOD THAT THEY WILL ENTER STREAMS, APPLICATIONS OF LIGNINSULFONATE WILLE ELIMITED TO A MAXIMUM RATE OF 0.5 GALLONS PER SQUARE YARD OF ROAD SUFFACE, ASSUMING A 8050 (LIGNINSULFONATE TO WATER) SOLUTION. R DUST-ABATEMENT ADDITIVES AND STABILIZATION CHEMICALS (TYPICALLY MAGNESIUM CHLORIDE, CALCIUM CHLORIDE SALTS,
 - APPLICATION OF DUST ABATEMENT CHEMICALS WILL BE AVOIDED DURING OR JUST BEFORE WET WEATHER, AND AT STREAM CROSSINGS OR OTHER AREAS THAT COULD RESULT IN UNFILTERED BELIVERY OF THE DUST ABATEMENT MATERIALS TO A WATERBODY (TYPICALLY THESE WOULD BE AREAS WITHIN 25 FEET OF A WATERBODY OR STREAM CHANNEL; DISTANCES MAY BE GREATER WHERE VEGETATION IS SPARSE OR SLOPES ARE STEEP). ô

C) IF BLOCK NETS REMAIN IN PLACE MORE THAN ONE DAY, THE NETS WILL BE MONITORED AT LEAST DAILY TO ENSURE THEY ARE SECURED TO THE BANKS AND FREE OF ORGANIC OND AND THE PROJECTI'S WITHIN BULL TROLI SPAWNING AND REARING HABITAT, THE BLOCK NETS MUST BE CHECKED EVERY 4 HOURS FOR FISH IMPINGEMENT ON THE NET. LESS FREQUENT INTERVALS MUST BE APPROVED THROUGH A VARIANCE REQUEST.

D) NETS WILL BE MONITORED HOURLY ANYTIME THERE IS INSTREAM DISTURBANCE

B) BLOCK NETS WILL BE SECURED TO THE STREAM CHANNEL BED AND BANKS UNTIL FISH CAPTURE AND TRANSPORT ACTIVITIES ARE COMPLETE. BLOCK NETS MAY BE LEFT IN PLACE FOR THE DURATION OF THE PROJECT TO EXCLUDE FISH.

A) BLOCK NETS WILL BE INSTALLED AT UPSTREAM AND DOWNSTREAM LOCATIONS AND MAINTAINED IN A SECURED POSITION TO

EXCLUDE FISH FROM ENTERING THE PROJECT AREA

STEP 1: ISOLATE

SALVAGE OPERATIONS WILL FOLLOW THE ORDERING, METHODOLOGIES, AND CONSERVATION MEASURES SPECIFIED BELOW IN STEPS 1 THROUGH 6. STEPS 1 AND 2 WILL BE IMPLEMENTED FOR ALL PROJECTS WHERE WORK AREA ISOLATION IS NECESSARY ACCORDING TO CONDITIONS ABOVE. ELECTROFISHING (STEP 3) CAN BE IMPLEMENTED TO ENSURE ALL FISH HAVE BEEN REMOVED. FOLLOWING STEPS 1 AND 2, OR WHEN OTHER MEANS OF FISH CAPTURE MAY NOT BE FEASIBLE OR EFFECTIVE. DEWATERING AND REWATERING (STEPS 4 AND 5) WILL BE MINELEMENTED INSTREAM WORK IS DEEMED TO BE MINIMALLY HARMFUL TO FISH, AND IS BENEFICIAL TO OTHER AQUATIO SPECIES. DEWATERING WILL NOT BE CONDUCTED IN AREAS KNOWN TO BE OCCUPIED BY LAMPREY, UNLESS LAMPREYS ARE SALVAGED USING GUIDANCE SET FORTH IN USPWS 2010.

SPILL CONTAINMENT EQUIPMENT WILL BE AVAILABLE DURING APPLICATION OF DUST ABATEMENT CHEMICALS. E) PETROLEUM-BASED PRODUCTS WILL NOT BE USED FOR DUST ABATEMENT. ô

SPILL PREVENTION, CONTROL, AND COUNTERMEASURES: THE USE OF MECHANIZED MACHINERY INCREASES THE RISK FOR ACCIDENTAL SPILLS OF FUEL, LUBRICANTS, HYDRAQUIC FLUID, OR OTHER CONTAMINANTS INTO THE RIPARIAN ZONE OR DIRECTLY INTO THE WATER. ADDITIONALLY, UNCURED CONTRETE AND FORM MATERIALS ADJACENT TO THE ACTIVE STREAM CHANNEL MAY RESULT IN ACCIDENTAL DISCHARGE INTO THE WATER. THESE CONTAMINANTS GAN DEGRADE HABITAT, AND INJURE OR KILL AQUATIC FOOD ORGANISMS AND ESA-LISTED SPECIES. THE PROJECT SPONSOR WILL ADHERE TO THE FOLLOWING MEASURES:

A DESCRIPTION OF HAZARDOUS MATERIALS THAT WILL BE USED, INCLUDING INVENTORY, STORAGE, AND HANDLING PROCEDURES WILL BE AVAILABLE ON-SITE.

CONSTRUCTION NOT FOR

> **TETRA TECH** 19803 North Creek Parkway Bothell, Washington 98011 425-482-7600 Fax: 425-482-7652

15A CEB SU HIP III TERMS AND CONDITIONS	30 PERCENT DESIGN	A
		B 1/8/18
JSA JSA CEB GENFRAI NOTES	60 PERCENT DESIGN	C 7/2/18
	REVISION DESCRIPTION	REV. DATE
DRW ENG APP COOSE CHECK CONTLICENCE FIGHT PAGGRA	PLOTTED AS ANSI B (11" X 17"), PLAN SHEET FULL SIZE ANSI D (22" X 34")	

G-004

CREATED: SHEET

HIP III GENERAL CONSERVATION MEASURES APPLICABLE TO ALL ACTIONS (CONTINUED):

STEP 2: SALVAGE: AS DESCRIBED BELOW, FISH TRAPPED WITHIN THE ISOLATED WORK AREA WILL BE CAPTURED TO MINIMIZE THE RISK OF INJURY, THEN RELEASED AT A SAFE SITE:

- A) REMOVE AS MANY FISH AS POSSIBLE PRIOR TO DEWATERING
- C) SEINES WITH A MESH SIZE TO ENSURE CAPTURE OF THE RESIDING ESA-LISTED FISH WILL BE USED. B) DURING DEWATERING, ANY REMAINING FISH WILL BE COLLECTED BY HAND OR DIP NETS
- D) MINNOW TRAPS WILL BE LEFT IN PLACE OVERNIGHT AND USED IN CONJUNCTION WITH SEINING.
- E) IF BUCKETS ARE USED TO TRANSPORT FISH
- THE NUMBER OF FISH WITHIN A BUCKET WILL BE LIMITED BASED ON SIZE, AND FISH WILL BE OF RELATIVELY COMPARABLE SIZE TO MINIMIZE PREDATION; THE TIME FISH ARE IN A TRANSPORT BUCKET WILL BE LIMITED, AND WILL BE RELEASED AS QUICKLY AS POSSIBLE;
- AERATORS FOR BUCKETS WILL BE USED OR THE BUCKET WATER WILL BE FREQUENTLY CHANGED WITH COLD CLEAR WATER AT 15 MINUTE OR MORE FREQUENT INTERVALS.
- ≓
- BUCKETS WILL BE KEPT IN SHADED AREAS OR WILL BE COVERED BY A CANOPY IN EXPOSED AREAS. ≥ >
- DEAD FISH WILL NOT BE STORED IN TRANSPORT BUCKETS BUT WILL BE LEFT ON THE STREAMBANK TO AVOID MORTALITY
- F) AS RAPIDLY AS POSSIBLE (ESPECIALLY FOR TEMPERATURE-SENSITIVE BULL TROUT), FISH WILL BE RELEASED IN AN AREA THAT PROVIDES ADECLUATE COVERS AND FICHOW REFUGE. UPSTREAM RELEASE IS GENERALLY PREFERRED, BUT FISH RELEASED DOWNSTREAM WILL BE SUFFICIENTLY OUTSIDE OF THE INFLUENCE OF CONSTRUCTION.

 G) SALVAGE WILL BE SUPERVISED BY A QUALIFIED FISHERIES BIOLOGIST EXPERIENCED WITH WORK AREA ISOLATION AND COMPETENT TO ENSURE THE SAFE HANDLING OF ALL FISH.

STEP 3: ELECTROFISHING: ELECTROFISHING WILL BE USED ONLY AFTER OTHER SALVAGE METHODS HAVE BEEN EMPLOYED OR WHEN OTHER MEANS OF FISH CAPTURE ARE DETERMINED TO NOT BE FEASIBLE OR EFFECTIVE. IF ELECTROFISHING WILL BE USED TO CAPTURE FISH FOR SALVAGE. THE SALVAGE OPERATION WILL BE LED BY AN EXPERIENCED FISHERIES BIOLOGIST AND THE FOLLOWING GUIDELINES WILL BEFOLLOWED:

- A) THE NMFS' ELECTROFISHING GUIDELINES WILL BE USED (NMFS 2004, HTTP://WWW.WESTCOAST.FISHERIES.NOAA,GOV/PUBLICATIONS/REFERENCE_DOCUMENTS/ESA_REFS/SECTION4D/ELECTRO2000.PDF).
 - B) INITIAL SITE SURVEYS AND EQUIPMENT SETTINGS
- IN ORDER TO AVOID CONTACT WITH SPAWNING ADULTS OR ACTIVE REDDS, RESEARCHERS MUST CONDUCT A CAREFUL VISUAL SURVEY OF THE AREA TO BE SAMPLED BEFORE BEGINNING ELECTROFISHING.
 - BE PRIOR TO THE START OF SAMPLING AT A NEW LOCATION, WATER TEMPERATURE AND CONDUCTIVITY MEASUREMENTS SHALL TAKEN TO VECTOR VALUAL TELECTROFISHER SETTINGS AND ADJUSTMENTS. NO ELECTROFISHING SHOULD OCCUR WHEN WATER TEMPERATURES ARE ABOVE 18°C OR ARE EXPECTED TO RISE ABOVE THIS TEMPERATURE PRIOR TO CONCLUDING THE ELECTROFISHING SURVEY. IN ADDITION, STUDIES BY NAMES SCIENTISTS INDICATE THAT NO ELECTROFISHING SHOULD OCCUR IN CALIFORNIA COASTAL BASINS WHEN CONDUCTIVITY IS ABOVE 350 MS/CM.
 - WHENEVER POSSIBLE, A BLOCK NET SHOULD BE PLACED BELOW THE AREA BEING SAMPLED TO CAPTURE STUNNED FISH THAT MAY DRIFT DOWNSTREAM. ≝
- EQUIPMENT MUST BE IN GOOD WORKING CONDITION AND OPERATORS SHOULD GO THROUGH THE MANUFACTURER'S PRESEASON CHECKS, ADHERE TO ALL PROVISIONS, AND RECORD MAJOR MAINTENANCE WORK IN A LOGBOOK. \geq
- EACH ELECTROFISHING SESSION MUST START WITH ALL SETTINGS (VOLTAGE, PULSE WIDTH, AND PULSE RATE) SET TO THE MINIMUMBAN BREDED TO CAPTURE THSH. THESE SETTINGS SHOULD BE GRADALLY INCREASED ONLY TO THE POINT WHERE FISH ARE IMMOBILIZED AND CAPTURED, AND GENERALLY NOT ALLOWED TO EXCEED CONDUCTIVITY-BASED MAXIMA (SEE TABLE 1), ONLY DIRECT CURRENT (DC) OR PULSED DIRECT CURRENT (PDC) SHOULD BE USED.
 - **ELECTROFISHING TECHNIQUE** â
- SAMPLING SHOULD BEGIN USING STRAIGHT DC. THE POWER NEEDS TO REMAIN ON UNTIL THE FISH IS NETTED WHEN USING STRAIGHT DC. IF FISH CAPTURE IS UNSUCCESSFUL WITH INITIAL LOW VOLTAGE, GRADUALLY INCREASE VOLTAGE SETTINGS WITH STRAIGHT DC.
- IF FISH CAPTURE IS NOT SUCCESSFUL WITH THE USE OF STRAIGHT DC, THEN SET THE ELECTROFISHER TO LOWER VOLTAGES WITH PDC. IF FISH CAPTURE IS UNSUCCESSFUL WITH LOW VOLTAGES, INCREASE PULSE WIDTH, VOLTAGE, AND PULSE FREQUENCY (DURATION, AMPLITUDE, AND FREQUENCY).
- ELECTROFISHING SHOULD BE PERFORMED IN A MANNER THAT MINIMIZES HARM TO THE FISH. STREAM SEGMENTS SHOULD BE SAMPLEDS SYSTEMATICALLY, MOVING THE ANDOE CONTINUOUSLY IN A HERRINGBONE PATTERN (WHERE FEASIBLE) THROUGH THE WATER, CARE SHOULD BE TAKEN WHEN FISHIG MAREAS WITH HIGH FISH CONCENTRATIONS, STRUCTURE (E.G., WOOD UNDERCUT BANKS) AND IN SHALLOW WATERS WHERE MOST BACKPACK ELECTROFISHING FOR JUVENILE SALMONIDS OCCURS. ≓

VOLTAGE GRADIENTS MAY BE HIGH WHEN ELECTRODES ARE IN SHALLOW WATER WHERE BOUNDARY LAYERS (WATER SURFACE AND SUBSTRATE) TEND TO INTENSIFY THE ELECTRICAL FIELD.

- DO NOT ELECTROFISH IN ONE LOCATION FOR AN EXTENDED PERIOD (E.G., UNDERCUT BANKS) AND REGULARLY CHECK BLOCK NETS FOR IMMOBILIZED FISH.
- ELECTROFISHING CREWS SHOULD BE GENERALLY OBSERVANT OF THE CONDITION OF THE FISH AND CHANGE OR TERMINATE SAMPLING WHEN EXPERIENCING PROBLEMS WITH FISH RECOVERY TIME, BANDING, INJURY, MORTALITY, OR OTHER INDICATIONS FISH SHOULD NOT MAKE CONTACT WITH THE ANODE. THE ZONE OF POTENTIAL INJURY FOR FISH IS 0.5 M FROM THE ANODE > ≥
- NETTERS SHOULD NOT ALLOW THE FISH TO REMAIN IN THE ELECTRICAL FIELD ANY LONGER THAN NECESSARY BY REMOVING STUNNED FISH FROM THE WATER IMMEDIATELY AFTER NETTING. ≓
- C) SAMPLE PROCESSING AND RECORDKEEPING
- FISH SHOULD BE PROCESSED AS SOON AS POSSIBLE AFTER CAPTURE TO MINIMIZE STRESS. THIS MAY REQUIRE A LARGER CREV
 - ALL SAMPLING PROCEDURES MUST HAVE A PROTOCOL FOR PROTECTING HELD FISH. SAMPLERS MUST BE AWARE OF THE CONDITIONS IN THE CONTAINERS HOLDING FISH; AIR PUMPS, WATER TRANSFERS FITC., SHOULD BE USED AS NECESSARY TO MAINTAIN SAFE CONDITIONS, ALSO, LARGE FISH SHOULD BE KEPT SEPARATE FROM SMALLER PREY-SIZED FISH TO AVOID PREDATION DURING CONTAINMENT.
- USE OF AN APPROVED ANESTHETIC CAN REDUCE FISH STRESS AND IS RECOMMENDED, PARTICULARLY IF ADDITIONAL HANDLING OF FISH IS REQUIRED (E.G., LENGTH AND WEIGHT MEASUREMENTS, SCALE SAMPLES, FIN CLIPS, TAGGING). ≡ⁱ
- FISH SHOULD BE OBSERVED FOR GENERAL CONDITION AND INJURIES (E.G., INCREASED RECOVERY TIME, DARK BANDS, VISUALLY OBSERVABLE SHING, INJURIES), EACH FISH SHOULD BE COMPLETELY REVIVED BEFORE RELEASING AT THE LOCATION OF CAPTURE A PLAN FOR ACHIENING EFFICIENT RETURN TO APPROPRIATE HABITAT SHOULD BE DEVELOPED BEFORE EACH SAMPLING SESSION, ALSO, EVERY ATTEMPT SHOULD BE MADE TO PROCESS AND RELEASE ESA-LISTED SPECIMENS FIRST. FISH SHOULD BE HANDLED PROPERLY (E.G., WETTING MEASURING BOARDS, NOT OVERCROWDING FISH IN BUCKETS, ETC.) ≥ >
- CONDITIONINJURESIMORTALITIES) SHOULD BE RECORDED IN A LOGBOOK TO IMPROVE TECHNIQUE AND HELP TRAIN NEW OPERATORS. IT IS IMPORTANT TO NOTE THAT RECORDS OF INJURIES OR MORTALITIES PERTAN TO THE ENTIRE ELECTROFISHING SURVEY, INCLUDING THE FISH SAMPLE WORK-UP. PERTINENT WATER QUALITY (E.G., CONDUCTIVITY AND TEMPERATURE) AND SAMPLING NOTES (E.G., SHOCKER SETTINGS, FISH Ę.
- THE ANODE WILL NOT INTENTIONALLY CONTACT FISH
- ELECTROFISHING SHALL NOT BE CONDUCTED WHEN THE WATER CONDITIONS ARE TURBID AND VISIBILITY IS POOR. THIS CONDITION MAY BE EXPERIENCED WHEN THE SAMPLER CANNOT SEE THE STREAM BOTTOM IN ONE FOOT OF WATER. <u>≅</u>
- IF MORTALITY OR OBVIOUS INJURY (DEFINED AS DARK BANDS ON THE BODY, SPINAL DEFORMATIONS, DE-SCALING OF 25% OR MORE OF BODY, AND TORPIDITY OR INABILITY TO MAINTAIN UPRIGHT ATTITUDE AFTER SUFFICIENT RECOVERY TIME) OCCURS DURING ELECTROFISHING, OPERATIONS WILL BE IMMEDIATELY DISCONTINUED, MACHINE SETTINGS, WATER TEMPERATURE, AND CONDUCTIVITY CHECKED, AND PROCEDURES ADJUSTED OR ELECTROFISHING POSTPONED IN ORDER TO REDUCE MORTALITY.

CK ELECTROFISHING	NOTES	IN CALIFORNIA COASTAL BASINS, SETTINGS SHOULD NEVER EXCEED 400 VOLTS. ALSO, NO ELECTROFISHING SHOULD OCCUR IN THESE BASINS IF CONDUCTIVITY IS	GREATER THAN 350 µS/cm.				IN GENERAL, EXCEEDING 40 Hz
ETTINGS FOR BACKPA	MAXIMUM SETTINGS	MAX. VOLTAGE	1100 V	800 V	400 V	5 ms	70 Hz
IAL AND MAXIMUM SE	MAXIMUM	CONDUCTIVITY (µS/cm)	100	100 - 300	> 300	5 .	02
TABLE 1. GUIDELINES FOR INITIAL AND MAXIMUM SETTINGS FOR BACKPACK ELECTROFISHING	INITIAL SETTINGS	100 V				srl 009	30 Hz
TABLE		VOLTAGE				PULSE WIDTH	PULSE RATE



CONSTRUCTION NOT FOR

DRW ENG	DO LO LO	_		ц	<u> </u>	_
DATE REVISION RESCRIPTION REVISION RESCRIPTION REVISION RESCRIPTION 80 PERCENT DESIGN 15 PERCENT DESIGN 15 PERCENT DESIGN		APP		CEB	괴	3
DATE REVISION RESCRIPTION REVISION RESCRIPTION REVISION RESCRIPTION 80 PERCENT DESIGN 15 PERCENT DESIGN 15 PERCENT DESIGN		ENG		JSA	CEB	JSA
DATE 7/2/18 1/8/18 1/8/17		DRW		JSA	JSA	JSA
	PLOTTED AS ANSI B (TT A TV), PLAN SHEET FULL SIZE ANSI D (22 A 34)	REVISION DESCRIPTION		60 PERCENT DESIGN	30 PERCENT DESIGN	
		DATE		772/18	1/8/18	10/31/17
				o	В	4

G-005

HIP III GENERAL CONSERVATION MEASURES APPLICABLE TO ALL ACTIONS (CONTINUED);

STEP 4; DEWATER: DEWATERING, WHEN NECESSARY, WILL BE CONDUCTED OVER A SUFFICIENT PERIOD OF TIME TO ALLOW SPECIES TO NATURALLY MIGRATE OUT OF THE WORK AREA AND WILL BE LIMITED TO THE SHORTEST LINEAR EXTENT PRACTICLE.

- A) DIVERSION AROUND THE CONSTRUCTION SITE MAY BE ACCOMPLISHED WITH A COFFER DAM AND A BY-PASS CULVERT OR PIPE, OR A LINED, NON-ERODIBLE DIVERSION DITCH, WHERE GRAVITY FEED IS NOT POSSIBLE, A PUMP MAY BE USED, BUT MUST BE OPERATED IN SUCHA WAY AS TO AVOID REPETITIVE DEWATERING AND REWATERING OF THE SITE. IMPOUNDMENT BEHIND THE COFFERDAM MUST OCCUR SLOWLY THROUGH TRANSITION, WHILE CONSTANT FLOW IS DELIVERED TO THE DOWNSTREAM REACHES.
 - ALL PUMPS WILL HAVE FISH SCREENS TO AVOID JUVENILE FISH IMPINGEMENT OR ENTRAINMENT, AND WILL BE OPERATED IN ACCORDANGE WITH CURRENT WINS FISH SCREEN CRITERIA. IF THE PUMPING RATE EXCEEDS 3 CUBIC FEET PER SECOND, A NMFS HYDRO FISH PASSAGE REVIEW WILL BE NECESSARY. œ
- C) DISSIPATION OF FLOW ENERGY AT THE BYPASS OUTFLOW WILL BE PROVIDED TO PREVENT DAMAGE TO RIPARIAN VEGETATION OR STREAM CHANNEL.
- D) SAFE REENTRY OF FISH INTO THE STREAM CHANNEL WILL BE PROVIDED, PREFERABLY INTO POOL HABITAT WITH COVER, IF THE DIVERSION ALLOWS FOR DOWNSTREAM FISH PASSAGE.
- SEEPAGE WATER WILL BE PUMPED TO A TEMPORARY STORAGE AND TREATMENT SITE OR INTO UPLAND AREAS TO ALLOW WATER TO PERCOLATE THROUGH SOIL OR TO FILTER THROUGH VEGETATION PRIOR TO REENTERING THE STREAM CHANNEL.

ω

STEP 5: SALVAGE NOTICE: MONITORING AND RECORDING FISH PRESENCE, HANDLING, AND MORTALITY MUST OCCUR DURING THE DURATION OF THE ISOLATION, SALVAGE, ELECTROFISHING, DEWATERING, AND REWATERING OPERATIONS. ONCE OPERATIONS ARE COMPLETED, A SALVAGE REPORT WILL DOCUMENT PROCEDURES USED, ANY FISH INJURIES OR DEATHS (INCLUDING NUMBERS OF FISH AFFECTED), AND CAJUSES OF ANY DEATHS.

CONSTRUCTION AND POST-CONSTRUCTION CONSERVATION MEASURES:

FISH PASSAGE: FISH PASSAGE WILL BE PROVIDED FOR ANY ADULT OR JUVENILE FISH LIKELY TO BE PRESENT IN THE ACTION AREA BUBING CONSTRUCTION, UNLESS PASSAGE IDIO NOT EXST BEFORE CONSTRUCTION OR THE STREAM IS ANTIVELY. IMPASSABLE AT THE TIME OF CONSTRUCTION, IN THE PROVISION OF TEMPORARY FISH PASSAGE DURNG CONSTRUCTION WILL INCREASE NEGATIVE FFECTS ON AQUATIC SPECIES OF INTEREST OR THEIR HABITAT, A VARIANCE CAN BE REQUESTED FROM THE NMFS BRANCH CHIEF AND USFWS FIELD OFFICE SUPERVISOR, PROPRIED TO SUPERVISOR. DEFICIED INCOMED FILE SUPERVISOR, PROPRIED TO STREAM REACH AFFECTED, LENGTH OF STREAM REACH AFFECTED, ROPOSED TIME FOR THE PASSAGE BARRIER, AND ALTERNATIVES CONSIDERED, WILL BE INCLUDED IN THE VARIANCE REQUEST.

CONSTRUCTION AND DISCHARGE WATER:

- A) SURFACE WATER MAY BE DIVERTED TO MEET CONSTRUCTION NEEDS, BUT ONLY IF DEVELOPED SOURCES ARE UNAVAILABLE OR INADEQUATE.
 - B) DIVERSIONS WILL NOT EXCEED 10% OF THE AVAILABLE FLOW.
- C) ALL CONSTRUCTION DISCHARGE WATER WILL BE COLLECTED AND TREATED USING THE BEST AVAILABLE TECHNOLOGY
 APPLICABLE TO SITE CONDITIONS.
- D) TREATMENTS TO REMOVE DEBRIS, NUTRIENTS, SEDIMENT, PETROLEUM HYDROCARBONS, METALS AND OTHER POLLUTANTS LIKELY TO BE PRESENT WILL BE PROVIDED
- COMPACTING) IN WHICH MECHANIZED EQUIPMENT IS IN STREAM CHANNELS, RIPARIAN AREAS, AND WETLANDS WILL BE COMPLETED AS QUICKLY AS POSSIBLE. MECHANIZED EQUIPMENT WILL BE USED IN STREAMS ONLY WHEN PROJECT SPECIALISTS BELIEVE THAT SUCH ACTIONS ARE THE ONLY REASONABLE ALTERNATIVE FOR IMPLEMENTATION, OR WOULD RESULT IN LESS SEDIMENT IN THE STREAM CHANNEL OR DAMAGE (SHORT- OR LONG-TERM) TO THE OVERALL AQUATION RIPARIAN ECOSYSTEM RELATIVE TO OTHER ALTERNATIVES. TO THE EXTENT FEASIBLE, MECHANIZED EQUIPMENT WILL WORK FROM THE TOP OF THE BANK, UNLESS MINIMIZE TIME AND EXTENT OF DISTURBANCE: EARTHWORK (INCLUDING DRILLING, EXCAVATION, DREDGING, FILLING AND WORK FROM ANOTHER LOCATION WOULD RESULT IN LESS HABITAT DISTURBANCE.
- CESSATION OF WORK: PROJECT OPERATIONS WILL CEASE UNDER THE FOLLOWING CONDITIONS:
- A) HIGH FLOW CONDITIONS THAT MAY RESULT IN INUNDATION OF THE PROJECT AREA, EXCEPT FOR EFFORTS TO AVOID OR MINIMIZE RESOURCE DAMAGE.
- B) WHEN ALLOWABLE WATER QUALITY IMPACTS, AS DEFINED BY THE STATE CWA SECTION 401 WATER QUALITY CERTIFICATION,
- C) WHEN "INCIDENTAL TAKE" LIMITATIONS HAVE BEEN REACHED OR EXCEEDED

HAVE BEEN EXCEEDED; OR

SITE RESTORATION: WHEN CONSTRUCTION IS COMPLETE:

- ALL STREAMBANKS, SOILS, AND VEGETATION WILL BE CLEANED UP AND RESTORED AS NECESSARY USING STOCKPILED LARGE WOOD, TOPSOIL, AND NATIVE CHANNEL MATERIAL.
- B) ALL PROJECT RELATED WASTE WILL BE REMOVED.
- ALL TEMPORARY ACCESS ROADS, CROSSINGS, AND STAGING AREAS WILL BE OBLITERATED. WHEN NECESSARY FOR REVEGETATION AND INFILTRATION OF WATER, COMPACTED AREAS OF SOIL WILL BE LOOSENED.







REV. DATE REVISION DESCRIPTION OR BAG. APP 60 PERCENT DESIGN
--

ALL DISTURBED AFEAS WILL BE REHABILITATED IN A MANNER THAT RESULTS IN SIMILAR OR IMPROVED CONDITIONS RELATIVE TO PRE-PACKECT CONDITIONS. THIS WILL BE ACHIEVED THROUGH REDISTRIBUTION OF STOCKPILED MATERALS, SEEDING, AND/OR PLANTING WITH LOCAL NATIVE SEED MIXES OR PLANTS.

REVEGETATION: LONG-TERM SOIL, STABILIZATION OF THE DISTURBED SITE WILL BE ACCOMPLISHED WITH RE-ESTABLISHMENT OF NATIVE VEGETATION USING THE FOLLOWING CRITERIA:

- A) PLANTING AND SEEDING WILL OCCUR PRIOR TO OR AT THE BEGINNING OF THE FIRST GROWING SEASON AFTER CONSTRUCTION
 - B) AN APPROPRIATE MIX OF SPECIES THAT WILL ACHIEVE ESTABLISHMENT, SHADE, AND EROSION CONTROL OBJECTIVES, PREFERABLY FORB, GRASS, SHRUB, OR TREE SPECIES NATIVE TO THE PROJECT AREA OR REGION AND APPROPRIATE TO THE SITE WILL BE USED.
- C) VEGETATION, SUCH AS WILLOW, SEDGE AND RUSH MATS, WILL BE SALVAGED FROM DISTURBED OR ABANDONED FLOODPLAINS, STREAM CHANNELS, OR WETLANDS.
 - D) INVASIVE SPECIES WILL NOT BE USED.
- E) SHORT-TERM STABILIZATION MEASURES MAY INCLUDE THE USE OF NON-NATIVE STERILE SEED MIX (WHEN NATIVE SEEDS ARE NOT AVAILABLE), WEED-FREE CERTIFIED STRAW, JUTE MATTING, AND OTHER SIMILAR TECHNIQUES.
- G) FENCING WILL BE INSTALLED AS NECESSARY TO PREVENT ACCESS TO REVEGETATED SITES BY LIVESTOCK OR UNAUTHORIZED F) SURFACE FERTILIZER WILL NOT BE APPLIED WITHIN 50 FEET OF ANY STREAM CHANNEL, WATERBODY, OR WETLAND.
- H) RE-ESTABLISHMENT OF VEGETATION IN DISTURBED AREAS WILL ACHIEVE AT LEAST 70% OF PRE-PROJECT CONDITIONS WITHIN
- I) INVASIVE PLANTS WILL BE REMOVED OR CONTROLLED UNTIL NATIVE PLANT SPECIES ARE WELL ESTABLISHED (TYPICALLY
- SITE ACCESS: THE PROJECT SPONSOR WILL RETAIN THE RIGHT OF REASONABLE ACCESS TO THE SITE IN ORDER TO MONITOR THE SUCCESS OF THE PROJECT OVER ITS LIFE. 3-YEARS POST-CONSTRUCTION).
 - IMPLEMENTATION MONITORING: PROJECT SPONSOR STAFF OR THEIR DESIGNATED REPRESENTATIVE WILL PROVIDE IMPLEMENTATION MONITORING TO ENSURE COMPLIANCE WITH THE APPLICABLE BIOLOGICAL OPINION, INCLUDING.
- B) EFFECTS TO LISTED SPECIES ARE NOT GREATER THAT PREDICTED AND INCIDENTAL TAKE LIMITAITONS ARE NOT EXCEEDED. A) GENERAL CONSERVATION MEASURES ARE ADEQUATELY FOLLOWED; AND
- AND RECORD WATER QUALITY OBSERVATIONS TO ENSURE THAT IN-WATER WORK IS NOT DEGRADING WATER QUALITY. DURING CONSTRUCTION, CWA SECTION 401 WATER QUALITY CERTIFICATION PROVISIONS PROVIDED BY THE OREGON DEPARTMENT OF ENVIRONMENTAL QUALITY, WASHINGTON DEPARTMENT OF ECOLOGY, OR IDAHO DEPARTMENT OF ENVIRONMENTAL QUALITY, WASHINGTON DEPARTMENT OF ECOLOGY, OR IDAHO DEPARTMENT OF ENVIRONMENTAL QUALITY WILL CWA SECTION 401 WATER QUALITY CERTIFICATION: THE PROJECT SPONSOR OR DESIGNATED REPRESENTATIVE WILL COMPLETE BE FOLLOWED.
- **STAGED REWATERING PLAN:** STAGED REWATERING PROVIDED AS A PART OF THE CURRENT PLAN SHEETS. 9.
- VARIANCE REQUESTS: BECAUSE OF THE WIDE RANGE OF PROPOSED ACTIVITIES AND THE NATURAL VARIABILITY WITHIN AND BETWEEN STREAM SYSTEMS, BPA (ON BEHALF OF THE APPLICANT) MAY REQUIRE VARIATIONS FROM CRITERIA SPECIFIED HEREIN. THE SERVICES WILL CONSIDER GRANTING VARIANCES, ESPECIALLY WHEN THERE IS A CLEAR CONSERVATION BENEFIT OR THERE ARE NO ADDITIONAL ADVERSE EFFECTS (ESPECIALY INCIDENTAL TAKE) BEYOND THAT COVERED BY THE OPINION. MINOR VARIANCES CAN BE AUTHORIZED BY THE OPINION. MINOR
 - VARIANCE REQUESTS MAY BE SUBMITTED AND APPROVED BY EMAIL CORRESPONDENCE AND WILL INCLUDE: 1) NAME AND BRIEF DESCRIPTION OF PROJECT, LOCATION OF PROJECT AND 6TH FIELD HUC NUMBER.
 - 2) DEFINE THE REQUESTED VARIANCE AND THE RELEVANT CRITERION BY PAGE NUMBER.
- 3) CURRENT ENVIRONMENTAL CONDITIONS (CURRENT FLOW AND WEATHER CONDITIONS).
- 4) BIOLOGICAL JUSTIFICATION AS TO WHY A VARIANCE IS NECESSARY AND A BRIEF RATIONALE WHY THE VARIANCE WILL EITHER PROVIDE A CONSERVATION BENEFIT OR, AT A MINIMUM, NOT CAUSE ADDITIONAL ADVERSE EFFECTS BEYOND THE SCOPE OF THE
- 5) INCLUDE AS ATTACHMENTS ANY NECESSARY APPROVALS BY STATE AGENCIES.

VITTO TOLICO	09		U E VI	
	АРР		CEB	징
	DRW ENG		JSA	CEB
	DRW		JSA	JSA
PLOTTED AS ANSI B (11 A 17), PLAN SHEET FOLL SIZE ANSI D (22 A 34)	REVISION DESCRIPTION		60 PERCENT DESIGN	30 PERCENT DESIGN
	DATE		772/18	1/8/18

G-006

CREATED: SHEET:

HIP III GENERAL CONSERVATION MEASURES APPLICABLE TO ALL ACTIONS (CONTINUED);

OBSERVATIONS TO ENSURE THAT ANY INCREASE IN SUSPENDED SEDIMENT DOES NOT EXCEED THE LIMIT FOR HIP III COMPLIANCE. RECORDS SHALL BE REPORTED ON THE HIP III PCF. IF THE GEOMORPHOLOGY OF THE PROLECT AREA (E.G., SILTY OR CLAYLIKE MATERALS) OR THE NATURE OF THE ACTION (E.G., LARGE AMOUNTS OF BARE EARTH EXPOSED BELOW THE BANKFULL ELEVATION) SHALL PRECLUDE THE SUCCESSFUL COMPLIANCE WITH THESE TRIGGERS, NOTIFY YOUR ECLEAD WHO SHALL PRE-NOTIFY THE SERVICES OF THE LIKELIHOOD OF AN EXCEEDANCE. TURBIDITY MONITORING PROTOCOL: THE PROJECT SPONSOR SHALL COMPLETE AND RECORD THE FOLLOWING WATER QUALITY

- A) TAKE A BACKGROUND TURBIDITY SAMPLE USING A RECENTLY-CALIBRATED TURBIDIMETER IN ACCORDANCE WITH MANALY-CTURRERS INSTRUCTORS, OR MASAURET URBIDITY WITH A NUSUAL TURBIDITY OBSERVATION (FIGURE 1). TURBIDITY SESPENATION (FIGURE 1). TURBIDITY SESPENATION (FIGURE 1). THE BUSTURED SHOULD BE MEASURED EVERY 2 HOURS WHIE WORK IS BEING IMPLED OR MORE OFTEN I SEDIMENT DISTURBANCE VARIES GREATLY. FREQUENT MONITORING WILL ENSURE THAT THE IN-WATER WORK AREA IS NOT CREATING TURBID CONDITIONS WITHIN THE WATER COLUMN. THE BACKGROUND SAMPLES WIS AND SAMPLES WIS A RECLEARLY AS A RELATIVELY UNDISTURBED LOCATION APPROXIMATELY 100 FEET UPSTREAM FROM THE RECLEAR RECORD THE OSSERVATION. LOCATION, AND TIME BEFORE MONITORING AT THE DOWNSTREAM POINT, KNOWN AS THE MEASUREMENT COMPLANCE POINT.
- B) TAKE A SECOND SAMPLE OR OBSERVATION, IMMEDIATELY AFTER EACH UPSTREAM SAMPLE OR OBSERVATION, AT THE MEASUREMENT COMPLIANCE POINT, APPROXIMENTELY SOFEET DOWNSTREAM FROM THE PROJECT AREA INSTREAMS THAT ARE 30 FEET WIDE OR LESS; 100 FEET DOWNSTREAM FROM THE PROJECT AREA TO FEET WIDE, 200 FEET DOWNSTREAM FROM THE PROJECT AREA FOR STREAMS BETWEEN 30 AND 100 FEET WIDE; 200 FEET DOWNSTREAM FROM THE PROJECT AREA FOR STREAMS GREATER THAN 100 FEET WIDE; AND 300 FEET FROM THE DISCHARGE POINT OR NONPOINT SOURCE FOR LOCATIONS SUBJECT TO TIDAL OR COASTAL SCOUR. RECORD THE DOWNSTREAM IS OSBERVATION, LOCATION, AND TIME.

 C) COMPARET THE UPSTREAM AND DOWNSTREAM OSSERVATIONS SAMPLES. F OBSERVED OR MEASURED TURBIDITY DOWNSTREAM IS MORE THAN UPSTREAM OSSERVATION OR MEASUREMENT (* 10%). THE ACTIVITY MUST BE MODIFIED TO REDUCE TURBIDITY. IF VISIAL, ESTIMATES ARE USED. AN OSYLOUS DIFFERENCE RETWEEN UPSTREAM AND DOWNSTREAM OSSERVATION OF MEASUREMENT (* 10%). THE ACSIVITY MUST BE MODIFIED TO REDUCE TURBIDITY. IF THE ASSUMPTION OF A (* 10%). DIFFERENCE (FIGURE 1), MARK "YES" OR "NO" ON YOUR DATASHEET. CONTINUE TO MONITOR EVERY THE ADDITION OF A (* 10%). DIFFERENCE (FIGURE 1), MARK "YES" OR "NO" ON YOUR DATASHEET. CONTINUE TO MONITOR EVERY
 - - IF EXCEEDANCES OCCUR FOR MORE THAN TWO CONSECUTIVE MONITORING INTERVALS (AFTER 4 HOURS), THE ACTIVITY MUST STOP UNTIL THE TURBIDITY LEVEL REFURNS TO BACKGROUND. AND THE ECL LEAD MUST BE NOTHEID WITHIN 48 HOURS. THE ECL LEAD SHALL BOCOLIMENT THE REASONS FOR THE EXCEEDANCE AND CORRECTIVE MEASURES TAKEN, THEN NOTIFY THE LOCAL NIFE BRANCH CHIEF AND/OR USEWS FIELD SUPERVISOR AND SERK RECOMMENDATIONS.

 JSA
 JSA
 CEB

 JSA
 CEB
 CJ

 JSA
 JSA
 CEB
 ENG TED AS ANSI B (11" X 17"), PLAN SHEET FULL SIZE ANSI D (22" X 34" REVISION DESCRIPTION 50 PERCENT DESIGN 30 PERCENT DESIGN DATE

7/2/18

CREATED: SHEET

HIP III TERMS AND CONDITIONS **GENERAL NOTES**


G-007


COUSE CREEK CONFLUENCE FISH PASSAGE 80 PERCENT DESIGN


CONSTRUCTION NOT FOR


TETRA TECH 19803 North Creek Parkway Bothell, Washington 98011 c 425–482-7600 Fax: 425-482-7652


94-6162 COUSE CREEK CONFLUENCE/60% DESIGNI, SHEET FILES/01-COVER PAGE AND NOTES, DWG. ANDREWS, JEREMY JUN 2, 2018 2-46 PM ----
















DATA	ELEVATION	1148.0	1152.0	1151.0	1150.0	1149.1	1149.0	1149.0	1147.0	1144.1	1145.9	1144.0	1144.0	1145.8	1146.3	1146.4
ROUGHENED RIFFLE POINT DATA	EASTING	8743942.18	8743982.43	8743986.00	8743985.86	8743987.59	8743989.64	8743981.38	8743970.75	8743956.32	8743942.00	8743949.94	8743945.43	8743949.55	8743939.20	8743938.62
OUGHENED R	NORTHING	824938.49	824939.06	824956.20	824977.83	824996.28	825003.13	825037.80	825060.63	825044.87	825042.38	825019.68	825010.42	824998.37	824977.49	824956.77
R	# LNIO4	-	2	е	4	2	9	7	8	6	10	11	12	13	14	15



| LEGEND: | STREAM ALIGNMENT | STREAM ALIGNMENT | EXISTING WATTERLINE | NATIVE MATERIAL | PROPOSED PROUGHENED RIFLE | PROPOSED ROUGHENED RIFLE | PROPOSED RIFLE | PROPOSED RIFLE | PROPOSED RIFLE | PROPOSED RIFLE



- ROUGHENED RIFFLE AND CHANNEL DROP NOTES:

 1. SIZE OF RIFFLE SAND FOOTER BOULDER SHALL BE 3-FT DIAM, BOULDERS.

 2. PROPOSED ROUGHENED RIFFLE STREAMBED SEDIMENT/COBBLE MIX. 2-FT DEPTH MAX. MATERIAL TO BE PLACED IN MAXIMUM 10 -12 INCH LIFTS

 2. PROPOSED ROUGHENED RIFFLE STREAMBED SEDIMENT/COBBLE MIX. 2-FT DEPTH MAX. MATERIAL TO BE PLACED IN MAXIMUM 10 -12 INCH LIFTS

 AND SURFACE WASHED IN WITH FINES UNTIL PONDING OF WATER IS OBSERVED. SEE SECTION 35 49 50. IN THE SPECIFICATIONS FOR MATERIAL SIZE AND GRADATION.

 3. RIFFLE BOULDER TO BE BURIED 50% MIN/90% MAX OF HEIGHT AND BE COMPLETELY SUBMERGED DURING THE 2-YEAR FLOOD FLOW.

 4. PROPOSED STREAMBED COBBLE FOR CUTOFF TRENCH. SEE SECTION 35 49 50. IN THE SPECIFICATIONS FOR COBBLE SIZING AND GRADATION.


Walls Walls Seein	1	
NOT FOR	CONSTRUCTION	


TETRA TECH www.tetratech.com 19903 North Creek Parkway Bothell, Washington 98011 Phone: 425-482-7652




DWG.NO.: C-104					CREATED: 7/2/18			SHEET:
ON OWG	COUSE CREEK CONFICEINGE FISH PASSAGE 60 PERCENT DESIGN			0 = 4 H L	DETAILS	DOLICHENED DIEELE	NOOGI IEINED INI I EE	
	АРР				CEB	L	3	3
	DRW ENG				JSA	010		JSA JSA CJ
	DRW				JSA	401	ś	JSA
PLOTTED AS ANSI B (11" X 17"), PLAN SHEET FULL SIZE ANSI D (22" X 34")	REVISION DESCRIPTION				60 PERCENT DESIGN	20 DEDOGNIT DEGLON	SO PENCEIN DESIGN	15 PERCENT CONCEPTUAL DESIGN
	DATE				7/2/18	410140	01.00	10/31/17
L	REV.		L		O	٩	٥	4

LOTTED AS ANSI B (11" X 17"), PLAN SHEET FULL SIZE ANSI D (22" X 34")
REVISION DESCRIPTION







CRITERIA FOR PLANTING PLAN 1. LOCAL STOCK OF NATIVE

- LOCAL STOCK OF NATIVE SPECIES SHOULD BE USED TO THE EXTENT POSSIBLE BECAUSE THESE STOCKS WOULD BE BEST SUITED TO AND ADAPTED TO LOCAL CONDITIONS.
 - FINAL PLANTING PLANS WILL BE BASED ON THE FINAL CONSTRUCTION DESIGN. FACTORS SUCH AS TOPOGRAPHY DISTANCE TO STREAM CHANNEL SHOUS DIE CHANNEL SHALL BE TAKEN INTO ACCOUNT. THE FINAL PLANTING PLAN WILL BE INTENDED TO FACILITATE PLANTING PLAN WILL BE INTENDED TO FACILITATE PROJECT GOAL OF IMPROVING AQUATIC AND RIPARIAN HABITAT. TO AUGMENT SURVIVAL OF RIPARIAN PLANTINGS. FINAL PLACEMENT OF PLANTS SHALL BE CHOSEN BASED ON MICROSITE CONDITIONS, BECAUSE SOIL PROPERTIES AND WATER TABLE DEPTH CAN VARY OVER SHORT DISTANCES, SUCH THAT SPECIES ARE
 - BEST MATCHED TO THEIR SITE CONDITIONS.
- SITE PREPARATION, SUCH AS REMOVAL OF WEEDS OR OTHER SPECIES THAT WILL COMPETE WITH SEED INGS AND TILLING OF THE SOIL SHALL OCCURENS THATING.
 IF NECESSARA'N, SOIL AMENDMENT, SUCH ARE THE TILZER, SHALL BE INCORPORATED PRIOR TO OR DURING

<u>.</u>

- IF NECESSARY, MEASURES SUCH AS TUBING, OR OTHER ANIMAL CONTROL TECHNIQUES, CAN BE PLANTING Ö Ö,
- UTILIZED TO PROTECT WOODY PLANTS FROM GRAZING/HERBIVORY.
 POSSBILE, LANTS SHALL BE NSTALLED IN HE LETTE FALL THROUGH EARLY SPRING TO MINIMIZE THE NEED FOR SUPPLEMENTAL WATER AND TO ALLOW FOR THE OPTION OF USING BARE ROOT PLANT STOCK. IF AVAILABLE

GENERAL PLANTING NOTES

- IF APPLICABLE, SUPPLEMENTAL FERTILIZER MAY BE ADDED TO THE BOTTOM OF EACH TREE AN SHRUB PRANTING HOLE PRIOR TO PLANTING AND BACKFILLING. IF USED FERTILIZERS SHALL BE SLOW RELEASE PRODUCTS THAT WILL NOT RESULT IN NUTRIENT RUNOFF INTO AQUATIC SYSTEMS. IF APPLICABLE, ADDITION OF MULCH THREE INCHES DEEP MAY BE PLACED IN AN 18 INCH DAMETER RING AROUND EACH TREE AND SHRUB TO PREVENT COMPETITION WITH INVASIVE SPECIES.

2

RIPARIAN PLANTING ZONE EXAMPLE SEQUENCE:

- SEED BARE SOIL AT APPROXIMATELY 30 LBS/ACRE IN SELECTED AREAS AS NEEDED/DESIRED FOR
- EROSION CONTROL. .
- INSTALL PLANTS BASED ON MICROSITE VARIATIONS WITHIN RIPARIAN PLANTING ZONE. DEPENDING ON DESIRED DENSITY: TREES SHOULD BE PLANTED 10 TO 16 FEET ON CENTER, SHRUBS SHOULD BE PLANTED AT APPROXIMATELY 4 TO 8 FEET ON CENTER, HOWEVER, FINAL PLANT SPACING WILL DEPEND ON SPECIFIC SITE CONDITIONS AND DESIRED OUTCOMES AND SHOULD BE DESIGNED DURING FINAL PLAN DESIGN.

LIVE STAKES DESCRIPTION:

IF USED, LIVE STAKES SHOULD BE INSTALLED ALONG BANKS OF SITE-MAND SIDE CHANNEL, WHERE APPLICABLE. THE WIDTH OF THE ZONE FOR PLATING LIVE STAKES WILL DEPEND ON SITE CONDITIONS AND DESIGN CHARACTERISTICS INCLUDING FINAL GRADE OF BANK AND MOISTURE AYALLABILITY.

EXAMPLE SEQUENCE:

- SEED BARE SOIL AT APPROXIMATELY 30 LBS/ACRE IN SELECTED AREAS AS NEEDED/DESIRED FOR EROSION CONTROL. 7
- VARIATIONS WITHIN RIPARIAN PLANTING ZONE.
 DEPENDING ON DESKED DENSITY, STAKES MAY BE
 LAUNTED AT APPROXIMATELY 1TO 10 FEET ON
 CENTER. INSTALL STAKES BASED ON MICROSITE ω.

- SELECTION AND INSTALLATION NOTES: 1. LIVE STAKES SHOULD BE BETWEEN 18-48 INCHES

- LONG AND AT LEAST ½" IN DIAMETER. STAKES SHOULD BE CUT STRAIGHT AT THE TIP OF THE BRANCH AND AT AN ANGLE AT THE BASE OF CUTTING TO ENSURE THE CORRECT END IS DRIVEN INTO THE GROUND.

ς;

KEEP STAKES MOIST AND IN A DARK PLACE UNTIL INSTALLED; DO NOT LET STAKES DRY OUT.

ω.

5

- SOAKING STAKES BEFORE INSTALLATION INCREASES SURVIVAL AND GROWTH WEIGHT.
- DRIVE STAKES INTO THE SOIL SO AT LEAST % OF ITS LENGTH IS UNDERGROUND; LEAVE AT LEAST 12 INCHES ABOVE GROUND. USE THICKER DIAMETER STAKES WHEN PLANTING
 - RESIST HEAT AND DRYING BETTER THAN SMALLER IN RIPRAP; THICKER DIAMETER STAKES WILL CUTTINGS 9
 - PLANT STAKES DURING THE DORMANT SEASON.

Quantity

Acre

(feet o.c.)

Propagation Method

Composition, Percent 4 4 10 20

Common Name

POPULUS BALSAMIFERA SUBSP. TRICHOCARPA BLACK COTTONWOOD

PONDEROSA PINE COYOTE WILLOW

DOUGLAS FIR

PSEUDOTSUGA MENZIESII

PINUS PONDEROSA

Tree

Growth Habit

POTENTIAL SPECIES FOR RIPARIAN REVEGETATION

Acres: 0.96¹

15 15 15

163 41 427 427 213

7

CONTAINER CONTAINER

LIVE STAKE

CONTAINER

10 2 임 9 10

LIVE STAKE OR CONTAINER

REDOSIER DOGWOOD LEWIS' MOCK ORANGE BLACK HAWTHORN PACIFIC NINEBARK


CONTAINER CONTAINER CONTAINER CONTAINER CONTAINER


SEED MIX DESCRIPTION:

SEED MIX, COMPOSED OF NATIVE SPECIES, SHALL BE USED ON BARE SOIL IN SELECTED AREAS OF THE RIPARIAN PLANTING ZONES AS NEEDED/DESIRED FOR EROSION CONTROL.

- NOTES:
 1. SEED AT APPROXIMATELY 30 LBS/ACRE; FINAL QUANTITY OF SEED MIX PER ACRE WILL DEPRINO ON SPECIES COMPOSITION AND SITE CONDITIONS.
 2. SPECIES TO BE USED FOR SEED MIX(ES) AND FINAL COMPOSITION SHOULD BE CHOSEN BASED ON SITE SPECIFIC DESIGN AND CONDITIONS (E.G. SLOPE, WIDTH OF PLANTING ZONE, MOISTURE AYAILABILITY)
 3. ALL SEED MIXES SHOULD BE CERTIFIED WEED-FREE.

POTENTIAL SPECI	POTENTIAL SPECIES FOR FLOODPLAIN SEED MIX	
	Acres: 1.01	
Total Seed Mix: 63 pou	Total Seed Mix: 63 pounds (at seeding rate of 30 lbs/acre) ¹	
		Percent
Scientific Name ²	Common Name	Composition
LEYMUS CINEREUS	GREAT BASIN WILDRYE	30
FESTUCA IDAHOENSIS	IDAHO FESCUE	20
DESCHAMPSIA CESPITOSA	TUFTED HAIRGRASS	15
ELYMUS GLAUCUS	BLUE WILDRYE	15
PSEUDOROEGNERIA SPICATA	BLUEBUNCH WHEATGRASS	15
BROMUS CARINATUS VAR. MARGINATUS	MOUNTAIN BROME	2
	TOTAL	100
Acres and seed mix required are estimates based on 60% design.	ssed on 60% design.	





213

203 102 102 102 102

51

CONTAINER

10

LIVE STAKE PLANTING DETAIL

OTTED AS ANSI B (11" X 17"), PLAN SHEET FULL REVISION DESCRIPTION

Acres, density per acre, and quantities are estimates based on 60% design, the final species list and quantities will be decided when construction plans are finalized. Percent composition adds to 100 for each strata (i.e., tree, shrub).

ROCKY MOUNTAIN MAPLE

CHOKECHERRY

PHYSOCARPUS CAPITATUS SYMPHORICARPOS ALBUS

Shrub

CRATAEGUS DOUGLASII PHILADELPHUS LEWISII PRUNUS VIRGINIANA

CORNUS SERICEA

This species should be placed near the bank of the side channel.

CONSTRUCTION NOT FOR 19803 North Creek Parkway Bothell, Washington 98011 Phone: 425–482-7600 Fax: 425-482-7652

TETRA TECH

rahed Council	
le Setin Wels	
Wallawa	
7)	

-					
COLISE OBEEK CONELLIENCE FISH BASSAGE	COUSE CREEK CONFLUENCE FISH PASSAGE 60 PERCENT DESIGN			PLANTING PLAN	
	АРР		CEB	징	3
	DRW ENG		JSA	GEB	JSA JSA
	DRW		JSA	JSA	JSA
PLOTTED AS ANSI B (11" X 17"), PLAN SHEET FULL SIZE ANSI D (22" X 34")	REVISION DESCRIPTION		60 PERCENT DESIGN	30 PERCENT DESIGN	15 PERCENT CONCEPTUAL DESIGN
	DATE		7/2/18	1/8/18	10/31/17
	REV.		О	В	<

7/2/18

CREATED: SHEET:

L-101

ACER GLABRUM