

Reference: Aerial image obtained from NAIP, 07/2005, base map obtained from ESRI.

\*These Design Drawings were not necessary for construction and have been removed from the Construction Drawings. Refer to 04/08/11 set of Design Drawings for more detailed design information. \*\*These Design Drawings were not necessary for construction and have been removed from the Construction Drawings. Refer to 06/27/11 set of Design Drawings for more detailed design information.

81								
P SF	Revision No:	Date:	Description:	Initials:	Designed: JJF	Walla Walla River	00 NALLA VALLA - Dy 00	
TEM	1	08/01/11	Channel downcut redesign	JJF	Drawn: MGF	Umatilla County, Oregon	3 COMPARENT OF THE	GEOENGINEERS
900					Checked: MKH		Rent A Drew or THE MARK	
2698	APPR	OVED F	OR CONSTRUCTION		Date: 06/27/11	Confederated Tribes of the	Treaty of 1855	523 East Second Avenue
P:\2\					Project No: 2698-006-02	Umatilla Indian Reservation		Spokane, Washington 99202

**Cover Sheet** Sheet

Lampson Construction Drawings

**S-1** 

### **GENERAL NOTES:**

These designs and drawings have been prepared for the exclusive use of the Confederated Tribes of the Umatilla Indian Reservation (CTUIR), and their authorized agents. No other party may rely on the product of our services unless GeoEngineers Inc. (GeoEngineers) agrees in writing in advance of such use.

- 1. These Lampson Site Walla Walla River enhancement plans represent an engineer-led (design/build) construction effort.
- These plans are not intended for construction without the direct supervision of a qualified GeoEngineers representative. 2.
- 3. The drawings contained within should not be applied for any purpose or project except the one specified; specifically the habitat enhancements on the Walla Walla River along the Lampson property as located on Sheet S-1.
- These designs and drawings are copyrighted by GeoEngineers, Inc. Any use, alteration, deletion, or editing of this document without explicit 4. written permission from GeoEngineers is strictly prohibited. Any other unauthorized use of this document is prohibited.
- The contractor shall construct the stream enhancement in accordance with the plans stamped "Approved for Construction." These plans will 5. be provided to the contractor by the engineer or project inspector prior to construction. Work shall not be done without the current set of approved construction plans
- 6. The enhancement designs depicted herein are approximate and are intended to express the overall design intent of the project. These designs will need to be adjusted in the field during construction in order to meet the specific site conditions and intended function. These stream improvements have been developed with the understanding that a qualified GeoEngineers engineer and/or scientist be on-site to provide construction guidance while the stream enhancements are constructed to ensure the overall intent of the design is met.
- Geomorphic conditions can change and these designs are based on conditions that existed at the time the design was performed. The 7. results of these designs may be affected by the passage of time, by manmade events such as construction on or adjacent to the site, or by natural events such as floods, earthquakes, slope instability or groundwater fluctuations. Always contact GeoEngineers before applying these designs to determine if they remain applicable.
- All streams, rocks and woody habitat structures are potentially dangerous. This proposed stream enhancement design is intended to address a wide variety of constraints which target more naturally functioning stream systems and habitat; they are inherently dangerous. It is therefore strongly recommended that the CTUIR address the necessary safety concerns appropriately with the landowner. Signs placed along the enhanced stream reaches in prominent locations to warn of the potential hazards should be considered a minimum.
- 9 The project is located in a detailed Flood Zone AE as identified on the Federal Emergency Management Agency (FEMA) Flood Insurance Rate Map (FIRM) 410204 0250B for Umatilla County, Oregon (Community Number 410204), dated March 4, 1987. The FEMA CLOMR/LOMR process has not been initiated. This project design does result in a "No Rise" flood condition and a No Rise Certificate from the county has been applied for.
- 10. In general, the proposed enhancements are intended to result in a more stable streambed, banks and floodplain, while increasing in stream habitat for fish. However, channel erosion, channel migration and/or avulsions can be expected to occur over time. These channel processes are natural and appropriate for these stream systems.
- 11. These figures were originally produced in color.
- 12. Refer to GeoEngineers accompanying stream enhancement design report for applicable design and contractual limitations.
- 13. All elevations are based on the National Geodetic Veritcal Datum of 1929. A detailed topographic survey was not performed for this project. All existing and proposed stream features shown are approximate. Topography was obtained from a topographic survey completed by the US Corps of Engineers in 1999.

### CONSTRUCTION NOTES:

All contractors working within the project boundaries are responsible for compliance with all applicable safety laws. The contractor shall be responsible for all barricades, safety devices and control of traffic within and around the construction area.

- 1. All material and workmanship furnished on or for the project must meet the minimum requirements of project permits, approving agencies, specifications as set forth herein, or whichever is more restrictive.
- 2. All work within or adjacent to any wetland area shall comply with the conditions of the 404 permit.
- Contractor shall obtain all necessary permits prior to any dewatering and/or river diversion activities on site.
- 4. The contractor shall install and maintain appropriate sediment control devices throughout the whole project site, including the construction be designed, constructed and maintained in accordance with all applicable local, state and federal regulations.
- 5. Stream construction shall occur during the fish window for the project area (July 1 September 30) See sheets S-11 S-14 for construction sequencing. See sheets S-11.1 - S-11.4 for specifics on fish handling.
- 6. Fish exclusion shall be conducted in the project area prior to any dewatering activities, or construction within or directly adjacent to the channel.
- 7. Surface and groundwater shall be drained away from active construction and into a sediment pond/trap to eliminate sediment from flowing into active stream channels
- 8. turbidity.
- stream segments.
- 10. Construction shall minimize disturbance to, and maximize reuse of, existing riparian vegetation.
- 11. All material not used on site shall be disposed of onsite as directed by the CTUIR and landowner or shall be hauled offsite and properly disposed of
- 12. Record information (as-built survey) shall be accurately recorded by the contractor and supplied to the owner for future use, reference and monitoring. Submittal of record information is a condition of final acceptance.
- 13. The Construction Specifications supercede these drawings where discrepancies exist between these drawings and the Construction Specifications

Revision No 1	Date: 08/01/11	Description: Channel downcut redesign	Initials: JJF	Designed: JJF Drawn: MGF	Walla Walla River	0.0 0.0 2 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5	GEOENGINEERS
				Checked: MKH	Umatilla County, Oregon Confederated Tribes of the	A DECEMBER OF A	
APP	₹OVED F	OR CONSTRUCTION		Date: 06/27/11		Trenty of 1855	523 East Second Avenue Spokane, Washington 99202
				Project No: 2698-006-02	Umatilla Indian Reservation		spokane, washington 99202

Contractor shall not work within any wetland area until the owner has obtained a 404 permit from the United States Army Corps of Engineers.

staging area and stockpile area throughout the project's construction. Temporary construction and permanent erosion control measures shall

Discharges entering active streams on site shall satisfy all state and federal standards and project permit requirements for contaminants and

9. Diverted and controlled streamflow can be used to test and adjust newly constructed stream structures prior to permanently activating new

### **General Notes**

Sheet S-2

# Vision

# Goals

## **Increase and Enhance Habitat**

### **Diversify In-Stream Habitat Complexity**

Multiple Habitats Close Together Primary Pool Habitat Substrate Diversification Structure Side Channel/Off Channel Habitat Floodplain Connectivity

#### Increase, Enhance Diversify Riparian Habitat

Diverse Vegetation (Cover, Temperature, Recruitment, Macroinvertebrates) Bio-Engineering (Native Plants. Channel, Floodplain and Habitat Stability)

#### **Geomorphic Stability**

Reduces Erosion, Sedimentation, Property Loss Self-Sustaining, Self-Maintaining Minimize Maintenance Cost Effective

**Design Practicality** 

Benefits to Other Species (Water fowl, Song Birds, Upland Species)

Accommodate Physical, Practical and Regulatory Site Constraints

In-Stream Habitat Structures

Floodplain Connectivity Layback Steep Existing Slopes Levee Removal and/or Setback Floodplain Benching

Create Spring Channels Wetlands Backwater Habitat

Vegetation Plan

Public Safety Flood Management

Landowner Desires

Neighboring Properties Grades, Access, Views

Economics

Revision No: Date: Description: Initials: Designed: JJF Walla Walla River GEOENGINEERS 08/01/11 Channel downcut redesign Drawn: MGF 22 Umatilla County, Oregon Checked: MKH Confederated Tribes of the 523 East Second Avenue APPROVED FOR CONSTRUCTION Date: 06/27/11 Spokane, Washington 99202 Umatilla Indian Reservation Project No: 2698-006-01

Increase and enhance juvenile and adult anadromous fish habitat by targeting limiting habitat factors within the limits of river geomorphology, property ownership, public safety, environmental regulations and project economics.

# **Objectives**

## **Treatment Options**

Woody Habitat Structures Roughened Channels, Boulder Structures

Floodplain Excavation

Side Channel / Off Channel Habitat

Meander Creation (Side Channel, Main Channel)

Preserve, Enhance and Minimize Disturbance to High-Value Resources

## **Practical Design Considerations**

Geomorphic Stability (Minimizes Avulsions, Erosion, Sedimentation, Habitat Destruction)

Zoning, Easements, Setbacks, Floodplains, Zones

**Property Boundaries** 

Bridges, Utilities, Water Rights

Permits, Schedule, Budget, Maintenance, Constructability

Vision, Goals and Objectives

Sheet


**S-**3,


	Treat	ments						E	Benefits	(1)					
Symbol <sup>(2)</sup>	Name	Description		Stream	Function		Stream	& Flood Man	agement			Hab	oitat		
			Dissipates Energy	Maintains Deeper Water	Focuses, Directs or Turns Flow	Promotes Gravel Sorting	Lowers Flood Elevation	Bank and Erosion Protection	Avulsion (Stream Movement) Protection	Fish Holding	Fish Rearing	Fish Cover and Refuge	Fish Food Source	Fish Spawning	Riparian and Upland Habitat Continuity
	Boulders	Boulders placed in stream or at bank toe. Obtained from existing levee.	$\checkmark$	$\checkmark$	$\checkmark$	$\checkmark$		$\checkmark$	$\checkmark$	$\checkmark$	$\checkmark$	$\checkmark$	$\checkmark$		
	Riffle	Boulders, cobbles and large gravel downstream of pools.	$\checkmark$		$\checkmark$	$\checkmark$				$\checkmark$		$\checkmark$	$\checkmark$		
	Pool	Deeper water. Typically on bends or below boulder drops.	$\checkmark$		$\checkmark$	$\checkmark$			$\checkmark$	$\checkmark$	$\checkmark$	$\checkmark$		$\checkmark$	
Not Shown	Pool Run Out (Run)	Downstream end of pool. Slow, deep, quite water.	$\checkmark$		$\checkmark$	$\checkmark$					$\checkmark$		$\checkmark$	$\checkmark$	$\checkmark$
Not Shown	Gravel Bar	Gravel on islands, banks or at downstream ends of pools, some with vegetation.				$\checkmark$					$\checkmark$		$\checkmark$	$\checkmark$	$\checkmark$
	New Channel	New Channel Meander, Side or Backwater Channel	$\checkmark$		$\checkmark$	$\checkmark$	$\checkmark$			$\checkmark$		$\checkmark$	$\checkmark$	$\checkmark$	$\checkmark$
<b>\$</b> = = <del></del>	Woody Habtat Structure	Large trees with or without rootwads buried in banks or in stream.	$\checkmark$		$\checkmark$	$\checkmark$				$\checkmark$	$\checkmark$	$\checkmark$	$\checkmark$	$\checkmark$	
	Levee Excavation, Regrade Slopes, Retain Select Trees	Selectively excavate levee. Save select trees and riprap for reuse. Bury removed trees in excavated floodplain/bank. Plant	$\checkmark$				$\checkmark$	$\checkmark$					$\checkmark$		$\checkmark$
	Spring Channel	Create new off channel stream from spring/irrigation return (Lampson)								$\checkmark$		$\checkmark$	$\checkmark$	$\checkmark$	$\checkmark$
	Selective Floodplain Excavation and Grading	Selectively excavate and grade floodplain. Retain 70% to 95% of trees. Plant.	$\checkmark$				$\checkmark$					$\checkmark$	$\checkmark$		$\checkmark$
Not Shown	Maintain existing bankfull depth	Where channel banks are lowered, maintain existing channel depth to maintain sediment conveyance.				$\checkmark$			$\checkmark$						
	preceeding sheet. ed on this sheet serve as a legend f	ior sheets S-7.1 through S-7.7.					1	1		1	1			1	<u> </u>
sion No: Date: 1 08/01/1	Description: 11 Channel downcut redesign	Initials: Designed: JJF JJF Drawn: MGF Checked: MKH	Umatilla	a Walla River County, Ore	gon	10 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5			oEngin			eneral Lege	nd and Tr	eatments	Sheet
APPROVE	D FOR CONSTRUCT			ated Tribes o ndian Reserv				52 Spo	23 East Sec kane, Washi	ond Avenue ngton 9920	2	Lampson Co	nstruction D	rawings	<b>S-3</b> .


õ									
P SF	Revision No:	Date:	Description:	Initials:	Designed: JJF	Walla Walla River	00 00 st. WALLA WA	LLA . Day, 0.0	
M E E	1	08/01/11	Channel downcut redesign	JJF	Drawn: MGF		S Commendation		GEOENGINEERS
900					Checked: MKH	Umatilla County, Oregon	Statute Dimension	The second se	
2698	APPF	OVED F	OR CONSTRUCTION		Date: 06/27/11	Confederated Tribes of the	Treaty of	1855	523 East Second Avenue
P.\2\					Project No: 2698-006-02	Umatilla Indian Reservation	▲ <u>) 中 (</u> ) 中		Spokane, Washington 99202





































## **Typical Sections**







▲ ) キ () キ () キ ( ▲


Date: 06/27/11

Project No: 2698-006-02

Umatilla Indian Reservation


523 East Second Avenue Spokane, Washington 99202







Umatilla Indian Reservation


👗 ) 🕸 () 🕸 () 🕸 ( 👗


















- 2. CHAIN SHALL BE COUNTER SUNK.
- 3. STABILIZATION THROUGH VEGETATION.
- 4.
- 5.





### GENERAL NOTES:

- 1. During the winter and spring of 2011, high persistent flows in the Walla Walla River caused the channel to degrade as much as 3 vertical feet along this project reach. This headcut is believed to have propagated upstream from where an old dam once existed about 1/2 mile downstream. This proposed Roughened Riffle is intended to stabilize the river bed near the downstream end of this river enhancement project.
- The proposed riffle is located near the downstream end of an existing riffle and where the proposed widened floodplain will return overbank 2. flows to the river. This is a good location to establish and maintain both vertical and horizontal control of the river.

### CONSTRUCTION NOTES:

- 1. At low flow, the water flows along the left (south) bank. To minimize disturbance to the river and water, it is proposed to reduce the width of flow along the left bank using concrete ecology blocks and construct the proposed riffle along the right bank. After the improvements are made along the right, the left portion of the riffle will be constructed.
- When constructing the left side of the riffle, raise the left bank back up to the top of the eroded bank, which is several feet above the existing 2. low flow channel currently along the left bank. Wood and rocks will be keyed into the left bank. The existing vegetation along the left bank shall remain.
- Install the Foundation Boulders into and along the banks. Then install the Footer Rocks and Sill Rocks. Do not over excavate anticipated 3. scour downstream of the riffle; allow scour to occur naturally.
- Construction shall commence downstream and proceed in an upstream direction so all rocks can be supported by downstream rocks. Footer 4 Rocks and Sill Rocks shall also be placed to buttress against the banks.
- Install Sill Rocks to maintain the existing river grade at downstream end. Sill Rock elevations may vary +/- 1 foot. Install to appear natural. 5.
- Channel elevations are approximate. The proposed Roughened Riffle shall be "field fit" with the direct supervision of the Engineer. 6
- Sill shall create a "U" shape in plan view; angled 30 to 40 degrees to the bank. 7.
- Sill and whole riffle shall create a gentle "U" shape in cross-section to maintain both low flows and full flood flows near the center of the 8. channel.
- 9 Upstream of the Sill, install Primary Boulders and Filler Rocks. Excavate rocks into existing bed material and backfill rocks with filler rocks and existing bed material so  $\frac{1}{2}$  to  $\frac{1}{3}$  of final boulder height is ultimately exposed. All rocks shall be supported by downstream rocks. Backfill in and around these rocks with local bed material.
- 10. Note there is a greater number of Primary Boulders near the Sill and the number (frequency) of Primary Boulders is reduced as the structure continues upstream. This is done to reduce costs while accommodating erosion and shifting of the whole structure in the future.
- 11. "Upstream Boulders" shall be installed upstream of the proposed Roughened Riffle. These boulders shall extend upstream to the extent of the existing riffle. These boulders are intended to encourage deposition of bed material delivered from upstream, extend the effective length of the Roughened Riffle and to slightly increase the water surface elevation in the pool immediately upstream.
- 12. "Downstream Boulders" shall be installed downstream of the Roughened Riffle. These boulders are intended to capture bed material scoured from the downstream end of the Roughened Riffle and to slightly raise the elevation of the pool immediately downstream of the Sill.
- 13. The volume of the proposed rocks is anticipated to increase the elevation of the river bed approximately 1.5 feet at the upstream end of the riffle
- 14. Several of the items for the proposed Roughened Riffle were included in the existing Bid Schedule and should not be considered extras. These items are noted in italics. The other items are considered extras.
- 15. Large wood shall be placed in the banks and bed as directed by the engineer.
- 16. The proposed Roughened Riffle shall be constructed to appear and function naturally.

### BOULDERS/ROCKS:

- 1. All proposed rocks shall generally be rounded and shall have similar dimensions along all three axes. Angular rocks are acceptable; however, flat elongated rocks are unacceptable
- on spherical shape.
- 3. Footer Rocks and Sill Rocks shall be installed as shown. All other rocks shall be buried so 1/4 to 1/3 of the boulder is exposed above the bed.
- 4 the boulders scouring down into the channel bed.
- 5. Foundation Rocks: Quantity = 4. Size = 7-feet. Volume / Rock = 6.6 cubic yard. Total Volume = 26.6 cubic yards.
- 6. Footer Boulders: Quantity = 15. Size = 6 feet. Volume / Rock = 4.2 cubic yards. Total Volume = 62.8 cubic yards.
- 7. Sill Rocks: Quantity = 15. Size = 6 feet. Volume / Rock = 4.2 cubic yards. Total Volume = 62.8 cubic yards.
- Primary Boulders: Quantity = 40. Size = 6 feet. (25 of the 40 boulders were included in the existing Bid Schedule. Bid Item 3530; Imported Boulders.) Volume / Rock = 4.2 cubic yards. Total Volume = 167.5 cubic yards.
- 9. Downstream Boulders: Quantity = 8. Size = 6 feet. Volume / Rock = 4.2 cubic yards. Total Volume = 33.5 cubic yards.
- 10. Upstream Boulders: Quantity = 8. Size = 5 feet, Volume / Rock = 2.4 cubic vards. Total Volume = 19.4 cubic vards.
- 11. Filler Rock (From Riprap on Site): Quantity = 200 vards. Size 2 to 5 feet (This item was included in the existing Bid Schedule, Item 3530: Salvaged Riprap.)
- 12. Upstream fish passage will be maintained by channel roughness.

### TREES:

- 1. These trees and anchors were included in the existing Bid Schedule.
- 2. Full Length Trees with Rootwads: Quantity = 5, L = 55-ft, DBH = 2 to 3-ft
- 3. Trees with Rootwads: Quantity = 20, L = 20-ft, DBH = 1.5 to 2-ft
- 4. Racking Members: Quantity = 40, L < 20-ft, DBH < 1-ft
- 5. Large Concrete Anchors: Quantity = 15.

### APPROXIMATE EXCAVATION AND FILL VOLUMES (ALL VOLUMES NOTED ARE BELOW THE OHWM):

- 1. Total Rock Fill = 572 cubic yards
- 2. Total Permanent and Temporary Excavation Below OHWM = 230 cubic yards
- 3. Total Temporary Excavation (Removal of Existing Bed Material for Boulder Placement) = 190 cubic yards
- 4. Total Permanent Excavation (North Channel Bank) = 40 cubic yards

Revision	No: Date:	Description:	Initials:	Designed: JJF	Walla Walla River	00 NNALIA WALLA - UIII 00	
1	08/01/11	Channel downcut redesign	JJF	Drawn: MGF		3 C PERIOD NO 1 RELEGICAL	GEOENGINEERS
				Checked: MKH	Umatilla County, Oregon	Charles Amount Statute	
API	PROVED F	OR CONSTRUCTION		Date: 08/01/11	Confederated Tribes of the	Treaty of 1855	523 East Second Avenue
				Project No: 2698-006-02	Umatilla Indian Reservation		Spokane, Washington 99202

2. Rock dimensions noted are minimums and measured along the intermediate axis. Quantities are also minimums. Rock volumes area based

Where boulders are not placed against one another, backfill boulder excavation with Filler Rocks (salvaged riprap) to reduce the likelihood of

### **Roughened Riffle Notes**






Image: state	inting A	pplication	Common Name	Instructions	Scientific Name				Trans	itional	Zone						Rij	parian	Zone	(8)						Ban	k Zone				Totals
<ul> <li> <ul> <li></li></ul></li></ul>						Size (gallons)	tings-ft) (ft on center)	lbs/acre)	coverage per	Acres	Units	Unit Cost	Total Cost	Size (gallons)	(sf	on center) /acre)	coverage per	Acres	Units	Unit Cost	Total Cost	Size (gallons)	Size (cuttings)	Spacing (ft on center) Planting Densitv (Ibs/acre)	Per la	Acres	Units	Unit Cost	Total Cost	Total Units	Total Cost
<ul> <li>         Amomposite of the series of the ser</li></ul>			Mountain brome		Bromus carniatus	NA	NA	1.2 1	100%	0.00	0.00			NA	NA	1.2	100%	2.2	3											3	
<ul> <li> <ul> <li></li></ul></li></ul>			Sandberg's bluegrass	mulch to disturbed areas.	Poa secunda	NA	NA	1.6 1	100%	0.00	0.00			NA	NA	1.6	100%	2.2	4											4	
A junga a necessary integral (a) shore (see all a shore (see all a) (b) (a) (b) (b) (b) (b) (b) (b) (b) (b) (b) (b	i G		Blue wildrye	,	Elymus glaucus	NA	NA	1.2 1	100%	0.00	0.00			NA	NA	1.2	100%	2.2	3											3	
Subtriate         Participate         Parite         Parite         Parti			Bluebunch wheatgrass	,	Pseudoroegneria spicata	NA	NA :	2.4 1	100%	0.00	0.00			NA	NA	2.4	100%	2.2	5											5	
k         Panderose pine Solubeity         Panderose pine Solubity         Panderose pine Solubeity			Idaho fescue		Festuca idahoensis	NA	NA	1.6 1	100%	0.00	0.00			NA	NA	1.6	100%	2.2	4											4	
Nursey and the series of t		Subtotal:						8		0.00						8		2.2													
Nr ref         Bile elderberry         No dropsol mix and/or organic mixed or lyand in media and plants i			Ponderosa pine		Pinus ponderosa	2	NA	40	10%	0.00	0.00																			0.00	
Nursery Stole         Node rose match a base of parts if notices at base of parts			Snowberry		Symphoricarpos albus	1	NA	18	15%	0.00	0.00			1	NA	12	25%	0.55	166											0.00	
Nursery       Woods rose       much at base of parts if       Nose woods       1       Na       Na			Blue elderberry		Sambbucus nigra	1	NA	30	5%	0.00	0.00			1	NA	30	5%	0.11	5			1	NA	12	5%	0.01	3			0.00	
stock         Sarucekery         Indecasary         Amelanchie almolola         1         NA         18         0.00         0.00         0.00         1         NA         18         10%         0.20         0.00 <td></td> <td>Nursery</td> <td>Woods rose</td> <td><i>,</i></td> <td>Rosa woodsii</td> <td>1</td> <td>NA</td> <td>18</td> <td>10%</td> <td>0.00</td> <td>0.00</td> <td></td> <td></td> <td>1</td> <td>NA</td> <td>18</td> <td>20%</td> <td>0.44</td> <td>59</td> <td></td> <td>0.00</td> <td></td>		Nursery	Woods rose	<i>,</i>	Rosa woodsii	1	NA	18	10%	0.00	0.00			1	NA	18	20%	0.44	59											0.00	
Wax currant       Wax currant       Ribes aureum       1       NA       18       5%       0.00       0.00       0 </td <td></td> <td>Stock</td> <td>Serviceberry</td> <td></td> <td>Amelanchier alnoifolia</td> <td>1</td> <td>NA</td> <td>18</td> <td>10%</td> <td>0.00</td> <td>0.00</td> <td></td> <td>0.00</td> <td></td>		Stock	Serviceberry		Amelanchier alnoifolia	1	NA	18	10%	0.00	0.00																			0.00	
Image: Note of the properties of the project noted. Unit costs may be input to calculate cost estimates. Head costs are dependent upon selected contractor and sources. Costs include a submit submit submit we disting the properties. Head costs are dependent upon selected contractor and sources. Costs include a submit submit we disting the properties. Head costs are dependent upon selected contractor and sources. Costs include a submit submit we disting the properties. Head costs are dependent upon selected contractor and sources. Costs include a submit submit we disting the properties. Head costs are dependent upon selected contractor and sources. Costs include a submit submit we disting the properties. Head the cuttings into a submit meter regime. The provide the tractor and sources. Costs include a submit we disting the properties. Head the cuttings into a distingt and the properties. Head the cuttings into a distingt and the properties. Head the cuttings into a distingt and the cuttings into a distingt and the properties. Head the cuttings into a distingt and the properties. Head the cuttings into a distingt and the properties of the project noted. Unit costs may be input to calculate cost estimates. Head the cuttings into a distingt and the cuttings measured by individual place. Head costs are dependent upon selected contractor and sources. Costs include are approximate. Head costs are dependent upon selected contractor and sources. Costs include are approximate. Head costs are dependent upon selected contractor and sources. Costs include are approximate. Head costs are dependent upon selected contractor and sources. Costs include are approximate. Head costs are dependent upon selected contractor and sources. Costs include are approximate. Head costs are dependent upon selected contractor. Head the cuttings into a distance and the cuttings into a distance and the cuttings into a distance and the cuttings into a distance andistance andistance and the cuttings into a distance and			Chokecherry		Prunus virginiana	1	NA	18	15%	0.00	0.00			1	NA	18	10%	0.22	30											0.00	
Subtrain         Subtrain         Image: Subtrain		Γ	Wax currant		Ribes aureum	1	NA	18	5%	0.00	0.00																			0.00	
Live Cutting         Black cotonwood         1.) Plant live cuttings into permanent moisture regime.         Populus trichocarpa         NA         5         12         0.0         0.66         570         NA         1.+         10         15%         0.03         15         12           Live Cuttings         Red Alder         2.) Plant immediately if possible.         Alnus rubra         Image: Compute Second Sec		Γ	Golden currant		Ribes aureum									1	NA	18	10%	0.22	30											0.00	
Live       Red Alder       2.) Plant immediately if possible,       Alnus rubra       Image: Comus serices       NA       5       12       5%       0.11       33       NA       1+       10       40%       0.09       40       10         Subtoal:       Subtoal:       Comus serices       One       One       Image: Comus serices       NA       5       12       5%       0.11       33       NA       1+       10       40%       0.09       40       Image: Comus serices       Image: Comus serices       Image: Comus serices       Image: Comus serices       NA       5       12       5%       0.11       33       NA       1+       10       40%       0.09       40       Image: Comus serices         Subtoal:       Comus serices       Comus serices       0.00       0.00       0.00       0 <td></td> <td>Subtotal:</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>0.00</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>2.2</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>0.23</td> <td></td> <td></td> <td></td> <td>0.00</td> <td></td>		Subtotal:								0.00								2.2								0.23				0.00	
Live       Red Alder       2.) Plant immediately if possible.       Alnus rubra       Alnus rubra       NA       1       10       40%       0.09       40       40         Red osier dogwood       4.) Irrigate as necessary       Comus serices       Comus serices       NA       5       12       5%       0.11       33       NA       1+       10       40%       0.09       40 <td< td=""><td></td><td></td><td>Black cottonwood</td><td>,</td><td>Populus trichocarpa</td><td>NA</td><td>5</td><td>12</td><td>30%</td><td>0.00</td><td>0.00</td><td></td><td></td><td>NA</td><td>5</td><td>12</td><td>30%</td><td>0.66</td><td>570</td><td></td><td></td><td>NA</td><td>1+</td><td>10</td><td>15%</td><td>0.03</td><td>15</td><td></td><td></td><td>585</td><td></td></td<>			Black cottonwood	,	Populus trichocarpa	NA	5	12	30%	0.00	0.00			NA	5	12	30%	0.66	570			NA	1+	10	15%	0.03	15			585	
Red osier dogwood 4.) Irrigate as necessary Comus serices   Subtoal: Image: as necessary Comus serices   Total: Image: as necessary Comus serices   Image: as necessary Image: as necessary Comus serices   Total: Image: as necessary Image: as necessary   Image: as necessary Image: as necessary   Total: Image: as necessary   Total: Image: as necessary   Image: as necessary Image: as necessary   Image: as necessary Image: as necessary   Total: Image: as necessary   Image: as necessary Image: as necessary   Image: as necessary Image: as necessary   Image: as necessary Image: as necessary   Total: Image: as necessary   Image: as necessary Im			Red Alder	2.) Plant immediately if possible.	Alnus rubra																	NA	1+	10	40%	0.09	40			40	
Total: 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.			Red osier dogwood	<i>i i i</i>	Comus serices									NA	5	12	5%	0.11	33			NA	1+	10	40%	0.09	40			73	
table identifies the plant species and quantities for the project noted. Unit costs may be input to calculate cost estimates. Seeds measured by pound. Potted plants and cuttings measured by individual piece. Cost estimates, if calculated, are approximate. Final costs are dependent upon selected contractor and sources. Costs include acquisition, handling, transportation, storage, and installation. Refer to Sheet S-10.1 for typical planting zone designations and locations. Planting Applications and Specifications are based on USDA-NRCS technical notes and literature. Transplanted materials and live cuttings integral with woody habitat structures shall be installed concurrently with structure placement.		Subtotal:								0.00								2.2								0.23				699	
Seeds measured by pound. Potted plants and cuttings measured by individual piece. Cost estimates, if calculated, are approximate. Final costs are dependent upon selected contractor and sources. Costs include acquisition, handling, transportation, storage, and installation. Refer to Sheet S-10.1 for typical planting zone designations and locations. Planting Applications and Specifications are based on USDA-NRCS technical notes and literature. Transplanted materials and live cuttings integral with woody habitat structures shall be installed concurrently with structure placement.		Total:								0.00								2.2								0.23					
Native vegetation previously established but the CTUIR shall be maintained to the best extent possible. All existing trees larger than 8" in diameter and root wads to be removed shall be incorporated into the proposed woody habitat structures in addition to those trees specified in these drawings. Riparian zone (over the total site) shall also include 30, 1 gallon containerized River Birch trees. Trees to be located as directed by Engineer (06/23/11). No: Date: Description: Initials: Designed: JJF Northeast Contract Contrect Contract Contract Contract Contract	Seeds r Cost es Refer to Planting Transpl Native v All exist	measured by timates, if ca o Sheet S-10 g Applications anted materi /egetation pr ting trees larg	pound. Potted plants ar loculated, are approximat 1 for typical planting zon s and Specifications are als and live cuttings integ eviously established but ger than 8" in diameter a the total site) shall also i	nd cuttings measured by individua e. Final costs are dependent upor the designations and locations. based on USDA-NRCS technical gral with woody habitat structures the CTUIR shall be maintained to nd root wads to be removed shall nclude 30, 1 gallon containerized	I piece. n selected contractor and notes and literature. shall be installed concurr the best extent possible. be incorporated into the	source ently v	es. Cost vith struc	s inclu cture p dy hat	placeme bitat stru	ent. uctures i	in additi	on to tho		-																	

ΡSF	Revision No:	Date:	Description:	Initials:	Designed: JJF	Walla Walla River	00 w.WMLLA WALLA . U.J. 00	
TEM	1	08/01/11	Channel downcut redesign	JJF	Drawn: MGF	Umatilla County, Oregon	S Commence of the second	GEOENGINEERS
9008					Checked: MKH	Confederated Tribes of the	Report Annual Providence	
2695	APPF	≹OVED F	OR CONSTRUCTION		Date: 06/27/11		Trenty of 1855	523 East Second Avenue
P:\2\					Project No: 2698-006-02	Umatilla Indian Reservation		Spokane, Washington 99202

MKH : MGF


- 1.33pm 2011 2


Application	Common Name	Instructions	Scientific Name				Tran	sitiona	l Zone						Rip	barian	n Zone	e <sup>(8)</sup>						Ba	ank Z	one			Г	Tota
				Size (gallons)		spacing (rt on center) Planting Density (Ibs/acre)	Percent coverage per zone	Acres	Units	Unit Cost	Total Cost	Size (gallons)	Size (cuttings)	Spacing (ft on center) Planting Density (Ibs/acre)	Percent coverage per zone	Acres	Units	Unit Cost	Total Cost	Size (gallons)	Size (cuttings)	Spacing (ft on center) Planting	Density (IDS/acre) Percent coverage per zone			Units	Unit Cost	Total Cost	Total Units	
	Mountain brome		Bromus carniatus	NA	NA		100%	4.70	5.64			NA	NA		100%	3.6	4						•	•				•	10	
	Sandberg's bluegrass	1.) Add topsoil mix and/or organic mulch to disturbed areas.	Poa secunda	NA	NA	1.6	100%	4.70	7.52			NA	NA	1.6 <sup>-</sup>	100%	3.6	6												13	
Grass Seed Mix	Blue wildrye	<ul><li>2.) Seed all disturbed areas</li><li>3.) Cover with straw or mulch if</li></ul>	Elymus glaucus	NA	NA	1.2	100%	4.70	5.64			NA	NA	1.2 <sup>-</sup>	100%	3.6	4												10	
	Bluebunch wheatgrass	necessary to minimize erosion. 4.) Irrigate as necessary	Pseudoroegneria spicata	NA	NA	2.4	100%	4.70	11.28			NA	NA	2.4 <sup>-</sup>	100%	3.6	9												20	
	Idaho fescue		Festuca idahoensis	NA	NA	1.6	100%	4.70	7.52			NA	NA	1.6 1	100%	3.6	6												13	
Subtotal:						8		4.70						8		3.6														
-	Ponderosa pine	_	Pinus ponderosa	2	NA	40	10%	0.47	12.80					r															12.80	
	Snowberry		Symphoricarpos albus	1	NA	18	15%	0.71	94.78			1	NA	12	25%	0.90	272												94.78	
_	Blue elderberry		Sambbucus nigra	1	NA	30	5%	0.24	11.37			1	NA	30	5%	0.18	9			1	NA	12	2 5%	0.0	)2	5			11.37	
Nursery	Woods rose	1.) Add topsoil mix and/or organic mulch at base of plants if	Rosa woodsii	1	NA	18	10%	0.47	63.19			1	NA	18	20%	0.72	97												63.19	
Stock	Serviceberry	necessary. 2.) Irrigate as necessary	Amelanchier alnoifolia	1	NA	18	10%	0.47	63.19				•	r <b>r</b>		r													63.19	
_	Chokecherry	_	Prunus virginiana	1	NA	18	15%	0.71	94.78			1	NA	18	10%	0.36	48												94.78	
_	Wax currant	_	Ribes aureum	1	NA	18	5%	0.24	31.59				1	r		r													31.59	
	Golden currant		Ribes aureum									1	NA	18	10%	0.36	48								_				0.00	
 Subtotal:								4.70								3.6								0.3	0				371.71	
	Black cottonwood	1.) Plant live cuttings into permanent moisture regime.	Populus trichocarpa	NA	5	12	30%	1.41	426.53			NA	5	12	30%	1.08	570			NA	1+	10	) 15%	6 0.0	)5	20			1016	
Live Cuttings	Red Alder	2.) Plant immediately if possible.	Alnus rubra										1							NA	1+	10	40%	6 0.1	2	52			52	
	Red osier dogwood	4.) Irrigate as necessary	Comus serices									NA	5	12	5%	0.18	54			NA	1+	10	40%	6 0.1	2	52			107	
 Subtotal:								4.70								3.6								0.3	0				1175	_
Total:								4.70								3.6								0.3	0					


P SF	Revision No:	Date:	Description:	Initials:	Designed: JJF	Walla Walla River	$\begin{array}{ccc} 0.0 \\ 0.0 \\ 0.0 \\ \end{array} \\ \left( \begin{array}{c} N^{NNLA, WALLA}, \ U_{AL} \\ 0.0 \\ \end{array} \right) \end{array} $	
TEM	1	08/01/11	Channel downcut redesign	JJF	Drawn: MGF	Umatilla County, Oregon	S Standard Bir Alland	GEOENGINEERS
9008					Checked: MKH	Confederated Tribes of the	E AND A DECEMPTOR	
2695	APPF	₹OVED F	OR CONSTRUCTION		Date: 06/27/11		Trenty of 1855	523 East Second Avenue
P:\2\					Project No: 2698-006-02	Umatilla Indian Reservation		Spokane, Washington 99202

**GF** 

2011 Aug 01, 0







### Construction Sequencing and Fish Management Plan (See note 1 below)

Work in the river below the Ordinary High Water Mark (OHWM) shall only occur during the "Fish Window" between July 1 and September 30, or as otherwise specified in project-specific environmental permits. Work above and beyond the OHWM may occur any time of the year as weather, site conditions and permits allow.

Construction will occur in two (2) general phases as described below. In general: Phase 1 includes work in the side channel areas whereas Phase 2 primarily includes in-channel work along the main stem of the river and the construction of the spring channel. Phases 1 and 2 may be constructed in either a single construction season or in two different construction seasons. Construction shall occur in the following general steps, which correspond numerically to those shown on Sheets 11.1 and 11.2. Refer to the preceding design sheets for specifics regarding the construction of the proposed improvements.

Should Phase 1 and Phase 2 be constructed during the same construction season, it is recommended the construction of the side channel (Phase 1) be postponed until after the construction along the main river (Segments A, B and C in Phase 2) has been completed.

### Phase 1

### 1. General site preparation

- 1.1. Remove blackberry bushes and unnecessary/undesirable underbrush in areas to be disturbed.
- 1.2. Establish survey control.
- 1.3. Establish limits of excavation/fill, stockpile areas, staging areas, haul roads and signage.
- 1.4. Mark all trees to remain.
- 1.5. Install and maintain necessary erosion and sedimentation controls.

#### 2. Excavate and rough grade side channel area

- Excavate side channel area. Do not connect to river. 2.1.
- Preserve existing trees where practical to maximize riparian integrity 22
- Place excavation spoils in fill area near downstream end of project (Spoils Location Option A) on existing dirt road (Spoils Location Option B) or in old quarry 2.3. up on adjacent hillside (Spoils Location Option C). Grade excavated spoils along existing dirt road to maintain road use during construction.
- 2.4 Temporarily stockpile suitable topsoil and channel bed material (gravel, cobbles & boulders) in specified locations. Stockpiled material will be used in Phase 2. No stockpiled material in temporary stockpile areas shall remain in on site after project is completed.

#### 3. Sculpt side channel (fine grade)

- 3.1. Excavate and sculpt the side channel. This step includes grading the pools and riffles. Place gravel, cobbles and boulders in side channel. Do not connect side channel to river
- Location of Phase 2 crossings and access routes as shown on Sheet S-11.2 do not require final sculpting at this time. 3.2.

#### 4. Install habitat structures in side channel

- Install habitat structures in side channel. 41
- Plant riparian shrubs and trees integral with habitat structures during installation of habitat structures. 4.2.
- Locations of Phase 2 crossings and access routes as shown on Sheet S-11.2 do not require habitat structures at this time. 4.3.

#### 5. Connect side channel to river at downstream end of side channel

- Connect side channel to river at downstream end to allow the side channel to drain, enable the river to backwater into the channel and enable the habitat to 5.1. mature
- Full connection to river is acceptable only if construction occurs during Fish Window and if Phase 2 is to be constructed immediately after Phase 1. Connect 5.2. side channel with main channel with minimum 24 inch diameter culvert if construction/connection must occur during non-Fish Window period and/or if Phase 2 is to be constructed during a later construction season.
- Install fish exclusion net, flood gates/flap gates and/or other suitable fish screen at downstream end of side channel to prevent fish from entering side channel. 5.3. Fish shall not be allowed in side channel until Phase 2 is completed and side channel is activated.
- Do not connect side channel to river at upstream end of side channel. 54

#### 6. Plant disturbed areas (If Phase 2 does not immediately follow Phase 1)

- Plant disturbed areas with appropriate vegetation. Planting of Phase 1 area may be postponed until after Phase 2 is finalized only if Phase 2 is to be 6.1. constructed immediately after Phase 1 during the same construction season.
- Location of Phase 2 crossings and access routes shall be protected with either temporary grasses or gravel to prevent erosion. 62
- Install and maintain temporary erosion and sedimentation controls to prevent erosion and sediment from entering side channel and/or river. 6.3.
- 64 Irrigate all new vegetation during growing season.

### Phase 2

#### 1. Construct Segment A

11 Excavate Phase 2 area along Segment A down to OHWM. Slope back steep slopes and remove portions of the levee down to OHWM, grade around existing trees to remain. Maintain viable existing root structure along bank to the greatest extent possible/practicable. Stockpile riprap/rock from levees near river for future placement of rock into river.

NOTE: Numbers correspond to construction steps as noted on

### sheet 11.2.

Revision No:	Date:	Description:	Initials:	Designed: JJF	Walla Walla River	0.0	
1	08/01/11	Channel downcut redesign	JJF	Drawn: MGF	Umatilla County, Oregon		GEOENGINEERS
				Checked: MKH		A CONTRACT OF A	
APPF	OVED F	OR CONSTRUCTION		Date: 06/27/11	Confederated Tribes of the	Through at 1957	523 East Second Avenue
				Project No: 2698-006-02	Umatilla Indian Reservation		Spokane, Washington 99202

- 1.2. rocks/riprap removed from levee for future use or resale by owner.
- 1.3. Excavate, stockpile and irrigate trees to be transplanted. Or transplant trees in final location to the extent possible.
- 1.4. proposed enhancements and fish health.
- 1.5. Construction of work zones shall commence at the upstream end of the project area and proceed downstream.
- 16 flowing portion of the river.
- 1.7.
- 1.8. Fish shall be pushed/seined out of active work zone.
- 1.9. Establish and maintain temporary construction access to the river from the bank in a manner that minimizes disturbance.
- extent possible
- 1.11. Remove cofferdam after segment is constructed.
- 1.12. placing rocks on existing river bed and excavation of existing bed shall be minimized.
- Remove and stabilize temporary constriction access sites.
- 1.14. Monitor and adjust wood and rock structures as necessary.
- 1.15. Plant woody vegetation, hydroseed and mulch disturbed areas throughout Segment A. Irrigate as necessary.

#### 2. Construct Segment B

2.1. Construct Segment B using procedure and sequence indicated for Segment A.

#### 3. Connect side channel to river

- 31 Isolate work zone around upstream end of side channel.
- 3.2. activation of side channel becomes absolutely necessary.
- 3.3 in side channel to be regulated to facilitate testing and adjustments of side channel.
- 3.4. Monitor and adjust side channel and side channel structures as necessary.

#### 4. Construct Segment C

- 4.1. Construct Segment C using same procedures and sequence indicated for Segment A.
- Remove cofferdams 4.2.

#### 5. Adjust and fine tune all structures

5.1. Adjust and fine tune all habitat structures in river and side channel.

#### 6. Construct spring channel

- 6.1. Excavate and shape spring channel.
- 6.2. Fine grade spring channel area.
- 6.3. Plant woody vegetation, hydroseed and mulch disturbed areas. Irrigate as necessary.

#### 7. Fine grade remaining disturbed areas

- 7.1. Remove all stockpiled soil, gravel cobble, rock and/or riprap from site.
- 8. Plant, transplant, hydroseed, mulch and irrigate disturbed areas as per vegetation plan
- 9. Remove and dispose of properly all debris from site, demobilize
- 10. Monitor, Irrigate and maintain

Place excavation spoils in fill area near downstream end of project (Spoils Location Option A) on existing dirt road (Spoils Location Option B) or in old quarry up on adjacent hillside (Spoils Location Option C). Grade excavated spoils along existing dirt road to maintain road use during construction. Stockpile large

Segment A may be divided into smaller sub-segments or "work zones" in the active river (below the OHWM) if desirable and less disruptive to water quality,

Install a cofferdam in the river along north bank beyond area immediate area of disturbance in work zone. Cofferdam is intended to isolate clean river water from turbid water in active work zone (it's not intended to dry up construction zone). Cofferdams may consist of seclusion fencing, floating booms, sand bags, inflatable bladders and/or other suitable means. Cofferdams should include plastic liner or fine mesh silt fence to reduce the amount of fines entering the free

Working from upstream to downstream, the isolated work zone shall be seined by a qualified crew of fish biologists, as designated by CTUIR and/or ODFW. The river channel can be seined in smaller lengths, if necessary, and as determined in the field. The CTUIR is responsible for performing and overseeing the fish removal and obtaining the appropriate fish collection permits. (Actual physical removal of fish is excluded from contractor's responsibilities.)

1.10. Construct work zones; installing woody habitat structures, excavating deeper pool areas immediately adjacent to wood structures and planting woody vegetation in and around woody habitat structures. Do not allow flow into proposed side channel. Disturbance of channel bed should be minimized to the

Install in-stream rocks and rock structures along Segment A using stockpiled riprap and rocks or imported rock. Construction equipment may be operated in the active river channel to place rock provided disturbance to the river bottom and water quality is minimized. Rock structures will primarily be constructed by

Construct/install woody habitat structures in upstream end of side channel. Maintain river flow through Segment B. Minimize flow through side channel until

Using bed excavation, gravel/cobble push up dam or other suitable, minimally disruptive means; divert water into side channel. Gradually connect side channel to river at a rate of approximately 10 cubic feet per second (cfs) per hour per to reduce large sediment entrainment in the main channel. Enable flow

## **Construction Sequencing Notes**

Sheet

S-11

					Ma	in Cha	nnel										
Struture ID	Structure Name	# Of Proposed Structures Per Channel	# Of Small Concrete Anchors Per Channel	# Of Large Concrete Anchors Per Channel		W	Full Len ith Rootw				Tree With	Rootwad	I	Tr	ree Witho	ut Rootw	ad
					DBH < 8" L < 20'	DBH = 8 - 12" L = 25'	DBH = 12" - 18" L = 30'	DBH = 18" - 24" L = 40'	DBH = 24" - 36" L = 60'	DBH = 8 - 12" L = 20'	DBH = 12" - 18" L = 20'	DBH = 18" - 24" L = 25'	DBH = 24" - 36" L = 40'	DBH = 8 - 12" L = 20'	DBH = 12" - 18" L = 20'	DBH = 18" - 24" L = 25'	DBH = 24" - 36" L = 40'
HS-1	Typical Meander Jam	3		40	100	10	20			5	20	30		5	5	5	
HS-2	Typical Root Wad								ļ						<b></b>		
HS-3	Typical Sweeper	5		5					5						<b> </b>		
HS-4	Typical Buried Snag	3						3							<b> </b>		
HS-5	Typical Step Turn														───		
HS-6 HS-7	Typical Boulder Cluster Typical Small Woody Debris																
HS-8	Typical Large Woody Debris	2		30	100	10				5	20	30		5	10	20	
HS-9	Typical River-Wide Boulder Placement Plan	2			100	10				5	20	50		5	10	20	
HS-10	Typical Pocket Water														<u> </u>		
IS-11	Typical Longitudinal Log (1)	3						3	3								
HS-12	Apex Jam	1		2				2	1								
Subtotal			0	75	200	20	20	8	9	10	40	60	0	10	15	25	0
	·		•	•	Sic	de Cha	nnel	•	•								
HS-1	Typical Meander Jam																
HS-2	Typical Root Wad	12	12		24						12						
HS-3	Typical Sweeper	8		8				4	4								
HS-4	Typical Buried Snag																
HS-5	Typical Step Turn	2	3	3	8				4						<u> </u>		
HS-6	Typical Boulder Cluster								ļ						<b></b>	ļ	
HS-7	Typical Small Woody Debris	3	20	20	80	5	15	10	ļ	15	15	30			<b></b>	ļ	
HS-8	Typical Large Woody Debris								3						<b></b>	ļ	
HS-9	Typical River-Wide Boulder Placement Plan														<b> </b>		
HS-10	Typical Pocket Water								<u> </u>						<b> </b>		
HS-11	Typical Longitudinal Log (1)														───		
HS-12	Apex Jam		25	24	110	F	15	4.4	11	15	27	30	0	0		0	
Total	l		35	31	112	5	15	14	11	15	27	30	U	0	0	0	0
						ole Pro	T .				1					1	
Total:	Main Channel and Side Channel		35	106	312	25	35	22	20	25	67	90	0	10	15	25	0
tion: I downcut r	edesign JJF Drawn: MGF		Valla Walla tilla County		ni ni	n n Suse watta w	ALLA - URACINA DO		Geo	ENG	INEEF	is G	Tree	Quanti	ities Fo	r Habita	at Stru
			derated Tril			Statula India	RESERVATO				econd A						
JUNSTR	UCTION Date: 06/27/11		la Indian Re			Treaty o	.r 18 <sup>55</sup>			ane, Was				Lompor	on Const	ruction D	rowing

# **Bid Schedule**

ltem #	Item Description	Units	Unit Cost (\$)	No. of
				Phase
Division 1	General Requirements	Lump Sum		1
2100	Environmental Controls	Lump Sum		1
2110	Cultural Resources	Lump Sum		1
2200	Protection of Existing Installations	Lump Sum		1
2300	Cleaning	Lump Sum		1
3110	Mobilization and Demobilization	Lump Sum		1
3120	Construction Staking	Day		10
3130	Traffic Control and Management	Lump Sum		1
3210	Clearing, Grubbing, Stockpiling and Disposal	Acre		4.00
3220	Topsoil Stripping, Stockpiling and Reuse	Acre		4.00
3230	Tree and Plant Protection and Salvage	Lump Sum		1
3240	Dewatering	Lump Sum		1
3310	Levee Excavation	CY		11,30
3320	Floodplain, Side Channel and Spring Channel Excavation and Grading	CY		9,700
3330	Fill and Grading (Spoils Area A)	CY		400
3330	Fill and Grading (Spoils Area B) (N/A, 06/23/11)	CY		_17,16
3330	Fill and Grading (Spoils Area C) (Changed, 06/23/11)	CY		_3,00
3340	Haul to Spoils Location C	CY		3,000
3410	Cofferdams	LF		2,10
3520	Woody Habitat Structures	Lump Sum		1
3530	Rock Structures (Imported Boulders)	Each		50
3530	Rock Structures (Salvaged Riprap)	Each		600
3530	Rock Structures (Cobbles and Gravel)	CY		500
3620	Seeding and Planting	Lump Sum		1
3630	Transplanting Trees and Shrubs	Lump Sum		1
3700	Haul and Disposal of Excavated Material	CY		0
3800	Site Cleanup and Repair	Lump Sum		1

L									
R	evision No:	Date:	Description:	Initials:	Designed: JJF	Walla Walla River Umatilla County, Oregon Confederated Tribes of the Umatilla Indian Reservation		GEOENGINEERS	
Г	1	08/01/11	Channel downcut redesign	JJF	Drawn: MGF				
Г					Checked: MKH				
Г	APPR	OVED F	OR CONSTRUCTION		Date: 06/27/11		Trans of 25%	523 East Second Avenue	
					Project No: 2698-006-02			Spokane, Washington 99202	

nite						
nits	Cost (\$)					
+ 2	Phase 1 + 2					
)						
<del>)</del> 0						
- 20,100						
C	Sheet					
	Lampson Construction Drawings					
Lai	mpson Construction Di	awings	S-11.6			