A 211-6050 DN

Received By OWEB

Type in the information for Sections I and II.

OCT 18 2010

Name of project: Lampson Levee Setback and Habitat Restoration

OWEB funds requested: \$97,985.00

Total cost of project: \$813,534.00

Project location:

This project occurs at (check one):

A single site

Multiple sites

Watershed Name(s)	County or Counties
Walla Walla River	Umatilla

Township, Range, Section(s)	Longitude, Latitude (e.g., -123.789, 45.613)	Watershed code(s) – Please note the 10-digit
(e.g., T1N, R5E, S12)	(required for federal/state reporting)	hydrologic unit code, previously 5 th Field HUC
T5N, R36E, Sections 18,19	-118.355, 45.902	1707010201

Applicant	Project Manager
Name: Brian Wolcott	Name: Wendy Harris
Organization: Walla Walla Basin Watershed	Organization: Walla Walla Basin Watershed
Council	Council
Address: 810 South Main St Milton-Freewater	Address: 810 South Main St Milton-Freewater
97862	97862
Phone: 541-938-2170	Phone: 541-938-2170
Fax: 541-938-2170	Fax: 541-938-2170
Email: brian.wolcott@wwbwc.org	Email: wendy.harris@wwbwc.org

Fiscal Agent	Landowner(s)
Name: Wendy Harris	Public: Agency:
Organization: Walla Walla Basin Watershed	Private: Name(s): Clark and Lyla Lampson
Council	
Address: 810 South Main St Milton-Freewater	Address: 54738 Day Rd. Milton-Freewater 97862
97862	
Phone: 541-938-2170	Phone: 541-938-4711
Fax: 541-938-2170	
Email: wendy.harris@wwbwc.org	

CERTIFICATION:

I certify that this application is a true and accurate representation of the proposed work for watershed restoration and that I am authorized to sign as the Applicant or Co-Applicant. By the following signature, the Applicant certifies that they are aware of the requirements (*see Application Instructions*) of an OWEB grant and are prepared to implement the project if awarded.

1	Anthe		1.1
Applicant Signature:	WR Hold	Date:	10/1
Print Name:	BRIAN R. WELCOTT	Title:	Eyer. D
Co-Applicant Signature:		Date:	
Print Name:		Agency:	

5/10 123-TOP WWBWC

09-11 OWEB Watershed Restoration Grant Application - Sections I & II - April 2010

Section II PROJECT INFORMATION

1. Abstract. In approximately 200 words, 1) identify the project location, 2) state the watershed issue or problem to be addressed, 3) the proposed solution including the area or other measurable units to be treated, 4) any proposed effectiveness monitoring, and 5) how OWEB funds will be used.

This project will remove portions of private levee that was constructed years ago and constricts the Walla Walla river's ability to meander, limits fish habitat complexity, and limits riparian vegetation. This project will implement a levee setback design that will provide meander room, improved fish habitat along a 3/8th mile stretch of river, revegetate the riparian area and floodplain, install a secondary backwater channel, and reallign a channelized spring creek. Approximately 22 acres of conservation easement exists on the Lampson property along the Walla Walla River floodplain however it is currently disconnected from the river by the existing levee. Over 3/8ths of a mile of riparian habitat will be restored along (ESA listed) steelhead and spring chinook spawning habitat and (ESA) bull trout rearing habitat. The river bank where the levee will be removed will be redesigned for stability and fish habitat, utilizing J-hooks, root wads, and rock structures to create pools and spawning gravels. OWEB funds will be used to purchase vegetation, prep planting areas, plant vegetation, purchase of rock, and rock placement. This will match BPA funds that will cover the levee setback and instream habitat work.

2. Has this project or ay element of this project, ever been submitted in a previous application(s) to OWEB?

		🖾 Yes 🗌 No
	If yes, what was the application number(s)? 201-363, 211-6023	
3.	Is this project, or any element of this project, a continuation of a previously funded OWEB restoration project(s)?	🗌 Yes 🛛 No

If yes, what was the grant number(s)?

4. Is this project a result of a previously funded OWEB Technical Assistance project (s)? 🛛 Yes 🗌 No

If yes, what was the grant number(s)? 208-5031

5. **Project Partners.** Show all anticipated funding sources, and indicate the dollar value for cash or in-kind contributions. Be sure to provide a dollar value for each funding source. If the funding source is providing in-kind contributions, briefly describe the nature of the contribution in the Funding Source Column. Check the appropriate box to denote if the funding status is secured or pending. In the Amount/Value Column, provide a total dollar amount or value for each funding source.

Funding Source Name the Partner and what their contribution is.	Cash	In-Kind	Secured (x)	Pending (x)	Amount/Value
OWEB	\$100,000.00	\$			\$97,985.00
Landowner(s):Clark and Lyla Lampson	\$	\$165,000.00			\$165,000.00
Confed. Tribes of Umatilla Indian Reservation Fish Habitat Program	\$ 666,009.00	\$			\$ 715,549.00
	\$	\$			\$
	\$	\$			\$
	\$	\$			\$
	\$	· \$			\$
	\$	\$			\$
	\$	\$			\$
	\$	\$			\$

		\$	\$			S
		\$	\$			\$
	Total Estimated Funds (add all amounts i	in the far-right	Column):			*\$880,549.00
	* The total should equal the total cost of the p	project on page 1	of the application	1.		· · · · · · · · · · · · · · · · · · ·
6.	Have any conditions been placed on ot	her funds that	may affect con	pletion?		Yes 🛛 No
	If yes, explain:					
7.	Are you requesting OWEB funds for E	Sffectiveness M	lonitoring?			Yes 🛛 No
	If you check "Yes", follow the instructions	in Question R1	<u>6</u>			
8.	Are you requesting OWEB funds for R	Riparian Plant	Establishment	?	\boxtimes	Yes 🔲 No
	If you check "Yes", follow the instructions	in Question R1	7			

.

Section III SPECIFIC RESTORATION PROJECT ACTIVITY

These essay questions and their answers are designed to guide you and reviewers through a logical process of understanding and identifying the problem to "fixing" the problem and measuring for success. **Refer to the Application Instructions for clarification and helpful examples.**

You may use the application form to respond to the questions, using additional sheets of paper as necessary **OR** answer the questions on separate pages. Be sure to include the question numbers and text of the questions before you begin typing your answers to assist the reviewers in evaluating your application.

Use 8½" x 11" paper. A double-sided application and materials are encouraged except for oversize maps and designs or multiple sets for reviewers. All materials should be **single-spaced** wherever possible, **unstapled** and **unbound**, except for sets of maps/photos/designs (see Page 1 of the application instructions for assembling multiples for reviewers). Use a 12-pt type size to answer the questions and a 10-pt type size for the tables. Use bullets where appropriate. Use **bold face** and *italics* for emphasis only. Do not use color highlights for text emphasis or in tables as the highlight turns black when the application is scanned. If the project involves multiple sites, be specific for each.

R1. Contextual Overview

Provide the location and significance of the project including why that location was chosen and a brief explanation of the history of the issues leading to the project. Describe the project in the context of the landscape including the key water quality, water quantity, species, habitat, land use and resource management issues (physical or social) that are proposed to be addressed in that watershed. See the Application Instructions for clarification.

The private levee along the Lampson property was constructed several decades ago and is one of many that constrict the river's ability to meander and prevent fish habitat complexity such as pools, spawning gravels, and large woody debris. This highly channelized reach of the river produces high flood velocities, imperiling juvenile fish, fry and fish eggs and limiting backwater or other low velocity refugia for fish during high flow events, and limits year round fish habitat complexity.

Designs have been completed and reviewed. Three alternatives were taken to a 50% design, one was selected.

The landowners at the project site, Clark and Lyla Lampson are committed to restoring the floodplain benefits of their property. They have put 22 acres of their land into a 15 year conservation easement with the Confederated Tribes of the Umatilla Indian Reservation. The Tribal fish habitat program has been restoring the former orchard lands to a mix of cottonwood and other native trees and grasses. The Lampsons are considering a permanent conservation easement with the Blue Mountain Land Trust.

The Lampson property is located on the mainstem Walla Walla River at river mile (RM) 49, approximately 2.5 miles southeast of Milton-Freewater, Oregon. The Lampson Reach of the Walla Walla River is located within the northeast quarter of Section 19 of Township 5 North, Range 36 East of the Bowlus Hill, Oregon quadrangle map. The site location is shown on Sheet S-1. An aerial photo of the existing site is presented on Sheet S-4.1. Site soils generally consist of silt loam in the riparian and agricultural areas, throughout the valley floor, which is laterally controlled by rock outcrops. Sheet S-4.2 identifies the site soils, rock outcrops and boundaries. Site topography is shown on Sheet S-4.3.

A long-term conservation easement, signed by the landowner in 1998, includes 2,000 feet of the mainstem Walla Walla River and 22 acres of adjacent riparian and upland habitat. The approximate location of this easement is shown on Sheet S-4.4. The river along this reach is confined by a near-vertical rock cliff on the south bank and a levee constructed in the 1960s on the north bank. The majority of the Lampson Reach consists of confined, moderately incised riffles with essentially no floodplain connectivity during all but extreme flood events (the 1996/1997 flood inundated much of the property on the backside of the levee. Based on field observations and conversations

with the CTUIR and property owner, the levee appears to have been "field designed" and most likely does not satisfy current U.S Army Corps of Engineers design standards.

The project reach riparian area is largely restricted to the immediate bank area due to natural confinement by a vertical rock cliff on the south (left) bank and artificial confinement by a levee on the north (right) bank. In general, the riparian vegetation on bars and the immediate banks, inside the levee, is dominated by a black cottonwood (*Populus trichocarpa*) overstory. The understory is largely comprised of Himalayan blackberry (*Rubus armeniacus*) and other woody shrubs, likely emerging from rhizomes of overstory trees. The levee itself is almost exclusively dominated by a black locust (*Robinia pseudoacacia*) overstory and herbaceous groundcover. Despite the separation created by the levee, a relatively robust riparian community is developing in isolated patches landward of the right-bank levee due to a successful re-vegetation effort implemented by the CTUIR in 2001. The success of this re-vegetation effort is evidence of relatively shallow groundwater and hyporheic connectivity associated with either the river, springs emerging on the valley floor, irrigation or all three. As such, this design was developed under the assumption that the overall riparian community will respond with increased density and expand to accommodate natural floodplain conditions.

R2. Problems to be Addressed

Provide information specific to the project: a) The specific problem(s) you are addressing; and b) the *root* cause(s) of the problem(s). **DO NOT describe the project here; you will do so in question #R3.** You may add narrative in addition to the table.

Specific Problem(s)	Root Cause(s) of the Problem
Channel confinement	Private levee
Limited fish habitat	Private levee
Disconnected floodplain	Private levee
Limited vegetation	Private levee

R3. Project Description

Using the table below, provide a description of the project that describes the restoration activities to occur (e.g., direct flow, remove 36" culvert, construct free spanning bridge, place 12 three log clusters between RM 44 and 52, etc.), including a description of the methodologies (e.g., juniper – burning or cutting; tree release – manual or herbicide; etc.) and the equipment planned for use. In addition, describe any Project Management functions/ activities necessary to implement the project (e.g., acquire permits or landowner approval; solicit bids, award contracts, etc.). The degree of detail should match the project complexity and technical difficulty to allow for full evaluation of technical viability. For projects involving multiple sites, be sure to identify and describe them separately, as appropriate. This is not the place to describe the benefits of the project, but rather the specific elements of the proposed project. You may add narrative in addition to the table.

The objectives of our work are to address some of the symptoms and causes of the degraded fish habitat, riparian area, and floodplain condition to enhance habitat for native salmonids within an ecological context. In other words; the proposed enhancement design focuses on improving habitat for all freshwater life history stages of native salmonids by restoring a self-maintaining geomorphic landscape. Since habitat for juvenile rearing, adult resting, and spawning are the most limiting factors, the design reflects measures that will increase both quantity and quality of habitats supporting these life history stages. Secondary benefits of these measures will span aquatic and terrestrial communities alike and reverberate throughout the watershed. Specific enhancement measures include:

- Levee setback to increase channel capacity, encourage bar development and sediment deposition, increase low-velocity channel margins, and increase riparian area width
- Add large woody debris (LWD) and boulders to increase complex pool and pocket-water habitat
- Create a side-channel, and a tributary (from springs and irrigation return flows), to enhance juvenile rearing

• Widen and diversify the riparian community

■ Promote hydraulic, geomorphic and biologic interaction between the river, spring/irrigation return, side channels, riparian areas, and floodplains

The ultimate success of these types of river enhancement projects relies largely upon establishing appropriate riparian vegetation throughout the disturbed areas. In addition to providing stability and erosion resistance along the banks and floodplain, the vegetation supports the desired habitat in terms of both cover and overall ecosystem function. Sheet 10.1 shows the planting plan for the proposed project. Sheets 10.2 and 10.3 present typical planting schemes and species-specific planting guidelines, respectively. More specific information regarding the planting plans are available in the Planting Attachment.

The instream habitat portion of the project includes the creation of roughened channels, pools, habitat rocks, pocket water, and large woody debris placement. See the design sheets for more information regarding layout and method.

Project Element	Proposed Action
Levee setback	a levee removal and levee setback to allow reconnection of the river with its floodplain, including re-establishment of meanders. The former leveed bank will be engineered to create habitat complexity while still providing stability needed to protect downstream property.
Fish habitat and cover	Instream habitat structures
Channel complexity	Side channel creation
Spring creek	Spring creek realignment
Riparian and upland habitat	Revegetation
Instream habitatComplexity	Rock purchase-install
Large woody debris	LWD installation

R4. Project Objectives

What are the proposed project objectives? Provide specific objectives based on the location, size and significance of the project and provide information on how the objectives could be evaluated. The measurements should be able to be reported to document successful implementation. See the Application Instructions for the distinction between project objectives and achievement of goals.

The proposed river design includes the following elements:

- Excavating a relatively large, single threaded, secondary channel and floodplain north of the main channel
- Selectively retaining desirable riparian vegetation along the banks and floodplains
- Removing the existing levee, riprap and debris along the north bank of the main channel
- Selectively laying back portions of the north bank of the main channel
- Extenuating two bends along the north bank of the main channel
- Sculpting/excavating in-stream pools in select locations along the main channel
- Slightly raising the existing channel elevation in between the excavated pool areas
- Installing both LWD and rock habitat structures throughout the main channel and side channel
- Creating a small channel and floodplain for the existing spring

Project Element	Specific Objectives	Measure for Evaluation
Increase and	Multiple Habitats Close Together Woody Habitat	Fish presence
enhance Instream	Structures	Fish habitat feature assessment
Habitat complexity	Primary Pool Habitat Roughened Channels,	Channel cross sections
and instream Habitat	Boulder Structures	Pebble Counts
structures	Substrate Diversification	
Levee	The levee setback will allow reconnection of the	Visual inspection
setback/floodplain	river with its floodplain along 2297 feet of river,	Cross sections
connectivity	opening up 25 acres of floodplain to a currently	
-	constricted river.	
	Side Channel/Off Channel Habitat Layback Steep	
	Existing Slopes	
	Levee Removal and/or Setback	
	Meander Creation (Side Channel, Main Channel)	Turbidity monitoring
	Reduces Erosion, Sedimentation, Property Loss	Flow and velocity monitoring
Geomorphic	Wetlands	
Stability	Self-Sustaining, Self-Maintaining Backwater	
	Habitat	
	Minimize Maintenance of levee	
Spring creek	Off channel fish habitat, hyporheic exchange	Fish presence surveys
realignment		Groundwater monitoring
	Revegetation of riparian area and reconnected	Plant surveys, plant mortality
	floodplain	inspection
Increase, Enhance	Diverse Vegetation (Cover, Temperature,	
Diversify Riparian	Recruitment, Macroinvertebrates)	
Habitat	Bio-Engineering (Native Plants. Channel,	
	Floodplain and Habitat Stability	
	Preserve, Enhance and Minimize Disturbance to	Bird, amphibian, and mammal
Upland habitat	High-Value Resource	surveys
creation	Benefits to Other Species (Water fowl, Song	
	Birds, Upland Species)	

In addition to the above mentioned objectives, the project also: Dissipates Energy Maintains Deeper Water Focuses, Directs, or Turns Flow Promotes Gravel Sorting Lowers Flood Elevation Provides Bank and Erosion Protection Avulsion (Stream Movement) Protection Fish Holding, Fish Rearing, Fish Cover and Refuge, Fish Food Source, Fish Spawning

Most notably the project creates the following quantifiable improves for steelhead and Chinook salmon productivity:

Creates .44 acres of new spawning habitat

R5. Project Design

a) Provide a list of qualifications and experience you will require for the project designer. If a project design has been completed, identify the designer and what qualifications and experience they have.

An RFQ was advertised and a scoring and evaluation matrix based on skill sets, experience, site visit interaction, and references was used by WWBWC staff and CTUIR staff to determine which of the competing engineering firms would be selected. GeoEngineers was the firm that was awarded the project. GeoEngineers have designed more than 60 instream and floodplain habitat restoration projects and have assembled a diverse team of a design engineer, hydrologist, fish biologist, wetland scientist, fluvial geomorphologist, and hydraulic engineer. They have designed two successful instream projects in the local area. One was a fish passage barrier removal and the other was a levee setback.

Jim Webster, fluvial geomorphologist, and Jed Volkman, fish biologist are both on staff at the Confederated Tribes of the Umatilla Indian Reservation and are providing extensive input on the design. Also we will receive review assistance from the district fish Biologist Oregon Department of Fish and Wildlife.

b) Describe the design criteria used or proposed and how those criteria take into consideration natural events and conditions (e.g., culvert design to 100-year flood event, wood placement to readjust with higher than bankfull flows, cultivation to retain at least 75% stubble, 4-strand fence to allow for wildlife passage, etc.).

The design is based on river channel and floodplain surveys. These were combined with extensive terrestrial and river survey work completed by the Corps in 1999-2000, analysis of upstream reference reaches, and completion of HEC-RAS modeling. A planning meeting occurred with the landowners and technical partners, prior to the engineering firm developing the designs. The design was completed in January 2010, following technical and landowner review. The project is designed to accommodate a 100 year event. Permitting and funding proposals based on designs and costing was initiated in January. As part of the permitting review, modifications to the original design have been made, with a final design to be completed in November 2010. Once permitting is complete, out of stream construction is planned to begin in winter of 2010/2011, and instream construction will occur during summer of 2011, with final planting occurring winter of 2011/2012.

Primary objectives are to increase fish habitat and fish habitat complexity. Secondary benefits anticipated by the proposed enhancements will include increased flood storage capacity, increased hyporheic connectivity, and dissipation of flood energy and channel aggradation. These goals are intended to be achieved within the hydrologic and geomorphic constraints of the river; the physical constraints of the adjacent topography; the practical constraints of the property's land use; the environmental constraints of applicable regulations permits; and the constraints of CTUIR's schedule and the availability of funds.

R6. Design Alternatives

Were alternative designs or solutions considered? (check one) X Yes No

If yes, explain why the design or approach proposed was chosen. If no, explain why alternative approaches were not explored.

Designs have been completed and reviewed. Three design alternatives were developed and reviewed. One design was selected and developed into a final design. The other two designs were dismissed. One design was not pursued as it did not create enough environmental improvements, and the other was dismissed as it created a potentially unstable river channel that could increase the possibility of flooding impacts downstream.

GeoEngineers and the CTUIR collaboratively developed three design alternatives that targeted fish habitat objectives. These alternatives, which are briefly discussed below, progressively increased in complexity, site disturbance, habitat benefits and cost.

■ Alternative 1 involved relatively minor enhancements in and along the existing channel, laying back the banks of the main channel and creating a small channel and floodplain for the existing spring. In-stream benefits would have largely been realized passively through the enhancements rather than through extensive in-stream work.

■ Alternative 2 involved the creation of a relatively large, single threaded, secondary channel north of the main channel; laying back the banks of the main channel; excavating in-stream pools; excavating a wider floodplain along the main channel and secondary channel, extenuating two bends in the main channel and creating a small channel and floodplain for the existing spring

■ Alternative 3 involved the creation of several relatively large, side channels north of the main channel; laying back the banks of the main channel; excavating in-stream pools; excavating a wider floodplain along the main channel and side channels, extenuating two bends in the main channel and creating a small channel and floodplain for the existing spring.

A variation of Alternative 2, which reduced the size of the proposed secondary channel, was ultimately selected by the CTUIR because it resulted in a suitable balance between the overall project costs and benefits. It is the design of this alternative that is described in this design package.

As part of the permitting process, options to minimize impacts to aquatic species during construction have been discussed among ODFW, CTUIR, USFWS, NOAA Fisheries staff and the GeoEngineers design team. The river will be rerouted around the instream work area during the latter part of the instream work window (August and September) to minimize impacts to fish species. This is typically the lowest flow time of year. A fish salvage will be conducted to remove fish from the reach prior to dewatering.

R7. Proposed Project Schedule

Use the table below to show the anticipated schedule for the project. Add or change the list of project elements to fit your project. See the Application Instructions for clarification and an example.

Project Elements	Start Date	End Date	Description
Permit Applications	Jan 2010	Dec2010	Has already been initiated with site visits
Materials Acquisition	May2011	Dec2011	
Bid Solicitation	Jun 2011	Jun 2011	
Contracting	July 2011	Jul 2011	
Construction	Aug 2011	Sep2011	
Project Inspection	Sep 2011	Dec2011	
Post Project Implementation Review	Jun 2012	Jun 2013	
Project Maintenance	Apr 2012	Ongoing	CTUIR Fish Habitat Program, BPA O&M \$
Add rows as needed	•		

See attached Sheet 11.2 for more detailed construction sequencing.

R8. Salmon/Steelhead Populations Targeted and Expected Benefits to Salmon/Steelhead

The information provided will be used by OWEB to better meet federal and state reporting requirements. Completion of this section is required but will not be used to evaluate this application for funding.

This project is NOT specifically designed to benefit salmon or steelhead.

▶ If you check this box, STOP here and GO TO Question R9.

Targeted Salmon/Steelhead Populations: Select one or more of the salmon ESUs (Evolutionary Significant Unit) or steelhead DPSs (Distinct Population Segment) that the project will address/benefit. For species where the ESU/DPS name is not known or determined, use the species name with unidentified ESU (e.g., Chinook salmon – unidentified ESU). Additional information on the designation and location of the salmon/steelhead populations can be found at http://www.nwr.noaa.gov/ESA-Salmon-Listings/Salmon-Populations/Maps/Index.cfm.

Chinook Salmon (Oncorhynchus tshawytscha)	Coho Salmon (O. kisutch)
Deschutes River summer/fall-run ESU	Lower Columbia River ESU
Lower Columbia River ESU	Oregon Coast ESU
X Mid-Columbia River spring-run ESU	Southern Oregon/Northern California ESU
Oregon Coast ESU	unidentified ESU
Snake River Fall-run ESU	Steelhead (O. mykiss)
Snake River Spring/Summer-run ESU	Klamath Mountains Province DPS
Southern Oregon and Northern California Coastal ESU	Lower Columbia River DPS
Upper Klamath-Trinity Rivers ESU	X Middle Columbia River DPS
Upper Willamette River ESU	Oregon Coast DPS
unidentified ESU	Snake River Basin DPS
Chum Salmon (O. keta)	Washington Coast DPS (SW Washington)
Columbia River ESU	Upper Willamette River DPS
Pacific Coast ESU	Steelhead/Trout unidentified DPS
unidentified ESU	

<u>Expected Benefits</u>: Write a brief description of the goals and purpose of the project and how it is expected to benefit salmon/steelhead or salmon/steelhead habitat. See Application Instructions for helpful examples.

The overall vision for this project is to enhance habitat for native fish and wildlife, particularly ESAlisted steelhead (*Oncorhynchus mykiss*), bull trout (*Salvelinus confluentus*), and reintroduced spring-run Chinook (*O. tshawytscha*). To achieve this vision, the project design focuses on addressing the limiting habitat factors of the project reach and, to the extent possible, this general reach of the Walla Walla River. Specifically, the proposed design is intended to decrease flow velocity, diversify in-stream structure, add low-velocity refugia, enhance spawning habitat and increase habitat complexity.

R9. Project Relationship to Regional Priorities

If the project specifically implements a plan or larger conservation effort, identify the effort and the specific role of this project. Explain whether the project implements a regional plan (e.g., ESA Recovery Plan, Coastal Coho Assessment, NWPCC Subbasin Plan, Groundwater Management Area). Specifically identify the relationship between the proposed project and the OWEB Basin Priorities. Priorities can be found on the OWEB website at: www.oregon.gov/OWEB/restoration_priorities.shtml. (See the Application Instructions for helpful links to various regional plans.)

This type of project to dechannelize the river and create fish habitat complexity is listed as a priority need for the Walla Walla River in multiple plans:

"The Walla Walla Basin Subbasin Plan 2004, (BPA)".

"The Mid Columbia Steelhead Recovery Plan, 2009 (NOAA/ODFW)".

"The Oregon Conservation Strategy 2006, ODFW

"Watershed Assessment and Action Plan; Upper Walla Walla River Subbasin 2003 (WWBWC)",

"Bull Trout Recovery Plan Draft 2002, (USFWS)",

"Walla Walla River Floodplain Restoration Report" (USACE-2000)

This project also implements riparian shading and floodplain reconnection actions recommended in the "Walla Walla River Temperature TMDL, 2005" (ODEQ).

Projects that create habitat complexity are second in priority only to projects that enhance and/or maintain fish passage and habitat connectivity and have been identified by NOAA Fisheries and the US Fish and Wildlife Service on several occasions as critical to efforts to restore listed steelhead and bull trout.

R10. Project Relationship to Watershed Processes and Functions

The restoration and protection of natural watershed process is the foundation of achieving watershed health. Since natural watershed processes have been eliminated, altered or reduced in many areas, habitat restoration activities are the primary method for reintroducing the necessary functions to watersheds that have been altered due to past management practices and/or disturbance events. Restoration activities are intended to address the watershed functions necessary to support natural processes that are indicative of healthy watersheds. This includes, but is not limited to improving water quality, water quantity, habitat complexity, flood plain interaction, vegetation structure, and species diversity.

OWEB wants to be able to track how restoration projects are addressing watershed process and function. Please check all the boxes below that apply to your restoration project. You may add narrative in addition to checking the boxes.

	Project Element	Narrative
X	Stream complexity	The site is currently dominated by a long riffle with minimal pocket water
X	Riparian vegetation structure	Removing the levee will allow riparian plantings and natural regeneration
X	Species diversity	The project will increase aquatic and vegetative diversity
X	Vegetative ground cover	More of the floodplain will be revegetated
_X	Floodplain connectivity	Levee removal
	Species migration patterns	
X	Sediment transport	Spawning gravels will now be able to develop rather than washout with current velocities
	Nutrient cycling	
X	Water quality	Better shading
	Water quantity	
	Water storage	
X	Hydrologic cycle	Increases opportunity for floodplain saturation and hyporeic exchange
X	Other (please describe)	Dechannelization of a section of the river

R11. Other Related Conservation Actions

a) Explain how the project complements other efforts under way or completed in the watershed. Identify other restoration, technical assistance, monitoring, assessment or education projects, conservation actions and ecological protection efforts in the watershed and explain how this project relates to those actions.

This project complements multiple flow restoration projects, fish passage projects, and fish habitat projects that have occurred or are occurring on the Walla Walla River upstream and downstream from this site.

b) If the project is a continuation of previously completed activities, describe the results of the previous project(s) and identify what you have learned from the implementation of similar project(s).

This project implements an OWEB Technical Assistance grant that funded the design with significant match funding from BPA via the CTUIR Fish Habitat Program.

R12. Project Inspection

Identify who will inspect and sign off on the completed project.

Name of Person & Agency/Organization	Telephone Number	Email Address	Project Element Inspected
Jason Scott, GeoEngineers	509-363-3125	jscott@geoengineers.com	Construction elements
Jed Volkman CTUIR	509-524-5224	jedvolkman@ctuir.com	Planting

R13. Educational/Public Awareness Opportunities

Explain <u>whether and how</u> you will raise public awareness about the project (e.g., install a project partner or interpretive sign, write an article for the local paper, lead a site tour for local citizens). See the Application Instructions for clarification of eligible education and outreach costs.

Site visits and presentations will be made available for the interested public, elected officials, and agency personnel.

"This project has high public awareness due to our U-pick farm operation, and we would welcome interpretive signs. We already are asked by numerous people what the lower half of our property is all about. We specifically point out in our farm advertising that we are nature friendly and note the conservation easement and numerous people comment on this when visiting. People visiting our property have expressed interests in doing conservation on their own properties, and we have referred people to Jed [CTUIR Habitat Program] before. Ideally, we would like eventually to have some walking trails through the area which our visitors could enjoy. We argue over the relative merits of letting hordes of people tramp through and scare out all the wildlife however, so...." Clark Lampson

R14. Project Maintenance and Reporting

Use the table below to document how the project will be maintained over time. State who will maintain the project. Identify their affiliation and provide contact information. In addition, please indicate who will conduct Post-Implementation. Status Reporting following project completion.

Name of Person & Agency/Organization and Addresses	Telephone Number Email Address	What will be done and for how long?
Brian Wolcott WWBWC	541-938-2170	Project stability/ plant survival 10 years
Jed Volkman CTUIR	509-524-5224	Project stability/ plant survival 10 years

R15. Budget Development

There are a number of assumptions used to develop any budget. This does not mean you must provide a line by line description of costs. Use this response to provide a clear understanding of what the budget estimate was based on.

a) Explain how costs were determined for the budget elements. Describe if contractor conversations, past projects or other cost figures were used for each major element of the budget. This is particularly important for lump sum elements in the budget. For project management costs describe the time and activities that would be involved.

Costs were developed based on going rates for contracted services and materials. The budget was determined from an engineered evaluation of the acreages to be planted, types of vegetation, cubic yards to be excavated, and typical costs for contracted services and materials based on other projects completed in the area.

b) If there are any unusual cost factors, explain them. For example, if the fencing costs are unusually high because of steep, rocky terrain and unroaded access, this is the place to explain the cost elements on the budget page.

Not applicable

- R16. Effectiveness Monitoring. If you plan to conduct Effectiveness Monitoring beyond post-implementation status reporting and you are requesting more than \$3,500 in OWEB funds to support these EM activities, complete the R16 Effectiveness Monitoring Application Insert, print it out and add after Question R15. See the R16 Effectiveness Monitoring Insert Instructions for clarification.
- R17. Riparian Planting. If you are proposing a Riparian Planting Project and you are requesting more than \$3,500 in OWEB funds for implementation and plant establishment, you <u>must</u> complete the R17 Riparian Planting Application Insert, print it out and add after Question R15 or R16 as appropriate. If you are asking for \$3,500 or less, you may answer the questions if you would like the reviewers to have additional information on the planting component of the project. See the R17 Riparian Planting Application Insert Instructions for clarification.

QUESTION R17 RIPARIAN PLANTING INSERT

Section I

RIPARIAN PLANTING INFORMATION

These essay questions and their answers are designed to guide you and reviewers through a logical process from understanding and identifying the problem to measuring for success. Refer to the Instructions for clarification and helpful examples.

You may use the application form to respond to the questions, using additional sheets of paper as necessary **OR** answer the questions on separate pages. Be sure to include the question numbers and text of the questions before you begin typing your answers to assist the reviewers in evaluating your application. Do not use color highlights for text emphasis or in tables as the highlight turns black when the application is scanned.

Use $8\frac{1}{2}$ x 11" paper. A double-sided application and materials are encouraged except for oversize maps and designs or multiple sets for reviewers. All materials should be **single-spaced** wherever possible, **unstapled** and **unbound**, except for sets of maps/photos/designs (see page 3 of the Riparian Planting Insert Instructions for assembling multiples for reviewers). Use a 12-pt type size to answer the questions and a 10-pt type size for the tables. Use bullets where appropriate. Use **bold face** and *italics* for emphasis only. If the project involves multiple sites, be specific for each. If the project involves multiple sites, be specific for each.

RP1 Clearly describe the condition of the site(s) to be planted and any site preparation activities that will be completed prior to planting. Why did you choose this approach to site preparation? Are there special conditions involved at this site? Discuss any predation or competition issues.

The site was formerly an orchard up to the landward side of a private levee along the river edge. The former floodplain has been partially restored over the last decade with grass and tree plantings. The project reach riparian area is largely restricted to the immediate bank area due to natural confinement by a vertical rock cliff on the south (left) bank and artificial confinement by a levee on the north (right) bank. In general, the riparian vegetation on bars and the immediate banks, inside the levee, is dominated by a black cottonwood (*Populus trichocarpa*) overstory. The understory is largely comprised of Himalayan blackberry (*Rubus armeniacus*) and other woody shrubs, likely emerging from rhizomes of overstory trees. The levee itself is almost exclusively dominated by a black locust (*Robinia pseudoacacia*) overstory and herbaceous groundcover. Despite the separation created by the levee, a relatively robust riparian community is developing landward of the right-bank levee due to a successful re-vegetation effort implemented by the CTUIR in 2001. The success of this re-vegetation effort is evidence of relatively shallow groundwater and hyporheic connectivity associated with either the river, irrigation or both. As such, this design was developed under the assumption that the overall riparian community will respond with increased density and expand to accommodate natural floodplain conditions.

- **RP2** Provide detailed information regarding the plants, planting locations, and planting techniques at the site(s). (A diagram would be very helpful for reviewers and may result in a more favorable evaluation.) Explain why you are taking this approach at the site and include information on:
 - Number and species to be planted;
 - Plants per acre;
 - Location of plantings;
 - Size (age class) of planting stock;
 - Type of stock (Rooted, bare root, or cuttings);

- Month(s) of plantings; and
- Protective devices/strategies to be used or vegetation competition and or predation.

For planting mosaics and delineation of zones please refer to the attached Sheets 10.1, 10.2, 10.3 from the River Enhancement Design, completed by GeoEngineers, Inc.

The following list describes planting methods and species to be planted. The size of planting stock can be determined by cutting length or pot size. Planting will occur from November through April, except for the lie cuttings that will be planted directly into the river bank and spring creek bank as large woody debris root wads are being installed.

Grass Seed Mix

1. Add topsoil mix and/or organic mulch to disturbed areas if necessary.

2. Seed all disturbed areas.

3. Cover with straw or mulch if necessary to minimize erosion.

Sandberg's bluegrass, bluebunch wheatgrass, blue wildrye, Idaho fescue and mountain brome Seeding rate: 7 lbs per acre, 14.08 acres, 98.56 lbs total

Upland Nursery Stock

1. Add topsoil mix and/or organic mulch at base of plants if necessary.

Ponderosa pine, snowberry, blue elderberry, woods rose, serviceberry, golden currant and chokecherry. Space individual plants 12 ft on center (oc) for tree species and 6 ft oc for shrub species

Riparian Nursery Stock

1. Add topsoil mix and/or organic mulch at base of plants if necessary.

2. Plant in proper hydrologic regime (see sheet 10.2)

Black cottonwood, woods rose, red osier dogwood, golden currant, coyote willow, Drummond's willow, snowberry, blue elderberry and chokecherry.

Space individual plants 12ft on center (oc) for tree species and 6 ft oc for shrub species

Nursery stock total: 2047 units, 14.55 acres Transition, riparian, and bank zones).

Live Cuttings

1. Plant live cuttings into permanent moisture regime.

Plant immediately if possible. When possible, materials will be salvaged from site prior to construction)
 Plant top end up.

Black cottonwood, coyote willow, Drummond's willow, red alder, and red osier dogwood.

Space individual trees 6-8 ft oc and shrubs 1-3 ft oc with highest densities in streambank protection zones, at LWD structures and along outside bends.

Live cuttings total 1458 units, 16.02 acres.

Tree and Shrub Planting Specifications by Species Common Name, Scientific Name, Recommended Size, Recommended Spacing

Trees

Black cottonwood	Populus trichocarpa	4 ft-6 ft cuttings	6-8 ft on center
Ponderosa pine	Pinus ponderosa	2 gallon pot	12 ft oc

Shrubs

Woods rose	Rosa woodsii	l gallon	6 ft oc
Golden currant	Ribes aureum	l gallon	6 ft oc
Red osier dogwood	Cornus serices	4 ft-6 ft cuttings	1-3 ft oc
Drummond's willow	Salix drummondiana	4 ft-6 ft cuttings	1-3 ft oc
Coyote willow	Salix exigva	4 ft-6 ft cuttings	1-3 ft oc
Snowberry	Symphoricarpos albus	s l gallon	6 ft oc
Blue elderberry	Sambucus nigra	1 gallon	6 ft oc
Serviceberry	Amelanchier alnifolia	1 gallon	6 ft oc
Chokecherry	Prunus virginiana	1 gallon	6 ft oc
Grass Seed Mix			
Common Name	Scientific Name	Application Method	Pounds Per Acre
Mountain brome	Bromus carniatus	Broadcast	1.2
Sandberg's Bluegrass	Poa secunda	Broadcast	1.6
Blue Wildrye	Elymus glaucus	Broadcast	1.2
Bluebunch wheatgrass	s Pseudoroegneria spic	ata Broadcast	2.4
Idaho fescue	Festuca idahoensis	Broadcast	1.6

As shown on attachment 10.1, the project area has been divided into a bank zone, a replant zone, and supplemental planting zone. Most of the riparian area is included in the bank zone and replant zone. The bank zone will be replanted with bank zone vegetation from the low water level to five feet beyond the top of bank per the typical section on Sheet 10.2. The replant zone will be planted with either riparian vegetation or transitional vegetation as designated by elevation per the typical section on sheet 10.2. The supplemental planting zone will be planted with either riparian or transitional plantings around existing native vegetation as previously established by the CTUIR habitat program per the typical section on sheet 10.2. Sheet 10.3 shows which of the above mentioned seed mixes and plant stock will be planted to which zone or zones. Native vegetation previously established by the CTUIR will be maintained to the best extent possible. All existing trees greater than eight inch diameter and root wads to be removed will be incorporated into the proposed woody habitat structures in addition to those trees specified in the attached drawings.

a. Refer to Sheet 10.1 for typical planting zone designations and Sheet 10.2 for typical plant groupings.

b. Planting Applications and Specifications are based on USDA-NRCS technical notes and literature.

c. Wetland seed mix shall be broadcast 1-2 years after the planting of live cuttings to allow sediment to build up on the cobble bottom. If wetland seed mix is planted immediately after construction, it shall be covered with straw and staked with live willow stakes.

d. Transplanted materials and live cuttings should be installed immediately upon completion of LWD placement.

e. All existing trees larger than 8" in diameter and root wads to be removed shall be incorporated into the proposed woody habitat structures in addition to those trees specified in these drawings.

RP3 Provide a *general* plant establishment plan that covers 3-5 years post implementation. Include a schedule with information on how frequently the site(s) will be visited, by whom (landowners or contractors), what type of invasive species and animal damage control will be implemented, what type of weather protection measures will be implemented, and what irrigation plans will be considered. If no plant establishment activity is planned, explain why.

CTUIR Fish Habitat Program staff will purchase and/or collect the planting materials, store them appropriately until installation, implement the planting by hand and with machinery. Mats will be installed to reduce weed encroachment and assist with moisture retention. Stem protection cylinders and or wire netting will be placed around stems to avoid deer browsing and beaver impacts. Crews will visit the site weekly throughout the

growing seeding, monitoring and maintaining the site as necessary to control weeds by hand pulling and if needed spraying individual noxious specimens, check on and replace if necessary stem protection cylinders that reduce deer browsing impacts, water trees, shrubs, and grasses from their watering truck, and if necessary replant any areas that are not successful. The only weather related concerns are the long dry season which will mitigated with wekkly watering fromn the CTUIR habitat water truck. The success of the prior revegetation work completed by CTUIR staff at portions of the project site demonstrates the CTUIR's skills and dedication to a successful project.

RP4 What is your measure of success for the plantings? If, in the course of the 3-5 years following planting, the success rate falls below your standard, what is your plan?

A success rate of 80% plant survival is acceptable within 5 years of planting. Natural reseeding over time will compensate for up to 20% mortality should that occur. If the success rate falls below this standard, the CTUIR habitat program will work to secure the funding necessary for plant materials and staff time for planting and maintenance.

RP5 Provide the name and contact information for the people who will be working on the various planting phases, if known.

Project Element	Name of Person & Agency/Organization	Telephone Number and Email Address		
	Jason Scott, GeoEngineers, Inc.	509-363-3125		
Site Prep		jscott@geoengineers.com		
	Jed Volkman, CTUIR	509-524-5224,		
Planting		jedvolkman@ctuir.com		
	Jed Volkman, CTUIR	509-524-5224,		
Plant Establishment Work		jedvolkman@ctuir.com		
	Jed Volkman, CTUIR	509-524-5224,		
Project Management		jedvolkman@ctuir.com		

Section IV WATERSHED RESTORATION BUDGET

IMPORTANT: Read the application instructions. Attach additional lines, if necessary.

CAPITAL BUDGET *Totals automatically round to the nearest dollar

Itemite projected costs under each of the following categories: Unit Number Cost In. Kind Match Cash Match Funds Total Cests PRE-IMPLEMENTATION. Must occur after for processing the Land Use form. OWEB funds will be disbursed only upon receipt of all required permits and licenses. 0 0 PRE-IMPLEMENTATION. Must occur after the OWEB grant agreement has been fully executed, unless it is a city or county charge for processing the Land Use form. OWEB funds will be disbursed only upon receipt of all required permits and licenses. 0 PROJECT MANAGEMENT. Includes actual in-house staff or contractors who coordinate project implementation. Line items should identify who will be responsible for project management and their affiliation. 0 0 WWBWC Project Management 10 days 250 2,500.00 2,500.00 2,500 CTUIR Habita Program Manager 12 days 12 days 800 9,600.00 9,600.00 SUBTOTAL (2) 3,600 9,600.00 0.00 0.00 CONTRACTED SERVICES. Labor, supplies, and materials to be provided by non-staff for project implementation. 0 0 Temporary Steam Diversion 1 LS 10000 100000 10,000 Contractor Staking 5 Days 101.8.8 5079 5,000 Staty Staty Stopping and m		Ā	B	С	D	<u> </u>	F
the following categories. Number Cost Match Funds (add columns, (add columns, (add columns, (add)))) PRE-IMPLEMENTATION. Must occur qirer the OWEB grant agreement has been fully executed, unless it is a city or county charge for processing the Land Use form. OWEB finds will be disbursed only upon receipt of all required permits and licenses. 0 For processing the Land Use form. WEB finds will be disbursed only upon receipt of all required permits and licenses. 0 SUBTOTAL (1) 0 0 0 0 WBWC Crojcet Management. 10 days 250 2,500.00 2,500.00 CTUR Habitat Program Manager 12 days 300 3,600.00 9,600.00 9,600 WBWC Crojcet Management. 10 days 250 2,500.00 2,500.00 2,500.00 CTUR Habitat Program Manager 12 days 300 3,600.00 9,600.00 9,600 CTUR Habitat Program Manager 12 days 10 days 250 2,500.00 2,500.00 SUBTOTAL (2) 3,600 9,600.00 0 0 0 Cost Management 10 days 12 days 1000	Itemize projected costs under each of	Unit	Unit	In-Kind	Cash Match	OWEB	Total Costs
(e.g., # of hours) (e.g., # ourly rate) (e.g., # ourly rate) (e.g., # ourly C, D, E) PRE-IMPLEMENTATION. Must occur after for processing the Land Use form. OWEB frant agreement has been fully executed, unless it is a city or councy charge for processing the Land Use form. OWEB frant agreement has been fully executed, unless it is a city or councy charge for processing the Land Use form. OWEB frant agreement has been fully executed, unless it is a city or councy charge for processing the Land Use form. OWEB funds will be disbursed only upon receipt of all required permits and licenses. 0 PROJECT MANAGEMENT. Includes actual in-house staff or contractors who coordinate project implementation. Line items should identify who will be responsible for project management and their affiliation. 0 0 0 WWBVC Project Management identify who will be responsible for project management and their affiliation. 2,500.00 2,500.00 3,600.00 GeoEngineers Construction Oversight I2 days 12 days 800 9,600.00 9,600 IN-HOUSE PERSONNEL, Includes andry actual in-house staff costs for project implementation. Temporary Stream Diversion 0 0 0 CONTRACTED SERVICES. Labor, supplies, and materials to be provided by non-staff (or project implementation. Temporary Stream Diversion 1 LS 10000 10000 10,000 Selectively Ly aback Steps Diposit, fifte, rendor gate States Diposit, fifte, rendor gate States Diposit, fifte, rendor gate St	the following categories.	Number	Cost	Match	Funds	Funds	
hours) rate) C, D, E) PRE-IMPLEMENTATION. Must occur <i>after</i> the OWEB grant agreement has been fully executed, unless it is a city or county charge for processing the Land Use form. OWEB funds will be disbursed only upon receipt of all required permits and licenses. 0 SUBTOTAL (1) 0 0 0 WBWC Project Management 10 days 250 2,500.00 2,500.00 CTUIR Habitat Program Manager 12 days 300 3,600.00 9,600.00 9,600 WBWC Project Management 10 days 800 9,600.00 2,500.00 2,500.00 2,500.00 3,600 GeoEngineers Construction Oversight 12 days 800 9,600.00 9,600 0		(e.g., # of	(e.g., hourly				(add columns
PRE-IMPLEMENTATION. Must occur after the OWEB grant agreement has been fully executed, unless it is a city or county charge for processing the Land Use form. OWEB funds will be disbursed only upon receipt of all required permits and licenses. 0 SUBTOTAL (1) 0 0 PROJECT MANAGEMENT. Includes actual in-house staff or contractors who coordinate project implementation. Line items should identify who will be responsible for project management and their affiliation. 2,500,00 2,500,00 PROJECT MANAGEMENT. Includes actual in-house staff or contractors who coordinate project implementation. Line items should identify who will be responsible for project management and their affiliation. 2,500,00 2,500,00 3,600 CTUIR Habitat Program Manager 12 days 300 3,600,00 9,600,00 9,600,00 SUBTOTAL (2) 3,600 9,600,00 9,600,00 15,700 IN-HOUSE PERSONNEL. Includes anly actual in-house staff costs for project implementation. 0 0 0 SUBTOTAL (3) 0 0 0 0 0 0 Construction Staking 5 Days 1015.88 5079 5,079 5,079 Selective Floodplain Grading 5 A Acres 14000 19,600 19,600 19,600 Construction Staking 5 Days 1015.88		hours)	rate)				C, D, E)
for processing the Land Use form. OWEB funds will be disbursed only upon receipt of all required permits and licenses. 0 SUBTOTAL (1) 0 0 PROJECT MANAGEMENT. Includes actual in-house staff or contractors who coordinate project implementation. Line items should identify who will be responsible for project management and their affiliation. 2,500.00 2,500.00 VWBWC Project Management 10 days 250 2,500.00 2,500.00 CTUR Habitat Program Manager 11 2 days 300 3,600.00 9,600.00 9,600.00 GeoEngineers Construction Oversight 12 days 300 3,600 0.00 0.00 SUBTOTAL (2) 3,600 9,600.00 9,600.00 9,600.00 0.00 SUBTOTAL (3) 0 0 0 0 0 CONTRACTED SERVICES. Labor, supplies, and materials to be provided by non-staff for project implementation. 10.00 10,000 10,000 Construction Staking SDays 1015.88 5079 5,079 5,079 Steletively Lay Back Steep Slopes 14 Acres 14000 75600 76,600 76,600 Clearing, grubbing, stockpile 26 Acres 3700.13 244480 24,480 74,48	PRE-IMPLEMENTATION. Must oc	cur after the C	WEB grant agre	ement has been fi	ully executed, unle	ss it is a city or c	ounty charge
SUBTOTAL (1) 0 0 PROJECT MANACEMENT. Includes actual in-house staff or contractors: who coordinate project implementation. Line items should identify who will be responsible for project management and their affiliation. 0 0 0 0 WWBVC Project Management 10 days 250 2,500.00 2,500.00 2,500.00 CTUIR Habita Program Managem 12 days 300 3,600.00 9,600.00 9,600 GeoEngineers Construction Oversight 12 days 800 9,600 2,500 15,700 IN-HOUSE PERSONNEL. Includes only actual in-house staff costs for project implementation. 0 0 0 Temporary Brane Diversion 11.1.5 100000 10,000 0 0 0 CONTRACTED SERVICES. Labor, supplies, and materials to be provided by non-staff for project implementation. 10,000 10,000 10,000 Construction Staking 5 Days 1015.88 5079 5,079 5,079 Selective Flockplin Grading 5 A Acres 14000 19,600 10,600 10,600 Croating grade stockpile 1.4 Acres 14000 75600 75,600 75,600 75,600 75,600 122,500 4,480 </td <td>for processing the Land Use form. OW</td> <td>EB funds will</td> <td>be disbursed only</td> <td>upon receipt of</td> <td>all required permit</td> <td>s and licenses.</td> <td></td>	for processing the Land Use form. OW	EB funds will	be disbursed only	upon receipt of	all required permit	s and licenses.	
Image: state in the second interactors who coordinate project implementation. Line items should dentify who will be responsible for project management and their affiliation. 0 0 0 WBWC Project Management 10 days 250 2,500.00 2,500.00 2,500.00 2,500.00 3,600 GeoEngineers Construction Oversight 12 days 300 9,600.00 9,600.00 9,600 3,600 IN-HOUSE PERSONNEL. Includes only actual in-house staff costs for project implementation. 0 </td <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>0</td>							0
SUBTOTAL (1) 0 0 0 PROJECT MANAGEMENT. Includes actual in-house staff or contractors who coordinate project implementation. Line items should identify who will be responsible for project management and their affiliation. 0 0 0 0 WBWC Project Management in 10 days 250 2,500.00 2,500.00 2,500.00 2,500.00 2,500.00 2,500.00 3,600 GeoEngineers Construction Oversight 12 days 800 9,600.00 9,600.00 9,600.00 9,600 IN-HOUSE PERSONNEL. Includes only actual in-house staff costs for project implementation. 0 0 0 0 Important Cite Services. Labor, supplies, and materials to be provided by non-staff for project implementation. 0 </td <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>0</td>							0
SUBTOTAL (1) 0 0 0 0 0 PROJECT MANAGEMENT. Includes actual in-house staff or contractors who coordinate project implementation. Line items should identify the will be responsible for project management and their affiliation. 10 days 2,500.00 <							0
PROJECT MANAGEMENT. Includes actual in-house staff or contractors who coordinate project implementation. Line items should identify who will be responsible for project management and their affiliation. WBWC Project Management 10 days 250 2,500.01 5,600.00 3,600.00 9,600.00 9,600.00 9,600.00 2,500.01 5,700.01 15,700.01 2,500.01 5,700.01 15,700.01 15,700.01 0,00 0.00			UBTOTAL (1)	0	0	0	0
identify who will be responsible for project management and their affiliation. WWBWC Project Management 10 days 250 2,500 2,500 2,500 2,500 2,500 2,500 12 days 800 9,600 0 0,500 2,500 15,700 N-HOUSE PERSONNEL. Includes only actual in-house staff costs for project implementation. N-HOUSE PERSONNEL. Includes only actual in-house staff costs for project implementation. N-HOUSE PERSONNEL. Includes only actual in-house staff costs for project implementation. N-HOUSE PERSONNEL. Includes only actual in-house staff costs for project implementation. N-HOUSE PERSONNEL. Includes only actual in-house staff costs for project implementation. N-HOUSE PERSONNEL. Includes only actual in-house staff costs for project implementation. N-HOUSE PERSONNEL. Includes only actual in-house staff costs for project implementation. N-HOUSE PERSONNEL. Includes only actual in-house staff costs for project implementation. N-HOUSE PERSONNEL. Includes only actual in-house staff costs for project implementation. N-HOUSE PERSONNEL. Includes only actual in-house staff costs for project implementation. N-HOUSE PERSONNEL. Includes only actual in-house staff costs for project implementation. N-HOUSE PERSONNEL. Includes only actual in-house staff costs for project implementation. N-HOUSE PERSONNEL. Includes only actual in-house staff costs for project implementation. N-HOUSE PERSONNEL. Includes only actual in-house staff costs for project implementation. Temporary Stream Diversion 1 LS 10000 10000 10,0	PROJECT MANAGEMENT. Include	es actual in-ha	use staff or contr	actors who coor	dinate project impl	ementation. Lin	e items should
WWBWC Project Management 10 days 250 2,500.00 2,500.00 2,500.00 3,600 3,600 3,600 3,600 3,600 3,600 3,600 3,600 3,600 3,600 3,600 3,600 3,600 3,600 3,600 3,600 9,600.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00 <	identify who will be responsible for proj	ect manageme	ent and their affili	ation.			
CTUIR Habitat Program Manager 12 days 300 3,600 3,600 3,600 3,600 3,600 3,600 3,600 3,600 3,600 3,600 3,600 3,600 9,600 3,600 9,600 3,600 9,600 3,600 9,600 2,500 15,700 IN-HOUSE PERSONNEL. Includes only actual in-house staff costs for project implementation. 0	WWBWC Project Management	10 days	250			2,500.00	2,500
GeoEngineers Construction Oversight 12 days 800 9,600 15,700 IN-HOUSE PERSONNEL. Includes only actual in-house staff costs for project implementation. 0 <t< td=""><td>CTUIR Habitat Program Manager</td><td>12 days</td><td>300</td><td>3,600.00</td><td></td><td></td><td>3,600</td></t<>	CTUIR Habitat Program Manager	12 days	300	3,600.00			3,600
SUBTOTAL (2) 3,600 9,600 2,500 15,700 IN-HOUSE PERSONNEL. Includes only actual in-house staff costs for project implementation. 0	GeoEngineers Construction Oversight	12 days	800		9,600.00		9,600
SUBTOTAL (2) 3,600 9,600 2,500 15,700 IN-HOUSE PERSONNEL. Includes only actual in-house staff costs for project implementation. 0 0 0 0 IN-HOUSE PERSONNEL. Includes only actual in-house staff costs for project implementation. 0					,		,
IN-HOUSE PERSONNEL. Includes only actual in-house staff costs for project implementation. 0 SUBTOTAL (3) 0 0 CONTRACTED SERVICES. Labor, supplies, and materials to be provided by non-staff for project implementation. 0 Temporary Stream Diversion 1 LS 10000 100000 Construction Staking 5 Days 1015.88 5079 5,079 Selective Joodplain Grading 5.4 Acres 14000 75600 76,000 Clearing, grubbing, stockpile trees & for any grade stockpile 6.6 Acres 3709.13 24480 24,480 Ploodplain Excavation, haul, stockpile 24500 CY 5 122,500 122,500 122,500 Rine and grade stockpile 24500 CY 5 122,500 2120,000 21,000 Boulder acquisition, haul & placement in stream. 2 to 6 feet in diameter 7 Days 3000 21000 21,000 Sys anchored 225 Pieces 750 168750 168,750 168,750 Best Management Practices, including in LAsume 23% anchored. 7 Days 8000 6,000.00 6,000 Pumping dirty water from in-water work overboard into settling basin. 7 Days 8000 5,600.00		S	UBTOTAL (2)	3,600	9,600	2,500	15,700
Image: Subscription of the set o	IN-HOUSE PERSONNEL. Includes a	nlv actual in-	house staff costs	for project imple	mentation.		
SUBTOTAL (3) 0 0 CONTRACTED SERVICES. Labor, supplies, and materials to be provided by non-staff for project implementation. 0		1					0
SUBTOTAL (3) 0 <t< td=""><td></td><td></td><td></td><td></td><td></td><td></td><td>0</td></t<>							0
SUBTOTAL (3) 0 <t< td=""><td></td><td></td><td></td><td></td><td></td><td></td><td>0</td></t<>							0
CONTRACTED SERVICES. Labor, supplies, and materials to be provided by non-staff for project implementation. Temporary Stream Diversion 1 LS 10000 10000 10,000 Construction Staking 5 Days 1015.88 5079 5,079 Selectively Lay Back Steep Slopes 1.4 Acres 14000 19600 19,600 Selective Floodplain Grading 5.4 Acres 14000 75,600 75,600 Clearing, grubbing, stockpile trees & 6.6 Acres 3709.13 24480 24,480 roots		SI	IBTOTAL (3)	0	0	0	0
Temporary Stream Diversion 1 LS 10000 10000 10,000 Construction Staking 5 Days 1015.88 5079 5,079 Selectively Lay Back Steep Slopes 1.4 Acres 14000 19600 19,600 Selectively Lay Back Steep Slopes 1.4 Acres 14000 75,600 75,600 Selectively Lay Back Steep Slopes 6.6 Acres 3709.13 24480 24,480 Cools 6.6 Acres 3709.13 24480 24,480 roots 6.6 Acres 3709.13 24480 24,480 banks 5 122,500 122,500 122,500 Fine Grade (sculpt) dry pools, riffle, sculpt dry pools, riffle, banks 2.10 Acres 4000 8400 8,400 banks 7 Days 3000 21000 21,000 Boulder acquisition, haul & placement 560 Ea 125 14,000 56,000 70,000 Install woody habitat structure. Acquire haul & install woody habitat structure. Acquire haul & install woody habitat structure. Assume 25% anchored. 25 Pieces 750 168,750 168,750 <td>CONTRACTED SERVICES Labor</td> <td>supplies and i</td> <td>materials to be pr</td> <td>ovided by non-st</td> <td>aff for project impl</td> <td>ementation</td> <td></td>	CONTRACTED SERVICES Labor	supplies and i	materials to be pr	ovided by non-st	aff for project impl	ementation	
Inspirat/Social Protocol1000010000Construction Staking5 Days1015.8850795,079Selectively Lay Back Steep Slopes1.4 Acres140001960019,600Selectively Lay Back Steep Slopes1.4 Acres140007560075,600Selective Floodplain Grading5.4 Acres140007560075,600Clearing, grubbing, stockpile trees & roots6.6 Acres3709.132448024,480Ploodplain Excavation, haul, stockpile24500 CY5122,500122,500& rough grade stockpile2.10 Acres400084008,400Boulder Grading of pools, riffles.7 Days30002100021,000Boulder acquisition, haul & placement in stream. 2 to 6 feet in diameter560 Ea12514,00056,00070,000Install woody habitat structure. Acquire twood from site, mostly small. Assume 25% anchored225 Pieces750168750168,750Management Practices, including installarion & maintenance.1 LS60006,000.006,000Pumping dirty water from in-water work overboard into settling basin.7 Days80005,600.005,600.00Wurk overboard into settling basin.7 Days80005,600.005,600.00	Temporary Stream Diversion	1 LS	10000		10000		10.000
Scheduler for a structure Support Support <thsupport< th=""> <thsupport< th=""> <thsupport<< td=""><td>Construction Staking</td><td>5 Days</td><td>1015.88</td><td></td><td>5079</td><td></td><td>5.079</td></thsupport<<></thsupport<></thsupport<>	Construction Staking	5 Days	1015.88		5079		5.079
Selective Floodplain Grading 5.4 Acres 14000 75600 75,600 Clearing, grubbing, stockpile trees & roots 6.6 Acres 3709.13 24480 24,480 Floodplain Excavation, haul, stockpile 24500 CY 5 122,500 122,500 K rough grade stockpile 24500 CY 5 122,500 122,500 Fine Grade (sculpt) dry pools, riffle, banks 2.10 Acres 4000 8400 8,400 In-Water Grading of pools, riffles. 7 Days 3000 21000 21,000 Boulder acquisition, haul & placement in stream. 2 to 6 feet in diameter 560 Ea 125 14,000 56,000 70,000 Install woody habitat structure. Acquire wood from site, mostly small. Assume 25% anchored. 225 Pieces 750 168750 168,750 Best Management Practices, including linstall woody habitat 1 LS 6000 6,000.00 6,000 Install woer board into settling basin. 7 Days 800 5,600.00 5,600	Selectively Lay Back Steen Slopes	1 4 Acres	14000		19600		19,600
Clearing, grubbing, stockpile trees & costs 6.6 Acres 3709.13 24480 24,480 Floodplain Excavation, haul, stockpile 24500 CY 5 122,500 122,500 Fine Grade (sculpt) dry pools, riffle, banks 2.10 Acres 4000 8400 8,400 In-Water Grading of pools, riffles. 7 Days 3000 21000 21,000 Boulder acquisition, haul & placement in stream. 2 to 6 feet in diameter 560 Ea 125 14,000 56,000 70,000 Install woody habitat structure. Acquire Mood from site, mostly small. Assume 25% anchored. 225 Pieces 750 168750 168,750 Best Management Practices, including installation & maintenance. 1 LS 6000 6,000.00 6,000.00 Pumping dirty water from in-water work overboard into settling basin. 7 Days 800 5,600.00 5,600.00 SUBTOTAL (4) 0 516,009 56,000 572,009	Selective Floodplain Grading	54 Acres	14000		75600		75 600
Floodplain Excavation, haul, stockpile 24500 CY 5 122,500 122,500 Floodplain Excavation, haul, stockpile 24500 CY 5 122,500 122,500 Fine Grade (sculpt) dry pools, riffle, banks 2.10 Acres 4000 8400 8,400 In-Water Grading of pools, riffles. 7 Days 3000 21000 21,000 Boulder acquisition, haul & placement in stream. 2 to 6 feet in diameter 560 Ea 125 14,000 56,000 70,000 Install woody habitat structure. Acquire wood from site, mostly small. Assume 25% anchored 100 Pieces 350 35000 35,000 Structure, Assume 25% anchored. 1 LS 6000 6,000.00 6,000.00 6,000.00 Installation & maintenance. 7 Days 800 5,600.00 5,600.00 5,600 Work overboard into settling basin. 7 Days 800 5,600.00 5,600.00 5,600	Clearing grubbing stocknile trees &	6 6 Acres	3709.13		24480		24,480
Note24500 CY5122,500122,500& rough grade stockpile2100 Acres400084008,400Fine Grade (sculpt) dry pools, riffle, banks2.10 Acres400084008,400In-Water Grading of pools, riffles.7 Days30002100021,000Boulder acquisition, haul & placement in stream. 2 to 6 feet in diameter560 Ea12514,00056,00070,000Install woody habitat structure. Acquire 25% anchored100 Pieces3503500035,00035,000Acquire, haul & install woody habitat structure. Assume 25% anchored.225 Pieces750168750168,750Best Management Practices, including installation & maintenance.1 LS60006,000.006,000Pumping dirty water from in-water work overboard into settling basin.7 Days8005,600.005,600SUBTOTAL (4)0516,00956,000572,009	roots	0.0110.05	5,05.15		21100		21,100
& rough grade stockpile Image: Stockpile	Floodplain Excavation, haul, stockpile	24500 CY	5		122.500		122,500
Construction of production production production production of production production production production production production product production product pro	& rough grade stocknile				,		,
banksIn-Water Grading of pools, riffles.7 Days30002100021,000Boulder acquisition, haul & placement in stream. 2 to 6 feet in diameter560 Ea12514,00056,00070,000Install woody habitat structure. Acquire wood from site, mostly small. Assume 25% anchored100 Pieces3503500035,000Acquire, haul & install woody habitat structure. Assume 25% anchored.225 Pieces750168750168,750Best Management Practices, including installation & maintenance.1 LS60006,000.006,000Pumping dirty water from in-water work overboard into settling basin.7 Days8005,600.005,600SUBTOTAL (4)0516,00956,000572,009	Fine Grade (sculpt) dry pools, riffle.	2.10 Acres	4000				8.400
In-Water Grading of pools, riffles.7 Days30002100021,000Boulder acquisition, haul & placement in stream. 2 to 6 feet in diameter560 Ea12514,00056,00070,000Install woody habitat structure. Acquire wood from site, mostly small. Assume 25% anchored100 Pieces3503500035,000Acquire, haul & install woody habitat structure. Assume 25% anchored.225 Pieces750168750168,750Best Management Practices, including installation & maintenance.1 LS60006,000.006,000Pumping dirty water from in-water work overboard into settling basin.7 Days8005,600.005,600SUBTOTAL (4)0516,00956,000572,009	banks				0.00		0,000
Boulder acquisition, haul & placement in stream. 2 to 6 feet in diameter 560 Ea 125 14,000 56,000 70,000 Install woody habitat structure. Acquire wood from site, mostly small. Assume 25% anchored 100 Pieces 350 35000 35,000 Acquire, haul & install woody habitat structure. Assume 25% anchored. 225 Pieces 750 168750 168,750 Best Management Practices, including installation & maintenance. 1 LS 6000 6,000.00 6,000 Pumping dirty water from in-water work overboard into settling basin. 7 Days 800 5,600.00 5,600 SUBTOTAL (4) 0 516,009 56,000 572,009	In-Water Grading of pools, riffles,	7 Davs	3000		21000		21.000
in stream. 2 to 6 feet in diameter Install woody habitat structure. Acquire wood from site, mostly small. Assume 25% anchored Acquire, haul & install woody habitat structure. Assume 25% anchored. Best Management Practices, including installation & maintenance. Pumping dirty water from in-water work overboard into settling basin. SUBTOTAL (4) 0 516,009 56,000 572,009	Boulder acquisition, haul & placement	560 Ea	125		14.000		70,000
Install woody habitat structure. Acquire wood from site, mostly small. Assume 25% anchored 100 Pieces 350 35000 35,000 Acquire, haul & install woody habitat structure. Assume 25% anchored. 225 Pieces 750 168750 168,750 Best Management Practices, including installation & maintenance. 1 LS 6000 6,000.00 6,000 Pumping dirty water from in-water work overboard into settling basin. 7 Days 800 5,600.00 5,600 SUBTOTAL (4) 0 516,009 56,000 572,009	in stream 2 to 6 feet in diameter				• • • • • •		
Install woody habitat structure. Acquire wood from site, mostly small. Assume 25% anchored100 Pieces3503500035,000Acquire, haul & install woody habitat structure. Assume 25% anchored.225 Pieces750168750168,750Best Management Practices, including installation & maintenance.1 LS60006,000.006,000Pumping dirty water from in-water work overboard into settling basin.7 Days8005,600.005,600SUBTOTAL (4)0516,00956,000572,009							
wood from site, mostly small. Assume 25% anchored 168750 168750 Acquire, haul & install woody habitat structure. Assume 25% anchored. 225 Pieces 750 168750 168,750 Best Management Practices, including installation & maintenance. 1 LS 6000 6,000.00 6,000 Pumping dirty water from in-water work overboard into settling basin. 7 Days 800 5,600.00 5,600 SUBTOTAL (4) 0 516,009 56,000 572,009	Install woody habitat structure. Acquire	100 Pieces	350		35000		35.000
25% anchored 225 Pieces 750 168750 168,750 Acquire, haul & install woody habitat structure. Assume 25% anchored. 225 Pieces 750 168750 168,750 Best Management Practices, including installation & maintenance. 1 LS 6000 6,000.00 6,000 Pumping dirty water from in-water work overboard into settling basin. 7 Days 800 5,600.00 5,600 SUBTOTAL (4) 0 516,009 56,000 572,009	wood from site, mostly small, Assume						,
Acquire, haul & install woody habitat 225 Pieces 750 168750 168,750 structure. Assume 25% anchored. 1 LS 6000 6,000.00 6,000 Best Management Practices, including installation & maintenance. 1 LS 6000 5,600.00 5,600 Pumping dirty water from in-water work overboard into settling basin. 7 Days 800 5,600.00 5,600 SUBTOTAL (4) 0 516,009 56,000 572,009	25% anchored						
structure. Assume 25% anchored. ILS 6000 6,000.00 6,000 Best Management Practices, including installation & maintenance. ILS 6000 6,000.00 6,000 Pumping dirty water from in-water work overboard into settling basin. 7 Days 800 5,600.00 5,600 SUBTOTAL (4) 0 516,009 56,000 572,009	Acquire, haul & install woody habitat	225 Pieces	750		168750		168,750
Best Management Practices, including installation & maintenance. 1 LS 6000 6,000.00 6,000 Pumping dirty water from in-water work overboard into settling basin. 7 Days 800 5,600.00 5,600 SUBTOTAL (4) 0 516,009 56,000 572,009	structure. Assume 25% anchored.						- ,
installation & maintenance. Pumping dirty water from in-water work overboard into settling basin. SUBTOTAL (4) 0 516,009 56,000 572,009	Best Management Practices, including	1 LS	6000		6,000.00		6,000
Pumping dirty water from in-water 7 Days 800 5,600.00 5,600	linstallation & maintenance.				,		
work overboard into settling basin.	Pumping dirty water from in-water	7 Days	800		5,600.00		5,600
SUBTOTAL (4) 0 516,009 56,000 572,009	work overboard into settling basin.				- ,		, , , , , , , , , , , , , , , , , , ,
SUBTOTAL (4) 0 516,009 56,000 572,009							
SUBTOTAL (4) 0 516,009 56,000 572,009		[
		SI	UBTOTAL (4)	0	516,009	56,000	572,009

TRAVEL. Mileage, per diem, lodging	g, etc. Must i	use current State of	Oregon rate.			
						0
						0
	4	SUBTOTAL (5)				0
		SUBIUTAL (S)			<u>_</u>	0
SUPPLIES/MATERIALS. Refers to	items that ty	pically are "used up	" in the course of	f the project. Cost	s to OWEB must	be directly
related to on-the-ground work.						
Donated land/Conservation easement	22 acres	\$500/acre/year	165.000.00			165.000
15 years		······································				
	-	SUBTOTAL (6)	165,000	0	0	165,000
CAPITAL FOUIPMENT List portal	le equipmen	t costing only \$250	or more per uni	t Useful life of co	unital equipment	is for the
CATTAL EQUITIVIENT. List polia		t costing only \$250	or more per un		<i>puur</i> equipment	is for the
duration of project and will be used on	ly for this pro	oject (see next page	for Non-Capita	d Equipment).		
						0
						0
		SUBTOTAL (7)	0		0	0

 CAPITAL SUBTOTAL [Add all subtotals, (1-7) above]
 168,600
 525,609
 58,500
 752,709

NON-CAPITAL BUDGET *Totals automatically round to the nearest dollar

DUCATION/OUTREACH. Refers to informational and promotional activities associated with the project.						
					0	
					0	
					0	
SU	BTOTAL (8)	0	0	0	0	
more.	250 or more per uni		with a useful life of	t generally 2 yea	rs or 0	
					0	
					0	
SU	BTOTAL (9)	0	0	0	0	
NON-CAPITAL TOTAL (10) [Add the two s	ubtotals, (8-9)	0	0	0	0	

FISCAL ADMINISTRATION *Totals automatically round to the nearest dollar

Not to exceed 10% of the Capital Subtotal (1-7) and the Non-Capital T (fiscal management); contract management (complying with the terms	otal (8-9). Refer and conditions of	s to costs associate the grant agreemen	d with accounting nt); and fiscal rep	g; auditing orting expenses
Tor the OwEB grant, including final report expenses for the grant.			h h 0 10 1	<u> </u>
Fiscal Administration	I-Capital I otal a	<u>na multiplying bot</u>	5,850.00	5,850
				0
SUBTOTAL (11)	0	0	5,850	5,850
grant (see Application Instructions).	iated with annual	reporting requirem	ents typically rec	quired for each
/yr				0
/yr				0
SUBTOTAL (12)	0	· 0	0	0
CAPITAL SUBTOTAL (1-7)	168,600	525,609	58,500	752,709
CAPITAL TOTAL (13) [Add the two Subtotals (10&11) to the Capital Subtotal from (1-7) above]	168,600	525,609	64,350	758,559

RESTORATION BUDGET TOTAL *Totals automatically round to the nearest dollar

RESTORATION BUDGET TOTAL (14)	168,600	525,609	64,350	758,559
[Add Non-Capital Total (10) and Capital Total (13), from above]				_

RIPARIAN PLANT ESTABLISHMENT BUDGET TOTAL

RIPARIAN PLANT ESTABLISHMENT BUDGET	0	21,340	33,635	54,975
TOTAL (15)				•
This only applies if you are doing a riparian planting project; see				
Application Instructions and R17. Transfer Budget Total (10)				
from the Riparian Plant Establishment Budget Insert.				

EFFECTIVENESS MONITORING BUDGET TOTAL

EFFECTIVENESS MONITORING BUDGET	0	0	0	0
TOTAL (16)				
This only applies if you are doing Effectiveness Monitoring; see				
Application Instructions and R16. Transfer Budget Total (11) from the				
Effectiveness Monitoring Budget insert.				
-				

PROJECT BUDGET TOTAL *Totals automatically round to the nearest dollar

PROJECT BUDGET TOTAL	168,600	546,949	97,985	813,534
[Add (14), (15), AND (16) from above]				

.

.

Section II RIPARIAN PLANT ESTABLISHMENT BUDGET INSERT

IMPORTANT: Read the application instructions. Attach additional lines, if necessary.

CAPITAL BUDGET *Totals automatically round to the nearest dollar

	_					
	A	<u> </u>	C	D	E	F
	Unit	Unit	In-Kind	Cash Match	OWEB	Total Costs
Itemize projected costs under each of the following	Number	Cost	Match	Funds	Funds	
categories.	(e.g., # of	(e.g., hourly				(add columns
	hours)	rate)				C, D, E)
PROJECT MANAGEMENT. Includes staff or co	ntractors who	coordinate pro	oject implement	tation. Line iten	ns should ident	fy who will be
responsible for project management and their affiliat	ion.					
WWBWC - Executive Director	40 hrs	48			1,920.00	1,920
						0
	<u>SU</u> B	TOTAL (1)	0	0	1,920	1,920
IN-HOUSE PERSONNEL. Includes only Applica	nt employee co	osts and the po	rtion of their ti	ne devoted to th	is project.	
						0
						0
						0
	<u> </u>	TOTAL (2)	0	0	0	0
CONTRACTED SERVICES. Labor, supplies, and	I materials to b	e provided by	non-staff for p	roject implemen	tation.	
Riparian Planting, live willow stakes, cottonwood						
poles, some conifers, seeding, 4.91 acres						
	158 hours	20		3,160		3,160
Transitional Zone Planting, live willow stakes,						
cottonwood poles, shrubs, bushes, 9.17 acres	396 hours	20		7,920		7,920
Bank zone Planting, live cuttings, nursery stock,	503 hours					
cottonwood poles, salvaged alder, 1.94 acres		20		10,060		10,060
Grass seeding, 16.02 acres	10 hours	20		200		200
		TOTAL (3)	0	21,340	0	21,340
TRAVEL. Mileage, per diem, lodging, etc. Must u	se current State	e of Oregon rat				
	<u> </u>					0
	· · · · ·					0
	<u> </u>					
			0		0	0
SUDDI IECALATEDIAL C. Defens to items that the	SUD	d un" in the co		ioat Costa to O	VEP must ho	dimonstly related
SUPPLIES/MATERIALS. Refers to items that typ	ically are use	u up in the co	urse of the pro	ect. Costs to O	WED must be	inectly related
Riparian Planting, live willow stakes, cottonwood	1000 1	3.72			4,538	4,538
poles, some coniters, 4.91 acres	1220 plants	5.25			10.5((10.566
I ransitional Zone Planting, live willow stakes,	1075 mlonta	5.35			10,366	10,500
Renk zone Planting, live outtings, purpers stock	1973 plants	2.21			12 471	12 471
Cottonwood notes, salvaged alder, 1.94 acres	5045 plants	2.21			12,4/1	12,7/1
Grass seed mix	114 lbs	10.00/16			1.140	1.140
	111105	10.00/10				0
······································						0
	SUB	TOTAL (5)	0	0	28,715	28,715
CAPITAL EQUIPMENT. List equipment costing	only \$250 or m	ore per unit	Useful life of c	anital equipmen	nt is for the dur	ation of
project and will be used only for this project (see ne	xt nage for No	n-Canital Equ	uinment)	apriat equipmen	it is for the du	
project and and only for this project (see he.			F			
	 erm	TOTAL				0
		(1 0 1 AL (0)		21 340	30.625	51 075
CAPITAL SUBTUIAL [Ad	a au subtotais	, (1-0) abovej	U	21,540	50,055	51,775
					<u> </u>	l

NON-CAPITAL BUDGET *Totals automatically round to the nearest dollar

EQUIPMENT. List equipment costing only \$250 or more per unit. Refers to it	tems with a use	ful life of genera	lly 2 years or n	nore.
				0
				0
				0
SUBTOTAL (7)	0	0	0	0
NON-CAPITAL TOTAL [subtotal (7) above	0	0	0	0

FISCAL ADMINISTRATION *Totals automatically round to the nearest dollar

Not to exceed 10% of the Capital Subtotal (1-8) and the Non-Capital Total (9). Refers to costs associated with accounting; auditing (fiscal management); contract management (complying with the terms and conditions of the grant agreement); and fiscal reporting expenses for the <u>OWEB grant</u>, including final report expenses for the grant.

FISCAL ADMIN. Compute by adding the Capital Subtotal and Non-Capital T	otal and multip	plying both by 0	.10 or less.	
Administration			3,000.00	3,000
				0
FISCAL ADMIN SUBTOTAL (8)	0	0	3,000	3,000
grant (see Application Instructions)				
/yr				
SUBTOTAL (9)				
CAPITAL SUBTOTAL (1-6)	0	21,340	30,635	51,975
CAPITAL TOTAL [Add the Fiscal Admin Subtotal (8) and PISR (9) to	0	21,340	33,635	54,975

PLANT ESTABLISHMENT BUDGET TOTAL *Totals automatically round to the nearest dollar

the Capital Subtotal from (1-6) above]

[Add Non-Capital Total and Capital Total, from above] PLANT ESTABLISHMENT BUDGET TOTAL (10)	0	21,340	33,635	54,975
Insert this TOTAL in the RPE Budget (15) in the Restoration Application				

ATTACHMENT A



MATCH FUNDING FORM

Document here the match funding shown on the budget page of your grant application

OWEB accepts all non-OWEB funds as match. An applicant may not use another OWEB grant to match an OWEB grant. However, an applicant who benefits from a pass-through OWEB agreement with another state agency, by receiving either staff expertise or a grant from that state agency, may use those benefits as match for an OWEB grant. (Example: A grantee may use as match the effort provided by ODFW restoration biologists because OWEB funding for those positions is the result of a pass-through agreement). At the time of application, match funding for OWEB funds requested does not have to be *secured*, but you must show that <u>at least 25% of match funding has been *sought*. On this form, you do not necessarily need to show authorized signatures ("secured match"), but the more match that is secured, the stronger the application. Identify the type of match (cash or in-kind), the status of the match (secured or pending), and either a dollar amount or a dollar value (based on local market rates) of the in-kind contribution. In the table below, the match may be identified as Effectiveness Monitoring (EM), Riparian Plant Establishment (RPE) or Other (OTHER) Dollar Value. If you are not requesting funds from OWEB to support effectiveness monitoring or riparian plant establishment, disregard the EM column or the RPE column and use only the OTHER column.</u>

EFFECTIVENESS MONITORING (EM): If you are requesting more than \$3,500 in OWEB funds to support Effectiveness Monitoring activities as part of a Watershed Restoration Grant Application and filling out information for Question R16, you must include matching funds which will be used as match for the effectiveness monitoring portion of the project. This is identified in the table below as EM Dollar Value.

RIPARIAN PLANT ESTABLISHMENT (RPE): If you are requesting more than \$3,500 in OWEB funds to support Riparian Plant Establishment as part of a Watershed Restoration Grant Application and filling out information for Question R17, you must include matching funds which will be used as match for the Riparian Plant Establishment portion of the application. This is identified in the match form table as the RPE Dollar Value.

If you have questions about whether your proposed match is eligible or not, visit our website at <u>www.oregon.gov/OWEB/GRANTS/grant_app_materials.shtml</u>, or contact your local OWEB regional program representative (contact information available in the instructions to this application).

Project Name: Lampson Levee Setback and Habitat Restoration

Applicant: Walla Walla Basin WSC

Match Funding Source	Type (√ one)	Status (√ one)**	EM Dollar Value	RPE Dollar Value	OTHER Dollar Value	Match Funding Source Signature/Date**
CTUIR Fish Habitat Program	⊠ cash □ in kind	⊠ secured □ pending		\$10,000.00	\$656,009.00	78
Clark and Lyla Lampson	□ cash ⊠ in kind	i secured ☐ pending			\$165,000.00	Lyla Lampson
	□ cash □ in kind	☐ secured ☐ pending				Charl Sauffor
	□ cash □ in kind	☐ secured ☐ pending				1
	□ cash □ in kind	☐ secured ☐ pending				
	cash	secured pending				
	□ cash □ in kind	secured pending				

****** <u>IMPORTANT</u>: If you checked the "Secured" box in the Status Column for any match funding source, you must provide <u>either</u> the signature of an authorized representative of the match source in the final Column, <u>or</u> attach a letter of support from the match funding source that specifically mentions the dollar amount you show in the EM, RPE or OTHER Dollar Value Column(s).

ATTACHMENT B



LAND USE INFORMATION FORM

This byformation is needed to determine if the proposed project complies with statewide planning goals and is compatible with local comprehensive plans (ORS 197.180). The form must be submitted before OWEB releases project funds. OWEB will release project funds only if the project either is not regulated by, or is compatible with the local comprehensive plan and zoning ordinance. If a project is regulated by the local comprehensive plan and zoning ordinance, OWEB will void grant agreements for projects the county determines to be incompatible with the local comprehensive plan and zoning ordinance. If the county requires additional local approvals for a project regulated by the local comprehensive plan and zoning ordinance, OWEB will not release project funds until these conditions are satisfied.

1. TO BE COMPLETED BY THE APPLICANT/GRANTEE

Applicant/Grentee Name: Walla Walla Basin Watershed Council

Project Name: Lampson Levee Setback and Habitat Restoration

2. TO BE COMPLETED BY CITY/COUNTY OR TRIBAL PLANNING OFFICIAL

Complete this section only after section 1, above, has been completed. Check the box below that applies:

This project is not regulated by the local comprehensive plan and zoning ordinance.

- This project has been reviewed and is compatible with the local comprehensive plan and zoning ordinance.
- This project has been reviewed and <u>is not</u> compatible with the local comprehensive plan and zoning ordinance.
- Comparibility of this project with the local planning ordinance cannot be determined until the following local approvals are obtained:

Conditional Use Permit
Plan Amendment
Other

<u>X</u> Development Permit Zone Change NOTE: A Floodplain Development Permit and a Zoning Permit will be required for this project before the County will give tinal approval.

An application has _____ has not _x_been made for the local approvals checked above.

of Local Official

April 15, 2010

Phone: 541-278-6249

Date

Print Name: Richard Jennings

Title; Senior Planner

ŧΙ

Email: tichardi@umatillacounty net

*Must be an authorized signature from your local City/County or Tribal Planning Department, regardless of which box is checked above.

09-! 1 OWEB Restoration Application - Attachment B - April 2010

ATTACHMENT C



PUBLIC RECORD CERTIFICATION

Oregon Administrative Rule 695-005-0030(4) states that "All applications that involve physical changes or monitoring on private land must include certification from the applicant that the applicant has informed all landowners involved of the existence of the application and has also advised all landowners that all monitoring information obtained on their property is public record. If contact with all landowners was not possible at the time of application, explain why."

<u>INSTRUCTIONS</u>: All applicants must complete Part One. In Part One, if you check the first box, skip Part Two and sign and date in the signature box below. If you check the second box, you must complete Part Two and sign and date in the signature box below.

PART ONE

Public land only (<u>STOP</u>: go to signature box and complete)

Private land only, or a mix of public and private land (complete Part Two and sign and date in the signature box)

PART TWO

I certify that I have informed <u>all</u> participating private landowners involved in the project of the existence of the application, and I have advised <u>all</u> of them that all monitoring information obtained on their property is public record. The following is a complete list of all participating private landowners.

1. 9	CLARK AND LYLA LAMPSON	6.	
2. /	ALBERT DWIGHT AND RUTH E. SMITH	7 .	
3.		8.	
4.		9.	
5.		10.	

I certify that contact with <u>all</u> participating private landowners was not possible at the time of application for the following reasons:

Furthermore, I understand that should this project be awarded, I will be required by the terms of the OWEB grant agreement to secure cooperative landowner agreements with all participating private landowners prior to expending Board funds on a property.

APPLICANT/CO-APPLICANT SIGNATURE

AR Kalat	4-15-2010
Applicant Signature	Date
BRIAN R. WOLGTT	WUBLUE EXECUTIVE DIRECTOR
Print Name	Title
Co-Applicant Signature	Date
Print Name	Agency

ATTACHMENT D



RESTORATION METRICS FORM

OWEB receives a portion of its funds from the federal government and is required to report how its grantees have used those funds. The information you provide in the following form will be used for federal reporting purposes. Please complete all portions of the form below as they apply to your project.

If you have any questions, please contact Cecilia Noyes, OWEB Performance Analyst/Reporting Specialist at 503-986-0204 or cecilia.noyes@state.or.us.

Section 1 - Project Overview

Answer all five questions below, even if you have answered a similar question in a previous section in the grant application.

1. Land Use Setting: CHECK ONE BOX ONLY.

Urban/Suburban/Exurban (Projects locaied within urban	Rural (Projects located outside urban growth
growth boundaries or rural residential areas)	boundaries or rural residential areas.)

2. Dominant Watershed Setting: CHECK ONE BOX ONLY. Example: Your project involves managing crosion in the upland area with some erosion control extended to the riparian area. Because most of the work is to occur in the upland area, you would check <u>only</u> the Upland box below.

Estuary (where freshwater meets and mixes with saltwater of ocean tides.)	\boxtimes	Riparian (adjacent to a water body, within the active floodplain.)
		Upland (above the floodplain.)
Instream (below the ordinary high-water mark or within the active channel — includes fish passage.)		Groundwater (Projects that recharge groundwater or primarily affect the subsurface water table.)
Wetland (areas inundated or saturated by surface or ground prevalence of vegetation typically adapted for life in saturate	water d soil	at a frequency and duration sufficient to support a conditions.

3. Total Acres Treated:26

Total Stream Miles Treated: _____ (do not include upstream stream miles made

accessible to fish with passage improvements)

4. Project Identified in Plan or Watershed Assessment: List the <u>primary</u> watershed/subbasin plan(s) or assessment(s) in which this project type is identified as a priority. The plans identified in Section III, question #R9 should include the plans or assessments listed below. Attach additional page, if needed.

Title	Author(s)	Date
Walla Walla Basin Strategic Action Plan	WWBWC	2003

- 5. Project Monitoring: All OWEB funded restoration projects require post-implementation status reporting including photo point monitoring. Please indicate below: 1) the location of the monitoring activities relative to the project, including photo point locations, 2) whether effectiveness monitoring is planned, and 3) whether additional monitoring will be conducted for this project.
 - 5.1) Identify the location for the planned monitoring activities relative to the restoration project location. Check as many boxes as apply.

X Onsite	Downstream	Unstream	[] Unclone

- 5.2) Effectiveness monitoring will be conducted for this project, this can be selected regardless of whether the effectiveness monitoring is funded by OWEB (refer to definition of effectiveness monitoring in the Application Instructions under R16)
- 5.3) Will this project conduct monitoring activities beyond the required post-implementation status reporting and photo point monitoring?
 - Yes I No If you answer yes, select the monitoring activities below, if you answer no proceed to Section 2.

Check all proposed monitoring activities

Adult Fish presence/absence/abundance/distribution survey(s)	Spawning surveys
Juvenile Fish presence/absence/abundance/distribution survey(s)	Upland vegetation (Presence/Absence)
Instream Habitat surveys	U Water quality
Macroinvertebrates	U Water quantity
Noxious weed (Presence/Absence)	Other (explain):
Riparian vegetation (Presence/Absence)	

Section 2 - Project Activities

Provide values for each Project Activity applicable to your application. Leave blank any Project Activity or metric line that is not appropriate to your application. All data entered in this form should be what you plan to do with the project. Data about completed projects will be reported at the end of the project to the Oregon Watershed Restoration Inventory (OWRI). For each activity type where you enter metrics, estimate the percentage of the total cost of the project (shown on page 1 of this application) that applies to the activity. The total of all of the activity cost percentages should equal 100%. Please distribute all administrative, project management and other general project costs among the various project activities when estimating percentages.

Example: A project will remove a fish passage barrier, place large boulders instream. and plant a riparian buffer. You would enter the appropriate metrics into the Fish Passage, Instream Habitat, and Riparian Habitat activity sections of this form. Then, estimate the percentage of the total cost of the project for each activity. For instance: 20% towards Fish Passage activities, 25% towards Instream Habitat activities, and 55% towards Riparian Habitat activities.

Fish Screening Projects: Projects that result in the installation or improvement of screening systems that prevent fish from passing into areas that do not support fish survival, for example into irrigation diversion channels.

_____ Estimated percentage of total cost of the project applied to fish screening activities.

_____ Estimated number of screens installed, replaced, repaired or modified.

Fish Passage Improvement Projects: Projects that affect or provide fish migration. Includes road crossings (e.g., culverts, bridges or fords), barriers (e.g., dams or log jams), and engineered fish barrier bypasses. For partial barriers, include total miles made accessible by the project. Check all proposed types of barrier that will be installed, removed or modified for fish passage.

Fish ladder installed/improved	Road Stream Crossing installed or improved/upgraded:
	Culvert(s) Bridge(s) Rocked ford(s)
Engineered fish barrier bypass (other than fish ladders) installed/ improved (e.g., rock/boulder step pools, weirs, bedrock chutes)	Tidegate alteration/removal
Fish passage blockage removed or modified (e.g., diversion dam, push-up dam, log-jam removed/modified)	Other (explain):
Road Stream crossing(s) removed (not replaced)	

____ Estimated percentage of total cost of the project applied to fish passage activities

Estimated total stream miles in the main channel and tributaries where access is improved above project. [Note: Calculate distance furthest upstream likely to be used by fish.]

Estimated stream miles for <u>Fish Barrier(s) removal/modification</u>, other than road stream-crossings : Miles of stream channel made accessible upstream by replaced/improved/removed fish passage barrier(s), other than road stream crossings

Estimated stream miles for <u>Road stream-crossing(s) only</u>: Miles of stream channel made accessible upstream by replaced/improved/removed road stream-crossing(s)

Estimated total number of passage blockages, impediments or barriers and road stream-crossings removed or altered to allow passage.

____ Estimated number of culverts, installed, replaced, or improved to allow passage

Instream Flow Projects: Projects that maintain and/or increase the instream flow of water. If these activities do not have a value for the estimated increase in instream flows then the activities should be recorded under Upland – Agriculture Management Activities. <u>Check all proposed activities.</u>

Irrigation practice improved to increase instream flows (e.g. install diversion headgate, replace open ditches with pipes)	Water flow gauges installed to measure water use
This project will dedicate instream flow.	Other (explain):

Estimated percentage of total cost of the project applied to instream flow activities.

Estimated miles of stream where increased flow is the result of decreased/eliminated water withdrawals.

The estimated increase in flow of water in the stream as a result of conservation effort (cubic feet per second).

_____ mm/dd/yyyy of initial start date

_____ mm/dd/yyyy of final end date

Instream Habitat Projects: Projects that increase or improve the physical conditions within the stream environment to provide needed habitat conditions. Check all proposed activities.

\boxtimes	Channel reconfiguration and connectivity (e.g., creating instream pools, meanders, improving floodplain connectivity, off-channel habitat)	Spawning gravel placement
\boxtimes	Channel structure - large wood placement	Plant Removal/control (instream); List scientific names of plants
\boxtimes	Channel structure - boulder placement	Beaver introduction
\boxtimes	Channel structure placement (<u>other</u> than large wood or boulder placements). e.g., engineered structures or deflectors, barbs, weirs, etc.	☐ Carcass or nutrient placement: ☐ salmonid carcass; ☐fish meal brick; ☐other nutrient
	Streambank stabilization	Other (explain):

80% Estimated percentage of total cost of the project applied to instream habitat activities.

Estimated miles of stream to be treated with instream habitat treatments

Riparian Habitat Projects: Projects above the ordinary high-water mark of the stream and within the floodplain of the stream. <u>Check all proposed activities.</u>

Riparian planting	Conservation grazing management (e.g., rotation grazing)	
Riparian fencing	Non-native/noxious plant control	
Livestock exclusion (by means other than fencing)	Vegetation management (e.g. prescribed burnings, stand thinning, stand conversions, silviculture)	
Water gap development	Other (explain):	
15% Estimated percentage of total cost of the project applied to riparian habitat activities		
26% Estimated acres of riparian habitat to be planted		
Estimated acres of riparian habitat to be treated for non-native/noxious weeds		

- _____ Estimated total riparian acres to be treated.
- Estimated miles of riparian streambank to be treated. Stream sides treated 📋 one 🗌 two (Do not double count miles if a

second side was treated)

Upland Habitat Projects: Projects implemented above the floodplain. Check all proposed activities.

Erosion control structures (e.g., sediment collection basins, WASCOBs)	Upland Agriculture Management (e.g., no/low-till, irrigation/water management)
 Planting/seeding for erosion control (e.g., convert from crops to native vegetation, grassed waterways, windbreaks, filter strips) 	Livestock Manure Management (e.g., relocate/improve manure holding structures and manure piles to reduce/eliminate drainage into streams)
List scientific names of plants	
Slope stabilization (e.g., grade stabilization, landslide reparation, terracing slopes)	Livestock Water Developments
Non-native/noxious plant control; List scientific names of plants:	Upland Livestock Management (other than livestock water developments), e.g., grazing plans, fencing
Juniper removal/control	Restore Historic Upland Habitats (e.g. oak woodland, oak savannah, upland prairie restoration)
Vegetation Management (<u>other</u> than Non- native/noxious plant control or juniper removal, e.g. tree thinning, brush control, burning)	Other (explain):

- _____ Estimated percentage of total cost of the project applied to upland habitat activities.
- Estimated number of livestock water developments
- Estimated acres of upland habitat to be treated for non-native/noxious plants
- Estimated total acres of upland habitat to be treated (do not include acres of upland habitat affected by livestock water developments)

Road Projects: Projects designed to improve road impacts to watersheds. Check all proposed activities.

Road drainage system improvements & reconstruction	Other (explain):
Road closure, relocation, obliteration (decommissioning)	

Estimated percentage of total cost of the project applied to road activities.

_____ Estimated miles of road treated

Urban Impact Reduction Projects: Check all of the urban impact related activities that will be used by this project:

Sewage outfall clean-up	Bioswales
Toxin reduction: list names of each toxic species, element or material:	Detention Facility
Pesticide reduction: list names of each pesticide:	Other urban impact reduction (explain):
Stormwater/wastewater modification or treatment	

Check all of the water quality limiting factors addressed by the activities selected above. Do not select limiting factors addressed by other types of restoration activities:

Bacteria	Pesticides	Nutrients
Dissolved Oxygen	Toxics	Sediment
Heavy Metals	High Temperature	Other (explain):

_____ Estimated percentage of total cost of the project applied to urban impact activities.

Wetland Habitat Projects: Projects designed to create or improve wetland areas. Check all proposed activities.

Wetland planting	Artificial wetland area created from an area not formerly a wetland
Non-native/noxious/invasive plant control	Other (explain):
Wetland improvement/restoration of existing or historic wetland (other than vegetation planting or removal)	

____ Estimated percentage of total cost of the project applied to wetland habitat activities.

Estimated acres of wetland habitat to be treated for non-native/noxious/invasive plants

Estimated acres of artificial wetland created

Estimated total acres of wetland habitat (existing or historic) treated

Estuarine Habitat Projects: Projects that result in improvement or increase in the availability of estuarine habitat.

Check all proposed activities.

Channel modification/creation (e.g., improve intertidal flow to existing estuarine habitat)	Non-native/noxious plant control
Dike or berm modification/removal	Creation of new estuarine habitat where one did not exist previously by methods other than tidegates or dikes
Removal of existing fill material	Other (explain):

____ Estimated percentage of total cost of the project applied to estuarine habitat activities.

Estimated acres of estuarine habitat to be treated for non-native/noxious plants

_____ Estimated total estuarine habitat (existing or historic) acres to be treated





























Landowner Letter of Support for Levee Setback/Removal

Clark and Lyla Lampson March 24, 2010

We own approximately 45 acres through which the main stem of the Walla Walla river flows on our southern boundary for 3/8 of a mile. The south side of the river approximately follows a bluff, which forms both a boundary for the river and for our property. The north side of the river is constrained by a levee. Our property lies within the flood control district for the town of Milton-Freewater, located two miles downstream. The Army Corps flood control levee terminates on the property downstream from ours with a well designed upstream funnel extending across the entire width of the river valley.

Figure 2 shows the current conditions and issues we have. Our property is demarcated with yellow lines. Red lines show levees. The flood control levee funnel is shown on the left (towards MF) on Pat Kelly's property. It spans the width of the river bottom, nearly reaching the Walla Walla River Road on the North. This forms the upstream flood protection for Milton-Freewater.

The existing levee on our property is shown as the red line on the north of the river. It starts on the west side but does not connect to any other levee on Pat's property. It abruptly terminates on the east boundary of our property without an upstream funnel. Consequently, upstream floods such as happened in 1996 and 1998 flood behind this levee as shown in Figures 1, and 3.



Figure 1

Flood flow isolated from the river by levee for the entire length of our property.

As shown by the blue arrows in Figure 2, flooding enters our property not directly from the river, but further upstream and consists of a wide, thin sheet of water. Figure 3 shows the river at flood stage on our upstream boundary. Water is actually returning to the river at this point. The water which enters our property to the north of the building shown in Figure 1 is now trapped behind the levee, and must flow the length of the property before it can reenter the river on Pat's land.



Figure 2

Overview of existing conditions and issues



Figure 3

Flood flow immediately upstream of levee terminus showing return flow to the river channel.

The deepest water behind the levee tends to flow close to the north side of the levee, following an old road bed. This erodes further in floods. However, a thin sheet flow spreads far to the north as shown by the blue arrows in Figure 2.



Figure 4

Levee upstream erosion

Figure 4 above shows the bank at the upstream end of the levee. Because of the river dynamics here, the riprap facing has eroded off, and the bank has been cut back about 15 ft during the floods of the 1990's. The bank is nearly vertical, and consequently has high erosive stress during floods due to the water depth along the bank. Unfortunately this erosion is occurring right at the head of the levee. There is significant risk that subsequent floods could erode enough additional bank that the river channel shifts behind the levee. An example of why this concerns me is shown in Figure 5.



Figure 5

Nick Peterson's property on S. Fork showing channel erosion in previous floods

This shows the erosion that occurred on Nick Peterson's property in one of the prior floods. His property used to extend out into the region of the current island. The river banks were steep, and thus erosion stress was high during floods. The main channel shifted 30 ft or more to be on the right during the flood. Work has since been done to shift it back to the left and protect the structures. A shift of less than this amount where erosion is occurring on our property will put the main flow of the river behind our levee.

If (when unless something is done) this occurs, we would have significant damage, including to our crops and buildings. In addition, Pat's land behind the levee funnel would likely have significant erosion as well.

It should be noted, that even if the main channel formed north of our levee, this would likely not have much impact on Milton-Freewater, since the flood control funnel on Pat's land forms the protection.

Our Goals

Figure 2 shows our crops are restricted to the northern portion of our property, while the southern portion has riparian/upland restoration. We would like to protect the northern portion from severe

flooding, but we are willing to let the southern portion be used in any way that is deemed useful for ecological benefit.

The proposed project by CTUIR address this in the following ways (please refer to Sheet S-5.1 of the GeoEngineers report to CTUIR).

- 1) Opening up the levee to increase flow capacity and reduce vertical bank height.
- 2) Erosion control structures both at the upstream portion and along the setback.
- 3) Side channel provides a defined channel to collect and return upstream flood water.
- 4) Structural protection at the west end to protect Pat's land.
- 5) Habitat enhancements.

The cost of this project is high and cannot be justified solely for the reduced flood risk, since these improvements are restricted to two land owners, and there is likely little risk reduction for Milton-Freewater, although there may be some risk reduction. Instead, the local flood improvement on our land comes as a side benefit of letting CTUIR use the land for habitat restoration using funding they have specifically for such projects. Since we have already allowed CTUIR to do restoration on this area, we are happy to achieve the dual benefit of enhanced flood control and enhanced river ecology.



Figure 6

Proposed CTUIR project.

Oregon Watershed Enhancement Board Region 5 (Eastern Oregon) Review Team Evaluation for June 1, 2001 Applications

APPLICATION NO.:	z201-363	PROJECT TYPE: Acquisition
PROJECT NAME: APPLICANT:	Walla Walla River Floodplain Restor Walla Walla Basin WSC	ration
BASIN:	Walla Walla	COUNTY: Umatilla
OWEB FUNDS REOUI	ESTED: \$235,150.00	TOTAL COST: \$1,591,850.00

NOTE

This project was not reviewed by the regional review team because the application is missing elements required by administrative rule, and thus is not eligible for consideration by the Board.

PROJECT DESCRIPTION:

This purchase of 73 acres of land easements and .25 cfs of water rights will expand the Walla Walla River in a stretch constricted by 7 miles of levees. This land and water acquisition is one facet of a \$1.6 million COE/CTUIR levee setback and riparian restoration project. If funded, 1.5 miles of riparian habitat for steelhead and bull trout will be restored. The land acquisition will result in new wetland habitat, benefiting steelhead and bull trout. The land purchase includes an 1877 water right for .25 cfs, which will remain in the river. This portion of the Walla Walla is usually dewatered in the summer. The threat of downstream flooding will be reduced as the river is able to meander more naturally, dissipating energy. The meander will create habitat diversity such as pools, large woody debris replacement, increased vegetative shading and backwater refugia during high-water events. Approximately 40 wells went dry when the levees were constructed and it is hoped that with the enlarged floodplain these wells will be recharged. Reconnecting the river with its floodplain will improve bull trout and steelhead habitats. American Rivers listed the Walla Walla River on its 1998 list of America's most endangered rivers, identifying the threats as instream flow depletion, agricultural pollution and channelization.

OWEB funds are requested for the land purchase and administration. Cost-share partners include CTUIR, COE, Oregon Water Trust, Walla Walla Watershed Council, WRD and the landowners.

REGIONAL TEAM REVIEW:

The committee did not discuss the project because the application was not complete.

Oregon Watershed Enhancement Board Region 5 (Eastern Oregon) Review Team Evaluation for April 23, 2007 Applications

APPLICATION NO.:	208-5031	PROJECT TYPE: Technical Assistance
PROJECT NAME:	Lampson Levee Setback & River	Channel Design
APPLICANT:	Walla Walla Basin WSC	
BASIN:	Umatilla	COUNTY: Umatilla
OWEB FUNDS REQUE	ESTED: \$18,210.00	TOTAL COST: \$28,750.00

APPLICATION DESCRIPTION:

A private levee constructed years ago constricts the Walla Walla River's ability to meander and also limits fish habitat complexity. This project will design a levee setback to provide meander room along a 2,000 foot stretch of river. It will also design a smaller levee to protect two structures on the opposite side of the property and protect the downstream property. Approximately 25 acres of conservation easement will expand the Walla Walla River floodplain where it is currently restricted by seven miles of levee above and below this reach. Over 2,000 feet of riparian habitat will be restored along steelhead and spring chinook spawning habitat and bull trout rearing habitat. The riverbank where the levee will be removed will be redesigned for stability and fish habitat, utilizing "J" hooks, root wads and rock weirs to create pools and spawning gravels. The watershed council will contract with an engineering firm to complete the design work.

OWEB funds are requested for project management (8%), design (83%) and administration (9%). Partners include the CTUIR, WWBWC and landowners.

REGIONAL TEAM REVIEW:

The team thought highly of this project as the landowner is giving up the use of a significant portion of his property. It was questioned why the area was not enrolled in CREP and then stated that this work needs to be completed prior to CREP enrollment; the work cannot be done once the area is enrolled in CREP. There is ongoing recruitment of other landowners in this levee reach, which may increase the potential environmental benefits. Previously, several other OWEB funded projects have been implemented in this reach of the Walla Walla River. This project will be a good opportunity to revitalize the large effort on the levee setback. The amount requested for engineering is very modest. The project is ready for funding this grant cycle and has high potential for restoration benefits if implemented.

RECOMMENDATION: Fund

PRIORITY: 4 of 8 Non-Capital

Oregon Watershed Enhancement Board Region 6 (Mid Columbia) Review Team Evaluation for April 19, 2010 Applications

APPLICATION NO.:	211-6023	PROJECT TYPE: Restoration
PROJECT NAME:	Lampson Levee Setback and Habitat Restoration	
APPLICANT:	Walla Walla Basin WSC	
BASIN:	UMATILLA	COUNTY: Umatilla
OWEB FUNDS REQUE	ESTED: \$ 102,212	TOTAL COST: \$933,221

APPLICATION DESCRIPTION:

This project is located on 22 acres of a 15 year conservation easement along the upper mainstem Walla Walla River at river mile 49, approximately 2½ miles southeast of Milton Freewater. The levee, built by a previous landowner for flood protection, is one of many in this area that constrict the Walla Walla River's ability to meander and dissipate energy. This project is being noticed by many neighbors who would like to potentially do something similar. Project components include implementing a levee setback design to provide meander and fish habitat complexity along a 3/8th mile stretch of river, revegetating the riparian area and floodplain, and connecting a channelized spring creek to the river. The results will provide ESA listed steelhead and Chinook spawning habitat and Bull trout rearing habitat. The river bank, where the levee will be removed, will be redesigned utilizing j-hooks, root wads and rock weirs to create pools and spawning gravels. Partners include the landowners and the Confederated Tribes of the Umatilla Indian Reservation. OWEB funds were requested for contracted services and fiscal administration.

REGIONAL TEAM REVIEW:

The application requests OWEB funding for riparian planting, and for excavation of the levee setback. The team thought the goals of the project are important: improved spawning and rearing habitat and floodplain connection. However, the team felt that the application provided insufficient justification and detail for them to support nearly \$80,000 in planting costs. The budget was a lump sum with no details for what was included and not included. Many reviewers thought that the planting costs seemed excessive, but without any budget breakdown, it was impossible to determine how the applicant had calculated the costs. The team felt without a more detailed application they couldn't recommend it for funding this cycle. They encouraged the applicant to resubmit the application with a detailed budget breakout and more detailed planting information.

REGIONAL TEAM RECOMMENDATION: No Fund

STAFF RECOMMENDATION TO BOARD: Do not fund